STUDIES

IN

INDO-MUSLIM HISTORY

A Critical Commentary on

ELLIOT AND DOWSON'S HISTORY OF INDIA

AS TOLD BY
ITS OWN HISTORIANS

WITH A FOREWORD BY
SIR RICHARD BURN, KT., C.S.L.

BY

SHĀHPŪRSHĀH HORMASJI HODĪVĀLĀ

Principal and Professor of History (Retd.), Bahāuddīn College, Junāgaāb.

Author of "Studies in Parsi History" and
Historical Studies in Mughal Numismatics."

BOMBAY

FOREWORD.

Professor Hodivala won the gratitude of all students of Indian numismatics by his constructive 'Studies in Moghul Numismatics' based on wide reading and collation of original sources and careful reasoning from the facts. Those Memoirs have also helped historians to verify, correct or supplement the statements of the Persian writers of Indian History.

He has now undertaken the more onerous task of annotating Sir Henry Elliot's "History of India as told by its own Historians," and he brings to this the ripest fruits of life-long scholarly studies. In the sixty odd years which have elapsed since the last volume appeared, new texts or better manuscripts have been discovered and Indian, European and American writers have produced many important works. Professor Hodivala has worked through all the new material, selecting or criticising and adding his own suggestions where previous comments do not exist or appear unsuitable. Though all these may not prove acceptable, as the author himself would be the first to admit, the book is one which every student of Elliot should be glad to refer to, and its intelligent use will prevent the repetition of early errors which are still being copied in modern books and articles.

R. BURN.

Oxford, 6th June 1939.

PREFACE.

Elliot and Dowson's work was published about sixty years ago and its value has only grown with the lapse of time. It is still indispensable to every serious student of the Muhammadan period of Indian History. It is universally quoted, and deservedly too, as an authority of the first class and even regarded by many readers as the very last word on the subject. It is true that several scholars have casually drawn attention to its errors and shortcomings, but these scattered criticisms and casual animadversions have had little or no influence on the general opinion in favour of its infallibility. It has continued to be followed in spite of them and it cannot be denied that this universal vogue and reputation has been responsible for misleading many modern authors, the dissemination of not a few inexactitudes and the circulation of some false and distorted history. It seemed, therefore, necessary in the interests of sound scholarship, to undertake a systematic and exhaustive review of its contents and rectify its errors of interpretation, as well as transliteration. The writer has ventured to undertake this laborious and difficult task and has, at the same time, availed himself of the opportunity to discuss and elucidate questions which were ambiguous or controversial. He has also devoted considerable attention to the restoration of the names of persons and the identification of toponyms which had been left in obscurity. An attempt has been also made to determine the chronology in disputed cases by the application of the week-day test, where it was available. He ventures to think that no one who glances through these pages will declare that such a critical and explanatory commentary was uncalled for and he trusts that his labours will make it possible for students to make a more intelligent and more profitable use of the original work. He lays no claim to be an historian. His object has been merely to investigate, ascertain and verify facts, to reject statements which were inaccurate or without adequate proof and to place the subject on a sounder critical footing.

It is seventy years since Blochmann remarked that our knowledge of the Muhammadan period of the history of this country was very limited and inaccurate in regard to details. It is true that much useful work has been done since he wrote, that many original sources have been more or less carefully edited and correctly translated, but these pages should convince any one that there is still considerable room for intensive critical labour and research in this field.

Many points are still so obscure and incomprehensible that there is no prospect of arriving at an opinion in regard to them. They have had to be passed over in silence, as it was not possible to say anything useful about them.

But there are other problems which are not so hopelessly intractable and the reader will come across in this volume, several attempts to find new answers to questions which have exercised the ingenuity of previous inquirers or have been left unlouched by them. Some of these suggestions and identifications are admittedly hypothetical or tentative and the writer begs that they may not be taken for more than they are worth and that they will not be supposed to have anything definitive about them. They have been put forward only for provoking discussion or stimulating research and eliciting more satisfactory solutions. It will be seen that a few have been already modified in the Corrections, and no one will be more ready to accept more convincing explanations.

Lastly, the writer would like to say that no one could entertain greater or more sincere admiration for the stupendous labours, either of Sir Henry Elliot, who collected, with astonishing ardour and perseverance for forty years, a prodigious quantity of manuscript material, or of Professor Dowson, who worked hard for more than twenty, in arranging, sifting and translating it Nothing could be further from his thoughts or more remote from his wishes than the intention to say anything to disparage or detract from the merit of their monumental performance. His only object has been to enhance the usefulness and value of their work and to bring it up to the standard of modern knowledge. He will think himself amply rewarded, if he is thought to have cleared some of the ground and facilitated, even in a small measure, the compilation of a more accurate and scientific history of the Muhammadan Period than any which we possess at present

The indulgence of the reader is craved for the long list of Errata and typographical imperfections.

S H. HODIVALA.

LIST OF ABBREVIATIONS.

Annals and Antiquities of Rajasthan, J. Tod. Ed. W. Crooke. A.A.R. A.F. 'Abu-l-Fazl. Ancient Geography of India. A. Cunningham, Edit. 1871. A.G.I. 'Army of the Indian Mughals. W. Irvine. A.I.M. Ain-i-Akbari, Bibliotheca Indica Text. Āin Ain-i-Akbari, Trans. Blochmann and Jarrett. Āīn. Tr. Akhar-Nāma, B. I. Text. A.N. A.N. Tr. Akbarnama, Trans. H. Beveridge. 'Amal-i-Sālih. B. I. Text. 'A.S. 'Agrarian System of Moslem India. W. H. Moreland. 'A.S.M.T. Budáuni. B. I. Text and Trans. Ranking and Lowe. B. B.G. Rombay Gazetteer. Bibliotheca Geographorum Arabicorum. Ed. De Goeje. B.G.A. Bāburnāms, Tr. A. S. Beveridge. B.N. C.H.I. Cambridge History of India. Chronology of India, C. Mabel Duff. C.I. Coinage and Metrology of the Sultans of Dehli, H. N. C.M.S.D. Wright. Chronicles of the Pathan Kings of Dehli, Edward Thomas, C.P.K.D. D.H.N.I. Dynastic History of Northern India. H. C. Ray. D.P.P. Delhi, Past and Present. H. C. Fanshawe. Elliot and Dowson's History of India. E.D. E.H.I. Early History of India. Vincent Smith. Edit. 1908. E.I. Encyclonaedia of Islam, Ed, T. Houtsma. Early Travels in India. Ed. [Sir] W. Foster. E.T.I. Tārīkh-i-Firishta, Lithograph, Nawal Kishore Press. F. G.I. Gates of India. Sir T. Holdich. History of Aurangzeb. [Sir] J. N. Sarkar. H.A. H.B.H. History of Baber and Humayun. W. Erskine. History of India. M. Elphinstone. Ed. Cowell. 1866. H.I. Hobson Jobson. Yule and Burnell, Ed. Crooke, 1903. H.J. H.M. History of the Mahrattas. Grant Duff. Reprint, 1873. H.M.H.I. History of Mediaeval Hindu India, C. V. Vaidva. H.N. Humāyun Nāma. Text and Tr. A. S. Beveridge. H.S.M.N. Historical Studies in Mughal Numismatics. S. H. Hodīvālā. I.A. India of Aurangzeb. [Sir] Jadu Nāth Sarkār. I.D.C. The Indus Delta Country. M. R. Haig. I.G. Imperial Gazetteer of India, Edit. 1908. I.M.C. Catalogue of Coins in the Indian Museum. Vincent Smith and H. N. Wright. I.N. Iqbālnāma-i-Jahāngīri. B. I. Text. Iab. Nām. Iqbālnāma-i-Jahāngīri. B. I. Text.

Ind. Ant.

Indian Antiquary.

zw

I O.C.	Catalogue of Persian Manuscripts in the India Office, H. Ethé.
JAS.B.	Journal of the Asiatic Society of Bengal
J.B B R.A.S.	Journal of the Bombay Branch, Royal Asiatic Society.
JBORS	Journal of the Bihar and Orissa Research Society.
	Introduction to the Jawami'au-l-Hikayat M Nizamu-d-din.
J.H	· · · · · · · · · · · · · · · · · · ·
JRAS ·	Journal of the Royal Asiatic Society of Great Britain,
Kh F	Kılıch Beg Trans of the Chach Nāma. Khazāınu-l-Futūh of Amīr Khusrav Ed. Moinu-l-Haq
	Khazāmu l-Futuh Tr Muhammad Habīb
Kh.F Tr. Kh.Kh.	
	Khwāfi Khān, Muntakhabu-l-Lubāb B. I Text.
LEC	Lands of the Eastern Caliphate Guy Le Strange.
LHP	Laterary History of Persia E G Browne
LM	Later Mughals W Irvine
M.'Ā	M'aāsir-1-'Ālamgīrī B I. Text
MG	Mahmud of Ghazna Muhammad Nāzim
Mihrān	The Mihran of Sind and its Tributaries H G. Raverty. J. A S B. 1892.
M.U.	Maāsiru-l-Umarā B I Text
NA	Notes on Afghanistan. H G Raverty.
OHI	Oxford History of India Vincent Smith
PM C	Catalogue of Mughal Coins in the Punjab Museum. R. B. Whitehead.
POG.	Post Office Guide (India)
PT.	Persian Translation of the Baburnama, Bombay Lith.
Races	Races of the North-Western Provinces H M Elliot. Ed. J. Beames
RI	Road Book of India J B. Seely, 1825
S	Alberuni's India Trans E Sachau
SIMI.	South India and her Muhammadan Invaders K S Aiyangar
TA	Tabagat-1-Akbari. Nawal Kishore Press 1292 A. H
TB.	Tüzuk-1-Bāburi, Bombay Lith 1308 H
T.C.	Tribes and Castes of the N W Provinces W, Crooke
TF.	Tārīkh-1-Firūz Shāhi Z Barani B I Text.
TF	Tārīkh-i-Firūz Shābi Shams-i-Sirāj B I Text.
Th	Gazetteer of the Territories of the East India Company. E
	Thornton One Volume Edit
T.J	Tuzuk-1-Jahangiri Ed [Sir] Sayyıd Ahmad, 'Aligarh, 1864.
TJ K.N	Tärikh-1-Jahan Kushai Nadiri. Bombay Lith 1309 H.
TM.	Tārīkh-1-Mubārakshahı B I Text.
TN	Tabagāt-1-Nāsîri B I. Text.
TR.	Tārīkh-1-Rashīdı, Tr Ney Elias and [Sir] E. D. Ross.
ZN	Zafar Nama Sharafu-d-din Yazdı B I Text.
** #**	of a surest to the transfer than

Zafar-al-Walth Ed Sir E Denison Ross.

ADDITIONS AND CORRECTIONS.

P. 5, 1. 28. (Note on I. 5, 1, 5).

Our knowledge of the extent of the ancient kingdom of Karna Snyarna is very vague. It is supposed to have lain west of the Bhagirathi and to have included the modern districts of Burdwan, Bankura, western Murchioābād and Hugli. (I. G. XXI. 237). See my Note on II. 318, 1. 2 £ f.

[who am known also as] Yāyāvarīya, think that all directions should be stated and measured from Mahodaya (Kanauj)" (Edit. Dalāl and Shāstri ın the Gaikawad Sanskrit Series, Saptadashodadhyaya, p. 94, l. 23) Rajashekhara was the poet-laureate and Guru of Mahipala, the Pratihara king of Kanauj, who reigned from about 910 to 940 A C, and that is probably the reason for his desire to have the capital of his patron accepted as the centre of Jambudwipa. But the fact that Alberuni follows his peculiar system, in preference to all others, and makes Qanauj the starting-point of his itineraries shows that he was acquainted with the Kāvyamīmānsā, and probably also with its now lost portion, the Bhuvanakosha, to which Rajashekhara refers his readers for further information in regard to the details of Indian geography (Ibid, p 98, 11. 8-9) It is just possible that some, at least, of Alberuni's Itineraries of the Third Class, that is, those relating to ancient landmarks of Hindu geography, are copied from the Bhuvanakosha The only difference is that the Yojanā of the Hindu author, whether short or long, is uniformly translated as and equated with the Farsakh This may account for some of the manifest errors in the Table of distances Unfortunately, this explanation cannot be tested. as the Bhuranakosha is not extant

P. 44, l 12 f f (Note on I. 54, 1 4 f f)

Dr Fleet who has more recently examined this vexed question in the light of all the available evidence, has proved that there were two kinds of $Yojan\bar{a}$ and comes to the conclusion that the Short $Yojan\bar{a}=4$ $Kroshas=4\frac{83}{195}$ miles and the Long $Yojan\bar{a}=8$ Kroshas $=8\frac{166}{198}$ miles The Krosha, however, was uniform and always measured $1\frac{3}{22}$ miles (J R A.S 1912, pp. 236-7)

P. 45, l 11 f f (Note on I 55, 1 6)

'Argha-tirtha' is mentioned as a typical or renowned holy site, and bracketed with Vārānasi, Prayāga, Kurukshetra or Shrīparvata in an inscription dated about 1200 A.C., which has been found at Ablur in Dharwar (Epig Ind V. 258) and several other epigraphs. In the Gohorwa grant of Karnadeva Chedi, 'Argha-tirtha' is said to have been situated in Koshambapattalā, or the Kosāmbi division Kosāmbi has been now proved to be identical with Kosam, which lies about 30 miles south-west of Prayag (Ind. Ant XVIII 137, D H N I 538, 610 notes) I venture to suggest that Alberuni's 'Araktırath' is this 'Argha-tirtha' and that it was at Piawan, where an inscription of Gangeya Chedi, the father of Karna, has been found The idea has occurred to me very recently after the perusal of a passage in one of Cunningham's Arch Surv Reports "The Tons river," he writes, "is known for the number of its waterfalls are found from 20 to 30 miles north and north-east of Rewa, where the river rushes down the Vindhya Hills to join the Ganges near Panasa 'All the principal waterfalls are considered holy by the Hindus and pilgrimages are still made to them by devout people One of these holy spots lies in a small valley called Piawan, 6 miles south-east of Kathaula

and 25 miles north-north-east of Rewa At the western end [of the valley, a stream falls over the cliff and the rock below on which the water falls has been formed into an Argha for the reception of a lingam.On the upper face of the Argha, there is an inscription It is a valuable one, as it is the only record yet found of the Kalachuri King, Gangeya Deva. It is especially valuable as showing that the dominions of the Kalachuri Kings of Chedi extended......to within fifty miles of Allahabad." The date of the record is 789 of the Chedi Era, i. e. 1038 A. C. (Arch. Surv. Rep. XXI, 112-13). As Piāwan is about 25 miles N. N. E. of Rewa, which is about 90 miles south-west of Allahabad and Alberuni's Araktirath was 12 farsakhs (about sixty miles) south of Prayag, it seems to be just the place intended. It becomes easy also to understand why Gangeya's son Karna performed his sacrificial ablutions at Piawan-the place where his father also had probably purified himself in the same way-before making the grant. As the location of the Argha-tirtha mentioned in the Gohorwa and other Inscriptions has hitherto baffled our archaeologists, this humble suggestion may perhaps be worthy of consideration.

P. 93, l. 29. (Note on I. 172, l. 16).

'Mangonels and Ghazraks' are said to have been used and "stones and arrows thrown from the walls of the fort" of Multān in another passage of the Chachnāma also. The Gharva was, like the mangonel, a balista, stone-sling or catapult. Dowson says in the note there (I. 204) that 'Ghazrak' means 'breast-plate, or dagger,' but this is obviously inapplicable to the context. May not the right reading there also be 'Je' and not 'Ghazrak'?

P. 101, l. 15, (Note on I. 222, l. 3 f. f.).

This Jāma-i-Ghūk ['Frog's Robe'] has been identified with Lemna or Herba Lentis Palustris and the 'Phakos' of Dioscorides. (E. G. Browne, Lectures on Arabian Medicine, 74 Note). He relates five other equally quaint or grotesque stories of "abnormal parasitic invasion" and states that such cures are quite common in what is known as the Literature of Nawādir—Tales of Wonder or Marvels. (Ibid. 75-79). The fabricator of the passage may have got the idea from some old collection of such yarns.

P. 107, l. 9. (Note on I. 235, l. 12).

The Mullā Firūz Library in Bombay possesses a good Ms. of M'asūm's Tārīkh-i-Sind, which is stated in the kolophon to have been transcribed on 25th Shawwāl 1085 H. This obscure passage is thus worded in it: و مسودة آن در كتب خانة مسود اين اور أق مست و بر اكثر كتب منداوله حواشي نوشته اند الله و مسودة آن در كتب خانة مسود اين اور أق مست و بر اكثر كتب منداوله حواشي او Folio 49 b, l. 2 f. f.). "And the original draft (or autograph) of that work [the Commentary on the Mishkāt] exists in the library of the writer of these pages and he [the Maulānā] had [also] written marginal notes on many other well-known (or standard) works." There can be no doubt that this is the real meaning. The library did not belong to an individual

named 'Masūd,' but to Mīr M'asūm, the 'Musawwad,' (صود) i.e. Writer or Author of the Tārīkh-i-Sınd

P. 112, 1 16 f f (Note on I 248, 1.6)

Here again, this manuscript enables us to solve the difficulty. The right reading is not باشیب or باشیب. but Sābāt سابات The sentence is written thus الله قرار داد از آل کدشته کرد سهوان مرحلها نست بوده درمهای ساختی سابات (Folio 148 b, I 5) They were preparing to lay a siege and سابات (covered approaches) is just the word required and which would be wrongly read or written as بایات in the Semitic script P. 115, l. 13 f. f. (Note on I. 256, l 4 f. f).

This earthquake theory may receive some support from a fact which has been unearthed from the Kāmilu-t-Tavārīkh by Dr Thomas Oldham (Memoirs of the Geological Survey of India XIX, Pt 111. p 3). Ibn-al-Athīr has left it on record that in Shāwwāl 280 H. (December, 893 AC) a town called 'Dabīl' [Daibal?] was totally demolished by a terrible seismic disturbance, (الحرال) and one hundred and fifty thousand people were killed (Ed Tornberg, VII 323, Bulāk Ed VII. 154, Il 8-11) This catastrophe may have been connected with the destruction of Aror also and the change in the course of the Indus Unfortunately, there is no clue to the situation of the town, the name of which is not quite certain and the year does not tally with any of the conjectural dates put forward by Cunningham, Raverty, Haig or other authors who have speculated on the subject. (I am indebted to Mr. C E.A.W Oldham for the information). P. 123, 1 9 f f (Note on I 306, l. 12 f. f)

The correct Turki form is, according to M Blochet, e.g., Virmish, which signifies Dieu donné or 'God-given,' and is a participial form of Virmak, the root of which is found in Virdi or Birdi, e.g. Allahvirdi. (Histoire des Mongols, Gibb Series, XVII. Pt. 2, Appendix, pp. 61-2) The name thus belongs to the Allahdad, Khudadad, Devadatta or Ishwardatta class.

P. 128, l 22 (Note on I. 326, 1 11)

The year of Muhammad Bāqi Tarkhān's death, which is given in Malet's Translation of M'asūm's History as 979 H, is undoubtedly wrong and must be due to some oversight or error, as it is written as عمد و سام 'nine hundred and ninety-three,' in words, in the Mullā Firūz Library Ms (Folio 131 b, 1 2 f f)

P. 143, l. 1. (Note on II 34, l. 5)

ţ

Hiuen Tsiang [Yuan Chwang] must be referring here to Bhimasthana, otherwise called Takht-1-Bahai, which is 28 miles north-east of Peshawar and about 10 north-east of Pushkalavati or Hashtnagar Nagarkot had been sacred to Devi or Bhima, from very early times, because when her body was dismembered, the lower part was said to have fallen there, and the head or tongue at Jwalamukhi, according to the Puranas (Ain, Tr. II. 313 and Note, Tieffenthaler, I. 107).

P. 146. 7. 12. (Note to II. 34, 1. 5).

In this connection, it may be worth while to invite attention to a passage in a Chandella inscription in which Kokalla Chedi II is spoken of as the Kalachuri Chandra, 'The Moon of the Kalachuris,' The sentence is translated thus: "From him (Ganda), there sprang that King Vidyadhara......Bhojadeva, together with Kalachuri Chandra worshipped, full of fear, like a pupil, this master of warfare who was lying on a couch". Dr. Hultzsch, who has edited the record, says that this 'Moon of the Kalachuris', must be Kokalla Chedi II. (Epig. Ind. I. 219). Dr. H. C. Ray agrees with Dr. Hultzsch (D. H. N. I. 689), and notes that "the silence of the later prashastikaras [about him] clearly shows that his [Kokalla II's] reign did not form a brilliant chapter in the history of the Kalachuris," (Loc. cit. 771). Is not this silence about an inglorious reign satisfactorily accounted for by Kokalla's disastrous defeat in the trial of strength with the Turushka? The prashastikāras habitually preserve a discreet silence about all reverses sustained by their heroes or their ancestors. It may be permissible to note that when Gardezi (Z. A. 75, 1.9) calls him 'Kulchandar,' he may have in mind his Hindu title, 'Moon of the Kalachuris.'

This important epigraph may also show that Kokalla and Vidyādhara Chandella had become allies or confederates at this time. We have little or no precise knowledge of the extent and boundaries of either the Chandella or the Chedi territories. They were probably more or less interlaced with each other, and even if the Chandella possessions intervened between the Chedi kingdom and Mahāban, this 'equal or subordinate alliance' between the two rulers may provide a sufficient answer to the difficulty and also explain why the task of encountering the invader was undertaken or assigned by mutual consent to Kokalla II.

An alternative suggestion is that the reference must be to Kokalla's father, Yuvarāja II., but this does not really affect the argument, as the real point is that 'Kulchand' or 'Kulchandar' of 'Utbi and Gardezi represents the Chedi ruler of the day.

P. 169, l. 8. (Note on II. 149, last line).

A village called Mināra or Manāra still exists about six miles east of Hund (Ohind or Waihind) on the western bank of the Indus. Shāhbaz-giri or Kapur-da-giri, which has been identified with 'Kīri,' is about twenty-five miles north-west of this 'Manāra'. I am indebted to Mr. H.C. Srīvastava, Superintendent, Archaeological Survey, Frontier Circle, for the information.

P. 175, l. 10 f. f. (Note on II. 176, l. 18).

The immediately preceding tale of the 'Self-possession of an Indian Minister' occurs in the Qābūs Nāma (Bombay Lith., 1325 A.H., pp. 154-5), but it is told there of the Khalif Māmūn and a Qāzi named 'Abdu-l-Malik 'Aqīri.

P. 192, l. 10. (Note on II. 270, l. 6).

Steingass states that A. Interally means "Who increases the offer, or bids more', hence, auction, auctioneering-room, market." It is explained in just the same way in the Müyyadu-l-Fuzala, an old Persian Dictionary compiled by Muhammad Lad in the 15th century. According to this authority, Manyazid means, "Is there any one who increases the price?" It is used in selling goods. Brokers say, 'Here is one who offers ten Is there any body who will augment it?' When any one bids more, they sell the goods to him." (Mulla Firūz Library Ms, Folio 179 a) P. 192, 1 14 f f (Note on II 270, 16).

The Futühu-s-Salātīn was written, not in the 15th, but in the 14th century about 1350 A C It has been published very recently by Dr A M Husain This interesting passage will be found at p 38, verses 649 652, of his Edition

P 210, l. 12 (Note to II 311, 1 4 f f)

See also Barthold, Turkestan, 389 Note. He states that 'Toyin' is the name given to the Buddhist priesthood in Mongolia even at the present day. He cites from 'Aws, a passage in which that author states that "a Buddhist priest was called a Toyin in the Khitāi language and Sthatira in India". M Blochet assures us that Toyin designates the Buddhist priests of the Uighūrs and thinks that it is an alteration of the Sanskrit Tapasvin, Ascetic, which becomes Tapassi in Pāli (Histoire des Mongols, Gibbs Trust Series, XVII. 2, p 313 Note)

P. 225, l 12. (Note on II 351, l 18)

An alternative, if not better, suggestion may be that the Ajar or Ijar of Chahad Deva may be Ichwaro (Ichhchhapuri?), which lies about twenty miles north-west of Narwar It is shown on Constable's Plate 27, C c.

P. 232, last line (Note on II 370, 1 7 f f.)

In the Prabandha Chintamani, Merutunga calls this man 'Vāhad' (Text, p 91, l. 2 and 123, l 1, Tr. Tawney, 82, 120), but 'Vāgbhata' on p 127, l f f and 141, l 10 (Tawney, 120, 134) This indicates that the first is only a Prākritic form of the second and that Minhāj is quite correct in calling the Rājā Bāhar and that his Bāhar is identical with Vāgbhata of the Hammin a Mahākāvya 'Bāhad' appears to have been a common name in those times and a physician of that name is also mentioned by Merutunga (Text, 200, l 7, Tr Tawney, 199).

P. 244, l 4 (Note on III. 49, l. 6).

But as he is repeatedly called 'Nānak Hindi, Ākhurbak-i-Maisara,' in the Futūliu-s-Salātīn also (pp 294-5, verses 5649, 5659, 5669), Nānak seems to be correct and may have been his old Hindu name

P 246, l 12 (Note to III 69, l 14)

As the week-days of both these events are specified in exactly the same way in an old Ms of the *Khazānnu-l Futūh*, written in 1147 H., which is in the Mullā Firūz Library, Bombay, (Folio 5 b, 1 5 and 6 a, 1.3), and work out correctly, the dates may be taken as reliable.

P. 249, l 25 (Note on III 76, 1, 2),

I now think that the first 'Bāhir Deo' stands for the name of the god Bhairav [...] and the second for that of the King. The meaning may be that the temple was of, i.e. dedicated to Bhairav Deva and the King Bāhir Deva (Bāhad Deva or Vāgbhata) was a devout worshipper of the idol and accustomed to implore the god's help.

P. 250, l. 8. (Note on III. 76, l. 6 f. f.).

As the year is given as 705 H. in the M. F. L. Ms. also (Folio 28 b, 1. 2), the objection loses what little force it has.

P. 250, l. 7 f. f. (Note on III. 78, l. 4).

The year is 708 H. in the Ms. also (Folio 33 a, 1. 6) and 710 of the Translation must be due to some error.

P. 280, l. 15. (Note on III. 280, l. 2).

If this explanation is correct, the 'Doaspa' of 'Alāu-d-dīn must be the Bārgīr of later times. Richardson and Steingass say that is means a horse or packhorse.' In the Āīn also, Bārgī or Bārgīr (lit. load-taker) is used for the horse and the rider is called if a called if a comparison of the trooper's comrade or for a trooper who did not ride his own horse. 'Alāu-d-dīn proposed to pay the Doaspa only one-third as much as the Murattab, because the 'Doaspa' did not ride his own horse and a horse was found for him, as Richardson puts it, by some one else. The rule seems to have been to give one share each for a horse and a man. The Murattab had three shares, one for himself and one for each of the horses which he brought. The 'Doaspa' had only one share, viz. that for himself.

The full pay of the Murattab was really 240 tangas per year or 20 per month. The figure is given by Barani as 234, because 6 tangas, or $2\frac{1}{2}$ per cent (chihalyak), were deducted in advance, for Zakat, just as incometax now is, on the salaries of all Government servants. So the Doaspa's $78=80-2\frac{1}{2}$ per cent of 80, or 2.

P. 282, last line. (Note on III. 206, l. 12).

There can be little doubt that the Malāḥida and Borahs are the persons meant. They were called 'Chirāghkush' and accused by their enemies of incestuous practices. Mirzā Ḥaidar Dughlāt says that the Malāḥida or Chirāgh Kush practise "the worst form of heathenism in the world" and that with them "sexual intercourse (vaṭi) with their own kindred is lawful, and enjoyment of it is in no respect dependent on marriage; thus, should one have a passion for some body, it is lawful to gratify it, be it with son or mother." (Tār. Rash. Tr. 213, 217 and 218 Note). Erskine quotes this passage and explains that the name of Chirāghkush was given to them from the practice said to exist at their religious meetings, where men and women met by night, and where, on the lamp being extinguished, indiscriminate indulgence followed". (H. B. H. Vol. I. 287 Note). The 'Borahs' were a branch of the Malāḥida and we know that they also were stigmatised as 'Chirāghkush'. Khwāfi Khān tells us that he was personally acquainted with the Mujtahid and Peshvā and Pe

Chiraghkush of Ahmadabad and that his name was Mulla Jivan—a fact which clearly indicates that he must have been an Ism'aili Borah.

'Isamı also states that the men put to death by 'Alau-d-din were "Almūtiān, [i e. the people of Alamūt], who knew no difference between wife and daughter and that the people of Hindustan called them Bodah also in their own tongue."

P. 292, L. 2 (Note on III, 235, 1 18).

Ibn Batūta's account of the assassination-plot is borne out by the Futūhu-s-Salātīn (p 407, verse 7807 sq) Though the writer does not make any mention of the clumsy device of the projecting beam', in the 'Kūshk' and does not enter into details, it is clear that the story was known to him and his contemporaries

P. 295, 1 5 f f. (Note on III. 245, footnote)

But Bīrāhān, may, after all, be used as the name of a tribe. 'Isāmi states that when Razīyya and Lātūniya [Altūniya] recruited an army to regain the throne, many men belonging to the warlike tribes in those regions, Tonwars, Jatūs, Khokhars and Bīrāhs gathered around them.

The nearest phonetic approach is to Parīhār, but there are no Parīhār Rājputs in the Punjāb. 'Parhar' and 'Parhār' are said by Mr H A Rose to be the names of certain Jat clans in the Montgomery, Dera Ghāzi Khān and Multān districts, but he also remarks that if 'Parhār' is a contraction of 'Parīhār,' the Parhār Jats are their only representatives P 319, l 28 (Note on III. 317, l 14)

In the Futuhu-s-Salātīn, this folktale is related of Sultan Mahmud of Ghazna and an old woman The drink offered is the juice of a pomegranate (pp. 51-3)

P 340, l 17. (Note on III 377, 1.5)

I have ventured to suggest that the Amīri-i-Tarab or Tarib was a tax on marriages, like the Tūi-Begi of Akbar's days Tūi means 'marriage' There was a very similar tax called Lagna-patti under Maḥrāthā rule. (S Sen, Administrative System of the Marathas, p 560)

A tax called *Chhāpa* also is mentioned by Dr. Sen, who states that it was a stamping duty on cloth Imported cloth had to pay a duty of 5 per cent and locally-made fabrics one of $2\frac{1}{2}$ per cent ad valorem (Ibid, 302) But the *Jhaba* [Chhappa] mentioned by the Sultān may have been levied for stamping weights and measures

P. 343, l. 11. (Note on III 380, l. 6 f f)

Mr. Hilary Waddington, Superintendent, Archaeological Survey,

New Dehli, has kindly informed me that the temple of Kālikā neār the Okhla Railway Station is in a village called Badāpur, (not Bahāpur), above a mile to the west of the Dehli-Muttra road, between the third and fourth kos minār from Dehli. The village called Malcha lies on the Ridge, about $6\frac{1}{2}$ miles from this temple of Kālikā and "there are a number of ruins there, including a hunting-box in a very fair state of preservation." This enables us to fix the spelling of the name which is written in so many different ways. The 'hunting box' must be the Kūshk-i-Shikār of Shams. The Kund of Malcha, mentioned by the Sultān, cannot therefore be the one near the Kālikā Mandīr, but some other tank on the Ridge, which was also regarded as holy. Bahārpur, where Sultan Jalālu-d-dīn is said to have encamped, is called Bhokal Pahāri by 'Iṣāmi (p. 201, verse 2928) and also by the T.M. (57, 1. 1).

P. 348, l. 16 f. f. (Note on III. 404, l. 7).

Elsewhere, Yazdi states that the 'Tūmān of Kapak Khān' and the 'Tūmān of Uljā Būghā Saldūz' were ordered to form and post themselves on the bank of river to keep guard there. (Z.N. Vol. I. 109, l. 6). They were evidently brigades or divisions, named after some famous heroes of the past.

P. 350, l. 3 f. f. (Note on III. 415, l. 3 f. f.).

A village called 'Jāl' or 'Chāl' cannot be found now anywhere in this neighbourhood and Raverty is most probably right in taking 'Chāl' as a common noun, meaning 'lake, swamp, pool of water or Dhānd.' He assures us that there is such a lake still in the old bed of the Bīāh, about thirty miles south-east of Multān. (Mihrān, 281). Yazdi himself, in another passage, writes thus about it: كَالْ مَنْ وَلِيْ وَلِيْلِيْ وَلِيْ وَلِيْ وَلِيْ وَلِيْ وَلِيْ وَلِيْ وَلِيْ وَلِ

P. 351, l. 17 f. f. (Note on III. 417, l. 10 f. f.).

It is recorded in the Bādshāh-Nāma of 'Abdu-l-Ḥamīd, that it rained so heavily and incessantly for 36 hours at Ḥaṭṭa and in all the towns and places in the vicinity in Rab'ī I. 1047 H. (August, 1637 A.D.), that "many buildings were destroyed and great numbers of men and beasts were drowned." (Text, I. ii. 276, l. 8 f. f.; E.D. VII. 61).

P. 354, l. 17. (Note on III. 444, l. 20).

Mr. R. B. Whitehead assures me that this copper coin is genuine and that Mr. John Allan of the British Museum is of the same opinion. A gold coin, weighing 210 grains, struck at Hisār in 801 H. in the name of المالية الأمير الخانان التمور كوكان (sic) ماحب فرآن was published by Dr. Hoernle in the J.A.S.B. LXVI. 1897, p. 135. Sir Richard Burn, who has a duplicate in his cabinet, thinks that it may be genuine. Mr. Allan also is not sure that it is a forgery. All that can be said for and against its

genuineness has been very fairly and fully stated by Dr. Hoernle and the matter must be left there. Dr Hoernle and Mr. Allan are strongly inclined to think, however, that this Flisar was not the place of that name in India, but one of the towns so-called in Central Asia.

P. 355, l. 1 (Note on III. 449, l. 10 f. f.).

The other village mentioned in this paragraph, Mūdūla (l. 21), which was six Kos from Wazīrābād, is Mandaula in pargana Loni It is shown on the Map (facing p. 194) in Mr. E 'T. Atkinson's Statistical Account of the N W. Provinces (1876), III Pt 2. It lies about 15 miles north of Dehli and eight miles south of Kātha. (Ibid. 321).

P. 355, l. 4 f. f. (Note on III. 452, 1 18).

The village of Mansura (1 11), where Tīmūr halted on the day before he reached Pīrozpur, is *Mansūri* or *Masūri* on the Mīrat-Bijnor road near Inchauli, about eight miles from Mīrat (*Ibid.* 322).

'As Mr Atkinson agrees with Elliot in holding that Pirozpur lay north of Bahsuma, on the Budh Ganga in Hastināpur tahşil, Mirat district (*Ibid*, 588), it seems to be the better opinion

P 371, l 15 f, f. (Note on III 545, 1 4)

The name of Khusrav's tribe is always written as J., Parāv, in the Futūhu-s-Salātīn (p 362, verse 6919, p 363, verse 6929, p 380, verse 7186) This can be easily read as J., Pavār, ie Parmār and may lend some support to the old suggestion that Khusrav was some sort of Rajput and a Parmār (Mirāt-i-Ahmadi, I 42, l 12, Bird's Translation in History of Gujarāt, 167 and Note) The T M (86, l. 12) and B (I 203, Tr 274) state that Khusrav had been captured and enslaved during the conquest of Mālwa, the Rājās of which were Parmārs. We know also that 'Alāu-d-dīn Khalji had a corps of Parmār Hājibs (Chamberlains or Guards) in his service and Amīr Khusrav speaks of them thus in his Chapter on the conquest of Dhūr Sāmandar "The Malik [Kāfūr] then ordered some Hindu Parmār ḥājibs to go along with the two or three ambassadors of the Rāi [Ladar Deo] The imperial messengers [i.e. the Parmār Ḥājibs] then attacked the Rāi with their tongues" (Text, 148, l 4, Tr. 92)

P. 372, last line (Note on III 551, 1 3 f. f.)

'Isamı also calls him 'Bhīlam', not 'Bhīm' (Futūhu-s-Salātīn, 226, verse 4417, 274, verse 5288) and this is undoubtedly the correct form. P 380, l 7 f. f (Note on III. 598, l 13 f. f).

'A more satisfactory explanation is perhaps this. Ibn Batūta says elsewhere that there were three cities in Daulatābād "It is divided," he writes, "into three sections, one is Dawlatābād proper, and is reserved for the Sultan and his troops, the second is called Kataka, and the third is the citadel [image], which is unequalled for its strength and is called Duvoaygīr [Deogin]" (Gibb 227)

Kataka seems to have been the old Hindu city of the Yadava Kings and was so called because it was their 'camp' (Sansk. Kataka) 'Isami also repeatedly speaks of the city as (Kahtaka) and the fort or

citadel as 'Deogīr', (p. 226, verse 4416; 227, verse 4425; 480, verse 9250). Ibn Baṭūṭa must therefore mean that 'Duwaygīr' was the name of the Qaṣba, (i.e. citadel, not 'country'), and 'Kaṭaka' that of the old Hindu town.

P. 381, l. 20. (Note on III. 616, l. 1).

These barbarities are mentioned by 'Isāmi also, who declares that Bahāu-d-dīn Girshāsp's skin was stuffed with straw and his flesh cooked and given to the elephants. ($Fut\bar{u}h$, p. 417, verses 7923-6).

P. 400, 1. 23. (Note on IV. 45, Footnote 2).

In the Tārīkh-i-Muḥammadi, compiled by Muḥammad Bihāmad Khān in 842 H., it is explicitly stated that "Mirzā Shāhrukh was still sitting on the throne, which he had occupied for nearly forty years and was recognised by the Kings of India as their suzerain." (Rieu, I. 85).

P. 437, l. 15 f. f. (Note on IV. 247, l. 17).

'Kinkūta' must be 'Gangtha' near Nūrpur (Post Office Guide).

P. 442, l. 11. (Note on IV. 282, l. 4).

'Dakdāki' is 'Dugdugee', 22 miles cast of Fathpur. (Th. 291).

P. 443, l. 21. (Note on IV. 285, l. 3).

Read 'Arra' for 'Kharīd.' Arrah (283, 1. 27) lies in Shāhabād district. Kharīd is now in Bālliā district and lies on the right bank of the Ghogra, but the Kharīd of the days of Bābur included the country on both banks of the river near Sikandarpur and thence on that river's left bank down to the Ganges. (B.N. 664, 637 Notes). Ballīā itself, of which Kharīd now forms a part is stated to have been formerly in Shāhābād district. (I. G. VI. 255). It was afterwards transferred to Benares and then to Ghāzīpur district. (Ibid. 252). It is now a district by itself.

P. 449, l. 22. (Note on IV. 342, l. 9).

Mr. C. E. A. W. Oldham who knows the area very well is sure that the battle took place near Sūrajgarh, probably about 5 miles south-west of the town. The "earthen embankments" of which 'Abbās speaks (339, l. 18), he says, "still stand, though much weatherworn." See his Edition of the Journal of Francis Buchanan (District Bhāgalpur), p. 296, Note 759.

P. 450, l. 13. (Note on IV. 349, l. 14).

Sir Richard Burn informs me that the correct name is not 'Deunru,' but 'Daunrūž.' It is shown on the Map attached to C. H. I. IV.

P. 450, l. 15. (Note on IV. 350, l. 9 f. f.).

This 'Nahrkunda,' or 'Bharkunda,' (p. 419) is not so easily fixed. Blochmann's description of the boundaries is neither clear nor free from difficulties. There is a place called 'Bhurkunda' in Hazārībāgh district. It is a station on the Gomoh-Sone East Bank Railway Line.

P. 486, l. 8. (Note on V. 18, l. 16).

This 'Jund' may be the same as Chund or 'Chaund,' (Chainpur in Shāhābād), mentioned, on IV. 323, l. 5 f. f. q.v. note. Mr. Oldham who holds that opinion, points out that "a main route constantly used by armies went across through Shāhābād from Chunār and Benares towards

South Bihāi "He reinforces the argument by stating that we have no evidence of Chirand being of strategic importance in those days.

P 488, l 17 f. f (Note on V 41, 1 13 f f).

This word is frequently used in the Journal of Peter Mundy also in the form 'Gawares,' for 'villagers, rustics, thievish Hindus, robbers or rebels' (Journal, II. 73, and Sir Richard Temple's Note, 92, 111, 120, 170, 172, 173)

P. 493, 1 7 f f. (Note on V 89, 1 11)

Sir Richard Burn points out that the name of the place is spelt as 'Baksar' and not 'Bagesar' in the U P Gazetteer (1903), (Unão), p. 154 It is there said to have been so called after the shrine of Bakeshwar Mahādeva, which was founded by Tilokchand's tenth ancestor, Rājā Abhaya Chand Bāgheshwar means the 'God of Tigers,' and is an epithet of Mahādeva There is a town called 'Bāgeshwar' in Almora district also. (I. G. VI. 182).

P 497, l 30. (Note on V. 101, 1 23)

Firishta uses the word المايس Kanāis, in connection with the destruction of Hindu temples in the Vijayanagar territories, by Ahmad Shāh Bahmani of Hindu temples in the Vijayanagar territories, by Ahmad Shāh Bahmani المراق الم

P. 511, l 2 (Note on V 217, 1 19)

The name of the place is written as -in the Alsanu-t-Tawārīkh of Hasan Shāmlu, a History of the early Safavis, written in 1080-1085 A.H (Ed N. C Seddon, p 309, 1 8 ff)

P. 512, l. 11 f f (Note on V. 227, 1 2).

The B I. text of the T.A (II. 69, 1 5 f f) inserts a negative in the sentence. If it is right, the meaning would be I have not killed your father (done you any irreparable injury) Why then do you pursue me?

P 519, 7 1 (Note on V 266, 19)

I learn from a local authority that Gunāchaur is just 31 miles southeast of 'Jullunder' city via Phagwāra and Banga or Bunga

'Dihakdār' is mentioned again at A N III Tr. 706 Akbar is there said to have crossed the Sutlej at Māchīwāra, halted his army at 'Dihakdār' and gone on to Ambāla by way of Hādiābād, Jālandhar and Sultānpur Dakdār, Dahakdār or Dārdak is really a compound of the names of two villages which formerly lay in close proximity to each other, viz. one called 'Dakha' and another named 'Dār' or 'Dhār' 'Dakha' still exists and has a Branch Post Office, but 'Dār' or 'Dhār' is now only a mound of ruins, a 'Tibba' or 'Khera'

P 528, 1 18 (Note on V 318, 1 16)

Abu-l-Fazl states that these bellicose Sannyasis were 'Kurs and Puris' and Mr. Beveridge's explanation is that these "names apparently repre-

sent the Kurus and Pāndūs". (A. N. Tr. II. 423 note). Sir Wolseley Haig supposes that these devotees were "accustomed to celebrate the anniversary of the great battle between the heroes of the *Mahābhārat* by a mock combat, but that they had arranged that the combat should be fought in earnest on this occasion." (C. H. I. IV. 95).

I venture to say that neither of these explanations will bear examination. These 'Kurs (or Gurs) and Pūris' belonged to two rival orders of the Dashnāmi Sannyāsis who were at war with each other in connection with their Dakshina and who have been often known to engage in similarly bloody contests. "Shankarācharya had four disciples, each of whom had two or more Chelās of his own, whose total number was ten. Their names were, Tirtha, Āshrama, Vana, Aranya, Sarasvati, Puri, Bhārati, Giri [also Gur or Gir], Parvata and Sāgara. When a Brāhman enters into any class, he attaches to his own denomination that of the class of which he becomes a member, as Tirtha, Pūri, Gir, etc." (H. H. Wilson, Religious Sects of the Hindus, Select Works, Ed. Rost, I. 202 and note). In a similar fight between Gosāins, and Bairāgis which took place at Hardwār in 1760, eighteen hundred persons are said to have been killed. (I.G. XIII. 53). An older incident of 1640 A.C. of which the scene was Dwārkā is recorded in the Dabistān. (Tr. Shea and Troyer, II. 197).

For Tieffenthaler's sarcastic remark, see Bernoulli, I. 137.

P. 537, l. 12 f. f. (Note on V. 369, l. 5 f. f.).

'Newta' or 'Neota' is correct. I am informed that it is a village about seven miles from Sanganer Railway Station.

P. 537, l. 1 f. f. (Note on V. 370, l. 11).

The town which is called Bajuna and said to have been 12 kos from Fathpur (p. 370, l. 11) is Bajna. It is now in Bhartpur State and shown in Constable, 27 C b.

P. 543, last line. (Note on V. 407, l. 4).

There is a town called Lünkaran-nagar in the State of Bikaner (P. O. G.). This should demonstrate the unsoundness of Mr. Beveridge's derivation of the name of the Rājā.

P. 544, l. 17. (Note to V. 407, l. 7).

Speaking of Tānsen, it may be worth while to note that Mr. Vincent Smith's statements about "the date of his death having not been recorded and of his having continued to serve in the court of Jahāngīr" (Akbar, 423) are erroneous. The death of the Master on 15th Ardībihisht of the 34th year, [26th April 1589], is registered in the Akbar Nāma (III. 537, Tr. 816). The portrait "of Jahāngīr's reign, depicting a court group, which is in the possession of the Royal Asiatic Society" may be "well executed" and of great artistic interest, but it cannot disprove the fact of his death having preceded Akbar's by sixteen years.

P. 555, l. 6 f. f. (Note on IV. 451, l. 13).

As there are at least five different recensions in Sanskrit of the Vetālapanchavinshati, it may be necessary to state that this story is the

fourth (not the third) in Dr Emenau's recently published text and translation of Jambhalabhatta's recension (pp 42-46) and is entitled 'How Virginara saved his Lord's life'

P. 580, 1 9 (Note on VI 91, 1.17)

I now think that it must be Shaikhūpur in Kapurthalā State. Akbar is stated to have gone out for hunting, and arrived at Sultānpur on the bank of the Biāh The Khān-i-Khānān was summoned from Sirhind, where he had gone to pay his respects to Prince Dāniyāl (Maāsur-i-Ralimi, E D VI 240) Shaikhūpur is about three miles west of Kapurthalā, which is about twelve miles north-east of Sultānpur

P 581, l 2 f f. (Note on VI 101, l. 6 f f)

He is called Vanangpāl Nāik Nimbālkar and Jagpatrão (not Jagpālrão as in Grant Duff) by Kincaid (I 114) But perhaps both these forms are factitious creations of local panegyrists.

P. 590, 1 16 (Note on VI 151, 1 13)

The origin of this strange and much-misunderstood designation is said to have been that Akbar was accustomed to take his both in a suite of rooms, which lay between the Harem and the Diwankhana At first, a few only of his most confidential attendants were permitted to see him here. The Diwan and the Bakhshi were then granted admission on urgent State business and lastly the greater nobles were granted the same privilege, so that many important State affairs came to be discussed and settled there As Shāh Jahān did not like the name, 'Ghusalkhāna,' he ordered it to be called 'Daulat Khāna-i-Khāṣ' (Bādshāhnāma, I i 148, I 3) See also 'A S (I 247), where the same explanation is given and it is said to have been called Khilvat Khāna also

P. 602 (Note on VI. 311, 1 12).

"The verse of Mîr Khusrau", which the Imperial diarist quotes, will be found in the Qirānu-s-S'adain

('Aligarh Lith p 32, 1.7)

P. 613, l 8. (Note on VI 368, l. 12).

This third opinion is held by Mr J. L. Dames also

"The Karlugh Turks were associated with the Shahs of Khwarizm and established a principality in Bannu and Kuriam and were known as the Karlugh Ming or Hazara" (Houtsma, EI Vol. II 298).

P 656, 7 12 (Note on VII 289, 1 7)


Nārāyan Shenvi, an English agent who had been sent to negotiate a treaty of peace between the East India Company and the ruler of Janjīra, speaks in a letter written from Rāigarh on 4th April 1674, of the 'Siddi Fath Khān' Sir Jadu Nāth Sarkār, who has unearthed the letter, remarks that "Khāfi Khān is thus proved by contemporary records to be unreliable, as Fath Khān was not an Afghān" (Shivaji, 263 note) See also D R. Banāji, Bombay and the Sidis, pp 11, 15
P. 675, 1 3 f. f (Note on VII 503, 1 3 f. f).

In John Burnell's recently published 'Account of Bombay in the Days of Queen Anne,' the writer speaks of "four brass petteraroes and ramtackers, fixt with swivels, which carry an eight-ounce shot" (p. 59). The Editor cites three other examples of the use of the word, and notes the suggestion that it may have some connection with Hindi takkar, 'striking, impact, knock.' But may it not be 'Ramjackers', or 'Ramjackees'—a corruption of Rāmchangi or Rāmjanki?

P. 676. l. (Note on VII. 512, l. 14).

Husainpur is a village in pargana Palwal, about 24 miles north-west of Agra, on the right bank of the Jumna. Biluchpur, where Muhammad Shāh had his camp, lies about six miles north of it. It is, most probably, identical with the Biluchpur which is mentioned on VI. 386, l. 17. Shāhpūr (511, l. 27) lies about ten miles south of Bilūchpur. (L.M. II. 80, 82). P. 694, l. 3 f. f. (Note on VIII. 196, l. 14 f. f.).

The 'Diwān-i-Tan' and the 'Diwān-i-Khāliṣa' are mentioned by Khwāsi Khān also. (E. D. VII. 426). As Dowson has translated the first phrase there as 'Diwān of the person', it seems necessary to stress the fact that 'Tan' is really the short form of 'Tankhwāh', i.e. Cash salaries. (Irvine, A. I. M. 39). Manucci tells us that "the second highest official in the Empire, (the Wazīr being the first), is the Dīwān of the Salaries. His duties are the receiving of all the revenues of the Empire, the realising of the property of deceased persons, and the resuming of the property of all those who are removed from the service. He also carries out any alterations in offices or allowances". (Storia. II. 419). Dr. Ibn Hasan says that as "all papers relating to the Tankhwāh passed through the hands of this minister, he had to keep a list of Manṣabdārs, a record of revenues collected and of sureties taken from officials, a Register of branding and verification, and the accounts of salaries of all Manṣabdārs." (Central Structure of the Mughal Empire, 208).



STUDIES IN INDO-MUSLIM HISTORY,

BEING

NOTES ON ELLIOT AND DOWSON'S HISTORY OF INDIA,

AS TOLD BY

ITS OWN HISTORIANS.

EARLY ARAB GEOGRAPHERS.

I. 1. 1. 7. Abū Zaidu-l-Ḥasan of Sīrāf.

Sīrāf has disappeared from all modern maps and its place knows it no more. It was situated midway between Bushire on the N.W. and Kīsh on the S.E. "It was the most important and flourishing port in the Persian Gulf in the early days of Arab rule. Its prosperity appears to have lasted from the seventh Christian century to the twelfth." (Dames, Tr. Barbosa. I. 80 note). Qazvīni compares it to Shīrāz and Muqaddisi to Baghdād (Le Strange, Lands of the Eastern Caliphate, 257-9). It is now represented by Tahiri, Lat. 27°-40′ N., Long. 52°-12′ E. which is shown in the Times of India New Pictorial Atlas of the World, Pl. 63.

1. 3. 1. 8 from foot. The Bulharā is the most eminent of the princes of India.

Elliot's note on the Balharā (354 infra) is now out of date. The power of the Rājās of Valabhi, with whom he seeks to identify them, had been demolished before the end of the eighth Christian century. The Balharās of Sulaimān and Mas'ūdi were the Rāshṭrakūṭas, who styled themselves 'Vallabha' in imitation of their predecessors, the Chālukyas. Govinda III Rāshṭrakūṭā calls himself Vallabha, Vallabha-Narendra, or Prithivi Vallabha. Vallabha-Narendra is identical in meaning with Vallabha-Rājā, the Prākrit form of which would be Vallaha-Rāya or Ballaha-Rāya. This was corrupted into Balharāy or Balharā by the Arabs. Dr. Bhāu Dāji was the first to advance the conjecture and it was endorsed by Bühler in Ind. Ant. VI. 64, but the question was really settled only when [Sir] R. G. Bhandārkar explained the true origin in his History of the Dekkan (First edit. 1884, p. 50. Vide also Bombay Gazetteer. I. ii. 209; Fleet, Ibid., 388 note; V. Smith, Early History of India, Ed. 1908, pp. 388-9).

I. 3. 1. 3 from foot. He gives regular pay to his troops, as the practice is among the Arabs.

This is differently rendered in the Old English Translation which was made from Renaudot's French version in 1733. "This king makes magnificent presents after the manner of the Arabs" (p. 15).

Mons. Gabriel Férrand also in the more recent translation of the writings of Sulaiman and Abū Zaid Hasan interprets the words in the same way "Le Balhara fait des dons genéreux comme les Arabes" (Voyage du Marchand Sulaiman, 1922, p 47) Thus there is really no contradiction between this statement and that to which Dowson draws attention in his footnote to p 7 post.

I 3. last line. The coins which pass in his country are the Tatariya dirhams

Cunningham identifies the Tātariya dirhams with "the rude silver pieces generally known as Indo-Sāssānian, because they combine Indian letters with Sāssānian types. They would appear to have been first introduced by the Scythian or Tātār princes who ruled in Kābul and North-western India, as they are now found throughout the Kābul Valley and the Panjāb, as well as in Sind, Rājputānā and Gujarāt. In weight, they vary from 50 to 68 grs and in age, they range from the fifth or sixth century down to the period of Mahmūd of Ghazni. They are frequently found with the silver pieces of the Brāhman kings of Kābul, which agrees with the statement of Mas'ūdi that the Tātariya dirhams were current along with other pieces which were stamped at Gandhārā. The latter I take to be the silver drachmas of the Brāhman kings of Kābul whose dynasty began to reign about 850 A.D." (Ancient Geography of India, Ed. 1871 pp. 313-14)

Cunningham's explanation is certainly more satisfactory than Thomas's functful derivations of 'Tatariya'-from the Tahirides or the still more remote Greek 'Stater' The only difficulty is that both Sulaiman and Mas'udı state that the Tatarıya dırhams exhibited on their surface the year of the reign of the king in whose name they were struck But these Indo-Sassanian or Gadhiya coins bear no inscription whatever, neither name of ruler, nor date They do not even exhibit an easily "intelligible device" and it was only after the study of an extensive series of specimens that modern numismatists were able to recognise in "the apparently meaningless marks, extreme degradations of the king's bust and the fire-altar with attendants, which are the characteristic features of the Sassanian coinage" (Vincent Smith, Catalogue of Coins in the Indian Museum, I 233 Pl. xxv). derivation of the synonymous designation, Gadhiya, is uncertain One suggestion is that the worn fire-altar was supposed to be an ass's head and gave rise to the appellation of 'Gadhiya Paisa' or 'Ass-money'. (BG I 1 469 n). Another connects it with the Gadhwal [Gahadwal, or Gardabhila] dynasty of Qanauj

I 4.1 2 They are dated from the year in which the dynasty acquired the throne

But Mas'ūdi who has copied the passage from Sulaimān says "The coins are impressed with the date when their king succeeded to the throne" (El-Masudi's Historical Encyclopaedia, Tr. Sprenger,

389). Meynard's rendering is similar: "they bear the date from the accession of the reigning prince" (Tr. in Prairies d' Or. I. 383). In the old English version, the passage is translated thus: "They bear the year of his [the king's] reign, from the last of the reign of his predecessor" (p. 15). The words used by Mas'ūdi are المنافذ المناف

I. 4, l. 15. And their [Balharā] kings live long, frequently reigning for fifty years.

This happens to be actually true of the Balharā or Rāshṭrakūṭa kings of the period in which Sulaimān and Masʿūdi lived and wrote. Amoghavarsha I reigned from 814 to 877, and his son and successor, Krishna II, from 877 to 915 A.C. (Duff, Chronology of India, 300; Smith, E. H. I. 387; Bhandārkar in B. G. I. ii. 199-203; Fleet, *Ibid.* 401-415).

I. 5. l. 1. The women [of the kingdom of Tāfak] are white and the most beautiful in India.

Mas'ūdi who has copied the passage into his own work adds these words: "They are praised for their beauty in books De Coitu (حَبَالِنَاء , Ars Amatoria) and sailors are exceedingly anxious to buy them. They are known under the name of Tāqinians." (Sprenger, loc. cit. 390, Prairies. I. 383). Yule understood the allusion as applicable to the "race now called Kāfirs, the beauty of whose women is still so much extolled." (Cathay and the Way Thither, Ed. Cordier, I. 242 note). Cunningham was disposed to think that the women of the lower hills in the Punjāb were meant (A.G. I. 152). But Sulaimān's Ṭāfak [or Ṭāqan] was a small kingdom which covered the modern districts of Siālkot and Gujrānwāla (Imperial Gazetteer ot India, Ed. 1908, XII. 353) and the allusion may be to the women of the Gakkhars, who are found in these districts and are "famed for their beauty." (Erskine, History of Babar and Humayun, II. 425).

The old kingdom of Tāqi which Hiuen Tsiang calls Tseh-kia, had "embraced the whole of the Punjāb plains from the Indus to the Beas", (Tr. Beal, Buddhist Records of the Western World, I. 165 note; Cunningham, A. G. I. 148; Smith, E. H. I. 327), but it was greatly reduced at this time and we know that Sankarvarman, the Rājā of Kashmīr, had compelled Alakhana, the Gurjjara king, to cede to him Takkadesha, which was a part of his dominions, at some time between 883 and 901 A.C. (Rājatarangini, V. 150; Duff, C. I. 80). The Takkas were "a powerful tribe who were once undisputed lords of the Punjāb and who still exist as a numerous agricultural race in the hills between the Jhelum and the

Rāvi" (A. G. I 152).

I 5 1 5 These three states border on a kingdom called Ruhmi

Most authorities are agreed that this kingdom of Ruhmi was in Bengal The elephants, the exceedingly fine muslins, the thinoceros, the Kaudis used as money, all leave no doubt on that head But the origin of the name has not been satisfactorily elucidated Yule was at one time inclined to trace Ruhmi to Rahmaniya, "the name by which Pegu is mentioned in Burmese literature" (Cathay and the Way Thither, Ed Cordier I 243) Afterwards. "he derived it from Rāmu, which lies half-way between Chittagong and Akyab, a few miles east of Cox's Bazar in Ārākān", because "during the dispute which led to the First Burmese War in 1823-4, the governor of Arakan demanded from the British the cession of Murshidabad and all the provinces to the east of it, as they were all natural parts of his own kingdom" (Travels of Marco Polo Tr II 100). The great Arabist Lane thought that Ruhmi was Sumātra (Trans Alf Laila, Notes, III 80) Other authors connect it with 'Mrohaung' or 'Myohaung' (now in Akyab district), one of the old capitals of Ārākān

But Ārākān is rarely, if ever, mentioned in Hindu literature or history. It was a remote tract inhabited by savages who were beyond the pale of civilization. It is also improbable that a kingdom of the fame and magnitude which the Arab travellers ascribe to Ruhmi should have been named after an obscure place like Rāmu or even after Mrohaung Moreover, it appears clearly from the annals of Ārākān itself, that the capital of the province in the ninth century was not at Mrohaung, but at Dwāravady near the modern Sandoway. It was removed to Mrohaung, further north, only in the tenth century, many years after Sulaimān wrote. (Imp Gaz v 391-2, Phayre, History of Ārākān.)

Mas'udı also mentions the kingdom of Rahma and expressly states that "Rahma is the title for their kings, and generally at the same time, their name." (25 infra) The significance of this cannot be over-emphasised It seems to me to furnish the clue to the solution of the riddle We know from the evidence of contemporary inscriptions that Bengal was at this time ruled by the Pala dynasty A chieftain named Gopala, who was a devout Buddhist, became king about 740 AC He is said to have have forty-five years and to been by Dharmapala who is certainly known from epigraphic evidence have reigned for, at least, thirty-two years "The Tibetan historian, Taranath, states that his kingdom extended from the Bay of Bengal to Jalandhar in the north and the Vindhyan range in the The chronology of the dynasty has not been exactly determined, but Dharmapala is held by a consensus of competent scholars to have been reigning about 810 A.C. (Smith, E H. I. 367-8, Duff, C I 75, 298). A more recent writer, Mr R. C Majmūdar, holds that he reigned from 780 to 812 A.C. (Art. on the Chronology of

the Pala Kings in J. A. S. B. 1921, p. 5). Mr. C. V. Vaidya thinks he was in power from 800 to 825 (Mediaeval Hindu India, II. 140).

It seems to me that 'Rahma' which is said by Mas'ūdi to have been the title or name of the king as well as of his kingdom, is to be explained by the fact that the kingdom was described in the original writing to which Sulaimān and Mas'ūdi were indebted for their knowledge, as which Sulaimān and Mas'ūdi were indebted for their knowledge, as the constant of the control of the lingdom of Dharma' and also 'the king Dharma'. The 'dāl' was subsequently supposed to be a 're' and the 're' a 'wāv'. The phrase was thus misread as of the control of the lingdom of Ruhmi'.

Sulaimān's account of the Indian kingdoms is, as Yule puts it, "a medley of disjointed notes put together at random and the information is extremely vague." His knowledge of India was both "slight and inaccurate and he had no distinct conception of the magnitude of the country" (Cathay, I. Introd. ciii). He does not appear to have personally known anything of Bengal and he is repeating only what he had heard or read in some previous author. This is clear from the expressions, 'It is said' and 'It is stated,' which he prefixes to his averments. It seems almost certain that he found the name of the kingdom or the king only in some manuscript and read it wrongly as Al-Ruhmi instead of 'Al-Dharmi' or 'Al-Dharma'.

Another possible elucidation may be 'Rangamati', which would be written as رجنى by Arabs, and might have been wrongly read as رجنى (Rajmi) and then رحبى (Ralmi). Rangamati (Constable, Pl. 29 Cc) was the old capital of Karna Suvarna and lies 12 miles north of Murshidābād in Bengal, on the site of an old city called Kurusona-ka-gaḍh, which is a local corruption of Karna Suvarna (J. A. S. B. xxii, 281 ff; lxii. 315-28; Ind. Ant. vii. 197; E. H. I. 311 note). The kingdom comprised the modern districts of Bhāgalpur, etc. and is said by Hiuen Tsiang to have been ruled by Śaśānka in the 7th century (Beal, loc. cit. I. 201, II. 210, 212). But this explanation is negatived by the fact that Rahmi is written by Sulaimān as well as Mas'ūdi (Prairies. I. 384; Sprenger, 390) not as condition is described by the Persian.

In any case, it is clear that if Mas'udi's statement about 'Rahma' having been the name of the king, has any meaning or significance, the derivations from Rahmaniya, Rāmu and Mrohaung must be untenable and badly off the mark.

1.5.1.7. He [the king of Ruhmi] is at war with the Balharā, as he is with the king of Jurz.

deprived of his throne by Nāgbhatta, the Gurjjara king of Qanauj "During the reign of Nāgbhatta, the chronic warfare between the Gurjjaras and Rāshtrakūtas continued, and Govinda III claims to have obtained a victory over his northern rival" (E H I 350, op. Vaidya, cit II 140, 146) In 916 A C "Indra III Rāshtrakūta captured Qanauj, but Mahipāla, the Gurjjara king, afterwards recovered his capital with the aid of the Chandel ruler" (E H I 351-2)

It may be worth while to stress here the fact that no ruler of Pegu or Ārākān is known to have ever gone to war either with the Rāshtrakūtas or the Gurjjaras of Qanauj or vice versa

1 5. 1. 5 from foot After this kingdom [Ruhmi] there is another in the interior of the country, away from the sea It is called Kāshbīn.

The reading in the corresponding passage of Mas'udi is کامن Kaman (25 infra, and Prairies I 388) M Ferrand proposes to transform 'Kāshbīn' into 'Lakshmipur' and to identify it with Lakhimpur in Assam But this is a violent and uncalled-for alteration and Mas'udi's lection indicates that the country referred to is Kamata addition of a single dot is all that is required Kamatapur, the capital. lav on the eastern bank of the Darla river, which flows south-west of the modern town of Kuch-Bihar and joins the Brahmaputra near Bagwah (Blochmann, J. A S B 1873, Pt 1. 240) The runs of the old city still strike all beholders with astonishment and are said, by Buchanan, to be 19 miles in circumference (Gait, History of Assam, 42) The place is marked in Constable's Atlas, Pl 29 C b and is about thirty miles north of Rangpur (I G XXI 225) Kāmata was the western division of ancient Kamarupa, which was itself the western part of the Brahmaputra Valley, Assam proper being its middle part and Sadiya the eastern (Cunningham, A. G I 500).

The chief point noted about the people of the country by Sulaiman, as well as by Mas'ūdi, is that the inhabitants were fair and handsome The beauty and charm of the women of Kāmarūpa is the subject of frequent allusion and admiration in Sanskrit literature. Abul Fazl states that the people of Kāmarūpa, (which he notes is also called Kāmta), are a good-looking race (Āīn Tr Jarrett II. 117). Shihābu-d-din Tālish, who took part in Mīr Jumla's illusory conquest of Āssām, and wrote a contemporary account of it, observes that "the women of Āssām are remarkable for the beauty and delicacy of their features, softness of body, fairness of complexion, and the loveliness of their hands and feet" (Fathīyya i 'Ibi iya. 'Tr by Sir Jadu Nāth Sarkār in Journal, Bihār and Orissa Research Society, I. 1915, p. 190).

The identity of this Kāshbīn or Kāman with Kāmta in Kāmarūpa is also shown by the fact that Khurdādbih specifically mentions the king of Qāmrūn, "which is contiguous to China", as the seventh of the great govereigns of India, the other six being the Balharā, the rulers of Ṭāfan, Jāba, Juṛr, Āua and Rahmi (13 and 14 infra).

I. 5, last line. He [the king of Kiranj] collects large quantities of amber.

What Sulaimin means, is not 'amber', but 'ambergris.' Amber is a fossilised vegetable production, or resin. It is, as Tavernier puts it," the congelation of a species of gum". (Travels, Tr. Ball. II. 137). Ambergris consists of the "ficees of the Cachalot or sperm-whale which inhabits the Indian Ocean". (Ibid. 138 note).

The confusion between 'amber' and 'ambergris' is of long standing. Mr. Dames notes that in Barbosa and other Portuguese writers of the 16th and 17th centuries, ambre means 'ambergris' and not 'amber' and he deplores the fact that Sir Clements Markham should have disseminated an ancient error by rendering ambre by 'amber' and not 'ambergris', in his Translation of Garcia d'Orta's work on the 'Drugs and Simples of India'. Garcia states that this ambre is of three sorts, white, grey and black, and that it is found in the Maldive Islands. The old English factor, Ralph Fitch, also speaks of this substance as 'ambre', but means ambergris. (Foster, Early English Travels in India, 47).

The word used in the original Arabic text is and it is correctly rendered by 'ambergreese' in the old English translation of 1733. Salaimān explicitly states there that 'ambergreese' is obtained in the Maldive Islands and is found there in "lumps of extraordinary bigness" at the "bottom of the sea." (loc. cit. 2). Abu Zaid also speaks of a variety of 'Ambar or ambergris, which is "found in the belly of a fish of the whale kind." (Ib. 94; see also Mas'ūdi, Sprenger, 349; Prairies. I. 334).

Qiranj may be Kalinga, the old name of "the region once known as the 'Northern Circars' on the coast of the Bay of Bengal, extending from the Krishna to the Mahānadi." (Yule, Hobson Jobson, s. v. Kling). Thornton says (Gazetteer, s. n.) that the 'Circars' correspond to the modern districts of Guntūr, Masulipatam, Rājmundry, Vizāgāpatam and Ganjam. But the form 'Qiranj' bears a greater phonetic resemblance to Coringa, an ancient seaport in the Coconāda tāluk of Godāvari district, which his 32 miles south-east of Rājmundry. The East India Company had a factory here. (I.G. X. 398; H. J. s. v. Coringa). The king of Qīranj is here said to have been also "well-provided with elephants' teeth," and Mas'ūdi, too, states (25 infra) that the country "produced large numbers of elephants." Hiuen-Tsiang had observed about three hundred years before, that Kalinga was noted for its breed of "tawny wild elephants which are much prized by neighbouring provinces". (Tr. Beal, II. 207).

1. 6, 1. 2. They eat pepper green in this country because it is scarce.

The meaning of this paradoxical averment seems to be that the quantity grown in the surrounding parts was not so plentiful that the surplus could be dried for purposes of export. Barbosa makes a very similar remark about the island of San Lourenço, (Madagascar). "There is," he writes, "ginger in the island, of which they make no use,

save to eat it green." (Travels, Tr. Dames. I. 25).

I 6, l. 4. When the king of Sarandib dies, his corpse is carried on a low carriage very near the ground, etc.

I do not know if this strange custom really existed at any time in Ceylon, though it is just what might be expected from the Buddhist doctrines of the vanity of all earthly things. The nearest approach to a parallel that I can recall is in the Sixth Voyage of Sindbād. It is there said of the king of Sarandīb that "while he is on a march, an officer who sits before him on an elephant, from time to time, cries out with a loud voice, 'This is the great Monarch, the powerful and tremendous Sultan of the Indies. ... This is the crowned Monarch, greater than even was Solomon or the great Mahrāj' After he has pronounced these words, another officer who is behind the throne, cries in his turn, 'This monarch who is so great and powerful must die, must die, must die, The first officer then replies, 'Hail to Him who lives and dies not!'"

I 6. l. 8 from foot. What astonished me was that he was not melted by the heat of the sun

But in the Old English Translation, the sentence is rendered thus "I was astonished he had not lost his eyesight by the heat of the sun." (p 32) And M. Ferrand's much more recent French version is in exact agreement with it "Je fus etonné que son œil n'ait pas été detruit par le chaleur du soleil" (loc cit 66). The man who stood naked with his face turned towards the sun was one of the sect of Ākāshamukhis whom Hiuen-Tsiang saw at Prayāg "They keep themselves," he writes, "stretched out in the air from the top of a pillar, with their eyes fixed on the sun, and their heads turning with it to the right as it sets" (Beal loc cit I. 234) Mr Crooke tells us that the sect still exists "They are followers of Shiva and are so called because they keep their face turned toward the sky until the neck muscles become rigid, and the head remains fixed in that position" (Tribes and Castes of the North-Western Provinces, I. 78)

I 8. l 1 There is a story concerning a king of Kumar

Qumār is neither the country about Cape Comorin, as Dowson imagined, nor Kāmarūpa, as others have suggested. It is Khmer, the old name of Cambodia or Annām "The various indications given by the Arab geographers leave," states Yule, "no doubt on that head. It was, they say, (1) on the continent and facing the direction of Arabia, i.e. West (2) It produced the most valuable kind of aloe-wood (3) It was three days' voyage west of Sanf (Champa or Cochin China) and 10 or 20 days' sail from Zābaj" ie Samātrā or Jāvā" (Cathay, First Ed 519, 569, H J s v Comar). Khurdādbih explicitly states that the Qumāri aloe wood was so called because it came from Qumār, a country three days' journey from Sanf i e Champa (Text in Journal Asiatique, (1865), p 291.—Goeje's Ed in the Bibliotheca Geographorum Arabicorum, VI, 68, 1 13, Tr 49)

I. 8. 1. 6. The inhabitants [of Comar] abstain from all sorts of wine.

Here is another parallel from the Arabian Nights. "From thence we made for the island of Comari, where the best species of the aloe grows, and whose inhabitants submit themselves to a law not to drink wine." (Sindbād's Fifth Voyage).

1.8.1.7 from foot. The king [of Zābaj] and his warriors all carried tooth brushes and cleaned their teeth several times a day.

This incidental reference to a characteristic trait of Hindu manners is noteworthy. Contrasting Chinese manners with those of the people of India, Sulaimān notes that "the Indians wash and clean, not only their mouths with tooth brushes and water, but the whole body, before they eat, while the Chinese have neither of these customs." (Old English Trans. 36). Hiuen-Tsiang also was struck by the novelty of the practice, as he had not witnessed it in his own country, and writes, "After eating, they [the people of India] cleanse their teeth with a willow-stick and wash their hands and mouth." (Beal, I. 77). The people of Zābaj (Sumātrā) had Indian affinities and appear, in fact, to have been colonists from India. Those of Qumār [Khmer] were offshoots of the Yellow Race. The two peoples had carried their national customs to the country of their adoption.

M. Gabriel Ferrand has recently suggested, in the light of certain inscriptions, that this Mahārāj was the king of Sumātrā, and not of Jāvā, and that this invasion of Khmer actually took place, at some time in the 8th century in the reign of Jayavarman II, r. 724-791 A.C., or that of his predecessor. (Journal Asiatique, 1932, p. 275 and note).

I. 9. 1. 8 from foot. All those who eat the rice are obliged, when the king dies or is slain, to burn themselves to the very last man.

This custom seems to have prevailed all over India and was not confined, as Reinaud asserts, to the Nairs. Mas'udi, who has copied the statement, adds that the men who thus killed themselves immediately after the death of their king were called الله المنابع الم

Bāṇa informs us that when Prabhākar Vardhana, the father of Harsha of Qanauj died (c. 605 A.C.), his physician and several of his ministers and servants burnt themselves with him (Harsha Charita, Tr. Thomas and Cowell, 161). The usage is mentioned also in Dandin's Dasha Kumār Charita (Pūrva Pīthikā, Ucchvās 4. sub initio). When Vīradhavala Vāghela died (1238 A.C.), "one hundred and eighty-two of his servants passed with their lord to the flames and Tejahpal, his minister, had to interpose a military force to prevent further sacrifices". (Forbes, Rās Mālā, Oxford University Press Reprint.

I 251, B G I Pt. 1 203).

The voluntary immolation of the intimate associates of Indian kings 18 also mentioned in the Kitab al Fihrist of Abul Faraj Muhammad bin Ishāq (written in 377 H. 987 AC) He states that "there is in India a sect called Al-Rahmaryna (الراحريه) They are the partisans of kings, and it is a part of their law in their religion to aid kings They say God the has made them kings and if we are slain in their service, we go to Paradise" (Tr by Rehatsek in JBBRAS XIV Rehatsek suggested, following Brokhaus and Reinaud, that the name must be Rapputriyah, 'sons of kings', but my submission is that the correct restoration is Rajamaitraiha, 'friends of the king', "sincere friends who died with his death, and lived with his life," as Mas'ūdi puts it The author of the عطاي الهد (c 1013 A. C) 'Book of the Marvels of Hind'. (Livre des Merveilles de l'Inde, Ed. Van der Lith and Marcel Devic, 115 and 118) also refers to the practice Amir Khusrau also, has left it on record that when Harpala Deva, the son-in-law of Rama Deva of Devgiri, was flayed alive by the orders of Qutbuddin Mubarak, "the Hellites who had accompanied him out of regard and fought by his side. also afforded food for the flames of the infernal regions" (Nuh Sipihr in E D III 564) At a still later date, Barbosa observes that "when the king of Narsynga [Vijayanagar] dies, not only four or five hundred women, but many men who are his intimates are also burnt with him " (Tr Dames, I 217) Lastly, Abul Fazl says in the Ain-i-Akbari that when the king of Assam dies, his principal attendants of both sexes voluntarily bury themselves in his grave (Tr Jarrett II 118)

I 10 l 15 from foot There is a numerous colony of Jews in Sarandib and people of other religions, especially Manichaeans

There is no specific reference to Manichaeans here. The word used is 'c' (Old English Trans p 84), which is applied very loosely to Dualists in general, ie to all persons who believe in Two Principles or Personalities and not to Manichaeans only Mas'udi reckons among the 'Sanawiya' the followers of Manes, Marcion, Bardesanes, Mazdak, etc (Sprenger, 22S and note = Piairies, I 200) An identical statement occurs in the Fihrist of Ishāq-al-nadīm (Nicholson, History of Arabic Literature, 364)

Cosmas, an Egyptian monk, who wrote about 547 A C a geographical treatise, entitled the 'Christian Topography,' says of the island of Taprobane or Siedliba [Sinhaldvipa] that it was "a great mart for the people of those parts and that it had a church of Persian Christians who had settled there, a Presbyter who was appointed from Persia and a Deacon and a complete ecclesiastical ritual" (Tr McCrindle, Hakluyt Society, 365) The men referred to by Cosmas were not Manichaeans but Nestorian Christians from Persia The Nestorians are included in the Sanawiya or Dualists, by Shahrastāni and other Arab writers, because though they "believed in the divinity and humanity of Christ, they

denied their union in a single self-conscious personality. As the personality was thus broken up by them into a duality, they were called Dualists." There can be little doubt that Abu Zaid's Sanawiya were Persian or Syrian Christians of the Nestorian persuasion, not Manichaeans. The old Christian communities which had settled at Quilon, Kottayam, St. Thomas's Mount and other places in Southern India, so early as the sixth century, all belonged to this Syrian or Nestorian Church (Smith, E. H. I. 221-2. Rae, the Syrian Church in India, passim; Houtsma, Encyclopaedia of Islam. III, 903.) Their descendants still constitute a progressive and influential community in Travancore.

I. 10, l. 13 from foot. Great licentiousness prevails in this country [Sarandīb] among the women as well as the men.

This is most probably an old voyagers' canard. Yule tells us that the custom of getting wives and daughters prostituted by strangers is attributed by old European travellers to various peoples. Marco Polo ascribes it to a province of Tibet. (Travels, Tr. Yule, I 210; 212; II. 530), Varthema to the people of Tenāsserim (Tr. Badger, 202), Richard to the inhabitants of Ārākān (Pinkerton's Collection of Voyages and Travels, IX. 760-1), Linschoten to those of Pegu and Tenāsserim (Ed. Burnell and Tiele. I. 98), Bernier to certain remote districts in the Himālayas, and Captain Wood and others to the Hazārās. (Journey to the Source of the Oxus, 129). Yule remarks (Tr. Marco Polo, II, 56-7 notes) that some at least of these asseverations are mere travellers' tales and totally unworthy of credit.

However that may be, this scandalous imputation of lubricity to Ceylon's womankind is found in Manucci also. He states that it was "the custom of the country and that they held it a great honour to entertain Portuguese soldiers and even friars in this way". (Storia, Tr. Irvine, IV. 152). And Robert Knox had, some years before, preferred the same charge against the people of the island. "When intimate friends or great men chance to lodge at their houses, they will send their wives or daughters to bear them company in their chamber.... They do not matter or regard, whether their wives, at the first marriage, be maids or not; and for a small reward, the mother will bring her daughter, being a maiden, unto those that do desire her." (Historical Relation of the Island of Ceylon, Ed. 1681, p. 92; Ed. of 1817, pp. 186-7).

I. 11. l. 5. The Indian aloes called al Kāmrūni from Kāmrūn, the name of the country in which it grows.

It is not easy to say whether this 'Kāmrūni' relates to Khmer. [Cambodia] or Kāmarūpa [Āssām]. "The fine eagle-wood of Champā" [Cochin-China] and Khmer [Cambodia]," writes Yule, "is the result of disease in a leguminous tree, the Aloexylon Agallochum, while at inferior kind, though of the same aromatic properties, is derived from an entirely different order [Aquilariacew], Aquilaria Agallochum. and is found as far north as Sylhet." (Traus. Marco Polo, Ed. Cordies, In

272). The first is the variety called Qumāri (p 8 ante), from Khmer, the old name of Cambodia, the second, is the Kāmrūni of Idrīsi But the two varieties are often confounded by Oriental writers on account of the phonetic resemblance between Qumāri, Qāmrūi, Kāmrūni and 'Kāmrūpi' The Kāmarūpi aloe-wood is that which Abul Fazl refers to, when he says that the darakhti-tūd exists in the hills of Sylhet (Aīn, Text. I 391. Tr Jarrett, II. 125)

Abu Zaid's 'Kāmrūni' aloe-wood may be the product from Khmer, as Mas'ūdi who has borrowed the passage speaks of it as 'Qumāri' (Sprenger, 384, Frances I, 376), and both these authors lay stress upon its having been of the 'finest' and most expensive variety But Abu Zaid's spelling may point to the Assām variety

Qazvīni quotes, from the spurious work attributed to Mis'ar bin Muhalhil, a passage in which Saimūri aloes or aloe-wood from Saimūris mentioned, but 'Saimūri' must be an error of transcription for Qumāri I 13, l 7 The other sovereigns of this country are those of Jābā, Tāfan,

Juzr, Ghānah. I he king of Zābaj is called Alfikat

The fourth name is written as ale, as and ale (1.17 infra) Goeje in his edition of Khurdādbih reads ale Ghāba (Text, 16, 1.11, Tr 13, 67, 17 Tr 47) I have shown in another note that Khurdādbih is referring to the king of the ale is the Pāndya ruler of Madura, M'abar or the Coromandel coast Goeje reads the name of the king of Jāvā as and explains it, on the authority of Kern, as Pati-jab, or Jāvāpati, Lord of Jāvā (Tr 13 note)

I 13 l 11. The kings and people of Hind regard fornication as lawful and wine as unlawful

The word in the text is which means illicit sexual intercourse of any kind, ie formication and adultery, but also prostitution. It is in this last sense that it is used here. Ma'sudi notes with surprise that was recognised and regulated by law in China and that the State derived a revenue from the women who lived such disorderly lives. Both Sprenger (l c 317) and Meynard (I 296) render where by "prostitution"

As regards the punishment of adultery by the Hindus, the older traveller, Sulaiman notes that "if any man in the Indies runs away with a woman and abuses her body, they kill both him and the woman, unless it can be proved that she was forced, when the man only is punished." (Old Eng Trans 34) On the other hand, Abu Zaid, remarks in his 'Supplement', that "in the Cans or Inns, which the Indians build for the accommodation of travellers, they settle public women ... who expose themselves to travellers and the Indians number this among their meritorious deeds." (Ib 87-8).

But Alberuni puts the matter in truer perspective thus "People think with regard to harlotry that it is allowed with them [the Hindus] ... In reality, the matter is not as people think, but it is rather this that the

what the Portuguese writers called the Costa da Ensiada, that is, "the Indian coast line beginning from Point Calimere and reaching as far as Tuticorin" (Manucci, Storia, Tr Irvine III 237 note) The Dutch also applied this term to "the southern boundary of Rāmnād and the coast line of Palk's Gulf or the Gulf of Manaar or to both." (Ib. IV. 149 note) The elephants of the Aghbāb were probably the same as those of M'abar (the Colomandel Coast), which were noted for their extraordinary height and bulk and are described as the largest in India by Amīr Khusrau (E. D. III. 86)

I 14, l. 8. From Zāranj, capital of Sijistān, to Multān, two months' journey.

Zāranj or Shahr-i-Sīstān is now represented by the ruins at Zahidān. Lat. 30°-55′ N. Long 61′-32′ E (G P Tate, Frontiers of Baluchistān, 229, 246) The ruins cover an enormous area to the east of Nasratābād—the present capital, which is itself a short distance south-west of the old town which was destroyed by Tīmūr. (Holdich, G I. 203) The ancient town lay along the old bed of one of the chief canals from the Helmand, which has now become dry (Le Strange, L E C, 335 note) Zāranj is, most probably, the name from which 'Drangiana,' the Greek designation of the province, afterwards called Sīstān, was derived

I 14, l 17 Vandān, Mandal, Salmān, Sairasb, Karaj, Rūmla Kūli, Kanauj, Barūh

In the new edition of Khurdādbih, Goeje reads several of the names differently His MS has Sāwandra instead of Vandān, Bailamān [Bhīlmāl] for Salmān, Sarasht for Sairash, [Saurāshtra] Marmad, for 'Rūmla' and Dahnaj for 'Kanauj' (57, 12, Tr 38) There is a Dhinoj, nine miles from Mehsānā in North Gujarāt, but Dahnaj is most probably correct It is mentioned by Bilāduri also, (126 infra, Murgotten's Trans 227) and seems to be identical with the Dahanjūr or Rahanjūr of Alberūni (61 infra), ie Rānder near Sūrat See my note on 61, 19 infra)

I. 14, l 4 from foot. The island of Khārak lies fifty parasangs from Obolla

Obolla occupied the piesent site of Basra (Gibb, Ibn Batūta, Notes 348) Khārak was a port of call for ships sailing from Basra to Kīsh and India Yāqūt says its soil was very fertile. It lies 30 miles N W of Būshire (L E C 266; Curzon, Persia II 4034) It is in Lat 29° N, Long 50° E

I. 14 l. 3 from foot It [Khār ak] produces wheat, palm trees and wines.

Throughout this paragraph, the word which is translated as 'wheat' is (ble in the French version), which signifies corn or cereals in general and not wheat in particular The Arabic word for 'wheat' is froment, in Meynard's rendering In this part of his work, is used by Khurdadbih only on one occasion and that is in connection with the

products of Kilakāyān and Kanja. (Journal Asiatique, 1865, text, 61-2; Tr. 283-4 = Goeje, 63, 1. 7).

I. 14, l. 2 from foot. The island of Lafat is at a distance of eighty parasangs from Khārak.

The name is spelt variously as Lafet, Laban, Labin, Labet and Lawan. Yagut (Meynard, Dict. Geogr. de la Perse. s. v. Lafet) and Mas'udi (Sprenger, 268,=Prairies, I. 240) state that Lafat was known also as the island of Bani Kāwān, but this must admit of doubt, as Khurdādbih distinguishes between the two. He speaks of Ibn Kawan separately (p. 15, 1. 8 infra) and locates it at thirty-nine [7 + 7 + 7 + 18] parasangs' distance from this Lafat. Le Strange thinks that Lafat or Lawan must be the island of Shaikh Shu'ayb which lies to the west of Kays or Kish. He declares that Bani Kawan is "the great island lying at the narrows of the Gulf, which is now known as 'Kishm' and also as the 'Long Island' and is the largest island in the Gulf." (L. E. C. 261; see also Dames, Tr. Barbosa. I. 81-2. Yule, Hobson Jobson, s. v. Kishm). Quatremére's identification of this Lafat with the Isle of Kenn is untenable, because Morier assures us that the 'Isle of Kenn' is called 'Gheis' or 'Kish' by the natives. (Second Journey to Persia, 31). Kenn [or Kish] and Ibn Kawan [or Kishm] are quite distinct. They have been confused with each other only on account of the similarity of the names in sound. Kīshi is senarately mentioned by Khurdadbih (p. 15, l. 5). According to Lord Curzon, one of the largest of the seventy villages in the great island of Kishm [or Ibn Kāwān] is called Laft. (Persia, II, 410). Unfortunately, the reading لافت is not at all certain. Goeje reads 'Lawan' or 'Laban' (Text. 61, 1, 16; Tr. 42). and we thus return to کاون or کاوان and We thus return to [Ibn] Kāwān. It seems that Mas'udi and Yāqut are right and that Khurdādbih has made some mistake either in regard to the name of Lafat, Labat or Labin or to its situation.

Le Strange supposes Abrūn to be the modern Hindarabi, which with Chin or Khyn [Khīn], lies near Qays or Kīsh (L. E. C. 261), but Dames thinks that it must be Gamrūn or Gombroon, i.e. Bandar 'Abbūs. Both are agreed that Armūn (l. 11) is the island of Jerūn and Goeje reads it as join (62, l. 5). Old Ormuz was on the mainland, but New Ormuz was founded on the island of [Armūn or] Jerūn about 715 H. 1315 A.C. on account of the constant incursions of the Tātār hordes (L. E. C. 319). Jerūn island is only 12 miles west-ward of Old Ormuz and about 5 miles from the shore. (Yule, Hobson Jobson, s. v. Ormus).

I. 15, l. 9. The inhabitants [of Ibn Kāwān] are heretics of the sect of the Ibāzites.

The Ibāzites are "the remnants of an important Puritanical sect of the first Islamic century, known as the Khawārij or Dissenters. Their only existing communities are now found in Omān, Zanzibar and the M'zab district in Southera Algeria." (Gibb, Ibn Batūṭā. 379).

"They derive their name from 'Abdulla bin Ibādh who flourished about 744-749 A. C. These sectaries rejected the Khilāfat of 'Usmān and 'Ali and asserted the right of True Believers, to elect and depose Imāms. The sect is still powerful in Omān, and the Imāms of the Ibādites have been usually temporal rulers also of Omān" (E. C Ross, art On the Imāms of Omān in J. A. S. B. XLIII. (1874), Pt. i. 189-90) They also "profess some extraordinary doctrines, one of which is, that if a man commits a Kabīra or great sin, he is an infidel and not a believer at all" (Hughes, Dictionary of Islam, s v Ibāziya, Houtsma, Encyclopaedia of Islam, II 266, s v Ibādiya)

I. 15, l 11 From Armun to Narmasīra is seven days' journey From Narmasīra to Debal is eight days' journey.

Goeje reads this very differently His MS, has it Thara' instead of 'Narmasira' and he suggests that Thara must be meant for Tiz in Makran. (Tr. 42 and note) In his Edition, (Bibliotheca Geographorum Arabicorum, Vol VI), the sentence is written thus

ثه الى نارا مسيرة سعه ايام * * و من نارا الى الدسل مسرة ثبايه ايام (62, 76)

Clearly, is not part of the name, Nārmasīra, but a common noun signifying 'journey' and 'Narmasīra' must be rejected. Morcover, Nārmasīra could not have been only eight days' journey from Debal Debal is in Lat. 24°-30′ N Long 67°-50′ E. Nurmanshīr is in Lat 28°-30′ N. Long. 56°-30′ E It is shown in the New Pictorial Atlas, Pl 63. The two places are four degrees of Latitude and eleven of Longitude apart from each other and the distance between them must be at least 850 miles. Goeje's proposed identification, Tīz, also seems hardly tenable. Tīz is in Lat 25°-0 N Long 60°-40′ E, at a distance of, at least, five hundred miles from Debal, which could not have been traversed in only eight days

1 15, l 14. From Debal to the junction of the river Mihran with the sea is two parasangs

Mas'udı puts the distance as two days, (24 infi a), but Idrīsi follows Khurdādbih and Jaubert makes it six miles in his French version, as he reckons the farsakh at three miles (p 78 infra) General M. R. Haig prefers Mas'ūdi's statement on the ground that a great city like Debal "could not possibly exist on the open delta coast, where it would be exposed to destruction during the stormy season and where fresh water would have to be brought from long distances". (Indus Delta Country, 43) I. 15, l. 16. From Sind are brought the costus, canes and bamboos

There is no specific reference here to bamboos. The words used by Khurdadbih himself are قبط و قبا و حير دان. Now his which is rendered here as 'canes', is really a generic term for various species of reeds and grasses, while خردان does not necessarily mean 'bamboo'. It was some sort of rattan or 'ruscus,' as Sprenger renders it (Mas'ūdi, Tr. 269, 353 note). Steingass also says that it means cane, reed or rattan. When Idisi

speaks of Qanā and 'Khaizurān,' Dowson, following Jaubert's French version of that author, translates the words as 'Kauā and rattan,' (p. Sō and 91 infra) not 'bamboo.' 'Khaizurān' or 'Ifaizurān' is described in an old Arabic work quoted by Sprenger, as "a species of ruscus imported from China; it has the form of ropes, a finger thick,... which are particularly useful for hanging cloth on them, for they do not make marks. Some say they are the branches of some shrub, others believe that they are roots." (l.c. 353 n). This description points to some sort of rattan, and it seems that the Arabs did not really know what 'Khaizurān' was. It is true that some modern Arabists translate the word loosely as 'bomboo,' but there are substantial reasons for questioning the correctness of the rendering in all cases. Such a rendering may be appropriate when the word is used in connection with Sindān, or Thāṇa, but not with Sind or other places where the bamboo can not and does not grow.

Neither rations nor bamboos are indigenous in Sind. They can flourish only in regions of heavy rainfall and there are no natural bamboo forests anywhere in the province. Dr. Watt tells us (Commercial Products of India, 98) that "canes, reeds and bamboos are often confounded together, as many of the purposes for which bamboos are utilised are met also by canes (Calamus) and by the reeds...and willows...The canes proper are climbing palms, and the reeds are species of grasses. From the industrial point of view, they are very nearly identical with the smaller bamboos, but botanically or scientifically, each belongs to a class or order of its own." Capt. Wood also tells us that 'Canī' is the Sindhi name for "a gigantic grass which attains the height of 12 or even 18 feet, the stalk of which is jointed like the bamboo, but one-third of its whole length is continuous. It is used just like the bamboo for making baskets and mats." (Journey to the Source of the Oxus, Ed. Yule, p. 4 note).

I. 15, l. 16. From the Mihran to Bakar, which is the first place on the borders of Hind, four days' journey; they are wanderers and robbers. From this place to the Meds are two parasangs; they also are robbers.

Dowson admits that the second name is illegible in the Paris text. Goeje reads it as 'Outakyn' (62, l. 10. Tr. 42) or 'and Idrīsi who has copied the passage has 'Aubkīn' (84, 85 infra). 'Outkyn' or 'Aubkīn' can be read also as 'leady 'Ovakhbat' and may stand for Okha or "Okhā-Bet." The mention of the robbers called Meds and their near neighbours, the Kols (or Kolis), indicates that the reference is to the pirates on the Kachh and Kāṭhiāwād coast and the thieves and brìgands of Koliwāra, i.e. Viramgām, Mahikānṭhā etc. in North Gujarāt.

The rest of the paragraph is a confused medley of names which can only mystify the reader, and many of them are spelt very differently in Goeje's manuscript. Bās (16, l. 1) is written there as Bābattan, 'Saji' as Sinjali, 'Askan' as Kabaschkān [Kaikasār in Idrīsi, 90 infra] and

'Kūrā' as 'Koudāfaryd.' Goeje supposes 'Bābattan' to be Budipattan, 'Koudāfryd' to be the Godāvari and taking his cue from a suggestion of Yule's, he seeks to identify 'Sanji' or Sinjali with Shinkali or Shingali, the old name of Cranganore (Text 63 Notes) But Khurdādbih did not possess any personal acquaintance with Southern India and he seems to have lifted the names from some other writer who had picked them up at haphazard and made a somewhat liberal use of his imagination in filling up the descriptions. The real distances of the places are so absurdly whittled down and the other statements are so trite, vague or obscure that it is difficult to relate them to any localities with which identification is possible.

I 16, l. 16. There are seven classes of Hindus, 1st Sābkufria, among whom are men of high caste and from among whom kings are chosen.

This 'Sābkufriya' [ماكلوم] in the original] is a puzzle and no such denomination is found in the Hortus siccus of Indian caste. I venture to suggest that the right reading may be ماكلوم 'Sākabfutriya', Sansk. Sākyaputra, 'sons of Sākya'. This was the honorific appellation assumed by Buddhist priests 'Furia' or 'futriya' must be a corruption of putriya

Thus, معود the Arabic title of the Emperor of China is derived from the Avestaic Bagha-puthra' son of God' (Yule, H J 49) "In agreement with early custom," Beal explains, "the mendicant priests who adopted the Buddhist faith changed their names at the time of leaving their homes and assumed the title of 'Sakyaputra' "Sons or mendicants of Sākya" (loc cit Intr I. xi) The Chinese pilgrim Fa Hiān observes that "the kings who are firm believers in the Law of Buddha remove their caps of state when they make offerings to the priests Theu daye not sit on couches in the presence of the priests." (Ibid I EXXVII) We know also from the Chachnama and Biladuri's Chronicle that Buddhist priests were governors of towns and districts in the beginning of the 8th century and they had to be maintained in power and authority by Muhammad bin Qasim even after the Arab conquest, in consequence of the respect and veneration in which they were held by the inhabitants We also read that when Chach went to visit the Samani priest of Budh-Vihar, the latter took no notice at all of him for some time, kept him standing till he had finished his devotional exercises and that the king sat down only when he was permitted to do so by the priest, (149 infra Kalich Beg's Translation, 35). The title 'Sakyaputra' was probably coined on the model of 'Swamiputra,' 'Son of the Lord', which was an epithet of Brahmans

Goeje reads مناكثريه (71, 19), Shākthariya and explains it as a reduplication of 'Kshatriya' Khurdādbih, he suggests, wrongly supposed the Kshatriyas to be divided into two classes, one of kings and nobles, and another of soldiers (Tr 52 Note) But this surmise is hardly convincing If the right reading is ناكثريه, Thākthariya, a possible and not unplausible

elucidation may be that it is another form of Takākira which is used by Bilāduri (121 infra) and is rendered by Reinaud as generals and construed by Dr. Murgotten as the Arabic plural of the Sanskrit 'Thakkura,' (Tr. 220 and note). But Takākira has little or no resemblance to either of the readings ما أحريه found in the two oldest MSS. Goeje's ما عادم aeems really meant for and may also be read us 'Shākbatriya,' Sākaputra.' Idrīsi has Sākariya.

I. 13, l. 18. The people of the other six classes do the men of this class homage and them only.

This is wrongly rendered. Khurdadbih's words are:-

وفيهم اشراقهم وفبهمالملك تسجد لهم الاجناس كلها ولايسجدون لاحد

(Journal Asiatique, 1865, p. 68; Goeje, 71, 1.8). "All the other castes bow to them, but they do not render homage to any." (See Tr. in J. A. 295; Goeje, Tr. 52). The sentence is copied by Idrīsi and Dowson himself translates it there more correctly thus: "All the other castes pay homage to them, but they render homage to no one." (76 infra).

I. 16, last line. 7th Lahud. The women are found of adorning themselves and the men are fond of amusements and games of skill.

This على المابقة Laḥūd (or Lhūd) appears, at first sight, to be another form of the local 'Lodh' [الوده] of the Tuḥfat-ul-Kirām (337 infra). Growse says 'Lodha' is the Prākrit form of the Sansk. 'Lubdhaka' and is almost equivalent in meaning to 'Nishāda,' 'Man of low caste', hunter, fowler. (J.A.S.B. LIV. 1885, Pt. i. 155). The Paris text has Zanya ناد المابة على المابة المابة

Idrīsi who has copied the passage substitutes 'Zakya' for 'Laḥūd' [1] He describes them as "jugglers, tumblers, and players of musical instruments." (76 post). Idrīsi's 'Zakya' is, perhaps, connected with 'Zingari', which is applied in various countries of Europe to the Gypsies, and which is derived by Goeje from the Persian 'Changi,' harper. A plural form of this, 'Changān,' occurs in Lane's Arabian Nights. (III, 730, Note 22). These 'Changis' or 'Changān' are the 'Aljink,' male dancers, of Burton's version of the Alf Laila. (VIII. 15. See also H. J. 984, s. v. Zingari). It may be that 'Idrīsi's 'Zakya' is a variant form of this 'Jink.' Vambery says that in Central Asia, dancar girls, singing girls and prostitutes belong to the trībe of Lūlīs or Grane

or guild" (Tr Sachau, I. 101). Sachau leaves 'Badhatau' unexplained and there is no such word in Sanskrit. It may be a mistranscription of J. Laddhiu, which sounds more like Lhodh or Lodha Goeje supposes to be a perversion of J., Bhand or Bhānd (q v Merveilles de l'Inde, p 117), buffoons, but if Khurdādbih wrote he had in mind the Dom or Donba, not the Bhānds Yule states that the Dome or Dhome are commonly called Dombaree or Dombar, that they are scavengers, sweepers or village musicians and that the word 'Romany' for 'Gypsies' is derived by many scholars from this Dome (H. J 322)

I, 17, l 3 Some believe in a Creator and Prophet (the Blessing of God be upon them), part deny the mission of a Prophet

The Arabic word in both places is in the plural الرسل, Prophets, not, (J A 69) The reference must be to the inspired Rishis who are said to have written the Sruti and the Smritis and perhaps also to the Ten Avatārs of Vishnu Idiāsi also speaks of the forty-two sects of India but what he says is that "some of them recognize the existence of a Creator, but not of Prophets, while others deny the existence of both" (76 post). Musalmān theologians assert that the Supreme Being has, at different times, sent 124,000 prophets to our world (Tārikh i-Guzīda, I 18, Tr II 8, see also the story in the Mirāt-i-Sikandari, Text 42-3, Tr. Fazlullah, 32).

I 18 Mur ūju-l- Zahab of Al Mas'ūdi

These extracts from Mas'ūdı about matters relating to India are far from being exhaustive or even fairly full. There are several other references of at least equal importance and interest. For example, this Arab Heiodotus, as he has been justly called, informs us that when he was at Cambay in 303 A. H., he witnessed the 'Bore' in the Gulf there. "The ebb is so marked in this estuary," he writes, "that the sand lies quite bare, and only in the middle of the bed, lies a little water. I saw a dog on this sand, which was left dry in the water, like the sand of a desert, the tide coming in from the sea caught him, although he ran as fast as he could to the land to escape, and the poor animal was drowned notwithstanding his swiftness."

He also records that the city was then governed by a Brāhman named Bābna Li on behalf of the Balharā, and that this governor treated with great favour Musalmāns and other foreigners who visited the province (Sprenger, 278, Prairies, I 254) There are two ways in which this name can be restored. It may be a miswriting of Lal Bhāṇā, a very common name in Gujarāt But it is at least equally probable that Bābnā was not the personal name of this official, but the designation of his caste He was a Bāniya li the Gujarāti Vāmā We know from the historics of the Chāvdās and Chālukyas that many of their ministers and even military commanders were 'Bāniyas'.

In another place, Mas'ūdi notes that when he was at Saimūr [Chaūl] in 304 A.H., the ruling prince was Djāndja E- and that ten thousand Arabs had married and settled in the locality who were known as 'Beiāsirch' (*Prairies*, II. 85). Modern researches have proved that Djāndja was the North Konkan Silahāra ruler Jhanjha. (B. G. I. ii. 17, 23, 232, 233, 539; Duff, C. I. 303) and this has proved to be a most useful sychronism for determining the history of the dynasty.

But more notable still is the reference to the city of Madura and the Pāndya rulers of the district. Mas'ūdi tells us that the country of (Sprenger) or مندورين بني (Meynard) lies opposite to the island of Serendīb just as Qumār [Khmer or Cambodia] is opposite to the islands of the Maharāj, to whom Ez-zābij [Jāvā or Sumātra] belongs. He also states that every king of the country of Mandūra is called el-Qāyidi التابدي (Sprenger, 397-8, Prairies, I. 394). It seems to me that the right reading is مندوري بن مندوري بن مندوري بن المعاملة ورنين مندوري بن المعاملة والمعاملة والم

This is fairly easy. التابدى is a harder nut to crack. I suggest that a transposition of the nuqtas will restore it to النائدى—Al Fāndi—the Fāndi—the form which 'Pāndya' would assume in Arabic. This عند ورفين is mentioned also by Qazvīni, but Gildemeister (Scriptorum Arabum de Rebus Indicis, Text, 71, Tr. 214) could make nothing of it.

Among other matters of minor interest in what Sprenger calls this 'Historical Encyclopaedia,' there is a graphic description of that 'wonder of creation,' the 'Bar' tree-Ficus Indica. (Prairies, II. 81), a curious account of the digestive, tonic and aphrodisiac properties of the betel-leaf (Ib. II. 84), stories illustrative of the astonishing sagacity and pudicity of two elephants belonging to the ruler of Mansura in Sind, (Sprenger, 386-7, Prairies I. 379) and an allusion to the Caves or temple of Ellora (וצינט or ווייס ווייס in the Text) near Deogīr or Daulatābād (Prairies, IV. 95). Qazvīni has copied this last passage also and writes the name لادذرى or للادرى (Gildemeister, l.c. Text. 79: Tr. 221). In another place, still, Mas'udi states that an inferior kind of emerald was exported from Cambay and Saimur to Broach, (III, 47-48). As there are no emerald mines anywhere in India or even in Asia, he would appear to be referring to the famous agate, carnelian or Bābāghūri mines at Ratanpur in Nandod State, near Broach. He has probably mixed up agates with emeralds.

I. 19, l. 20. He [Brahmā the Great] was succeeded by his eldest son Bahbūd.

Sprenger (p. 170) and Meynard (Prairies, I. 157) read Bâhbūd, but if the 'wāv' is pronounced as a consonant, the name would be 'Bāhbavad' and bear some resemblance to Bhāgbavad, Bhagvada' or 'Bhagvata,' i.e. Vishnū. But in Shahrastāni's المناب اللل و النحل, there is the

Capudan, does not mean, he contended, that they are the same Go'a and Chintākul "are close enough to be grouped together, in laying down seasons for the voyage from Western India to Aden" They are only fifty miles distant from each other. It may be also urged in favour of Chitākul that "Kārwār is the only first-rate harbour on the western coast between Bombay and Colombo. It offers every convenience to shipping at all times of the year" (B G. XV Pt. 11. (Kanāra), 318) Sindābūr was undoubtedly a very well-known port, as it is mentioned by Idrīsi (89 infra), Rashīdu-d-dīn, (68 ibid), Abul Fedā (in Gildemeister, Text 40, 46; Tr 184, 188), and also in the Livre des Merveilles de L'Inde, (157-158) But Chitākul does not bear the close phonetic resemblance to Sindābūr that is required

Sindabūr must be derived from some such name in Sanskrit as Chandrapura, which would assume in the vernaculars, the forms Chandapur, Chandrawar, Chandawar, etc This has led to a fourth suggestion, viz, that Sindabur was Chandrapura, the old capital of the Kadambas of Goa Mayanalladevi, the daughter of Jayakeshi I, married Karna I Chālukya of Gujarāt who reigned from 1063 to 1093 A. C Mayanalladevi was the mother of the renowned Siddharaja Jayasinha This Chandrapura has been identified with Chandawar, six miles south of Gokarn and five miles north-west of Kumta Gokarn is in Honawar taluka and lies south- east of Goa in Lat 14° 32', N , Long 74° 22' E It is a place of great sanctity on account of an image of Mahableshwar. ie Shiva, which is said to have been brought here by Ravana capital of this dynasty was at Chandrapura in 916 A C, when Mas'udi wrote It was removed to Goa only in the middle of the 11th century (B G I 1 171, Fleet, J. B B R A S IX 283, G M Moraes, The Kadamba Kula, 178, 182, 185, 333, B G, Canara, XV, Part n 277)

In any case, it seems certain that Sindabur was somewhere near the coast between Goa and Kumta

The name Bāghara, which is written of and also of in Sprenger's MSS (loc cit 234) has also baffled the commentators, probably because it has been supposed to be the designation of a place instead of a person I venture to suggest that it is the latter. Mas'ūdi has the commendable habit of mentioning the name of the king or governor along with that of the country. Thus he meticulously records the names of the rulers of Cambay, Saimūr, Multān, Mansūra and Qanauj in his day. It seems to me that the true reading is of Nāghū or Nāgū, the short form of Nāgavarman

A reference to the dynastic list of the Kadamba rulers of Hāngal in Dhārwār district, shows that there were two kings called Nāgavarman, the second of whom may be the Bāghara or Nāghū of Mas'ūdi (Fleet in BGI ii 550, Duff, CI 252, Moraes, Kadamba Kula, p. 167-8) It is perhaps necessary to state that Dr Fleet and others were disposed, in the last century, to question the existence of this Nāgavarmān and

the genuineness of the old dynastic lists. But the recent discovery of the Marcella Copper-plates of his great-great-grandson, Shashtha Deva II, who is also called Chatta or Chattaya, must dispel all doubts and settle the matter. See Moraes, Kadamba Kula, 387-393, for the original text and translation of the epigraph.

The Arabs frequently changed the hard 'g' of a foreign tongue into . as in (Pythagoras) . فيثاغورث (Bulgaria) . المغار (Magian) مغناطيس (Magnet) . بخرافيه (Geography) . ايثاغوجي (Magnet) .

I. 22, 1. 8. The king of Kanauj, who is one of the kings of Sind, is Bauura. This is a title common to all kings of Kanauj. There is also a city called Bauura, which is a dependency of Multan.

This name is another of our unsolved conundrums. Meynard's spelling is . Rect. (I. 372), but it cannot be depended on, as he never gives any variants. Sprenger says that the MSS. he consulted had .; ecc. and .; (loc. cit. 380). The copies belonging to Raverty showed and another another again, as in the case of Ruhmi, the clue to the solution may be found in the dynastic list of the Gurjjara-Pratihāra rulers of Qanauj. The right reading seems to be .; e.c. o. e.c. o.

Bhoja the Great ruled at Qanauj from c. S40-890 A.C. "His dominions were very extensive; his power was acknowledged upto the Vindhyās from sea to sea and he is also known to have conquered his formidable foe, the king of Bengal." He was succeeded by Mahendrapāla (S90-910) and he, by another Bhoja who died after a short reign and was succeeded by his half-brother, Mahipāla, who ruled from about 910 to 940 A.C. (V. Smith in J. R. A. S. 1909, p. 269; E. H. I. 350-1; Duff, C. I. 77, 79, 296). Mas'ūdi's statement that the title was common to all the kings of Qanauj is probably due to the fact that Bhoja the Great was succeeded, after some years, by another prince of the same name who had been ruling shortly before the time of Mas'ūdi's arrival in India.

The reference to a city which was also "called Bauüra after its princes" and "was a dependency of Multān" under Islamic sway, must be to the district called Būdha by Istakhri and Ibn Hauqal (29, 38, 39 post). It may be worth while to note that if this toponym were written with a or or (as o), it would be pronounced as "Būdhah" by Arabs but as 'Bozah' or 'Būzah' by Persians. Bozah is not unlike 'Bhoja' in sound and eçc' (Boözah) is one of the variants actually found in Manuscripts.

I. 23, l. 9. The kingdom of the Bauura, king of Kanauj, extends about one hundred and twenty square parasangs of Sind, each parasang being equal to eight miles of this country.

Mas'ūdi's Sindian parasang has again led him into a pitfall. 120 Sindian parasangs would be more than 960 statute miles, as the

I. 23, 1, 9,

Arabian mile was a fraction longer than the English. The square area of the kingdom would be then more than 9,21,600 miles—which is obviously inadmissible. The total area of the Indian peninsula is about 14 million miles. Here again, the statement would be less incredible if the Sindian par asang was reckoned at only four miles.

I 23, 1. 20 Around it (Multan) there are one hundred and ticenty thousand towns and villages.

This also must evoke "an elevation of critical cycbrows" The words in the original are "" (Prairies, I 375). The kingdom of Multān comprised only some parts of modern Punjāb and Northern Sind The total number of villages in all British India is about 5,00,000 and in the whole of the subcontinent about 7,00,000 Mas'ūdi does not mean 'towns and villages' but "farms and hamlets", that is, farms, estates or holdings given on military tenure to Musalmān soldiers and villages occupied and cultivated by the indigenes. The total number of towns and villages in the whole Province of Sind now is officially stated to be only 4429 (I G XXII 403)

I. 23, l. 5 from foot. When all the rivers which we have enumerated [Jhelum, Biyās, Rāvi, etc.] have passed - .

Multān, they unite at about three days' journey below this city at a place called Dūshāb into one

stream which proceeds to the town of Al Rur

Raverty hazarded the opinion that the name of this place was derived from the Persian 'Dosh' "meeting," and 'Āb' "water," and that it was so called because the waters of six great rivers met here (Mihrān, 209) In the first place, 'Dūsh' does not mean 'meeting' but 'milking' and 'Dūshāb' signifies "syrup of dates or grapes," according to Richardson's Dictionary In the second, it is extremely unlikely that such a conspicuous landmark as that where several of the greatest rivers of the country assembled in confluence, should have had no indigenous name and been known to the people by a meaning-making designation of foreign manufacture, so early as the first quarter of the tenth century

I venture to suggest that what Mas'ūdi wrote was ووشاك Wūshāb, and that what he meant was Wūshā, e Uchchā

It is perfectly true that the five rivers now fall into the Indus at Mithankot, about forty-eight miles south of Uchcha, and not at Uchcha itself. But these old writers were not scientific geographers, recording the results of careful surveys or of even their own observations. Their information about the physical features of the country was, for the most part, derived from chance acquaintances who had themselves obtained theirs from not very reliable sources. Their assertions are often only vague expressions of nebulous ideas and restricted knowledge. They frequently repeat only the common view of their times, mere hearsay or popular rumour and sometimes render also an uncouth and outlandish name by one more familiar or intelligible to

themselves or to their readers.

Now we, ourselves, do not now know where the six rivers actually met a thousand years ago. But it is fairly clear, from the passages which I shall presently quote, that the junction of the five rivers with the Indus was popularly believed, at this time and long afterwards, to take place at Uchcha itself. It may have been a wrong belief, or vulgar error; it may not have been in exact correspondence with fact, but we have nothing to do with that. All that we are concerned with is to show that the idea was widespread and generally held even by fairly well-informed persons.

I will first cite an old Sanskrit inscription of V. S. 1333, i.e. 1276 A.C. which was found in a Bāoli or step-well at Pālam, about twelve miles south-west of Delhi. It is recorded there that the step-well was excavated by the orders of one Udhdhara, the son of Haripāla, who came originally from Uchchapura, "where the Vitastā (Behat or Jhelum), Vipāśa (Beās) and Shatadru (Sutlej) join in front....with the swelling waves of the Chandrabhāgā, where stands also the friendly Sindhu with its affluents and where the land is laved by the water of that Sindhu, where the town of Uchchapura laughs at Amarāvati;......., even there was the abode of his father Haripāla." (Dr. Rājendra Lāl Mitra's Tr. in J.A.S.B. XLIII, 1874, p. 106). The epigraph is mentioned in the Āṣāru-s-Ṣanādīd, as well as in Thomas's Chronicles of the Pathān Kings of Delhi, (p. 136-7) and clearly reflects the general opinion that the rivers named met the Indus near Uchcha.

We have next the testimony of Sharafu-d-dīn 'Ali Yazdi who states that the Jamd [Jhelum] "joins the Chināwa above Multān.....and below it, they join the Rāvi.....Afterwards, the river Biyāh joins them and the united streams pass by Uch and join the Sind or Indus". (Zafarnāma, Text, II. 179, l. 5 ff, E. D. III. 522). A parallel statement will be found also in the Malfūzāt-ī Tīmūri where also it is stated that "the united rivers fall into the Sind or Indus in the neighbourhood of Uch." (E. D. III. 476).

There can be little doubt that the confluence of the Punjāb rivers with the Indus was generally said and believed to take place at or very near Uchcha. The belief or averment may not have been in accordance with fact even in those days, as it is not now. But that is beside the point. We are concerned with the popular opinion of the times and not the scientific fact. Indeed, even so late as the last decade of the 18th century, Mogul Beg, a surveyor employed by Warren Hastings, after mentioning the Five Rivers and their confluences, wrote thus: "Near Uch, it [the Ab-i-Sind or Indus] unites with the Panj Ab or Panch Nad and towards the Bandar of Lahri, it unites with the ocean." (Mihrān, 298).

Major Rennell, also, shows the five rivers falling into the Italian just below 'Uch' on the Map, facing page 65, of his famous Memorian a Map of Hindoostan, in 1793.

And Raverty himself assures us that "in the last century, the Panch Nad existed, united with the Indus close to Uch, on the west, and did not then exist, as it does at present, but was situated a little higher up than Uch," (Mihrān 344 note)

Elsewhere also, he writes thus "Uchcha stands on the east bank of the Chenāb and its tributaries now, but in former days, stood on the west bank of the Biāh . . and a little above its junction with the Sindhu of Ab-1-Sind and at the period in question, the Chenāb and the other rivers of the Punjab were tributaries of the Biāh" (Mihrān, 244 Note).

Mas'ūdi was, after all, only a casual visitor to this country, and we have no right to demand from him and his ilk anything approaching to our modern standards of scientific geography. His statements have no pretensions to precision and he is merely repeating a popular geographical idea. Only a few lines lower down (p 24, 1 7 ff), he propounds the extraordinary dictum that "several great rivers on the Lārwi coast [the coast of Saimūr, Sopārā and Thāna], run from south to north, whilst all other rivers of the world flow from north to south, excepting the Nile and the Mihrān of Sind' Every one knows that there are no such rivers anywhere in India and the Mihrān (Indus) does not flow from south to north, either—It only proves that his notions of the hydrography of this country were exceedingly jejune and it should also teach us that we have to make allowances for the low level of geographical knowledge in his day

Indeed, Yule, than whom few were more learned in the History of Geographical Science, was so exasperated by the topographical errors of another Arab traveller, Ibn Batūtā that he declared the Muhammadan mind almost incapable of "relating accurately that which is witnessed in Nature and Geography." (Cathay, I. 402) General Haig also complains of the "utter lack of precision" in the early Arab geographers. (I D C. 71)

I. 24, l 6 Multan is seventy-five parasangs from Mansura. Each parasang is eight miles. The estates and villages dependent on Mansura amount to three hundred thousand

The real distance is between 350 and 400 miles only—just a little more than half as much as 600 (75 x 8)—according to Elliot (373 infrit) and Raverty (Mihrān, 190 note). Here again, the inflated estimate of the length of the Sindian parasang has misled Mas'idi and his statement would be in fair accord with fact if the parasang was equated with 4 or 4½ miles Note that the word with 4 or 4½ miles Note that the word (Prairies, I 378) is here rendered as 'estates', by Dowson himself

I 24, l 13 from foot The inhabitants of Mankir, which is the capital of the Balhara, speak the Kīrīya language, which has its name from Kīra, the place where it is spoken.

A slight alteration of the discritical points would restore the hames

to 'Kanariya' and "Kanara." Alberūni, while mentioning the varieties of alphabets or dialects current in India in his day, enumerates nine, viz., "Nāgari, Ardhanāgari, Mālwari, Andhri, Drāvidi, Lāri, Gauri, Bhaikshuki and Karnāṭa, which is used in Karnāṭadesha, whence those troops come which in the armies are known as Kannara." (Tr. Sachau. I. 173). Mas'ūdi's Kīra [Kanara] and Kīrīya [Kanariya] are evidently identical with this language of Kannara or Kannada, i.e., Karnāṭaka. He himself tells us a few lines lower down, that the country of the Balharā is "also called 'Kamkar' (p. 25, l.c.) i.e. Kannar. Kannara is derived from the Drav. 'Kar', 'black' and nādu country. Karnāṭak has reference to 'Nāṭi,' the adjectival form of 'Nādu'. (Caldwell, Dravidian Grammar, Introd. 34-5).

It [Firanj or Qiranj] is situated on a tongue of land which stretches into the sea, from whence large quantities of amber are obtained.

The word used here also is it (Text in Prairies. I. 388) and Sprenger's rendering is "The sea throws ambergris on the shore". (l. c. 393). Wassaf notes that "White amber [called also Grey amber, Grisamber or Ambergris] is the dregs of the Sea of Hind". (E. D. III. 29). Tavernier speaks of two large pieces of ambergris weighing 33 and 42 pounds (French livres) having been found in the Indian Ocean (Travels, II. 141-2). Mas'ūdi (Sprenger, 353), Rashīdu-d-dīn (71 post) and Duarte Barbosa (Tr. II. 181) also speak of ambergris being found in the Indian Ocean.

I. 28, l. 10. Its [that of the Multan idol] whole body is covered with a red skin like Morocco leather and nothing but its eyes are visible.

Alberūni tells us that, "a famous idol of the Hindus was that at Multān, which was dedicated to the Sun and therefore called Āditya. It was of wood and covered with Cordovan leather; in its two eyes were two red rubies." (India, Tr. Sachau. I. 116). He cites also the rules laid down for the construction of the image of Āditya by Varāha Mihira. "The idol of the sun, must have," that author states, "a red face like the pith of the red lotus.....and wear a crown of several compartments and be clad in the dress of the Northerners, which reaches down to the knees." (Ib. I. 119). The original passage will be found in the Brihat Samhitā, Ch. LVIII, sections 30-48, 56-7 and Kern's Trans. in J. R. A. S. 1871.

A much older description is found in Hiuen Tsiang, who says that there was in Multān an "idol dedicated to the Sun which was very magnificent and profusely decorated, to which the kings and high families of the five Indies never failed to make their offerings and to which means from all countries came to offer up their prayers." (Beal's Tr. II. 272. A more modern account can be read in Thevenot. The notice indicates that the temple of the Sun at Multān continued to attract were and was frequented in the 17th century just as much as it used to die in the sun at Multān continued to attract were and was frequented in the 17th century just as much as it used to die in the sun at Multān continued to attract were and was frequented in the 17th century just as much as it used to die in the sun at Multān continued to attract were and was frequented in the 17th century just as much as it used to die in the sun at Multān continued to attract were and the sun at Multān continued to attract were and the sun at Multān continued to attract were and the sun at Multān continued to attract were and the sun at Multān continued to attract were and the sun at Multān continued to attract were and the sun at Multān continued to attract were and the sun at Multān continued to attract were and the sun at Multān continued to attract were and the sun at Multān continued to attract were and the sun at Multān continued to attract were and the sun at Multān continued to attract were and the sun at Multān continued to attract were and the sun at Multān continued to attract were attracted to the sun at Multān continued to attract were attracted to the sun at Multān continued to attract were attracted to the sun at Multān continued to attract were attracted to the sun attracted to the sun at Multān continued to attract were attracted to the sun attracted to

**

the 7th, 9th and 11th He states that the "Banyans and Catrys have in Multan an idol of great consideration, because of the affluence of people that come there to perform their devotions after their way. . . . 1 know not the name of the idol that is worshipped there, the face of it is black and it is clothed in red leather; it has two pearls in place of eyes and the Emir or Governor of the country takes the offerings that are presented to it" (Travels into the Levant, Eng. Tr. of 1687, Part III (Indies), p 55). The shrine was demolished, some years after Thevenot wrote, by Aurangzeb in one of his periodical paroxysms of iconoclastic rage and a mosque was erected on the site (A. G I 235)

The Multan Sun-god is pictured on several coins also of the sixth century Cunningham thus describes three which he had found in the city itself. "The reverse of one of them," he writes, "shows the bust of a god, which Prinsep refers to as the Mithra of the Persians, but which I believe to be the Multan Sun-god Aditya. The bust is surrounded by rays after the Indian fashion and is quite different from the head-dress of the Persian Mithra A second coin bears the same head and the name of Khusru Parviz of Persia The third bears the same Sun-god's head. On the obverse is a legend with the words 'King of Multan' at the end and on the reverse the rayed head of the Sun with the name in Nagari of 'Shri Vasudeva' and 'Panchan (?) Zibulistan." (Arch Surv. Reports, Vol V 122-3, see also Cunningham, Coins of the Later Indo-Scythians, 122-125).

1 29. 1 12

entertained at their first publication, of shedding welcome light on the historical geography of Sind and Baluchistan. They have served rather to obscure the subject than to illuminate it. They are bare catalogues of toponyms transcribed by one writer from another with scant regard for precision and tables of distances not infrequently set down at random Not a word is said about the nature of the roads, the physical features of

These

much-heralded Itineraries have not fulfilled the hopes

the country traversed, its degree of altitude, or the mode of travel and transport. We are not told, even when the he of the land requires it, whether the journey was performed by land or by water

The distances themselves are propounded in terms either of the farsakh, the day's journey or the Marhala. Unfortunately, the true value of any of these measures of length is a matter of great uncertainty and very difficult to determine The farsakh is reckoned in various districts and by different authors at $2\frac{1}{2}$, 3, $3\frac{3}{4}$, 4 and even 5 miles. (Elliot, 400 post and note) Some modern writers make it three miles at one time and four at another, according as the one or the other estimate suits some pet hypothesis. We are also told that in Afghānistān to-day, the Farsakh is ordinarily reckoned at 4 miles, but varies in different parts of the country, being 6 miles in Sīstān and $5\frac{1}{3}$ in Afghān Turkestān (L.G. V. 62). The Arab geographers themselves speak in two voices on the point. Khurdādbih makes it 12000 cubits, each of 24 fingers (about 18 inches), that is,

about 18000 feet or 3 9/22 miles (Journal Asiatique, 1865, p. 228 note; Goeje's Ed. Text. 4, Tr. 2), but Mas'ūdi (Sprenger, l.c. 201, 203; Prairies, I. 186) and Alberūni reckon it at 16000 cubits = 24000 feet = 4 6/11 miles.

. The precise length of the day's journey is equally uncertain. as it must necessarily and constantly vary according to the nature and conditions of travel. Rennell in his 'Memoir of a Map of Hindustan,' (Ed. 1793, p. 317) reckons it ordinarily at 22 miles but 30 or 33 and even more for a courier. General M. R. Haig, basing his calculations on certain statements picked out from these Itineraries, declares himself in favour of an average of 22 or 23 miles. (I.D. C. 66, 138). Mr. Guv Le Strange equates six days' journey with 50 farsakhs (L. E. C. 389) and one day's journey with 81 farsakhs or 30 miles (Ibid., 338). Alberuni makes one day's journey equal to only 31 farsakhs, that is, 15 or 16 miles, (54, 56 infra). Sprenger reckons it at $6\frac{1}{3}$ farsakhs, or about 21 or 22 miles (Die Post und Reiserouten, xxvi). Sir Thomas Holdich differs from all these authors and contends that "the routes described by the Arab geographers are camel-routes and their day's journey was as far as a camel could go in a day, which was far in the more waterless spaces of desert or uninhabited country and very much shorter, when convenient halting places occurred." (Gates of India, 227). He contends that "taking an average from all known distances, it was about 40 and 50 miles in a well-populated district, but might be 80 across an open desert" (Ib. 298). However correct this opinion may be about Makran and Kerman, it is almost certainly inapplicable to Sind.

Again, the day's journey or marhala is said by the Arabs to have been of three degrees, short, average and long. Istakhri and Ibn Hauqal speak of a and a and a speak of a ashort stage and a long stage. (Goeje, 168, 169; Gildemeister, 34, l. 21). Idrīsi reckons an ordinary stage at thirty miles (Climate V, Sect. I), but states that a long day's journey was 40 miles (79 infra). The fact is that the stage or halting place for each day was fixed, not according to distance only, but in conformity with the conveniences available at each stage, i. e. its capacity to satisfy the needs of the traveller and even the general necessities of life. The abundance or scarcity of convenient halting places thus shortened or increased the length of the Marhala.

When all these facts are borne in mind, it is not difficult to understand why these apparently meticulous Tables have proved to be only wandering fires which have served more to darken counsel than to enlighten it. Instead of enabling us to put our finger on the Map and spot the obscurer place-names, they have only engendered interminable disputes, surmises, and speculations or given modern authors opportunities for playing, so to say, the unprofitable game of knocking down one another's topographical nine-pins. They have, besides, been frequently convicted of error, by the results of modern travel and explora-

tion, in regard to toponyms of which the situation is certain or nearly so. It is true that many of the errors are due to the deterioration of manuscripts and the defects of the Semitic script which lends itself with fatal facility to the corruption and even perversion of proper names, but some of them at least must be laid at the door of the authors themselves.

Lastly, we have to remember that all speculations relating to the historical geography of Sind are rendered more or less futile by the fact that the Indus is the most fickle and changeable of rivers. "It is," (as Captain John Wood despairingly remarked just a hundred years ago), "utterly vain and unprofitable to identify localities in the delta of such a river". Its lower valley is "a mud basin undergoing continual change, its banks are perpetually falling and the total absence of any tangible localities constantly involves the investigator in a maze of doubt." (Journey to the Source of the Oxus, Ed Yule, 1872, pp. 20, 3). In other words, there are few or no fixed landmarks in the valley of the Indus and everything is at the cross roads of uncertainty Discussion and speculation often means only "blundering up and down blind turnings"

I. 29. 1. 14

Darah. Rāsak, the city of Schismatics. Bih, etc

"Darak, Beh, Band, Kasrakand, Asfaka and Fahlafahra are represented in modern geography by Dizak, Geh, Binth, Kasrkand, Asfaka and Bahu Kalāt" (GI 311-2). The situation of Rāsak is doubtful Holdich thinks it was somewhere near Sarbaz which lies about half way between Dizak and Bahu Kalāt, but he is not sure about the identification. "There is a place called Rāsak in Makrān even now, but it does not fit the position assigned to it by the Arab writers. It is a small village where there is no room for a city of such fame as Rāsak is said to have been. There are also no ruins or other vestiges of former greatness round about it" (Ibid 312-4, see also Le Strange, L E.C 330).

Most of the distances given here are not in accord with modern geographical knowledge. The real distance between Tīz and Kīz or Kej (near Turbat) is at least 160 miles—about eight days' journey, not five. The distance of Kīz from Kannazbūr (Panjgūr) is put down here as only two days, but the two places are actually more than 110 miles apart—a very long two days' journey. The other statements which follow either diverge considerably from fact or yield discordant and mutually conflicting averages for the length of the day's journey. Witness the following—

Fahlafahra to Asfaqa 160 miles Two days
Asfaqa to Band 45 miles One day.
Asfaqa to Darak (Dizak) 160 miles Three days
Band to Qasraqand 70 miles Two days

Qasraqand to Kīz 140 miles Four days G I 314

No wonder Le Strange complains that "the earlier Arab geographers know little about Makran and that the later ones add nothing worth mentioning." (L. E. C. 330 note)

I. 29, 1. 17. From Kiz to Armābil six days, etc.

As Kīz is in Lat. 25°-40′, Long. 63°-20′ and Las Beyla [Armābīl] in Lat. 26°-10′; Long, 66°-45′, Haig must be right in remarking that there is some error here. The real distance is 230 miles and he observes that, at the present day, at least twelve days would be required to travel from Kīz (Kej) to Armābīl [Las Beyla]. The actual distance from Armābīl to Kambalī, which is put by Istakhri at two days is, for once, correct, as it is forty-six miles. The real distance of Debal from Nīrūn [Ḥaidarābād] is 87 miles. (I. D. C. 66 and 138). Istakhri makes it four days, but Idrīsi only three (78 post). The Chachnāma, on the other hand, makes it a six days' journey and the distance 25 fārsakhs (158 post).

I. 29, l. 18. From Armābīl to Kambali two days. From thence to Debal four days.

Qambali was on the high road from Armābīl (or Armāīl) to Debal and has been located near Khairkot, about 20 miles to the North-west of Lyāri and commanding the Hālā Pass, by Holdieh (G. I. 150) as well as Le Strange (L.E. C. 329, 330). Khairkot is "an ancient site, an undoubted relic of mediaeval Arab supremacy," and there is ample evidence that this corner of the Bela district was once "flourishing and populous." (G. I. 308). General Haig also places Qambali near Khairkot, but thinks it was somewhere about ten miles to the South-east of Lyāri and about 46 miles from Armībīl. (I. D. C. 137). Lyāri is shown in Constable, Pl. 26 Ac. Qambali is probably the Kambal (Bilāduri, 119 infra), where Muhammad the son of Hārūn died.

I. 29, l. 5 from foot. From Mansura to the nearest frontier of Budha five days.

Budha is the Būdhiya of the Chachnāma (159, 160 post) and Mas'ūdi also speaks of a dependency of Multān called Bauūra [Baūdha] at 22 ante, but Ibn Ḥauqal and Idrīsi write Nodha or Nadha. Dames was inclined to favour the latter reading, because there is a Balūch tribe called 'Nodhaki', who have been in possession of Gwādar in Makrān for centuries and are mentioned by Albuquerque as 'Notakani' in his Commentaries (Tr. Barbosa, I. 87 note). I may point out that Hājji Dabīr also says that in 877 A. H, "forty thousand wild piratical bowmen called Notaks, who had invaded the territories of the King of Sind, were attacked and routed by Sultān Mahmūd Begada of Gujarāt, who was the grandson of the King of Sind." (Zafar-al-Wālih, Ed. Sir E. D. Ress. 22, last line).

The distance between Mansura and the nearest, i. e. southernwish frontier of Budha is stated by Istakhri here (Goeje's Ed. 179. I. 1) as five days, but Ibn Hauqal makes it fifteen and Idrīsi six days (3). Si infra). 'Fifteen' is probably an error of transcription and Istakhri estimate of five days is accepted by Haig. He holds that the extension southern limit of Budha must have been about forty miles are the southern limit of Budha must have been about forty miles are the southern limit of Budha must have been about forty miles are the southern limit of Budha must have been about forty miles are the southern limit of Budha must have been about forty miles are the southern limit of Budha must have been about forty miles are the southern limit of Budha must have been about forty miles are the southern limit of Budha must have been about forty miles are the southern limit of Budha must have been about forty miles are the southern limit of Budha must have been about forty miles are the southern limit of Budha must have been about forty miles are the southern limit of Budha must have been about forty miles are the southern limit of Budha must have been about forty miles are the southern limit of Budha must have been about forty miles are the southern limit of Budha must have been about forty miles are the southern limit of Budha must have been about forty miles are the southern limit of Budha must have been about forty miles are the southern limit of Budha must have been about forty miles are the southern limit of Budha must have been about forty miles are the southern limit of Budha must have been about forty miles are the southern limit of Budha must have been about forty miles are the southern limit of Budha must have been about forty miles are the southern limit of Budha must have been about forty miles are the southern limit of Budha must have been about forty miles are the southern limit of Budha must have been about forty miles are the southern limit of Budha must have been about the southern limit of Budha

Sehwān, and coincided with the southern limit of the present Kākar pargana of the Shikārpur division, west of the Indus. (I D C. 57 note) As Qandābil is said to have been its chief town or capital, Budha must correspond to the Kachh-Gandāva province and Elliot points out that there is still a town called Budha, on the Nīri river, in the very centre of Kachh-Gandāva. (388 infra)

I. 29, l. 3 from foot. From Multan to the nearest border of the tongue of land, known as Biyalas, about ten days.

Byālas is Bālis or Wālistān or Wālishtān It was, Le Strange says, a district to the north of "ūrān and included Sībi and Mastang. (L E C. 332, 347) Gardezi says Mahmūd of Ghazna marched to "Bhātiya by the Wālishtān route (Zain-al-Akhbār, Ed Nāzim, 66, last line). It is also mentioned by Baihaqi, who speaks of Bust, Wālistān and Qusdār as if they were near one another. (Tārīkh-i-Mas'ūdi, Bibl. Ind, Text, 72, 1.9)

The passage is not correctly rendered here and there is no reference to any 'tongue of land' in the original text of Istakhri. What that author says is, "And from Multan to the nearest boundary of Alastan, commonly known as Balis, ten stages."

ومن الملنان الي أوّل حدود الاستان المعروب سالس بحو دا مراحل (Goeje, 179, l. 4)

Dowson seems to have read of 'tongue', instead of lead in In another passage, Istakhri says that the number of stages from Qandābil to Mastanj, the city of Bālis, is four. (Ib 1 6) Mastanj is our Mastung—which lies south of Quetta and west of Sībi Constable 24 B c. 'Kasdān' (on the same line) is meant for Quedār It is in Goeje (179, 1.3).

I 30, l 7 Between Multan and Basmand about two days From Basmand to Al Ruz three—Annan, four—Kallari, two—Mansura, one

The position of Basmand cannot be determined but this statement implies that Mansūra was only twelve (2+3+4+2+1) days' journey from Multān, which is very wide of the mark, even if a day's journey is reckoned at 22 miles. The true distance is about 400 miles, according to Elliot $(373 \ infra)$ and at least 350, according to Raverty (Mihrān, 190 note). Alberūni $(61 \ infra)$ makes the distance 50 farsakhs of about five miles each, which is also too low

The journey between Multan and Al Ruz [Aror] is stated as only five days, though the real distance, as the crow flies, is not less than 240 miles (Mihran, 248 note).

I. 30, l 11. From Debal to Tiz four days, from thence to Manjabari two days

There is great confusion here Goeje's text has "From Debal to Nii un four Marāhil (stages) and from Nirun to Mānhātrā two" (179, L 15) Idrīsi puts the distance from Debal to Nīrun as three days' journey (78 post) Ibn Haugal states that Manhābāri or Manhātāra was two days' distance from Debal, not from Nīrun. (40 post: Gildemeister,

Text 36, Tr. 179). He understands 'thence' as from Debal, not from Nīrūn. Haig is sure that the right reading is not Tīz, but Nīrūn. (I. D. C. 45-6). Tīz is a port in Makrān and it could not possibly have been at a distance of only four days from Debal or of only two days from Manhābāri. Tīz lies in Lat. 25°-0′ N., Long. 60°-40′ E. Debal (about 20 miles S. W. of Tatta) is in Lat. 24°-35′ N., Long. 67°-45′ E. A difference of seven degrees of Longitude implies a distance of about 500 miles on Latitude 25°. I. 30, 7. 17. The Mihrān passes by the borders of Samand and Al Rūr (Aror) to the neighbourhood of Multān; from thence to Manṣūra and onwards until it joins the sea.

Raverty denounces this as nonsense and suggests that 'to' is a blunder for 'from'. His remark that the river could not possibly have flowed back from Al Rūr to Multān is just. (Mihrān, 211 n). This is what Istakhri himself says:-فان لهم بهراً يعرف بعران و بلنني انْ

مخرحبه من ظهرجبل يغرج منه بعض انهار جعون فيظهر مهران يناحبه الملتان فيجرى علمى حدّ بسمد و الرورثم على المنصوة حتى يقع فى البحر شرقى الديبل فيجرى علمى حدّ بسمد و الرورثم على المنصوة حتى يقع فى البحر شرقى الديبل (Text 180, 1, 2).

In the translation from Ibn Haugal, the mistake is avoided and there is no such averment. What the latter is made to say is that "its source is in a mountain from which some of the feeders of the Jihūn also flow. Many great rivers increase its volume and it appears like the sea in the neighbourhood of Multān. It then flows by Basmad, Alrūz and Mansūra and falls into the sea to the east of Daibal." (40 post). A comparison of the text of Ibn Haugal with the words of Iṣṭakhri inclines one to surmise that a line has been missed out in the text of the earlier or added in that of the later author. Ibn Haugal has these additional words after the word,

(Gildemeister, 36, 1, 8). [يمده انهار كشيره غزيرة و يظهر قوافرة [بناحيه الملنان]. I. 31, l. 2. The "Ashkālu-l-Bilād" or the " Kitābu-l-Masālik Wa-l Mamālik" of Ibn Haugal.

The confusion between the Ashkāl-al-Bilād, the Masālik-al-Mamālik and the Suvar-al-Buldān of Ibn Hauqal, to which Elliot refers, has been cleared up by De Goeje. He has shown that the Masālik-al-Mamālik or Kitābu-l-Aqālīm, of Istakhri is only an enlarged edition of the Suvar-al-Aqālīm, also entitled Ashkāl-al-Bīlād, of an older author named Abu Zaid Ahmad bin Sahl-al-Balkhi. (Art. on Istachri-Balchi-Frage, in Z.D.M.G., XXV, 42-58).

This enlarged edition brought out by Istakhri is found in two recensions—a smaller and a larger. The former is represented by the text in Moeller and this is also what is found in Elliot. The fuller recension is the one edited by De Goeje. (Houtsma, Encyclopaedia of Islām, IV. 560). There are several Persian translations or paraphrases of Istakhri's compilation. The so-called "Oriental Geography of Ibn Hauqal", published by Ouseley, is an English rendering of one such ab-

ridgment. The Suvar-al-Buldān is another and fuller recension of this Persian epitome, and two copies of still another version of the same compendium are in the British Museum (Rieu, Catalogue of Persian Manuscripts, I 415-417). Balkhi, the real author or progenitor of all these compilations, died in 322 AH = 934 AC The compiler of the Surar al-Buldān was Muhammad bin Asad bin 'Abdulla, and there is a copy of it in the Bodleian, which is said to be the translator's autograph. The date is not clearly inscribed, but Ethé has read it as 670 AH = 1272 A.C (Sachau and Ethé, Catalogue of Persian MSS in the Bodleian Library, column 397, Ethé, Catalogue of Persian Manuscripts in the India Office, column 365).

I 34, 1 3. I ush (Kambalı)

Holdich challenges Dowson's identification of Yush with Qambali He states that Yush is the modern Uthal or Utal, near which there are unmistakable ruins of a considerable Arab town (G I 307-8) Utal is shown in Constable, 26 A c It is about 20 miles north-east of Lyāii, while Qambali is located by him about the same distance north-west of Lyāri, and by Haig at ten miles south-east of it. Utal is now in Las Bela State

I 38, l. 8 from foot The villages of Dahük and Kalıcân ai e contiguous to each other

Istakhri's spelling is 'Rāhūq' (Goeje, p 176, l 13) and Idrīsi's 'Rāhūn' (80 post) The districts meant are those now called Dashtak and Kolwah Kolwah is a well-cultivated tract lying to the south of the liver, which Ibn Hauqal calls Labi and is now known as the Lob (GI 304) Kolwah is in Lat 26°-0' N, Long 64°-0' E It is shown in the IG Atlas, Pl 35 C3,

I 40, l. 2 From Debal to Kannazbūr, fourteen, from Debal to Manhātara (Manjābari) two, and that is on the road from Debal to Kannazbūr.

The first of these distances is not laid down categorically or in so many words, in Istakhri, but it is implied Cf 29, l 11, where he says: "Kannazbūr to Kīz, 2 days, Armābil 6, Kambāli 2, Debal 4", total 14 Dowson makes Istakhri say that Debal was 4 days from Tīz, but Tīz is a manifest error for Nīrūn It is also stated that it was 2 days from Nīrūn to Manjābari (Manhābāra) and that (Manjābari) was on the road from Debal to Mānsūra (30 ante, Goeje, Text, 179, l 15, 175, l 15). But Ibn Hauqal differs from him here He puts Manhābari at tico days' distance fi om Debal—on the i oad to Qannazbūr, which was 14 days from Debal Both these statements appear to be correct

Manjābāri or Manhābari or Manhātara is a place most difficult to identify Cunningham was sure that it was Tatta (AGI 289), an opinion denounsed by Haig as resting on "a number of gratuitous assumptions" (IDC 31) Raverty was in favour of locating it near Badīn, which is about 62 miles south-east of Haidarābād (Mihrān, 227-229 notes)

The statements of the Arab writers on its situation are so conflicting with one another and so inconsistent with their own averments, that no place can possibly answer all the descriptions found in their writings. Istakhri says it was to the west of the Mihrān and that any one going from Debal to Manṣūra would have to cross the river at Manjābāri, as the two places lay opposite to each other. (Goeje, 175, l. 15). But he also states that Manjābāri was two stages from Nīrūn which was four stages from Debal. (Text, 179, l. 15, 30 ante, q.v. my Note).

At page 37 ante, Ibn Ḥauqal mechanically copies this and puts Manḥābari at two days' distance on the road to Manṣūra, bùt here, he asserts that it lay on the route to Qannāzbūr and two stages from Debal, not from Nīrūn, as Istakhri has it.

Idrīsi further perplexes the matter by locating Manhābari at three days from Sehwan, six days from Firabuz and two days from Debal on the road from Debal to Firabūz, i.e. Qannazbūr. (79-80 post). It is obvious that Manhābari could not have been on the road from Debal to Nīrūn or Mansura and also on that from Debal to Qannazbur. Haig and Holdich attempt to cut the knot by supposing that there were two places bearing the same name. One of them, they locate twenty miles N.E. of Karāchi. somewhere near Mugger Pir and the other, eight miles south-east of Shāhdādpur or about forty miles north-east of Ḥaidarābād. (I. D. C. 68, 138: G. I. 309-10). But this duplication seems uncalled for, as it is founded on the supposition that every statement in Idrisi's Omnium gatherum is correct and must be reconciled with the facts as we know them, even when it is prima facie impossible to do so. It seems that Nīrūn and Mansūra are copyists' errors and that we should read "Qannazbūr" in their stead. Manjābari or Manhābari was really a place which was two days from Debal on the road to Qannāzbūr and it lay opposite to Debal, not to Mansura.

I venture to suggest the identity of Manhabari with Bhanbor. is said by Hughes (Gaz. 120) as well as by [Sir Richard] Burton (Sind Revisited, I. 128) to have been known as Mansawar or Manhara. Bhanbor lies at about two days' distance from Debal on the Gharo channel, about twelve miles north-west of Larry Bandar. (A. G. I. 299). Larry Bandar is about 40 miles south-west of Tatta. (Ibid. 289). In other words, Bhanbor is 52 miles distant from Tatta and about 32 from Debal, which is located by Haig, Raverty, Le Strange and many other writers at about 20 miles south-west of Tatta. Bhanbor is reputed to be the most ancient port in Sind (Burton, l. c. I. 125), and the site is strewn with ruins of "houses, curtains, bastions and amorphous heaps" in which coins and other antique objects are found in abundance. (Elliot, 368 post). It is not a very large place but Manhabari also was not one, as it was only a place of landing or crossing on the road to Makran. The Gharo channel, on which it lies, is an old arm of the Indus which had to be crossed and Manhabari must have been, just what Bhanbor was,

"an outpost guarding the creek and regulating the shipping admitted into the open waterway " (Cousens, Antiquities of Sind, 8")

The real name of what is called Manhābarı was probably Bānhābārı or Bāhnābārı Babhanbārı, i.e., Bāhmanbārı, Sanskrit Brāhmanwāra The Sanskrit form of Brahmanābād is, most probably, Brahmanvāta or Brāhmanvāsa—"Brahman's Dwelling" There are very similar toponyms elsewhere in India i rāhmanbāria is a well-known place in Tippera, Bengal (I G IX. 9) Constable 30 A d Bāmanbore is a petty State in Kāthiāwād (I. G. VII 343) and Bāmnāsa in the same province must be another vernacular form of Brāhmanvāsa There is a Bāmanwās or Bāmaniāwās in Jaipur State, Rājputāna (I. G., Ibid) and about thirty other toponyms of this type are registered in the official Guide to Indian Post Offices General Haig assures us that bān i is an old Sindhi suffix to place-names, e g, Ghorābāri in the Lower Delta, Hurbāri in Shāhdādpur pargana, etc. (I. D C 33)

I. 40, l.5. Kāmuhul from Mansūra is two days' journey.

The forms 'Kāmuhul' and 'Fāmhal' are errors for Amhal (Recte Anhal, Anhil) The distance is palpably wrong Kāmuhul (Anhilwād or Nahrwāla-Pātan in Gujarāt) could not have been only two days' journey from Mansūra in Sind Gildemeister's Text makes it eight stages (35, 1 12 = Tr 179) and this is also what is found in Istakhri (30 ante, Goeje's Text, 179, 1 9) A glance at any map must suffice to show that "eight" is correct Idrīsi states that "from Māmhal to Mansūra, through Bānia, is considered nine days" (84 infra) The error is perhaps due to what having been wrongly read as

1.40, 1.15. The river Sandarūz is about three days' distant from Multān.

Raverty's theory is that this Sandarūs (Sind-rūd of Istakhri, ante 30) must be the "Biyāh and its tributaries, the Bihat, Chināb and Rāvi, which, in those days, passed north-east and afterwards east of Multān and united with the Biyāh some 28 miles to the south-ward of the last-named city." As regards the other river Jandarūz, or Jandrūd, he is positive that it must be "the Hakra, Wahinda or Sind Sāgar, of which, at the period in question, the Sutley was a tributary" (Mihrān, 213-4) He also contends that Jandrūz or Chandrūd—the city which is said to have stood on the banks of the river—is "an impossible name for a town." (Ibid. 219).

It seems more natural to understand these vague and jejune references in such a manner as would be consonant with the names as they stand. These old writers had no real knowledge of the source, alignment or confluence of any of the great Indian rivers. Iştakhri knew the name of the Mihrān and that of only one out of the five rivers of the Punjāb. Ibn Hauqal had picked up, in a blundering sort of way, those of two of them. Mas'ūdi mentions the Rāid (Rāvi), the Bahātil (Biyāh?) and what he calls the 'river of Kashmīr,' but he had never so much as heard of the

Chināb or the Sutlej. He even makes some sort of confusion, by mixing up the river of Bust, Ghazni, Rukhaj and Dāwar [the Helmand] which falls into the Hāmūn of Zarrah, with the Kabūl river and speaking of it as if it was one of the five rivers of the Punjāb. Idrīsi's knowledge did not extend beyond the crude statements of Ibn Ḥauqal and his only original contribution to the subject consists in the portentous pronouncement that Nahrwāra and Mathura stood on the banks of the Ganges (p. 91 infra). Two centuries later, Waṣṣāf was acquainted with the names of only four of the Punjāb rivers, and he mentions them in the wrong order. (E. D. III. 36). 'Unṣuri also speaks of Maḥmūd of Ghazna crossing "the Chandāha, Sihūn, Rahwāli and Behat.' (Ib. IV. 516). Amīr Khusrau is guilty of a similar error (Ib. III. 70 note) and that most "erudite geographer" and author or two "Universal Histories", Ḥāfiz Abru, declares that the Biyāh "falls into the sea in the country of Kambāya."! (Ib. IV. 4).

I venture to suggest that all that is necessary to arrive at the true solution to this puzzle is to add a 'dot' to the second letter and read puzzle or Satadrūz or Satadrūd. The old Hindu name of the Sutlej was 'Shatadru' and Sayyid Muhammad Latīf assures us that it is even now "called Satadru by the lower mountaineers of the Punjāb." (History of the Punjāb, p. 9 note). This Sandrūz or Sindrūd, as Iṣṭakhri calls it, is said to be "about three days' distant from Multān and to fall into the Mihrān above Basmad, but below Multān." Now, the Sutlej is the most eastern of the five Punjāb rivers. It is known as the Ghārā after its confluence with the Bīāh and the combined stream now joins the Trimāb—the Jhelam, Chīnāb and Rāvi—near Uccha to form the Panjnad. Uchha, in fact, "lies on the south bank of the Sutlej opposite to its confluence with the Trimāb". (I. G. XXIV, 82). Uchha is about 72 miles south of Multān or about "three days' journey below" that town.

The courses of the Punjāb rivers have changed considerably within the thousand years that have elapsed since Istakhri wrote. It has been held by more than one authority of great weight that the "Sutlej flowed about this period in the present dry bed of the Hakra, some forty miles south of its present course." (I. G. XVIII, 24). Its old bed through Bhāwalpur and Bikāner can be still traced. (I.G. XXXIII. 79).

(E.D II. 41) Barhaqi also speaks of it as Ab-i Chandrah (Text, 328, 1 3)

The town Chandrūz which stood on its banks is, probably, what is now known as 'Sodhra' or Sodra Chandrūz or Chandrūr must be the vernacular form of Chandrāpura—the city on the Chandrā Chandrāpura would become Chandrāwara, Sandrawara, Sandror Sondrā and Sodrā It is common knowledge that the Indian 'ch' is often changed into a dental or palatal 's' or 'sh' in Arabic, e g, Chaturanga—Shatranj—Chach, Sassa (). Chīna, Sīn, Chāmara (flywhisk), Samara (ante p 5); Chāch, Shāsh A town called Beas stands yet on the river of that name and another called Satrod also exists (Constable, Pl 25 Ab, Ac)

In a word, Raverty's hypothesis is that the Sindrud is the Beas and the Chandrud his favourite Hakrā My submission is that the right solution is just the reverse. The Sindrud is the Satadrud or Sutley which then flowed in the bed of the Hakrā, and the Chandrud is the united Chināb or what we now call the Trimāb. This explanation has the advantage of completely satisfying the phonetic requirements and appears also to be less far-fetched

I. 44, 1. 6 Philosophers and geometricians have divided the land of Hind into nine unequal parts --- as appears from the book called Bātankal.

The identity of this 'Bātankal' with "Patanjali" has been doubted, as there is nothing corresponding to this statement in any of the extant works of Patanjali. The discussion on the subject in Vol II to which Dowson refers is misconceived and gets us nowhere. An examination of the original Arabic text shows that the above quotation is not from Patanjali himself but from a Commentary [Tikā] written by an unnamed author or glossator on some book of Patanjali's. The words used are that I this Tikā is cited in several other places also by Alberūni and the excerpts from it are neither philosophic nor metaphysical. They are all of a Purānic character, treating of cosmographic subjects (Sachau, Tr II, 263-4 Notes)

I 45, 1 6 And the mountain of Meru stands opposite to the southern pole

It should be pointed out in justice to Alberuni that what is here put into his mouth regarding Meru and the heavenly bodies revolving round it by Rashidiu d-din does not represent his own knowledge or opinion. It is merely part of an excerpt from Brahmagupta and the Chapter in which the sentences occur is entitled "Of Mount Meru, according to the authors of the Puranas and of others" (S. I. 243). The "others" are Brahmagupta, Balabhadra and Aryabhatta. Alberuni even warns his readers that "all that Balabhadra produces is foolish, both in words and matter" (Ib 244).

I 46, l 11. This mountain is so high that Firdausi probably meant the following verse to apply to it

This also does not occur anywhere in the original Arabic. The

'verse' is only a purple patch interpolated by Rashid or the Persian paraphrast (cf. S. I. 202).

1. 47, 1. 5. There are rivers and large streams, etc.

The Persian text appears to have been very defective here and this important passage is rendered very differently in several places by Sachau. Some of the toponyms also are very differently spelt. Saciau translates it thus: "In the mountains bordering on the kingdom of Kayabish, i.e., Kābul, rises a river which is called Ghorvand on account of its many branches. It is joined by several affluents. 1. The river of the Pass of Ghuzak. 2. The river of the gorge of Panchir below the town of Parwan. 3.4. The river Sharwat and the river Sawa, which latter flows through the town of Lanbaga, i.e. Lamghan; they join the Ghorvand at the pass of Druta. 5. 6. The rivers Nur and Kira. Swelled by these assuents the Ghorvand is a great stream opposite the town of Purshavar, being there called the Ford, near the village of Mahanara, on the eastern bank of the river and it falls into the river Sindh at the Castle of the capital of Al Qandahar which is Vaihand." Bitur, below (S. I. 259).

Now Thornton writes thus in his article on the Kābul river. "It rises about sixty miles from Kābul, at a short distance beyond which it receives the Lohgar river...... About 40 miles below Kābul, it receives the river of Panchshīr...... It then receives the Tagao river..... The united streams of the Alishang and Alingar join it about 20 miles further down. At a distance of 20 miles more, the Surkhrūd or Red River falls into it. 20 miles further east, it receives the Kāma, called also the river of Kunar..... Just below Dobandi, it is joined by the Landye or Panjkora.....and receives the river of Swāt from the north-east. After this confluence, the Kābul river falls into the Indus opposite Attock."

It is clear from this that Alberuni's river of Ghorvand is not, as Dowson says in his note, the affluent or tributary called Ghorband in our mans but the main stream, the great Kühul river itself. It will be

pur after getting off a little above Jahannuma, i.e Jalalabad" (A' Beveridge, Bāburnāma, Tr 421). The Ford [M'abar] of Mahnāra is the Marminara of Baihaqi (ED II, 150) and may have been near what is now called Pratah Minara—the Fallen Minara for Towerl (Raverty N. A 93) Bitur which is said to have been below Waihind is probably the Petora of Captain Wood, who states that he passed by it on his journey by boat from Attock to Kalabagh (Journey to the Source of the Oxus, Ed Yule, p 76) Mr H C Srivastava informs me that Petore still exists at about 31 miles south of the Attock Bridge and is locally known at Kot Pethere The ruins of a Buddhist stupa, two rock-cut wells and of a castle can be still traced and are clearly visible. The Nur and the Qira are two rivers of Kasiristan in the north-west of Lamghan (Raverty, NA 108, 135) They are shown in (Sir) C R Markham's 'Map of the Sulaiman Mountains on the Northern Frontier of India' in the Proceedings of the Royal Geographical Society for January, 1879 See also E. D II 465

- I. 48, l 2. After that there comes from the west the rwer of Tibet, called the Javlam
- Tibet' is a palpable error for الله Behat, the ancient Vitasta and the Kashmiri Veth
- 1 49, 1 16 It comes from the city of Turmuz and the eastern hills
- says is that "between the mouths of the rivers Sarsūti and Ganges is the mouth of the river Narmadā, which descends from the eastern mountains and takes its course in a south-western direction" (S I 261)
- I 50, l 4 The three eastern streams are the Balan, Ladafi and Nalin

Sachau reads Nālini, Hrādini and Pāvani (I 261) All that follows upto the end of section iii at page 53 infra is, again, not an expression of Alberüni's own opinions or knowledge, but an exposition of the Purānic geography. He is merely reporting or repeating what is said about the rivers of India in the Matsya and Vāyu Purānas (S I. 257, 259). The mention in the latter part of the excerpt of people whose lips are like inverted ears, whose ears hang down to their shoulders and whose faces are like those of horses, indicates that we are in the region of cosmographic myth and not of scientific geography

I 54, l 4 from foot. In stating these distances we will begin from Kanauj

Alberuni's Indian Itineraries are, speaking generally, more accurate and reliable than those of Istakhri or Ibn Hauqal, and he appears also to have been fully aware of the pitfalls which he in the path of a scientific investigator, who had to depend upon the assertions of individuals of the Hindu mentality. His Tables of Distances are introduced with the following prefatory observations, the significance of which cannot be too strongly emphasised, especially as they have been lightly passed over in this version of Rashīd-ud-dīn's abstract "It is only with the greatest

exertion and caution that we can, to some extent, correct the statements of the Hindus. But we could not make up our mind to suppress that which we knew on account of that which we did not know. We ask the reader's pardon, where there is anything wrong." (S. I. 200; see also Reinaud, Fragments, 82-3; Tr. 102).

The information contained in these fifteen or sixteen itineraries is derived from three different sources of very unequal value: (1) The Quarter-Master-General's Department of the Sultan, as regards the routes along which Mahmud's cohorts had marched, in the course of his invasions, leaving fire, famine and slaughter in their trail. Many of the places mentioned in 'Utbi's history, Bhātiya, Nandna, Narāin, Thanesar, Barhamshil, Loharin, Mathura, Bari are noticed here also. They are the most reliable part of this lucubration. (2) The information supplied by Musalman traders, travellers and authors about the more distant parts of the country. (3) The literary and traditional statements of old Hindu writers and living pandits about towns and countries famous in Hindu literature and history, e.g., Ujjain, Bhilsa, Tanjawar, Rāmeshar, Kāmarūp, Khajurāha, Bāroi (Dwārkā), Uwarayahār, Odravishaya, etc. Respecting these, Alberuni had to rely on the assertions of persons whose knowledge he knew to be derived merely from tradition or hearsay, but he had to accept them for the nonce, for want of anything more trustworthy.

It will be observed that whereas the distances tabulated in the itineraries of the first class are expressed precisely in tens and units as 8, 9, 12, 15 or 17 farsakhs, those drawn from the second and third sources are expressed only in round numbers, 20, 40, 50, etc. In fact, these numbers are all but useless and rarely helpful in the identification of place-names which are doubtful or incorrectly transcribed or relate to extensive districts or provinces. These latter were, for the most part, only vague geographical expressions, the connotations of which were not fixed and must have varied from time to time in accordance with historical events which changed the political map of India.

Alberuni states here that his farsakh is four miles but this is the Arabian mile, which is neither the English statute mile nor the English geographical mile. He is careful to define this mile here as equal to 4000 cubits & (S. I. 166-7) and at I. 200, he again declares that 1 Farsakh = 4 miles = 1 Kuroh = 16000 cubits. If the cubit is reckoned at 24 fingers or about eighteen inches (A. G. I. 571), Alberuni's mile must be valued at 6000 feet and his Farsakh at 24000 feet = 4 6/11 English miles. But the length of the cubit or & is variously estimated and Sprenger reckons the Arabian mile as equal to 2000 metres = 2186 English yards = 6558 feet. (Die Post und Reiserouten des Orients, Vorrede, xxvi apud S. II. 316 note). Mr. Gibb equates the Arabian mile with 1921 metres (Travels of Ibn Batūta, 347-8). Now, four Arabian miles of 2186 English yards each would be = 8744 yards = 4 39/40 miles. Or if

Mr Gibb's estimate is preferred, 4 Arabian miles = 7684 metres = 25200 feet = 4 17/22 English miles Dr. (Sir) Aurel Stein takes Alberûni's farsakh to have measured a little short of five miles (J A S. B. 1899, p. 25)

Elliot, Cunningham, Raverty and others who have animadverted on the undue abridgment of the distances laid down in Alberüni's itineraries, have done so on the supposition that his farsakh was equal to only three miles. But it will be seen that this fundamental postulate or assumption is demonstrably incorrect. It follows, not only that the animadversions are founded on their own error, but that the identifications they have proposed on the basis of that assumption must be of doubtful validity.

The following comparative table will show that Alberuni's farsakh works out at five miles or even more, when he speaks from his own knowledge or had trustworthy sources of information —

Kābul to Ghazna	17 f	88 miles	(I G. XIV 12)
Parshāwar to Dünpur	15 f	79 "	(I G XIV 12)
Washind-Parshāwar	14 f	60 ,,	(Sarkār, I A. cu)
Dünpür to Kābul	12 f.	90 ,,	(Sarkār, I. A ciii)
Patna-Müngir	15 f 10	00 "	(Seeley, Roadbook, 3).
Qanauj-Kajurāha	30 f	180 "	(A G I 481).
Qanauj-Jajmau	12 f	58 "	(Thornton, Gaz 542).
Müngir-Champa	30 f	136½ "	(A G I. 572)
Qanauj-Mathura	28 f	1654 "	(A G I 572)
Anhilwära-Somnäth	50 f.	260 ,,	(Measured on the map)
Qanauj Mīrat	40 f.	225 ,,	11 27
Pānipat-Kithal	10 f	25~Kos	(Yazdî in E D. III 494).

But this does not mean that his distances are always correctly stated They are often undoubtedly faulty, but this is because his informants—Hindu Pandits, Muhammadan travellers, merchants or sailors had no real knowledge of the remote districts and towns which they had heard of, read about, or casually visited. Some confusion appears to have been introduced also by the fact that Alberūni has copied some of his distances from Hindu authors who had stated them in terms of the ambiguous Yojanā, which had to be converted into Farsakhs.

The Yojanā has been variously estimated at from $4\frac{1}{2}$ to 9 miles and its exact length has been a frequent subject of puzzlement and controversy (A G I 571-2) In fact, the Yojanā, like the Kos, would appear to have been kachā as well as puccā and it is often exceedingly difficult to say whether the Yojanā in a particular case is of the first class or of the second We have just seen Alberūni stating explicitly that a Kui oh was equal to a Farsakh or 4 Arabian miles. But at I 166, where he gives the Hindu Table of measures of length, he states as explicitly that the Kuroh was only 4000 Arabian yards or cubits, i.e. 6000 feet or one Arabian mile. Then at I. 167, he assures us that the Yojanā was equal to 8 Arabian miles or 32000 Arabian yards = 48,000 feet and that the Kuroh was $\frac{1}{2}$ of a Yojanā, i.e. 4 Arabian miles.

Elsewhere he tells us that Valabha [Valā] is 30 Yojanās from Anhilwāra (Text. 205, l. 21 = Tr. II. 7). Here, the Yojanā must be the short one of about 4½ miles, as the real distance is about 150 miles. Anhilwād [Pāṭan] is in Lat. 23°-52′ N.; Long. 72°-10′ E, Valā near Bhāvnagar in Lat. 21°-46′ E.; Long. 72°-11′ E. It is evident that the Yojanā was of two sorts and Alberūni himself makes no secret of his own bewilderment.

I. 54, last line. Eight parsangs from that [Jājmau] is Karwa; from Karwa to Brahmashk eight; thence to Ābhābūdi eight; thence to the Tree of Barāgi (Prāg) twelve.

The relative situations of three of these places are reversed in the Arabic. According to Sachau and also Reinaud, (83; Tr. 103), what Alberūni says is; "Jājjamau 12 farsakh from Qanoj. Abhāpūri 8 f., Kuraha 8 f., Barhamshil 8 f., Tree of Prayag 12 f." (S.I. 200). If the Arabic is right, Kuraha must be Kora-Jahānābād, which lies about 29 miles west of Fathpur in Khajūha Tahṣīl, Fathpur District, and about 112 miles north-west of Prayāg by road. (Agra and Calcutta Gazetteer quoted in Sarkār, I.A. cxii). Alberūni gives the latitude of Kuraha as 26°-1′ N. The I. G. makes it 26°-7′ N. (XV. 398).

Barhamshil reminds one of "the Brahman's Fort" of 'Utbi' which was also called 'Munj'. 'Brahmashil' literally means, 'Brahman's or (Brahma's) Rock or Stone.' Munj has been supposed by Elliot to be Majhāwan or Manjhāwan, ten miles south of Kānhpur (Cawnpore). (E.D. II. 458). Dr. Nāzim thinks it must be Munjh, which lies about thirteen miles north-east of Etāwa (Maḥmūd of Ghazna, 109). But a glance at the map will show that neither Manjhāwan nor Munjh can be identified with Alberūni's Brahmashil, as the latter is said to have been 12 farsakhs, about 60 miles only, north of Prayāg. Majhāwan is 10 miles south of Cawnpore which is 124 miles north-west of Prayāg (Th. 24) and Munjh, near Etāwa, is ruled out a fortiori, as it is even more remote.

There is a Manjhanpur about thirty miles north-west of Allahābād (Constable 28 Bc). It is approximately in Lat. 25°-32′ N., Long. 81°-30′ E. (I. G. XVII. 197) and may be Brahmashil.

Abhāpūri (Abhaypuri?) cannot be identified.

identified I suggest that the right reading may be level Awaddihār—the Awandbihār of Minhāj (Tabaqāt-1-Nāsii i, Text 128, 1 2), which is said to have been one of the districts conquered by M'uizz-uddīn Sām Uddandapur or Uddandvihār was the old capital of Magadha and is now represented by the town of Bihār. There was a great Buddhist monastery and college here. It is mentioned in an inscription of Surapāla of the Pāļa dynasty (Rākhaldās Bānerjea in J. A.S B 1911, p 760) The distance given is only approximate and meant probably for the nearest boundary of the kingdom Another phonetic approach may be extend videha Its capital, Mithilā (Darbhangā), was in North Bihār (J A S B 1897, p 89, I G XVII, 380). In a word, Uwaryahār must be either Awandbihār or Videha, ze South Bihār or North Bihār, but the former is to be preferred

Urdabishak (Ourdabishau in R 104) which was on the borders of the sea, fifty farsakhs from Awandbihār (or Bihār) must be 'Udravishaya' or 'Odravishaya', the country of the Odras, ie, Oriyas, not 'Urdhva-Vishaya' as Sachau suggests (II 318 Notes) His MS read 'Ūrdabīshau', but this must be due to the copyist having transposed the and "The ancient province of Odradesha," says Cunningham, "comprised the whole of the present districts of Cuttack and Sambalpur and part of Medinipur" (Midnāpore) (A G I 511) Odra is mentioned by Alberūni himself in the list of countries in the east, in juxtaposition with Magadha, Mithilā, Samatata, Paundra, Utkala, etc (S I. 301)

I 55, last line There is a Lingdom which is at present near Chūn, and the beginning of that is Dar (or Dūr), forty

The Arabic has it thus 'Thence along the coast towards the east are countries which are now under the sway of Jaur first Daraur, which is 40 f from Ūrdabīshau, Kānji 30 f, Malaya 40 f., Kūnk which is the last of Jaur's possessions in this direction' (S I 200, R 104) 'Jaur' is the Arabic way of writing 'Chola' and the king referred to is the great Rāja Rāja Cholā I, who reigned from 985 to 1011 A C, or his son Rājendra Cholādeva I, who succeeded him and ruled upto 1052 A C. "In the course of his reign, Rāja Rāja passed from victory to victory, conquering the eastern Chālukyan kingdom of Vengi, then Coorg and Quilon, and even the northern kingdom of Kalinga At his death, he was the undoubted Lord Paramount of Southern India and ruled a kingdom which included nearly the whole of the Madras Presidency, Ceylon and Mysore His son continued his father's ambitious career and his conquests extended to Orissa and even Bengal" (Smith, E H I 345 6)

Daraur is Dravara, ie Dravida Malaya must be the Pandya country comprising the modern districts of Tānjore, Madura, etc. (A G I 549, 551) Kunk is Kongu-nād, the old name of a province which comprised Coimbatore and the south-western tāluqs of the present Sālem district. "Coimbatore is even now called Kongunād. During the ninth cen-

tury, the Kongu country passed under the Chola kings who held it for nearly 200 years. It then fell in the eleventh century into the hands of the Hoyshalas." (I.G. X. 358).

It is perhaps worth noticing in connection with Alberuni's spelling of the name 'Chola' that the oldest form is 'Chora', as in the Inscriptions of Asoka. Ptolemy has 'Chorai' and Pliny 'Sora'. (I.G. X. 326).

I. 56, 1.8. Thence [from Pātaliputra] to Mangūri, fifteen.... Champa thirty; Dūkampur fifty,......Gangā Sāgar, thirty.

Mangīri is Monghyr, the old name of which is said to have been Mundagiri or Modagiri (A.G.I. 476) or Madgagiri (Inscription of 12th or 13th century), "Hill of Madga". (I. G. XVII. 401-2). The actual distance of Monghyr from Patnā is about 100 miles. (Seeley, Road-book of India, Pt. 1, p. 3). It is reckoned at 37 Shāhjahāni Kos—each Kos of 500 yards = about 2 3/5 miles, i.e. 96 miles by Bakhtāwar Khān, the secretary of Aurangzeb, in the Mirātu-l-'Alam. (E. D. VII. 163).

Champā is the old name of Bhāgalpur district. Close to Bhāgalpur, two villages named Champānagar and Champāpur still exist. (A. G. I. 477).

Dūkampur has not been located, probably because the name is spelt wrongly. The reference seems to me to be to وَرَمُوو Vikrampur (the old capital of the Sena kings of Bengal), eight miles south-east of Dāccā. The copyists appear to have first turned it into south-east of Dāccā. The copyists appear to have first turned it into vice the property, and lastly into this fantastic دو کيور Vikrampur is still the name of a pargana in Munshiganj division of Dāccā district. Lat. 23°-33′ N., Long. 90°-30′ E. (I. G. VIII 220; XXI. 182). Vikrampur was the favourite residence of Ballālasena, the great grandfather of Lakshmanasena (r. 1119-1192 A. C.)

Gangā Sāgar, where the Ganges fell into the sea at one time, must be Saugorisland. It is said to be about thirty farsakhs—140 miles—from Dūkampur. As Vikrampur is in Lat. 23°-33′ N., Long. 99°-30′ E. (I. G. XXI. 182), and Saugorisland, at the mouth of Hooghly, lies between Lat. 21°-30′ and 21°-36′ N. and Long. 88°-2′ and 88°-11′ E. (I.G. XXI. 366), the real distance between the two places must be nearer 240 miles than 140. The error may be due to the confusion or ambiguity about the length of the Yojanā. Two hundred and forty miles would be about equal to thirty pucca Yojanās of about eight miles each.

I. 56, last line. Thence [i.e. from Māli Bāri, ten f., from Qanauj], to Dūkam, forty-five.

"Dūkam" is Dogāon, on the bank of the Sarju, about four miles west of Nānpāra station on the Bengal North-Western Railway. It is 22 miles north of Bahrāich in Oudh. (I. G. XVIII, 367). Lat. 27°-55′ N., Long. 81°-35′ E. It is now in ruins, but was a prosperous town in the days of Akbar and copper coins struck here by him and Shāh Jahān are not uncommon. (Vost, The Dogāon Mint, in J. A. S. B. 1895, pp. 69-71). It is said to have been destroyed about the end of the reign of Shāh

Jahān in consequence of the curse of a saint named Shāh Sājan. (Gazetteer of Oude, Ed. 1877, I 144).

I. 56, last line. Thence (from Dūkam) to the kingdom of Silhet, ten; thence to the city of Bhut, ticelve.

This Silhet is, as Dowson notes, Shāhjahānpur-Silhat in Gorakhpur. It is 30 miles east of Gorakhpur town Lat. 26°-40′ N. Long 83°-53′ E. Bhut may be Bettiah, Lat 26°-48′ N., Long 84°-30′ E., which is 82 miles east of Gorakhpur, ie 52 east of this Silhet (Th). Bettiah is the chief town of Champāran, the north-east division of the district of Sāran, and that division is often called Bettiah even now. (Th) If Sylhet is the place of that name in Gorakhpur, Reinaud's identification of this 'Bhut' with Bhutān (Fragments, 105 n) will not bear examination.

I 57, l. 2. Thence for two hundred parasangs, it is called Tilūt, where the men are very black and flat-nosed like the Turks

The words for "two hundred parasangs" are not in the Arabic Text, (98, 1 11), which merely says that "further on, the country to the right [of Bhut] is called Tilwat, the inhabitants Tarū, people of very black colour and flat-nosed like the Turks" (S I. 201; R Tr 105). Tilwat (or Tilūt) is Tirhūt The old Sanskrit form Tirubhukti is probably derived from its "flat-nosed" Mongoloid inhabitants called Tharus The Tharus are mentioned along with the Koch and Mech by Minhāj (T N. in E D. II. 310, q v my Note See also Blochmann, J A S B 1873, p 239 note).

1 58, l. 1 Thence to Dhāl, of which the capital is Bītūri, to the king-dom of Kankyū.....is twenty parasangs.

In the Arabic, "the capital is \mathcal{LLE} Tiauri or Tivari" (Text 99, 11), of which the ruler is called "Gangeya" (S. I. 202, R Tr. 106). Sachau says that "its position cannot be determined", but there can be little doubt that it is Tripuri, the ancient capital of Dahāla or the Chedicountry. It is now called Tevar and was also known as Karanbel. The village of Tevar lies about four miles from Jabalpur (Jubbulpore) (IG. XIV, 207). 'Tiwāri Brāhmans' are a well-known caste in the United Provinces. Kankyū (Gangyū) is Gāngeyadeva Chedi, who ruled from about 1020 to 1040 A C. He is mentioned by Baihaqi also, who says that Banāras was in the kingdom of Gang[eya], when Ahmad Niāltigīn sacked it in 424 A. H. 1034 A. C. (Text, 497, 1. 9 f. f., E. D. II, 123)

1. 58, l. 3. Thence to Asūr, thence to Banawās, on the shore of the sea

Banawāsı is a place of great antiquity and is mentioned by Ptolemy. It has sixteen miles south-west of Hāngal in the Sirsi taluka of Dhārwār district Lat 14° 33′ N, Long. 75°-6′ E. Alberüni is mistaken in saying that it has on the sea coast (Fleet in B G I ii 278-9 note)

Asūr or Arsūr, as Sachau and Reinaud read it, has not been identified. It may be the old part of Barcelore, the name of which is Basarūru in Canarese and is also written Abasarūr by Ibn Batūta

(IV. 77-8), Bésarûr by Abulfeda (Gildemeister, 184) and Barsalur, Bassaloor, Barcalur by others, Lat. 13'-55' N. It lies ten miles south of Bhatkal. (Yule, H. J. 15), Constable 34 B c. v.n. Barkalur.

1, 59, 1. 7. From Mahura (Mathura), at the distance of thirty-five f.
you come to a large town called Diathi; thence to Bug'hur,
seven.

Dailhi may be Dudahi, now in pargana Bilbahat, Jhinsi district, nincteen miles south of Lalitpur. It contains a great number of Chandel rains and a large Chandel tank. (Silberrad's Art. on the "History of Western Bundelkhand" in J.A.S.B. 1902, p. 125 note). Dudahi is raid in the I.G. also (XI. 374) to have been a place of great importance at one time. The tank and temples are stated to be undoubtedly of the Chandel period and a colossal image, twenty feet high, of the manifold inextration of Vichnu, which is carried on a rock close by, is also mentioned. Dudahi is shown in Constable 27 Deandis in Lat. 21-257 N., Long. 78-227 E. (I.G. loc. cit.). It is true that this differs from that given by Albertini himself—25-40′ N.—in the Qānūn-i-Max'ādi (S. II. 317 Noted), but this is of little or no moment. Albertini's results constinct vary from those of modern surveys by 2, 3 and even 4 degrees in regard to places, the names and situations of which are absolutely certain. Compare the following:

•	Alberimi	Bartholomeic's Atlas.
Kibul	33'-47'	84°-30′
Pedriwar	31 -111	34°-17
Jailam	33-21	32°-55′
Multin	20 .407	30"-12/
Timeri (Jubbulpore)	530.	24°-36′
Pătaliputra	22,307	25°437/
Müngir	22'-0'	25°-23′
Dahmil (Nürpur)	31 -10'	32°-17′
Ujjain	24 -0'	23°.9′
Tănjore	15°-0′	10°-47′
Rimeshwar	13'-0'	9°-17′
Brahmanäbid	26'-10'	25°-52′
Tin	26°-15′	25°-0′ .

(Sachau, II. 311, 317).

This should teach us that in those cases in which the situation of a place admits of doubt, the Table of Latitudes given in the Qānūn-i Mas'ūdi is not likely to prove helpful and may be even misleading.

Reinaud and Sachau read the second name as Bāmahūr, not Bās'hūr and there is also the variant 'Māhūra'. Sachau makes the distance from Dūdhi to Bāmahūr, seventeen farsakhs (I. 202), but Reinaud agrees with Dowson in reading the figure as seven. All three agree, however, in placing Bās'hūr or Bīmahūr five farsakhs north of Bhīlsā. There is a place called Bīsoda which lies about 25 miles north of Bhīlsā (Constable,

27 Cc) and it may be the town meant, if the right reading is Bās'hūr

Alberun makes the distance between Mahībalistān (Bhilsā) and Ujjain nine (or ten) farsakhs only, which is wrong Bhīlsā is in Long 77°-50′ E, Lat. 23°-30′ N., Ujjain in Long 75°-47′ E The two places are really about two degrees of Longitude, about 130 miles, not 45 or 50 miles only, distant from each other Ujjain, again, is more to the north of Dhār, than to the east of it

I. 60, 1.5. From Dhar going south, you come to Mahumahra, ten f, thence to Kundaki, twenty, thence to Namaicar on the banks of the Nerbadda, ten, thence to Biswai, twenty, thence to Matdakar, on the banks of the Godavery, sixty f

Almost all the toponyms are written differently in the Arabic (Text, 99, 1 11) Sachau has "Bhūmihara, Kand, Namāvur, Alīspur and Mandagir" Reinaud reads "Mahūmahra, Kandwahū, Namāwar, Albaspur and Matdakar" All that can be said of the first of these names is that it seems to be a miswriting of Maheshwar and that the second may be Khandwa The third must be meant for Nimāwar which lies on the right bank of the Narmadā, 90 miles south of Ujjain (Th) Alīspur may stand for Ellichpur and Mandagīi, which Sachau was unable to locate, is undoubtedly Mungipattan (now called Paithan), a place of great antiquity and the legendary capital of Shālivāhan It is mentioned by Ptolemy and also in the Periplus It is now in Aurangībād district and ites on the north bank of the Godāvery (I G XIX 317) Constable 31 Cb Ellichpur is said to have been founded by an old-time Jaina Rājā named II (I G XII. s, n) and is mentioned by Barani (T F Text, 222, 19)

Khandwa also is said in the I G to be a place of considerable antiquity "Owing to its position at the junction of the two roads leading from Northern and Western India to the Deccan, it must have been occupied at an early period. It is mentioned by the geographer Alberuni In the twelfth century, it was a great seat of Jain worship. The town has four old tanks with stone embankments" (XV 241)

Khandwa may be, as this writer suggests, the Kundaki (Kand or Kandawaha) of this passage, but it is at least forty miles south of the Narmadā and not north of it, as Alberūni locates it Nimāwar is on that river, but it lies about 80 miles north-east of Khandwa and not fifty south of it Again, it is said to be 49 (9 + 10 + 20 + 10) farsakhs, that is, about 240 miles distant from Ujjain, but this is more than double the true distance, which is 90 miles only (Th) Alberūni has, in fact, reversed the positions of and doubled the distance between the two places

The whole of this Mālwā itinerary is more or less full of error. The great Arab polyhistor is merely repeating what he had learnt from books or from his Pandits about all such places in the province as were "renowned in Hindu story". He is not moving due south from Dudahi, but jumping from one famous town to another and towards all noints of the compass, as the names occurred to him. The ambiguity

relating to the Yojanā and the Kūroh may have been partly responsible for the disparity in the distances and his informants' ignorance of topography for the confusion in the bearings.

I. 69, l. 10. Bahrūj and Dhanjūr, forty-two f. south of Anhilwara.

Bahrūj is, of course, Broach, but Dhanjūr is not so easily identified, Reinaud reads 'Rahanhour' and Sachau 'Rihanjur' (Fragments, 88, Tr. 112; S. I. 205). The place meant is Rānder, a very old town near Sūrat on the other side of the Tāpti. Barbosa speaks of it about 1514 A. C. as 'Rānel' and says it was "a rich and agreeable place of the Moors, which had very large and fine ships." The Portuguese sacked it in 1530. It is mentioned also in an inscription of the time of Muḥammad Tughlaq, which is now in the mosque at Navsāri, about eighteen miles south of Sūrat. It relates to a mosque erected at 'Rānel' by Malik Maqbūl, who was then Governor of Gujarāt.

I. 61, l. 14. West from Narāna is Multān at the distance of fifty parasangs; thence to Bhāti fifteen; south-east from Bhāti is Aror, fifteen. Bhāti is situated between two arms of the Indus.

Aror was south-west, not south-east, of Bhāti according to Sachau. (S. I. 205). But Dr. Nāzim translates the passage thus: "From Bazāna towards the west, Multān is 50 f. and Bhāti is 15 f. and from Bhāti towards the south-west, Aror is 15 f. It (Aror) is a township between the two arms of the river Sind." (M. G. 199 note). Dr. Nāzim's point is that it is Aror and not Bhāti which is said to lie between two arms of the Sind [Indus] and he is, most probably, right. It may be worth while to note that Sir H. Elliot had rendered the sentence exactly like Dr. Nāzim in his First Edition (Bibliographical Index to the Historians of Muhammadan India, 1849, p. 30).

Alberuni's 'Bhāti' has been supposed by some writers to be identical with the 'Bhātiya' of 'Utbi and Gardezi, but the phonetic resemblance seems illusory. Wherever Bhātiya was—whether at Uchch. Bhera, Bhaṭinda, or Bhaṭner, it was not this Bhāti, which was 15 farsakhs—about seventy miles—north-east of Aror. The latter is really one hundred and sixty miles distant from Uchch, (Mihrān, 248 note) and much more remote still from all the other places mentioned—Bhera,

(I.G. s. n.) 'Balawarda' is really Ballavar which lies west of Chambi and south of Bhadravab. It is frequenty mentioned as 'Vallapura' in the Rayatai angini. It is now called Bisolih and was the capital of one of the chiefships attached to the Jamma division of the Alpine Punjab. (Stein, J.A.S.B. 1899, p. 127; A.G. I. 133, 135). Constable 25 A.a. s.n. Belaor.

Lidda (1.8) is the valley of the Liddar river which is one of the principal feeders of the Jhelum. It rises in the southern slope of the mountains bounding Kashmir on the north-cist, in Lat 31°-8' N Long 75°-48', and falls into the Jhelum five miles below Islāmabād (Th) Sir Walter Lawience says it is also called the Limbodri and that it comes down from the everlasting snows, overhanging the head of the valley, which is famous for its beautiful scenery (Valley of Kashmir, 18)

1. 62, 1. 7. Thence (from Dyamau) to Gati, ten, thence to Ahar ten, thence to Mirat ten, Panipat ten

1.62, l 10. In going south-icest from [Sunām] to Arat-hūr, nine f, thence to Hagnīr, six, thence to Mandhūkūr, the capital of Lohāwar, eight f

R has Adat'hūr (88) S reads it as آدِ تَوْد (Text, 101, 1 2) 'Adittahaur' (I. 206) If the second letter is read as a $v\bar{a}v$, and the third as a be, we get let let Aubbahor, te Abohar, a place of great antiquity on the old channel of the Sutley It was the frontier town of the district of Dibalpur It is mentioned by Barani as well as Budium, as lying on the route from Minhaj (E D II 350) and Ibn Batūta both passed Delhi to Multan through it in going to and coming from the latter town (Gibb, 190) It was the native town of Shams-1-Siraj, the historian, and his grandfather was revenue officer of the dirtrict. Abohar is said to mean 'Pool of Uboh' and to have been named after Uboh, the wife of Janra, a grandson of the legendary Bhatti king, Raja Rasalu (Mihran, 263 note and 278) Alberuni's spelling seems to lend countenance to this traditional derivation and indicates that the old name was not 'Abohar' but 'Aubbahor' or 'Aubohhar' The town is now in the Fazilka tabsil of Ferozepore district (LG V 2) Constable 24 E b.

' Hajnīr' or Jajjanır (S Text, 101, 1 2) is an equally knotty problem. It is mentioned by Wassāf (E. D. III 36) and it is probably the same as

Sayyads in the reigns of Balban and 'Alāu-d-dīn Khalji, according to Barani (Tār. Fir, Text, 118. l. 8; 350, l. 3 ff). But it seems that the real name was neither 'Hajnīr' nor Janjer but Jajner and that it is now represented by Janer village—a ruined site in the Zīra tahṣīl of Ferozepore district, Panjab. Janer is twelve miles distant from the town of Zīra and six from that of Moga, q.v. Constable 25 Ab. It is locally said to have been the capital of the Parihār rulers of the district in old days and a huge mound of ancient times can be still seen in the place.

The last name is written by R. as Medhūkūr (88), by S. as Mandahūkūr (206) and by Baihaqi as Mandākkūr (Text, 523, l. 6 ff.) Alberūni and Baihaqi both state that it was the specific name or designation of the strongest fortress, fortified camp or citadel (50) in the town of Lāhore. Abul Fazl mentions a 'Mankoknor' in his list of the Dastūrs or Revenue Divisions of the Sūba of Lāhore and places it in juxtaposition with Sīālkot, which is 63 miles N.N.E. of Lāhore. (Aīn. Tr. II. 110). But if this Mandakkūr was the citadel of Lāhore itself, it could not have been identical with or even in close proximity to Siālkot.

Medhükur, Mandahükur, 'Mandakkur' look like corrupt or debased forms of some such Hindu name as Madrakgarh or Mand-i-Khokhar. Eastern Punjab was known in ancient times as Madra-desha, the country of the Madras or Madrakas. In the Mahābhārata (Sabhā Parva, XXXI. 1196-7), Shalya is called the King of Madra, the capital of which was Sākala and was situated between the rivers Chenāb and Rāvi (Archaeological Survey Reports, II, 192-6; see also Pargiter, J.A.S.B. 1895, p. 251). Dr. Fleet has almost conclusively shown that this Sākala was Siālkot (E. H. I. 68 note) and this may indicate that the name is connected with Madra or Madrakas and with their capital, Siālkot. But Alberūni himself gives the latitude of Siālkot as 32°-58′, of Mandahūkūr as 31°-50′, of Nandna as 32°-0' and of Multan as 29°-40' N. (S. I. 317). Unfortunately, that of Lähore itself is not stated, but the fact that Siālkot is said to have been 1°-8' further north than Mandahūkūr proves that the two are not identical and that Mandahūkūr must have been somewhere near Lahore and almost in the same latitude. Alberuni's latitude of Mandahūkūr is nearly the same as the true latitude (31°-36' N.) of Lähore. But very little can be built upon this, as his figures are often wrong.

I. 63, l. 14. The people of Kashmīr are carried on men's shoulders in a Katūt which resembles a throne.

ويركب كبارهم الكتوت وهي الاسر. و يحملون على اعناق ال رجال . (8 . 1 . 101)

"The nobles ride in palankins called Katt carried on the shoulders of men". (S. I. 206). Here (R. 89, I. 7) is an Indian vocable connected with the Sanskrit Khattākā or Khattīkā, Hind. Khāt, 'cot, bed-stead'. Sir Aurel Stein speaks of the Kattūt as 'palankins' and traces the word to the Sans. Karni-ratha of the Rājatarangiṇi, (J.A.S.B. 1899, p. 23 and note) but this may admit of doubt. 'Palankin' itself is derived from

the Pers. Palang, bedstead, and 'Palang' is connected with the Sanskrit Paryanka, a bed. (H.J sv Palankin).

I. 63, l. 3 from foot. The principal entrance is at Birāhān, half way between the Sind and Jailam

S and R. 89, I 13 read Babrahān Dr. Stein rejects Cunningham's identification of it with 'Babarkhāna'. He says it is Babrahān, a place near the village of Chamhad, which lies SW of Abbottābād. Latitude 34°-7′ N Longitude 73°-7′ E He states that the easiest route to Kashmir from the west, leads through the open central portion of Hazārā district to Mansehra, thence to Muzaffarābād and thence to Bāiāmula The eight farsakhs (39 miles) which Alberūni counts from Babrahān to the bridge over the river—which must have been at what is now called Muzaffarābād—would well agree with the actual distance between Babrahān and Muzaffarābād (l c 24, 222)

I. 64, l 1. Where the water of the Kusari is joined by that of the Mamhari

Sachau reads 'Kusnāri' and 'Mahvi' (I 206) Sir Aurel Stein identifies the Kusnāri with the present Kunhār river which "falls into the Jailam, a few miles below its great bend at Muzaffarābād, near which the bridge at the confluence of the Jailam and the Kishanganga must be located" The Mahwi, he says, must be the Kishangangā itself The only error in the description is that Alberūni makes the Kunhār join the Mahwi (Kishangangā), whereas it really falls into the Jailam after the latter's junction with the Kishangangā (loc cit 23-24)

I 64, l 3. Thence [from the Bridge] you as rive at a distance of five days' journey at a defile through which the Jailam runs

"The gorge through which the Jailam flows below Bārāmula, is, according to Drew, (Jummoo, p. 205) about 84 miles distant from Muza ffarābād where the bridge must have been and this accords fairly well with Alberūni's five days or marches (Stein, l c 25) The 'Harmakut' mountain (19) is Haramukha, which is 17,000 feet above sea level. It dominates the view towards the north from a great part of the Kashmir valley. The name 'Haramukuta' means 'Hara's, i e 'Shiva's diadem' and refers to the belief that it is the god's favourite residence (Ibid) Haramukh is shown in Constable A c 23

I. 64, l 4 At the end of the defile lies Dawarul-Marsad

Recte, 'the Watch Station, Dvār' (S I 207) 'Marsad' is not a part of the toponym, but an Arabic word signifying 'Place of observation,' watch-station,' hence 'custom house' and also 'observatory' Alberuni is "referring to the Watch-station at the Kashmir end of the gorge of Bārāmula, the position of which is marked to this day by the site of the old Gate known as Drang" (Stein, l c 25) "These Dvāras served, at the same time, the purposes of defence, customs and police administration, and were garrisoned by troops under special commanders They were known as Rāhdāri in Mughal times." (Ibid 68-9).

I. 64, 1.7. The city of Kashmir is four parasangs from Adashtan.

What Alberuni really says is that "the city of Kashmir, covers a space of four farsakhs" (S. I. 207). 'Adashtān' [Adhishṭhāna], was the 'city [i.e. capital] of Kashmir' itself. Sir A. Stein remarks that the statement is fairly correct, if it is understood to mean that the city and the suburban area was four farsakhs, about nineteen miles in circumference. He reckons Alberuni's farsakh as equal to 4^{77}_{50} miles (l. c. 24 note). According to the I. G., the modern city of Srinagar has a length of 3 miles and a breadth of $1\frac{3}{4}$ miles and had houses on either bank of the Jhelum even in 1050 A. C. (XXIII. 99).

I. 64, l. 9. The source of the Jailam is in the mountains of Harmakut, near the source of the Ganges.

This is of course wrong. Alberuni is only repeating the popular Kashmirian belief which places the source of the Kashmir river Sind, the most important tributary of the Jailam, in the sacred Gangā lake and identifies it with the Ganges, as the Jailam itself is identified with the Jumna. The Sind is generally known as the 'Uttaragangā.' Its confluence with the Jailam is spoken of as a *Prayāga* and is a place of pilgrimage (Stein, *l. c.* 26).

I. 65, 1. 2. The country of the Bhûtawart Turks.

These people must be *Bhauṭṭas*, "the Tibetan inhabitants of the Indus region towards the north-east and east of Kāshmīr, the people of Tibetan descent in the modern Drās, Ladākh and the adjacent mountain district." (Stein, *l.* c. 92-3, and 125). The mention of Gilgit, Astor and Chilās in the same connection (on p. 46 ante) indicates that the people of the Dard country are also included. (*Ib.* 26).

Mr. Crooke explains that the proper name of the tract of Chinese territory which we call Tibet is Bodyul [Bod = land] and that of the people Bodpas, corrupted by the Indians into Bhotiyas,—a name now applied to the Tibetans living on the borders between India and Tibet. (T. C. III. 6).

I. 65, l. 8. It [the mountain Larjal] can always be seen from the boundaries of Kashmir and Lohawar.

S. and R. read 'Kulārjak' instead of 'Lārjal,' and 'Takeshar' instead of 'Kashmīr' (S. I. 208). Their reading of the second name must be correct, as it is said, in Dowson's own translation, that the mountain of Kalārchal "can be seen from Tākas and Lahāwar" (46 ante).

Cunningham was sure that 'Kalārchal' or Kulārjak' was the great Dayamur or Nangā Parbat to the west of Kash nīr, which he remembered to have seen repeatedly from Rīmnagar on the Chenīb, a distance of 200 miles. 'Nangā Parbat', Bare Mountain, had, he urged, the same meaning as 'Karāchal,' 'Black Mountain' as 'Barcness' meant 'Blackness,' from want of snow. (A. G. I. 151 and note). But Dr. Stein thinks Kulārjak' must be the Taṭakūṭi peak which he has seen from the "Mināras of Lāhore on very clear days and is visible also from Siālkot

and Gujrānwāla, the Takkadesha or Takeshar of Alberuni. This peak rises to a height of 15,500 feet and is the central part of the Pir Panjāl range and the loftiest and most conspicuous point of the mountain range to the south of Kashmīr." Lat. 33°-45′ N., Long 74°-38′ E. (Loc cit 27 and 79). May not the true reading be, not Kulārjak, but Kulājal, ie Kulāchal, 'a great or principal mountain'?

I. 65, l. 9. The fort of Rāzgīri is to the south of it [Lārjal] and Lahūr, than which there is no stronger fort, is to the west

This Rajgiri should not be confounded with the modern Rajauri Its position cannot be definitely fixed and all that can be said about it is that it was somewhere in the upper Suran valley.

Lahūr or Lohar is the present Loharin. Lat 38°-48′ N Long 74-°23′ E The entrance to the valley of Loharin lies almost due west of Tatakūti, (Stein, l. c. 27-8 and his article on the 'Castle of Lohar' in Ind Ant. 1897, p. 225). Rājāwari (l. II) where merchants carried on much traffic and which was three f distant is the Rājauri of our maps. Constable 25 A a. Lat 38°-19′ N. 74°-21′ E. (Th)

I. 65, last line. From Debal to Tülishar is fifty parasangs, to Loharăni twelve

General Haig cites this as an "instance of the confusion made by copyists in transcribing the names of places, on account of the resemblance which several characters of the Samitic alphabet bear to one another''. He has no doubt that Tulishar is a blunder for رَوْسِيْر. Koteshar in Kachh (Cutch) Koteshwar is a place of great antiquity and is mentioned by Hiuen Tsiang who speaks of it as bordering on the ocean, and containing a great temple "where the Pashupata heretics dwell" (Tr. Beal II 276) It lies about 20 miles south-west of Lakhpat and about one mile from Nārāyansar or Nārāyan Sarovar, q v Constable. 26 B. d. The name Koteshvar signifies "ten million deities" and is an epithet of Mahadeva, and the town even now contains a shrine visited by the devotees of the god from distant parts. (I D C. 36-7 notes) The difficulty is that Kotesar is, at most, only 125 miles from Debal, not 50 f or 240 miles as Tulishar is said to be J Burnes says that previous to 1762, the Puran or Eastern branch of the Indus emptied itself into the sea by passing Lakhpat and Kotasir (Account of Sind, 21 See also Raverty, Mihran, 459 Note).

If Tülishar is Kotesar, Loharani may be the Khorai [Kori] or some eastern mouth of the Indus, as it is placed at 12 farsakhs [60 miles] further towards the east from Kotesar According to the B G. (V 229), "Kotesar lies near the mouth of the Khori river and is almost entirely cut off from the mainland by tidal creeks". This was the Eastern mouth of the great river and it was in old times of as much importance as the Western mouth. The main stream of the river is believed, by many high authorities, to have turned to the west only at some time in the eleventh or twelfth century.

Daibal [near Tatta] is in Lat. 24°-30′ N.; Long 67°-45′ E. Kotesar is, approximately in Lat. 23°-40′ N. Long. 68°-40′ E., which works out as a map-distance of about 100 miles only, not 250.

It should be noted that this Lohrāni, which was 62 f. from Debal, must have been different from the place of the same name, which is said to have been 30 f. from Mansūra at 61 ante. The latter may have been meant for Latry Bunder. The Map-distance between Brahmanābād and Larry Bunder is about 130 miles.

I. 66, l. 1. To Kach, the country producing yum, and bardrud (river Bhader), six f.

This has been muddled by the Persian translator. S.'s rendering is: "To Kach where the muql tree grows and Bāroi [432], six farsakhs". (I. 208. See Dowson's note, in which it is said that Reinaud's MS also reads [402] 'Baroua' as the name of a place. (R. Tr. 120 n.) The muql tree is the Balsamodendron muql, which yields bdellium—a fragrant gum resin. It is the Gugala of the Hindu pharmacopæia. The parenthetical gloss after 'bārdrūd' is misleading. 'Bārdrud' or Bādrū means Balm or Bezoar. The Bhīdar is a river of Kāthiāwāḍ which falls into the sea near Porbandar. It has nothing whatever to do with Kachh and is more than a hundred miles distant.

Sachau also understands Bāroi as the name of a place but his identification of it with Baroda is inadmissible. I venture to suggest that it is the vernacular form of Dvārā-vati, i.e., Dwārkā. The Sanskrit Dva becomes 'ba' in Gujarāti, e.g. Dvāra becomes 'Bār', Dvija 'Bija'. Elsewhere. Alberūni writes that the linga of Somanāth was originally erected on the coast—least of the golden fortress of Bāroi, which had appeared as a dwelling-place for Vasudeva. ... The fact that this just mentioned fortress [Bāroi] should have appeared out of the ocean is not astonishing for that particular part of the ocean at all." (S. II. 105-6). Now this is just what is said of Dwārkā in the Purāṇas and the mythological writings of the Hindus. It is "believed to have been raised in one night by supernatural agency." (I. G. XI. 387: B. G. VIII.

The distance from Baka to Kachh and Bāroi also seems wrong and should be perhaps read as six days, not farsakhs. There is, probably, some corruption or lacuna in the text

I. 68, l 1. Beyond them the country of Malibar, which from the boundary of Karoha to Kūlam is 300 parasangs in length.

The people are all Sāmānis (Buddhists) and worship idols.

As there were no Buddhists anywhere in Malabar, or for the matter of that, anywhere in Southern India, at the time when Rashīdu-d-dīn wrote, Sāmāni must stand here, as elsewhere, for the Jamas infra also, where Dowson makes Idrisi say that in the twelfth century, the people of Kambaya were Buddhists, we must take Samani. the word used in the original, to signify the Jamas or followers of Mahavīra, not of Buddha During the seventh and eighth centuries. Buddhism was, "slowly declining and suffering gradual supersession by its rivals, Jainism and Brahmanical Hinduism" (V. Smith, E. H. I 386) Jamsm was "specially popular in the Southern Mahratta country." (Ib "Buddhism finally disappeared from the Dekkan in the twelfth century" (Ib 387) During the reign of Vishnu or Bittiga of the Hoysala dynasty, the Jam religion enjoyed high favour under the protection of his minister, Gangaraja (Ib 392) Lassen also tells us that, on the Malabar coast, the Kings of Tuluva, the chief of whom ruled al Ikkeri ... greatly loved the doctrines of the Jainas (Indische Alterthums-Tr Rehatsek in Ind Ant II 263-5) kunde, IV 771 ff

Karoha was identified by Yule with Gheria or Vijyadrug (ED VIII App p xl), while others have supposed it to be Goa [••••]. In either case, the length of coast is greatly overestimated. The distance is only about 7½ degrees of latitude, approximately 550 miles

I. 69, l 4 from foot. 1,0000 horses from all the islands of Fars, such as Katīf, Lahsa, Bahrein, Hurmuz, Kilahāt etc.

Katīf lies at about twenty miles distance from Bahrein It was the principal port of Al-Hasā" (Dames, Barbosa I 77 Note) Tavernier says that Katīf was noted for its pearl fishery and was situated opposite to Bahrein on the coast of Arabia Felix (Yemen) (Travels, Tr Ball II 108) Lahsa or Al-Hasā is on the eastern coast of Arabia and south of Basra Lat 27° N, Long 49° E

I. 72, l 2 from foot. Beyond that is the country of Ratbān, then Arman, then Zardandān · afterwards comes the country of Rāhān, the people of which eat carrion and the flesh of men

'Ratban' looks like 'Martaban', with the initial (dropped. 'Arman' is probably Mramyan, the old name of Burma The variant 'Aman' must be another form of the same name, as Burma is called 'Amien' or 'Mien' by Marco Polo (Travels, Tr Yule II 109-110) But 'Arman' may be meant for 'Araman', which was the name given to the capital founded on the site of modern Rangoon by Punnarika who reigned from

740 to 761 A.C. (I.G. XXI. 214). The geographical expression Zardandān has not been satisfactory elucidated. Marco Polo writes that the people of the country of Zardandān, "have their teeth gilt; or rather every man covers his teeth with a sort of golden case made to fit them, both the upper teeth and the under. The men do this, but not the women." (Travels, Book II. Ch. 50; Tr. Yule. II. 84). "The country meant," Yule notes, "seems to be Western Yunnān, but I can learn nothing of the continued existence of the custom among any tribe of the Indo-Chinese continent, though the practice of casing the teeth in gold is followed by some of the people of Sumātrā, as Marsden and Rafiles have shown." (1b. 88-90).

Rāḥān, "of which the people ate carrion", must be Mrohaung—the ancient capital of Arākān or Rākhang, as it was called by old Muslim authors. Jahāngir says of the Mugs of Arākān that "they cat everything there is, either on land or in the sea, and nothing is forbidden by their religion." (T.J. 115, l. 19; Tr. I. 236). Rashīdu-d-dīn probably wrote Claic Rākhān. The modern form Ārākān is said to be derived from the Arabic 'Al-Rākhang.' Rashīd seems to have made some mistake in regard to the relative situation of Rathān and Rāḥān.

I. 74. The Nuchatu-l-Mushtak of Idrisi.

Idrisi was born at Ceuta in 1099 A. C. and died about 1160 A. C. He tells us that he finished the Nuzhat al Mushtāq during the last days of Shawwāl 548, 1154 A. C. (Jaubert. I. xxii). Elliot asserts that "the court of the Anhilvād king, Siddh Rāj Jaysinha, was visited by Idrīsi who distinctly states that at the time of his visit, the chief adhered to the tenets of Buddha." (Races of the North-Western Provinces. Ed. Beames. I. 50), and this statement is repeated in the Cambridge History of India. (III. 517). But no authority for it is cited by either of these writers, and it appears to be founded on error. Moreover, Siddharāj was not a Buddhist, but a devout worshipper of Mahādeva.

Idrīsi's "account of south-eastern Asia, including India" is, in the opinion of Yule, "very meagre and confused". Another defect, according to that acute critic, is that "professing to give the distances between places, he underrates them enormously, in so much that a map of Asia compiled from his distances would assume very contracted proportions." (Cathay, Ed. Cordier, I. 141). Elsewhere also, Yule writes that "Edrīsi's information about south-eastern India is a hopeless chaos." (Ibid. I. 242 note). These animadversions are not unjust, but the real offender is Khurdādbih, from whom Idrīsi has copied his account. (Cf. 15-6 ante). Idrīsi aspired to compose a cyclopaedic treatise which was to embrace the entire geographical knowledge of his day. His ambition was to leave out nothing that he had read in the fifty and odd books which he cites, but in thus endeavouring to incorporate everything and pretermit nothing, he has frequently involved himself in contradiction and confusion. He has been frequently misled also by the apparent similarity or identity

of place-names transcribed in the treacherous Semitic script. Moreover, the continuous plagiarism which is a characteristic feature of all the Arab geographers, has led him to lift from writers of the 9th and 10th centuries statements which were true of their own times, but had become obsolete in his own, and their combination with items of more recent knowledge, has produced a composite picture which is often giotesque. Unfortunately, his errors have often misled European authors who, taking it for granted that whatever he states must be correct, have undertaken the impossible task of harmonizing and reconciling his conflicting assertions with those of others

Idrisi's work with its seventy-one maps may, taken as a whole, be "the most important geographical work of the middle ages" as Seyhold says, (Houtsma E I III 451), but it is also true that "the older writers on whom he draws so largely, are often wrongly interpreted, (a striking example is in J. Marquart, Éranshahr, p 261). His information, even when correct and accurate, is often used in an uncritical way and we learn more and more to use his work with much circumspection" (J H Kramers in Houtsma, E I Supplement B, 57). Indeed, it is not safe to accept any of his statements without tracing it to and comparing it with the source from which it is derived. The original text also has never been critically edited and Jaubert's version, which Dowson has implicitly relied upon, is replete with error.

I. 75, last line. After him [the Balharā] comes Makamkam whose country is Saj

Sulaiman had said that ' the kingdom of the Balhara commenced at the seaside, at the country of Komkam" and Masû'di stated that the country of the Balhara was called Kamkar (pp 4 and 25 ante), that is, Konkan or Kannakara [Kanara or Karnataka] Khurdadbih also had spoken of it as Kamkam and added that the teak tree was found in it (Goeje 67, 1 6, Tr 47, but left out in Dowson's Tr.) This is turned here into 'Makamkam' and the name made to look like the personal designation or dynastic title of the king. There is a bare possibility of a reference to the Kadamba rulers of the Konkan, "whose kingdom at one time rivalled that of the Chalukyas" But the better and most probable opinion is that Makamkam is the name of the district and a miswriting of 'Kamkam', e Konkan 'Konkan' denotes, in modern times, a much smaller extent of country than it did in the old Hindu geography. Hamilton observes that the term is now applied to the region between the 16th and 19th degrees of Latitude, but that, according to ancient usage, it began in Lat 14°-37' and what is now called North Canara was included in its southern part (East India Gazetteer, Ed 1815, s v. Concan) In late Sanskrit works, the name is even applied "to the whole western coast of India from about Trimbak to Cape Comorin and they mention seven divisions, the names of which are variously given, but Konkan Proper [the strip of the West coast from Daman to Goal is

always one of them. (I. G. XV. 391). 'Sāj' is teak wood, for which the Canara forests are still famous.

I. 76, l. 17. This caste [the Kastariyas] may marry Brahman women, but Brahmans cannot take their women to wife.

Idrīsi is copying from Khurdādbih, but has inverted the meaning of his author, who states that "the daughters of the class of Brahmans are not given in marriage to the sons of this class, [the Kataria] but the Brahmans take their daughters (p. 16 ante).

1.77, l.6. In that part of the sea.....there are the isle of Sāra, the two rocks of Kasair and 'Awair, that of Dardūr.

Sāra is Sohar on the coast of 'Omān, which Mas'ūdi locates at fifty farasangs' distance from Masqat. (Sprenger, 262, 347). It is in Lat. 24°-10′ N. Long. 56°-58′ E. This Sohar is entirely different from 'Shihr' which is on the southern coast of Arabia (Hazramaut) and noted for its exports of horses and frankincense. (Dames, Tr. Barbosa, I. 64-63 notes). Shihr is near Makalla. Lat. 15° N., Long. 49°E.

Mas'udi states (Sprenger, 26S; Prairies, I. 240) that Kasair and 'Awair are two mountains near the island of Beni Kāwān [Kishm.]. He tells us that Durdur is known as 'Durdur-i-Musaddam' 'the terrible Durdur' and is styled by sailors, the 'Father of Hell', because in this part of the sea, rise enormous black rocks high over hanging the waterand under them the sea is very stormy; hence everybody who sails there is filled with fear. The rocks are between Sirāf and 'Omān and vessels cannot help sailing through the midst of them." This enables us to identify Dardur, which is mentioned also by Sulaiman (Old Eng. Tr. 8) and Khurdadbih (J. A. 1865, pp. 60, 282; Goeje's Ed. Text. 60. l. Tr. 41) as the Cape Mussendom of modern geographers. It is the extreme eastern point of Arabia at the entrance of the Persian Gulf, Lat. 26° N., Long. 56° E. Lord Curzon thus describes the stormy cliffs of Cape Musandim. "At the end of a long and rugged promontory, whose black basaltic cliffs rise sheer from the water's edgeto 6750 feet, an isolated needle of rock is severed from the mainland by a gloomy channel only a few stones' throw in width, winding between walls of basalt 800 feet high. This island is Ras or Cape Musandim.....Arab and Hindu sailors still offer sacrifice to the rock and present thank offerings to it on their safe return." (Persia, II. 446-447).

I. 77, l. 15. Debal is a populous place but its soil is not fertile.....; the highlands are arid and the plains sterile.

Ibn Hauqal also states that it is a sterile place on account of the lack of artificial irrigation. (37 ante, Note). "Lower Sind is almost entirely barren in parts, with nothing but huge stretches of baked mud, broken here and there by shapeless mounds. Even in Upper Sind, vast areas remain untilled because no water can get at them; others are merely scratched, owing to the brief irrigation period. The inundation lasts only for a few weeks". We learn from the I. G. also that "with the

exception of an alluvial strip of great fertility, bordering either bank of the Indus in Sindh for about twelve miles, the province is sterile." (XXII. 896). It is now common knowledge that nearly two-thirds of the cultivable area was lying waste for lack of water before the construction of the Sukkur Barrage, which is expected to irrigate more than five million acres of hitherto untilled soil

I 78, 1 3. Nirūn is half way between Debal and Mansūra and people going from one town to the other cross the river here.

Idrīsi is copying here from Ibn Hauqal, but as is not unusual with him, copying inaccurately What the earlier author really states is that "Nirūn is between Debal and Mansūra but rather nearer to the latter. Manjābāri is to the west of the Mihrān and there [i e at Manjābāri, not at Nīrūn], any one who proceeds from Debal to Mansūra will have to pass the river, as the latter place, [Mansūra] is opposite to Manjābāri" (37 ante). In other words, the crossing was at Manjābāri not at Nīrūn. See also my note on l. 2, p 40 ante Haig remarks that the Mihrān did not run close to Nīrūn at all at this time. (I D. C. 53)

1.78, l 11 from foot Al-Masisa on the Mediter ranean

This is the ancient Mopsuestia (Jaubert, Tr. Idrīsi, II 129, 133 note) Mas'ūdi mentiona Masīsa along with Tarsus, Antioch, Latākia, Tripoli etc. in a list of towns washed by the Mediterranean (Sprenger, 28, 1, 289, 300=Prairies, I. 256, 264, 276, see also Aîn, Tr Jarrett, III 78 and note) Mopsuestia was an important city of Cilicia Campestris on the river Pyramus and lay about twelve miles from its mouth on the road from Taisus to Issus. It is now called Messis (W. Smith, Classical Dictionary, 8 v), Lat. 36°-55′ N Long 35°-42′ E. (See also Houtsma E I III 521-527 s. v Messis).

1 79, 1 15 ff Near it [Kalri] the Mihran sepai ates into two branches. Kalii, where the Mihran separated into two branches at about two days' distance from Mansura is located by Raverty at "some miles above the low-lying tract near Jakrão, because Jakrão is just twenty seven miles above Mansura" (Mihran, 457 note) Haig remarks that "there is much in Idrisi's description which is absurd, "as the Indus is represented as running from south to north There is a place called Kalri about 30 miles north-west of Mangura and ten miles north-east of Sakrand, but it does not suit the other directions. No place could have been three days' journey from Sehwan and also one day's hard journey of 40 miles from Mansúra, as Idrisi says it was He has confused the distance between Schwan and Kalri with that between Schwan and Manhabari or some other place" All that can be said is that Kalri was somewhere in this part of the country. But Haig thinks it must have been east of the Mihran, not west of it, as Ibn Haugal and Idrisi put it (I D C 69-70).

I 80, l 2. In going from Debal to Firabuz, the road passes by Mankabari and between these two places, it runs through

Khūr, a small but populous town.

This Firabuz must be 'Qirbuz, Qizbur or Qanzbur' [Panjgur]. Holdich believes Khur to be now represented by Khair, a village near the Malir water works of Karachi. There is a fine group of Arab tombs there in a good state of preservation. (G. I. 310).

The mountain of salt near Dirak (l. 2 ff) is "the Bampusht Koh, which is the highest mountain in Makrān, and there is enough salt in the neighbourhood to justify the geographer's description." (G. I. 313).

I. 81, l. 6. A considerable trade is carried on in a sweetmeat called faniz, which is made here.

It was not a 'sweetmeat' but a species of white loaf-sugar, according to Le Strange. "The chief product of Makrān," he writes, "was the sugar cane and the particular kind of white sugar, known to Arabs as al Fānīdh (from the Persian Pānīd), made here was largely exported to neighbouring lands." (L. E. C. 329). Idrīsi has borrowed this statement from Iṣṭakhri. (Ed. Goeje. 177, l. 15). Richardson (Dictionary, s. v.) also says implements 'sugar' and Vullers explains that when the boiled sap is refined by reboiling and thrown into moulds shaped like a pine-apple, it is called Fānīd. The pine-apple shape was, in fact, the origin of our sugar-loaf. (Lexicon Persico-Latinum, s. v. See also Houtsma. E. I. IV. 509. s. v. Suķķur). Etymologically, the wor'd is connected, by Vullers, with the Sanskrit Phānīta, sugar.

Kasrān (l. 8) must be an error for 'Quṣdār,' which is the reading in Goeje (177, ll. 15-16). Māskān where "the cultivation of sugar was extensively pursued must be Mashkel, which is even now the best date-growing district in Southern Balūchistan and produces dates of such excellent quality that they compare favourably with the best products of the Euphrates." (G. I. 314).

I. 81, l. 12 from foot. Tūbarān is near Fahraj which belongs to Kirmān.

Holdich points out that Idrīsi has confounded Tūrān and Tūbarān in this paragraph. Tūrān was the district of which Quzdār was the capital. Tūbarān is said by him to have been near Fahraj, [Pahara which is 20 miles north of Regān and a few miles east of Narmāsīr], in Kermān. (L. E. C. 318, 330 note). Idrīsi makes the distance between Tūbarān and Multān and Tūbarān and Mansūra, ten and fifteen days respectively. This may well be true of Tūran [modern Jhalawān], but it is impossible to predicate the same of Tūbarān in Kermān. (G. I. 315.). Idrīsi has borrowed the name Fahraj from Khurdādbih, who says it is a city of Kermān. Narmāshīr, the latter writes, is 7 farsakhs south of Bamm. Fahraj, is 7 [or 4] farsakhs from Narmāshīr, (Goeje, Text. 49, l. 10; 54, l. 1, = Tr. 34, 36). Taberān or Tābarān is 10 farsakhs from Fahraj and Basourjān or Masourjān [Regān of our maps?] 14 from Tabarān [Tābārān or Taīrān]. Ibid, 55, l. 1. Tr. 37. This Bamm is in Kermān in Lat. 29°-4′ N., Long. 58° 20′ E. Regān is in Lat. 28°-40′N; Long. 58°-58′E.

The Fardan which was to the east of Kirkayan, four days' distance from Tubaran, has not been satisfactorily identified. It may be another perversion of Quzdar, which was, like Kirkayan, in Turan (34 ante), and the conjecture receives support from the fact that Quzdar is not mentioned under its proper name by Idrisi anywhere in his description of Hind and Sind

I 82, l 12 It [the idol of Multan] is, as we have said, square and its arms below the elbows, seem to be four in number.

This is again founded upon some misunderstanding of the original authorities who say nothing about the idol having more than the natural number of arms. What they state is that it was 'sitting cross-legged' (28 and 36 note ante) The error may be due to this word having been misunderstood by Idrisi or by his French translator Reinaud complains that the version of Jaubert is full of errors (Tr Abul Feda I exxi See also Houtsma, E I II 451). Dowson's rendering was made at secondhand from the French متن منت منت منت منت المعادية والمعادية المعادية الم

I 82, l 2 from foot It bears the name of "the House of Gold Farkh" Farkh and Bahar have the same signification

'House of Gold Farkh' is meaningless Idrīsi's copies of the Masālīh of Istākhri and Ibn Haugal must have been very faulty and the whole statement is misleading. Here, having committed one error by reading Instead of Istakhri and Idrīsi Idrīsi or instead of Istakhri and Ibn Haugal must have been very faulty and the whole statement is misleading. Here, having committed one error by reading Instead of Istakhri Idrīsi installation of the Sanskrit Bhār. In Alabic means 'an idoltemple, a place of infidels' worship' Now the Sanskrit 'Vihāra', a Buddhist monasteiy, college or shrine, assumes in Arabic the form Istahhār', e.g. in Nau-bihār Khuidādbih had said that 'Bhār' was a Hindu weight equal to 333 mans of two ratls each and that Muhammadiqāsim [not Muhammad bin Yusūf, as Idrīsi styles the conqueror of Sind], had found forty such Bhārs of gold in the temple of Multān Idrīsi jumbles up the meanings of two entirely distinct Sanskrit words, Vihār and Bhār, and makes utter confusion in the process

Biladuri also reads of and explains that there was an aperture above the chamber through which the gold was poured (123 post)

I 83, l. 11 Sandur is situated three days' journey south of Multan

It is situated on the banks of a river which falls
into the Mihran above Samand

This is all copied wrongly or carelessly from Istakhri and Ibn Hauqal and the statements of the two writers are so travestied and mixed up as to become incomprehensible

The river Sandūr is Istakhri's Sind-rūd and Ibn Hauqal's Sandarūz, which was about three days distant from Multān and whose confluence with the Mihrān was above Basmad It was a river only and it is not stated anywhere that it had a town on its banks (30 and 40 ante) Then

Ibn Haugal adds that Jandruz was another river, on whose banks lay the city of Jandaruz. (40 ante).

Idrīsi has confused the two names. His town, Sandūr is Ibn Ḥauqal's city of Jandarūz on the river Jandarūz. His river Sandūr is Istakhri's Sind-rūd and Ibn Ḥauqal's Sandarūz. (30, 40 ante).

I. 84, l. 12. Masūrjān is a town built upon the banks of the river of Tūbarān.

"Masūrjān of Idrīsi is perhaps Regān in the Narmāshīr province of Kirmān and Darak Yāmūna may be Yakmina. Regān is about forty miles from Fahraj in Kirmān." (G. I. 317). Khurdādbih locates Darak Bāmūya at 48 f. [144 miles] from Basourjān (Goeje, 55, 1. 5. Tr. 37). Regān is in Lat. 28°-40′ N.; Long. 58°-58′ E. a little south of Narmāshīr. Yakmina is shown in the London Times Atlas. Lat. 28° N. Long. 61° E.

When Idrīsi enumerates, a few lines higher up (l. 7), the dependencies of Tūbarān, he is again making confusion. Kīr Kāyān, Sūra [Surab in Kelāt State], and Fardān (Quzdār) were in Tūrān, i.e. modern Jhalawān in Baluchistān, but Kashrān (?) and Masūrjān [Regān] belonged to Tūbarān or Tābarān in Kirmān. He has taken the first three names from Istakhri (34 ante), and lifted the other two from Khurdādbih, (q. v. my note on p. 81, l. 12 f.f. ante).

A few lines lower down (21-2), Māmhal and Nahrwāra are both mentioned as two distinct towns. Idrīsi has copied the first of these from Iṣṭakhri and the second from some other author, without being aware that they are identical. He is also wrong in transferring the title Balharā to the Chālukyas of Anhilwād.

I. 84, last line. There is [at Kambāya] a fine fortress erected by the government of India to prevent the inroads of the inhabitants of the island of Kish.

The island of Kīsh lies in Lat. 26°-30′ N. Long. 54°-0 E. about seventy miles south of Sirāf, which it supplanted in the 12th century. In the 14th, Hormuz rose on the ruins of Kīsh and then Hormuz had its turn and its place was taken by Bandar 'Abbās in the 17th. "Kīsh is also called Ghes or Kenn, and is singular among the islands of the Persian Gulf in being well-wooded and well-supplied with water. It is about ten miles long and five broad and is better cultivated than most of the islands of the Persian Gulf.

But it seems to me more than doubtful if there is any reference here to this Kish. The place really meant is, most probably, Kachh—the inhabitants of which have enjoyed an unenviable notoriety for naval brigandage and robbery on the seas from very ancient times down to our own. "The chief references to Cutch in the writings of the Arab travellers of the 10th and 11th centuries are connected with its pirates, who were known as Bavārij." [Vide Alberūni, 65 ante]. Bilāduri also speaks of the Meds of Surast as pirates [123-4 infra]. In the 13th century, they are mentioned by Marco Polo who says that they 'landed and en-

camped at Socotra, and sold their spoil there to the Christians who bought it gladly, knowing that it was pagan gear.' (B. G Cutch, V. 131 and Note)

1 85, 1 3. Its [Kambāya's] mountains produce the Indian Kanā.

but فالأبدي seems to be used here as the specific designation of the bamboo' The Italian traveller, Pietro della Valle, was struck by and notes the fact that boats in India were not rowed with oars, but guided by two men, with poles of "Indian canes, or Bambu". (Travels, Ed Grey, II 841) Elsewhere, he informs us that he saw Indian reeds of excessive height called by the country people, Bambu, growing very thick along the banks of the river of Gersoppa. (Ibid, 220). The bamboo is here called the liver of Gersoppa. (Ibid, 220). The bamboo is here called and the liver of Gersoppa. (Ibid, 220). The bamboo is here called and the liver of Gersoppa. (Ibid, 220). The bamboo is here called and liver the betch nut عبر البندي 'Indian nut' and Malabathrum [Tamāl-patra] عالم المنافعة الم

Pliny also speaks of bamboos specifically as Indian reeds. They attain, he states, "the thickness of a tree and are said by the Indians to be male and female, the body of the male being more compact, that of the female, of greater amplitude. A single section, moreover, between two joints, is large enough, if we take their word for it, to make a cance," (Lib. XVI Cap 34 (62), Tr. in McCrindle, Ancient India in Classical Writers 126)

I. 85, l. 4 The inhabitants [of Kambaya] are idolators (Buddhists)

The word used in the original, 'Sāmāni,' means 'idolators' and also 'Buddhists,' but there were no Buddhists in India and certainly not in Cambay, in the 12th Christian century Idrīsi must mean the 'Jainas' or Shrāvaks, who have always been strongly represented in Cambay, and still constitute an influential section of its population See my Note on I. 68 1 1 ante and E. D. II. 163, 1 4 post

I. 85, ll 11, 20 From Subāra to Sindān is considered five days Saimūi, five days from Sindān is a large, well-built town

The two statements are inconsistent and will not hold together. Subāra [Sopārā near Bassein] is about 37 miles, and Sindān [Sanjān near Damaun], 88 miles north of Bombay, while Saimūr [Chaul or Chewal] is 23 south of Bombay The actual distance between Sopārā and Sanjān is about 51 miles, that between Saimūr and Sanjān more than 110 miles. Both could not have been covered in the same number of days. Alberūni states that Sūbārā was six farsakhs, not five days, from Sindān (66 ante and S I 209) which is less wide of the mark

I. 85, l 13 from foot. The pepper vine grows in this island, [Māli near Kūlam Māli] as in Kandai īna and Jīrbatan, but it is found nowhere else but in these three places

This is hardly correct, as the pepper plant is indigenous to the whole of the Malabar coast and is also cultivated in Malaya, the

Philippines and even in the West Indies. Idrīsi is also wrong in asserting that "white pepper is what is gathered as it begins to ripen, or even before" (l. 8 f. f.). It is really the seed freed from the skin and fleshy part of the fruit, by soaking in water and rubbing the dried fruit." (Chambers, Twentieth Century Dictionary). It is, in fact, the dried fruit decorticated.

I. 86, l. 12 from foot. The ruler of Ghāna is called Ghāna, the king of Kaugha is called Kaugha.

Ghāna was a town in the West Sudān lying on the Niger near Walata or Timbuctoo (Cooley, Negroland, 14; Reinaud, Abul Feda, III. 1. 21). It is said to have possessed gold mines and to have exported gold dust. (Āīn. Tr. Jarrett, III. 47 note). Mr. Gibb assures us that the place was so called after Ghāna—the title of its Soninke rulers. (Ibu Baṭūṭa, Notes, 378). It was the southern terminus of the trans-Sahārān route in the 12th century (Ibid). Lat. 18°-0'N, Long. 7°-8' E. (Houtsma, E. I. II. 139). Kaugha, also written Kūkū or Gogo, was to the east of Ghāna and west of Kānem, in Central Sudān. Ibn Baṭūṭa speaks of 'Gaogao' as a large city on the Niger, which he reached after arriving at Timbuctoo. It was an important trading station at the convergence of the salt route from the west, the trans-Sahārā route from the north-east, and of the Transcontinental route. (See also Yule, Cathay. Ed. Cordier. IV. 40 note). Gogo in Sudān is shown in the Times Atlas. Pl. 108, E. 5. It is in Lat. 16°-12' N. Long. 42°-55' E. (Houtsma, E. I. II. 172).

I. 86, l. 10 from foot. Among the towns of India,.....are Khābīrūn and Asāwal.

I do not know of any one having attempted to identify 'Khābīrūn.' I suggest that it should be pronounced 'Khabīrwan' and that Kapadvanj is the place referred to. Kapadvanj is a town of considerable antiquity and Siddharāj Jaisinha (R. 1094-1143 A. C) is said to have built a kund or reservoir there. (B. G. I. Pt. i. 180 note). If is mentioned in a Rāshṭra-kūṭa copper-plate grant dated 909 A.C. as 'Kārpaṭavanijya' and the district around it upto Kaira [Kheda] is known to have been included in the dominions of Krishna II. (Fleet in B. G. I. Pt. i. 383. 413; Duff. C. I. 81. 84). It derives its importance from lying on one of the main trade routes between Central India and the coast. (I. G. XIV. 406). Forbes (Rās Mālā), has described one of its old Hindu monuments, a beautiful arch. An underground temple of Mahādeva also has been recently found and explored (I. G. XIV. 278).

I. 87, l. 19. Between Barūh [Broach] and Nahrwāra, there are two towns, one called Hanāwal or Janāwal, the other Dūlakā.

By the addition only of one or two diacritical points to the first letter, 'Hanāwal' can be read as Janāwal or Chanāwal. The old name of the district round about the town of Viramgām was Chunwāl. A pargana of that name still exists in the Viramgām taluka and there is a branch office at a village called Chunwāl-Dāngarwa. (Rās Mālā. II. 95, "

notes) Idrīsi is not quite correct in stating that Dholkā stands on a river I 88, l 19 When a man has a right to demand anything of another and meets him, he has to draw a circle round him etc

This is perhaps the oldest description in a foreign writer, of the old Hindu custom of 'Sitting Dharna' 'Marco Polo also mentions it and states that it was carried out against the King of Malabar (Travels, Tr. Yule, 2nd Ed II 327, 335) Another early reference may be found in Varthema (Badger's Trans 147-8) Ibn Batūta also gives an account of a slightly different form of the same usage (De Frémery III 412) Qazvīni has copied the passage from Idrīsi (Āsāru-l-Bilād in Gildemeiter, Text. 55. Tr 197)

I 88, l 5 from foot When the King of India dies they construct a vehicle etc

Here again, Idrīsi jumbles up things and carelessly ascribed to the kings of India a practice which Sulaiman and Mas'udi had specifically attributed to the rulers of Ceylon only

I 89, l 16 from foot. From Sindan to Balbak is also two days

It is here that vessels change their course for the different islands of India. From hence [Balbak] to the Great Abyss, they reckon two days From the island of Balbak to that of Sarandib is one day or more

In other words, Idrīsi would have us believe that Sarandīb [Ceylon] was only three days' distance from Sindān [Sanjān], which lies about ninety miles north of Bombay Istakhrī and Ibn Hauqal had put it at twenty days (30, 39) Idrīsi is copying from Khurdādbih But what Khurdādbih really says is that "Bās where you can take passage to Sarandib, is two days from the 'Great Sea' [Gulf of Manaar], which is two days from Balbun, which is two days from Māli, which is five days from Sindān" In other words, Bās, the port for Sarandib was eleven days' journey from Sindān according to Khurdādbih (p 15 ante)

The 'Great Abyss' is the , 'Great Sea, gulf or deep' of Khurdādbih and the , 'Great Gulf' of Alberūni It must be the Gulf of Manaar which "abounds in dangerous shoals and rocks at the northern extremity and is exposed to the fury of the monsoons, being quite open towards the South-west and only partially protected by the Ceylon coast on the South-east." (I. G XVII. 108) Idrīsi's 'Balbak' is the 'Balbun' of Khurdādbih who says that the route divides at that place (15 ante), or as Idrīsi puts it, "vessels change their courses here" Rashidud-din makes a similar statement about Kābal, ie Kāyal (72 ante), and 'Abdu-r-razzāq tells us that Kāil lies opposite to Sarandib (E. D IV. 103) Balbak [Balbun] is, probably, meant for Kāyal.

I 89, l 11 from foot From the town of Barūh, to Sindābūr four days From thence to Bāna [Tānnā] upon the coast, four days

As Broach lies about two hundred miles north of Bombay, Idrīsi would seem to have mixed up Sīndābūr, which was somewhere in Canara, with Sindān [Sanjān,] 50 miles north of Thāna and 88 miles north of Bombay. Sindābūr, whether it was near Goa, Ankola or Kārwār must have been at least 250 miles south of Bombay, i. e. 450 south of Broach. Yule (H. J. 838) and Dames (Barbosa. II. 171. n) have both drawn attention to the error. Yule remarks that Abul Fedā also has jumbled up Sindān and Sindābūr in his Tables. (Gildemeister, 46. 188).

I. 89, l. 3 from foot. The Tabashir is adulterated by mixing it with ivory cinders.

The tabāshīr is "a siliceous substance sometimes found in the joints of the Bamboo. It is the Sanskrit Tavakshīra or Vānsrochana, Hindi Bānslochan, or Bānskapur. It is also called Sākar bāmbū or Bāmboomanna." It is said in Hindu medicine to have numerous curative properties, but chemical analysis shows that "it is a saccharose related to, if not identical with, cane-sugar, and that it must be really inert." (Watt, Commercial Products of India, 110-112. See also H. J. 863).

I. 89, l. 2 from foot. But the real article [I abāshīr] is extracted from the roots of the reed called Sharki.

Idrīsi's Sharki must be the reed called Sara, Sarakanda, Sarkara and also kāns or kasā. The Hindu God of War, Kārtikeya, is said in the Purāṇas to have been born in a grove of Sara, which gave notice of the event by bursting into flames. Its botanical name is Saccharum Arundinaceum. Its blades are used for thatching houses, its flowering stems (Sirki) for making baskets, screens etc., the internodal parts of its culms as writing pens, and the fibre of the culms for weaving the sacrificial thread or Maunji, (Watt, op. cit. 929-30).

But this Sara, Sarkanda or Kāns does not yield the *Tabāshīr*, which is produced, not in the *roots* of any reed or cane, but in the *joints* of the bamboo. Idrīsi would appear to have mixed up the one with the other. Yule says that 'Sirky' is a tall reed-grass, *Saccharum Sara*, from the fine cylindrical culms of which matting and chicks are made. (H. J. s. v. Sirky).

1. 90, l. 4 from foot. North of this town [Fandarina] there is a very high mountain, ... the cardamom tree grows there and forms the staple of a considerable trade.

This mountain must be Mount Delly, which is erroneously stated by some old European writers also to be the "solitary habitat of the true cardamom." They appear to have thought that the name was connected with 'Elachi', 'Ela' and 'Hil,' the Gujarāti and Marāthi words for the cardamom. (Cathay, IV. 75 note). This is evidently a folk-etymology, but modern scholars are not agreed as to the real derivation. Some have traced. 'Delly' to the old Malabār kingdom of Eli or Hili. (I. G. s. n.). Burnell had no doubt that it was the Malayālim 'Eli mala,' 'High mountain'; others have favoured Elu Mala, 'seven hills' and

fancied it was 'Eli Mala' 'Rats' Hill.' (H. J s v Delly; Dames, Barbosa, II 1 note). Whatever the true derivation may be, the statement that Mount Delly is the only place where the true cardamom grows is wrong. It is found in several other parts of Southern India

Mount Delly is 855 feet high and lies 18 miles to the north of Cānnānore It is said to be visible to sailing vessels from a distance of 25 miles (Th s n Delly)

I. 90, l 11 From Fandarina to Jirbatan is five days

Ibn Batūta states (Defremery, IV 109) that he went from Manjarūr to Hīli, from Hīli to Jurfattan, Dahfattan, and Budfattan, and thence to Fandarāina and Calicut Yule rightly remarks that in placing Jīrbatan, (which he identifies with Cānnānoie), at five days' voyage from Fandarīna, [the real distance is about 45 miles], Idrīsi has committed an error (Cathay Ed. Cordier IV. 76, 77) Gibb (op cit 234) accepts Yule's location of Jīrfattan near Cānnānoie (Tr Varthema, 132 note) See Constable 34 Bd Būdfattan or Pudupattan ('New City') must have been somewhere near Waddakere or Badagere, q v Constable Pl 34, Bd

I 91, l 17 From thence [Madiar on the Ganges] to Nahricara on the west bank of the Ganges - seven days From Madiar to the city of Malica two days

What confusion? "Nahrwāra on the west bank of the Ganges"? And yet, Sir Henry Elliot and Sir Wolseley Haig assure us that Idrīsi personally visited and stayed at the court of Siddharāj Jaysinha of Nahrwāra! (Races, I 50, C H I III 517) Idrīsi never visited India

If Madiar, which is said to be seven days from Yanāsat, [Banāras?], is Mathurā, Idrīsi has confused the Jumnā with the Ganges He does not appear to have heard of the former river

1 92, 1 4 From Kandahār to Nahrwāra is five days' journey in carriages

Here, in one and the same paragraph, three entirely different places are confounded under one name, Kandahār, viz (1) Qandahār in western Afghānistān, (2) Gāndhāra, or the lower Kābul valley, ie Peshāwar district and parts of Kohāt, Swāt, Bājaur and Buner and (3) Gandhār, a ruined town in Broach district on the left bank of the Dhādhar river, $4\frac{1}{2}$ miles from the Gulf of Cambay. It is mentioned by Ibn Batūta (Defrémery, IV 578) and also in the Aīn (Tr II 255) It was plundered and almost destroyed by the Portuguese in one of their piratical raids along the shores of the Gulf in 1546. (B. G. Vol II Sūrat, 561-2) It is this 'Gandhār' or 'Kandahār' which was five days' journey from Nahrwāra.

The 'Kandahār' whose kings could not take the title of Shāh until they had been crowned at Kābul is Gāndhāra, and the kings were the Hindu Shāhis who were compelled by the aggressive inroads of the rulers of Ghazni to remove their capital from Kābul to Waihind near Attock.

The 'Kandahār' which was "accessible by one road only" and had "a strong citadel built upon a scarped rock" must be Qandahār in Afghānistān, as its inhabitants are said to have had large and thick beards and worn the Turkish costume.

The worst feature of this muddle is that Idrīsi transfers to the 12th century, statements which were true only in the 10th. The power of the Shāhi dynasty had been totally eradicated by Mahmūd of Ghazni about 1021 A. C. and their inauguration at Kābul was, when Idrīsi wrote, only a tale of by-gone days, a tradition or legend of the dead and forgotten past. Idrīsi happened to come across the statement in the Kitāb-i-Masālik wa mamālik and copied it without any attempt at verification. It may have been true of the times in which that work was written, though Mr. Vincent Smith denies it. He holds that Kābul which was captured by Y'aqūb Lais in 257 H. 870-1 A. C. was never the capital of the Shāhiyas. (I. M. C. Vol. I. 245).

But it would appear from Alberūni and other Arab historians that though the city was compelled to receive a Muslim governor, the Hindu Shāh or Aspahbad, as he was also called, always remained at his side. About A. D. 950, the city of Kābul was Muslim, but the suburb was inhabited by the Hindus. It would seem that Kābul was the Coronation City of the Shāhis, as Konigsberg in Prussia was of the Hohenzollerns. (Alberūni, India. Tr. II. 157 and Sachau's note at 394). But though this may have been the state of affairs in the tenth century, it was not at all true of the twelfth and Idrīsi cannot be absolved of blindly copying from earlier authorities statements which had no reference whatever to his own period. (Dames in Houtsma, E. I. II, 595).

I. 92, l. 8. The mountains [near Kābul] produce excellent aloe-wood, and the neighbourhood supplies cocoa-nuts and myrobolans of that sort which is called Kābuli, from this town.

Cocoa-nuts in Kābul! But Idrīsi is not primarily responsible for the howler. He has just pilfered it from Khurdādbih (J. A. l. c. 265; Goeje. 38, l. 1. Tr. 27). Kābul has been always famous for its myrobolans, which are called 'Chebulic', but surely cocoa-nuts never grew or could have grown anywhere in its neighbourhood. The alleged production of aloe-wood in its mountains is also a botanical 'inexactitude'.

I. 95, l. 14 from foot. There is another Persian translation..... bearing the name Sairu-l-bilād.

There is a copy of this version in the Bodleian. Ethé says it is really a translation of the second $B\bar{a}b$ or section only of the $As\bar{a}ru$ -l- $Bil\bar{a}d$. The translator was a Muḥammad Murād bin 'Abdur Raḥmān and he has dedicated his version to Nawwāb Musawi Khān. (Sachau and Ethé, Bodleian Catalogue, No. 400, Col. 400). This Mūsawi Khān was probably the Amīr of that name who was the minister of Jahāngīr and Shāh Jahān, I. 95, l. 5 from foot. Mis 'ar bin Muhalhil who visited the place [Kūlam].

Qazvini who wrote in the third quarter of the 13th century cites

here and in his accounts of Saimur and Multan, the authority of this writer who is said to have "fravelled into various countries" about 331 A H 942 H C. Unfortunately, Qazvini also appears to have been blissfully oblivious and ignorant of the changes which had taken place in those remote parts during the three centuries which had intervened

The original work of Mis'ar has been lost and Yule, as well as other critics, have expressed doubts about the genuineness of the extracts which have been preserved Yule opines that it is very difficult to say "how much it has suffered from the manner in which it has been coopered from loose fragments" (Cathay, Preliminary Essay, I 139 See also In any case, what Mis'ar bin Muhalhil says here Kulam is not calculated to inspire confidence in the authenticity of his narrative. Among other things, we are informed that when the king of Kulam died, his successor was chosen from China, that there was no physician in India except in this city, and that it had neither a temple nor an idol The statement that Multan was "the last city of India bordering on China" must also make a modern geographer 'stare and gasp' Two other averments about the same town-that the temple of the Sun was 300 cubits (450 feet) in height and that the idol itself was 20 cubits (30 feet)—are likewise suspect He also tells us that there were Fire worshippers and Fire temples in Saimur in his time. As this statement about Saimur has been frequently cited in the B G (I. 1 510 n. 516, 517 n) and relied on by several writers on the history of the Indian Parsis, it may be worth while to note that the extracts given in Yaqut's Mu'ajjam are, in Brockelmann's opinion, "a late falsification" and "the geographical information given by the compiler is quite unreliable in detail" (Houtsma, Encyclopaedia of Islam III 519-20) Horowitz also has denounced the excerpts as spurious, while Barthold declares that the story of Mis'ar's Travels, as it is given in Yaqut's extracts, is "undoubtedly fraudulent" (Houtsma, E I IV 148).

I 96, l 1 Nor do they slaughter animals, but they eat carrion

The word used for slaughter is £3, which means killing animals which are lawful food, in the particular manner and after the recitation of the particular Arabic formula, enjoined by the Islamic law. The flesh of any animal, lawful or unlawful, which has not been done to death in the manner so prescribed, is polluted or unfit for consumption and ranked with 'carrion' [عردار من من عن الله Merchant Sulaiman had made, almost three centuries before Idrīsi, the same remark and observed that neither the Chinese nor the Indians "kill their meat by cutting their throat, as the Muhammadans do, but by beating them on the mouth till they die" (Old English Translation of 1733, p. 35). Qazvīni again writes of the infidels of Saimūr also they do not slaughter animals, ie kill them in the Muslim manner. (97 infra) In other words, Zabh, 'slaughter' has a peculiar or technical meaning here and in this sense, all those persons who dine off mutton or beef killed by non-Muslims may be said to eat

'cafrion.' Minhāj says that as Chaghatāi, the son of Chingīz, held Islām and all professors of that faith in the greatest detestation, it was not possible in his territories "to slaughter [خرائي] a sheep according to the ordinances of Islām and all sheep used to be rendered thereby unclean." [Carrion. اعرائي]. (T. N. Text, 397, l. 5: Tr. Raverty, 1146).

I. 96, 1. 9. Rhubarb grows here [Külam] the leaves of which are called Sāzaju-l-Hindi.

This is all wrong. The leaves of the Rhubarb are poisonous. It is the stalks and roots only which are edible and medicinal. Rhubarb is the dried and decoroticated erect rhizome of Rhei Palmatum and Mis'ar is mistaken in saying that its leaves are called Sāzaju-l-Hīndi. The latter is really the 'Indian Leaf,' Folium Indicum' or leaf of the Laurus Cassia, the Tamālpatra of Sanskrit writers and the Tejpāt of the bazars. Garcia d'Orta also speaks of this 'Sāzaj' as Folius Indu. It is "the pungent leaf of several wild species of Cinnamon and is found in the hills of Eastern Bengal as well as the forests of Southern India and was highly esteemed at one time as a medicine." (Yule, H. J. s. v. Malabathrum).

1.98, l. 6 from foot. When the king asked his companions what they had to say about the marvel of the idol etc.

This story of the mysteriously suspended idol of Somanāth is found in 'Awfi's Javām'iu-l-Hikāyāt. (Bk. IV. ch. xx. No. 1996; Nizāmu-d-dīn, Introduction. p. 29) and also in the Tārikh-i- Nigāristān (Bombay Lith. 1829, p. 100). 'Utbi says this of the idols at Mathurā. (E. D. II. 44). Old European writers repeatedly state that Muḥammad's tomb at Medīna was "fixed in the air without support" in the same way. These and other tales are only part of the medieval mythology of the lodestone.

I. 99, l. 18. The lord of the fortress presented many gifts to the Sultan, among which was a bird in the form of a dove.

This story of the bird which was a toxicologist by instinct and the stone which could perform surgical miracles has been traced by Dr. Nāzim to the Akhbāru-d-dawal, written by Ibn Zāfir in the beginning of the 7th century of the Hijra. These presents are there said to have been sent to Maḥmūd, after his generous treatment of Nanda [Ganda] of Kālinjar, by a neighbouring ruler named 'Kābakan' who was also known as 'Taḥda' or 'Najda.' These wonder-working gifts are also mentioned by Ibn al Athir (Kāmilu t-tavārikh. ix. 234), who records the event under the Hijri year 414 (M. G. 114 note).

Dr. Nāzim makes no attempt to identify this 'Kābakan' who is said to have been the master of 1000 elephants. I venture to suggest that is a mistranscription of Gāngeya , the diacritical points having been misplaced by the copyists. Similarly or or is an error by transposition of the letters of chedah.' We know from contemporary inscriptions that Gāngeya Chedi—the son of Kokalla—was one of the greatest Hindu potentates at this time and that he reigned

from about 1020 to 1040 A C [A H 411 to 432]. He is mentioned by Alberuni as the ruler of Dahāla, the capital of which was at Tiauri, ie Tevar near modern Jabalpur (Sachau's Tr. I 202 See also 58 ante) Baihaqi also states that when Ahmad-1-Niāltigīn raided Benares in 424 H, the city was in the territories belonging to Gang [eya]. Gāngeya is, in fact, the Chand [Chedi] Rāi of 'Utbi, Gardezi and other historians of Mahmūd and I hope to show in another note that his father Kokalla Chedi is no other than the Kulchand is who took up his station at Mahāban and died by his own hand, after his defeat on the banks of the Jumnā.

I 104, l 2 They [the Jats and Meds] dwell in Sind and on the banks of the river which is called Bahar "

I suggest the transposition of the dot and read π 'Nahr'—'The River' The Indus is often called 'Sihūn' and this vocable is used on 138 and 158 infra, as a common noun for 'river' and also applied to the Indus as 'the River of Hind' (158 note) So the Oxus is known as π 'the River (of Rivers)' and Transoxiana is called 'Māwarāu-n-Nahr' Similarly, Pahan, (1.5), the other river which this author mentions, is a miswriting of 'Bahat' π is a tension of the Jats and Meds was probably the hilly "tract near the Salt Range, on the part which is in the proximity of Multān" (E D II, 477) Firishta says that the Jats against whom Māhmūd led a punitive expedition in 1026 A C: dwelt on the bank of the river of the Koh-1-Jūd, is the Salt Range (I 35, 14) Gardezi (Zainu-lAkhbār, Ed Nāzim, 88) states that they dwelt on the Sīhūn Their country was evidently what was afterwards known as the Sind-Sāgar Duāb, the interamnia of the Indus and the Jhelum (Āīn, Tr II, 311)

I 109, l 1. When the information of the Brāhman reached the Hindus Dowson suggests in a footnote that we should read "Bahman" for Brahman, but the words cited by him from the original show that לביי is right יביי "The [أخر] information given by the Brāhman" was the interpretation put by him upon the dreams of the king, the news or tidings of the events presaged by the visions Reinaud's translation is as follows—'Les explications donées par le Brahmane s'étant répandues parmi les Indiens' (Fragments, 46)

I 109, l 2 from foot Three other countries of the kingdom of Samid he bestowed upon another

Dowson complains in his note that the whole of the passage is ambiguous. The phrase which he translates here as "three other countries" is rendered as un troisième principauté, (a third principality) by Reinaud, 47. Reinaud is quite right. Gardezi uses the expression exactly in the sense which Reinaud assigns to it. In his account of 'Amr bin Lais, he says that 'Amr had four store-houses [Khazāna], one containing arms and armour and three containing money. He then states the sources from which the latter were replenished and the

purposes for which their contents were disbursed. He writes: یکی مح خزینه مال صدقات و گزندهای ×× و دیگرخزینه مال ×× و سه دیگر خزینه مال مدقات و گزندهای ×× و دیگرخزینه مال × خوینه مال صدقات و گزندهای خوینه مال محتم جم شدی (Zain-u-l-Akhbār, Ed. Nāzim, 15, 1. 11.) He uses the phrase again, (Ibid. 48, 1. 15), where three points are mentioned seriatim. The first has the heading دیگر the second میک میک مسلم سه دیگر There can be no doubt that سه دیگر means "Another still, (after the second), i.e. the third. It is a pleonastic expression or idiom. Anwari also uses the phrases میک میک میک میک شود. و دیگر for 'second' and 'third.'

I. 110, l. 1. He consigned the countries of Hindustan, Nadama and Lohana separately upon another.

Sic also in Reinaud (18, 1.3 ff, Tr. 47), but the true reading seems to be 'Sadūsān, Samma and Lohāna.' 'Sadūsān' and 'Hindūstān' are very liable to be confused in the Semitic script and this identical error is perpetrated again in the Bibl. Ind. text of the Tabaqāt-i-Nāṣiri (142, 1.1 f. f. = E.D. II, 302; Raverty's Tr. 532 and Note).

I. 110, l. 8. History of Rawwall and Barkamaris.

I. 110, l. 4 from foot. He had a Vazīr blind of both eyes named Safar.

Here also, the mere addition of a single nuqta may give a clue to the right reading, سقر Suqra, i. e. Shukrāchārya who is said to have had only one eye. Cf. 106 ante, where قاسف (Kāsyapa) is written قاسف.

In this connection, it may not be amiss to point out that the book '\$\overline{A}d\bar{a}bu\cdots\cdot\cdots\cdot\cdots\

1. 120, l. 8. There was at Debal a lofty temple.

Elliot contends (376 and note *infra*) that the temple was only contiguous to the town of Debal and not within it. He relies upon this passage, in which it is said that the temple was b'il Daibal. (Reinaud, i.c. 168), but these words may mean both 'in Daibal' and 'at Daibal'. The Chachnāma, however, explicitly states that the tem-

ple was "in the midst (or middle) of Daibal," در ميان ديدل. Elliot tenaciously held to the idea that Daibal was at Karāchi and the temple at Manora. Haig accepts the statement of the Chachnāma and holds that the temple was in the town itself. As Elliot's identification of Daibal with Karāchi is now universally rejected, the minor contention has ceased to be a live issue. Manora is about five miles distant from any source of fresh water and it is hardly likely that a large temple could have been situated in such a spot

I 121, l 13 Then he saw approaching near him Sarbidas, the Samāni, who came to demand peace

I 121, l 15 Muhammad then went towards Sahban and took it

The reading of this place-name is uncertain Reinaud's MS (I c 169, I 10) had it without any dots Biladuri cannot mean Sahban (Sehwan), as he says only a few lines lower down, that Muhammad bin Mus'ab was sent to Sadusan, which is only another form of Sehwan Haig reads the name as 'Ashbhar' (62 note), while Raverty supposes to be an error for the Sisam of the Chachnama q v 161 infra, (Mihran, 232) Sisam, now called Shah Hasan, (Constable 26 A b) is a township at the western end of Lake Manchar Dr Murgotten reads Sahban If the place meant is 'Seisam,' the difficulty may be surmounted by reading it is Sahsan Shah Hasan seems to be only a modern form, a factitious Muhammadan perversion of the original name

I 122, l 8 Old Brahmanāhād, two parasangs from Mansūra

All authors agree that Brahmanābād was somewhere near a place called Bhambrā-kī-Thull—about eight miles east of Shāhdādpur and 48 miles north-east of Haidarābād But the relative situations of Brahmanābād and Mansūra have been the topic of acute controversy. There are three ruined sites in close proximity to each other, viz, Bhambrā-kā-Thull or the Great Mound, Dalūra, 1½ miles south-east of Bhambrā, and Depur Ghangro, 5 or 6 miles north-east of it Cunningham thought Bhambrā or the Great Mound was Mansūra and that Dalūra was Brahmanābād (A G I. 273) Raverty was for just reversing the positions. The smaller and more compact town—Dalūra—was, he thought, Mansūra and Depur Ghangro was old Brahmanābād (Mihrān, 202 note and 239) General M. R. Haig held the opinion that Depur Ghangro stood on the site of old Brahmanābād, but Mansūra must be represented by the Great Mound or Site, i.e. Bhambrā (J R A, S. 1874, Vol. XVI,

1, 126, 1, 1,

Part II). Mr. Cousens disters from all his predecessors. Brahmanābād and Maneura lie, he maintains, on one and the same site—the Great Mound—but Maneura is on the top and Brahmanābād at the bottom. But this contention can hardly be correct as Bilāduri explicitly states that Maneura was two farsakhs distant from Brahmanābād. Mr. Cousens also holds that Dalūra is Malefura and Depur Ghangro is the Buddhist colony or Vihīr of Sīwandi, which is mentioned in the Chachnāma. (A. S. 59, 66; Arch. Survey Rep. 1903-1, p. 182, ff). Sir Wolseley Haig locates Maneura, a few miles to the north-east of Brahmanābād. (C. H. I. III. S).

I. 125, I. 8 from foot. Junaid proceeded against him in ships and they fought in the lake of Ash Sharki.

which Reinaud renders as بطبحه الشرقي The words in the original are بعليجه Yetung ("Lake") de Alscharky (l. c. 175, 203). Dr. Murgotten says means' swamp', (Tr. II, 226). Raverty insists that it is "the Estuary of Ush-Sharki or Ush-Shagira or the Kohrai mouth, by which the branch of the Mihrin which flowed past Mansura united with the Ocean, but which 'estuary' in that day existed much further north." (Mihran, 256). But Haig denies that * means 'estuary' and quotes the great Arabic Dictionary of Lane in which it is said to mean 'a wide water course or channel of a torrent.' Haig thinks it must be the 'Eastern inland sea', the sea that once permanently covered and still periodically covers the Ran of Kachh. (I. D. C. 65). But it seems hardly profitable to dispute about the point, as there is nothing to guide us save an ambiguous and vague geographical expression. Indeed, Raverty himself does not seem to have known his own mind on the subject, as he declares elsewhere in the same Ersty, that this Shagira must be the Samarah lake or dhand running parallel to the old bed of the river Nara or Hakra, which is somewhere near Amarkot. (Mihran, 463 and Note). The phrase itself means nothing more than the "Eastern swamp, lake, pool of water or lagoon." (See also Houtsma, E. I. III, 236).

 1. 126, l. 1. He then sent his officers to [invade] Marmad, Mandal, Dahnaj, Barüs,Māliba, Baharīmad, Bailamān and Jurz.

These toponyms are discussed by Sir II. Elliot in his Notes at pp. 3:0-1, and 440-1 infra, but they are so uncertainly written and so many alternative identifications are possible that it seems hardly worth while to spill any more ink about them. I may, however, refer to Dr. Bhagvanlal Indraji's opinions on the subject. He thought that 'Marmad' was Marumad, or Mārwād, Mandal, the place of that name near Viramgām, Barūs, Broach, Māliba, Mālwā, Baharīmad, Mewād, Bailamān, Bhilmāl and Jurz, Gujarāt. (B. G. I. Pt. I. 109). Māliba, however, may be Baliba (Valabhi) and Baharīmad, Bāhadmer or Bādmer which is so called after its founder, Bāhad. (I. G., VII, 22).

But though there is considerable uncertainty about the location of

these names, there is no reason to doubt the fact of the incursions. The raids are said, by the Arab historian, to have been undertaken in the reign of the Khalif Hishām (r. 105-125 H. 724-743 A.C.) Now, the defeat and repulse of one of the Tājik (Arab) inroads is actually recorded in a copper-plate grant of the Chālukya king Pulakeshi, which is dated in the 490th year of the Traikūtaka Era, i e 738-9 A C. It is stated there that the Tājik (Aiab) army had afflicted the kingdoms of Sindhu, Kacchella, Saurāshtra, Chavotaka, Maurya and Gurjjara, i.e. Sindh, Kachh, Kāthiāwād, the Chāvadās, the Mauryas (of Chitor) and the Gurjaras (of Bhinmāl). Pulakeshi was at the time ruling at Navsāri He was one of the members of the third Gujarāt branch of the Western Chālukyas (B G I i 109, 117, 465, Duff C I. 64, Vaidya, H M. H I, Vol II 73).

Dr Bhagvānlāl did not attempt to locate Dahnaj The name is spelt in the same way in Murgotten's rendering and he also leaves it unidentified But in one of the MS. of Khurdādbih, it is written (Goeje's Text 57, note f), and mentioned in association with Barūs, Mandal, Bailamān, and Jurz, just as it is here Vide my note on I. 61, 1 10. It is most probably Rānder, which Alberūni calls can and which is also written.

I 126, l. 12 This water was so called because buffalos took refuge there from the bears which infested the banks of the Mihran

The word in the original for 'bears' is color Remaud's rendering is 'wolves', loups, (176, Tr 208) and Murgotten's 'blue flies' (1 c. 223). Louis mean 'bear', but color which is the reading favoured by Murgotten, signifies "flies or bees", according to Richardson

I 127, l. 10 from foot. He sent 'Amrū son of Jamāl in boats to Nārand.

Dowson says the name has no points and is in the MS. Reinaud also admits his inability to fix the reading for that reason. He was sure, however, that it was a place situated to the south-east of Mansura on an arm of the Indus or on the sea-coast, but at no great distance from the river. He thought also that this raid or invasion is the same as that recorded by Ibn-al-Athīr in A H 160, q v my note on II 246, l. 14 post. Reinaud's description would suit modern Vala (the old Valabhi) fairly well, but the aspect of the country has, as he says, (l. c 212 note) changed so considerably during the last thousand years that little or nothing can be built upon the apparent coincidence in chronology.

I 127, l 5 from foot. He then went [from Multan or Qandabil] to Kandahār in boats and conquered it

Remand thought that this must be Gandhar in Broach district, near the Gulf of Cambay (Fragments, 212 note), and Dr. Bhagyanlal Indrali (B G I. 1 96) as well as the compiler of the Surat volume of the B. G. (II. 561) supports that view. But Elliot was in favour of

Khandādhar, on the north-west angle of the Peninsula of Kāthiāwād (445 infra). Raverty was for identifying it with Kandhiāro, in the south-west corner of Bhāwalpur, on the banks of the now dried-up Hakra or Waihinda. (Mihrān, 207, 257 n). This last opinion is followed in the C. H. I. (III. 9), but it is not possible to reach any definite conclusion, as there is little else to guide us than a doubtfully spelt name.

I. 128, l. 10. There he constructed a band, which he called Sakru-l-Med, 'Band of the Meds.' He encamped on the river at Alrūr.

Reinaud reads و المرازي المرازي (180, 1. 7. Tr. 214). Raverty insists that this Alrūr cannot possibly be Alor or Aror and that 'Imrān's camp was near Adhoi in Cutch (Kachh), which lies 'sixty miles east of Bhuj and by which a small river still runs'. (Mihrān, 258). This view is accepted also in the C. H. I. (III. 9). Adhoi is in Lat. 23° 23′ N.; Long. 70° 29′ E. (Th). Constable 26 c d. Elliot and Raverty understand 'Sikr' as a Band, i.e. a mound or dike for damming up a river. But Dr. Murgotten says 'Imrān "built a highway, which is known as the Highway of the Meds." (232). Reinaud has Chaussee (214), i.e. causeway or raised way though a marsh. The meaning is that he built a dam or causeway and afterwards dug a canal from the sea to the lake from which they drew their supplies of drinking water, so as to inundate it with salt water.

'The small river which runs past Adhoi'is scarcely worthy of that name. It is nothing more than a monsoon torrent, which is dry during the rest of the year and the construction of 'a dike or mound' as a military or naval barrier on such a streamlet could have served no strategic purpose and would have been an act of supererogatory folly. This fact seems to discredit Raverty's identification. Indeed, we have it on the authority of the I. G. that "there are no permanent rivers in Kachh at all. During the rainy season, some streams flow from the hills to the Ran and the Gulf of Kachh, but during the rest of the year, the courses of these streams are only marked by a succession of detached pools". (XI. 75). Dr. Murgotten also in his excellent version of Biladuri says that "the camp of 'Imran was upon the river of [not at] Ar-rur." (232). As all that is really said is that 'Imran encamped somewhere on the river of Arur, i.e., somewhere on the Indus, between Rohri and the sea-a distance of several hundred miles-it seems infructuous to dogmatise about the matter. Idrisi says of the Meds that they "dwell on the confines of the desert [Ran of Kachh] and extend their incursions as far as Aror and sometimes to the frontiers of Makran." (79 supra).

I. 129, l. 6. Fazl son of Māhān got into Sindan and subdued it.

There are two opinions about the Sindan of this passage. Some say it is Sanjan [St. John's Point], near Bulsar, and about 88 miles north of Bombay. But the compiler of the Cutch volume of the B.G. thinks that it must be Sandhan on the coast of Kachh, about thirty miles west of Mandvi. (V. 131 note 5, and 250). The statements regarding the situa-

tion of Sindān in the 'Arab geographers, Istakhri, Idrīsi and Abul Fedā are so inconsistent or mutually discordant that it is not easy to say where it really was Some of them seem to have even mixel it up with Sindābui which was somewhere on the coast of Canara between Goa and Kumta

I 133, l 21. 'Annu-l-Mulk bin Abi Bakr bin Muhammad Husuin Al Ash'ari

He was at first, the Vazir of Nāsiru-d-din Qubācha, but after the death of that ruler, entered the service of Iltutimish and was made Divān or Vazir of the Prince Ruknud-dīn Firūz, when the latter was sent to Budāun as governor in 625 A. H (T N Text 172-3 and 181-2 = E D. II 325, 330) 'Ainu-l-Mulk's ancestor, Abu Mūsī al-Ash'ari is said in the Chachnāma (Tr Kalich Beg, 9 and 58) to have been Hākim of 'Irāq during the Khilāfat of 'Umar, Circa 16 A H, about the time when Mughaira ibn Abu-l-Ās attacked Daibal and was killed there See also Bilāduri, 115 ante and 416 post

I. 138, 7 5. Chach, son of Silāij

Elliot says that "the very name of Chach is a subject of some uncertainty", and he gives several variants (409 post). But there can be little doubt that it is really 'Jajja' This name was borne by a brother of Jayāpīda, the King of Kashmīr, who stirred up a revolt in Jayāpīda's absence and was overthrown and killed when that ruler returned (Vaidya, H M H. I II 215) Jajja also occurs in an inscription dated V S 1207, (1150 A. C) from Mahāban near Mathurā. (Duff, C I 151) Jajjala Deva was the name also of two Rājās of Ratnapūr, who belonged to the Kalachuri dynasty and reigned in the 12th century (Ibid, 158, 163, 293) Jajja is the Prākrit form of Yayāti Chach seems to be a local or dialectical form of 'Jajja' Chāchikdeva appears in the dynastic list of the Biatti rulers of Jaisalmir, Circa V S 1505 = 1448 A. C (Ibid, 256-290) A Hindu surgeon named Jājā [or Chāchā] is also mentioned by Barani in the reign of 'Alāu-d-dīn (T F. 363, 1 8)

Some of the other Hindu names are hopelessly corrupt and cannot be set right. But Siliij, the name borne by the father of Chach must stand for Shilidityi. Siharas is probably meant for Shri Harsha, Silir i for Shijiga or Sinhasena, Chatera (141, 122) for Jaitrasinha,

written by the copyists in a truly bewildering multiplicity of forms— התוט - זמרוע - בארוע - פֿערוע - אוע הארוע - פֿערוע - אוע הארוע - פֿערוע - אוע הארוע - פֿערוע -

Ibn Hauqal says that the governor of Qusdār lived at Kaba Kānān (Kīkānān) and also declares that Qusdār was the capital of Tūrān. (38, 39 ante). Turān roughly corresponded to modern Jhalawān. (I. G. VI. 275). Kirkāyān, Haig thinks, is Kachhi and perhaps also the country east of it as far as the Indus. (I. D. C. 59). But Cunningham locates Kirkāyān in the valley of Pishīn or at Pishīn itself, north of Quetta (A. G. I. 86), Marquart (Éranshahr, II. 275-6) and Lestrange (L. E. C. 332) at Kelāt, while the writer in the I. G. places it at Nāl, which is about forty miles due west of Quzdār. (XIV. 110). This divergence of opinion is probably due to the fact that Kirkāyān is described as a town and seems to have been also an ill-defined district.

Elliot points out that there is no place now extant which recalls the name of the old province or town (383 infra). It may be therefore pertinent to invite attention to the fact that Masson came across in his Travels, the vast ruins of a great city called Lakoriān, "between Kelāt and Quzdār, about sixty miles south of the former. The fortifications are, he says, remarkable for their magnitude and the skill displayed in their construction, (Kelāt, 63; Travels in Balochistan, II. 46; A. G. I. 311). This name Lakoriān looks like a survival of Kirkān or Kirkāyān, with the Arabic article Al prefixed to it. It may have been the town [A] Lakirkān—and the initial 'alif' clided. It may have been the town Kirkāyān, while the district or province which was so called included not only Kachhi but parts of modern Jhalawān and Sarāwān. It may be also noted that as Khurdādbih mentions Al-Qairūniya and Qinnazbūn separately (14 ante, Paris Text. 57-8), Al-Qairūniya cannot be Panjgūr, and may be meant for Lakoriān.

I. 138, l. 5 from foot. Under him were placed Budhpur, Jankan and the skirts of the hills of Rūjhan to the borders of Makran.

Haig suggests that Jankān is the Jhangār in Schwān taluqa, which lies about 12 miles south-west of Schwān town, (I. D. C. 57 note) and has road-communication with Schwān as well as Shāh Ḥasan [Sīsam]. (Hughes, Gazetteer of Sind, 269). But there is a Jangān or Jagān, about 17 miles N. W of Shikārpūr and there is a Rūjhān also, 39 miles from the same place, Lat. 28°-18′ N. Long. 68°-18′ E. (Th). The country from Rūjhān to Naushera is 'a desert for 96 miles'. (W. Hough, Narrative of the March and Operations of the Army of the Indus (1838-9), pp. 38, 427). This Jangān is called "Jagun' by Thornton. Lat. 28°-8′ N; Long. 68-°33′. E. The name Rūjhān is read by Haig as 'Dūnjhān (I. D. C. 57), but Kalīch Beg's MS. (p. 11) had the same lection as Dowson's and Rūjhān is probably correct, as Jangān is also in its vicinity. As Budha was, according

to Haig, "a province of which the northern boundary touched Gandāva and the southern was in the Kākar pargana in Shikārpur district," the places mentioned must be the Jangān and Rūjhān which lie north-west of Shikārpur The hills of Rūjhān must be the Kirthar range

Elliot states that the old name Budha "still survives in Budha, which lies in the very centre of Kachh Gandāva on the Nāri river" (388 post). According to the I G (VI 275) also, Budha was the same as Kachhi

I 138, l 2 from foot Askalanda and Pābiya which are called Talwāra and Chachpur

Elliot attempted to identify the second pair of toponyms with Mīrbar and Chāchar "which are situated at the junction of the Chenāb and the Indus opposite Mittankot" (366 infra), but the names themselves are variously written in the MSS and K. B's reading is 'Sawārah and Jajhor', not 'Talwāra and Chachpur' (p 12) The relative clause is not found in all MSS of the Chachnāma and it looks like a gloss or conjecture which the copyist had read somewhere and which he afterwards interpolated in his transcript of the original Chronicle Such adventitious glosses may be ben trovato, but they are suspect and of little value

Cunningham suggested that Askaland or Askalandusa was Uccha (A. G I 245) and Elliot appears to have been disposed to accept the conjecture (366 and 520 infi a), but it has not found favour with any other writer Pābiya is written variously as Māībar, Pāya, Bāya and Bābiya in MSS, as Dowson points out It is even called 'Yābība', when again mentioned at 202 infra Raverty was sure that it was Pubberwalla, which is 29 miles eastward of Uccha, twenty-four Kos from Dirāwal and twelve Kos from Bhāwalpur (Mihrān, 369 and note) But this surmise also has little to be said for it and even Sir Wolseley Haig will have nothing to say to it He pronounces both Askalanda and Pābiya hopelessly unidentifiable (C H I III.6)

1 139, l 1 The fourth at the great city of Multan and Sikka and Brahmapur und Karur

Sikka and Brahmapur also are unsolved conundrums Cunningham and Raverty agree, for once, in thinking that the last name may be Kahror which lies on the southern bank of the Old Beas river, 50 miles south-east of Multan (A G I 241, Mihran, 253 Note)

Kārūr is mentioned by Alberūni as lying between Multān and the castle of Loni (Tr Sachau, II. 6) Cunningham thinks this Loni may be meant for Ludhan, an ancient site on the old bed of the Sutlej, 44 miles E N E of Kārūr (or Kahror) and 70 miles E S E of Multān (A G I 241) Kārūr is said by Alberūni (*Ibid*) to have been the site of the great battle between Vikramāditya and the Shakas, about A. C 78, but the battle, the site and even the existence of this Vikrama are all problematical (I G XIV 273)

I, 139, l 13 and footnote 4. The army of the King of Numroz marched from Fars to Makran

Dowson says the text adds ביין לנט: which may mean 'in Arab fashion'. I suggest that the right reading is ירים לנט: "by way of invading countries." פעים לנט is synonymous with the Mulk-giri of the Marātha rulers of the 18th century and the 'Digvijaya' or 'world-conquest' of the Kāvyas—the aggressive raids, forays and marauding, sacking and slaughtering expeditions which were only too common in 'the good old days.'

I. 140. l. 8. Chach marries Rani Subhan Deo.

The matrimonial entanglements of Chach and his sons, as they are described in this part of the work, must be incomprehensible to any one acquainted with the social conventions of the Hindus of the 7th century. He is represented by this author as a very moral, devout and orthodox Brāhman and yet he marries his quondam paramour and widow of his former master after he had waded through pools of blood to a throne. He then disposes of Mahrat by an atrocious act of perfidy and marries another widow of a lower caste than his own—who had been the wife of Āgham, the Lohāna. His son Dāhir forms an incestuous connection, real or nominal, with his own sister and he is represented as marrying yet another dowager, who had been the wife of his own brother Dharsiya and was also the daughter of their father's wife—the wife of Āgham the Lohāna. (K. B.'s Tr. 54). Moreover, Chach is said to have given the daughter of his nephew Dharsiya to Āgham Lohāna's son Sarband. (148 infra; K. B.35).

It may have been permissible for Hindu kings, in the seventh century, to enter into polygamous Anuloma unions with women of castes inferior to their own, but no Brāhman could have married a widow. The pratiloma marriage of a Brāhman virgin with a low caste Lohāna male must also have been the 'abomination of desolation' to every one in the seventh century. It is difficult even to imagine the perpetration of such social turpitude by any Brāhman prince. 'Ali Kūfi has, in fact, seen things in the light of his own imagination or given the story a dash of Muslim colouring and ignorantly postulated in a Brāhman king the sort of conduct in relation to the wives of his vanquished foes, which Muslim conquerors were accustomed to adopt.

The whole of the first part of the work is overgrown with legendary matter and all but valueless as history. The description of Chach's conquests from Multān on the one side to Makrān on the other seems imaginary. It looks like a rifaccimento in Persian prose of a poetical Digvijaya' and is every whit as unhistorical as similar lucubrations of Sanskrit poets and Rājput bards. It bears, also, such a close resemblance to the victorious progress of Muhammad-i-Qasīm himself from Makrān to Multān and the places conquered by both also differ so little, that it is impossible to refrain from suspecting that the one is only a réchauffé of the other. It may have had some basis in the flotsam and jetsrof local tradition, but if so, the tradition has been so grossly corry

the course of transmission by the fantastic accretions of subsequent inventiveness, as to amount to a travesty of the truth

I 142, l 8 from foot Chach placed Amīr Alīu d-daula in the fort of Sikka

Dowson has understood this as a proper name, but the more probable meaning is 'one of the exalted or leading [Hindu] nobles of the State' It is not likely that Chach had a Musalman Amīr in his service at this time. The Alālis appear to have been the earliest followers of that faith to take service with the Hindu kings of Sindh, but they are said to have done so only during the Khilāfat of 'Abdu-l-Malik ibn Marwān, about AH. 80, i e in the reign of Dāhir, the son of Chach (KB. 69, see also 425-6 infi a). Cf. also 145 infi a, where Chach is said to have placed one of his confidential officers (Shahna in the text) after taking Siwistān.

I 144, l 4 At last he reached the fort of Shākalha, an elevated place which is called Kumba on the borders of Kashmir

Dowson notes that the words in the original are

[[], which may also mean "And they say [or it is said] that the place [Shākalha] is above [or higher than, that is, north of] Kumba on the borders of Kashmīr" Here 'Kumba' seems to be the name of a town and it is spoken of as a town on the borders of Kashmīr, elsewhere also in the Chachnāmā (139 ante) 'Kumbha' also means in Sanskrit 'a lake, pond or piece of water' and the words may mean that "the place was situated above, ie north of a lake"

But the right reading here may be neither Inor I but Kassa', as it is written at 201 infra, where Jaisiya is said to have gone to "the land of Kassa on the borders of Jālandhar" or as K. B renders it to "Jalandhar in the land of Kashmir" (p 185) Vide my note there

I 145, l 5. Chach crossed the Mihran at a village called Dihayat which formed the boundary between Samma and Alor

General Haig thinks that this may be Dehāt, a township on the northern border of the Kandhiāro pargana, which is known to have been the border of the Samma lands The old river channel still exists here (I D C 133)

I 145, l 8 He [Chach] proceeded to Būdhiya, the chief of which was the son of Kotal bin Bhandai gū Bhagū

K. B calls him 'Basarkotad, son of Bandar Kobhko' (p 30) Dowson would seem to have read 'pisai' instead of 'basar' and understood it as 'son' If the right reading is Basarkotad, a plausible restoration would be 'Vishvakirti [or Vasugupta] bin [son of] Bhadra-rakhu Bhikku' 'Bhikku' is frequently appended to the names of monks in the inscriptions at Mathurā (J A S B XXXIX (1870), Pt. I, 128) 'Vasugupta' and 'Vasubandhu' are well-known names in the history of Buddhist literature But only two lines lower down, it is said that Kabā, son of Kākā, came forth to ask quarter for the chief. This may indicate that Kākā, the actual name of the ruling chief, has been inadvertently omitted

here and that his full name was Kākā, son of Kotal, [Kirti, Gupta or Gopāla,] son of Bhadra-rakhu Bhikku.

I. 146, l. 13. Malik Ramal who was called Bhati.

The confusion in the original regarding this' Ramal' is inextricable. Here 'Ramal' is said to be the name of the Malik or King, but elsewhere, (pp. 154 and 155 infra), it is spoken of as the designation of the country or kingdom. K. B.'s rendering is 'the king lom of Nirmal, called Bhatti' p. 32). The ambiguity is due to the fact that "Malik' means 'king' and "Mulk,' kingdom. Again, as 'Raml' in Arabic signifies 'sand,' Mulk-i-Raml' may be understood as 'the sandy country' also, which is an appropriate designation for parts of modern Mārwād and Jaisalmir.

Khurdādbih and Idrīsi (14, 84, 87 ante) also speak of a town or district called 'Rūmala' and associate it with a desert or the borders of a desert. It is common knowledge that Jaisalmīr is "almost entirely a sandy waste forming part of the 'Great Indian Desert'. The general aspect is that of an interminable sea of sandhills." (I.G. XIV. 1). But in Goeje's Edition of Khurdādbih, the reading is not but a but i.e. Marumad or Mārwād. If a person and not a place is meant, the name may be read as i.e. 'Bharmal' or even 'Nirmal'. If it is a district, the reference must be to the country to the east of Sind, parts of modern Jaisalmir and Jodhpur. This is the nearest we can get to an answer.

I. 147, l. 9. He had a temple which was called Budh Naw-vihār and the the idol Dilha (?). He was a devotee thereof.

The reading in Dowson's Ms. was او را نووهار گفتند و بت دلها [E. I. Lib. Ms مراهب او بود [دکهاد E. I. Lib. Ms مراهب او بود [دکهاد I venture to suggest that we should read the doubtful words as و بت [من بد] کنبهاره and translate them thus: "He had a temple which was called Bud Nav Vihār and also Bud [or idol-temple] Kanbihār or [Kanvihār]. He was its priest."

The meaning is that the temple was known as 'Nav-vihār' and also as 'Kaṇvihār' and this Sāmāni was its priest. We are told on p. 148 infra, that "Chach afterwards went to the temple of Budh [and] Kanbihār with the intention of killing the Sāmāni."

I. 151, l. 6. But they [the Jats] might wear their outer garments of silk, provided they were of a red or black colour.

There is some blundering here, as the averment is utterly inconsistent with the general import of the paragraph. These unfortunate people who were treated as helots or outcastes and pariahs of the human race could scarcely have been permitted to disport themselves in outer garments of red or black silk, though the wearing of under-garments of shawl, velvet and silk was strictly prohibited. The cruel treatment meted out to them is again mentioned on p. 187. But there we are told that they "were not allowed to wear soft clothes or cover their heads with velvet; but they were to wear a black blanket beneath and throw a sheet of cloth over their shoulders."

The error is probably due to a misunderstanding of the meaning of

a word like رالات which really signifies some kind of coarse cloth of hair, or wool, but which has been rendered here as 'silk' Cf Yule's Note on the confusion between Sackcloth and Suclat or Scarlet in H J. 861

Chach treated the Jats just like 'Chandālas Manu says of the latter that "they should be made to live outside the town, that their sole wealth must be dogs and asses, their clothes must consist of the cerecloths of the dead, their dishes broken pots and their ornaments of rusty iron" (Institutes, X 12, 2930) The Jats are said to be the oldest inhabitants of Sind and to have been reduced to a state of serfdom by the Aryan or some other conquerors. Burton gives them a very bad character and says they are idle, addicted to intoxicants, filthy and immoral in the extreme (Sind or the Unbappy Valley II 118). Crooke has pointed out that not very long ago, the Rājputs in the Punjab actually treated the Jats in exactly the same way

"They would not allow the Jats to cover their head with a turban not to wear even red clothes nor to put a crown (Mor) on the head of their bridegrooms, or a jewel (Nath) in the women's nose. They also used to levy seignorial rights from virgin brides. Even to this day, Rajputs will not allow inferior people to wear red clothes or ample loin-cloths in their villages." (Tribes and Castes of the North-Western Provinces. 1896, III 23)

Another parallel comes from Gujarāt -

"In the days of Siddharāj Jaysinha," writes Forbes, "the Dheds were compelled x x x to wear only untwistd cotton round their heads and a stag's horn as a mark hanging from their waists, so that people might be able to avoid touching them" (Rās Mālā Reprint 1924, I 110) The injunction regarding dogs must have been imposed to indicate that they were outcastes [Sii D] Ibbetson says of the Punjāb Nāts—a vagrant tribe of so-called gypsy dancers, acrobats and prostitutes—that "their chief occupation is the keeping of dogs with which they hunt and eat the vermin of the jungle" (Punjab Ethnography, Section 588 apud Crooke, T, C IV, 58)

I 152, l 12 Chach bin Silāij bin Basābas

'Bısās' in K B 38 Sılāij must be Shilāditya, just as Diwāij, the name of the father of Sihāras (140 supra) is Devāditya 'Basābas' may be Vishvāsaka, which occurs in several inscriptions on the Buddhist monuments at Mathurā (Rājendra Lāl Mitra in J A S B 1870, Vol. XXXIX, Pt i p 128) Vishvās Rāo and Biswās still survive as names or surnames in Mahārāshtra and Bengal

I 153, l 1 He patronised the religion of the Nāsiks (Buddhists) and monks

According to Richardson's Dictionary, 'Nāsik' signifies 'devoted to God or virtue' and the word is defined in the *Ghiyāsu-l-Lughāt* also, as "he who worships, prays or performs sacrifices to God"

I venture to think that these Nasiks were the members of a third

sect. They were neither Brāhmans nor Sāmānis (Buddhists), but Jainas. There are many old Jaina remains in Sind, e.g. an old temple in the Pārkar portion of Thar Pārkar district, 14 miles north-west of Virāwah. It contains an image of great sanctity. Near the same place, are the ruins of a very old town called Parīnagar, covering six miles in area and strewn with marble pillars. (I. G. XXIII. 310). At Bhodesar, four miles north of Nagar Pārkar, there are the ruins of three old Jaina temples which are at least six hundred years old. (I. G. XVIII. 299). It may be noted that Brahmanābād also lies in the Thar Pārkar district.

87

I. 154, l. 18. Dharsiya resided for some time at the fort of Rāwar, of which Chach had laid the foundation, but did not live to see completed.

Haig thought that Rawar must have been at considerable distance from Brahmanābād-about eighty miles at least-as two strongly garrisoned fortresses-Bahrur and Dahlila-each of which sustained a siege of two months in succession, stood between them. As Dahir, besides, is said to have spent the summer months at Rawar, where the cool breezes blew, he locates it on the Eastern Nārā in Lower Sind, at least 80 miles from Brahmanābād and 70 miles south-east of Nirūn, which lie identified with Haidarabad. (I.D. C. 63-4). Cousens rejects this view and opines that Riwar was much further north, about twenty-five miles west or west by south of Alor, just below Kingri. Raverty, on the other hand, placed Rawar at about ten miles west of Brahmanahad, but Cousens ascribes this to his erroneous location of Nirun, not at Haidarabad itself, but about 35 miles south of it. Raverty was thus obliged, Cousens argues, to bring Rawar also much farther south than it really was. (A. S. 28 note). The passage which is the subject of this note shows that Rawar was in Middle Sindh, the territory assigned to Dharsiya, and not in Upper Sindh near Alor, which belonged to Dahir. The allusion to its milder climate (155 infra) and the other references at 167, 170. 171, 174 infra, all indicate that Rawar was somewhere south of Brahmanābād and north of Nirun, (which two places are only 47 miles apart), if Nirun is Ḥaidarābād.

Rāwar is not mentioned by any of the Arab travellers and Mīr M'aṣūm even confuses it with Alor (Aror), an error which has entirely vitiated his summary of the *Chachnāma* and misled later writers. But a town called Rāwar does appear to have been in existence so late as 1612 A. C. The India Office Library contains a translation in Persian verse of the Pehlevi 'Dinā-i-Mainōg-i-Khirad, or 'Opinions of the Spīrit of Wisdom,' which was made in that year by a Zoroastrian named Marzbān, residing at Rāwar in Sind. (Sachau, J. R. A. S. New Series. IV. 24; West, Pahlavi Texts, III in Sacred Books of the East, XXIV, Introduction, p. xxiii).

I. 156, l. 2. Hajjāj obtains permission to leave the capital.

The caption is manifestly wrong. K. B.'s translation is, "Hajjāj

asks for permission from the seat of the Khilafat to send a fresh expedition" (p. 71) This is undoubtedly what the author meant See Biladuri (119 ante) and what Elliot himself says at 431 infra

I 158, l 16 God grant that his resolution may be fulfilled

Such a prayer is obviously out of place and uncalled for in this context. The author knew that the country had been conquered, long before the year in which he sat down to write his narrative of the triumph of Muslim arms. Kalich Beg renders the passage very differently and much more rationally thus "He [Muhammad-i-Qāsim] prayed to the glorious God to give enlightened reason and right thought to the people of Arabia for their guidance and to make it possible for them to fight successfully against the infidels" (p. 93). It will be seen that the prayer is here rightly put into the mouth of Muhammad-i-Qāsim and not that of the author.

I. 159, l 12 And the river Sindhu Rawal flowed to the north of the selected ground

Haig suggests that the right reading is ران حوي سده اول المده (اول المده المد

K B's rendering is "Muhammad Qāsim encamped on the sand hills near the gate of the town, since there was no other open field for a battle and there was a flood of rain-water all around, and to the north the river of Sind was flowing" (p 9!) This shows that neither ادل nor ادل سند ادل was to be found in his Mss مدر ادل 'Sindha of Aral' seems meaningless and if دهند ادل is right, perhaps we should read دهند ادل 'The Dhānd, or Water-channel of Aral'

I. 160, l 18 At a place called Nilhan on the banks of the Kumbh

The name is uncertain and there are the variants, 'Nidhān' and 'Budhān'. (K B 95) Haig thinks it must be Bilhān, a village on the Manchhar lake, seven miles west of Se'iwān (I D C. 58) Raverty insists that the name is 'Nidhāhah' or 'Nidhān' (Mihrān 234 Note) He holds that 'Kumbh' is the name of a river and he puts it into his map and shows it as running from a little west of Alor and flowing about ten miles east of Sehwān down to Hālā Cousens, however, denies the existence of any such river. (A S 4). Haig understands 'Kumbh' as a

common noun meaning 'Lake' and this 'Kumbh' must, he thinks, be Lake Manchhar on which Bilhān still stands. In this connection, I may just note, without unduly stressing the point, that Sīsam also is said to have been situated on the banks of the 'Kumbh'. The modern village of 'Shāh Ḥasan', with which Haig and Cousens identify Sīsam does stand at the western end of Lake Manchhar. In any case, there are no solid grounds for denying the existence of Lake Manchhar in the days of Muḥammad, while the existence of any river named 'Kumbh' is nothing more than a speculative conjecture.

I. 160, l. 7 from foot. The Rānās of Būdhiya are descended from Au.

They had originally come from the banks of the Ganges, from a place called Aūndhār.

The copyists have bungled the names and the passage is hopelessly corrupt. The meaning assigned to it by Raverty is even more unsatisfactory and incomprehensible than Dowson's interpretation. It is; "The chief priests of Budh at Nidhān traced their lineage from Ikrānah [or Akrānah] on the Gang, which they call Adward-Bihar." (Mihrān, 234 note).

Raverty does not explain where this Ikrānah or Akrānah is to be found. The fact is that he has read the name wrongly, even if it is granted that some such name was written in his copy. There is a place called Ikrāna (not Ikrānah), three miles from the left bank of the Ganges and 43 cast of Ghūzīpur town. Lat. 23°-43′N, Long. 84°-20′E. (Thornton, s. n. Ikouna or Ekouna). Ikauna is now in Bahrāich taḥṣīl (I. G. VI. 212) and is shown in Constable 28 B b. It is really about one hundred miles distant from Adwand-Bihār or the town of Bihār. Lat. 25°-11′ N. Long. 85°-31′ E. and the two places cannot possibly be the same. Adwand-Bihār, moreover, is not on the Ganges, but about twenty miles away from it. K. B.'s version may be cited to show that there was no reference in his Mss. either to the 'priests of Budh' or to 'Ikrānah.' (p. 95.) It is, "The princes of Būdhiya whose origin was from Gang, commonly known as Dandohar,"

I. 160, last line. But the Bahliks and monks have told methat this country would be conquered by the Muhammadans.

Dowson has left the first word untranslated, because in has no meaning whatever either in Persian or Arabic. I venture to suggest that the right reading is in Bhikuk—Sans. Bhikshuka, the general designation of Buddhist priests. They were supposed to be wonderfully proficient in astrology.

I. 161, l. 2. He placed a chief whose name was Pahan at their head.

Kalich Beg's Ms. reads 'Free 'Bahsabbi' (p. 96). I venture to suggest that the right reading is Free or 'Bhaṭṭi 'or 'Bhaṭṭi 'or 'Bheṭṭi.' The commander was, probably, a Bhaṭṭi Ṭhākur or Chief whose name the author was not acquainted with. The tribe is frequently mentioned in the Chachnāma and some of its leaders not only submitted to the invader

but acted as his auxiliaries At p 167 infra, Dowson makes the author say that "the Bheti Thakurs had entered the Arab service," and K. B. calls them 'Thaku of Babhsi' (124) I have shown elsewhere that in is miswritten for in Behat, ie, the Jhelum See the note on 104 ante. I. 162, l 16 When Kākā had invested him with the robe

This is an evident slip Read 'himself' instead of 'him' It was Kākā himself who was invested with the dress of honour. K. B (p 97) renders it correctly and says it was Kākā who "put on the robe of honour" The Sanskrit form of Kākā is probably 'Kakka,' which occurs frequently in old Hindu records and dynastic lists. (Duff, C I 66, 94, 96, 97, 301)

I 163, l 19 In the vicinity of it [Nirun] there is a reservoir.

Raverty supposes this to be the Sonhāri Dhānd, as it is now called (Mihrān, 234 Note) It is near Jeruck and not far from Helāi, which is about thirty-five miles from Haidarābād But this supposition is only a corollary of his location of Nīrūn, not at Haidarābad, but at about 35 miles south of it. If Nīrūn was, as Haig, Cousens, and many others think, Haidarābād itself, the lake cannot be the Sonhāri Dhānd, on account of the distance. Both the hypothetical identifications put forward by of Raverty must stand or fall together (See Cousens, A S 131 note)

I 163, last line That part of the territory ... which is opposite the fort of Baghrur (Nirun) on the Mihran is taken

'Aghror' in K B 99 Raverty reads 'Laghiur' or 'Baghrur' The identity of Baghrur and Nirun which is postulated in the parenthesis is quite inadmissible Baghrur is mentioned by Biladuri in juxtaposition with Alor and is explicitly distinguished from Nirun by him. (p. 122 ante). It lay east of the Mihran, while Nirun was situated, not on the river itself, but at some distance to the west of it. (Mihran, 235 note)

I 164, l 18. Muhammad Kāsım hears that Dāhır Rāi had proceeded to Nīrūn.

This caption is wrong and misleading Dāhir never went to Nīrūn in person. What he really did was to send the old Sāmāni, who had been governot of the town, with a letter addressed to the Arab general, when he heard of the latter's arrival at Nīrūn. What K B says (103) is "Rāi Dāhīr receives the news of Muhammad Kāsim's arrival at Nerūn." 'And this is undoubtedly right as Bilāduri states that Muhammad "went to the banks of the Mihrān and remained there. When this news reached Dāhir, he prepared for battle" (121 ante)

I 165, l 8 from foot Dahir consults with Sisakar, the minister

'Sihākar' or 'Shiyākar' in Dowson's Ms B The original Sanskrit form may be 'Shikshākar,' Teacher, preceptor He was probably a learned man who had been Dāhir's Guru But it may also be 'Yashaskara,' which was borne by, among others, a Brāhman who became king of Kashmīr about 939 A.C and died in or about 948 (Duff, CI 89, 91, 294).

I. 166, l. 16. He ordered Sulaimin bin Tihan Kuraishi to advance boldly with his troops against the fort of Aror.

.Raverty's translation is فرمودكه أو بالشكر خود بغرور رو درمقاً بل حصار إرور است "He ordered him to go with his army to Baghrūr and take up his position opposite to the fort of Aror." (Mihran, 235 note). Haig also understands the sentence in the same way and takes it to mean that Sulaiman was " to observe Alor, by which the river was then running and hinder Fufi, the son of Dahir, from any diversion against the communications of the invaders." (I. D. C. 62). As regards the situation of Baghrūr, Haig was inclined to identify it with Bhakkar (Ib. 62), but Raverty and Cousens think that Bhakkar was not in existence at this time. Their theory seems to be that the island on which Bhakkar stands emerged only after the great change in the course of the river, two or three centuries later and "the river did not flow in that bed in those days." (Cousens, A.S. 23 Note). On the other hand, it may be noted that Biladuri always brackets together Alrur and Baghrur (122, 123 ante), and the Chachnama also states that Baghrur was in the country of Alor (164 ante) and stood just opposite to the fortress of that name [مقابل حصار ارور], as Ms. A quoted in Dowson's footnote puts it.

I. 166, l. 20. To watch the road with 500 men, by which Akham might be expected to advance in order to cover Gandāva.

Raverty understands Akhām or Aghām as the name, not of a person, but of a place on the Purāṇā Dhoro, which lies 25 or 30 miles south-east of Ḥaidarābād. He also reads 'Kandārah' (Kandhāro) and not 'Gandāva.' Tifli [or Ṣalabi], he thinks, was stationed on the road to Akhām to watch the territory of Kandārah. (Mihrān, 237 note). As Dowson's Ms. B read and K. B. also states that "Saalabi was ordered to go to the road of Agham, to keep a watch over the country of Kandrāh" (p. 123), there appear to be good reasons for rejecting 'Gandāva.' The Kandhiāro district was occupied at this time by the Northern Sammas (I. D. C. 79). They were the Sammas who gave a great ovation to Muḥammad-i-Qāsim with drums and dances when he passed through their district on the way to Alor (191 infra).

I. 167, l. 1. The Bhetī Thakūrs and the Jats of Ghazni who had made submission and entered the Arab service.

K. B. has "Thakurs of Babhsi and the Jats" (p. 124). Haig (I. D. C, 61 n) and Raverty (Mihrān, 235 note) agree in reading "Western Jats," i.e. the Jats occupying the western parts of the province and this seems to be undoubtedly preferable to 'Jats of Ghazni.' The Eastern Jats are mentioned in the Chachnāma as forming part of the army of Dāhir. (Tr. K. B. 137). These Western Jats were probably the followers of Kākā bin Kotal, the ruler of Būdhiya, who was a "Jat Sāmāni" (161-2 ante) and who had submitted to and entered the service of the invaders. Bilādūri also says that four thousand Jats were recruited and brought over as auxiliary troops from Sīwīstān. after

its conquest by Muhammad bin Mus'ab (121 ante). This contingent may have been made up of the 'Western Jats'

I 167, l. 3 from foot. Between Rawar and Jewar (Jaipur) there was a lake, on which Dahir had stationed a select body of troops

The name of the lake near Rāwar where the Muslim forces crossed the river is written in the Manuscripts of M'asūm's History as or Gujri, Gūjri and Kanjri Raverty supposes it to be Kingri, which lies about twenty miles west of Alor. (Mihrān, 240 note) But Cousens points out that if he is right here, he must be wrong in fixing Rāwar itself about ten miles west of Brahmanābād, which is more than a hundred miles south of Alor. (A. S 20 note) In other words, if the lake was only about 20 miles from Alor and also near Rāwar, Rāwar could not have been ten miles to the west of Brahmanābād.

But this name Gujri or Kanjrı does not occur anywhere in the Chachnama or in Biladuri and it is probably only a conjecture of M'asum's or a repetition of some local tradition or legend Moreover, M'asum's account of the battle is vitiated by the erroneous supposition that Rawar was the same as Aror If Rawar was somewhere between Brahmanābād and Nirūn, the lake could not possibly have been that of Kingri near Aror There is another Dhand or lake called Kunjur or Kinjore, lying south-west of Haidarabad and there is some phonetic resemblance between Kanjri and 'Kunjur' but M'asum's knowledge of the ancient geography of Sind was, at best, indifferent and it is hazardous to build anything upon his statement. Haig says that the river was crossed by the Arabs somewhere to the south-east of Nīrūn (I D C 63) but lake Kunzur lies to the south-west of Nirun The Chachnama puts the crossing at Jham, the stronghold of the district called Bet, but neither Jham nor Bet can be identified with any approach to certainty, though the first name bears some resemblance to the modern Jhimpīr Constable 26 Ac.

When his minister Sisākar heard of it, he said 'Alas! we are lost That place is called Jaipur or the town of victory' Dāhir said with anger, 'He has arrived at Hindbāri, for it is a place where his bones shall lie'

K. B reads 'Hab' [Hat] Bari'. (p 132) This anecdote must be unhistorical and an expost facto concoction of some imaginative Muslim Such a play upon words is possible only in Persian and is founded on the morphology of the Semitic script, of which Dāhir could not have possessed any knowledge. It is a since of which Dāhir could not have possessed any knowledge. It is a since of the tween Jatpūri between Jatpūri or Matpūri or Hatbāri from Hat bone. The pun depends on the fact that the bodies of the letters of the toponyms are identical, the difference lying only in the discritical point or Nugta. The story seems to have been interpolated, either by the author or trans-

lator, only to give the narrative a dash of rhetorical colouring in the Muslim style.

1.170, 1.2. Dāhir was slain at the fort of Rāwar on Thursday, the 10th of Ramazān, in the year 93.

10th Ramazān 93 H. = 20th June 712 was a Monday,

10th Ramazān 92 H. = 1st July 711 was a Wednesday,

10th Ramazān (Ruyyat) 92 = 2nd July 711, was a Thursday.

The chronology of the Chachnāma is utterly lawless and inconsistent with itself. Dāhir is said to have been killed in Ramazān 93 H. It then took some time to capture Rāwar and the reduction of each of the fortresses of Dhalīla and Baghrūr took two months. But we are told that Muhammad began the siege of Brahmanābād in Rajab 93 and that it fell six months afterwards on the last day of Zi-l-hijja of that year. (177 infra).

All this is manifestly wrong and inextricably confused. The only criterion available or of any use appears to be the week day and the correct chronology may perhaps be ascertained by the application of that test. The correct date must be 10th Ramazān 92 H.

1. 172, l. 16. And the other to throw naphtha, fardāj, (?) and stones during the night.

'Fardāj' is a doubtful reading and Dowson could make nothing of it, as there is no such word in the dictionaries. I venture to suggest that غراستک is a copyist's error for غرواه . Richardson says غراستک or غرواستک signifies 'the stone ball of a cross bow'. This so-called 'fardāj' was really a stone-sling or balista which hurled large stones. Barani speaks of siwastān. K. B. renders the phrase here as 'naphtha torches and burning stones' (153), but a few pages further on, the same expression is translated as "naphtha arrows and battering-ram stones" (156). This shows that the conjunction is an interpolation and that the right reading is

This [or غراد looks in Persian writing very much like غراد. Shams-i-Sirāj in his description of the siege of Nagarkot says that both sides possessed *Manjāniqs* and that 'Arādah-stones were hurled by both, سنگ غراده خاست (T. F. 188, 1. 4).

I. 174, l. 1. After this, give no quarter to any enemy except to those who are of rank. This is a worthy resolve, and want of dignity will not be imputed to you.

The sentence runs thus in Dowson's Ms.

دشهن رامان مده الا همكنان ترا بزرگ است رای وفتور شوكت حمل كنند

He thinks a negative is required here. The text is evidently corrupt and it may be suggested that we should read الا هَمَنَانَ تَرَ الرَّاكَ راى After this give no quarter to any enemy, otherwise your coadjutors will attribute to you weakness of judgment and lack of

majesty, ie the power to command"

I 176, l 19. From that place to Brahmanabad there was distance of one parasang

It is evident that something is amiss or has been omitted here. What is meant by 'that place' is not at all clear The copyist of Dowson's Ms. has missed out a clause or sentence. Kalich Beg's version dispels the obscurity.

"Some say that after taking Dahlila, Muhammad Kāsim ed to Banuna son of Dharan, the work of collecting and superintending the boats along the bank of the river from Dahlila to a place called Wādhātiya The distance between that place and Brahmanābād was one league" (K B 158) 'That place' must be 'Wadhātiya'

I 176, l 8 from foot Muhammad Kasım marched and encamped on the stream of the Jalvali to the east of Brahmanābād

K B speaks of it as "the small channel of Halwai" (158) Dowson's suggestion that this may be the Fuleli will not bear examination. It is rejected by Haig on the ground that the Fulch did not exist at all in the 8th century "It is a recent inundation channel which has its head only in the recent course of the Indus, some twelve miles north of Haidarābād, a course which was taken by the river only about 1758 A D" (I D C 54) Raverty also is sure that the Jalwali cannot be the Fuleli, as the latter is thirty miles south-west of Brahmanabad (Mihran, 241 note), whereas this Jalwali appears, from the context, to have been in close proximity to the city Haig surmises that it may be an old form of Jarari, the name of an extant branch channel of the Indus in this neighbourhood. (I D C. 135)

I 176, l 2 from foot Jassya had gone to Chanir.

Raverty is sure that it is 'Chanesar' He locates it at about 23 miles south-west of Dırawal and about 20 west-north-west of Ghausgarh or Ruknpur. (Mihran, 426). Dowson notes that the name may be read as "Chansir" also and that it seems to be the same as the "Chanesar" of p. 179 infi a K. B calls it 'Janesar' (p 158)

I 177. l 2 The battle commenced on Saturday, the first of Rajab six months passed in this manner On Sunday in the end of Zi-l-hijja A. H 93, Jaisiya came back etc.

1st Rajab 93 = 13th April 712 was a Wednesday But 1st Rajab 94 = 2nd April 713 was a Saturday 29th Zi-l-hijja 93 = 6th October 712 was a Thursday But 29th Zi-l-hijja 94 = 25th September 713 was a Sunday. See my note on 170, 1 2 ante.

I. 178, l 11. Jaisiya son of Dāhir goes to the Rāna (of Kashmīr)

K B reads 'Alafi' instead of 'Jaisiya.' (p 160) He points out that the caption is wrong and does not occur in the better manuscripts. It was 'Alafi' who really went to Kashmir at this time Jaisiya separated from

him and proceeded by way of the desert, first to Jaitūr [or Chaitūr], then to Kuraj, and it was only after passing some time there that he went to Kassa (on the borders of Jālaudhar), which is believed on fairly good grounds, to be meant for Kashmīr (197 and 201 infra).

The next heading (l. 15) "The Rāi of Kashmīr gives presents to Jaisiya, son of Dāhir" is also founded on error. The presents were given to the "Alāfi," not to Jaisiya. (See Dowson's note 2). The discrepancy or rather the direct contradiction between the words of the caption and the import of the paragraph itself did not escape him, but he could not account for it or clear up the confusion, as the fault lay with his Mss. The fact that Ḥamīm, [or Jehm] the son of Sāma the Syrian, is said to have been the companion, deputy and ultimately the successor of the fief-holder, also shows that the grant must have been made in the first instance to the Arab Alāfi.

I. 179, l. from foot. Muhammad Kāsim granted them protection on their faithful promises, but put the soldiers to death, and took all their followers, and dependents prisoners.

The context and the narrative which follows clearly shows that the translator must be writing in anticipation of the event. The soldiers were not put to death at this time and could not have been, as Muhammad had not become master of the town. This and the following sentence embodies only the conditions on which the civil population clandestinely and traitorously agreed to deliver the city to the invader. They were the terms provisionally granted to the chief merchants of the city, subject to ratification by Hajjāj, to whom they were to be submitted for sanction. That sanction was still to arrive and it was only after its receipt and the actual surrender of the town, subsequently to the mock assault and pretended sally, that the fighting men were killed and those 'who had arms, taken prisoners' (180 infra). The correct rendering would be "Muhammad-i-Qāsim granted them protection on their giving their promises, but he was to put the soldiers [the fighting men] to death and to take all their followers and dependents prisoners."

I. 182 and foot note. Slavery, the tribute and the poll-tax. [Bandagi wa Māl wa Gazīd (or 'gazand') as Ms. A. has it].

Gazīd means 'bit,' Guzīd signifies 'chose, selected,' Gazānd signifies 'injury,' but the right reading here must be guzaid خريد which is defined by Richardson as 'tribute imposed by conquerors.' The Ghiyāṣu-l-lughāt states that it is synonymous with Bāj, Khirāj and also the Jizya which is imposed on infidels. Gardezi uses the word أَرَا اللهُ أَنْ اللهُ اللهُ اللهُ أَنْ اللهُ الله

I. 183, l. 13. Muhammad Kāsim then ordered twelve dirams weight of silver to be assigned to each man, because all their property had been plundered.

This is very obscurely worded here The real meaning seems to be that after the census was taken, Muhammad issued orders for the jiziya or poll tax to be fixed at its lowest limit of twelve dirhams. The inhabitants were all rated in the third or lowest class, and had to pay only 12 dirhams per head, because the ten thousand who were 'counted,' that is, assessed and declared liable to pay, had been reduced to a state of indigence on account of their houses having been robbed and plundered by the invaders.

I 186, l. 16 They were to allot three dirams out of every hundred dirams of capital

The reference seems to be to 'revenue' and not to 'capital.' They were to allot three dirhams out of every hundred dirhams of the land-revenue originally due to the State (اصل مال) to these indigent Brahmans for their maintenance. The rest they were to pay into the State Treasury, and it would be taken into account (i e credit for it would be given to them) by the officers of the Huzur, i e, His Excellency the Nawāb [or Deputy Goyernor] appointed by Muhammad-i-Qāsim. The right reading appears to be المعالي عمور أوال not المعالي عمور أوال not المعالي عمور أوال so in Dowson's Ms. See his footnote 2. The conjunction must be deleted 'Huzūr' is often used for the supreme or central authority at head-quarters in the historical literature and in ordinary parlance even now.

I 190, l 12 He [Muliammad-ι Qāsim] marched from that place (Brahmanābād) on Thursday, the 3rd of Muharram Λ Π 94

3rd Muharram 94 H was 9th October 712, Sunday.

3rd Muharram 95 H [Ruyyat] was 28th September 713, Phursday.

If the week day is right, the correct year must have been 95 H.

See my note on 177, 18 3rd Muharram 95 H would fit in fairly well, as it would leave about 17 or 18 months for the subsequent operations against Alor, Sikka and Multan Muhammad was recalled and put to death only after the demise of the Khalif Walid in Jumadi I. 96 H. (437 post) Hajjaj had died in Ramazan 95 H (Houtsma, E I. Vol. II 204). I 190, 13 He stopped at a village called Manhal.

"Mathal" in Ms B and 'Musthal' in K B (p. 173) The name is supposed to survive in a village now called Shah 'Ali-Muthalo, which lies four miles south of Brahmanabad by Cousens (A. S 31). 'Danda' (l. 15) is probably not a toponym but the common noun, 'Dhand,' which is well defined by Thornton as "an extensive and permanent piece of stagnant water left by the Indus, after it has retired to the channel to which it is confined in the season when it is lowest'' (Gazetteer, 541) 'Danda and Karbaha' should probably be read as 'Dhand-i-Wakarbha' or 'Dhand-i-Ükariya,' the 'Pool of Wakarbha [Wakariya or Ukariya] A son of Dihir was named Wükiya [Ukariya?] (194 infra note) Ul a and Ukar are even now common personal names.

1. 193, l 22. One was a Samint whose name was Bawadu and the

other Budchi Bamman Dhawal.

K. B. reads 'Bāwad' and 'Zaman (or Baman) Dhol' (p. 173). The first name may perhaps be 'I' 'Nārada' and the second 'Buddhivarman Dhaval.' Buddhivarman Pallava is mentioned (Dufi, C. I. 299). 'Dhaval' also occurs very frequently in old records. This name was borne by a Rājā of the early Chālukya dynasty of Gujarāt about 640 A. C. (Dufi, C. I. 279), by a Rāshtrakūta and also a Vāghelā chief and by several others. (C. I. 103, 252). It is found also as a suffix in Vīradhaval, Yashodhaval, Raṇadhaval, Pratāpadhaval, Prasiddhadhaval, etc. It occurs, morcover, at 174 ante, where Jaisiya is said to have written letters to "Dhawal, son of Chandar", his cousin. The names of these men are specially mentioned, perhaps, to indicate that one of the two delegates selected was a Buddhist and the other a Brahman, as the object was the equitable adjustment of the burdens on the followers of each religion.

I. 196, l. 1. Muhammad Kāsim said, " Does not your God know who has got his bracelet?"

[Sir R.] Burton tells this story with some variations of Muhammad-i-Qāsim and the idol-temple of *Deveal*. Muhammad does not take away the bracelet but puts his own mailed glove on the hand of the image. (Sind or the Unhappy Valley, I. 133). Bilāduri has an analogue, but it is about an idol at Zūr in Sīstān. When 'Abdu-r Raḥmān conquered that province in A. H. 35, the idol's hand, he says, was cut off and the rubies in its eyes plucked out. The *Marzbān* or governor was then asked to note how 'powerless was his idol for good or evil'. (Reinaud, *Mémoire sur l'Inde*, 173; E. D. II. 413-4).

This Zūr was in Zamīudāwar and in the vicinity of Lake Zaranj or Zarrah, which is formed by the Helmand and the Farrah Rūd. (Elphinstone, Account of the Kingdom of Caubul, Bk. iv. ch. iv. apud E. D. II. 579). The Sea or Lake of Zūr is said to be identical with the Lake Hāmūn of modern maps. (Beveridge, Tr. Akbarnāma, II. 415 note).

Alberuni has another version of the same tale. He says that when Muhammad sacked the temple of the Sun in Multan, he 'hung a piece of cow's flesh on the neck of the idol by way of mockery.' (India, Tr. Sachau. I. 116). Idrīsi repeats this variant. (Tr. Jauhert, I. 167; Reinaud, Mimoire sur l'Inde, 165).

I. 200, I. 2). It is not checkmate; that sheep must not be slain.

"Sheep" can have no sense or meaning in this context. K.B. has 'chessman' instead (p. 185), which seems to be preferable, as they were playing that game. The literal or exoteric meaning of the words uttered might then be, "There is no checkmate, that pawn must not be taken." The names of the myrmidons are spelt by Dowson as 'Kabīr Bhadra' and 'Bhaiū' (ante 199, last line). They may, perhaps, be restored to 'Kālibhadra' [or 'Kālabhadra'] and 'Bhairay.'

I. 201, l. 1. Till he reached the land of Kassa on the borders of

Jālandhar The chief of it was called Balharā, and the women of the country called him Astān Shāh.

This 'land of Kassa' is most probably Kashmīr, the land of the people called 'Khasa,' or 'Khasha,' who are frequently mentioned in the Rājatarangini and other Sanskrit works. They are stated to have "lived in the region comprising the valleys lying to the south and west of the Pîr Pantsāl range between the Jhelum and Lohar and Kishtwār. They are identical with the modern 'Khakha' tribe, to which most of the petty hill chiefs and gentry in the Vitastā valley below Kashmīr belong." (Sir A Stein's Note to Tr. Rājatarangini. Bk I verse 1317) Sir George Grierson says that these 'Khasas are found not only in Kashmīr but in the Kumāon and Garhwāl. "The great mass of the Aryan-speaking population of the Lower Himālayas from Kashmīr to Darjeeling is of 'Khasa' descent." (Indian Antiquary, 1914, p. 151)

According to K B's Mss also, Jaisiya 'arrived at Jālandhar in the land of Kashmīr' (p 185), and this may be right, as the name by which the king is said to have been popularly known does point to Kashmīr 'Āstān Shāh' looks like a corruption of 'Ādashtān Shāh' Cf Wākhān Shāh, Bolor Shāh, etc. 'Ādashtān' was the name by which the capital of Kashmīr was known (E D I 64) 'Ādashtān' is the Sanskrit Ādhishthāna which signifies 'capital, chief city' (Sachau, II 181)

I 202, l 21 Kaksa, son of Chandar.

This may be 'Kākutstha,' a name which occurs in the Rāmāyana and also in the list of the Pratihāra rulers of Qanauj about 740-755 A C (V Smith in J R A S 1909) This Kākutstha was the successor of Nāgabhatta, the founder of the kingdom. (Vaidya, H M H.I II 100)

I 205, l 17 And silver to the weight of sixty thousand dirams was distributed, and every horseman got a share of four hundred dirams weight

So also in K. B 190, but it can hardly be correct. If the total amount was 60,000 dirhams only and each horseman's share was 400, there could not have been more than 150 horsmen all told, in Muhammadi-Qāsim's army, when he besieged and captured Multān, which seems absurd

1 205, l 7 from foot There was a chief in this city [Multān], whose name was Jībawīn, and who was a descendant of the Rāi of Kashmin xxxx He always occupied his time in worshipping idols

The name is written in a multiplicity of ways as حنویں -حور - حویں - عام and has eluded all attempts at restoration. I beg to suggest that the right reading is عسليو 'Janbadeva' [Sambadeva] Sāmba, son of Krishna by Jāmbavati, the daughter of Jāmbavat, was made king of Multān after the defeat of Bāna the Asura Jāmbavat had presented to Krishna the Syamantaka Mani [Gem or Talisman] "which yielded daily, eight Bhārs of gold", along with his daughter (Vishnu Purāna, Tr. Wilson Ed.

Hall, iv. 76-79). Simba was afflicted with leprosy, in consequence of an impression of the very irascible sage Durväsas whom he had insulted. Simba was then led, by the advice of Nārada, to establish himself in the groves of Mitra-vana and he was, thanks to the assiduous worship of Mitra (the Sun-god), cured of his leprosy. He then erected a golden statue to Mitra in a temple and the worship of the Sun was thus begun by Simba. (Bharishya Purāṇa, quoted in Wilson's Note. Ibid. V. 381, Works X. 381; A. G. I. 232-3). Alberūni also notes that one of the many names of Multān was Sāmbapura, 'city of Sāmba.' (India, Tr. Sachau, I, 296). Elsewhere, he states that "the Hindus of Multān have a festival which is called Sāmbapurayātrā; they celebrate it in honour of the Sun and worship him. (Ib. II. 184).

The Indian Museum and other collections possess several silver coins weighing about 50 grs. each and of the Indo-Sassanian type. There is a Brāhmi legend on the obverse in which the king, who was probably an Ephthalite, is called Vahi-tigin or Shahi-tigin and is believed to have ruled at Multan about 500 A.C. On the reverse, there is the bust of a deity generally believed to be that of the Sun-god of Multan and a سف تنسف ثبت الله Pehlevi legend which was read tentatively by Thomas as سف تنسف ثبت 'Saf Tansaf Tef' and supposed to stand for 'Shri Tansaf Deva.' There is also in the field on the obverse, a legend in corrupt Greek letters which has been read as 'Shri Shono.' May not the real name be 'Shri Samba [or Somba] Deva' and the same as the Janbawin' [or Jambadeva], who is said to have been the founder of this Sun-temple? (Thomas, Pahlavi Coins of the Arabs, p. 92; I. M. C. I, 231, Pl. XXV. I; Cunningham, Coins of the Later Indo-Seythians, 123; White King Catalogue, No. 911). A Treasure of three hundred and thirty I. 206, l. 1. buried there.

The sentence is not found in K.B.'s version (p. 190). It is obviously inconsistent with the immediately preceding averment that "the treasure exceeded all limit and computation." A few lines lower down also, it is stated that "thirteen thousand and two hundred Mans weight of gold [not 330 only] were taken out of the forty jars."

A probable explanation of the discrepancy is that 330 Mans of gold were buried, not in the 40 jars altogether, but in each and every one of the forty; $330 \times 40 = 13209$. This would be in fair accord with the statement of Khurdādbih. He makes the total amount of the treasure 40 Bhārs, each Bhār containing 333 Mans; $(40 \times 333) = 13320$ Mans, or 26640 Ratis or Arab pounds at two Ratis to the Man. (p. 14 ante). To put it differently: 'Ali Kūfi says that there were forty jars, Khurdādbih that there were forty Bhārs. Each jar of 'Ali Kūfi must have held a Bhār, that is, 330 or 333 Mans.

I. 206, l. 4 from foot. It is found that sixty thousand dirams in pure silver have been expended for Muhammad Kāsim, and upto this date there have been

received ...altogether one hundred and twenty thousand dirams weight

I 208, l 2 When the army reached as far as Udhāfar

Variants اودهابور اوردها (KB 192). M'asūm turns it into 'Depālpur,' but his authority on such a point is negligible Raverty says it must be Odipur, fourteen miles south of Alwāna on the Ghaggar, and he is followed in the CH.I. (III.7). But the reading is altogether uncertain and the place impossible to determine.

I 216, l 19 Hāmūn carried on the government in the fort of Dahak, and she deputed her brothers to govern Muhammad Tūr and Thāri.

Thari is an exceedingly common place-name in Sind Haig thinks that this Thari was on the right bank of the Western Puran, about 6½ miles east by south of Muhabbat Dero. The change to Tur was, he surmises, 'due to the drying up of the river' (I D C 75). Elliot locates it somewhere near Badin, on the Gungro river, about 40 miles further to the south (404 post) 'Dero Mohobat' is marked in Constable 26 B c. It is now in Haidarabad district Thar, Thari, Thari, Thal Thul mean 'mound' or 'old ruin,' and any spot where there are vestiges of ancient occupation is indiscriminately so called in Sind. Dahak seems to be called Dirak in the Tarikh-i-Tahiri, where it is stated that Muhammad Tur was included in the paragana of Dirak. (256 infra). Elliot assures us that the ancient pargana of Dirak was represented, in his time, by the divisions of Chachgan and Badin on the borders of the Tharr or sandy desert between Parkar and Wanga Bazar (403 infra)

I 222, l 3 from foot Having got two small fine iron hooks, he tied a silken line to them

This saems to be the rechauffe of a folk-tale which is preserved in the Tibetan Kah-gyur The hero there also is a prince named Jivaka, the son of king Bimbisara He comes across in his wanderings, a man carrying a bundle of wood, whose bones and internal organs were visible When asked the reason of his looking like a living skeleton, he replied that he had been in that condition ever since he began to carry the bundle of wood The prince purchases the bundle from him and finds in it a Mantgem or talisman—which had the power, when placed before any invalid, of revealing the nature of the internal malady, and illuminating him just as a lamp lights up the objects in a house. He then cures, by its means,

two men who had been suffering from an incurable headache, by drawing out its cause—a centipede which had crept into their brains. (Tibetan Tales. Translated from the German of A. Schiefner by W. S. Ralston. 99-100 and 103).

The extraordinary mode of treatment said to have been adopted by Dūda bears also a most curious resemblance to another circumstantially described by Ibn Khalliqān in his biographical notice of Ḥajjāj ibn Yūsuf. That tyrant, he tells us, "was afflicted by a cancer in the stomach and he was cured by a physician who tied a piece of meat to a string and passed it down his throat. The string was drawn out after some hours, when a swarm of worms were found adhering to it." (Mc Guckin de Slane's Trans. I. 356).

Muḥammad 'Awfi also speaks of the renowned physician Zakarriya-i-Rāzi (Rhazes of the Mediaeval European authors) curing a patient of haematemesis by making him swallow some weeds called Jāma-i-Ghūk (Lit. Frogs' Robes). The leeches or worms adhering to the weeds were thus drawn out of the intestines. (Nizāmu-d-dīn, Introduction to the Jawām'i-al-Hikāyāt, I. XX. Story No. 1046, p. 184).

I. 224, l. 8. Malik Ratan also came out of the fort [Siwistān] with his force and the battle began.....Malik Firoz and Ali Shāh Turk were at this time in the vicinity of Bhakkar.

There is no reference to these events in the Delhi historians, but M'asum's account is substantially corroborated by Ibn Batuta who passed through Sind in 734 H. (1333-4 A.C.). He says that some time before his arrival, 'Imadu-l-Mulk Sartīz, the governor of the province, had ruthlessly put down a tribal revolt which was centred round Schwan. The rising was due to the nomination by Muhammad Tughlag of a favourite Hindu accountant named Ratan as castellan of Schwan. The elevation of the misbeliever so exasperated the Samma chief Wunar [Unar] and a Musalman Amir named Qaisar that they combined together and attacked Ratan by night and slew him. 'Imadu-l-Mulk then came up on the scene to avenge and re-establish his master's outraged authority. Wunar fled and sought refuge with his tribe. Qaisar made some resistance and after standing a siege in the fort of Sehwan for forty days, capitulated on terms, but the terms were perfidiously violated and he and the other insurgents were decapitated, flayed alive or cut into pieces. (Defrémery, III. 105-8; M. R. Haig, Ibn Batūta in Sind, J.R.A.S. XIX, Part 3). Ibn Batūta has nothing to say about the subsequent course of events, but there was a recrudescence of the trouble which terminated in the alienation of Southern Sind from the empire of Delhi and the inauguration of Samma dominion in the province.

1. 225, l. 4. After the death of Jām Unar, Jūna of the tribe of Samme received the title of Jām.

Raverty (Mihrān, 329-30) has pointed out that M'asūm's account office. Sammasis full of errors and inconsistencies. Here, he states that Tamāchi

who succeeded Jam Juna was taken captive by 'Alau-d-din (who died in 715H), though the Sammas are known to have come into power only after 734 H He also asserts that Tamachi's son Khairu-d-din was sent back from Delhi and was the Jam who was called upon to surrender by Muhammad Tughlag in 752 H and that Babiniya, Khairu-d-din's son, was the Jam who was carried off as a state prisoner to Delhi by Firuz Tughlag But in the Delhi section (which is reproduced in the Tuhfahtu-l-Kirām at 341-2 infra), there is no reference to any Samma Jam either under 'Alau-d-din or Muhammad Tughlaq and the Jam who was taken captive by Firuz is called Khaii u-d-din, upon whose death in Delhi, his son Juna is said to have been sent back to rule in Thattha According to Shams-1-Sirāj, the contemporary historian of Firūz, the Jām whom Firūz carried off to Delhi, was the brother of Unar and Babiniya, the Jam's nephew and son of Unar was joint ruler Shams states that the administration of the province was entrusted to the son of the Jam and Tamāchi, the brother of Bābiniya, after its annexation to the Empire of Delhi When some time afterwards, Tamāchi rebelled, the Jām was allowed to return to Thattha to suppress the revolt (TF 254, 1.6 f f.=E D III 322, 338)

A dynastic list of the Sammas, very similar to that given by M'asûm here, is found also in the TA (p 635), F (II 318-32) and the Ain, (Tr II 342) The names and regnal periods are not absolutely identical, but the four lists are all derived from one and the same source—the Tārīkh-i Bahādur Shāhi of Husām Khān Gujārāti—as the TA candidly admits (635, 12) The initial date is nowhere stated and the discrepancies make it difficult to construct anything like an exact chronology, but a fairly correct list can be made out on the basis of three or four fixed dates or epochs and two points of contact between the Provincial and Imperial History, which can be determined with tolerable certainty. These epochs or points are—

Accession	n of Jām Unar	736 H. (Circa)
11	" Fāth Khān	801 H [Timūr's invasion]
77	" Nandā	866 H
Death of	f Nandā.	91 4 H

The following series of dates can be then evolved by fitting these points into the framework of the names and regnal periods given in the lists —

Unar	3	years and 6 months	736-740 H.
Juna	13	years .	740-753 H
Bābanīya	15	years	753-768 H
Tamāchi	13	years and some months	768-781 H.
Şalāhuddīn	11	years and some months	781-792 H.
Nızām-d-dîn	2	years and a fraction.	792-794 H.
'Alı Shīr	7	years	794-801 H
Karaņ	11	days.	, 801 H.

Fath Khan	15	years and some months.	801-817 H.
Tughlaq	28	years.	817-846 H.
Mubārak	3	days.	846 H.
Sikandar	1	year 6 months.	846-848 H.
Rāidhan	8	years and months.	848-857 H.
Sanjar	8	years and some months.	857-866 H.
$\mathbf{Nand} \mathbf{\bar{a}}$	4 8	years.	866-914 H.
Firuz	12	(or 14) years.	914-927 H.

I. 225, l. 8. These men crossed the river Mihrān at the village of Talahti.

This must be Talti, about six miles north of Sehwan (Vide note to Vol. I. 309 post). It is said to have been four kos from Sehwan.

I. 225, l. 16. Ulugh Khān then sent Tāj Kāfūri and Tātār Khān to oppose Jām Jūna in Sind.

The whole passage is full of anachronisms, but M'asūm has, in this case as in that of Malik Ratan, stumbled by chance upon a part of the truth and got at least one name correctly. Malik Tāju-d-dīn Kāfūri was governor of Multān and Sīwīstān, during the last years of 'Alāu-d-dīn Khalji. (Barani, T. F., 323, 1. 16). This man should not be confused with the better-known Malik Kāfūr-i-Hazār-dīnāri.

I. 226, l. 2. Sultan Muhammad [Tughlaq] died in the neighbourhood of Bhakkar.

Read 'Tatta' as in Malet and K. B.'s Tr. in History of Sind. II. 43. See also 342 post). Sin (1.5) is Sann, a town in Schwān, eleven miles north of Mānjhand and the same distance south of Amri. (Hughes, Gazetteer, 696). It is about a hundred miles distant from Thattha and the Jām is said to have harassed the retreat of the Sultan and pursued him to that distance. (I. D. C. 80). Constable 26 B b.

I. 226, l. 9. The following story is told of this prince [Jām Khairu-d-dīn].

Fractly the same story is told of Kabak, or Kapak, the son of Dawā, the fifteenth Khān of the race of Chaghatāi, the son of Chingiz, in an old History of the Mongols called Shajratu-l-Atrāk. (Tr. Miles, Ed. 1838, p. 369). The resemblance is so close that it is worth while citing the original. "One day, [Kabak] was riding out for exercise with his servants and in a cave near the road, he discovered a number of human bones. On seeing these, he pulled up his horse and remained in thought for some time and then said to his attendants, 'Do you know what these bones have been saying to me?' His attendants, being surprised at the question, remained silent, when he, answering himself, said: 'They are the bones of men barbarously murdered, who cry to me for vengeance'. He then xxx immediately summoned the hazāra to whom the land appertained and ordered him to examine as to whom these bones belonged.xxx. It was discovered that three years previous, a Karwaun had arrived there from Khorasan, and that this tribe had murdered the whole of the

persons composing it, and had seized their property, and that some part was still in their possession. When this fact was established, the Khan ordered the murderers to be apprehended and the property collected and despatched by a messenger to the chief of Khorasan, that he might search for and produce the heirs of the murdered men. On their being found, they were sent to the Khan, who immediately delivered up the property, with the murderers, into their hands."

It is impossible to say that the two stories are not identical. Either M'asum has 'lifted' the tale from the Shajrat or both have pilfered it from some other source

I. 226, l 9 from foot. Jām Bābanīya.

The name of this Jām has been a puzzle and a pitfall to the later epitomists and commentators. F. speaks of him as 'Māni, the son of Jūnā,' (II 317-8), T A as 'Mānībha' (635, 1 3) and Abul Fazl as 'Banhatiya' (Aīn, Tr. II. 342) Raverty's impetuous assertiveness was responsible for the pronouncement that it was not a name at all, but an epithet or title, is it.e. 'The Founder of Thatta'! (Mihrān. 329 n) But this whimsical conjecture is put out of court by the fact that Bābaniya is said by M'asūm, Muhammad Tāhīr and others to have been the name not only of the father of Unar, the founder of the dynasty but also of that of its most renowned member, Nandā or Nizāmu-d-dīn (224 ante, 273 and 275 post, Malet 47).

The fact is that 'Bābaniya' is a corruption of 'Bāmaniyo', a name which occurs frequently among the ruling dynasties, not only of Sind, but of Kachh and Kāthiāwād It was borne by a Thākor of Rājkot who ruled from 1675 to 1694 A C (B G VIII, Kāthiāwād, 632) The Rājkot chiefs are Jādejā Rājputs belonging to the same clan as the Rāos of Kachh and the Jāms of Jāmnagar 'Bāmaniyo' occurs also in the dynastic list of another Kāthiāwād State named Kotda Sangāni, whose rulers, as cadets of the ruling family of Gondal, are also Jādejās. (Ibid 521-2) A Jām Bāmaniyoji who was the son of Jām Unad is said to have conquered Ghumli and to have ruled in Kachh also about the beginning of the 16th Christian century (Ibid, 566). The name of a Bādshāh (or Jām) Bāmaniyo also occurs in a widely-known Kāthiāwād folk-tale which is related at some length at 690 Ibid

I. 228, l. 13 Sikandar and Kai an and Fath Khān, sons of Tamāchi According to Malet's translation of M'asūm's history, Sikandar and Karan only were the sons of Tamāchi Fath Khān was the son of Sikandar and this is the true relationship of the men It is so stated in Dowson's own version (229, 14 post), T A (636, 14) and F (II, 318, 12 f f) also declare that Fath Khān was Sikandar's son and not

Tamāchi's

I 229, l 15. He sent 3000 horses from the royal stables for the service of the Mirzā

^{&#}x27;Thirty thousand' in Malet, p 50, and this is the correct number.

(Malfūzāt-i-Tīmūri in E. D. III, 420; Zafarnāma, Ibid, 486).

'Bhatti and Ahan' (l. 16) also must be an error for 'Bhatner and Ajodhan', both of which were sacked by Tīmūr. (Ib. 487). There is a place called Bhattiwahan, but there is no reference to it in any of the histories of Timur's devastating inroad, and it did not lie on his route. It is said to have been in the Birun-i-Panjuad Sarkar of the Multan Sūba (Aīn, Tr. II, 331) and situated just midway between Multān and Aror. (Raverty, Mihran, 248 note).

I. 229, l. 10 from foot. Sayyid Abu-l-L'ais.

means 'abundance of غيس .' Malet (p. 15) calls him 'Abdul Ghais wealth.' Budauni speaks frequently of Mir Abul Ghais Bukhari, a warrior-saint of the reign of Akbar. (II. 21, 245, 304, 347; Lowe, Tr. 14. 252, 313, 358). K. B. reads Abu-l-Ghais (History of Sind, II. 49) and this is most probably the correct form.

Mirzā Pīr Muḥammad did not start for Delhi after Timūr had captured Delhi, as is said here on 1. 2, p. 230, but accompanied his grandfather to Delhi from Tulamba.

I. 230, l. 3 from foot. On the sixth of Jumada-l-awwal, in the year 858 H., Jām Rāi Dan came forth.

This date is irreconcilable with the writer's own assertions. M'aşūm has just stated (229 'ante) that Timur's invasion took place when Fath Khān was Jām. Fāth Khān is said to have ruled for 15 years and some months, his successor Tughlaq for 28, and Tughlaq's son Sikandar for 12 years. Timur ravaged Hindustan in 801 H. If that calamity overtook Northern India in the first year of Fath Khān's reign, the accession of Rāidhan must be put into 846 H.; into 845, if in the second; into 844, if in the third and so on.

But Räidhan himself is afterwards said to have ruled for 82 years, his brother Sanjar for 8 years and the accession-date of Sanjar's successor, Nizāmu-d-dīn is given as 25 Rab'ī I. 866 H. This means that Rāidhan must have ascended the throne 16½ years before Rab'ī I 866, i. e., in 849. But as he is said to have come forth out of Kachh and to have been employed for a year and a half in establishing his authority in the provinc), the death of Sikandar and the coming forth of Raidhan may be put $16\frac{1}{2} + 1\frac{1}{2} = 18$ years before 866, *i. e.* in 847-848 H. appears as if 858 is a miscalculation or slip for 848 H. The month and date, 6th Jumādī I, may have been correctly recorded.

But there is another complication. T. A. and F. know nothing of Raidhan and leave out his name altogether. Abu-l-Fazl has it, in the Ain, but it is inserted only as another name for Sanjar. As the original source of the information, the Tarīkh-i-Bahādurshāhi, is no longer extant, it is impossible to say who or which is wrong. If M'asūm is right in adding the name of Raidhan, the inconsistencies in the latter part of his chronology may be reconciled by the supposition that 858 H. was the year in which Sanjar, not Raidhan, ascended the throne. Raidhan appears to

have been a common name in Sindh and was borne by one of the Jādejā Samma rulers of Kachh, who died about 1697 AC (Duff, CI 290, I. GXI 78) There is a place in Sindh called Rāidhan between Lārkhāna and Dādu and the name is preserved also in Rādhanpur

I 231, l 7 from foot On the boundaries of Mathila and Ubawar

(Mīrpur) Mātheld is now in the Ghotki tāluqa of Rohri district, about 45 miles north-east of Rohri and six miles S.E of Ghotki Railway station. It is a very old site and is said to have been captured by Abul Hasan, the general of Sultan Maudūd Ghaznavi (Raverty, Mihrān, 488, Cousens, Antiquities of Sind, 175). Ubauro is in the Rohri Deputy Collectorate, seventy-five miles from Rohri and on the road leading from Rohri to Multān. Lat 28°-11′ N., Long. 69°-30′ E. Constable 26 B. a. Ghotki is in Lat. 28°-0′ N., Long. 69°-21′ E. (I. G. XII 236).

I 233, l. 2. Nizāmu-dīn succeeded Jām Sanjai on the 25th of Rab'i I 866 II

According to the Tulifatu l-Kiiām, Jām Nandā reigned from 866 to 914 H (K B II 51 note) General M R Haig accepts M'asūm's date, 866 A II, for the accession of Nizūmu-d-dīn or Nandā and states that he died in 914 H after a reign of 48 years (I D.C 82). T.A (636, 1 23) and F (II 320, 1 5) assert that he reigned for 62 years, but this is undoubtedly erroneous, as 866 + 62 = 928 H. This would leave no room for the reign of Jām Firūz which lasted from 914 to 928 H. In the inscription on Jām Nandā's tomb at Thatta, it is stated that the foundation-stone was laid in 915 H. The year of death is not stated, but it appears probable that the event had taken place some time before. (I D C 83) See also the discussion in Erskine's H B H (I 359 Note)

I 234, l 4 It advanced as far as Dara-Karib, commonly known by the name of Jalugar

Jalūgīr is a place in the Bolan Pass near Bibi Nāni (Haig, I D C 83) Bībī Nāni is 55 miles south of Quetta, 30 north of Dhādar and about 1695 feet above sca-level—It is about 30 miles from Kohundilan or Khundilān, which is the first stage of the Pass (Hough, op cit, 425, Sir Clements Markham in Proc R G S 1879, p 59)

I 234, l 9 Maulānā Jalālu-d-din Muhammad Dīwāni formed the project of leaving Shīvāz and going to Sind

I venture to suggest that the litterateur referred to here may be Jalālu-d-dīn Dawwāni (not Dīwāni), the author of the well-known ethical and political treatise called Akhlāq i-Jalāli He was born at Dawwān, a village near Kāzeiūn in Fārs, in 830 H (1426-7 A C) He was the Qāzi of Kāzerūn and was also a professor in the Orphans' College in Shirāz, where he died in 908 H (1502-3 A C), just six years before Jām Nizāmu-d-din (Browne, L H P III 444, 423 See also Āīn, Tr III 422, 424) This work was translated by J W F Thompson under the title of 'Practical Philosophy of the Muhammadan People' in 1839

I. 235, l. 12. He compiled a commentary on the Mishkāt but did not complete it. Some portions are still extant in the library of Masūd (مرد) and passages are commonly written as marginal notes in books.

The Mishkāt-al-Maṣābiḥ is a collection of the Hadis or Traditions of Muḥammad. A translation into English by A. N. Matthews was published in 1809-10.

- 1. 238, l. 1. Between Sīwi, Dehra and Kasmūr, there is a tract of land called Bārgān, which breeds horses not inferior to those of 'Irāk. The young colts..... can go unshod even amongst the hills.
- "Dehra" is Dera Bugti. Constable 24 C c. It lies in "the angle of the Sulaimān mountains between the Indus and Kachhi. (Dames, Baloch Race, 57.). "The ponies of the Marri and Bugti hills are light in limb and body, but carry heavy weights unshod over the roughest ground. (I. G. XXII. 339). "The Sarawān country and Kachhi still produce the best horses in Baluchistān." (Ibid. XIV. 30I). Bārgān is perhaps Bārkhān which with Sanjaki and Dūki, formed part of the Thal Chotiāli district, but was transferred to Loralai in 1903. (I. G. XXII. 349). It is shown in the I. G. Atlas. 35 E 2. Kashmor is marked in Constable 26 B a.
- I. 238, l. 6. At Chhatūr, there is a tribe called Kahari, so called from the tree called Kahar, on which one of their ancestors mounted...and it moved on like a horse.

The Baluch tribe of Kaheri is still found in the Kachhi and Sibi districts. (I. G. XIV 250; XXII. 338; Dames, Baloch Race, 19, 58; Eastwick, Dry Leaves from Young Egypt, 100). The tree called Kahar (I. 6) is the Kirrār or leafless Caper (Capparis aphylla). It grows to the height of ten to fifteen feet and its evergreen twigs or branches which are leafless, produce a fruit called tent which is pickled by the poorer classes. (Elliot, Races. II. 393). Hughes (Gazetteer, 13) says that its wood also is valuable and is used for rafters and the knees of boats. It is the Kariraka of the Shukra-nīti. (Ed. Oppert, IV. iv. 1. 118). Chhatur or Chatar is now in British Baluchistān. Constable 24 C c. The story reminds one of the tales of witches in Europe riding upon broomsticks.

I. 238, l. 4 from foot. Within this recess, are inscribed the names of Bābar Bādshāh and.... Mirzā Kāmrān. Mirzā

'Askarı and Mırzā Hındāl .Of all his dominions, Kandahār was the only place mentioned When I visited the spot, it came into my head, etc

Dowson suggests in the footnote that a negative is required here and that the sentence should read 'Kandahār was not even mentioned as forming part of his dominions' But the emendation is not only uncalled for but positively wrong The 'Great Qandahār Inscription' engraved under the directions of M'asūm has been edited, translated and commented upon by Darmesteter (Journal Asiatique, 1890, pp 195-230) and also by J Beames (Geography of the Qandahār Inscription, J R. A S 1908, pp 795-802) Mrs Beveridge gives the following translation of the original epigraph commemorating the conquest of Qandahār, which M'asūm sought to supplement and complete —

"Abul Ghāzi Bābur took possession of Qandahār on Shawwāl 13th, 928 A.H In the same year, he commanded the construction of this Raicāq-i-Jihānnumā, and the work had been completed by his son, Kāmrān at the time he made over charge of Qandahār to his brother 'Askari in 9 " [937 ?]. (B N Tr Appendix xxxiv, see also Mohan Lal's Travels in Afghanistan and Turkistan, 312)

The fact is that Qandahār was the only part of his dominions that was mentioned in the original epigraph and the primary object of inscribing it had been to record and commemorate the conquest of the great stronghold. It was just because Qandahār was the only part of Akbar's dominions which was mentioned in this ancient record, that M'asūm thought it necessary to have another engraved, in which the names of all the other notable towns and districts comprised in the Great Emperor's realm, from Orissa and Gaur-Bangāla in the East to Bandar Lahri and Thatta in the West, were registered

On line 10 from foot. 'Sıbūda'ıs wrongly spelt Malet is right ın reading 'Seepoozah' (Sīpūza).

I. 239, last line He [Bābā Hasan Abdāl] accompanied Mirzā Shāh Rukh, son of the Sāhib Kirān (Tīmūr) to Hindustān.

This statement is not quite correct, as Mirzā Shāh Rukh did not really accompany "the great Tartarian" to Hindustān or take any part in his devastating and sanguinary invasion. He did leave Samarqand in the train of his father, but was sent back from somewhere near Kābul to Herāt, as he had been appointed governor of all Khurāsān about a year before (May, 1397 A. C). He remained at Herāt all the time and a servant of his actually waited upon Tīmūr, when the latter was encamped at Janjān near Tulamba and brought assurances of his good health (Zafarnāma, Text, II 31, 59, see also E.D. III 408, 417). Another attendant brought letters from the Prince when Tīmūr had passed Kābul and Shibar-tu on the return journey (Z. N. II. 187, 1.14).

Mir M'asum states in an inscription engraved under his supervision

on the Buland Darwāza at Fathpur Sikri that he was a descendant of Bābā Ḥasan Abdāl. (Muḥammad Hādi's Introd. to Tūzuk-i-Jahāngīri. Text 4 Note, last line; Blochmann, Tr. Āīn, 515; Beveridge, A. N. Tr. I. 397 note). M'aṣūm was evidently proud of his ancestry and this accounts for his going out of the way to mention the spot where the saint performed his miracle of the 'golden brick' and to refer also to his having accompanied Mirzā Shāhrukh to Hindustān. The saint is also known as Bābā Wali.

I. 241, l. 11. He [Gisu Khān] sent them firing and fighting towards the Shrine of Khuāja Khizr.

The shrine is situated on a small island, a little to the north of Bhakkar and separated from it by a narrow channel of easy passage. A mosque in it contains an inscription which has been supposed to prove that "the Indus had deserted a former channel and taken its present course [in or] before the year 341 H." in which the mosque is believed to have been erected. The inscription runs thus:

چو این درگاه عانی شد هویدا که آب خضر دارد در حوالی خضر با خط شیرین در نوشته ناریخش باب از درگاه عالی

E. B. Eastwick appears to have been the first to draw attention to the epigraph. (Handbook for India. Part II, Bombay, (1859), p. 492; Dry Leaves from Young Egypt, 38).

He translated it as follows:-

"When this Court was raised, be it known,
That the waters of Khizr surrounded it:
Khizr wrote this in pleasing verse, (lit. handwriting)
Its date is found from the "Court of God."

As the numerical value of the words $Darg\bar{a}h$ -i-'Āli is 341, the conclusion he drew from the words was that the epigraph was a contemporary document of great historical value, which "fixed the date on which the Indus abandoned Alor and directed its course into a new channel between Rohri and Sukkur.' But Haig rejects this rendering and understands the first couplet to mean only that "the Indus [or some branch of it] was running by Bhakkar in 341 H. It does not tell us how much earlier or when it came there." He renders the lines thus:—

"When this sublime temple appeared,

Which is surrounded by the waters of Khizr." (I.D.C. 133-4).

Raverty who had pinned his faith to the legend of Saifu-l-Mulk and had a pet theory about the Hakra having been diverted from near Aror, in the time of Dalurai about 335 H., made much of the epigraph, as it fitted in with his preconceptions (Mihrān, 491 n.), but the more recent and better opinion is that the inscription is a fake of comparatively recent origin and historically worthless. The principal reason

for this view is that the Nastalia script in which it is engraved is known to have been devised and come into voque only in the 14th or 15th Christian century. The practice of composing such mnemonic lines or chronograms in verse also does not appear to have existed at all in 341 H 952 A C (Cousens, AS 145-6) Mr Abbott also has recently declared that the inscription is "a pious fraud contrived to give the shrine a hoary antiquity (Sind, 76 n). In this connection, it may be worth while to invite attention to a passage in Ibn Batūta's Travels. He says that when he was at Bakkhar in 734 H, he saw in the middle of a canal derived from the river Sind, a superb hermitage where travellers were lodged and fed. It had been erected by Kishlu Khān Bahrām when he was governor of the province, i.e., about 1320 A.C (Defremery, III. 115) May not this 'Shrine of Khwāja Khizr' be the hermitage erected by Kishlu Khān?

Rānīpur (1 6) is now in Khairpur State. It is shown in Constable 26 B b

1. 242, l 8 When Tarsun Muhammad Khān received permission to depart from the court [after being appointed to Bhakkar], some of the nobles objected that it was impolitic to place the children of Saifu-l-Mulk on the borders of the country

Tarsun Muhammad Khan was the sister's son of Shah Muhammad Saifu-l-Mulk, who had been, at one time, independent ruler of Gharjistan, but had to submit to Shah Tahmasp of Persia in 940 A.H Tarsun Muhammad himself afterwards took service under Akbar rose to be a Pang-hazāri and was killed in Bengal by the insurgent M'asum Khan Farankhudi in 992 H (Blochmann, Ain, Tr I 342-3) When Tarsun Muhammad Khan sent his cousin Muhammad Tahir (the son of Shah Muhammad Saifu-l-Mulk) and two other relatives in advance, to take charge of the Jagir, (see 241 ante), his rivals and enemies at the Court pointed out that as he was the nephew of a quondam ruler of Gharustan, a man with a following and connections in Persia and on the Indian Frontier, it was not safe to make him governor of an impregnable fortress, situated, like Bhakkar, in a remote part of the Empire The Emperor was thus persuaded to cancel the appointment and he was made governor of Agra, as he would be there under the Emperor's own eye and find it impossible to turn traitor. M'asum merely records the reasons for the change

Raverty's assertion that Shāh Muhammad was entitled Saifu-l-Mulk, because he was a descendant of 'this very merchant' Saifu-l-Mulk, to whom local legend attributes the diversion of the river and the destruction of Alor, is a fantastic and absolutely groundless supposition. He had somehow convinced himself of the truth of the folk-tale, but his attempt to bolster it up by this grotesque conjecture is a dismal failure. (Mihrān, 485-6 Notes) Many other persons have been styled Saifu-l-Mulk and Saifu-d-daula, Saifu-l-Mulk are very common Ilqāb

His argument that the story must be true because the graves of Saifu-l-Mulk and his sons Ratta and Mutta (or Mātta) are still pointed out and visited by pilgrims at a village called Ratta-Matta, lying about 5 miles from Jatoi and 32 from Derā Ghāzi Khān (Mihrān 409, 486 Notes) is scarcely worthy of serious attention. Its logic is almost as naïve as that of the 'simple child' in Wordsworth's poem. The names of the sons and of the village are obvious fabrications of the eponymous type, while those of the merchant and his slave girl are found in the Arabian Nights (Lane's Trans. III, 744 and Note) and other story books.

1. 243, l. 7. He sent a force against the Mankinjas of the district of Gāgri.

The correct form is 'Mangnejas.' Hughes states that they are a Sindhi clan settled in Naushahro district. (Gazetteer, 583). They are perhaps so called because they are descended from a person named 'Mangne.' Cf. Samejas, Jādejas, Kākeja, Kūrejā-Sammas. (339, 340 post).

Gambaz or Gambat (l. 13) is twelve miles south of Khairpur and ten miles east of the Indus. (Hughes, Ib. 170). Constable 26 Bb. 'Bajrān' (l. 13) is written 'Vejūran' in Malet and may be Vanjhrot or Vinjrot or Vijnot, a very old Hindu town which lies four miles south of Reti station and 63 miles west of Rohri. (I. G. XXIII. 121). There are extensive ruins here in which very large bricks like those of Brahmanābād have been found. (Cousens, A. S. 72).

I. 244, l. 8. The Emperor granted the country of Bhakkar in jāgīr to Fath Khân Bahādur, Rājā Parmānand and Rājā Todarmal.

Dowson states that Ms. B makes no mention of Todarmal and speaks of only two grantees. The explanation is that Rājā Parmānand was a relation (خوش) of Todarmal. (A. N. III. 70, Tr. 97; K. B. History of Sind, II. 109). The copyist of Ms. A must have dropped out the word and interpolated the conjunction in its stead. خوش also means 'son-in-law' and that may have been Parmānand's exact relationship to the great minister.

I. 244, l. 11 from foot. He [Shihāb] led a force against the fort of Kin-Kot, which was in the hands of Ibrāhīm Nāhar.

Malet's reading is 'Kamkot.' It must be Kin or Kinkot. "About 1450, the Nāhars who are a branch of the Lodis......succeeded in establishing their authority in Kinkot and Sītpur in Derā Ghāzi Khān district and even extended their dominions further in the Derajāt, but their power was afterwards circumscribed by the Mīrāni Baloch." (I. G. XI. 250-1). I. 246, l. 12. His advanced guard was composed of Baluchīs.

Dowson says in the note that the original words are بلوج يلدي بودند and he has left out ميلدى as he could make nothing of it. Malet speaks of them as 'Boordee Beloochees.' The tribe is known as Buledi or Burdi. According to the I. G. (VI. 290), the most important Baluch tribes are the Marris, Bugtis, Buledis, Magassis and Rinds. (See also Ibid, XIV, 250, art. on Kachhi; Wood, Journey, 33). The name is derived. from the Buleda valley in Makran. (I G. Atlas, Pl 35 B b) They are also called 'Burdi' and there is a tract in Upper Sind near the Indus called Burdika, where they are found in great numbers (Dames, Baloch Race, 17, 57)

I. 247, l 12 from foot The officials assigned to me the pargana of Durbela, Gagri and Chanduka (in the Sarkar of Bhakkar).

Cf. 234, 1 2, ante where 'Lakri, Chandūka and Sindicha' are mentioned Abu-l-Fazi registers Kākhri (or Kākri), Darbela and Jandola (Recte Chandūka) as Mahāls in Sarkār Bhakkar (Āīn, Tr Jarrett, II, 334) Chandūka or Chāndkoh is said to be 20 Kos west of Bhakkar by Malet (83, 153) It is now the chief town of Līrkhāna district

Gägri (which can be read also as Kākri) may be Kangri or Kingri, which hes about 20 miles south-west of Bhakkhai (Mihiān, 240 note) It is stated in the Maāsiru-l-Umaiā that Mīr M'asūm was born at Bhakkar and educated under Mullā Muhammad of Kingri (III 326; Blochmann, Tr Āīn, I 514) But Gāgri is, more probably, Kākar in the Mehar Deputy Collectorate of Lārkhāna District (Hughes, 314, 730, I G. XIV. 289) KB (History of Sind, II) reads 'Kākri' Darbelo is 10 miles north of Naushahro, which is about 76 miles south-east of Bhakkar (Th) Chāndkoh, Darbelo and Kākar are all in proximity to one another and are shown in Constable Pl 26 B b The name Chandūkā or Chāndkoh, the old designation of what is now called the Lārkhāna sub-division, is derived from the Chandia tribe of Balūchis (I G XVI 139)

1. 248, 1.5. The river was crossed, batteries were raised and we began to take measures for securing a passage over the river

در مقام ساختی بایات شدند Dowson observes that "the text says word pay-ab, commonly means 'a ford'" As the river had been already crossed, there was neither sense nor reason in making 'a ford' Besides, a ford is not 'made'. I suggest that the right reading is بأشب pāshīb, which is used by Barani more than once (TF Text, 213, 1.18, 253, 1 20; 277, 1 6) in connection with sieges and in juxtaposition with Dowson renders it as 'mound' in his translation of the second passage (E D III 165) and leaves it untranslated in that of the third (Ibid, 174) Amir Khusrau also uses the word frequently in his accounts of the sieges of Ranthambor and Warangal and says in connection with the first, that "sandbags were sewn and with them was constructed a Pāshīb high enough to touch the western tower of the fort Maghribis then shot large stone-balls from the summit of the Pāshīb'' (Khazāin, Tr Habīb. 39, see also Ibid, 41) Elsewhere, he speaks of a Pāshīb "reaching the summit of the hill on which the fort of Siwana stood" (Ib 54), of a Pāshīb "so wide that files of hundred men abreast may ascend over it to the fort " (Ib 66) and describes a 'Pāshīb' as "the means of opening the way to a besieged fort" (Ib 83) There can be little doubt that the right reading here is بأشب 2 e "Earthworks to mount and protect the guns."

I. 248, 1. 10. Jani Beg then threw up a sort of fort on the bank of the river at the village of Lohari above Nasrpur.

The correct name is Bohiri or Bohri, a village which still exists about ten miles north of Nasrpur. It "lies in a large loop of land formed by an abrupt recurving of the river, the neck of which Jani Bey closed with strong earth-works armed with artillery." This earth-work was Marina's 'sort of fort' and it was "protected on other sides, either by the river or by soft and treacherous quickeands or quagmires. His fleet of boats enabled him to command the river and keep open his communications with the land and draw supplies from the whole of Lower Sindh." (I.D.C. 103-1 and 103 note).

1.249, 1.18. Khusru Khān acted judiciously; keeping his own ghrāds in the river, he sent others in persuit, and several of the enemy's vessels with soldiers and Fixingi fighting men on board fell into his hands.

This translation is manifestly wrong and Malei's rendering in very different. The 'Firingi fighting men' were employed, not by the Machele,

As Shāhgarh is an oft-recurring toponym, it may be as well to say that it was a fort about ten miles north of Bohīri (I D. C 106) In the $T\bar{a}r\bar{\imath}kh$ - \imath - $T\bar{a}hiri$, Shāhgarh is said to have been in the province of Nasrpur (286 post) Bohīri was ten miles north of Nasrpur.

I. 250, l. 5. Another force went against Badin, Fath Khan and Jun.

Badīn lies 62 miles S S E of Haidarābād and is now a station on the North-Western Railway Constable 26 B C Fath Khān is an error for 'Fath Bāgh.' It lay about five miles N W W of and higher up than Jūn on the right bank of the Ren, and six miles south-east of Tāndo Muhammad Khān on the route to Badīn (I D C. 93) It is the 'Bāgh-i-Fath' of the Āīn (Tr II 340) Jūn itself lay 75 miles south-west of Amarkot and 50 north-east of Thatta—It is now a small village in the Gūni tāluqa of Haidarābād district—It is centrally situated in the Delta—All these three places lay on the main route north-wards to Nasrpur, Sehwān and Bhakkar (I D C 92, Mr C E A Oldham in Indian Antiquary, (LIX), 1930 p 240, Cousens, A S Map, Pl Ciii)

I 251, l 1 Jani Beg retreated to Unarpur twenty kos from the battle field

Abul Fazl says Unarpur was four kos from Hālā Kandı (Old Hālā), and forty south of Sehwān (A. N III 613, Tr III. 938). This agrees with Haig's location of it at four miles north of Matāri and about twenty-two north of Kotri near Haidarābād The battle-field must have been somewhere near Fathpur in Sakrand pargana and about 8 miles west of Sakrand town (I D C 108-9) Sann (1 24), where the Khān-i-Khānān encamped, is about thirty miles north-west of Unarpur and thirty-four south of Sehwān (I D C 109) See also Hough, op cit. 436 Both places are shown in Constable, Pl 26

I 252, l 4 And Khusru Khān was named to be his [Jāni Beg's] son-in-law

The reference is not to Khusrau Khān Charkas, who is mentioned at 249 ante, but to the Shāhzāda or Prince Sultan Khusrau, the eldest son of Akbar's son, Salīm, who afterwards became known as the Emperor Jahāngīr There is a reference to Prince Khusrau's betrothal to Jāni Beg Tarkhān's daughter in the Tūzuk-1-Jahāngīn 1 (Text 8, 1 2 f f = Rogers and Beveridge's Tr I 20)

There is some confusion in Dowson's version of the Tārīkh-i-Tāhiri also, in regard to these two names At p 287 infra, Khusrau Khān Charkas, the quondam slave of Jāni Beg, is spoken of as 'Sultan Khusru Charkas,' which is a solecism 'Kāsim' (1 6) is a blunder for 'Āsir' Malet has it right and calls the place 'Asseerghur'

I 252, l 6 On the 25th Rajab, Mirzā Jāni Beg died of brain fever

The year is left out here It is given as 1008 H by Malet but that is wrong Abul Fazl gives the exact date as 13 Bahman in the 45th year of Akbar's reign Faizi Sirhindi says the event took place on 1st Sh'aban 1009 H = 26th January, 1601 A. C. (A N. Tr. Beveridge, III,

1172 and Note).

Calculation shows that Abul Fazl's 13th Bahman XLV R. corresponds to 25th Rajab 1009. The fortress of Asir was taken on 7th Bahman 45 R = 16th-17th January 1601 (O. S.). The Ilähi equivalent of 1st Sh'aban (26th January 1601) would be 18th Bahman. The 46th Ilahi year of Akbar's reign began on 15th Ramazan, 1009 H. Between 25th Rajab and 15th Ramazān, the number of intervening days is 48 (5 + 29 + 14) and 13th Bahman XLVR was 48 (18 + 30) days before 1st Fravardin of the XLVIth Regnal year. The date given by M'aşum is practically identical with Abul Fazl's. Faizi Sirhindi puts the event six days later, but the correct year is, according to both these authors, 1009 and not 1003 II, as given by Malet. Mirzī Jāni really died of excessive indulgence in strong drink, which brought on paralysis and delirium tremens. (Maasiru-l-Umara. III, 310; Ain. Tr. I. 363). There is no truth in the report that Akbar had Jani Beg poisoned on account of his having made an indiscreet remark in connection with the capture of Asirgarh. (Ibid).

I. 256, l. 4 from foot. Every night he possessed himself of a maiden.

This exercise of the droit de seigneur is a very commom feature in folktales about dragons, tyrants and monsters of sorts, but it may be worth while to note here that similar wickedness is actually ascribed to Mirzā Ghāzi Tarkhān, the son of Jāni Beg, who was Ṣūbadār of Ṭhaṭṭa in the reign of Jahāngīr, by the compiler of the Maāsiru-l-Umarā. "He required," this author assures us, "every night a virgin and girls from all places were brought to him and the women of the town of Ṭhaṭṭa were so debauched, that every bad woman, even long after his death, claimed to have had relations with the Mirzā." (Text. III. 348; Blochmann, Aīn, Tr. I, 364). The anecdote may be only a canard, but it would seem as if the enforcement of this 'ancient privilege' was associated in the popular mind of Sind with the exercise of strong and vigorous rule, even in the seventeenth century.

The alleged feat of the merchant is a romantic folktale masquerading as history. Aror was most probably destroyed, as the I. G. states, by "the great earthquake which diverted the Indus into another channel and also deprived the town of its water supply. (VI. 4; see also I. D. C. 72). The legend appears for the first time in the $T\bar{a}r\bar{i}kh$ -i- $T\bar{a}hiri$ and there is no allusion or reference to it in the History of M'aṣūm. It will be observed also that neither the merchant nor his handmaiden is given any name at all in the earliest version. They are called Saifu-l-Mulūk and Bad'iu-l-Jamāl for the first time only in the Tulfatu-l-Kirām, which was compiled only about 1181 H. 1767-68 A. C. (p. 328 infra). Both these names occur frequently as those of lovers in Oriental story-books and are fictitious. A Dakhani poet named Ghawwāṣi also is known to have written in Hindustāni a maṣnavi on the loves of Saifu-l-Mulūk and Badī'u-l-Jamāl in 1035 H. (Houtsma. E. I. IV. 1025, s. v. Urdu).

I. 258, l 8. Destruction of Brahmanābād

Brahmanābād, Bhāmbor and Alor are all said to have been destroyed in a single night and by divine wrath The legend of Chhota Amrani, the maiden Fatima who taught him to read the Quran and who, after marrying him, escaped from the doomed city just on the eye of the catastrophe, bears a very suspicious resemblance to the story of Zobeide, in the Arabian Nights There, the prince who was the only inhabitant not turned into stone was saved because his Muslim nurse had taught him to read the Quran and made him one of the Faithful Ibn Batuta's tale (Defrémery, III, 113) of the petrified Kafir city which lay about seven miles (Kos) from Larry Bunder, looks like another variant of this same legend of Chhota Amrani. That city was probably the ruined town of Bhambor or Bhanbarwa, which lies about 12 miles north-west of Larry Bunder (AGI 299) Hughes notes that Bhambor is still known as the 'Kafar' or 'Infidel City' and was formerly called 'Mansawar' or 'Manhavar' (Gazetteer, 120) Cunningham supposed "the petrified city" to be Daibal, but that was because he sought to locate the latter at Larry Bunder, an opinion which is now almost universally rejected

I 259, l 2 from foot On the second night, they were saved by the watching of Gunigir, but on the third, the whole city was swallowed up

It is not easy to say what this 'Gunigir' means or stands for. It cannot be a personal name, as no such name is known In the English version of the legend, as it is related on the authority of the Tuhfatu-l-Kirām in Hughes' Gazetteer (p. 141), it is understood as a Sindhi vocable or common noun signifying 'Oil-presser' and not as the personal designation of any individual But the interpolation of a vernacular word in the Persian text of the story seems to be neither appropriate nor necessary and I suggest that کنیکبر is a miswriting of کسیرکی Kanīzakı, "a maid-servant, a young girl"

Stories of the fate of doomed cities having been temporarily delayed by the prayers or on account of the presence of some saintly individual of humble birth are common in folk-lore and have been not infrequently related even by the credulous authors of contemporary histories instance, we are assured that the conquest of Thatta by Sultan Firuz Tughlaq was delayed because a saintly old woman was one of its residents The city could not fall so long as she was alive, but it was destined to surrender to the invader immediately after her death. (Shams-i-Sirāj, Tai îkh-i-Fii üzshahi, Text. 241 = E D'III 334)

It may be also noted that as "the destruction which hovered over the city was staved off on the first night by the watching of an old widow," it seems quite appropriate and in the true vein of folk-lore to suggest that it was held up on the second, by the vigils of a young virgin ningham remarks that "the same stereotyped legend is told of all the old cities in the Punjab, as well as those of Sind Shorkot, Harappa and

Atāri are all said to have been destroynd on account of the sins of their rulers as well as Alor, Brahmanābād and Bambhura." (A. G. I. 275).

I. 263, Footnote. The Tuhfatu-l-Kirām says, Mir Tāhir is here in error, the real author being Idrahi Beg.

The statement will be found in the Translation at 350 infra.

The "Chauesar Nāma" was really written by Idrāki [not Idrāhi] Beg, but as it was dedicated to or composed under the patronage of Mīr Abul Qāsim Sultān, it is said in the Tārīkh-i-Ṭāhirī to have been "written in his name." (عَنَّ الْ الْهُ الْمُلْهُ الْمُلْعُلِلْمُ الْهُ الْمُلْعُلِلْمُ الْمُلْهُ الْمُلْلُكُ الْمُلْلُكُ الْمُلْلُكُ الْمُلْلُكُ الْمُلْكُ الْمُلْكُ الْمُلْكُ الْمُلْلُكُ الْمُلْلُكُ الْمُلْكُ الْمُلْكُلُكُ الْمُلْكُ الْمُلْكُ الْمُلْكُ الْمُلْكُ الْمُلْكُ الْمُلْكُ الْمُلْكُ الْمُلْكُ الْمُلْكُلِكُ الْمُلْكُ الْمُلْكُ الْمُلْكُ الْمُلْكُ الْمُلْكُلِكُ الْمُلْكُلِكُ الْمُلْكُ الْمُلْكُلِكُ الْمُلْكُ الْمُلْكُلِكُ الْمُلْكُلِكُ الْمُلْكُلِكُ الْمُ

تمانِف او اکثر بنام عرش آشانی نوشت (Maāsiru-l-Umarā, II. 134, last line). The Emperor Jahāngīr tells us that his Vazīr, Āsaf Khān composed a poem on the Loves of Khusrau and Shīrīn and entitled it Nūr-nāma, 'after my own name' بنام من نظم کردد (Tūzuk, 108, l. 3 f. f.) This is rendered as "dedicated to me" by Mr. Rogers. (Tr. I. 22). The Laţaif-i-Ghiyāsi of Rāzi also was so called because it was "written in honour of" Sultan Ghiyāsu-d-din Sām. (Budāuni, I. 53 = Tr. I. 73).

I. 267, l. 8 from foot. This was the plan.

This is an age-old ruse which has been associated with diverse places and fathered on diverse national heroes. Grant Duff states that Mahratta traditions ascribe a similar stratagem to Shivaji and that a fort called Parichitgarh is said to have been captured in this way by a body of insurgents in the reign of the Peshwa Baji Rao II. also. "Having corrupted one or two persons in the garrison, a party of them, each loaded with a bundle of grass and having his arms concealed below it. appeared at the gate in the dress of villagers to deposit, as they pretended, the annual supply for the purpose of thatching the houses in the fort, and admittance having been thus gained, they surprised the garrison and possessed themselves of the place." (History of the Mahrattas, Reprint 1873, p. 64 Note). This story of the trick by which the two Samma chiefs, whose names are said to have been Mudā and Manāi, laid the foundation of their rule in Kachh is well-known and was related to Burgess during his tour in the province. The event is there said to have taken place about 1320 A. C. and the fort to have belonged to Wagam Chavada of Gunthri, now a small village about 36 miles north-west of Bhuj. (Arch. Survey Reports, 1874-5, p. 200; B. G. V, Cutch, 133, 222-3) The date is given by other authorities as 1270 A. C (Duff, C I. 290)

I 268, l. 21 Rai Bhara and Jam Sihta, the Rajas of both Great and Little Kach, are descended from the Samma tribe

Rāi Bhāra is Bhārmal, the Rāo of Kachh, who paid a visit to the Emperor Jahangir at Ahmadabad in 1027 A H (Tuzuk, Text. 235) Jam Sīhta (Satā) is Jām Satarsāl of Nawānagar, whose son and successor Jasā was similarly compelled by a show of force to pay his respects at the same time, to the Mughal Emperor "Sixty years ago," writes Abul Fazl about 1595 A C "Jam Rawal . was driven out of the country of Kachch and settled in Sorath and founded the city of Nawanagar and his country received the name of Little Kachh Satarsāl, the present Rājā, is his grandson" (Ain, Tr II 250) The rulers of Kachh and Nawanagar are Jadeja Sammas, i e Sammas descended from Jada The Sammas are said to have fled from Sindh to escape the tyranny of the Sumras and become masters of the country about 1320 A. C "They then ruled over it, in three branches, upto 1540 A C, when Khengar drove out Jam Rawal and became sole master of the whole province" (L G XI 78) Rão Bhārmal ruled in Kachh from 1585 to 1631 A C (B G V Cutch, 136) Satarsal (Satajı or Satojı) was Jam from 1569 to 1608 A C (Ibid VIII 567-569)

I 269, l 3 They [the Sumras] had many strange customs, such as the strong branding the stamp of slavery upon the shoulders of the weak

The author of the Mirāt-i-Sikandari, a history of the independent Sultans of Gujarāt which was written about 1610 A C., says that Sultān Mahmūd bin Latīf (r 943-961 H. 1537-1554 A. C) actually revived this custom and enforced it in the turbulent parts of his kingdom "With a view to putting down the turbulent Kolis of Bānswārā, Rājpiplā, Lunāwārā and the Mahikānthā, he ordered all those who remained in his territories and worked at the plough to be branded on the right arm, and if any Rājput or Koli was found without the brand-mark, he was killed He also ordered that no Hindu could ride on horseback in the city and every Hindu had to carry a piece of red cloth round his sleeve." (Bombay Lith 334, Tr. Fazi Lutfulla, 239; Tr Bayley, 439) Bilāduri states that 'Amrān son of Musā who was governor of Sind-in 222 H summoned the Jats, took from them the jizya, ordered every one of them to carry a dog with him and "sealed their hands," by which he probably means that they were branded on the arm (128 ante)

It was the practice to brand slaves to facilitate capture in the event of flight or secure proofs of identification in cases of disputed ownership 'Abbās Khān Sarwāni informs us that when Shīr Shāh came to Khushāb and "ordered the Baluchis to brand their horses, 'Ism'āīl Khān, their chief, said, 'other persons brand their horses, I will brand my own body', Shīr Shāh was so pleased that he excused him from the branding and

confirmed to him the country of Sind." (E. D. IV. 388).

According to the *Tulifatu-l-Kirām*, the nails were extracted by the roots, not from their own hands and feet, but from those of other people who were their inferiors (Trans. in K. B. History of Sind, II. 38), but the older author appears to have grasped the inside meaning better.

I. 270, l. 6. The late Mirzā Muhammad Bāki Tarkhān.... gave away in charity the produce of his husbandry.

The story, as it is translated here, is pointless and incoherent. The person who gave away in charity "the produce of his husbandry" was not, as this rendering makes out, the mean and miserly Mirzā Bāqi, but the Dervish. "The Fakirs, widows and the poor were the recipients of the bounty" of the Dervish and not of the Mirzā. Again, it was the Dervish and not the Mirzā who asked the guest why he did not partake of "the sumptuous meal ordered for him". The word "Your Holiness" applies really to the devotee and is wrongly translated as "Your Majesty". It is this fundamental error which is responsible for the confusion. Tahir Muḥammad, like other devout Musalmans of his day, was a great admirer of Santons and hermits and the anecdote is evidently related with a view to emphasise the greatness of the Dervish, by laying stress on the reverence and awe in which he was held by a sanguinary tyrant and grasping curmudgeon like Muḥammad Bāqi.

The sordid nature of Muhammad Bāqi is illustrated in the *Tulifatu-l-Kirām* by the anecdote that one of his servants who collected "a heap of grain from the dung of the horses" in the stables was promoted at once to a high office and became a great favourite. (Tr. in K. B. l. c. II. 102).

I. 271, 1. 23. These people [the Sammas of Kachh] hold in high respect their minstrels, such as the Katriyas, the Chārans, the Doms and the Mārats (?)

'Katriyas' is a puzzle. Can it be meant for 'Katviyas' i.e. Gadvi, 'Mārat' looks like an error for الروت or المروى: Bārat or Bārot, a name by which Chāraṇs are known. (B. G. II, Surat, 374). "Doms" are a very low caste who are sweepers but also village musicians, tumblers, dancers, etc. (Yule, H. J. s. v. Dome).

I. 275, l. 2. One day [Jam Nandā] went out to hunt, taking with him his minister Lakhzhir,

Dowson observes in the footnote that "the $Tuhfatu-l-Kir\bar{a}m$ is doubtful about the real name, saying it is Lahakdir or Lahgir". The right reading is 'Lakhdhir,' a common name still in Kachh and Kāṭhiāwād. The present Mahārāja of Morvi is named Lakhdhirji. The father of the ruling Thākor of Rajkot bore the same name. The Sanskrit form must be Lakshadhira or Lakshmidhar. The name seems to have been spelt with the Persian $d\bar{a}l$, ' which is pronounced like 'Z or $z\bar{a}l$ ' and also as 'd' or 'dh'.

It may be noted that Jam Nanda is here said by Tahir Muhammad also to have been the son of Babiniya [Bamaniyo]

I 275, l 15 The lad filled the cup and threw in it some small blades of grass

This is a very common by-plot in folktales about kings who have lost their way while out hunting and suffered from a burning thirst. It is an episode in the 'Tale of the King and the Gardener's Daughter' which is told by Jahāngīr (Tūzuk, Text 251, Tr II 52) and also in an older variant in Burton's 'Book of the Thousand Nights and A Night, (V 87-8), where it is associated with Khusrau Anūshīrwān Manucci relates a very similar anecdote of which the hero was neither Jām Nandā nor the Sāssānian Kisrā, but the Timūride Shāh Jahān. He tells us that "the emperor was once separated from his retinue while out hunting and felt very thirsty. He went to a village where a Brāhman gave him water, but seeing that he was drinking it very greedily, threw into the vessel a little grass. On being angrily asked to explain the reason, he declared that it was just what he did to his asses, so that they might not get an attack of colic" (Storia, Tr Irvine, I 214)

I 276, l 3 from foot. Sack and burning of Tatta

This event is put by the author into 973 A H but the $Tarkh\bar{a}n$ $N\bar{a}ma$ has the right year which was 963 H (324 infra) The Portuguese accounts leave no doubt as to the raid having been perpetrated in 1555-6 A C (Faria Y Souza, Tr John Stevens (1693), pp 184-5, Danvers, History of the Portuguese in India, I 508, I D C 99) A H 963 began on 16th November 1555 and ended on 3rd November 1556 A C

I 278, l 18 His [Mirzā 'Isā Tarkhān's] reign ended in 984 H.

The Tārīkh-i Tāhiri is again wrong Mīr M'asūm gives 974 (Tr. Malet 133) and so also the Tarkhān Nāma (325 infra) Abul Fazl states that in or about Rajab 974 H Muhammad Bāqi Tarkhān sent ambassadors to Akbar saying that his father 'Isā Tarkhān was dead and professing his own allegiance He also complained that Sultan Mahmūd Bhakkari was preparing to invade his territory, upon which Akbar issued orders to Mahmūd Khān to confine himself to his own dominions (A. N II. 277, Tr II 411) Elsewhere in the same work, it is stated that Mirzā 'Isā had died some years before 978 A H (Text II Tr II, 526). The arrival of the embassy from Muhammad Bāqi, reporting the death of his father is also mentioned in the T A. in the annals of the eleventh year (973-974 H.) of Akbar's reign (E D V 315, Text, 277, 1 9 and 628, 1 5) and also by B (II 91, Tr II, 93) and F. (II 322) This contemporary testimony from independent sources settles the matter

Mr Cousens (A S 35) gives 980 H, which must be due to some error

I 285, l 3 from foot. When he drew near the Lakki mountain, which weise men hold to be the key of the country

There are two places of this name in Sind. This is the Lakki about

twelve miles south of Sehwän. "Between the town of Lakki and Sehwän, the mountain has a nearly precipitous face about 600 feet high towards the Indus, between which and the precipice there was at one time a road, though in some places so narrow that only a single camel could pass at a time. This defile was washed away in 1839 [A. C.] by the Indus, which now sweeps along the base of the cliff." (Thornton, 570; see also Hughes, Gazetteer, 686).

1. 286, 1.7. Tribes of the Buluch and Nahamrui, of the Jokya and Jat. The Jokiyas are a tribe among the Baluch. (Wood, Journey, 12). The Numria and Jokia tribes are mentioned by Hughes (Gazetteer, 290, 428) as dwelling in the Jhirk and Kohistan districts. He supposes the Numria to be a clan of Rajput origin. "It is said that Esub Khan with his eight brothers left Rājputānā and settled at Kej in Makrān. They were well received by the chief, but they subsequently assassinated him on account of an insult offered to the eldest brother. After this outrage, they were driven out of Makran and obliged to settle on the Western frontier of Sind." (Ib. 291). They are again mentioned at 291 infra wrongly as 'Nabūmiya.' Abul Fazl speaks of them as 'Nohmardi' (lit. nine men). He notes that they were then dwelling in the Kirthar range of hills (which runs from Sehwan to Siwi) and were able to furnish a force of 300 horse and 7000 foot. (Ain, Tr. II. 337). According to Tod. their correct name is 'Lumris' or 'Luka' from 'Lukri', a familiar term for 'fox' and they are originally Jats. (A. A. R. II. 1198, III. 1299). More recent writers, however, regard them as the aboriginal inhabitants of Las Beyla. According to the I. G. (XVI. 146), the Sabra, Gunga, Burra and six other tribes constitute a group of nine tribes which are termed Numria. See also Census of Baluchistan (1911), p. 17 and I. G. XVI. 5.

I. 287, l. 6. Mirzā Jāni Beg made this agreement with his soldiers that every one who brought in an enemy's head should receive 500 gabars, every one of them worth twelve Mīrīs,.....of which seventy-two went to one tanka.

The passage is cited in Hobson Jobson by Yule, but he admits his inability to elucidate it. 'The Gubber,' he says, would appear from three other excerpts cited in the article, to have been "some kind of gold ducat or sequin," but the 'gabar' of this passage could hardly have borne any such signification. The fact is that the gold coin which is called 'Gubber' in his excerpts from Lockyer and Milburn has nothing to do with the 'Gabar' of the Tārīkh-i-Ṭāhiri. The clue to the correct explanation of the term is found in the Āīn. Abul Fazl informs us that an Ibrāhīmi was equal to 40 Kabīrs and that 14 Kabīrs were equal to a rupee of Akbar Shāh. (Tr. II.56). Now we are told here that one Gabar= 12 Mīrīs and 72 Mīrīs = a Tanka, (of Sind). This tanka was the Shāhrukhi or Miṣqāli, which was worth about 2/5ths of an Akbari Rupee. (Hodivālā, Historical Studies in Mughal Numismatics, 1-10). The Gai

was therefore equal to 1/6th of a Tanka and 1/15th of an Akbari Rupee. This result is so close to the equation given by Abul Fazi (1/14th of the rupee), that there can be little doubt in regard to the identity of the Gabar and the Kabīr. See also my Notes on Hobson Jobson in the Indian Antiquary for 1929, p 171. s v The name of the Hindu, 'Giriya' (1 11) should be read, perhaps, as Gīdiya i e Gidumal

I. 288, l. 13 Charkas Daftir, the chief of the merchants of Firang, who repaired yearly to Thatta from Hormuz

As the identification of this 'Charkas Daftir' is not easy, it may be worth while to note the ingenious suggestion of Mr Beveridge in regard to the matter. Abul Fazl in his description of this naval battle, writes "Four ghrabs full of men and stores were captured In one of them was the ambassador of Ormuz The rule is that the governor of Ormuz Mırzā Jānı (Beg) had blought him leaves one (ambassador) at Tatta in order to proclaim that these tribes (the Portuguese) had come to help him. Active men brought up their ghrabs and wounded Khusru and he was nearly made prisoner. Suddenly, a gun burst and the boat was broken to pieces and some were killed" (Akbarnāmā, Tr III 920) Mr Beveridge observes that the word for "ambassador" is بطود in his own manuscript and לאפנ in the Igbālnāma-1-Jahāngīi i of the other contemporary chronicler, Mu'atamad Khan The latter author explains that he was the Gumāshta or Agent of the Governor of Ormuz 18 the Portuguese 'Feitor,' which is synonymous with the English 'Factor' Mr Beveridge thinks that 'Daftir' must be a corruption of e e . Agent 'Feitor' Charkas stands for 'Jarjis' or 'Jurgis' (George) and 'Charkas Daftir' would be a perversion of George, the Factor'

A Charkas Rūmi is mentioned in the T A (258, 1 4=E D V 434)

1 288, l 16 But the attempt cost both of them [Daftīr and Khusrau]
their lives.

Khusrau Khan did not lose his life in this battle. He was captured, but escaped in the confusion caused by the explosion of a powder magazine in the Imperial ghrāb (249 ante) When Jani Beg was obliged to go to Agra and leave his minor son, Ghāzi Beg, as his deputy in Thatta, this Khusrau was appointed one of the members of the governing council Subsequently he was accused of the embezzlement of public funds, but Mırzā Ghāzi happened to die soon afterwards (1021 A H 1611 AC) and he was again saved by the skin of his teeth. He is credited by local tradition with the erection, in the days of his power and glory, of no less than 360 public buildings, including mosques, tombs, wells and bridges Popular legend describes these benefactions as undertaken by way of atonement for the involuntary sin of having accidentally beheld a neighbour's wife while she was bathing. It is said that he wanted to gouge out his eyeballs and was with difficulty persuaded by the 'Ulema to adopt and rest content with this mode of expiation The oldest mosque in Thatta -the Dabgar Masjid-is known also as Khusrau Khān's Mosque and

dates back to 1588 A. C. (Cousens, A. S. 121-2). There are biographical notices of Khusrau Khān in Blochmann, Āīn, Tr. I. 363; Maāṣiru-l-Umarā. III. 346-7; K. B. History of Sind, II. 123-4, 144, and elsewhere.

The author is mistaken in prefiring the title "Sultān" to the name of Khusrau at 287, l. 10 f. f. Khusrau Charkas was only a slave of Mirzā Jāni Beg.

I. 293, l. 6 from foot. Rāi Dhar Raj of Jesalmīr.

The real name of the Rājā ruling at this time was Har Rāj. Abul Fazl says that Rāwal Har Rāj's daughter was married to Akbar in the 15th year, 977-978 H. (A. N. II. 358, Tr. II. 518). She gave birth to a daughter named Māhi Begam who died in the 22nd year of the reign. 1577 A. C. (Ib. III. 200, Tr. III. 282). See also the Dynastic List of the Rāwals of Jaisalmīr in Duff (C. I. 291), and Tod (A. A. R. Edit. Crooke, II. 1225 note).

I. 296, l. 16. The Chiefs of 'Umarkot, Jesalmir, Bikānir, Nirohi, Mahwa (Miwār?), Kotāra, Bāhalmer, Nilma, Bārkar Kach, Nākti, Rāmdinpur, Chauduwār and the like, were gained by his bounty.

Some of these place-names are indubitably corrupt. 'Nirohi' must be Sirohi and Bāhalmir, Bahādmir, also called Bārmer, Bālmer or Bādmer in Jodhpur. Kachh-Nakti is Kachh-Nāgan q. v. Hobson Jobson s. v. Cutch. It is another name of Nawānāgar or Jāmnagar. Nāgna or Nāgan is said to have been the name of the village on the site of which Jām Rawal of Nawānagar (also called Little Kachh) founded his new capital. (Ranchhodji Amarji, Tārīkh-i-Sorath, Tr. Burgess, 241; B. G. VIII, 566). Tavernier says that Dārā Shikoh passed through the country of the King of 'Kachnāgona' in his flight. (Travels, I. 347). 'Rāmdinpur' must be Rādhanpur, 85 miles north-west of Aḥmadābād. Constable 26 C. d. Kotāra is Kotra, 60 miles south-west of the town of Jaisalmir. (Tod, A. A. R. II. 1226 and note; Āîn, Tr. II. 278). Barkar may be Pokaran (Pokhran) or Pungal. Both are mentioned in the Āīn as Maḥāls in the Sarkār of Bikāner (Ibid). Constable 26 C b; 27 A a.

This absurd panegyric on the largesses of Khān Zamān is more in the style of a Rajput *Bhāt* than of a sober historian. The name of the Bhatti bard given here (l. 6 f. f.) as 'Hewanda' (حبونده) must be a mistranscription of Chonda جونده.

I. 306, l. 12 from foot. At this juncture, Warash Khān marched upon Karā, and set up his standard.

"Dermish Khān" in Malet (p. 76). Budāuni says Darmish Khān was governor of Khurāsān under Shāh Ism'aīl Ṣafavi. (I. 342 = Tr. I. 449). Khwāndamīr informs us that Durmesh Khān was appointed governor of Herāt by Shāh Ism'aīl in 927 A. H. and that Durmesh entrusted the administration to Khwāja Karīmu-d-dīn Ḥabībulla, his own patron and the person after whom his history is named. (Ḥabību-s-Siyar. Preface. See also Rieu, Catalogue, I. 98). The name is written 'Dūrmesh Khān'

in the M U. (II 549, 17) He is called 'Duimesh Khān' by Erskine also (H B H I 457) A Malik Ruknu-l-mulk 'Izzu-d dīn Durmeshi was killed in 652 A H Raverty says he was called Dhimeshi, as his family came from a place of that name (T N 218, 1 10 'Tr 697-8 note)

'Karā' also is an error Malet (p 76) has 'Furat' The right reading is 'Farrāh It is 170 miles south of Herāt and about 220 north-west of Qandahār. (Angus Hamilton, Afghanistān. 181 Tānīkhi-Rashīdi, Tr 205, E D II. 576, Hunter, I G I 35) Lat 32°-26' N Long 62°-8' E Farrāh is shown in Bartholomew's Atlas of Asia in Everyman's Library, Pl 45 and the I G Atlas 47 B 4

The date of the death of Muhammad Khān Shaibāni is given wrongly here as 915 H (1509 A C) M'asūm, from whom the account is copied, has 917 H (Malet, 76) The correct date is stated as 29th Sh'abān 916 H 2nd December 1510 A C (Houtsma, E I II 545, IV 274, Bāburnāma, Tr 350 note) 'Purdili' Birlās (last line) is called 'Peer Wullee' in Malet (p 74) and more correctly, 'Pīr Wali' in K. B II 61 I 307, l' 9 Ann Hīj 919 (1513 A D), the Emperor [Bātur] having determined upon the conquest of Kandahār, marched upon

This account of Babur's invasions and sieges of Qandahar has been copied by the compiler of the Tarkhan-nama from M'asum's History of Sind and the dates given below are also borrowed from the earlier author But Mrs Beveridge is convinced that M'asum's chronology is quite wrong and she charges him with "setting a regularly discrepant series of dates from the success Shah Beg Khan had at Kahan This event he allots to 920 H, whereas Babur himself states that he received news of it only in 925 H (1519 A D) M'asum makes Shah Hasan go to Bābur in 921 H but Hasan spent the whole of the year 925 H with Babur Again, M'asum makes Shah Beg surrender the keys of Qandahār in 923, but 13th Shawwal 928 A H is inscribed in the Inscription at Chihalzīna, which Babur himself ordered to be cut in commemoration of the event Briefly, all his dates from 919 downwards are ser ratim five lunar years earlier" (Bābur Nāma, Tr 435-6 See also Ibid, 338, 340, 365 and 431)

Mirzā Haidar Dughlāt says that Bābur went on laying sieges to Qandahār for five years and five months (Tārīkh-i-Rashīdi Tr Elias and Ross 357, sce also A N Tr I, 233 note) F gives the date of the capture of Qandahāi as 928 H and states that the final siege lasted for three years (I 202, J 10) Erskine also puts the final surrender into 928 H (H B H I 355) As the real date of surrender was 13th Shawwāl 928, the first siege may be put into Jumādī I 923

I 307, l 5 from foot Shāh Leg took the villages of Kākān and Bāghbān Kākān (Recte Kāhān) is Gāha, 48 miles north-west of Sehwān It is 21 miles north west of Bāghbānān, which is 27 miles north-west of Sehwān and near Dādu Kākān and Bāghbān are mentioned in

-

the Ain as Mahals in the Sarkar of Sewistan. (Tr. II. 340).

Elliot's identification of Kāhān with another place of that name which was gallantly defended by British troops in the First Afghān War, (see footnote), is erroneous. That Kāhān was not in Sind Proper, but in the Marri country in British Baluchistān. (I. D. C. 84 note, Raverty, N. A. 20). The Kāhān of Baluchistān is markel in Constable, Pl. 24 Ce. I. 308, last line. Sultān 'Ali Arghūn and Zībak Tarkhān.

Sultān 'Ali Arghūn was Zū-l Nūn's brother and Shāh Beg's uncle. The second name is variously spelt. On 311 infra, 'Zībak' is called 'Kaibuk' and at page 320 'Kabaik' by the same author. The name seems to be the Mongol 'Kapak' or 'Kaipak' or 'Gucbek', as D'Ohsson writes it. (Histoire des Mongols apud E. D. III. 42 note, See also E. D. III. 72). Mīr M'aṣūm calls him Kībak. (K. B. History of Sind, II. 53, 64, 66).

I. 309, l. 4. He learnt that an army of Samejas.... ...was encamped at Thatta, four kos from Siwistān.

A comparison with the $T\bar{a}r\bar{\imath}kh$ -i-M'aṣūmi, from which the whole account is borrowed, shows that Thautha is a slip for 'Talti' which is 6 or 7 miles north of Schwān and appears to have been on the left bank of the river. (K.B. II, 64; I.D.C. 86: Mihrān, 240 Note).

On p. 310 last line, there is another puzzling perversion of Talti, which is written Thati. It is called 'Talahti' in another extract from M'asum which is translated at 225 ante, q. v. my Note. The river which Shah Beg had to cross was, Haig thinks, probably the Kalri. (I.D.C. 85-6). I. 309, l. 5 from foot. Jam Firoz lest I hatta and fled without stopping

until he reached the village of Pirar.

Pīr-Ār village is 13 miles south of Thattha. The river which Jām Firūz crossed was the Baghār. The Baghār channel was, in old times, called the Ār and so the shrine on its left bank, as well as the village in which it stood, came to be called Pīr-Ār (I.D.C. 86, 126), the Ār of the Pīr or Saint. See also Burton, Sind or the Unhappy Valley. (I. 168).

I. 312, I. 9. In the month of Sh'abān 928 H.;Shāh Beg died.

Authorities differ in regard to the date of the death of Shāh Beg Arghūn. The Tārīkh-ī-Ṭāhiri puts it into 924 H., the Tarkhān-nāma into 926 H., M'aṣūm into 928 (Elliot's Note 502 post), while the T.A. (637,1.1 f. f.) and F. (II, 321,1.14) are in favour of 930 H. M'aṣūm cites in support of 928 H., the chronogram مثر شمان, the numerical value of which is 928, but the prefixing of a بن to the مثر مثر شمان would make it equal to 930. The discrepancy between the T. A. and M'aṣūm is probably due to this difference in the reading of the chronogram as

Modern Europe an writers also are divided into two camps on the point. Elliot (5 02 post), Haig (I.D.C. 87) and the compiler of the I.G. (XXII. 397) are advocates for 928 H. (1522 A.C.), while Erskine (H.B.H., I. 376), Mrs. Beveridge (B.N. 437, 443), Sir Wolseley Haig (C.H.I. III. 501) and Cousens (A.S.) vote for 930 H. (1524 A.C.). The origin of the cleavage centres really found the preference of one party for the

opinion of M'asum and of the other for that of Nizamu-d-din Ahmad 1 313, l 2. When he reached Chāchkān and Kāhmān, he collected an army.

Chāchgān was a district in the Eastern Delta country and the present Tāndo Bego pargana is a part of old Chāchgān. (I D C. 88) It is the Hajkān of the Āīn Hajkān, Rahbān, Jūn, Bāgli-i-Fath and seven other Mahāls, which were in a Sarkār also denominated Hajkān, are registered in the Āīn (Tr. Jarrett, II 340) Chāchgān and Badīn are both on the borders of the Tharr or Sandy Desert between Pārkar and Wangā Bazar. (403 infra) There is a pargana called Chachro still in Thar Pārkar (I G. XXIII 310) Haig thinks that the battle took place at Khāri Khabarlo in the Tāndo Bego pargana This village is near the old route from Chāchgān to Gujrāt, where Jām Firūz sought and found refuge (I D C. 88-9 and Note)

Rahmān is probably identical with Rahīm ki Bāzār or Raham-kā Bāzār or Rahmaka, which lies about forty miles south-east of Badīn and 88 south-east by south of Haidarābād on the border of the Ran of Kachh It is called 'Rahīma' in the Treaty between Muhammad Shāh and Nādir Shāh. (E.D VIII, 92) Tāndo Bego is shown in Constable 26 B b Rahamkā Bāzar is in Lat 24°-20′ N, Long 69°-14′ E It is marked in Constable Pl 26 B c., but the name is printed wrongly as 'Baham Kā Bazār' in the map as well as in the Index

I. 316, l 15 He [Humāyūn] established his own residence · in Babarlūka

Babarlo is about five miles south of Rohri It is now included in the territory of the Mīr of Khairpur (Hughes, Gazetteer, 411, Cousens, AS 34)

Hālā Kandı (1 25) i e Old Hālā is two miles from New Hālā, which is 36 miles north of Haldarābād Lat 25°-45′ N Long 68°-28′ E (Hughes) Constable 26 B c Bitūra of Bathoro as M'aṣūm spells it, was a place, lying on the other side of the river, i e west of the Ren, which is the river referred to (Haig, I D C 93) It may be the Mirpur Batoro of Constable 26 B. c Erskine says the territory north-west of the Ren is meant (H B. H II 216 note)

, I 318, l 3. He [Humāyūn] marched with great speed to Sātalmir

Sātalmir lies two miles distant from Pokharan, which is 85 miles from Jodhpur town It is said to have been founded by Sātal, the eldest son of Rāo Jodhā, about the end of the 15th century (I G XXII 158, Tod, A. A. R 1221 note). Pokharan is shown in Constable 26 C b I 318, l.6 On his arrival, Dair Sāl, the chief [of Amarkot] came out to meet him

'Wair Sal' in the Tulifatu l-Ku ām and 'Bair Sal' in M'asum (K B Tr. II 80) The 3 has been wrongly read as a 3. The right reading is Wairsal (Sanskrit, Vairisal) Bairi Sal or Bersi occurs in the Dynastic List of the Bhatii rulers of Jaisalmir (Tod, III, 1224, Duff, C I 291)

Bairi Sal, the Rija of Bundi, fell in the defence of his capital against the Sultan of Mālwā in 1457 A.C. (I.G. IX 80). Gajpati, Rājā of Jagdishpur, had a brother named Bairi Sal. (A. N. III. 188, Tr. III. 255). Wairsi (Sansk. Vairisinha) is still a common personal name in Sind and Kachh. Wairisāl assumes the fantastic form of [Rānā] 'Parsād' in the A. N. (I. 182; Tr. I. 375), but يرساد is really a miswriting or misreading of يرساد Birsilpur, a town in Jaisalmir, which contains many old monuments of Hindu architecture, is named after Birsil, another form of Bairisal. (I. G. XXI, 104). Raverty also calls the Rānā of Amarkot, Bīrsil. (Mihrān, 464 note). One of Akbar's favourite courtiers was called Rai Sal Darbari. (Blochmann, Aîn, Tr. 1. 419). The Wairsi Rīnā of Amarkot mentioned at 290 ante was this Wairisal or Bairisal and Rana Kumbha Wairsi (p. 292 ante) was his son. Elliot appears to be mistaken in correcting the Beglar-Nama and asserting that 'Wairsi' was not the name of the Sodha chief but that of "the chief clan among the Sodhas". (531 infra). Wairsal or Wairsi was his personal designation.

I. 321, l. 14 from foot. Ahmad Khwāja flourished......nineteen generations after 'Iddi' son of Hātim Tāi.

According to the most accredited Arab chronologists, Hātim Tāi flourished some time before Muḥammad in the latter half of the 6th and the first quarter of the 7th century. His daughter is said to have been led as a captive before the Arabian Prophet. (Nicholson, Literary History of the Arabi, 86; Houtsma, E. I. II. 290.). As Aḥmad Khwāja was taken prisoner in Timūr's sack of Isfahān in 789 A. H. [1387 A. C.] (Rauzatu-s-Ṣafā, Bombay Lithograph, Jild IV. 73; Browne, L. H. P. III. 181, 188), the number of intervening generations must have been nearer 25 than 19, even if the average duration of a generation is reckoned at 30 years. 1387-622 = 765.

I. 323, l. 11. Mirzā Shāh Husain marched back to Bhakkar and on the 12th of the same month [Rab'i I. 961], died at the village 'Aliputra, twenty kos from Thatta.

'Alipūtra' is now called Aripota and lies about six miles from . Tāndo Muḥammad Khān in Gūni pargana (I. D. C. 95) which is about 40 miles north-east of Thattha. Tāndo Muḥammad Khān is shown in Constable 26 B. c. The year of the Mirzā's death is given as 962 in the T. A. (638) and also by F. (II. 322). According to the contemporary traveller Sīdi 'Ali Raīs, Shāh Husaīn was alive so late as Jumīdī I. 962 H. He states that this peace or compromise between the Shāh and Mirā 'Isā Tarkhān was effected by his own intervention and that in the first days of Jumādī I. 962, Sultān Maḥmūd of Bhakkar, who was in command of Husain's forces, returned with the troops towards Bhakkar, while the Shāh started back by river, but died on the tenth day of the voyage. (Mirātu-l-Mamālik, Tr. Vambēry, p. 40. See also Mr. C. E. A. W. Oldham's Art. in Indian Antiquary, LX. (1931), p. 6). But Mir Masarr gives the exact date as Monday. 12th Rab'i I. 962 H. (K. B. Historical Contents of the contents of t

Sind II 91) It may be worth while to note that this wis 4th February 1555 A C which is shown by calculation to have been really a Monday See also 498 infra and Note The C H I puts the death into 1556 A C. (III 502), which must be wrong The events which are said on this page and on 322 ante and 324 post to have taken place in 961 or 962 H, should be put back by a year and 962 and 963 read in their stead I 324, 1 21 He fled to Wanka which was the abode of the Sumras

Wangā Bazar is 74 miles south-east of Haidarābīd Lat 24°-39′, Long 69°-19′ (Th) Sīdi 'Ali speaks of it as the frontier town of Sind (Travels, Tr Vambery, 37) It lies on the bank of the Nīrī, the main eastern branch of the Indus and on the road which crosses the Ran of Kachh to Bhu; (Mr Oldham in Indian Antiquary, 1930, p 240)

I 325, l 10 from foot The opposing forces met at the village of Rakban

Rafiān رئاں in Malet and also in Kalich Beg's Translation from M'asūm in H S II 97) Rafiān may be Rafi Dero where there is a ferry and which lies a few miles south-west of Kingri (Mihrān, 240 Note) But there is a place called Rukān also, about ten miles north-east of Kākar and eighteen south-west of Mehar (Hughes, Gazettetr, s n)

I 326, l. 11 Muhammad Bāki ascended the throne

Authorities differ very considerably in regar1 to the duration of the reign of this monster In Malet's Translation of M'asūm, he is said to have died in 479 A H (1571 A C) and this is repeated by General Haig (I D C 101), but the T A (638, 17), F (II 322, 118) and the Tulifat-u-l-Kii ām (K B II 102) put the event into 993 H The Maäsir-i Rahīmi states that he reigned for 18 years after the death of Mirzā 'Isā in 974 H (B I. Text, II, 326, 1 21) His tomb at Thattha is stated to have been built in 995 H (Cousens, A S 32, 119) Sir Wolseley Haig follows F and gives the date as 1585 A C which corresponds to 993 H (C H I III 502) 979 H cannot possibly be correct, because Muhammad Baqı was alive in 982 H M'asum himself explicitly states that when Kīsū [Gīsū] Khān was appointed governor of Bhakkar in that year by Akbar, he had orders to "proceed to Tatta (that is to invade it) and make Bägi Muhammad Tarkhan prisoner". (240 ante). The same chronicler declares that when Muhammad Sādiq Khān arrived as governor in Rab'ī I 994 H, Mirzā Jānī had not been long in possession of the throne (Ibid 244-5) According to the Tarikh-i-Tahir i also, Muhammad Bagi was alive when Fath Khan was governor of Bhakkar on behalf of Akbar. e between 986 and 994 A H (284-5 ante) His daughter Sindi Begam was also offered in marriage by him to Akbar after the capture of Bhakkar in 982 H (282 ante) The M U also gives 993 H (III 308, 1 8)

I 330, 1 4 A modern story runs thus A woman stole a pair of shoes etc

This is neither a modern story nor a tale known only in Sind It is
a hoary old saga which has travelled 'from China to Peru'

,

[&]quot;Tales in which a person swears falsely and yet tells the truth are

writes Mr. Clouston, "common in folklore. There is one in the Metrical Romance of Sir Tristrem. A Mongolian variant is found in the 'Tales of Ardshi Bordshi'. There are others also in the mediaeval Life of Vergilius and in the [Sanskrit] Shuka Santati or 'Tales of a Parrot'". (Popular Tales and Fictions, I. 177-180). Still another analogue is in Cervantes' Don Quixote (Part II, Chapter 45), where a similar case is said to. have come up before Sancho when he was Governor of Barataria. An. even more modern parallel is found in Manucci. He tells the story of two brothers, "one of whom took the whole inheritance and gave nothing to the other. The rogue put all the wealth in the form of jewels which was the other brother's due, into a hollow staff and during the ordeal gave it to the wronged brother to hold. He then took the oath thus: 'I owe you nothing; what was mine I took; what was yours I made over to you; meanwhile hold this staff.' When he came out successfully from the ordeal, the wronged brother struck the staff angrily on the ground and broke it; by the blow, the precious stones dropped out and the fraud was exposed." (Storia, III. 225).

I. 330, l. 17. The Ordeal of Water.

"Under the government of the Mirs of Sind," Hughes informs us, "trials by ordeal, especially those of fire and water, were frequently resorted to in cases where the accused person declared his innocence or where there was no direct proof forthcoming. The Ordeal of Water mentioned in the Tuhfatu-l-Kirām is described in almost the same terms. by Lieut. James, when he was Deputy Collector of Shikarpur" about 1850. (Gazetteer, 48). Captain Wood also has a word-picture of a similar trial which he witnessed at Mithankote in 1836. (Journey, 45-6).

1. 331, 1. 10 from foot. There are also women who feed on liver and foretell things to come.

"There are amongst the people of Sind", Ibn Batuta writes, "some who merely look at a man and he falls dead on the spot. The common people say that if the breast of a man killed in this way is cut open, it is found to-contain no heart and they assert that this heart has been eaten. This is commonest in the case of women and a woman who acts thus is called a Kaftar". (Gibb, Ibn Batūta, 225; Defrémery, IV. 36). The Turkish admiral Sidi Ali Capudan also notes that "in Sind are a great number of liver-eaters, against whom you must be on your care, because if they meet a man who eats his dinner in public, they have the talent of eating up his liver with their eyes and so kill him ". (Al Muhit, Tr. Von Hammer, J. A. S. B. V. (1836), p. 463). Abul Fazl describes the liveeater or جگرخواد as " an individual who by glances and incantations e= extract a man's liver...... He can convey intelligence from long distances in a brief space of time and if they are thrown into the river with a stone tied to them, they do not sink ". (Ain, Tr. II, 338-9). The of the Maāsir-l-Umarā says that the 'Jigar-khwār' is called et Dākin in the vernacular. (III. 313, 1. 3).

I. 331, l. 5 from foot. There is a tribe entitled 'Bawartiya' which go about in the guise of beggars professing to explain mysteries and past events

There is no tribe or caste so called any where in India sition - has been wrongly read as a part of the name, which is really ' Vartya'. The reference is to the priests of the Jainas and the designation is derived from the Sanskrit, Vrat, a vow. These ascetics are mentioned by Du Jarric, who says that Akbar was supposed by some people to follow the opinions of the 'Verteas' (Payne, Akbar and the Jesuits, p. 69) In one of the contemporary Jesuit Letters also, Pinhero writes of Akbar, that "he follows the sect of the Verteas, who live together like monks in one body and undergo many penitential observances. They eat nothing that has had life Before they sit down, they clean the spot with cotton brushes in case they sit on and kill the insects" (Maclagan's Art on 'Akbar and the Jesuits' in J A S B 1xv, 1896, Part I 70) The Italian traveller Pietro della Valle (c 1626) describes a temple he saw at Cambay which belonged to the race of Indians who shave their heads, (a thing unusual to all others, who wear long hair like women), and are called 'Verteas' (Ed. Grey, I. 104) Thevenot also (c 1665) speaks of the Jama monks as 'Vartias' and describes their manners and customs at some length. (Travels into the Levant, Tr. 1687, Part iii, 61, Ch. xxxvi). The priests of the Jainas have been reputed from very remote times to possess great skill in astrology and other occult arts (A. N L 50, Tr I. 147 and III 67, Tr. III 93, Dabistan, Tr Shea and Troyer, II 210-6).

The art of tracking footprints—the Puggy system,—as it is also called, is described by Burton, Sind Revisited, I. 180, see also Yule, H. J. 786.

I. 332, l 17. The story of Sassi and Pannun.

Burton repeats a popular derivation of the first name from 'Sansār me Suni', 'Heard (renowned) in the world' (Sind Revisited, I. 128, note) But it seems to be the Sanskrit Shashin, one of the many names of the Moon 'Pannūn', 'Pannū' or 'Panhu' also is derived most probably from the Sanskrit 'Bhānu', the Sun The legend is of some interest as indicating that the old channel of the Indus flowed directly from Brahmanābād past Bhāmbor. Bhāmbor stands on the Ghāro which ceased to be an arm of the Indus only within recent times (I. D C 52, Holdich, G. I. 153).

I. 335, l 9 Kāzi Murtazā Sorathi, a resident of the village of Katiāna This is 'Kutiāna' now in Junāgadh State, Kāthiawād, about 25 miles east of Porbandar and on the banks of the Bhādar It is an old town and is said to derive its name from Kunti, a Chāran woman (I G. XVI. 57; B G. VIII Kāthiāwād, 525). The sobriquet 'Sorathi' is derived from the fact that Kuṭiāna is in Sorath. Constable Pl.31 A a writes the name Kuntiyāna,

I. 343, l. 11 from foot. They [the Sumras] sprang from the Arabs of Samra.....who arrived in Sind in the fourth century of the Hijra.

The author means 'Simarra' on the Tigris in Iraq, the name of which was changed by the Khalif Mut'asim into 'Surra-man-raa', 'he who sees it, rejoices', for the sake of good augury. It was from 836-892 A.C. the capital of the 'Abbāsides, but sank into insignificance after the return of the Khalifs to Baghdād. It is still, however, a place of pilgrimage, as two of the Shi'a Imāms are buried there. (Guy Le Strange, in J. R. A. S. 1895, p. 39; L. E. C. 53).

I. 343, l. 5 from foot. With the 'Ulamāi Mūsawī, he brought to Sind.

Is a misrcading of I. The person intended is Sayyad 'Ali Mūsawi. He is spoken of as "the Sayyid" in the very next sentence. (See 485 infra and also K. B. History of Sind, II. 38).

Mut'alwi [Mat-'Alwi, Mat of 'Ali] is so called from this 'Ali Mūsawi. It is now known as Matāri. (481 infra note). It is in the Hālā Tāluqa and lies about sixteen miles north of Ḥaidarābād. (Hughes, 487). Constable 26 B c.

I. 347, I. 8 from foot. Story of Chanesar and Laila.

The name of the lady is here spelt as if it was the Arab W. but it seems to be really the Hindu Lila (or Lilavati) and it is so spelt at 263 ante.

So, 'Kaunrū' must be Kāmarūpa, and 'Marghin' (348, l. 6) 'Mrignaina', deer-eyed. The Gujari queen of Rājā Mānsinha Tomar of Gwālior bore the latter name. Similarly, 'Mendra' (p. 347, l. 6) must be 'Mahendra'.

VOL. II. GHAZNAVIDES, GHORIS AND SLAVE KINGS.

II 3, l 1. He [Albertini] was indebted to the Sultan of Khwarizm for the opportunity of visiting India, for he was appointed by him to accompany the embassies which he sent to Mahmud of Ghazni, .[Abu Rihān] is reported to have stayed forty years there [in India]

The statements made in this paragraph are almost all wrong Alberuni was a native of Khwarizm and was in the service of its rulers only until the annexation of the province by Mahmud in 408 H 1017 A C "The princes of the deposed dynasty and the leading men of the country were then carried off ", says Sachau, " as prisoners of war or hostages to Ghazni They were then sent away to distant fortresses more or less as prisoners of state Alberum was one of them, and appears to have stayed in different parts of India and been treated as a hostage or political prisoner, kept on honourable terms. But he was no favourite with Mahmud or the persons in power But a radical change in his life took place soon after the accession of Mas'ud, who settled upon him a handsome pension, which enabled him to devote himself entirely to his scientific work" (Tr Pref viii-vvi) He died on 3rd Rajab 438 H, 13 Dec 1048 (Houtsma, E. I I 727, LHP.II. 105) Alberuni appears to have left India soon after the death of Mahmud and resided during the rest of his life at Ghazni or Khwarizm As Mahmud did not reign for more than thirty-three years, Alberuni's stay in India could not possibly have extended to so many as forty Its duration could not have exceeded thirteen years, even if he returned in the year of Mahmūd's death

The 'Tarikhu-l-Hind' treats of the literature and science II 5, l 14 of the Indians at the commencement of the eleventh century

This is how the work is generally called and cited even in Huart's History of Arabic Literature (p 302) and Houtsma's Encyclopaedia of Islam, (I 726), but the correct title is 'Kitābun fi Tahqīq-i-mā li-l-Hind, (Nizāmu-d-dīn, Introduction to the Javāmi'u-l-Ḥikāyāt, 37, Nāzım, Sultān Mahmūd of Ghazna, p 6, Raverty, Mıhrān, 186 note) 'Alberuni himself writes in the Preface that his "book is nothing but a simple historic record of facts" (Sachau, Tr I 7, کال × × × عن تحقیق ماللهد Text Pref p iv and p i)

II 9, l 6 from foot. This care is now well-known by the name of Bakar

' Bakar' has no sense or meaning here Sachau has the right reading 'Var', an old Avestaic word meaning 'enclosure' (Tr II 10) word is also used for 'cave, place of refuge' etc The 'Var-Jam-kard', the 'Var made by Jam or Yima' is described at length in the Vendidad It was to be "as long as a riding ground on every side of the square, and he was to bring thither the seeds of sheep and oxen, of men, of dogs, of birds and of red blazing fires," to preserve them from "the fatal

winters which were to fall upon the material world and bring fierce, foul frost and make snow-flakes fall thick on the highest tops of mountains." (Fargard II. 22-25, Darmesteter's Trans. in Sacred Books of the East. IV. 15-16). The story is told there in connection with a great Deluge and the 'Var' is the Indo-Aryan analogue of Noah's Ark.

II. 12, l. 18. Jaipāl, whose successor was Nardajanpāl, who ascended the throne in 412 A.H. His son Bhīmpāl succeeded him after the lapse of five years, and under him the sovereignty of India became extinct.

This is translated wrongly. S. renders the passage thus:

"The latter [Tarojanpāla, i. e. Trilochanapāla] was killed in A.H. 412 and his son Bhīmapāla five years later." (II, 13).

At 463 infra, Elliot himself speaks of Alberuni giving 412 H. as the date of Pur Jaipāl's [Trilochanapāla's] death and not of his accession. Ibn-al-Athir, (Kāmilu-t-tawārikh, Ed. Tornberg, IX, 219) and Farrukhi also, in his Qaṣida, state that Trilochanapāla was murdered by his mutinous soldiers in 412 H. (Nāzim, M.G. 95 n and 206). Banākati also states that he was killed in 412 H. (Tr. in E.D. III. 59).

II. 13, l. 1. Though I have vanquished you, I do not desire that any one but myself should obtain the ascendancy over you.

It is stated in the footnote that this is translated differently by Reinaud. Sachau renders the sentence just as Reinaud does in *Fragments Arabes et Persans*, (p. 154), and as both agree to differ from Elliot, it is safe to say that the true meaning is, 'I have been conquered by you, therefore I do not wish that another man should obtain the ascendancy over you!' (S. II. 13).

It may be also observed that Anandapala had never vanquished Malimud, and the epigram or trope as it is worded in Elliot's rendering would be a mendacious as well as wantonly provocative vaunt.

II. 13, l. 3. This prince [Ānandapāla] was a determined enemy of the Musalmans from the time that his son Nardajanpāl was taken prisoner, but his son was, on the contrary, well disposed towards them.

Reinaud (l. c. 154) and Sachau understand this also differently. As 'Nardajanpāl' is not known from the histories to have been taken prisoner at any time by Maḥmūd, it seems preferable to accept here also, Sachau's version: 'This prince cherished the bitterest hatred against the Muḥammadans from the time when his son was taken prisoner, whilst his son Tarojanpāla [Trilochanapāla] was the very opposite of his father'.

II. 14, 1. 16. He ['Utbi] records an event as happening in 420 Hijra, but the interest of his work ceases with the year 410.

Elliot has been misled on account of a copyist of Jurbādhaqāni's Persian translation having ascribed an event, which really occurred in H. 402 to H. 420. (Reynolds' Tr. 474, but see 'Utbi, Dehli Litho.

Text 427, 1 3) Rien (Persian Catalogue, I. 158) states that all the Mss of Jurbādhaqām in the British Museum agree in reading the date as 402 H Browne states that the latest event recorded by 'Utbi relates to 411 H (1020 A. C), though the author is said to have died so late as 427 A H =1037 A C (L H P. II 114) Di. Nāzim repeats the statement (M. G 4), but in the last chapter, the date 413 H. "It is clearly mentioned in connection with the proceedings of the Vazīr Ahmad bin Hasan Maimandi (Delhi Lith of A H 1263, p 478, 1 8) The death of Mahmūd's brother Amir Nasr which took place, according to Gardezi, (Z A Text, 79, 1 7) in 412 H is also explicitly mentioned, though the year is not specified ('Utbi, Dehli Text 441, 1 11, Reynolds' Tr 486)

II. 15, l 4. The most ancient of these [Persian translations of 'Utbi] is that of Abu-l-Sharaf Jarbāzkāni

Jurbādhaqān, also called Gulpāyaġān, is a place situated between Ispahān and Hamadān Mīrkhwānd, Khwāndamīr, Firishta and other late compilers have all freely used and implicitly relied upon Jurbādhaqīni's Persian version and never turned to the Arabic original, but it is really of small value. Nöldeke has shown that it is "exceedingly free, the translator's object being not so much to produce an accurate rendering, as a rhetorical imitation of the original He changes, omits and adds as he pleases" (Browne, op cit II 471-2) He has also omitted several portions of the text, and to judge from Reynolds' translation, which is extremely incorrect, muddled the proper names fearfully Most of the errors and discrepancies which are found in the later epitomists are, in fact, due to their having used this secondhand authority instead of the original

II 20, l 9 and Footnote 2 There was a clear fountain of water of the dimensions required by the Hanafi law for purification, [that is, a cube of ten spans, q v the footnote]

Here 'ten spans' must be an error for 'ten cubits'— each of 24 fingers or about 18 inches

"Among the orthodox (Musalmans), it is generally held that if a dead body or any unclean thing falls into flowing water or into a reservoir more than ten cubits square, the water can be used. It is for this reason that the pool near a mosque is never less than ten cubits square. If of that size, it is called deh dar deh (literally, 10 × 10). It may be, and commonly is, larger than this. It should be about one foot deep. (Sell, Faith of Islam, quoted in Hughes, Dictionary of Islam s v. Water). Babur tells us that he ordered such a tank to be carved out of a single mass of rock and he gives the dimensions as 10 by 10 cubits (B. N. Tr. 606; see also Gulbadan, Humāyūn Nāma Tr. A. S. Beveridge 98). II 20, 19 There was a clear fountain of water. If any filth were thrown into it, black clouds collected, whirlwinds arose etc.

This 'tale of monder' reflects and records the survival of an ancient

superstition. The spring was, what the Buddhists called a Nagahrada a 'Niga-lake' or 'dragon-fountain'. The Chinese monks, Fa Hian, Sung Yun and Hiuen-Tsiang naively relate wonderful tales about such springs in their Travels. The Nagas were believed to be demons, half men. half-brutes, who had the power of hurling down or stopping rain, piling snow, sending tempests of drifting or flying sand and hail, raising high winds, riding the clouds and gliding over the waters. These halfhuman, half-divine beings resided in such natural reservoirs and many circumstantial accounts of offended Nagas or 'Poison-dragons' spitting winds, rain and snow to punish those who had polluted the waters or otherwise incurred their displeasure arrest attention in the Pilgrims' Journals. (Beal, Buddhist Records, Fa Hian, I. xxix, xlii; Sung Yun, l. xcii: Hiuen Tsiang, Ibid. 25, 49, 64-6, 122, 137, 159). Dragon worship was, in fact, the real religion of the people in many parts of Afghinistan and the Indian frontier in the 6th and 7th centuries of the Christian era. The road to all happiness and prosperity was believed to lie in the propitiation of the Nagas or Dragons, while any offence given to them wittingly or unwittingly was sure to bring in its train the most dreadful calamities. (See A. M. T. Jackson's Note in Bom. Gaz. I. 502-503).

Stories of such fountains are common also in other writers. Alberuni had heard of a well in the mountains of Farghana, "where it begins to rain as soon as any one throws any dirty thing into it, also of a cave in Tabaristan, where heaven becomes cloudy as soon as it is polluted by filth and of a mountain between Herat and Sistan, where you hear a clear murmur as soon as it is defiled by human excrement". (Sachau's Tr. of Atharu-l-Bagiya, or Chronology of Ancient Nations. 235). Abul Fazl speaks of a lake in the mountains of Lar between Kashmir and Tibet where "a heavy fall of snow and rain ensues, if the flesh of an animal fall into it ". (Ain, Tr. II. 363). The strangest thing about the matter is that this old-world belief is not, even now, quite extinct. Sir Frederick Goldsmid was credibly informed that such "a mystic spring" was actually in existence in the mountains of Dāmaghān in Persia. "It is said," he writes, "that when the Shah [Nasiru-d-din] passed through Damaghan en route for Mashhad, being incredulous of the story, he ordered some of his suite to throw dirt into the spring, when immediately such a wind arose, that the royal camp was rolled up like so much paper and the Shāh was compelled to have the cistern completely cleaned out and purified before the wind would cease ". (Eastern Persia, p. 381).

'Utbi and Jurbādhaqāni say that the fountain was in the Pass of Ghūrak or Ghūzak i and that the site of the battle was between Ghazni, Farwān and Lamaghān. Alberūni tells us that one of the tributaries of the Ghorwarand, that is the Kābul river, was the river of the Pass of Ghūzak. (Indica. Tr. I. 259). But in 'Awfi's version of the story, the fountain is located at a place called Bagharū or Nagharū (182 infra).

(Nizāmu-d-dīn, Introduction to the Jawāmi'a, 63, 252) Now Ghūzak ıs mentioned by Baihaqı also as تورك Baz or Faj [or Pass] of Ghūrak and as a place on the route from Ghazni to Hindustān (127 infra, Text 502.1.7 f. f.) See also Text 500.1.7 where there is another reference to the place The connecting link here is found in Muqaddasi who states that there was at Shiyan (near Naghru) a place in the district of Askimasht, "a wonderful spring" (Alisan, Ed Goeje, in B G. A'viii 303). Askimasht is apparently the Iskamish of our maps (Constable 22 C b) شيال is a miswriting of شيال is a miswriting of 'Shupiān' i e Hupiān or Opiān, which lies about five miles south of Parwan, three miles north of Charikar and about twenty miles east of Ghorband Opian possesses "many vestiges of antiquity" and is "distinguished by its huge artificial mounds, from which copious antique treasures have been extracted" (Masson, Journeys, III 126, 161, Cunningham, A G. I 24 and Map III, Beal, loc cit I 55, 59, II 285 Notes) The wonderful spring of Shiyan may have been, therefore, near Parwan and the 'Uqba or Pass may have been that of Ghurak, 2. e. Ghurband, which is said by some to have been so called because it lay on the route to Ghur or Ghor The fact that Parwan is called 'Paryan' in the Malfuzāt-z-Timuri (E D III 401, A. N I. Tr 540) may also indicate that the place was associated in the popular imagination with 'Paris' or 'Fairies,' and believed to have something uncanny or supernatural about it. The phenomenon which was responsible for the panic in Jayapal's host was, no doubt, a snow-storm and Wood assures that a whole party of his former fellow-travellers was actually destroyed in the Pass of Ghorband by a violent one when traversing it (Journey 123)

II 21, l. 13 There is no alternative for us but to destroy our property, ××× cast our children into the fire and rush on each other with sword and spear etc

This is an early allusion to the 'Johar' or Juhar, 'Shaka' or 'Sakha' in Muhammadan literature, though there is an older one in Biladuri, who says that when Dahir, the King of Sind, was slain, his wife set fire to the fort and burnt herself with all her handmaids (E D I. 122, Remaud, op cet 170, 198) But the practice must be of much greater antiquity as Quintus Curtius (IX 4) mentions it "When Alexander the Great marched during his retreat, against the Agalassoi, they were routed after an obstinate defence, but the survivors, who were said to number 20000, set fire to the town and cast themselves with their wives and children into the flames" (V Smith, E H I 91 and note) The popular derivation of this word 'Johar' is from 'Jivad' 'life' and 'hara' 'taking', as in C H I III 19 note, but this is rejected by Sir G. Grierson He traces it to the Jatugriha, the house of shell-lac and other inflammable materials which the Kauravas had perfidiously prepared in secret for burning to death the Pandavas. (Mahabharata, I 141-151) The Prakrit form, 'jauhara' is said to occur in Jaina literature

(V. Smith's Note in Akbar the Great Mogul, 72; Crooke's Note in Tod, A. A. R., I. 310).

II. 21, 1. 21. [Peace was made] on condition of receiving 1,000,000 dirams of royal stamp and fifty elephants.

They were not royal dirhams but Shahiya dirhams. The words in the text of 'Utbi (Dehli Lith, 26, l. 8) are clearly الفا لف درهم شاهيه, which must mean 'Shāhi dirhams'—dirhams struck by the Shāhiya rulers of Waihind. Elsewhere, also, in his account of the booty obtained at Bhimnagar, 'Utbi says that "the stamped coin amounted to seventy thousand thousand Shāhiya dirhams" سبون الف الف درهم شاهيه (Text, 290, 1. 11), not 'royal . dirams' as in Dowson, at 35 infra. It is significant that 'Utbi does not use. the word when dirhams are mentioned in other places. The reason probably is that the dirhams spoken of in those passages were not the Shāhi mintages but the dirhams of Sultan Malmud. For instance, all that he states in connection with the capture of Multan is that the indemnity demanded was "twenty thousand thousand dirams". [32 infra; Text. 263, 1, 13]. The total money value of the booty carried off after the Qanauj expedition is similarly estimated at "three thousand thousand dirams". ثلثه الف الف درهم (50 infra; Text, 403, 1.9). The specific references to Shahiya dirhams in connection only with Jaipal and Bhimnagar which was in Shahiya territory and the deliberate omission of the qualifying denomination in all other passages are, I suggest, of pregnant significance.

II. 23, l. 6 from foot. The Rājā [Jayapāla] was contented to offer the best things in his most distant provinces to the conqueror, on condition that the hair on the crowns of their heads should not be shaven off.

This direct reference to still another 'Hindu Institution' is noteworthy. Hiuen Tsiang remarks in the 7th century, that the Hindus wore a little knot of hair on the crowns of their heads. (Tr. Beal, I. 75). In the 16th, Du Jarric records that when a Brahman of Lahor "who had determined to......turn Christian cut off his 'sendi '-the long lock of hair they let grow on the top of the head as a mark of gentilism, the Pagans were filled with consternation as they had never seen any one do such a thing before". (Payne, Akbar and the Jesuits, 141-2). Sir Thomas Roe's chaplain, Edward Terry, also mentions the Hindu custom of shaving off the hair from the head, reserving only a lock on the crown, but he adds, in a grotesquely blundering fashion, that this is "for Mohomet to pull them into Heaven"! (Early Travels in India, Ed. Foster, 308). Chotikat is even now, a term of reproach which is applied in the Punjab, to those who have, on conversion to Islam, cut off the 'Choti' or Hindu scalp-lock. (Ibbetson, Punjab Ethnography, quoted in Crooke, Tribes and Castes of the North-Western Provinces, IV. 226). But perhaps the oldest notice of this peculiar feature of Hindu manners is to be found in Megasthenes. He has left it on record that "if any Indian

is guilty of a very heinous offence, the King orders his hair to be cropped, this being the punishment to the last degree infamous" (Fragment xxvii Tr in McCrindle, Ancient India as described by Megasthenes and Arrian, Ed. 1877, pp. 73-4) The excision of the scalp-lock (Shikhā or choti) would thus appear to have been regarded as a stigma or symbol of infamy and social degradation even about 803 B. C

II 26, l. 2 from foot On Thursday, 8th of Muharram, 392 H

Gardezi, the author of the contemporaneous Zainu-l-Akhbār, has the same date but gives the week-day as Saturday. (Ed Nāzim, 66, l 11) He is followed in the T A. (5, l 2 f f) and B (I 11=Tr I 19) F makes it Monday (I 24, l 8), though the date given by all these three authors also is 8th Muharram As 1st Muharram 392 H corresponded to Thursday, 20th November 1001 A. C., (vide Burnaby, Jewish and Muhammadan Calendars or Pillai, Indian Ephemeris, Vol III), 8th Muharram or 27th November must have been a Thursday and not a Saturday or Monday 'Utbi is thus right and those who differ from him must be mistaken

II. 28, 1 7 from foot The conquest of Bhatia.

Bhera, Uchch, Bhatner, Bhatinda and even Bhawalpur have been put forward as identifications of Bhatiya, but all, except Bhera, are ruled out by the crucial test of strategetical considerations. The capture of Waihind had merely opened Mahmud's way into the Northern Punjab and he had only just acquired the power of extending his incursions to the other side of the Indus He had not even crossed that river and it is difficult to conceive how he could have advanced so far into the interior of an unknown continent as Uchch, Bhatner, Bhatinda or Bhawalpur, without possessing a single base of operations within its borders, any means of keeping up his communications or of preventing the rulers whose territories he had invaded from cutting off his retreat None of these four towns is less than three hundred miles distant from Waihind and it would not have been possible to reach any of them without opposition in crossing several of the Punjab rivers Mahmūd is not said to have crossed any other river than the Indus to reach Bhera, which lies on the Jhelum, the very next river to the Indus. and only about 80 miles distant from Waihind It lies, in fact, "on the ancient trade-route between India and Afghanistan and is even now the largest and the most prosperous commercial town in the Western Punjab" (LG sn) "The two great routes of the caravans from the Salt Range diverged at Bhera and here also was the most frequently used ferry on the Jhelum" (Cunningham, AGI 155) We know that the river was crossed at Bheda by the Chinese pilgrim Fa Hian (Beal, Buddhist Records, I xxxi) Bhera has also figured prominently in the history of all invasions of India from the north-west. It is recorded among the conquests of Chingiz Khan's general Turtai, who sacked it

and afterwards proceeded to beleaguer Mūltān. (Tārīkh-i Jihān Kushā, 392 infra). Raverty was of opinion that the island on the Jhelum from which Shihābu-d-dīn Tamīmi vainly attempted to repel the advance of Tīmūr was near Bhera. (Mihrān, 279 note). Bābur notes that Bhera was on "the border of Hind" and he captured and held it to ransom in his very first invasion of 1519 A.C. (Tūzuk in E.D. IV. 230, 233). Elsewhere, he speaks of Bhera as if it was the furthermost outpost on the Hindustān Frontier. "The Kingdom of the Lody Afghāns," he writes, "extended from Bhera to Bihār" (Tūzuk-i-Bāburi in E. D. IV. 259) and he exultingly records that "the countries from Bhera to Bihār which were under his dominion yielded a revenue of fifty crores". (Ibid. E. D. IV. 262).

When Humāyūn fled to the Punjāb after the rout of Qanauj, it was at Bhera that the treacherous Kāmrān and 'Askari deserted him as they wanted to march to and take possession of Kābul. (T. A. 203. l. 9=E. D. V. 206). Bhera was sacked by Bābur's grandson, Mirzā Muḥammad Ḥakīm also, during his invasion of Hindustān. (Akbarnāma, Tr. III. 508, Note).

Again, when Prince Aurangzeb was sent to reconquer Qandahār, in 1059 H, with S'adu-lla Khān the Vazīr as his colleague and director, he was ordered to march from Multān to Bhera, where S'adu-lla was to join him with his own army and they were to proceed from that base to Kābul via Bangash. ('Amal-i-Sāliḥ, Text. III. 72, l. 6; Shāh Jahān Nāma in E. D. VII. 89). Bhera, in fact, was a conspicuous point d'appui in the North-western Punjāb and the spot from which military operations could be most advantageously conducted. It was the thoroughfare of every invading army—a key-position, or strategic pivot the importance of which is demonstrated by historical facts which it will not do to ignore.

II. 30, Foot-note. Firishta says 280 [elephants were captured] and Mirkhond 120, but does not notice that this was the personal share of the Sultan.

Neither of these authors takes notice of the point because it does not stand in need of any. The question of the 'personal share' of the Sultan does not at all arise. Elephants were not allowed, at this time, and for long afterwards, to be retained by private individuals or subjects, and every animal which was captured in battle, fell ipso facto to the share of the Sultan. See infra 40, where 'Utbi explicitly states that after the sack of Thānesar, "all the elephants were driven into the camp of the Sultan, except one which had fled and could not be found". Reynolds' rendering is, "they were all brought to the Sultan's halter-place". (l.c. 395). Amīr Khusrau tells us that after the conquest of Deogīr in 706 H., Malik Kāfūr gave orders that "the soldiers should retain the booty they had acquired, with the exception of horses, elephants and treasure, which were to be reserved for the Sultan". (Khazāinu-l-Futūḥ in E.D. III. 77. See also ibid. 91-2). All the elephants captured by Balban from Tughril

and by Prince Ulugh Khān in the raid; of Jājnagar are explicitly stated by Barani to have been reserved for the Sultan (E. D III 120 and 235). All the elephants captured by Firūz Tughlaq in his campaigns in Bengal and the jungles of Orissa or sent to him as gifts or tribute by Sultan Sikandar and the Rājā of Jājnagar are said, by Shams-i-Sirāj, to have been led and mustered before the Sultan and carried off along with himself to Delhi. (T F 175, I 16, E D III, 316).

Budāum says in illustration of Islām Shāh Sūri's ambition to establish an absolute autocracy and one-man rule, that he "would not allow any Amir to keep more than a sorry female elephant, adapted only for carrying baggage" (Text I. 384. Tr. I. 496=E D. V 487). The author of the Wāqiāt-i-Mushtāqi also declares that in the last two or three years of his reign, Islām Shāh did not present to any of his Amīrs a single elephant (E. D IV 504 note) Elephants were occasionally bestowed by the Sultans of Dehli as marks of special favour on their subjects and great Amīrs and leaders of armies do appear to have kept them, but it was a regal privilege which was jealously guarded and its assumption without permission was regarded as an overtact of treason or rebellion (Tabaqāt ī-Nāsiri in E. D II 338, 343 post, Text 192, 1. 8, 198, 1 10, Raverty's Tr. 650 note, and 662) The gift of an elephant was a special favour (Ibid. 252, 1 19)

But evidence still more direct is available. It appears from a Qasīda of the contemporary poet, Farrukhi, that the rule was to divide the booty collected after a battle in the presence of Sultan Mahmūd himself Ordinary articles were, after valuation by experts, distributed among the soldiers, but "all precious stones, arms and elephants, to the value of one fifth of the total spoils were, set apart for the Sultan" (M. G. 138). Baihaqi also explicitly states that all the elephants were under the direct control of the Sultān Masūd, (349, 488) and that they were annually reviewed by him in person. (M. G. 139) Indeed, Nizāmu-d-dīn Ahmad explicitly states that in those early days, no one had the right to keep elephants except the Bādshāh (T. A. 33, 1.10, see also F. I. 69, 1.9)

Dr. Nazim gives the purport of 'Utbi's words thus "He ['Utbi] states that the booty was so immense that the share of the Sultan alone amounted to 120 elephants, besides, gold, silver and arms" (M G 101) Altogether, only 120 were captured and all of them formed part of the Sultan's share Not one went to anybody else The words used by 'Utbi are in the arm of the arm of the corresponding to 'personal' or 'special' in the Arabic text (Dehli Lith 260, 1.8) Reynolds' translation is "a hundred and sixty (sic) elephants augmented in this victory the stables of the royal stud, with an enormous booty in money and weapons" (p. 324). All that Gardezi states is that 280 elephants were captured (Z A 67, 19)

Il 31, last line He [Abi-l-Fatuh Daud] determined to load all his property on elephants and carry it off to Sarandib,

and he left Multan empty.

This assoveration is, on the face of it, so preposterous, that Raverty hazarded the almost equally amazing conjecture that 'Sarandīb' must stand for Kachh Bhuj. (Mihrān, 325n). But as he has not advanced any reason for the pronouncement, it seems scarcely necessary to discuss it. Dr. Nāzim makes Dāūd fly to "an island in the Indus". (M. G. 97). It seems futile to indulge in further speculations and surmises, but if it is at all worth while to do so, 'Debal-Sind' would appear to be a more plausible restoration. Muḥammad-i-Qāsim is said to have sent the prodigious treasure acquired at Multān to Debal by boats with a view to its ultimate transportation to Baghdād. (Chachnāma in E. D. I. 207 and note).

The Qarāmata rulers of Multān were closely associated with Debal and Mansūra. In fact, the Ism'āīli heresy seems to have found its way into Sind and the Punjab mainly through Debal, which was the great entrepot of commerce with other parts of Asia. Maḥmūd of Ghazna is known to have led a punitive expedition against Khafīf; the ruler of Mansūra, because he was "an apostate Muḥammadan" or Qarmatian. (249 infra). Khafīf was most probably a Sūmra and the letter from the chief of the Druses to Shaikh Ibn Samar bin Rājā Bal exhorting him to "bring back Dāūd the Younger, into the true religion" indicates clearly that the Qarmatians of Multān were closely connected with the Sūmra chiefs of Upper as well as Lower Sind, i.e. with Mansūra as well as Debal. (See Elliot's Note, 491 infra). 'Utbi, though learned in the history of Islāmic conquest, was almost entirely ignorant of Indian geography and he seems to have mixed up 'Sarandīb' with 'Sind-Debal' or 'Debal-Sind'.

Firishta [I. 24, l. 1 f. f.] speaks of Abi-l-Fath-i-Dāud as the grandson of Shaikh Ḥamīd Lody, and the error is reproduced and propagated in-C. H. I. III. 14, although it had been demonstrated and denounced long ago by Raverty. (Mihrān, 325 note). 'Lody' must be a miswriting of Lawi, who was the son of Ghālib. Mas'ūdi (Prairies, I. 377; Sprenger, 384; E.D. I. 21), Iṣṭakhri (Ed. Goeje, 175, l. 7] and Ibn Ḥauqal (E. D. I. 36) all say that the rulers of Multān were descended from Usāma bin Lawi bin Ghālib, an Arab of the tribe of Quraish, the same to which Muḥammad belonged. The Lodis are known to have been Afghāns and "there were no Lodis, nor Lodi rulers", as Raverty incisively states, "in Multān, at this time nor centuries afterwards".

II. 33, l. 13. Victory near Waihind.

Nothing more specific than this can be gathered from the Chronicles, but it is stated in the Official Gazetteers of the districts of Attock and Rāwalpindi and by Delmerick also in his History of the Gakkars (J. A. S. B. XL. (1871), p. 71) that, according to a tradition still current in the locality, this battle was fought in the plain of Chach between Hazro and Aṭak. Waihind, which is fifteen miles above Aṭak on the left bank of the

Indus, is, by its position on the river, a place of strategetical importance, and Alexander The Great is generally thought to have crossed the Indus at Waihind. (Smith, E H I 55) It appears to have been regarded as a military station of consequence even so late as the reign of Akbar During the campaign against the Raushanāis or Tārīkis in 994-5 H (1586-7 A.C.), Mādhav Sinha, the brother of Rājā Mān Sinha of Amber, was stationed at Waihind with a well-appointed army and was, consequently, able on a critical occasion, to come to Mān Sinha's assistance and rout the Afghāns (B II 355, Tr II. 366, see also TA in EDV 455 note)

Raverty, misled by a blundering gloss of F's, confounds Waihind with Bhātinda, and avers that Bhātinda was the capital of Jaipāl, whose kingdom he extends to the Hakra or Wahinda, (N A 320, T N Tr. 79-80 note), but both these assertions are demonstrably erroneous. The nameless Hindu History of Kashmīr which he relies upon so implicitly and cites so frequently (T N Tr. 453, 455, 460 Notes) is a modern compilation of no value.

II. 33, 1 7 from foot. Brahmanpal, son of Andpal

I venture to say with some confidence that رحيال is a misreading of the outland his copyists do not appear to have ever known what to make of the outlandish name Tarojanpal (Trilochanapāla). Here it is written Brahmanpāl, elsewhere (47, 48, 50 infra), it assumes the form 'Purū Jaipāl' and in some Mss of Jurbādhaqāni's translation 'Perou Hebāl' (Ibid 47 note). Even Dr. Nāzim has not been able to escape the pitfall. He says that Ānandapāla's army was placed under the command of Brahmanpāl his son and defeated in the battle of Waihind in 399 H (M G 90), but رحنيال (Delhi lith 279, l 3 or Lāhor lith 224) is, like 'Perou Hebal' and 'Purū Jaipāl', really nothing but 'Verou Hebal' and 'Purū Jaipāl', really nothing but Nugtas misplaced

II. 34, 1 5. Capture of Bhimnagar

F calls it the 'Fort of Bhīm' (I 26, I 4 f f). B confuses it with Thāna Bhīm or Thāna Bhawan which is a place in Muzaffarnagar district (Constable 25 B c) 'Unsuri asserts that the treasure had accumulated since the time of the Pandava Bhīma (Dīwān, p 60, verse 3, ED IV, 173 note) Reinaud surmised that the place must have derived its name, not from that mythical giant, but from Bhīmadeva of the Shāhiya dynasty, while Elliot was inclined to think that "this town of Bhīm was on the spot called Bhawan, which hes about a mile from the fort [of Nagarkot] and Bhīm is a mistake arising from its presumed foundation by the heroic Bhīm" (445 infra).

All these conjectures are unhistorical The correct name was probably Bhimanagar Nagarkot is not specially associated in Hindu tradition with the Pandava giant and the name may have been derived from Bhima, one of the names of the Devi who is the consort of Mahadeva The explanation has suggested itself to me in the course

of a study of the Travels of Hiuen-Tsiang who writes: "To the nort heast of the city $\times \times \times \times 50$ li or so, we come to a high mountain on which is a figure of the wife of Ishvara Deva......This is $Bh\bar{\imath}m\bar{a}$ Devi. All the people of the better class and the lower orders, too, declare that this figure was self-wrought. It has the reputation of working miracles, and therefore is venerated (worshipped) by all, so that from every part of India men come to pay their vows, and seek prosperity thereby. Both poor and rich assemble here from every part, near and distant". (Tr. Beal, I, 113 note; see also Ibid. II. 214, where there is a reference to the worship of the foot-print of Bhīmā, i.e., Durgā, Pārvati, Bhavāni, Kāli etc.) in another place also.

The temples in the fort itself as well as in Bhawan are dedicated to the worship of Bhīmā as Ambā or Vajreshwari Devi, and the name 'Bhavan' is merely due to the fact that every temple raised to a female deity or Shakti is called 'Bhavan', as Elliot himself says. (445 infra). The temple at Nagarkot is said, by the author of the Wāqiāt-i-Mushtāqi, to have been sacred to Devishankar (E. D. IV. 554) and Nizāmuddīn Aḥmad also observes that Bhavan was an idol-temple of Mahāmāyā, (Ţ. A. 303, l. 8, E. D. V. 358), another name of the same goddess. The Devi [of] Shankara and Māhāmāyā are synonymous with Bhimā or Bhavāni, Pārvati, Bhairavi, Durgā, Kāli, Ambā, Jagdhātri etc.

II. 35, l. 13. Among the booty was a house of silver, like to the houses of rich men, the length of which was thirty yards and the breadth fifteen. It could be taken to pieces and put together again. And there was a canopy.....supported on two golden and two silver poles which had been cast in moulds.

This yard (٤٠٤) must be the cubit of about eighteen inches. The canopy must have been what the old Jaina annalists of Gujarāt call a Mandapikā. The author of the Sukrita Sankirtana, a Jaina chronicle written in 1227 A.C., states that the King of Sapādlaksha, i.e. Sāmbhar, presented to Ajayapāla Chālukya, King of Gujarāt, a silver Mandapikā as a feudatory's offering to his suzerain. (B. G. I. 194). A Mandapikā of gold is also said to have been captured in battle by Damara, the general of Bhīmadeva Chālukya from Karņa, the King of Chedi, and to

11.39, l. 18 and Footnote. A stone was found there in the temple of the great Budda [at Nardin]

It [the word 'Budda'] cannot be meant for an idol, as that word is Persian (Foot-note)

The foot-note is likely to mislead, and should be read in connection with what Elliot himself says at E D I. 507 'Utbi does not mean that the temple was a Buddhist shrine or dedicated to the worship of Gautama, the Buddha 'Budda' here is really the generic Persian term for 'idol', in Arab guise. It is frequently used for 'idol' and 'idol-temple' in Biladuri who says that "the Indians give the name of budd to an idol" (E. D. I. 120). See also Ibn-al-Athīr, 246 infra

On line 20, 'Fifty thousand' is a slip for 'forty thousand', which is found in Jurbādhaqāni. (Reynolds, 392) The old Dehli lithograph of 'Utbi also has ارس العب (335, 1 10) See also F (I. 31, 1 17)

II. 40, 1 3 In the country of Thanesar there were elephants of the Sailaman (Ceylon) breed famous for military purposes.

There can be little doubt that the readings 'Muslim', 'Musalman' and 'Sulaimani' are copyists' errors (Vide Elliot's Note 455 infra). Tavernier states that the elephants of Ceylon were famous for their courage, and for that reason, much sought after in India even in his day. (Travels Tr Ball I. 276) His contemporary, Thevenot, also bears witness to the great esteem in which they were held (Travels into the Levant Eng Tr of 1687. Part in 45). The fame of the species is of ancient date. The trade in elephants between Ceylon and the mainland is mentioned by Aelian in the Third Christian century, Cosmas Indikopleustes in the Sixth, (Cathay, I, 230), Odoric in the Fourteenth, 'Abdu-r-razzāq in the Fifteenth (E. D. IV. 111) and Ribeiro in the Sixteenth. The last author observes that King Dharmapāla of Ceylon (c 1697 AC) used to "sell 20 or 30 elephants every year to the Mogor at a very high price" (Barbosa, Tr. Dames, II. 41 and 113-4 Note)

The name of the island is written by 'Utbi's copyists, but the contemporaneous poet Mas'ūd S'ad Salmān's spelling is L. IV 519). It is not improbable that 'Utbi himself wrote and that the scribes have altered the 'hā' into a 'mim' Qazvīni writes 'Sailān' (Gildemeister, Op. cit 61, 293), Rashīdu-d-dīn and 'Abdu-r-razzāq (E, D I 70 and E D. IV. 103), 'Sīlān'.

In this connection, it may be worth while also to draw attention to

the fact that wild elephants were found, in former times and are, even now, in the Siwālik range in the neighbourhood of Thānesar. Thornton states in his article on Hastināpur, the traditional capital of the Kauravas, which lies about 20 miles N. E. of Meerut and 60 miles south-east of Thānesar, that "these animals abound in the forest about 50 miles north of Hastināpur, at the south-western base of the Siwālik range". Hastināpur itself is said by him to derive its name from Hasti-Elephant. (Gaz. 401). May it not be that these 'Sailamāni elephants' of the Rājā of Thānesar were those found in the Siwālik Hills close to Thānesar? Ceylonese elephants are generally Muknās, that is tuskless (Yule, H. J. s. v. Mukna), and perliaps all that is really meant is that these Thānesar elephants resembled the Ceylonese species in that respect.

II. 42, l. 3. Sabli, son of Shāhi, son of Bamhi × × × × came forward, offering his allegiance and his services as guide.

As the variants are ..., ..., and ..., he may be the Jangi, Japki or Chapki, who is said to have been governor of the fort of Kālanjar in the hills, by Baihaqi. (61 and 92 infra). The Jakki or Chakki Hindu, who is again mentioned in the same author's account of Mas'ūd's expedition against Hānsi as the commander of a fort near Jhelum, may perhaps be the very same individual. (140 infra; Text, 88, 169, 211, 664). 'Bamhi' is spelt ... Bīhmi in the Dehli lith. (397, 1. 10) and the name may be read as Bhīmi. The infamous Kashmīr queen Didda was the maternal grand-daughter of Bhīma Shāhi of Waihind and her father was a Prince of Lohar (Duff, C. I. 91). It is possible that a son or grandson of Bhīma Shāhi had also married into the Lohar family and that this Sabli, Japki or Janki was the issue of that union and thus related to both families.

This fort of Kālanjar appears, (Baihaqi, Text, 664, l. 3 f. f.), to have lain north of the Jhelum in the pass leading into Kashmīr. Sir A. Stein has identified it with Koṭli in Kashmīr, Lat. 33°-38′ N., Long. 78°-58′ E. Koṭli lies to the north of Jhelum and in the hills to the north-west of Punch. These hills were held, till early in the nineteenth century, by petty chiefs known as the Rājās of Koṭli. (Art. on Ancient Geography of Kashmīr in J. A. S. B. 1899, p. 129; Rājatarangiṇi, Trans. II. 433 Note). Gardezi, Nizāmu-d-dīn and F. inform us that Khwāja Aḥmad Ḥasan, the Vazīr of Maḥmūd, was imprisoned in the fort of Kālanjār of which Janki was the governor. (Z. A., 96, l. 16; T. A. p. 11; F. I. 40, l. 4 f. f.).

The man was probably a cadet of the ruling family of Lohar, not the Rājā himself, as is suggested in the C. H. I. (III. 18), but a brother or nephew who aspired to oust his relative and pave his own way to the throne. He was, in fact, one of those domestic traitors who have always been common, both before and since, in all ruling dynasties. He had gone over and offered his services to the invader only with that object. But when Maḥmūd had to retire discomfited from Lohar, this Sabli, Janki or Chakki was consoled and had to be content with the governorship of Kotli, the nearest frontier fortress of the province, as the prize for which

part of his extensive dominions in 424 A.H.=1034 A.C. A Hindu record also found at Piawan shows that Gangeya was in power in 1038 A.C. and there can be little doubt that he reigned from about from 1020 to 1040 A C. (Duff 118, 121 apud C.A.S.R XXI. 113; Epig. Ind II. 804) The fact of the matter is that this Gangeya Chedi is no other than the Chand Rai, i e. Chid (عبد) Rai of 'Utbi and Gardezi and their copyists. 'And this will stand out clearly if we bear in mind that 'Utbi speaks of him as "one of the greatest kings of Hind, who in his pride and self-sufficiency, thought that he held the Pleiades in his hand even while sitting ". The site of Sharwa, [Terva. Tevar?] the fort in which he took refuge and from which he was obliged to fly has not been fixed, but the most probable opinion is that it, and also the lofty hills and impenetrable jungles to which he was pursued by Mahmud, lay somewhere in the Chedi country. I have shown elsewhere that the great Hindu king who was a neighbour of Ganda of Kalanjar and master of one thousand elephants and who sought to placate Mahmud by sending him some most extraordinary presents must be this Chand Rai, Chid Rai, or Chedi Rai. His name 'Kabakana 11.45. l. 2. There was a sapphire . .. the weight of which was 450 mıshāls.

This statement has stumped the commentators. Sir Wolseley Haig refuses to believe in the existence of a sapphire "weighing over sixteen pounds and a half" (C.H.I. III. 19) and Dr Nāzim also remarks that 450 misqāls is "an impossible weight for a precious stone". (M G 108 note).

The real question is, was the stone a sapphire at all, as modern mineralogists understand that term? "The sole criterion of the old lapidaries", Mr. C. W. King warns us, "was the eye. Their system of nomenclature was also utterly unsound". (Natural History of Precious Stones, p 63) Although we now possess chemical, microscopic, optical and other scientific tests, it is not infrequently difficult to place a precious stone in the proper class and even competent experts differ on the point. Many semi-precious stones are, even now, liable to be confused with and pass for their really precious congeners. The grey hyacinth is said to be occasionally mistaken for the diamond and its red variety for the ruby. (Emanuel, Diamonds and Precious Stones, 140) Spinels also are often wrongly classed as rubies. (Ibid 105, 108).

Many Oriental writers appear to have had very foggy notions on these matters. Minhāj assures us that M'uizzu-d dîn Sām had amassed "1500 mans of diamonds which are the most precious kinds of gems" إيات مراز و يأصد من الماس كل بين ترين حوم ها استأر (T. N. 125, I. 3) Mīrkhwānd asserts that Mahmūd of Ghazna possessed more than a hundred ratls of precious stones." (E. D. IV 135) See also Amīr Khusrau in E. D. III. 92.

Tavernier observes that even professional jewellers in the East were so ignorant that "they called all coloured stones rubies The sapphire is a blue ruby, the amethyst a violet ruby, the topaz a yellow ruby' (Travels,

Tr. Ball. II. 101). Ibn Batuia naively states that "in Ceylon, some of the rubies are red, some yellow and some blue." (Gibb. 257).

This particular stone is called blue ruby by 'Utbi, Mirkhwand and Firishta, while Gardezi speaks of it as 'a ruby of the colour of antimony', bic (76, 1. 1) and Khwandamir as a 'purple ruby' (16, 1. 1) and Khwandamir as a 'purple ruby' (11. S. II. 4, p. 23, 1. 3 f. f.). The sapphire is a variety of corundum of different shades of blue, and when possessing an amethyst or purple colour is known as the Oriental amethyst. Mr. Emanuel complains that even jewellers confound the ordinary, i. e. semi-precious amethyst with the Oriental variety. (Op. cit. 114, 157). It would seem that this stone was not a real sapphire but a very fine specimen of the semi-precious amethyst, which is found in large blocks in Ceylon, (Tennent, Ceylon, I, 544) and many other places. (Dana, Mineralogy, II. 196).

The weight of the stone also has been greatly overstated in the C. H. I., probably on account of some arithmetical error. The real weight appears to have been only about 4 2/3 lbs. The misgāl was equal to about 72 grains. (C. P. K. D. 161; Poole, Coins of the Shahs of Persia, Introd.; Alberūni, Tr. I. 160; Tārīkh-i-Rashīdi, Tr. 256, 469 notes). 450 misgāls would be 32400 grs. i. c. about 4 2/3 lbs. Avoirdupois or 5 5/8 lbs. Troy, not 161, as the C. H. I. makes it.

Again, Sir Wolseley Haig observes that the quantity of gold yielded by the idols "may very well have been over 548 lbs. as is recorded." But the weight recorded by 'Utbi, B. (I. 15, Tr. 25), and F. (I. 29, 1. 2 f. f.) is 98300 misgāls, i.e. more than 1010 lbs. Avoirdupois, not 548 only.

The name of the ruler of Qanauj was Rājyapāla (العالى in 'Utbi), not Jaipāl as it is here on l. 4 f. f. There is no authority for calling him Jaichand. (C. H. I. 19). He is called Rājyapāla in several inscriptions. (V. Smith in J. R. A. S. 1908, p. 791; E. H. I. 354 note; Duff, 105, 113-4). II. 46. l. 11 from foot. Canture of Munj.

Elliot identified Munj with Majhāwan, on the Pāndu river, ten miles south of Kānhpur (Cawnpore), Asni with a town ten miles north-east of Fathpur and Sharwa with Sriswāgarh on the Pahūj or with Seunrā on the Ken. (458-9 infra). Dr. Vost was for locating Munj at Manaich, which is said to have been the old name of Zafārābād near Jaunpur and for placing Asni also in its vicinity. (J. R. A. S. 1905). Sir Wolseley Haig accepts Dr. Vost's hypothesis. (C. H. I. III. p. 20). Dr. Nāzim differs from them all. He postulates that Māḥmūd captured these forts not on his direct route, but on the return march from Qanauj to Ghazna and locates Munj at 14 miles north of Etāwa, Asni at Asai Ghāt 6 miles west of it and Sharwa at Sarsāwa 13 miles west of Meerut. (M. G. 109). II. 50, 1. 14. Battle of the Rāhib.

Elliot (462-3 infra), Sir Wolseley Haig (C.H.I. III. 21), and others are agreed that the battle took place somewhere between Qanauj and Bāri on the Rāmgangā or the Syc. Dr. Nāzim, however, contends that the site was near 'Afzalgarh in Bijnor. (M.G. 95 and note).

The reason he gives for this opinion is that "the Ramganga is known as the Ruhut in the upper part only of its course, according to the I. G. XXI. 175" (M. G. 94 note). But this argument is almost decisively invalidated by the fact that, however correct the statement of the I G may be, in regard to modern usage, it is not at all borne out by what we find in the historical literature.

Albertine explicitly states that the waters of the Ganges, the Rahab, the Gudi and the Sarju meet near the city of Biri, which he places at three days' march eastwards of Qanaul (E D I. 49-50, 54 = Sachau's Tr. I, 199, 201). The author of the Tarikh Mubarakshahi (written about 850 II.) tells us that in 817 II, Taju-l-mulk, pursuing the course of the Rahab, arrived at Sargdwari, and crossing the Ganges there, attacked the infidels of Khor and Kampila. (Text. 184, I 9=E. D IV 47) This statement is also found in the T A (184, 1.10). Again, Ni'amatulla writes that when Buhlul Lody invaded Jaunpur, Sultan Husain, being unable to resist, retired towards Bahraich, towards which place Sultan Buhlul likewise directed his foot-steps and they met on the banks of the Rahab. (E.D.V 89=Dorn. I. 53 See also T. A 158, l. 10, B. I 311=Tr. 409, F. I. 178, 17). The last of these passages seems decisive and indicates that the designation was not confined, in the fifteenth century, to the upper course only of the Ramganga, but was applied to its lower course also. The fact is that the name Ramganga is not found anywhere in the older chronicles and appears to be modern. The original name of the entire stream, from its source in Kumaon to its confluence with the Ganges opposite Qanauz, appears to have been Rahab or Rahat.

It may be worth while to note that Gardezi, the only other contemporary authority, places this battle on the Ganges and also states explicitly that the eight men who crossed the river proceeded to Bāri and finding it empty, sacked and looted it (Z. A 72, 12). This is manifestly inapplicable to Afzalgaih or to the *upper* course of the Rāmgangā. The T A. (9, 1.8) and F. (I 31, 1.3) have substituted the Jumnā, but this is one of the numerous blunders into which these compilers have fallen

II 53, l. 7 from foot. The portion [of Baihaqi's work] relating to Mahmud's history was called Tāju-l-Futūh as is evident from 'Unsuri's Kasāid.

But 'Unsuri died either in 481 II. or 441 II (F I 39, l. 9 f f; Beale, Oriental Biographical Dictionary, s. n and as Elliot himself states, E. D. IV. 515) Baihaqi explicitly informs us that he began to write his annals, only in 448 II. (Text, 79, 1 5 f f) and his work could not have been published at all before 455 II as Sunday, 11th Rajab 455, is mentioned in this passage as the actual date of writing. It is, therefore, impossible for 'Unsuri to have made any reference to Baihaqi's Chronicle. The name of the author of the 'Tāju-l-Futūh' is not certainly known, as the work is not now extant. Dr. Nāzim ascribes it to 'Unsuri himself on the ground that

he poet refers to it "in glowing terms" repeatedly (M. G. p. 1 note), but he reason advanced for the conjecture is hardly convincing and it seems neither fair nor charitable to accuse him gratuitously of puffing himself so impudently.

II. 56, l. 6. Most people love silly stories,.....as where the narrator says that in a certain sea, 'I saw an island on which people landed.....and it then moved away, and we saw it was a fish.'

It is strange to come across in Baihaqi (Text, 836, l. 1) this ancient sailor's yarn, which is referred to by Milton (Paradise Lost, I. 200) and has been traced by his commentators to Olaus Magnus' History of Scandinavia. The tale is told in Hakluyt's Voyages (I. 568) also and is the theme of Sindbād's Fourth Voyage. The legend of the old woman who turned a man into an ass by witchcraft is another hoary mythus. It is Apuleius' story of the Golden Ass which was written in the second century, in imitation of one of the works of his Grecian contemporary,

Lucian.
II. 59, l. 5. Abul Fazl mentions in his Ayīn-i-Akbari that Sultan Mahmūd twice visited Benares.

Abul Fazl's authority on such a point is of little or no weight, especially as both the contemporary historians, 'Utbi and Gardezi, say nothing about it and as all the other later compilers also are silent. It is true that such silence proves nothing but there is in the work of Alberuni a categorical statement which clearly implies that the 'Holy City' had been never harried by the iconoclast Sultan of Ghazna. Writing in 1030, he observes that "Hindu sciences have retired far away from those parts of the country which have been conquered by us, and have fled to places which our hand cannot yet reach, to Kashmir, Banāras and other places." (Sachau's Tr. I. 22). Alberuni's statement read side by side with Baihaqi's (123 infra) is decisive.

II. 65, l. 14. The Amīr said, 'I will entrust him with all the duties excepting such as respect conviviality, wine-drinking, fighting, the game of Chaugān and Chank-kabak

Dowson has left the word جنگ in بنت in تنافق (Text, 173, l. 14) untranslated. here may mean 'harp', i.e., music and musical entertainments. literally signifies 'gourd', hence 'archer's mark or target'. The literally signifies is thus described in the Ghiyāsu-l-Lughāt. "A pole

the event (A.N. Text, I. 335=Tr. I. 613) See also Ibid I. 218, where the phrase יונונ فق كرم ענ"the Qabaq bazar was hot, i.e. archery was keen" are نبق الدارىand جوكان ازى Tr. I 440) arrests attention The games of نبق الدارى and نبق الدارى mentioned twice in connection with Humayun's solourn in Persia in the Maasiru-l-Umarā (I. 374, 395). See also S'adı, Gulistan, Ch. III. Story xxviii; Houtsma, E. I. II 592, sv Kabak. Richardson says in his Dictionary, (s v. دار کدو is "a tall post from which they suspend cups of gold as marks and prizes for archers who shoot riding at full speed ".

حک و تن but Dowson has read چنگ نبق but Dowson has read and the meaning may be that the conduct of military operations was to be outside the Minister's province. The words may be also read as with an izafat and mean 'the contests for the Qabaq'-the Archery Matches.

II. 65, l. 21. I will write down some points which must be taken tomorrow to his Majesty

T will write down ' مواضعه بويسم نا قردا بر راى عالي عرضه كنند .T will write down the deed of agreement (containing the conditions or terms on which I will accept the Vazīrship), that it may be submitted the next day to His Majesty'.

It was customary for the Grand Vazir to submit a written statement clearly defining his own powers, his authority in relation to and as against the other ministers and high officials, and even as against the Sultan himself. It appears from the context that the Sultan was to formally signify his acceptance of every one of those articles or conditions, and then the Vazīr had to take orally and also write out with his own hand an oath of allegiance to his master. (66-7 infra). Similar agreements or were indited and signed by some of the other ministers, and the terms and conditions laid down in those relating to the inferior officials were settled and determined by the Grand Vazīr himself The was, in fact, a Covenant or Contract of Service, in which the duties, obligations, rights and privileges of both the employer and the employee were precisely defined. A few lines higher up on this page, the Khwaja is made to say that he " must be fully informed of the duties of his office and have authority to offer such advice and counsel as may be necessary"

خط مواصعة The word occurs frequently in Baihagi. At 86 infra, خط مواصعة (Text 197, 1. 9) is rendered as 'bond' (for the fine imposed on Hasiri) and at 136, (Text 661, 14) it is translated as 'engagement' But at 123 infra, خراح و مواصع (Text 497, 1. 9) is rendered as 'revenue and tribute '. II. 68, l. 1. When Khwaja Ahmad had gone to Hirat, the Amir said, 'There is none fitter than he ['Abdu-s-samad] for his

office'.

When Khwaja Ahmad " چوں خواج احد كدشت شد بهرات .11 .17 [ibn Hasan Maimandi, the Grand Vazīr] died at Herāt—passed away

or went from Herāt to the 'bourne from which no traveller returns'. It is clear from what follows that the subject of the Sultan's cogitations was the appointment of a capable and trustworthy successor in the place of the deceased Prime-minister.

II. 71, l. 9 from foot. Bu 'Abdul-lla Pārsi was chief of the royal messengers at Balkh and lived in great splendour.

ود بايخ بود. 180, l. 9. The Sahīb-i-Barīd was rather, the Postmaster-general, Head of the Department of Political Intelligence and Chief Informer or News-Reporter rolled into one. His duty was to keep the Sultan informed of every important event in every district and of the conduct and proceedings of the civil and military officials. (M. G. 146). He occupied a position of great trust and responsibility. (See 119 'Utbi the historian, as well as Ibn Khurdadbih the geographer, had been Sāhīb-i-Barīd in his day and two of Mahmūd's Vazīrs, Abul-'Abbas Fazl and Hasan bin Muhammad [Hasnak of Baihaqi] had been 'Masters of the Post' before they rose to the highest station in the Sultan's service. Originally, the word 'Barid' was used for the postmule, then for the courier who rode it and lastly for the distance from one postal station to another. The word is said in the Arabic Dictionaries to be derived from Pers. . cut, as the mules had their tails cut or docked (Sprenger, Tr. Mas'udi, 331 note), but Yule traces it to the Latin 'Veredus', a post-horse, a courier's horse, and this appears to be the correct etymology.

The Munshi who translated these extracts from Baihaqi for Dowson has made a mess of the passage. 'Abdūs camels' is sheer nonsense.

بنج مرکب خاص و ده اشتر عبدوس نزد او برد چون عبدوس با این کرامت بنزدیك خواجه رسید خواجه برخاست....و عبدوس بازگشت .1.1 182,

'Five horses of the class reserved for the Sultan's own use and ten camels were taken by 'Abdūs to him. When 'Abdūs, with these presents, approached the Khwāja, the Khwāja rose up.....and 'Abdus [not the camels] then returned'.

'Abdūs was the favourite personal attendant of the Sultan. He is frequently mentioned in these extracts, e. g. on 62, 90, 91, 92, 101 infra. His full name is given by Gardezi (98, l. 8 f. f. and T. A. 11, l. 6 f. f.) as Abu S'ad 'Abdūs bin-'Abdū-l-'Azīz.

11.73, l. 4. The next day, the Khwāja attended the Court. The Amīr was very severe and the day passed in great pomp and splendour.

دو روزی سخت بزرگ بود . 182, 1. 4. " The Amir [Sultan

Mas'ud] held a Court of Justice, to hear the complaints of those who had been oppressed or wronged, and it was a very great (or eventful) day."

is the plural of مطله 'oppression, tyranny' (Richardson) The was the Tribunal of Justice presided over by the Sultan himself to hear and redress the grievances and complaints of the masses as well as the classes Bailingi has just said on the immediately preceding page (72, 1 5 supra) that Khwaja Ahmad Hasan, the Prime Minister, had ordered all complainants منطايان (Toxt, 181, 1. 4) and suitors to be called Gardezi says of Sultan Mas'ud that, soon after taking his scat on the throne, he sat in the Court of Justice (سطام شعب), heard what the subjects had to say and dispensed justice (95, 1 f f Sec also 42, 1.1) At Ibid, 98, 1 5, the synonymous phrase کارهای مطالی ساخت 18 used and also explained by him Baihaqi states in another passage that Sultan Mas'ud announced that a the would be held twice a week in the palace, the doors of which would be open to all and every individual who had to complain of tyranny [مطالي] should speak out freely and without restraint, so that perfect justice might be awarded (40, 1 7) Elsewhere, he declares that Sultan Ibrāhīm Ghaznavi listened to the complaints of the oppressed and gave them justice on the very first day of his accession in 451 A H. مطالم Alinhaj-1-Straj also uses مطالم معلل شيد و دادنداد 'redress of grievances' and مدل كسترى, 'dispensing of justice', as synonymous expressions (T N 275, 1 2) and speaks of dispelling of tyranny and injustice' (64, last line) Elsewhere, he describes the Dwan-1-Muzalim as the "place where disputes are decided and grievances remedied" (3,1 3) The phrase also occurs in the Maasti-1-'Alamgiri of Muhammad Saqı who notes that Aurangzeb ordered the 'Diwan-i-'Adalat' to be called 'Diwan-1-Muzalim' (460, 1 11, see also Ibid, 473, 1. 6 and 520, 1 9) There is a reference to this order of Aurangzeb's which was issued in the 46th year of his reign, [1114 H] in the Maāsı u-l-Umarā also. (I. 314, 1 15)

II 73, l. 10 The business of reporting matters was not properly conducted

The words in the original are ما حال است 182, 1.8

"The department of Military Affairs (lit of the Muster-master-general) is in disorder or confusion, [for want of a capable man at the head]" The duties of the 'Ariz, as the author of the T A (138, 1 17) explains, corresponded to those of the Bakhshi in the days of the Mughal Emperors of Delhi. He was the head of the military administration. He recruited and reviewed the army, directed all arrangements for the payment of the troops, kept a muster-roll, and was also the controller of the commissariat department in war-time. The designation, which literally signifies 'Petitioner', is said to be derived from the fact that "it was his special business to bring into the presence of the Emperor any one seeking for employment or promotion and there to

state the facts connected with his case". (W. Irvine, Army of the Indian Moghuls, 3S).

Dr. Nāzim maintains that the منال المراني على, to which, the other minister Hamdūni is said to have been appointed, was not the "control of financial affairs", as Dowson calls it (p. 74, l. 5 infra), but the Department of Secret Intelligence, Secret Service or 'Political Police' as the French now call it. It was so called, he says, because it employed a large staff of spies under inspectors or overseers or Mushrifs. It was their business to keep a sharp look-out on the conduct of foreign princes, courtiers, ministers and even the Sultan's own sons and submit confidential reports to this department. (M. G. 144-5). Baihaqi himself describes the Ghaznavide system of espionage at 101 infra, in connection with the arrest and imprisonment of Ariyāruq, and uses عادوسان و مشرنان و م

II.76, l. 20. He repeated the matter.....making it ten or fifteen times worse to him.

. عال باز كفت بد . يانزد ، زياد . 186, l. 5. 'He related the circumstances, exaggerating them in the ratio of ten to fifteen, i.e., fifty per cent.' The and similar ده چهل, ده سی, ده بیست, ده یانزده, ده دوازده, ده یازده collocations are idiomatic expressions which have been often incorrectly understood by some European writers. Thus come not mean, as Dowson says, (E. D. VI. 354), 'ten times and twenty times' but 'double', i.e.. 'in the ratio or proportion of ten to twenty'. So •> should not be rendered 'one-tenth or one-eleventh' as Mr. Morland and Mr. Dewhurst do, (Agrarian System of Northern India, 42-3, 227), but 1/10, or ten per cent, the difference between 11/10 and 10/10. ده پانرده by the same rule. signifies as 'ten is to fifteen,' (15/10-10/10), i. e. 5/10 or fifty per cent more. Similarly, د. دوازد which occurs in the T. J. (5, 11, 1, 2, 3) means twenty per cent. (12/10-10/10). ده ازده is spoken of by Minhāj in the T. N. (275, 1. 18) as a customary perquisite or fee exacted by the Chief Justiciaries of the Empire from suitors. Raverty has wrongly read and translated it erroneously as 'ten per cent or د مازد ، cannot be the correct lection in this ده يازده. (Tr. 790). ده يازده passage, as a fee of fifty per cent on the value of suits is unthinkable. It is due to Messrs Rogers and Beveridge to say that they have understood these expressions correctly in their version of Jahangir's Tuzuk. They have rendered د.دوازده by 'an increase of 20%' (I. 10, by 'one of fifty per cent' (1b. 10) and ده پانزده by 'one of one hundred per cent.' (I. 10, 417). The phrase ده دوازده occurs also in the Akbarnama. Abul Fazl states that a د دوازده remission of the land revenue in the Punjab was sanctioned in 1007 H. 1599 A.C., on account of a fall in the prices of agricultural produce. Mr. Beveridge's rendering is "in the proportion of ten to twelve, i.e., 'two in ten' or 20%". (Text, III, 747; Tr. III. 1117.) ده چهل و ده پنجاه is found (Ibid.

Text. I, 299) and is rendered as 'four or five times' (Tr. I, 562) So In the Bāburnāma is translated by Mrs. Beveridge as "thirty or 40 on 10, i e, 300 or 400 per cent". (202 and note).

II. 88, 1. 14. Execution of Amir Hasnak

Hasnak's real name is given as Hasan bin Muhammad-al-Mīkāili by Gardezi. (96, 1 6 f f) F says it was Ahmad Hasan bin Mīkāil, (I 38, 1 11 f. f), but 'Utbi speaks of him as Abu 'Ali Hasan bin Muhammad bin 'Abbās (Lāhor lith 329, Reynolds' Tr. 479) Khwāndamīr follows 'Utbi and calls him Abu 'Ali Husain [recte Hasan] bin Muhammad (Dastūru-l-Wuzarā in E. D. IV, 151) 'Hasanak' is the diminutive or familiar form of 'Hasan'.

Il 88, l. 9 from foot It is some years since Khwaja Bu Suhal Zauzani passed away, and was placed in the prison for the ansiver which he gave.

و خواحه انوسهل رورنی چند سال است تا گذشته شده است باسیم آنانکه ازوی گرفتار و مارا بآن کار بیست .12 .1 .207

signifies 'imprisoned', the meaning may be that he was imprisoned, as a punishment or retribution (;) for the deeds he had done (let. that which proceeded from him). It was Abu Sahl who had advised Sultan Mas'ud to compel the aimy and the courtiers to refund the douceurs they had received as largesse from his brother. Muhammad, at the time of the latter's accession Mas'ud incurred great odium in consequence, and Abu Sahl fell out of favour. Some time afterwards, he is said to have again misled the Sultan by false representations in regard to the conduct of the Khwarizm-shah Altuntash and he was deprived of all his offices and imprisoned in the fort of Quhanduz in 422 H. (Baihaqi, Text, 311, 351, 389, 402) At 508-9 infra, Elliot notes that the story told there on the authority of Baihaqi's Tarîkh-i-Naşırı explains the "unintelligible allusion to Abu Sahl on p 88". Abu Sahl was subsequently appointed head of the Divan-i-Risalat, Department of Correspondence, (in which Baihagi was Deputy or Under-Secretary), after the death of Abu Nasr Mishkan in 431 H Baihagi complains of having been treated unkindly by him But the reference is, most probably, not to imprisonment or punishment in the earthly life, but to retribution for sins in the next.

II 92, l. 7 We marched towards Māwarāu-n-Nahr and visited it with Kadr Khān.

Māwarāu-n-Nahr and had an interview with Qadr Khān'. Mahmūd's march was an invasion and he did not visit Transoxiana in the company of Qadr Khān The interview took place early in A H. 416. (Baihaqi, 246, 1 14) Gardezi has a lengthy chapter on the Mulāqāt or meeting between Mahmūd and Qadr Khān. (82, 1.12, see also T A 11, 1.7, B I 17—Tr. I, 27 and F. I, 31, 1.1 f. f) who put the event, not quite accurately

into 415 H. Qadr Khān was the ruler of Turkestān or Māwarāu-n-Nahr itself and it is manifestly wrong to speak of Maḥmūd "visiting his country with him".

II. 92, l. 14 from foot. Tell the Khwāja to issue such orders as may be proper.

خواجه را بكوى آنچه واجب است فرموده آيد. 211, l. 4 f. f. "Tell the Khwāja that all such orders as are proper will be issued", (by the Sultan, not by the Khwāja). The context shows that no orders were passed by the Khwāja. He said he knew nothing of the rights and wrongs of the matter and afterwards did everything he could to stay the execution of Ḥasnak. II. 93, l. 6 from foot. Until at length Mahmūd obtained the Farmān.

تا امير محود فرمان يافت. 213, l. 4, i. e., "until Amīr Maḥmūd received the summons or call (from the Almighty which every mortal has to obey "i.e., until Maḥmūd died. Waṣṣāf uses. the same phrase: "Bahrām Shāh had died, having received the order of God" (E. D. III. 37), where the meaning is correctly given, but that is because the passage was translated by Sir H. Elliot, not by Dowson's Munshi.

The phrase occurs very frequently in Baihaqi who repeatedly speaks of the event of Maḥmūd's death in these identical terms. (Text, 27, 1.11; 95, 1.2; 234, 1.8; 236, 1.9; 301, 1.9). Gardezi also informs us that the Prince Mas'ūd was in Gūzgānān when Sultan Maḥmūd نرمان يانت المعانية (92, 1.2 f. f.).

The idiom or periphrasis is used and also explained in the highly rhetorical passage in which Abul Fazl records the death of his brother Faizi: "On 21st Mihr, Saturday, 10 Safar 1004 H., the order came to the King of Poets, Shaikh Faizi, my elder brother, and that high-souled and enlightened one, on receipt of the Call for the Last Journey, proceeded with open brow to the Holy City". (Akbarnāma, Tr. Beveridge, III. 1034; Text, III. 673). B. also uses it in speaking of the death of Mahmūd's father, Subuktigīn. (I. 9=Tr. I. 15).

II. 94, 1. 7. The wise Amir sent there the Commander-in-chief of the army and Nasr Khalaf.

و امیر دانشمند بنیه [منبه or نبیه variants] و حاکم لشکر و نفر خُلف را آنجا فرستاد. 213, 1. 12.

There is no izāfat after and the seems redundant. "And the Amīr sent the learned theologian Baniya [or Nabiya or Munabbih] and the Commander of the Army, [and] Naṣr-i-Khalaf there". المائة is frequently used as the title of theologians or jurists and this Dānishmand Baniya (or Nabiya or Munabbih) is mentioned elsewhere also by Baihaqi (54, l. 11), and at 216, l. 9, he is spoken of as the "Faqīh [lawyer, jurist] Baniya" [variants, Munabbih or Nabiya]. Elsewhere, he speaks of the Dānishmand Ḥaṣīri, (51, l. 13) and he is also styled Faqīh Bu Bakr Ḥaṣīrī. (Ib.52, l. 13). Shaikh Lādan Dānishmand is said to have been the 'Imām', 'Religious Director' or 'Keeper of the Conscience' of Sikandar Lody,

(Tārīkh-i-Dāūdī in E D. IV. 470, see also Ibīd 538) Mullā Nizām Dānishmand was one of the persons burnt along with Shīr Shāh at Kalanjar. (T. A 232, 1 15, B I 372 = Tr. 482, F I 228, 1 17). The Dānishmand was really a jurisconsult or jurisprudent, a 'Counsel learned in the Law' of Islam

II 96, l. 9 from foot An account of this assembly was given to the Amīr by the governor of the city and the lawyers

و اس على راحاكم لشكر و وقيه سه (سه منه منه و المع درات و اس على و المع درات و اس على و المع درات و المع و

11 99, l. 1 Let the prayers of the Nishāpūrians be made for me, but they were not made

the prayers of the people of Nishāpur will seive (save, protect or avail) me', but they did not avail him (in fact)" The remark is Baihaqi's Hasnak had been the Raīs-head of the civil administration of Nishāpur, before his appointment as Prime Minister (Baihaqi, 765, 13, MG 136 apud 'Utbi, Lāhore Text, 329-333), and the meaning seems to be that he had become very popular there, and earned the prayers and good wishes of its inhabitants by his just and sympathetic sway.

II 100, l 13. She [Hasnak's mother] then exclaimed, 'What a fortune was my son's? A king like Mahmud gave him this world, and one like Mas'ud the next'

An equally biting and pathetic retort is ascribed to the mother of the 'Amīdu-l-mulk Al-Kunduri—the Vazīr of the Seljūq Sultan Tughril, when he was put to death by Jughril's nephew, Alp Arslān. "Lo, a fortunate service hath your service been to me", he cried out in bitterness of heart, "for thy uncle gave me this world to rule over, whilst thou, giving me the martyr's portion, hast given me the other world. So by your service, have I gained this world and that". (Ibn-al-Athīr, sub anno 450 H. Ed Tornberg X. 11, quoted by Browne, L H P II. 174) As it is not likely that either author borrowed from the other, the close coincidence in phraseology between these tu quoques is not unworthy of note

II. 101, 1. 8. These two generals had two clever, wise and experienced men to conduct their business.

What the author really says is just the reverse.

The Bibl. Ind. Text (262, 1.8) reads a negative which has been inadvertently dropped in the translation. What Baihaqi means is that the counsellors and managers [] of these Turki generals were neither wise, clever nor experienced. As he states, a few lines lower down, that they were "servants of little worth and low position", and also 'despicable base persons', he would be stultifying himself if Dowson's rendering was correct. The masters themselves were simpletons like other Turks and as their counsellors and guides were equally lacking in prudence and experience, their affairs went naturally to ruin.

Ghāzi's name was Āsightigīn (Baihaqi, 97, l. 5; 286, 10; 'Utbi, 35 ante; Delhi Lith. 281, l. 8), not Āṣaftigīn as it is written in C.H.I. 28.

II. 106, l. 5. Various dishes were ordered and brought in.

As statements throwing light on society or manners are very rare in Oriental histories, this gastronomic allusion deserves comment.

II. 112, l. 5. Who still survives and lives at the Kandi inn.

The word translated here as 'inn' is by which was used at this time, not in the sense of an 'inn' or a 'hostel,' but for a "frontier place exposed to the invasions of those who have not embraced Islam. In order to form, in such places, an armed population for the defence of the Moslem territory, some worldly advantages, all possible privileges in heaven and the title of 'w' were attached to a resident in them." (Sprenger. Tr. Mas'ūdi, 241 note). These Ribāts or "fortified barracks constructed on the frontiers of the Empire' as Dozy describes them (B. I. Tr. 44 note), afterwards came to be used also as stations for the post, where the horses were changed and later still, became inns and hostelries. See also the article on 'Ribāt' in Houtsma, E. I. III. 1150-3, where it is said that life in the 'Ribāt' was spent in devotional and religious exercises, but also in doing military duty and keeping guard. The Ribāt was both a monastery and a fortified picquet.

Alberuni gives the latitude of Kandi, or the 'Guard Station of the Prince' (رباط امير) as 33°-55′, that of Kābul being 33°-17′, of Ghazni 33°-

I venture to suggest that Kīri, which is explicitly said by Baihaqi to have been in Hindustān (546, 1 3 f f), and appears to have been near Mārgala, may be Shāhbāz-Gīri or Kapur-da-Gīri, which lies about 40 miles north-east of Peshāwar Shāhbāz-Gīri is a place of great antiquity and one of the seven recensions of the Fourteen Rock Edicts of Asoka has been found there (V Smith, E H. I. 156 note) It was "on the ancient circuitous route to India from the Kābul valley which lay through Peshāwar, Chārsadda, Hoti Mardān, and Shāhbāzgīri to Waihind" (Ib. 55 note) Kapur-da-Gīri, means 'Infidels' Mount'or 'Gīri of the Infidels,' and must have been a place of note in ancient times It is only one mile distant from Shāhbāz-Gīri and the two places are practically identical

II 114, l 11 from foot When the bridge was so destroyed that no one could pass over it, that holy personage (Amīr Mas'ūd) constructed the present bridge of one arch of such excellence and beauty

چوں ار سبل نماه شد عمومه داررگاں آن مرد بارسا ما خبر *** چس آبلی بات طاق برآورده 316, l. 11. "When it was destroyed by the flood, that pious man 'Abūya, the merchant, erected the fine and beautiful Bridge of One Arch [which is now extant]". It is clear from the context that the rebuilder was not Sultan Mas'ūd, but a godly or devout and philanthropic merchant Mas'ūd, whose outrageous carousals and drunken orgies are described with ill-concealed disgust by Baihaqi, was not and is not likely to have been belauded by that author as 'a holy personage' (بارسا). It would appear from the words, 'no one could pass over it' in the translation, that the name of the merchant, عبوره was wrongly deciphered and written as عوده by the copyist and misunderstood in consequence This نار باد 'Bridge of One Arch' in Ghazni is mentioned by Minhāj at 289, 292 infra

II. 118, l. 5 from foot. First came the golden girdle which was of the value of one thousand kans and with it * * a cap * * prepared at the expense of the same sum

326, 1 8 f f و پیش آمد کررر هرارگایی سته وکلاه مادو شاح و ساختش هم هزارگایی بود. The word is clearly printed as گانی gāni in the text, and the real meaning

is that it was worth one thousand dirhams or misgals of gold or silver. فزاركان is the collective plural of خزاركان 'thousand'. A similar phrase حرزر منتصدكاني occurs elsewhere in Baihaqi (Text, 182, 1.7 f. f.) and is more correctly rendered as "a girdle worth (not 'with' as in the print), seven hundred pieces of gold "at p. 73 supra.

We again hear of حرزر بانصد مثقال, a girdle worth 500 Misqāls (Text, 24, l. 3 f. f.), of a محروه منتصد كاني and a حروف أنه in connection with a presentation of Khil'ats (Text, 417, l. 13 and 462, last line). Neither of these passages is translated by Dowson, but in another, Dowson himself says that when Khiwāja Ḥasan Maimandi was appointed Prime Minister, he received a rich Khil'at, a long chain and a girdle of one thousand Misgāls (p. 69 supra; Kamar-i-hazār Misgāl in Text, 177, l. 15).

One thousand Kānīs' has no meaning, as Kāni is not a monetary or ponderary unit in Persian and the real meaning in all these passages is the same—a girdle weighing or worth so many hundred or a thousand dirhams or Misgāls. The question is discussed more fully in my article in Num. Suppl. No. XLII to the J.A.S.B. Vol. XXV, 1929, pp. 46-54.

II. 124, l. 3 from foot. He crossed the river Ganges and unexpectedly arrived at a city which is called Benares and which belonged to the territory of Gang.

و از آب کننگ کذاره شد ... ناگاه بر شهری زد که آنرا بنارس کویند از ولایت کننگ بود 497, 1. 9 f. f.

The 'territory of Gang' must mean here 'the Kingdom of Gangeya' (Chedi), who was at this time at the height of his power. Alberūni also mentions him and states that Dahāla, the capital of which was Tiauri, i. e. Tevar near Jabalpur, was, at the time he wrote the *Indica* (1030 A. C.), ruled by Gangeya. (S. I. 202=E. D. I. 58). We know also from inscriptions that Gangeya was ruling in 1038 A. C. (E. H. I. 362, 369; Duff, 118).

I have shown elsewhere that this Gangeya نال is the 'Kābkana', [عابكا] who sent the extraordinary presents to Mahmud which are mentioned by Ibnu-l-Athir (Ed. Tornberg. IX, 234), Qazvīni, Firishta and others.

II. 124, last line. Wrote these letters from Indar-dar-bandi.

Dowson notes that Elliot's Mss. read 'Indar-bedi' and that form is certainly less incorrect. Alberuni speaks of the Duāb as 'Indra-vedi'. (S. I. 211 and note at II, 321). 'Antarvedi' is the old Hindu name of the Lower Duāb from about Etāwah to Allāhābād and it is sometimes loosely used for the whole Duāb also. The name is said to be derived from the Sansk. Antar, within and vedi, altar, hearth or earthen platform in the courtyard of a house. (Elliot, Races. II. 10). But others say it means 'between the waters'. (I. G. XI. 364).

II. 125, l. 2 and Footnote. Here occurs the lacuna mentioned in the Bibliographical Notice at p. 54.

Dowson, following Morley, states that "about a page and a half of

matter is missing" at p 498 [not 408] of the Bibl Ind. Text. This seems to me to be an estimate so conservative as to be utterly misleading. The lacuna is much more extensive and embraces the chronicle of no less than eleven months. The record of the occurrences of the year 424 H. commences on 1 13, p. 446 of the B I Text. The latest event of that vear which finds mention is the death of Abu-l-Hasan 'Ugaili on the 4th of Rajab (491, 1 4 f f.) The next four pages relate to some events which had taken place at Nishapur in the summer and this is followed by the account of Ahmad Nīāltigin's conquests in Hindustan. (pp. 496-8) This is where the lacuna is found, but the event recorded on the immediately following page relates to Friday, 4th Jumadi II [425 H] Then we have references to Tuesday, 15th Jumadi II, middle of Rajab, 1st Sh'aban and 5th Sh'aban on p. 506 and 16th Sh'aban and 1st Ramazan on p. 509. Along story of Hārūn-al-Rashīd and the Barmecides intervenes on pp 512-522 and then there is an explicit reference to the arrival on Monday, 10th Ramazān 425 H, of bad news from Khwārizam on p 522, 1 8. The diary of the rest of the year then proceeds as usual and a regular series of dates in the three subsequent months arrests attention at pp 524, 526, 528, 531, 536, winding up with Wednesday, 21st Zi-l-hijja at p 538 Baihaqi then notes that the 1st of Muharram 426 fell on a Saturday (540.1 10) He had meticulously registered before, the week day on which the 1st of Muharram of 422, 423 and 424 had fallen (pp 103, and also 168, 353 and 446) The fact that there is no such record for the initial day of 425 H proves beyond doubt that the events of the latter half of 424 and the first five months of 425 H. find no place in the extant portion of his History. This also explains why the Expedition to Hindustan and the siege and capture of Sarsūti in 424-5 H which is descri bedin some detail by Gardezi (Z A. 99, 1 8), the T. A (11, 1.2 f. f), and Firishta (I. 41. 1 10 f f.) is apparently ignored there, altogether

II 125, l 8 from foot Insurrections have also broken out in Khatlan and Tukhāristan

Khatlan or Khutlan was the country of the Haiatala, Hephthalites or Ephthalites and its capital Hulbak, was near the modern Kolab (L. E C 438) Tukhāristān lay to the eastward of Balkh, stretching along the side of the Oxus as far as the frontiers of Badakhshan and was bounded on the south by the mountain ranges north of Bamiyan and Panjhir The towns of Khulm, Samangan, Andaraba, Walwalij and Tayiqan were all included in Tukhāristān (L E C 426-8) and the province corresponded roughly to the Afghan Turkestan of our maps. The derivation of the name from the Sansk Tushar, 'cold or snow', does not sound convincing. II 126, l 15 The Amir sent a Persian Secretary to Tilah

501, 1 5 f f 'He sent 'Iraqı, the وعراقي دير را بوشيد ، نزد تاك مرستاد secretary, privately to Tilak' 'Iraqi was the nisba oi surname of the Secretary 'Iraqı the Secretary (درر) is frequently mentioned by Baihaqi who gives his full name as Abul Ḥasan-i-'Iraqi (Text, 618, 622,

see also 549, 617). The death of Abul Hasau-i-Iraqi the Dabir, on 6th Sh'abin 429 II, is also recorded. (Ibid, 672, 1.6).

II. 127. 1. 9 from foot. This Tilak was the son of a barber.

II. 134, l. 11. The Amir arrived at Herāt on Thursday, the middle of Zi-l-hijja.

The month is given but the year is not specified in Dowson's translation. It was 425 H. (538, l. 4). The next event mentioned—the appointment of Prince Maudūd as Governor of Hindustān on Saturday 6th Zī-l-q'ad—is also recorded without any mention of the year. It was 427 H. (622, l. 4).

15th Zi-l-hijja 425 H. was Thursday, 31st October 1034 A. C. 6th Zi-l-q'ad 427 H. was Tuesday, 31st August 1036. But 3rd Zi-l-q'ad 427 H. was Saturday, 28th August 1036. The printed text has 65- 'third of Zi-l-q'ad,' not is sixth, as in Dowson.

II. 134, l. 9 from foot. And S'ad Salman to be accountant and treasurer.

This S'ad-i-Salman was most probably the father of the poet Mas'ud-i-S'ad-i-S'alman. Mas'ud says in a Qasida written in the reign of Ibrahim Ghaznavi that his father had been in the service of the dynasty for sixty years. (E. D. IV. 521). Sultan Ibrahim died in 492 H. The statement is repeated in another of this poet's or 'Prison-rhymes', where the father is said to have done service for fifty years and to have been rewarded with large estates, which after descending by inheritance to Mas'ud, had been taken away from him on account of the intrigues of his adversaries. (1b. 526).

II. 135, l. 14. On another day of the 'Id.

'Another day of the 'Id,' is hardly intelligible. بدير روز مد (660, 1. 9) means 'On the day after the 'Id,' i.e., after the 'Id-i-Qurbān, 10th Zi-hijja 428 H. The event next recorded, the investiture of the Commander-in-chief, 'Ali Dāya, with a robe of honour, is referred to Thursday, the middle, i.e. 15th of Zi-l-hijja. As the 'Id or 10th had fallen on a Saturday (Text 659, last line), 15th, Thursday is serially correct. The 17th is stated to have been a Saturday. (138 infra).

II. 136, l. 1. Tūs, Kohistān Hirāt, Ghurjistān....are well garrisoned. in Text, 661, l. 1. Quhistān is the specific name of specific name of the specific n

district which lay north-west of the Zarah lake and on the border of the Great Desert. Its chief towns were Tūn and Qāin Tūn was one of the strongholds of the Assassins Qāin was the central town of Quhistān Tūn (Lat. 34°N, Long. 58°E) lay about fifty miles westward of Qāin (Lat 33°N, Long. 59°E). (Browne, L. H. P. II, 458). Birjand has now taken the place of Qāin as the chief town of Quhistān They are all shown in the Map appended to Holdich's Gates of India

Gharjistān lay north of Ghor and to the east of Bādghīs, at the head of the Upper Murghāb (Le Strange, L E O 415, Houtsma, E I. II. 141). It should not be confused with Gurjistān or Georgia, as it has been in the Index to Raverty's Translation of the T N and elsewhere

II 137, l 8 After the Sultan has subdued Re, Khurāsān and the Jabbāl (Hills).

Jibāl (not Jabbāl) does not mean here 'hills' in general, but is the specific or proper name of a district which corresponds roughly with the Media Atropatene of the old Greek and Roman geographers or the 'Irāq-i-'Ajam of the Arabs It was called 'Pahlev' or 'the Hilly' region in Sāssānian times 'Jibāl', lit 'mountains', is the Arabic rendering or substitute of 'Pahlevi'. The boundaries of the province were rather ill-defined "Sometimes Āzarbāijān and the Caspian provinces were considered to form part of it, sometimes, they, as well as Rai and Isfahān, were considered as being outside of it" (Houtum-Schindler, Eastern Persian Iraq, p 5) Elsewhere, the Jibāl is described as "the mountainous district from Isfahān to Zanjān, Qazvīn, Hamadān, Dinawar and Kirmisin". Ḥasan-i-Sabaḥ was indebted for his sobriquet of Shaikhu-l-Jibāl—'Old Man of the Mountains'—to this district (Āīn Tr. III 396 note)

The 'son of Kāku' (18) was 'Alāu-d-daula J'afar bin Kākūya 'Kākū-ya' signifies in Turki 'maternal uncle' and this Prince was so called because he was the maternal uncle of Majdu-d-daula Dilami (Khwāndamīr, H. S in E D IV, 195)

II. 137, l. 9. The chief of the Ghazis, the army of Lahore .. might undertake the business

'Chief of the Ghāzis' was the official designation at this time of 'Abdulla Qarātigīn, who is mentioned under his proper name at 119 supra. (Text, 802, I 3). The warriors (Ghāzīs) who are said at 123 supra to have sided with Ahmad Niāltīgīn in his struggle with Qāzi Shirāz were under the command of this 'Abdulla Qarātigīn. (Text, 497, I. 1) Qarātigīn had been one of the favourite Hājibs of Sultan Mahmūd Ghaznavi (M G 139 note) These Ghāzīs were men who had volunteered for service in India. Mr Gibb points out that "though the old feeling for Jihād had cooled down by this time, the inducement of paradise held out as the reward of the martyr was still strong enough to maintain a steady movement of volunteers to the theatres of war against infidels. These volunteers lived on the frontier in forts or fortified lines called 'Ribāţ' which means literally 'Pickets' and were known as Ghāzīs or

Murābiţs, "Mounted Frontiersmen". (Ibn Baţūţa. Introd. 33. See also Houtsma, E.I. III. 1150-3). The Sālār-i-Ghāziān was their Commander-in-chief. "Twenty thousand volunteers from Māwarāu-n-nahr, who were anxious to be employed in some holy expedition" had taken service under Maḥmūd when he invaded Qanauj. ('Utbi, 41 ante; see also 31, 49 ibid.). There is another reference to them in Ibnu-l-Athir's account of the Somanāth expedition also, where the invading force is stated to have consisted of "30000 horse, besides volunteers". (469 infra).

II. 139, l. 9. He appointed Khwāja Bu Nasr Noki, my preceptor, to be in attendance on him [Amīr S'aīd, the son of Sultan Mas'ūd].

.9. 664, 1. 9 خواجه بو نصرنوکي را استاد نامزدکرد بغرمان

He [the Sultan] appointed Khwāja Bu Naṣr Noki, as the preceptor [of his young son Amīr S'aid, who was left in Ghazni, as the representative of his father while Mas'ūd was away on the expedition against Hānsi]. Noki was never the preceptor or superior of Baihaqi. Is here used in the sense of 'guide, director, manager, virtual administrator'. Abu Naṣr Mushkān was Baihaqi's Ustād and Head of the Correspondence Department upto his death in Ṣafar 431 H. (Text, 748-749), when Abu Sahl Zauzani succeeded him. (Ibid. 753, 1. 16). Abu Naṣr Noki was employed in the same department, and Baihaqi was, in fact, the senior officer. (Ibid. 332, 1. 1).

II. 139, l. 8 from foot. He encamped on the banks of that river [Jailam] near Dinarkotah.

This camping ground has not been identified, probably because the 're' and 'kāf' have been transposed by the scribe. The place meant is, most probably, Dhangrot or Dangrot on the Jehlum, still a well-known place of mahseer fishing on that river. It is now in Jehlum district and is mentioned in the I. G. (XIV. 151). It is also called Tangrote and is close to Dinā, a railway station eleven miles north of Jhelum town. Dinā is in Lat. 32°-40′ N.; Long. 73°-50′ E. Constable, 24 E c. This Dhingrot or Dingrot should not be confused with Dinkot or Dhankot (Lat. 32°-58′ N.; Long. 71°-40′ E.) which is mentioned sometimes in the Mughal Chronicles. Dinkot was situated on the *Indus*, about seven miles above Kālābagh. It has been now washed away by that fickle river. (Wood, Journey 76).

II. 140, l. 6 from foot. He came through the pass of Sakāwand, where so much snow had fallen that it was beyond calculation.

Le Strange says Sagāwand was one of the three chief towns of the district of Bāmiyān. (L. E. C. 418). Bābur describes it as one of the villages of Luhugar [modern Lohgar] which was one of the tumāns (subdivisions) of the Kābul district proper, and locates it near Charkh.

place under notice. The fact is that this Sakawand was not near Jalalābād at all, but lay about 50 miles south of Kābul, and about 35 miles north-east of Ghazni. The Sagāwand Pass lay along the direct route from Ghazni to India, (by way of Iriyāb, Kurram, Shanūzān and Naghar), which was followed by Mahmūd Ghaznavi as well as Shihābūddīn Ghori and other early Musalman invaders of India (Raverty, N. A 72-4). The Sajā van Pass is shown in Constable 24 Ca.

II. 141, l 7. The commanders and officers of the garrison of the five forts also returned to Ghazni.

The B I text says nothing specific about the number of the forts of the families and the honoured ones and the other great persons (who had retired for a time) to the forts came back." — means 'lettring' and المنافي may mean "fortresses to which people could retire" But Richardson says that [sipanj] also means 'a place to which one retires to take rest for a few days' Elliot's Ms appears to have read [panj] instead of منافي [sipanj], but there is no specific reference to 'five' forts anywhere in the preceding context. It would appear that when Mas'ūd marched to India, the palace establishments, the women, the servants, etc. who did not accompany the Sultan were sent away to rusticate during his absence in certain fortresses, which, from their natural position or capability for defence, were regarded as secure places of refuge in critical times

II 141, l 14 On Tuesday, the 3rd of Jumāda-l-awwal, the Amīr celebrated the festival of New Year's Day.

There must be some error here, as we have just been told that Mas'ūd returned to Ghazni on Sunday, the 3rd of Jumādiu-l-awwal (140, 1 7 f f) and stayed for one week at the old palace of Mahmūd (141, 1 4). According to the B I. text, the festivities connected with the Naurūz commenced, not on Tuesday, the 3rd, but when four days remained of Jumāda-l-awwal, jumāda-l-awwal, the 3rd, but when four days remained of Jumāda-l-awwal, te the 26th Jumādi I, was Tuesday, 6th March 1038 This reckoning is also serially correct, as if the 3rd was a Sunday, the 26th must have been a Tuesday.

II 143, l 7 The author out of employ

There is nothing corresponding to this caption in the printed text and its interpolation here is uncalled for and misleading Barhaqi does not speak here of himself at all The person who is here said to have been thrown out of employ and ordered to remain as a soit of prisoner in his own house was not Baihaqi, but Khwāja Abul Fath Mas'ūd, the son-in-law of the Sultan's Vazīr, Khwāja 'Abdu-s-Samad This manhad been appointed 'Kad-Khudā' of the Prince Maudūd, through the influence of his father-in-law, as is related only a few lines lower down. He appears subsequently to have fallen out of favour and what Baihaqi says is that this

Masū'd was, at the time when he wrote this paragraph in 451 H., out of employ and kept as a prisoner in his own house by the command of Sultan Ibrāhīm. Baihaqi then moralises in his platitudinous way upon the vicissitudes of earthly things and the changes brought about by the whirligig of time in men's conditions. Baihaqi also explains the causes of the man's downfall in subsequent times. He observes that this Khwāja Mas'ūd was a handsome and elegant youth of good family, but he was totally inexperienced in practical affairs and the ways of the world. He had been brought straight from his domestic circle and his school to the foot of the throne without any training and so "had afterwards to see what he saw and bear what he bore." (Text. 822, 1. 13; 823, 1. 9).

Baihaqi does appear to have been dismissed from office in the latter part of the reign of 'Abdu-r-Rashīd and was out of employ also in the fifty-seven days' usurpation of Tughril. He appears to have been reinstated after the accession of Farrukhzād, but again sent into compulsory retirement towards the end of his reign. He does not appear to have been "out of employ" at any time during Mas'ūd's reign, (see Text, 754), though he is said to have been sent to prison, for some misdemeanour by a Qāzi, in that of Maudūd. (Barthold, Art. in Houtsma, E. I. I. 593).

II. 144, l. 5 from foot. A sumptuous feast was prepared and messes of potage were placed round.

This is another allusion to good living and gastronomy. The word used is (\$\sim_{\sigma}\$) (\$\scale 24\$, 1.12). It occurs again on \$25\$, 1.2, and is translated by Dowson as 'dinner' at \$145 infra\$. But 'Harīsa' really signifies a sort of ragout, a delectable viand like potpourri and not 'dinner'. Abul Fazl gives the recipe for making it thus: "Take ten seers of meat, 5 seers of crushed wheat, 2 seers of ghee, \frac{1}{2} seer salt and 2 dāms weight of cinnamon". (\$\overline{A}in\$, Tr. I. 60). Steingas says 'Harīsa' is made by boiling bruised wheat to a consistency and adding to it meat, butter, cinnamon and other aromatic herbs. 'Harīsa' is mentioned by Firdausi as a rich dish placed before Bahrām Gor when he found shelter in a dihkān's house after losing his way in the chase. (Turner Macan's Ed. of the Shāhnāma, III. 1514, 1.19). Budāuni tells us that Shāh Fath-ullah Shirāzi died, because he "treated himself by eating Harīsa, when he had a burning fever and however much the Ḥakīm 'Ali forbade it, he would not be prevented". (Text, II, 369, Tr. 381).

II. 147, l. 17. He sent me a sealed answer by the hands of the Sik-kadār or seal-bearer.

الكدار 'Askudār' and it is used by Baihaqi at 363, l, 4, 392, l. 7, 424, l. 6, 451, l. 9, 494, l. 7, and 694, l. 9, either for a courier or for his post-bag. Sprenger states that "in the post-office (ديوان البريد), every letter or parcel put to post or come by post was entered in a list, which was called الاسكدار in Arabic, that is to say, از كدارى. In this list, the number of letters

and parcels was named and the address of every one of them specified." (Tr Mas'ūdi, 331 note). The derivation from الركادارى is only one of the many etymological enormities of the Arab lexicographers and is absolutely worthless. In the very same note, Sprenger tells us that the postal station where the mules and the horses were changed was also termed and included an

II. 147, l. 9 from foot. During the night, Amir Muhammad was brought from the fort of Naghar.

Dowson notes that "Elliot read the name as 'Naghz,' which must be wrong, as the author probably "means the fort of Nagarkot" But the context shows that Elliot was right. This Naghar (or Naghz) was not so very far from Ghazni itself. Gai dezi, in the counter-part passage, calls and states that the Prince Yazdyar, who is here برعبة 'and states that the Prince Yazdyar, who is here said to have brought Muhammad, had been sent shortly before on a nunitive expedition to the [Foot-hills or] 'Koh payeh-i-Ghazni,' as the Afghans in that region had been again refractory and truculent. (Z. A. 109.1.3: B I 29. Tr 44). I venture to suggest that this is the Naghar or Naghz which is mentioned in the Zafarnama of Yazdi (E D III 522) and the Matlau-s-S'adam of 'Abdu-r-Razzāq (Ib. IV. 93). It was near Iryāb, and situated in close proximity to, if it was not identical with, what is now called Baghzan or Bazghan Gardezi's رصد appears to be only another form of ثرض or رغبد. Bazghan "is the chief place in Iryāb " and lies thirty-five Kuroh or about seventy miles south-east of Kabul. (Raverty, N. A 68). Bāyazīd Biyāt also speaks of Gardez (65 miles south-east of Kābul,) Naghz and Bangash in juxta-position (Memoirs, Tr J. A S. B (1898), LXVII, 299) Naghar or Baghzan is now in the Kurram Political Agency.

II 149, l 18 They asked Hurra Khutali, the mother of the Sultan, to interfere in the matter

ال حرة ختلي والدة سلطان درخواسند تا درين ال سعن كويند. 828, 1 18 The Bibl Ind. text also reads the sentence thus, but there must be some error and a sor copulative conjunction must have been inadvertently dropped out by the copyist. Baihaqi repeatedly states that Hurra-i-Khutali was the aunt of Sultan Mas'ūd and not his mother (Text, 12, 1. 9, 18, 18, 136, 1. 5). On p 18, 18, Baihaqi explicitly speaks of the Sultan's mother and Hurra-i-Khutali as two different persons والدة المير مسود و عش و حرم ختل والدة سلطان مسود و حرب من 'The mother of Sultan Mas'ūd and other ladies of the harem and Hurra-i-Khutali' The mother of the Sultan is frequently mentioned by him as Sayyūda. (Text, 3, 1 4 f f, 5, 1 16, 125, 1 10)

II. 149, l 20 But she replied that any one who wished to fall into the hands of the enemy might remain at Ghaznin

It was not the lady or ladies who gave the reply. It was the Sultan who rejected the request and used these angry words in doing so.

ایشان گفتند و جواب شنودند که هم کسی که خواهد که بدست دشین انتد بخزنین بیاید بود S2S, l. 14. "They spoke [to the Sultan] and heard in reply that whosoever wished to fall into the hands of the enemy should stay in Ghaznīn'.

II. 149, last line. I have determined to go to Hindustān and pass the winter in Waihind and Marmināra, and Barshūr (Peshāwar) and Kīri.

Waihind, Ohind or Hund, as it is now called, lay about fifteen miles north of Atak. Marminara has not been identified and the name of the place is probably spelt wrongly. It may be the 'and' the Ford' fof the villagel of 'Mahanāra', which is mentioned by Alberuni. "Swelled by these affluents", he writes, "the river Ghorvand, [i. e. the Kabul river] is a great river opposite the town of Purshavar, being there called the Ford, from a ford near the village of Mahanara, on the eastern bank of the river", and it falls into the river Sindhbelow the capital of Algandahār [Gāndhāra], i.e., "Vaihind". (Sachau's Tr. I 259). It is not unlikely that this c is a copyist's error or local corruption for There is still a place called 'Prata'h Mināra', signifying in Pushtu, 'the Fallen Minara' [or Tower], in this neighbourhood and Bayazid Biyat states that Hūmāyūn crossed the Indus somewhere near it in 950 A. II. = 1551 A. C. (Rayerty, N. A. 93; J. A. S. B. 1898, p. 305). Elsewhere also, Rayerty says that Prata'h Mināra lies "on the west bank of the Indus, above Aţak." (T. N. Tr. 78, 1043 notes). Peshawar is 43 miles W. of Atak (Attock).

Kiri or Giri is probably, Shāhbāz-Giri, or Kāpur-da-Giri, 'Giri of the Kāfirs', 40 miles north-east of Peshāwar (Vincent Smith, Asoka, note) and 20 miles north-west of Waihind. (Beal. Buddhist Records, I. 114 note). Peshāwar is 22 miles N. W. of Waihind. See my notes on II. 112, l. 5 ante and 273, l. 8 post.

II. 154, l. 6. And of my being appointed to the government of Khicārizm and of my losing it and going to Re and of Altūntāsh. All this I will mention.

و ولابت از دست ما شدن و خوارزم و التونتاش و آن ولابت از چنگ ما رنتن ما مندن و خوارزم و التونتاش و آن ولابت از چنگ ما رنتن ما مندن و دونت موی دی نامی بکولیم عمل الله عمل الله عمل الله عمل الله و دونت موی دی نامی بکولیم و دی نامی بکولیم بکولیم بکولیم و دی نامی بکولیم بکولیم بکولیم بکولیم بکولیم بکولیم بکول

This tenth volume of Baihaqi's work is entirely devoted to the affairs of Khwārizm and contains a detailed account of its history from the days of Abu-l-'Abbās Māmūn to the year 432 H.

Khwandamir informs us that in 426 H., Mas'ud marched with a great army to Jurjan and Labaristan, because his governor in 'Iraq had,'

The inhabitants of Qum and bawa also had revened and Ada daula bin Kakuya (ED. IV. 1967, see had been driven out by 'Alau-d-daula bin Kakuya plored help from him against the Seljuqs also Gardezi, Z.A. 99-100) Mas ud had to march again to Rai in H 430, as the Seljugs had besieged that town Baihaqi himself refers to the

II 155, 1 8 The author was Maulana Nin u-d-din Muhammad 'U fi Dr. Nizāmu-d-din has pointed out that 'Awfi's real lagab was Sadidu-d-din and not Nuru-d din, as Elliot and other writers have given event at 137, 141-2, ante.

it on the authority of Hamdulla Mustaufi

(A-e) Infoliation have been exceptioned and other writers have given to the authority of Hamdulla Mustaufi

(A-e) Infoliation have been exceptioned and other writers have given to the facts of the it on the authority of riumduna musicaun with precision All that can 'Awfi's life-history have been ascertained with precision of policies of the state of the st be said is that he was born between 1171 and 1176 AC in Bukhārā

De Said is that he was norm between the land the Jarcami'a and the and died about AC 12323 Besides composing the Jarcami'a Fac and the said died about AC 12323 COD IT of the said the and the about A of 120 20 Desides composing the Januarit a and the Lubabu-l-Albab, he made in 620 H a translation of Tanukhi's Far at

b'adu-sh-shidda, which takes priority over the better known version of Dihistan. The latter was made about 650 H and, before its discovery,

So he (Bahram Gaus) placed his as my and country in was supposed to be the earliest (J.H 14-19)

IS an error for to Narsi (Narses) (Rogers, Tr Shahnama 414, 415, Rawlinson, Seventh Oriental Monarchy, 296, 298) I am that ferocious lion, I am that huge elephant, II 159, ¹ 20 My namers Bahram Gir, and my patronymic Biyabala,

مم آن شیر شله و میم آن سریله

This story, as well as the distich, is held by modern scholars on a man and ma 11 160, 1 17 This story, as well as the distinct, is near by modern scholars to be spurious, though it is sponsored by Th'alibi (Ghard), Ed and Tr spurious, though it is sponsored by the older of not more reconstable. Spurious, though it is sponsored by the and the older, if not more respectable Zotenberg, 556-7), who quotes it on the older, the three tale of Bohnom Clon's

authority of Khurdadbih Browne says that this tale of Bahram of Porsian only "one of many apocryphal legends relating to the origin of Persian poetry, which the authors of the Tazkirahs delight to tell Daulatshan poetry, which the authors of the Talance ascribing the invention of the Persian relates still another anecdote ascribing the invention of the Persian relates suit another anecuote ascripting the invention of the Dilaram. Couplet to the joint efforts of Bahram Gor and his mistress Dilaram. couplet to the Julia enters of Dange of Shirin or was the graneful larguage was incombad on the Dalage of Shirin or was the graceful or composed by 'Abbās language was inscribed on the Palace of Shīrīn, All these tales are unworthy

of serious attention and entitled to little or no credence, (LHP.I12-14) utterance of a young son of Y'aqub ibn Lais of Merv in praise of the Khalif Mamun

Perhaps the most curious and arresting thing in the couplet is the Perhaps the most curious and arresting thing in the couplet is the Perhaps the most curious and arresting thing in the couplet is the Perhaps the most curious and arresting thing in the couplet is the Perhaps the most curious and arresting thing in the couplet is the Perhaps the most curious and arresting thing in the couplet is the perhaps the most curious and arresting thing in the couplet is the perhaps the most curious and arresting thing in the couplet is the perhaps the most curious and arresting thing in the couplet is the perhaps the most curious and arresting thing in the couplet is the perhaps the most curious and arresting thing in the couplet is the perhaps the most curious and arresting thing in the couplet is the perhaps the most curious and arresting thing in the couplet is the perhaps the most curious and arresting the perhaps the most curious are the perhaps the most curious are the perhaps the most curious are the perhaps the p word Bujabala, which Bahram says was his patronymic and Bujabala, but Tobolo, may meen in Archie and Tobolo, may meen in the complex is the contract of the contr See also Berthels in Houtsma (EI III 1058-9)

Word Dujanan, which Danram says was ms patronymic . Bujabala, or . Bujabala, but . Abu Jabala, may mean in Arabic, recombined to the Constant . Abu Jabala, may mean in Arabic, recombined to the Constant . Purchala, also hears a close phonetic recombined to the Constant. Bulabala, also bears a close phonetic resemblance to the Sanskrit Bujabala also pears a close phonetic resemblance to the Substitution of the Bhujabala, strong-armed,—a name or epithet actually borne by more

than one Hindu king, (Duff, C I 155, 160)

II. 161, 1. 8 from foot. The Solis of Persia.

'Soli' is a miswriting of 'Lūli' or 'Lūri,' which is generally derived from Lūristān, the district from which the Persian gypsics are believed to have originally come and spread over other parts of Asia. Th'alibi speaks of them as 'Luriy-yūn'. (Ghurar, 564-9). The interchange of 'r' and 'l' is very common. Lūristān is in Lat. 34° N., Long. 47° E. Dames says that the Loris or Lolis of Persia are really the same as the Poms or Mirāsis, the hereditary minstrels of Indian villages. (The Baloch Race, 17).

II. 162, I. 2 from foot. Muhammad 'Ufi, the compiler of this work had once been in Kambāyat (Cambay).

Dr. Nizimu-d-din's comments on this incidental personal reference are more imaginative than historical. "Soon after this", we read, "he ['Awfi] was sent as the Chief Judge at the behest of Qabicha to the recently acquired country of Gujarat or Nahrwala, as it was then called ". (J. H. Introd. 14). And again, "We gather that he ['Awfi] was the judge of that place (Kambayat) in the province of Nahrwala,.....then a dependency of Malik Nāsiru-d-dīn Qabācha". (Ibid, 8), Now, it is common knowledge that Nahrwala or Gujarat was an absolutely independent Hindu kingdom upto 1298 A.C. and that it came really under Muhammadan sway only in that year. If Qabicha ever invaded any part of the country, it was only a lightning raid like Mahmud's in 1026 or Aibak's in 1199 A.C. This learned writer seems to me to have completely misunderstood the real position of 'Awfi and the nature of his duties. Istakhri and Ibn Haugal tell us that "from Kambaya to Saimur is the land of the Balhara and in it there are several Indian kings. It is a land of infidels, but there are Musalmans in its cities and none but Musalmans rule over them on the part of the Balhara, There are Jam'a Masjids in them." (E.D.I. 27, 34, See also Idrisi, Ib. 88). Elliot, commenting upon this, states: "The Musalmans in these parts were treated with great consideration by the native princes. They were governed by men of their own faith, as the traveller (Ibn Haugal) informs us, was also the case with Musalmans in other infidel dominions, as among the Khazars on the Volga, the Alans of the Caucasus and in Ghana and Kaugha in Central Africa. They had the privilege of living under their own laws, and no one could give testimony against them, unless he professed the Muhammadan faith". (Ibid. 457). 'Awfi was sent as Chief Judge only to decide cases among the Musalmans who had resorted for commerce and trade to the country, which was still held firmly in the grasp of its Hindu kings. His functions were like those of Consuls in our own times. The author of the Kitābu-l-'Ajāib al Hind informs that the Hindus punished theft in a Hindu with death, or a heavy fine or with confiscation of property. But "if the thief is a Musalman, he is judged by the Behermen of the Musalmans, who pronounces sentence according to the laws of Islam. The Behermen takes the place of the Qadi in a

Musalman country He can only be chosen from those who have made a profession of Islam "(Book of the Marvels of India, Eng. Tr. 140 See also *Ibid*, 120-1) "In every one of the cities of China", writes Ibn Batūta also, "there is always a Shaikh-al-Islām, to whom all matters concerning the Muslims are referred, ie who acts as an intermediary between the government and the Muslim community, and a Qādi to decide legal cases between them" (Gibb, 290)

II. 163, l.3 In this city, was a body of Fire-worshippers as well as the congregation of Musalmans

The word rendered as 'Fire-worshippers' is 'j (164 infra, note), which Dowson himself translates as 'Buddhist' at 311 infra He states that it "means Christianity as well as Fireworship" and is applied probably to "any established religion other than Muhammadanism" Raverty also tells us that according to the Dictionaries, "it is very widely applied, to signify a Christian, also a worshipper of fire or Gabr, a pagan, an infidel or any unbeliever" (Tr. T.N 567 note) Vullers and Steingass both give 'Lamaism' as one of its many meanings and there can be little doubt that Din-i-Tarsāi is employed by Minhāj for Tibetān Lamaism or Shāmā nism in the passage translated at 311 infra

Moreover, two statements are made by 'Awfi himself in the course of the narrative which militate with considerable force against the 'fireworshipper' interpretation "None of the courtiers of the Rāi", writes 'Awfi, "paid any attention to him [the complainant, Khatīb 'Ali] or rendered him any assistance, each one being desirous to screen those of his own persuasion". And again he informs us that the "Rāi then told them [his courtiers] that he had felt unable to place implicit confidence in any one, because a difference of religion was involved in the case".

Now, if these words have any meaning, they must imply that some at least of the courtiers of Siddharaja were Parsis or Indian Zoroastrians, and that they possessed such influence, that he was apprehensive of their suppressing and distorting the truth. In other words, these Tarsā must have constituted not only a numerous and dominant element in the population of Cambay, but a powerful party or faction in his own court, whose clannishness he distrusted and whose bigotry he disliked No one who knows anything of the history of the Indian Parsis can entertain any such supposition for a moment and the unavoidable conclusion must be that these $Tars\bar{a}$ must have belonged to some other Indian sect. e q the Jama, whose tenets bore a striking resemblance to those of the Buddhists Now the similarity between these two creeds is so close and remarkable, that European scholars are still divided in opinion as to their historical relation and philosophical connection. Some hold that the Jamas are a mere offshoot of the Buddhists, while others are sure that they are an independent sect," which sprang from the same period and the same religious movement, in opposition to Brahmanism." The political connection of the Jamas with the rulers of Gujarat also dates from very

early times and it is common knowledge that not only the councillors and ministers, but the commanders and leaders of the armies of the Chālukyas were Jainas. (B.G.I. i. 169-171; Forbes, Rās Mālā, 139-41). These Tarsā were, I think, Jainas. I leave the matter here as I have discussed it more fully in the Journal of the Cāmā Oriental Institute, VIII, 1926, pp. 19-37. II. 164, l. 9 from foot. But when the army of Bāla invaded Nahrwāla, they [the mosque and minarets] were destroyed.

Dowson notes that 'Bala' is also written 'Balwa' and 'Malu' [Mālwa?]. An invasion of Gujarāt by a king of Mālwā named Subhat Varman (died c. 1211 A. C.) in the reign of Bhima Deva II (1178-1241 A.C.) and another by his son Arjuna Deva are mentioned in contemporary inscriptions. (Duff, C.I. 162, 177). The Jaina chronicles of Gujarāt also state that Ballala, the King of Malwa, invaded Gujarat about 1145 A.C. in the reign of Kumārapāla and that Kumārapāla took the war into the enemy's country, beheaded Ballala and reduced the rulers of Malwa to their former position of vassals of Gujarat. This statement is confirmed by several epigraphic records. (B.G.I. i. 185; Ind. Ant. LVI. 1927. p. 10). The name of Ballala is not found in the dynastic list of the Paramāras of Mālwā (Duff, 300), but it may have been the familiar or contemptuous appellation of some king who appears in the list under a more pompous or dignified designation. In any case, it is certain that the Chālukyas and the Paramāras were at constant war with each other and their invasions of each other's territories were frequent. The destruction of the mosque in one of these incursions is, therefore, not at all improbable.

A king named Devapāladeve also ruled in Dhar about 1218 A. C. (C. I. 178, 185; H. M. H. I. III. 176) and he may be this Bala.

II. 165, l. 5. The Rai of Daur, who was the head of all the Rais of Hindustan...sent ambassadors.

Dr. Nizāmud-dīn reads 'Dwārkā' here, but Dwārkā was probably included in Siddharāja's own territories and even if it was not, its petty chief was not "the head of all the Rais of Hindustān' and he would not have dared to send such an insolent and minatory message to a great king like Siddharāja. The conjecture is also ruled out by the fact that the king of 'Daur' is said to have been a great king whose territory was as a great distance (176 infra), which is inapplicable to Dwārkā. Domana

invaded and sacked Dhar about 1120 A C. and confined in an iron cage its king, Yashovarman, whom he had taken prisoner (Ind Ant. X. 159. Duff, C I. 134, Vaidya, H M.H I III 172) He may have been provoked to do so by some such truculent embassy. The war between them is said to have lasted for twelve years (B G I 1, 177-8) There are several references to the ancestral feud between the two dynasties in the Gujarat Munja, who ruled at Dhar, cu ca 1000 A.C, is said to have insulted the Chalukya Raja Chamunda and to have taken away his umbrella when the latter was passing through Malwa on pilgrimage to Banaras (BGI i. 162) A general of Munja's nephew, Bhoja, is stated to have invaded Anahilvad and sacked the capital, when Bhima I was engaged in a war against the King of Sindh (Ib 163) Yashovarman's predecessor. Narayarman, is also stated to have continually raided and harassed the Gurnan a-Mandala (Ib 172-3)

II. 168. 1 5 from foot. There was a Rai of Nahrwala named Gurpal -Before he had been raised to throne, he had passed many of his days in beggary and endured all the miseries of travel

Dr Nızamu-d-din reads' Kürpal', but makes no attempt to identify him I venture to say with some confidence, that he is no other than 'Kumārpāl' [or Kuvarpāl] Chālukya who ruled from 1143 to 1173 A C He was bitterly hated by his predecessor, Siddharaja Jayasinha, who is said to have repeatedly tried to seize and make an end of him stories of his wanderings in remote places and hair-breadth escapes are related with much gusto and wealth of detail by the Jaina chroniclers. Hemachandra, Merutunga and others (Forbes, Ras Mala Rep. 1874. pp 138-41; B G I. 1 182-3) 'Kuvar' is the Gujarāti form of the Sanskrit Rurpal is a miswriting of Kumāra

There is a curious parallel of the story related by 'Awfi in the Bappa Bhatti Charita, a biography of a Jama saint so named, which is incorporated in the Pi abhāvakacharita of Chandraprabhāsūri, written The tale told there is that Amaraja, who reigned at ın 1277 A. C Oanauj after his father Yashovarman in the first quarter of the 9th century, was so charmed with the beauty of a low-caste Matangi (Mang) dancing girl that he gave himself up to her embraces At last, the Jaina saint, Bappa Bhatti, who is said to have lived from 800 to 895 A C, made him realise the grievousness of his sin. The exponents of the Hindu Dhai mashāstras, on being asked by the king to prescribe the proper penance, decided that adequate expiation could be made only by the Rājā embracing a red-hot copper image of the woman-as she was a Chandala As this meant certain death, Bappa Bhatti, who was the lang's friend and counsellor, pointed out that the sinful deed had proceeded only from sinful thought, that if he would keep his mind free from sinful thoughts, there would be no sinful deed, and that the best mode of expiation was the eschewing of all sinful thought The king

was delighted with this reasoning, and agreed to follow his advice. (Dr. S. K. Ayyangar's art. on the Bappa Bhatti Charita in J.B.B.R.A.S. 1927, p. 112). 'Awfi's anecdote seems to be a replica of this old Jaina legend, with a change in the name. Bappa Bhatti is said to have converted Amarāja to Jainism, just as Hemachandra is stated to have brought over Kumārapāla from Shaivism to the faith of Mahāvīra. II. 172, l. 3. Rāī Kamlū and the Governor of Zābulistān.

Kamalu's date is fixed by the fact that his adversary 'Amr Inot 'Amru] bin Lais reigned from 265 to 287 H. = 878-900 A. C. suggests that Kamalū must be a hypokoristikon of some such name as Kamalavardhana (Alberüni's India, II, 361 note), but R. B. Dayārām Sāhni has recently published an inscription of Bhīma, the father of Jayapāla, from which it appears that the full name was Kalakamalavarman. (Arch. Surv. Rep. 1917, p. 20; Vaidya, H. M. H. I. III. 21). According to the Rajatarangini (V. 232-3), the Kashmir king Gopalavarman deposed Samantadeva, the rebellious ruler of Udabhandapura (Waihind), and gave his kingdom to Toramīna, son of Lalliya, (Kallar of Alberūni. 12 ante), with the title of Komaluka. (Duff, C. I. 83 and the authorities quoted there; I. G. XIX. 150). This 'Komaluka' must be the Kamalū of 'Awfi and Alberuni. The British Museum possesses the unique coin of a king called 'Shri Kamara' or 'Khamarayaka' which has been attributed to the Shāhi Kamalū. (Cunningham, Coins of Mediaeval India, 59; Smith; I.M.C. I. 243-4). Kamalūka was succeeded by Bhīma and he by Jayapāla, the antagonist of Subuktigin and Mahmud.

The name Fardaghān (l. 6) is read as 'Furu'ān' or 'Furughān' by Dr. Nizāmu-d-dīn (loc. cit. 164). I suggest that the correct form is Farūkān or Farūkhān. We know that Ardashīr Bābakān or Pāpakān, the founder of the Sāsānian dynasty, married the daughter of a Persian noble named Farūkān or Farrukhān. Farrukhān was also the name of one of the Ispahbads of Ṭabaristān, who ruled from 709 to 722 A. C. (Houtsma, E. I. II. 69; Browne, Tr. of Isfandyār's History of Ṭabaristān, 99). Farrukān or Farrukhān was, in fact, a very common name at this time and Justi gives details about no less than twenty well-known men who bore it. (Iranien Namenbuch. 94-5). 'Sanjari' is an error for 'Sijizi', i.e. of 'Sijistān' or 'Sīstan.'

II. 176, l. 18. Rūsal.

There is a veritable plethora of variants, Ratbal, Ratbil, Rasal, Rātsal, Rānbal, Zanbīl, Rūnabil, etc. As the name occurs continuously in the Arab Chronicles in some corrupt shape or other, for more than two hundred years beginning from A. H. 43, it seems clear that it was not the name of an individual, but the designation of a dynasty or a hereditary regal title. The Arab writers give one and the same name. Betrīl. Ratbal, Ranbal etc. to the 'Kābul Shāh' or the Shāh of Sijistān throughout this period of more than two centuries. H. H. Wilson through must be Ratanpāl (Elliot's note, 417 post), while Raverty comis notes.

up his mind between Ratanpal [Ratna-pala] and Ranapala (N. A 62), but neither of these emendations has found favour with other writers seems unprofitable to indulge in further conjectures, but it may be per-ريرىل Ran-zabal or دويل Ran-zabal or دويل Rai-zabal, i.e. Rānā or Rāi of Zābul, the old name of Sīstān the father of Mihirakula and the leader of the White Huns of Zābul who conquered Sind and Malwa about 500 A.C., is often styled Toramana Jauvula The name of 'Rajuvula' or 'Ranjubula' is found on Indo-Scythian coins (Smith, I M C I, 56 note, 191 and 196) and there are monetary issues of the Ephthalites also in the name of Shah Zobola, 'Shahi Jabula,' 'Shāhi Janabula' or 'Shāhi Jabuvla'. (Cunningham, Coins of the Later Indo-Scythians, 95-97 and 108-110) It is possible that the clue to the 'Rūsal' puzzle lies here and that under it is disguised some such name or title as 'Rā-juyala', 'Rāi Jabula,' or 'Rāno Jabula', ie King of Jābul, Jāvul or Zābul It is possible that the name of the country itself is eponymous and that 'Jauvula' or Zobola was the name of some old Ephthalite king of great renown (Ib. 108-9) Indeed, the name Rajuvala or Ranjubula seems to be older than the rise of the Ephthalites and some coins on which it is inscribed have been assigned to an Indo-Scythian Mahākshtrapa who reigned about 110 B C (Smith, loc cit 196)

II 189, foot note It appears from a statement of Ibn Haugal that the Sultans used to reserve a large portion of indigo to themselves as a sort of royalty

Indigo was, in the old days, a highly-prized substance and Pliny says that it used to sell for twenty *Denarii* the pound (Tr Philemon Holland II 531) Baihaqi states that Sultan Mas'ūd sent, on one occasion, twenty-five thousand mans of indigo along with other presents to the Khalif of Baghdād and the members of his court (361, 1 10) Mr W. H Moreland thinks that this Man must be the small Man of only two pounds, as having regard to the scale on which the trade in indigo was carried on and the great money value of the article, twenty-five thousand mans or twenty-two tons of indigo would be a very substantial figure for those days ('Notes on Indian Maunds' in Ind Ant LX. 1931, p. 202)

Daulatshāh also relates that when Sultan Mahmūd sought to make tardy reparation for his niggardliness to Firdausi, he sent him twelve camel-loads of indigo Unluckily, the beasts arrived at one gate of Tūs only when the poet's coffin was being carried out of the town by another gate (Tazkira, ed. Browne, 54).

The point of the anecdote in the text is not very clear. The name of the minister was not Hasan Maimandi but Ahmad ibn Hasan Maimandi. When the father of the scamp begged the Vazīr to forgive his son, because the son was an Ahmaq, [50] (fool), whose name was Ahmad, he would seem to have unwittingly alluded to the vulgar gibe or word-play, that "Every Ahmad is an Ahmaq," i.e Fool See the version in Nizāmu-d-dīn, J H. III. 21.1, p 222.

II.:193, l.:14. Destruction of robbers by Sultan Mas'ud.

This story can be traced to the Siyāsatnāma of Nizīmu-l-mulk, the Vazīr of Malik Shāh Seljūqi, which was composed in 485 H. 1092 A.C.—long before 'Awfi's Javāmi'a. The anecdote which follows about the poisoned apples is also related there, but with many variations. (Ed. Schefer, 58-65; Bombay Lith. Pt. i. 69-78). As Mas'ūd was governor of Herāt about 408 H. (Z.A. 74, l. 18). the first story must relate to that period. In the Tārīkh-i-Guzīda and the Zīnatu-l-Majālis (506 post), the hero of the apples anecdote is Maḥmūd himself, but there is no real difference, as the Prince Mas'ūd was appointed Governor of Irāq by Sultan Maḥmūd soon after its conquest in 420 A. H. Maḥmūd was king, Mas'ūd his lieutenant or viceroy and it is even said in the T. N. by Minhāj that Maḥmūd "placed Mas'ūd on the throne of that country". (272 infra).

II. 193, l. 18. In the desert of Khabis there was a body of Kafaj and Bulūchis who robbed on the highway.

Khabīs lies on the edge of the Great Persian Desert (called Lūt), which separates Kirmān from Khūrāsān. (Dames, Baloch Race, 31, 33), It was the northern sub-district of Bardasīr, one of the five divisions of the Kirmān province. Lat. 30°-26′ N., Long. 57°-42′ E. (L. E. C. 299, 322). The Kūch (written Qufs by others) were a lawless and most truculent Kurdish tribe which dwelt in the mountains of Kirmān from very early times, down to the seventh century of the Hijra. They, are said to have been finally exterminated only by Qūtbu-d-dīn, the Qarī Khitāi ruler of Kirmān, who reigned between 651-655 H. (Tārīkh-i-Guzīda; Gibb Series, 180, 399, 418, 530). They had been severely trounced and almost decimated before by 'Azudu-d-daula Dilami also. (J. Ḥ. 80 note).

There are two places called Tabas and it is far from easy to decide which of the two is meant. (1) Tabas-i-Gilaki or Tabas-i-Tamr, i. e. Tabas of the Date. It lies on the border of the Great Desert of. Lūt, where many of the roads meet, for which reason Balādhuri calls it the 'Gate of Khurāsān.' (L. E. C. 359-60).. It is also described as a town in the Desert between Nishāpur, Ispahān and Kirmān. (Āin. Tr. III. 67 note). Lat. 33°-40′ N., Long. 56°-54′ E. But the Tabas of the text, the place to which some of the persons attached to the mission fied after the attack is, probably, the other Tabas—Tabas-i-Unnāb, Tabas of the Jujubes or Tabas-i-Masinān, which lies some fifty miles east of Birjand (L. E. C. 361-2) and two marches from Qāīn. (Iṣṭakhri, loc. cit. 285, l. 10). Lat. 33° N., Long. 60° E. Khābis, Birjand and the two places called Tabas are shown in the map prefixed to Holdich's Gates of India. See also Houtsma, E. I. IV. 582.

II. 196, l. 14. He showed favour to Abu Suhail Rāzihi and they conspired against the great Khwāja 'Abdu-r-Razzāq. He quarrelled with Ahmad Maimani and had him suspended and called to account.

There is some blundering here. The same story is translated again by Dowson from the Zinatu-l-Majālis (512 infru), where the sentence

runs thus. "Among these, he supported Abu Suhal Rāzikī, whom he pitted against the good Khwāja, 'Abdu-r-Razzāq, son of (Ahmad) Hasan Maimandi," and it appears to be more correct. At any rate, this Tūmān could never have quarrelled with Ahmad Maimandi, as the latter had died so long ago as 424 A.H., 17 years before the accession of 'Abdu-r-Rashīd. The person 'suspended and called to account' was really 'Abdu-r-Razzāq his son and it is the latter who is said in the Zīnat to have been dismissed and heavily fined by 'Abdu-r-Rashīd The father and son have been mixed up with each other in the version of the story in this part of the volume Mubārak Marde's sobriquet should perhaps be read as Lov or Lov, ie 'of Merv.' Rāziki Lova or Lova, ie 'of Merv.' Rāziki Clauzani by Baihaqi Can it be a miswrīting of Rāfizi Liu, which is used as a term of reproach for a Shī'a as a heretic?

Dowson says here and also at 511 post, that he was unable to find this story in the Mss of the Javaami'a which he had used But it does occur in those which were consulted by Dr Nizāmu-d-din, J H Introduction, 63

II 202, l 15 Abū Rihān mentions - that there exists an animal called Sharū.

Read 'Sharta' The last letter in the name is a consonant and the 'animal' is the Sanskrit 'Sharabha,' a mythical beast which is described as a lion with an elephant's trunk The Puranic story is that when the Narasımba avatār of Vishņu had destroyed the giant Hiranyakashipu, his fury was so great that it began to destroy the whole world appealed to Shiva, who then transformed himself into the 'Sharabha', the terror of the lion Vishnu then changed himself into the Gandabherunda—another mythical monster apparently resembling a double-headed eagle, which can devour the 'Sharabha', the elephant and all living creatures 'Awfi's paraphrase of Alberum's account is not quite accurate The animal is said by Alberuni to be found, not in the country "east of the Ganges" or in "the forests of Oudh," but in "the plains of the Konkan called Dang" (Sachau's Tr I 203, see also E D I 61). is a misreading of كن Konkan Dr Nızāmu-d-dın's Ms of 'Awfi's Jaıcāmi'a also reads 'Konkan' and 'Danak' (Introd. p 37; IV xxiii No 2057, p. 257), but his gloss that 'Danak' is a "sea-coast place situated to the south of Samhita in India," is incomprehensible and founded on some misapprehension or madvertent error The Dang is a wild forest-region now included in the Khandesh district of the Bombay Presidency shown in Constable 31 D a

II. 215, l 8 from foot. The Rai of Azmer appears to have been detected in some intrigue, which is very obscurely indicated

Hasan Nizāmi is at times so intoxicated with the fumes of his own magniloquence that his speech is no more than a stutter, and Elliot

appears to have been unable to make much sense out of his verbiage. It may be therefore pertinent to cite the following statement from the Hammīra Mahākāvya. "When Udayarāja, a great friend and ally of Prithvirāja, heard of his captivity, he sat down before Delhi and besieged it. During the siege, a courtier of the Ghori Sultan suggested to his master that it would be becoming on his part to release the Chauhān. M'uizzu-d-dīn, it is said, was so incensed by the proposal that he denounced the adviser as a traitor and ordered Prithvi Rāja to be imprisoned in the citadel, where a few days afterwards, he breathed his last." (Ed. Kirtane, Introd. 20-21). Can this have been the obscure intrigue of the text?

II. 217, l. 9 from foot. The accursed Jatvān....had raised his hand in fight.....against Hānsi.

The name is a puzzle. It has been conjecturally interpreted as 'a body of Jats.' But this will not bear to be looked into, because, as Elliot points out in the note, the singular is used throughout, and Jatwan himself is explicitly stated to have been killed. Elliot seeks to evade the difficulty by suggesting that Jatwan must be supposed to have been "a mere leader of the Jat tribe which still maintains its position in the neighbourhood of the scene of action". But this quibble or supposition has not found much favour. I venture to think that is a mistranscription of ite action. The insurgent was a Chauhan, a member of the same tribe to which Prithvi Rāja belonged, perhaps one of his paladins. Ḥasan Nizāmi did not know his name or had not troubled to ascertain it. It was enough for him that he came of the same 'accursed stock' as the 'Kola Pithaura.'

This confusion between جوان and جوان is not uncommon in Mss. On E.D. III. 109 and also on 245, Dowson and the B. I. text of Barani's Tārīkh-i-Firūz Shāhi read 'Jatwān' [Jats], (65, 1.4 f.f.; 483, 1.4 f.f.) but the I'. A. (104, 1.8) and F. (I. 137, 1.4 f. f.) write 'Chauhān' in the counterpart passages. Jatwan is said to have wrested the fort of Hansi from its Musalman commander. Now we know that Hariana—the district round Hānsi and Ḥiṣār-had been under the sway of the Chauhāns for many years before this and the fact is explicitly mentioned in two inscriptions of V. S. 1337 (1280 A.C.) and 1384 (1327 A.C.), in which it is stated that several generations of Chauhans had ruled there before the Muhammadan conquest. (J. A. S. B. XLIII. 104; Epig, Ind. V. App. p. 34; Ibid. I. 93). A very large number of Chauhans are still found on the site of their old kingdom near Karnāl and Ambālā. F. (I. 61, l. 11) makes Jatwān one of the relatives or connections of Bhimadeva, the Raja of Anhilwar, and states that he fled to Gujarat after this defeat by Aibak in 589 H., although Ḥasan Nizāmi explicitly declares that he was killed. Elsewhere again, F. avers that Jatwan was the Commander-in-Chief of the Raja of Anhilwar and that he was routed and killed in attempting to repel Qutbu-d-din from before the fort of Anhilwara two years later in 591 H. (I. 62, 1.3). He does not cite any authority and his assertio.

be accepted as they are in conflict with the contemporary chronicle. In the C. H. I Jatwan is made "the leader of an army of Jats" who owed allegiance to Rājā Bhīm, but F.'s statements about his escape and flight are rejected and he is said to have lost his life at this time (III. 41).

II 218, l. 3. The soldiers of Islam came up to the army of Mind on the borders of Bagar.

"The Bagar tract stretches from the south and south-west of Sirsa along the western border of Hissar district through Sirsa, Fathabad, Hissar and Bhiwani, gradually widening towards the south." (I G. XIII 149) The southern and eastern parts of modern Bikaner are included in this sandy region (Ib VIII. 20) Hansi was the capital of Hariana, which was a part of Bagar It was in the centre of the old Chauhan kingdom of Sapadalaksha, or Siwalik. (I A. XLI 17-19)

II. 219 and note The rebellion of Hiray, brother of the Rāi of Aymer. The real name is neither Hīray nor Dhīrāy, nor Bhūray or Bahraj as Raverty (T N Tr.517 note) will have it, but Harirāya. This is now known from the Prithvirāya Kāvya—a Sanskrit poem written by a contemporary Kashmīri author (J R A S. 1913, pp. 275, 278-9). According to another work also, the Hammīra Mahā-Kāvya—a poetical biography of Hammīra Chauhān of Ranthambor, composed by Nayachandra Sūri about 1430 A C—Harirāy was the brother of Prithvirāy On hearing of his death, he abandoned himself to despair, took no thought of the government and passed his time in the company of women and musicians. But when Shihābu-d-dīn invaded his country, he performed the Sak and ascended the funeral pile with all the members of his famīly (Kirtane's Edit, Introd. 21-22)

II 220, l. 17. The son of Rāi Pithaura sent abundant treasure together with three golden melons, which with extreme ingenuity had been cast in moulds etc.

The name of this son is said, by Nayachandra Süri, to have been Govindarāja but others give it as Rainsi The things sent were not 'melons' but kettle drums Fakhruddīn Muḥārakshāh also states that there were four Kharbūzas which weighed three hundred mans and that Qutbu-d-dīn sent them all to the Sultan M'uizzu-d-dīn Sām, who presented one of them to his brother Ghiyāsu-d-dīn The latter had it conveyed to Herāt and the Jām'i Mosque in that town was constructed out of the proceeds of the Kharbūza (Ed Ross, 22-23) A similar statement is found also in Minhāj's T N (91, 1 8 f. f = Raverty, Tr 404) The word does not here mean 'melons', but 'kettle drums' or Nagār as shaped like melons, and Minhāj speaks of them as 'co Cara golden drums' A '18, according to the Ghiyāsu-l-Lughāt, a 'golden drums' a great drum or Nagāra' 11. 224, l 13.

The right reading is 'Ughlabak' , as in the T. N. Bibl. Ind text, 178, l. 10, and at 305, anfi a Raverty has Aghūlbak (Tr. N. 627) and he is followed in the C. H. I. (III. 42).

Hisimu-d-din is mentioned by 'Awsi in the Javāmi'au-l-Ḥikāyāt and the title is read there as 'Aghlabak.' 'Awsi says that Ḥisīmu-d-dīn was falsely accused by Jamāl Pārsāi and Qāzi Muḥammad Gardezi of extortion in connection with the assairs of Miyāna [Bayāna?] and that when those charges were found, on investigation by Nizāmu-l-Mulk Junaidi, the Prime Minister of Iltūtimish, to be baseless, the slanderers were publicly disgraced. (J. II. III. xix, 9 = No. 1729, p. 228). Ughli in Turki is said to mean 'Prince' or 'General' and the title may signify 'Chief of Princes or Generals'.

II. 225, l. 13. Jihtar, supported by an army, hastened to the borders of Dehli.

Elliot notes that the name is written 'Jihtar' and 'Jhitar.' I submit that it stands for 'Jaitra Sinha'—a form which occurs, not infrequently, in the dynastic lists of Hindu principalities. In the C.H.I. III. 43, and Raverty's Tr. of the T. N. (519 note), he is called 'Jhat Rai,' but this is an impossible name for a Hindu. There is a somewhat similar name in the Chachnama, where it is spelt variously as 'Jhatra,' 'Chatera' (E.D.I. 141 and note), 'Jetar' or 'Chitra' (Kalich Beg's Translation, 31) and this may be meant for some such form as Jaitra (Sinha) or 'Chhatra' (Sinha). In any case, Jhat Rai, Jihtar and Jhitar are alike untenable. It is not easy, in the absence of any other clue than the name, to identify the person meant, but the conjecture may be offered that this 'Jihtar' may be the Mahārājaputra Jayanta Sinha of an inscription at Bhiumāl, which is dated in V.S. 1239-1183 A.C. (B.G.I. i. 470, 474). There is a temptation to identify him also with the Jaitsi Paramar of Abu whose daughter's beauty is said by the bards to have been the cause of the disastrous feud between Bhima Chilukya and Prithvi Raja. (Forbes, Ris Mālā, Ed. 1924, I. 202 note and 215). But the tale told by Chand Bardai seems to be a fiction, and the existence of Jaitra Paramāra is more than doubtful. This Jayanta Sinha of Bhinmal was the Chauhan ruler of Nādol who reigned there between c. 1249 and 1262 V.S. = 1192 and 1205 A.C. He was the son of Kelhana, eleven of whose inscriptions ranging from 1221 to 1249 V.S. = 1164 to 1192 A.C. have come to light. (Epigr. Ind. XI. 46-52). Jayantsinha was succeeded by his son Udayasinha who was Raja of Jhalor and ruled circa V.S. 1262 to 1305 = 1205 to 1249 A. C. (Ibid. 73; Tessitori, Bardic Survey of Rajputānā, J.A.S.B. 1914, pp. 406-7. See also my note on l. 16, p. 236 infra). II. 226, l. 24. They marched towards Thangar.

This name is written Thankar, Bhankar and Bhangar at 297 and 304 infra. Ranking (B. I. 51, Tr. I. 71 note) and the writer of the Article on Budaon in the I. G. are mistaken in identifying it with Bangarh near Budaun. F. (I. 59, l. 2) asserts, in his characteristically careless way, that it is now known as Bayana and Raverty has reiterated and disseminated the error. (T. N. Tr. 471 note). But Thangar is really 'Tahangarh,' a fort lying about 15 miles south of Bayana. (Seeley, Road Book of India,

19) Minhāj states that it was in the country of Bayāna (304 infra). It was built by Tahanpāl [Tribhuvanapāla] Jādon, the ancestor of the Rājās of Karauli (I G. XV. 27) The contemporary writer Fakhru-d-dīn Mubārak Shāh calls it Fakhru-d-dīn Tahank(g?)īri, and says it was taken in 592 H. (Tārīkh, Ed. Ross, 23, 15 f. f) Tahangarh is now in the State of Karauli and lies 24 miles north of Karauli town. Bayāna is now in the State of Bharatpur. (I. G. XV 27, 34) The Rājā of Bhangar [Recte Tahangar] is mentioned in the Tārīkh-i-Mubārakshahi also (E. D. IV. 62, l. 9 f. f. q. v. my note) Tahangarh was a place of importance even in Bībur's days and is mentioned by him in his Tūzuk (B. N. Tr. 538) It is marked in the Oxford Indian School Atlas of John Bartholomew, Pl. 24, and also in the I. G. Atlas, Pl. 34, E. 2. The local pronunciation now seems to be Timangarh

II. 229, last line. The people (of Pāli and Nādūl) had collected under their leaders, Rāi Karan and Dārābars in great numbers at the foot of Mount Ābū

'Rāi Karan' is called 'Kunwar Pāl' in the CH I. III. 43, but contemporary inscriptions of the Gujarāt Chālukyas and other ruling dynasties now enable us to restore both the names correctly نم is an error for Kırat, ie, Kırtīpāla Chauhān of Nādole, who is known to have wrested Jālor from its former rulers, the Paramāras (I. GXIV 301)

The Chauhāns of Nādole were a branch of the ruling family of Sāmbhar and were feudatories of the Gujarāt Chālukyas The first king of Nādole was Lakshmana, a younger son of Vākpatirāja One of his descendants, Āsarāja had a son Alhana who had two sons, Kelhaņa and Kirtipāla Several of their inscriptions dated in the 13th century V.S. have been found. (Epig Ind. XI, 72, 77, Vaidya, H.M. H. I. III. 302, G. H. Ojhā's Hindi Tr of Tod's Rājasthān, 40, Ray, D. H. N. I. 1123-1132).

Udayasınha his grandson submitted to Iltütimish (236 infi a) about 1215 A C Dārābars is Dhārāvarsha Paramāra, Chief of Ābū, who was the son of Yashodhaval He was the general of the Gujarāt army both in the battle of 1178 and of 1197 A C The Paramāra rulers of Ābū had been feudatories of the Gujarāt Chālūkyas ever since the reign of Siddharāja (1094-1143 A C), if not earlier. (B. G I. i 160) Fifteen contemporary epigraphs prove that Dhārāvarsha ruled at Ābū from 1163 to 1218 A C as the feudatory of four kings of Gujarāt. (Ojhā, loc. at. 384; Vaidya, l c III. 301-2, Duff, C I 175, 220; Rās Mālā, I. 225, 255, I A XI 220. LVI. 47-48)

F gives the names of the leaders of the Gujarāt army as 'Wālan and Dārabsı' (I 62, I 9 f f) 'Wālan' must be a miswriting of or of or e, Pāhlan, the short form of Prahlādanadeva—the younger brother of Dhārāvarsha. The town of Pāhlanpur near Ābū is said to have been founded by and named after this Prahlādana or Pāhlan Deva (Forbes, loc. cit 261-2) 'Dārābsı' is only a perversion of Dhārāvarsha

The battle is said to have taken place on Sunday, the 13th of Rab'iu-

l-awwal 593 A. H. The Julian equivalent of 13th Rab'i I. Hisābi, 3rd February 1197, was a Monday. The date given may have been the 18th according to the 'Hilali,' the 'Ruyyat' or orthodox system, as it was a Sunday.

II. 231, l. 19. His Diwan, or Mahtea Aj Deo was not disposed to surrender so easily.

F. (I. 62, last line) calls him 'Jadah Dev' جده د. The real name was probably Baj Deva or Vaj Deva. We know that Bach Deva or Bachharāja or Vachharāja [Vatsarāja] was the prime minister or Amātya of Parmardideva, 'the accursed Parmār' of this author. He was a poet and wrote six dramas entitled Rūpaka Shatkam, which have been published in the Gāikawād's Oriental Series. Bacchon, a small town about fifteen miles north-east of Ajaigarh, is said to have been founded by this Baj Deva or Bachha Rāj and an inscription dated V. S. 1376 (1320 A. C.) has also been found near an old tank in which the town is called Vacchiun. (I.G.V. 130). Baj, Bachha, Vachha are vernacular forms of the Sanskrit Vatsa, Calf.

II. 231, l. 12 from foot. On Monday, the 20th of Rajab 599 H. [Kalanjar surrendered].

20th Rajab 599 H. = 4th April 1203, Friday. 8th Rajab 599 H. = 23rd March 1203, Sunday. 20th Rajab 598 H. = 15th April 1202, Monday.

Fakhru-d-dīn Mubārakshāh puts the event into 599 H. (24, 1. 1 f. f.) and so does F. (I. 62, l. 4 f. f.). T. A. and B. do not specify the year. The I. G. (XIV. 312) and Mr. Vincent Smith (O. H. I. 222) vote for 1203 A.C. but Sir Wolseley Haig favours 1202 (C. H. I. III. 47). If 599 H. is right, the correct date must be 8th (not 20th) Rajab (Ruyyat) 599 H. = Monday, 24th March 1203. and are often confused in the Semitic script and 20th Rajab may be an error for 8th Rajab [Ruyyat]. But the week-day works out correctly with 20th Rajab, [Hisābi] 598 also.

II. 233, l. 11. He went immediately to Amīr Dād Hasan, the lord of a standard.

'Amīr-i-Dād' (Chief Justiciary) was the designation of his office and Ḥasan only and not 'Dād Ḥasan' was his personal name. The Amīr-i-Dād was also called 'Dādbak' at this period, just as the 'Āriẓ' was also called Mīr-i-'Arẓ or 'Arẓbegi.' Barani says Niẓāmuddin was the Amīr-i-Dād of Sultān Mu'izzu-d-dīn Kaiqubād (T. F. 148, l. 12) and he speaks of him elsewhere as Dādbak (126, l. 5 = E. D. III. 126), which shows that the two official titles are identical. The same author states that Malik Tāju-d-dīn 'Irāqi was Amīr-i-Dād-i-Lashkar, Judge-Advocate-General of the Army, in the reign of 'Alāu-d-dīn Khalji. (358, l. 1; 361, l. 17).

II. 234, note. (The river) Sodra is so called from the old town of that name on its eastern bank.

It is more correctly described as the 'River of Sodra,' just as the Ravi is spoken of as the 'River of Lahore' and it is arguable that the town was founded and named after the river. The described Hindu

name of the Chināb was Chandrabhāga and Abul Fazl says that it is made up of two streams, the Chandrā and the Bhāgā, which unite near Khatwār [Kishtwār], (Āīn. Tr. II 310) 'Utbi speaks of it as the 'Chandrāha' (E D II 41) and so also Baihaqi (Ib. 120, Text, 328, I 3) and Alberūni, (E D.I. 68, Tr. Sachau, I 206, 259). The mutation of the Sanskrit 'Cha' into 'S' or 'Sh' is very common and Chandrāha would become Sandrāha, Sandra, Sondra and Sodra The town of Jandarūz (Chandrūr or Chandrawar) which was on the banks of the river of Jandarūd (the Chanda-rūd, ie. Chand-āb or Chīnāb) is mentioned by Ibn Hauqal (E D I 40), and this is most probably no other than the town of Sodra Sodra must have been originally Chandrāpura, then Chandrāwar, Chandror, Sandror and Sodra by the metathesis of the vowel. Sangwān which is said to be within the borders of Multān may be Sanawān in Muzaffargarh, Punjāb, q. v. Constable, 24 D b.

11. 236, l. 3. Some impious men .. inflicted five or six desperate wounds upon him [M'uizzu-d-dīn Sām]

The word used in the original 18. ملاحد (Raverty, T. N Tr 485 note) which indicates that in this author's opinion as well as in that of Minhaj, who speaks of them as مرائي ملاحد، Malahida Fidais or desperadoes' (T N Text, 124, 11 2, 3), the assassins were Fidais of the Batini or Ism'ailiya order M'uizzu-d-din Sam had been at war with these heretics throughout his life. He had driven them out of Multanan 571 H (T N 243 post) and in 595 H., he had routed and expelled them from Khurāsan, where they had established their sway. The sect had developed assassination into a fine art and Yule gives a list of nearly twenty distinguished men-Khalifs, Ruling Princes and their Vazirs (including two Europeans, Raymond Count of Tripoli and Conrad of Montferrat, titular King of Jerusalem)—who were murdered by its emissaries in the course of the century intervening between 1092 and 1191 A C (Tr Marco Polo, I 145) and there is still another long list of their victims in Browne (L H P II. 311-2) Baızāwı (E D. II 258) and Hājjı Dabīr also state that the assassins were Malahidas of the Ism'aili sect (Z W 682, 1, 16)

Firshta is chiefly responsible for the dissemination of the error that the assassins were Gakkhars. He has been followed by Elphinstone (p. 367), Thomas (C.P. K. D. 12) and others. But his account is enriched with so many adventitious details, that it looks more like a dramatic reconstruction of the scene by a poet or painter than real history. The number of the conspirators was, if we are to believe him, just twenty. One of them wounded the Sultan's gatekeeper with a knife and fied and when the other attendants were all gathered round him, some others cut open the tent in which M'uizzu-d-din was lying down and inflicted just twenty-two knife-wounds upon his person. (I. 60, I.7) F. does not state his authority. But it would appear that the idea of ascribing the assassination to the Gakkhars is not older than the 16th century. Yahiyabin 'Abdu-l-Latif

who wrote the Labbu-t-tawārīkh in 1541 A. C. seems to have said that the conspirators were with in it is 'Hindi Fidāīs'. Qīzi Aḥmad Ghaffāri who compiled the Nusakh-i-Jahānārā in 972 H. then turned this phrase into the Historians of Muhammadan India, 1849, Persian Extracts, pp. 34, 37). This was followed in the T. A. (20, 1. 1) and the Tārīkh-i-Alfi (T. N. Tr. 486 note). F. then copied this gratuitous conjecture, but at the same time perverted the name 'Khokhar' into 'Gakkhar.' The Gakkhars are not mentioned by any of the older historians and their name occurs for the first time only in the Memoirs of Bībur (16th century). Most modern ethnologists are agreed that the two tribes are quite distinct. (Raverty, T. N. Tr. 455 Note). See also Mr. H. A. Rose's Art. in the Ind. Ant. XXXVI (1907), p. 4.

II. 237, l. 10 from foot. This army.....vas drawn out.....near the Bāgh-i-Jūn (the Jamna Garden).

So also in the T.N. (Text, 170, l. 12; 323 infra), where the battle is said to have been fought in the plains (0 = 0) of the Jumna, but the better copies have 0 = 0 and this is the preferable reading. (Raverty, Tr. 606 and note). See also my note on 357, l. 10, post.

II. 238, l. 16. Udi Sāh the accursed, took to the four walls of Jālewar.

We may safely identify this Udi Sāh with Udaya Sinha Chāhamāna (Chauhān), who is called ruler of Jāvālipura [Jālor] in the Kolophon of a Manuscript of the Viveka-vilāsa of Jinadatta, who flourished under him about 1220 A. C. Udaya Sinha was the grandson of the Kirtipāla Chauhān of Nādole—Rāi Karan of p. 230 ante—and ruled between 1206 and 1249 A.C. He was a contemporary of Vīradhavala Vāghelā of Dholkā and Viradhavala's son Vīrama was married to Udayasinha's daughter. (Bhandārkar, Report on the Search for Sanskrit Mss. 1883-4, p. 156; I.A. VI. 190; B. G. I. i. 474-6; Duff, C. I. 179, 185; Epig. Ind. XI. 55-57).

II. 239, l. 18. [Shamsu-d-dīn Iltutimūsh] advanced with a large army to Sāmānd which he reached on Monday, the 3rd of Shawwāl 612 H.

This was Monday, 25th January, 1216 A. C. Minhāj says the battle was fought near Narāin or Tarāin, 324 infra. Sāmānd may be Samāna in Patiāla, which lies about 40 miles north-west of Tarāin or Tirāuri.

II. 241, l. 22. Conquest of Kālewar (Gwālior)....Behār and Bārah.

Bārh (or Barr, as Thornton calls it) is a town on the right bank of the Ganges, 44 miles east of Dīnāpore, which last is 10 miles west of Paṭna. Constable, 29 A c. It is now the headquarters of the north-eastern sub-division of the same name in Paṭna district. (I. G. VII. 15). Bakhtyārpur which is named after Muḥammad-i-Bakhtyār is now in Bārh. I. G. s. n.

II. 242, l. 20. Nāsiru-d-dīn died shortly after of grief and the boat of his life was drowned in the whirlpool of death.

Whether Qubacha was drowned by accident or by design is not

quite clear The author's words are equivocal and may imply either death by misadventure or deliberate suicide. Minhāj states explicitly (30½ infra) that "he drowned himself in the Indus". (Text, 144, 115) F. merely says that he "got into a boat and was drowned in the sea (or river)" (I 66, 17) and the J. A (28, 1.7 f f.) is even more obscure. It may be therefore pertinent to draw attention to the fact that 'Awfi speaks not only of his having deliberately committed suicide, but quotes a Rub'āi which he is said to have recited, before throwing himself into the river. The verses are

The quatrain is cited on the authority of 'Awsi by Hājji Dabīr also. (Z W. II. 696, ll 22-3)

In view of the explicit declarations of these contemporary authors—both of whom had been in the service of Qubācha—it seems safe to hold that Qubācha did commit felo de se. It should be noted that Minhāj mentions the event in two passages and the second is even more emphatic than the first if the work is a second is even more emphatice than the first if the work is a second is even more emphatice than the first if the work is a second is even more emphatice than the first if the work is a second is even more emphatice than the first if the work is a second is even more emphatice than the first if the work is a second is even more emphatice than the first if the work is a second is even more emphatice than the first if the work is a second is even more emphatice than the first if the work is a second is even more emphatice than the first if the work is a second is even more emphatice than the first if the work is a second is even more emphatice than the first if the work is a second is even more emphatice than the first if the work is a second is even more emphatice than the first if the work is a second is even more emphatice than the second is even more emphatice. It is a second is even more emphatice than the second is even more emphatice. It is a second is even more emphatice. It i

The question is left open in the C H I (III p 54) and no opinion is pronounced, but the contemporary evidence points clearly to premeditated self-immolation and not to accident or misadventure. The non-committal verdicts of the later compilers carry little or no weight, as they had no other contemporary sources of information than those we possess

II 246, l 14. Higra 160, A D 776, Conquest of the town of Barada

Biladuri also mentions an expedition by boats against Narand or Barbad (الرباء or الرباء) in the days of the Khalif Mansur, who reigned from 186 to 158 A. H (E D I 127) Elliot notes that the Manuscript in the British Museum reads 'Barbad' and surmises that 'Barbad' may be the Bardā Hill district of Jaitwār near Porbandai in Kāthiāwāḍ (E D I 125, 444) Alberūni states that soon after Mansūra was founded, Ranka, a disaffected subject of 'Balaba' (Valabhi), persuaded the Arab lord of Mansūra to send a naval expedition against that town The king of 'Balaba' was killed in a night attack and his people and town were destroyed. Alberūni gives no date, but as Mansūra was founded about 750 A C and as the latest Valabhi copper-plate is dated in 766 A. C. it has been suggested that this expedition to 'Bārbad' which was des-

patched by sea in 776 A. C. may be the one referred to by Alberüni. Dr. Bhagvānlāl Indraji tells us that in some Jaina chronicles, the destruction of Valabhi is said to have taken place in the year 826 of some Era, which he thinks must be that of Vikrama, i. e. in 770 A.C. (B.G.I. i. 94-6 and note). But the two dates do not exactly tally and the whole question is enveloped in doubt. The Hindu accounts give several other conflicting and discordant dates for the destruction of Valabhi which are eited by Dr. Bhagvānlāl, but which it would be infructuous to repeat here, as they really lead nowhere. The actual cause of the destruction of the town of Valabhi also—fire, flood or foreign invasion—has been the subject of dispute and the truth seems past finding out, as nothing decisive can be inferred from the ruins on the spot.

II. 249, l. 15. He fined the inhabitants of Multan 20000 dirhams.

'Utbi says (Text. 363, l. 3=E. D. II. 32) that the amount was twenty thousand thousand dirhams. Gardozi states that Abu-l-Futuh Da'ud bin Nasr was compelled to pay a tribute of twenty thousand thousand dirhams annually. (Z.A. 97, last line). Mahmud's dirhams were silver pieces weighing from about 40 to 50 grs. (Rodgers, Catalogue of Coins in the Indian Museum, Part IV; Catalogue of Dr. White King's Collection of Coins. Part III. Sect. XXIV). 20000 dirhams would have contained only about as much silver as 6000 of our rupees, which appears to be an absurdly small war-indemnity for a kingdom like that of Multan-a kingdom which is said by Mas'ūdi, though with some exaggeration, to have contained 120000 villages. (E. D. I. 23; Tr. Sprenger, 384). Influenced most probably by some such consideration, F. (I. 25, l. 8) turns it into an annual tribute of 20000 gold dirhams درهم سرخ and he has been followed in the C. H. I. (III. 15), but there is no warrant for the whittling down of the amount or for the substitution of 'gold' for 'silver', in either of the two contemporary historians, 'Utbi or Gardezi. The discrepancy between the primary authorities and the later compilers is most probably due to the omission by some scribe of the second مزار or 'thousand'-a frequently recurring error.

II. 249, l. 18. Bhim, the chief of Anhalwara had gone to the fort of Kandahat.

Variants, Khandama, Khandabā (q.v. 473 infra), Kandana, Khandana etc. The location of this mysterious fort has taxed the ingenuity of the commentators and at least five identifications bearing a superficial phonetic resemblance have been suggested. Dr. Bühler was in favour of Kanthkot in Vāgaḍ (East Kachh), Watson of Gānḍhvi on the Kāṭhiāwāḍ coast, a few miles north-east of Miāni near Porbandar, Reinaud of Gandhār at the north of the Dhādar river near Broach, and Elliot of Khanḍādhar at the north-east angle of Kāṭhhiāwād. (473 infra; B.G.I. i. 167 and note). Sir Wolseley Haig thinks that it must be Bet Shankhodhār at the north-western extremity of Kāṭhiāwāḍ (C. H. I. III. 25), though he admits that the description is not applicable to Shankhodhār and he is obliged to add

that "if the chronicles are to be credited, it was possible in those days to reach the island on horseback at low tide, though it cannot be done now" As there is no evidence to indicate that any great change has taken place on this coast, his suggestion may be safely dismissed

The only clue to a correct solution is the statement that the ford near Kandahat was so exceedingly treacherous that "if the wind blew a little, all would be submerged" or, as the Tai ikh-i-Alfi expresses it, "if the tide should rise a little at the time of their passing, it would drown them all." (473 infra) This is the real crux of the matter and the phenomenon to which reference is made must be a Bore-" a tidal wave of great height and force which appears in certain rivers at the period of high or spring tides Rushing from the estuary along the gradually narrowing channel of the river, the impelling force resolves the water into a huge wall or wave which carries everything before it" (Yule, H J s v Macareo). Yule assures us that there are only two places in India, where there is such a Bore, Eagre, Macareo or Mascaret, (as it is variously called), viz, the Bore in the Hoogly and the Bore in the Gulf of Cambay There is no such 'tidal wave' either at Kanthkot or at any of the places which have been put forward by the authors named Ibnu-l-Athir's and the Bore آسبت and the Bore there The phenomenon was well-known to Mas'udi, who was hugely struck "The ebb here is so marked in this estuary by it He writes of it thus that the sand lies quite bare and only in the middle of the bed lies a little water. I saw a dog on the sand which was left dry in the water, like the sand of a desert, the tide coming in from the sea caught him, although he ran as fast as he could to the land to escape, and the poor animal was drowned, notwithstanding his swiftness "(Tr Sprenger, 278=Prairies I There is a reference to it in Ibn Batūta also (Defrémery, IV 60) and several of the old European writers, e g De Barros (II in Cap 9), Varthema (Tr Badger 105), Barbosa (Tr Dames, I 138), Pietro della Valle (Tr. of 1665, p 33) and Hamilton (II 83) were greatly impressed by it last of these authors informs us that "a body of water comes rolling in on the sand .. and whatever body lies in its way it overturns and no ship can evade its force, but in a moment is overturned." (Yule, loc cit).

Ibnu-l-Athir says that 'Kandahat' was about forty far sakhs distant from Somanāth Now Cambay is in Lat 22°-18' N, Long 72°-39' E and Somanāth in 20°-55', Long 70°-26' E, a map-distance of about 165 miles According to Thornton, Cambay is 52 miles south Ahmadābād (Gaz. 179) and Somanāth 210 south-west of it (Ib 923)—a difference of about 160 miles Forty farsakhs would be equal to about 160 miles at 4 miles to the farsakh Alberūni says Somanāt'i is 30 farsakhs from Cambay, i e, about 150 miles (E D. I 66), as he reckons the farsakh at five miles

II. 251, l 6 from foot. When the elephants were brought before
Shihābu-d-dīn they all saluted except the
white one

This wonderful story of Jayachand's white elephant refusing to make the Salām to the victor of his master finds a parallel in Manucei's tale of the Emperor Shah Jahan's favourite elephant, Khaliq-dad, refusing to salute Aurangzeb after his usurpation and of his running amuck when induced to do so by a trick. That animal also is said to have died of grief on the very day on which Shah Jahan expired. (Storia, II. 10, 127). F. says that as Jayachand's white elephant refused to salute the Sultan, it was given away some days after the battle to Aibak and that it died on the third day after Aibak's death. (I. 61, l. 11 f.f.). Other equally tall stories are told in connection with the salāming of elephants. Tavernier assures us that when elephants from India and other parts of the world see a Ceylon elephant, they instinctively pay it reverence by placing the ends of their trunks on the ground and then elevating them. He emphatically assures us that, incredible as it may appear, this statement is quite true. (Tr. Ball. II, 317). His contemporary Fryer goes even further and asserts that "Ceylon elephants exact homage from all others, which prostrate themselves submissively before them." (New Account of East India and Persia, Calcutta Reprint, 169). But these asseverations are derided by Sir J. E. Tennant as 'fanciful.' (Ceylon, II. 380).

F.'s story of the tragic end of Jayachand's white elephant must, if Raverty is right, be a fable. It would appear from the contemporary sources cited by him that ... animal was really presented after Shihābuddīn's death by his nep'iew Ghiyāṣu-d-dīn Maḥmūd, to Muḥammad Khwārizmshāh. It was neither turned over to Aibak nor died of grief after his demise. (T. N. Tr. 258, 402, 470 notes). Old histories abound in similar tales of wonder. Aḥmad Yādgār, who is inordinately partial to the fabulous, says that the Rājā of Jhārkhand had a white elephant which never "threw dust upon its head." (E. D. IV. 362 note). Modern zoologists discredit these yarns and have exploded much of the 'mythology of the elephant.'

II. 255, l. 1. The Nizāmu-t-tavārikh.

These extracts from Baizāwi's History are full of demonstrable errors and serve only to introduce further confusion into the perplexed chronology of the Ghaznavides. E. G. Browne justly says of the Nizāmu-t-tavārīkh that "it is a dull and jejune little book, scarcely worth publishing. It is doubtful if it contains anything new or valuable and it is not calculated to add to the fame which its author enjoys as a jurisconsult, theologian and commentator." (L. H. P. III. 100).

II. 255, l. 11. Muhammad was taken prisoner and sent to the first of Balbad.

Tukhāristān (Ed Goeje, 275, 1 6; 286, 1 1, Le Strange L.E C. 428) and Abul Fidā makes it the capital of that district. (Vide In, Tr 111 68 note) Minhāj calls it Walakh [Recte, Walaj]. (T N. Tert 343, 349, 359) Holdich says it was just north of Qunduz (G I. 272) and it is shown on his Map Lat. 37°-0′, Long. 69°-0′. F. states (I 40, 1. 14) that Walaj in which Muhammad was interned is also called 'Khalaj' and Elliot consequently seeks to identify it with Kelāt-i-Ghilzīi (E.D. IV 192 note), but the gloss as well as the conjecture must be rejected. Sultan Mahmūd of Ghazna had a mint at Walwālīj and silver dirhams struck by him at a place, the name of which has been read as eleliot coins in the Brītish Museum (Lane Poole, Catalogue of Oriental Coins, II p 148, No 503, Thomas, J.R A.S XVII). I suggest that the right reading is (elelion) Walwālīj II. 266, l. 10. Sultan S'aīd Mahmūd heard from his father.

Here 'S'aid' is not a name or part of the name of the Sultan, but a laudatory epithet or benedictory prefix signifying 'Happy, blessed, august' Sultan Sanjar, Sultan Ghiyāsu-d-dīn Muhammad-i-Sām and his brother Mu'izzu-d dīn as well as Iltutmish are all called 'S'aīd' on pp. 279, 280, 281 and 301 infra by Minhāj

II. 267, l 4 from foot Alptigin acrested Ghaznin from the hands of Amir Anuk

The last name is, as Dowson notes, variously spelt. The correct form seems to be [AbuBakr] Lawik. The history of the predecessors of Subuktigin in Ghazna is obscure and there is considerable divergence of opinion on the subject. Vide Khwāndamīr in E.D. IV. 159 and Elliot's remarks there. Raverty has a lengthy note on the subject (T. N. Tr. 71-73), in which he maintains that Alptigin reigned for eight years and died in 352 H, that Ishāq his son was in power upto 355 H, that Ishāq was succeeded by Bilkātigīn whose rule lasted for eight years upto 362 and that his successor Pīrey was defeated and expelled by Subuktigīn in 367 H.

Dr Nāzim who has recently re-examined the whole question arrives at the following conclusions—Alptigin conquered Ghazni about Zī-l-Hijja 351 H. after a siege of four months, but died after a reign of only eight months (not years), on 20th Sh'abān 352 H. Abu Ishāq, after being driven away by Abu 'Ali, [son of Abu Bakr] 'Lawīk' returned and defeated Abu 'Ali on 27th Shawwāl 354 H Ishāq died on 25th Zi-l-q'ad 355 H. Bilkātigīn ruled for eight or nine years from 355 to 364 H and Pīrey from 364 to 27th Sh'abān 366 H. (M G 24-27, 175-176) Minhāj is therefore right in saying (269 infi a) that Sultan Mahmūd was born in the 7th year of Bilkātigīn

II 268, l. 15. On the 27th of Sh'aban A. H. 366, on Friday... he [Subuktigin] ... was confirmed in the government.

Fasih's Mujmil (quoted in Raverty, Tr. T. N. 73 note), F. (I 18, 1. 8 f f), B. (I 8 = Tr I 14) and Elphinstone (p 320) give the year as 367 H, but this must be an error as 27th Sh'aban, 367 H., or 9th April 978 A. C. was a Tuesday. Ibnu-l-Athir (Ed. Tornberg, VIII. 507)

gives the same date as Minhāj. As 27th Sh'abān, 366 H.=20th April 977 A. C. was a Friday (Ind. Eph.), it must be correct. The date given in the C. H. I. (p. III. 11) is 9th April 977 A. C., but it must be a miscalculation, as that day was a Monday and its Hijri synchronism was 16th Sh'abān 366, not 27th.

II. 268, l. 2 from foot. All the sources of internal dissensions in Khurāsān were eradicated [by Subuktigīn].

p. 8, 1. 4. "And he uprooted the stock of the heresy of the Bāṭinīya from [all parts of] Khurāsān." The Bāṭinīyas were identical with the Qarāmiṭa, Malāḥida, Ismāʿilia or Tʿalīmiya. 'Bāṭin' means 'inner, esoteric' and they were so called because they taught an 'Inner' or 'Secret Doctrine' based on the allegorical interpretation (الحريل) of the Qurān and the Law of Islam. Their Imāms also claimed to be the sole inheritors and guardians of that Law. (Browne, L.H.P.II. 196). II. 269, 1. 20. Amīr Subuktigīn saw in a dream.

Both these tales—of Subuktigin's dream and of the falling down of the idol in a place called Waihind (or 'Bahind', not 'in Hind')—are in 'Awfi's Jawāmi'a (I. XXI, No. 1072, J.H. 61, 185) and are both related there on the authority of the Tārīkh-i-Nāṣiri, that is, the earlier and lost portion of Baihaqi's History of the Ghaznavides. 'Awfi also states in the course of the first story, that the birth of Maḥmūd took place in 361 H. Neither of these anecdotes is to be found in the chronicle of 'Utbi, but Minhāj also explicitly eites the lost portion of Baihaqi's work as the Tārīkh-i-Nāṣiri (266, 267 ante) and we may be sure that he has taken the stories directly from Baihaqi and not at second-hand from 'Awfi.

II. 269, l. 5 from foot. An idol-temple in India, in the vicinity of Parshauar, on the banks of the Sind, fell down.

But see Corrections in Vol. VIII, p. xiii. The idol temple was not 'in India,' but at it Bahind', i. e., Waihind, a place 15 miles north of Attock and 26 south of Peshāwar. F. says 'the idol temple' was on the banks of the Sodra (I. 23, l. 12) and thus turns the 'Sind' into the 'Chenāb.' Minhāj's spelling is probably influenced by Jurbādhaqāni, who writes it. Raverty is in error in transporting 'Bahind' or 'Waihind' to Bhatinda (T.N. Tr. 80 note; Mihrān, 411note) and Mr. Vincent Smith also, following his lead, is mistaken in speaking of Bhatinda as Jayapāla's capital. (O.H.I. 190).

II. 270, l. 6. Kept him [Jayapāla] at Yazd (?) in Khurāsān and gave orders so that he was bought for eighty dirhams.

But the Text reads وجيال × × رابكرنت و در من يزيد بخراسان بدائت 9, 1.17. Raverty observes that "nearly every copy" agrees in reading the name as "Man-Yazīd" and his rendering is, "He was kept a prisoner at Man Yazīd" (Tr. 82), but he does not say where this 'Man-Yazīd' is to be found. He also surmises that either the word 'thousand' has been left out after 'eighty' or that "Maḥmūd did not set much value on his capture.' (Ibid, note). Dr. Nāzīm reads the name of the place as 'Mirand' because it is so written in a Ms. of 'Unsuri's Qasida and surmises that "the sale

of Jaipal meant only the fixing of his ransom "(M G S7 note).

I submit that Raverty's Mss are quite right in reading 'Man Yazīd,' but that he and others have erred in supposing it to be the name of a place I understand it as a common noun signifying 'auction' or 'sale in a market' This clue to the solution of the puzzle is obtained from and founded on the authority of the Ghiyā, u-l-Lughāt 'o' is defined there as a "kind of sale in which that person purchases who gives a higher price than the other bidders the word is also used, this author says, for 'the sale of goods' and 'a market' ('Jol')"

The real meaning is that Jayapala was publicly exposed at one of the slave-auctions in some market in Khurāsān, just like the thousands of other Hindu captives As he was an old man and had few or none of the qualifications or attractions of the superior classes of slaves, the price he would fetch in the open market would be of course low and it was fixed at only 80 dirhams The object of exposing him to public derision and contumely was evidently to compel and frighten him into surrendering unconditionally to his victor's demands, to impress upon him that the Sultan was resolved to show no consideration for his person or position and that he would be treated just like any other bondman, if he did not purchase his release on his captor's own terms 'Utbi also informs us that Jayapala himself and his relatives "were strongly bound with ropes and carried before the Sultan, like common cuil-doer s," and that Jayapī lawas "paraded about so that his sons and chieftains might see him in that condition of shame, bonds and disgrace" He states, besides, that Mahmud" entered into conditions of peace with him" only after inflicting upon him the public indignity of "commingling him in one common servitude" with his subjects The conditions were the surrender of 50 elephants and of his son and grandson as hostages (26, 27 ante) It is clear that this exposure in the 'slave market' or من يريد was intended to be the crowning humiliation of Jayapila's life and part of a callous and deliberate plan of frightfulness and intimidation In this connection, it is worth while to note that the author of the Futuhu s-Salatin has interpreted the passage in the same way This is a metrical History of the Sultans of Delhi written by a poet named 'Asamı ın the fifteenth century and is frequently cited by Firishta

The author writes

The lines are quoted in Dr Nāzim's Article on the 'Hindu Shāhīya Kingdom of Ohind' in J R A S 1927, and thus translated by himself (p 494). "He (Mahmūd) scattered the army of the Hindus in one attack and took Rāi Jaipāl prisoner He carried him to the distant part of the kingdom of Ghazni and delivered him to an agent of the Slave Market

[נצ'ל וֹנוֹע]. I heard that at the command of the king (Maḥmūd), they [the Brokers of the Market, יביל in the original,] sold Jaipāl as a slave for 80 Dīnārs and deposited the money realised by the sale in the Treasury."

It would be difficult to-get better evidence than this. This author has understood in exactly the same sense that is assigned to it in the Ghiyāṣu-l-Lughāt, and it should finally settle the question regarding the real meaning of this knotty passage.

II. 270, l. 12. 'Unsuri composed a long Kasida on this victory [of Somanāth].

There is an inadvertent error here. Minhāj cites the two first couplets of the poem itself (10, 1.1), but the real author of the lines which he quotes was 'Usjudi and not 'Unsuri. F. (I. 39, 1.8 f.f.) and B. (I. 10 = Tr. 1.17 note) agree in attributing the lines to the former and the entire Qaṣāda in which these couplets are found is quoted in the Majm'au-l-Fuṣaḥā in the section devoted to 'Usjudi. (I. 340). The two first Baits of a Qaṣāda composed by 'Unsuri on the conquest of Khwārizm are transcribed by Baihaqi. (851, 1.8). They differ in toto from those cited by Minhāj. Fakhru-d-dīn Mubārakshāh informs us that Farrukhi a lso wrote a panegyrical ode on the destruction of the Temple at Somanāth and was rewarded with an elephant-load of silver. (Tārākh, Ed. Ross. 52). Farrukhi's Qaṣāda also is reproduced in the Majm'au-l-Fuṣaḥā (I. 452-3).

II. 270, l. 15. He died in the year 421 H., in the thirty-sixth year of his reign.

Sic also in the printed text, (11, 1.7 f.f.), but it must be an error for and Raverty has 'after a reign of thirty-three years'. (Tr. p. 88). As Subuktigin died in Sh'abān 387 H. and Maḥmūd defeated Ism'aīl several months after that date, the duration of his reign could not have much exceeded thirty-three lunar years. As Ism'ail's rule is said to have lasted for about seven months, he must have been deposed in Rab'īu-l-awwal, 388 H., not 389 as Raverty says. (75 note). See also Nāzim, M. G. 40 and note. II. 270, l. 19. Many curious poems are attributed to him.

and not غربه and understands the words to mean that he was "an authority with respect to the text of several Arabic poems." (Tr. 88 note). He may be right, as Baihaqi actually cites two couplets of an Arabic ditty of which Amīr Muḥammad was very fond and which were frequently sung in his assemblies by his favourite musicians. (79, 1. 4). If the reading is it may mean 'rare, curious, not generally known, out of the common, recondite.'

II. 271, l. 8. When Mas'ud was killed at Mārikala.

صاحب وانه شد (12, l.16), i. e. when a disaster or calamity befell him.' Mas'ūd was not killed at Mārīkala. Alberūni identifies Mārīkala with Takshshilā or Taxila. (Sachau, I. 302). The name is preserved in that of

a pass and a range of hills, about two miles to the south of Shāhdheri (Cunningham, A. G. I 111) and a few miles east of Hasan Abdāl. (TN Tr. 95 note) Takshashilā or Shāhdheri is twelve miles north-west of Rāwalpindi Raverty's derivation of 'Mārīkala' from the Hind 'Mār-gala,' a place chosen by "brigands for attacking travellers and Kārwāns of traders," (T.N. Tr. 95 note) is an example of meaning-making, a popular etymology invented ex post facto and possessing little or no value

II. 271, l. 9 from foot. And even an elephant could not stand before him.

يل and not بيل See Corrections in Vol VIII, p xxiv Raverty reads and, says In Bil or Bil means "a target or butt for arrows" But neither Richardson nor the Ghiyasu-l-lughat gives any such meaning for that word and F who has copied the passage from Minhaj, paraphrases it thus و تير او ار مر كستوان آهيل كدشته مر مدن ديل مشتى (I 40, l.11 f.f) " And his arrow, having passed through the iron armour, used to pierce the body of the elephant" Minhaj himself mentions مركستوان بل on 55, l. 18. This indicates that the reading in F.'s copy also was Fil or Pil and not Bil or Bel F, with all his faults, may be justly postulated to have been at least as good a Persian scholar as Raverty and his interpretation of Minhaj's words must be taken into consideration. Mas'ud was a man of extraordinary physical strength Barhaqi says that he used to wield a mace [عمود] weighing twenty mans (Text, 131, 17) and that in a hand-tohand struggle with a tiger, he smashed the skull of the beast by a single blow of his hands. (Ib 141, see also Tuz Jah Text 366, 1 6 f.f., Tr II 270). II. 273, l. 2 He [Mas'ud] eventually fought a bloody battle with them at Tālīkān

So also in the C H.I (III 31), but Gardezi (107, 1 19), Baihaqi (792-4), T. A (Bibl Ind Text, 25, 1 21) and F (I 43, 1 14) all agree in calling the place Dandāiqān or Dandānqān This town is two or three days' journey, te about 40 miles, north west of Marv-ar rūd, also called Marūchak, Maiv-i-Kūchik, or Little Marv, as distinguished from Marv-i-Shāhjān or Great Marv. Dandānqān was on the road from Marūchak to Sarakhs. There is a Tāliqān or Ṭāiqān near Marv-ar-rūd, but it lies about 50 miles south-east of it, not north-west, towards Sarakhs Holdich says that 'Dendālqān' was near the modern Āk-tepe, which itself lies not far from the now famous Panj-deh (G. I 244-6) See the Map prefixed to that work The battle was fought on Filday, 9th Ramazān, 431 H (Baihaqi, 777, 1 7 ff) See also T'N Tr. Raverty, 131 T'A 13, 1 2 ff F. gives 8th Ramazān 431, H (I 43, 1 14). It was the 3rd of May 1040 A.C. II. 273, 18. They sent Mas'ūd to the fort of Kīri, and there he was slain in the year 432 H

This Kiri has not been satisfactorily identified. Raverty thinks that it must be Gibar-kot, a ruined fort lying about $3\frac{1}{2}$ Kurohs north of Pashat, the chief town of Kunar in Käfiristän (N.A. 151 and note)

But it appears from the context that Kiri was not very far from

Mārīkala, where the slaves in charge of the Sultan's treasures revolted and looted them. The Sultan took refuge in the fortified Ribat at Mārīkala, was taken prisoner and sent to Kīri, which must have been in the vicinity of Marikala and not in Kunar which lay far off and was occupied by unfriendly tribes. Baihagi, moreover, speaks of Waihind. Marminara, Barshor and Kiri, as if they were in proximity to one another. (150 ante, Text 829, 1.2). Mārīkala is about fifteen miles northwest of Riwalpindi. Waihind lies about 15 miles north of Atak (Attock). which is about 27 miles distant from Mīrīkala and Hasan Abdāl. (Chihār Gulshan, in Sarkir, India of Aurangzeb, p. ci). Peshawar is about fortysix miles from Atak by rail or about thirty from Waihind. (Ib. cii). seems to me that Kîri must be Gīri, i.e. Shāhbāz-Gīri, or Kāpar-da-Gīri, which lies about forty miles north-east of Peshawar. It was situated on the old road from Waihind to Kābul (V. Smith, E. H. I. 55 note), about 20 miles north-west of the former. (Beal, loc. cit, I. 114 Note).

II. 274, l. 4. Maudud defeated him at Takarharud.

Bakhrāla, the identification suggested in the foot-note is wrong. 'Takarhārūd' is a misreading of تكرهاد 'Nagarahāra,' the old name of a town and district near modern Jalalabad in Afghanistan. There is a village called 'Nagaraka' even now near Jalālābīd. (N. L. Dey, Geographical Dictionary of Ancient and Mediaeval India, s. n.). Baihagi explicitly states (867, 11. S-15) that the battle took place at Dīnūr. The latter name is also written Depur or Dunpur. These are all forms of Udayanapura, 'Garden-city,' another name by which the Nagarahara district is known in Sanskrit literature. It seems as if this old form, 'Udayanapura' still survives in 'Adinapur,' which is now represented by Bala Bagh, twelve miles from Jalalabad. (Masson, Journeys into Balochistan etc. I. 180, 182). Fathabad. the town founded by Maudud to commemorate his victory, still exists, four miles south of Balabagh. (Ibid. 184; Beal, I. 91 note). In some Persian chronicles, 'Nagarahāra' is also written 'Nang-nahār' and supposed to refer to the 'nine streams' or 'torrents' which are said to issue from the Safed-koh and join the Kābul and Bārān river. 'Nang' is said to be the Pushtu word for 'Nine.' (Elphinstone, Caubul, I. 160). Raverty (N. A. 49) vehemently upholds this view, but the better opinion is that 'Nangnahār' [or 'Neknahār' or 'Nangarhār'] are all later corruptions, and that the correct form is 'Nagarahāra,' which occurs in the Ghosrāwā inscription of about \$40 A. C. which was first published by Kittoe in J. A. S. B. 1848, pp. 492-8, and has been re-edited by Kielhorn in the Ind. Ant. XVII. 1888, p. 311. Nagarahāra is mentioned in the Chinese annals of the Sung dynasty also as 'Nang-go-lo-ho,' which corresponds exactly, Stanislas Julien says, with the Sanskrit 'Nangrahāra.' (Voyages du Pélerins Bouddhistes, II. 96). Bellew derives the name from Nava vihāra, 'nine monasteries '(Races of Afghānistān, Ed. 1880, p. 64), but this seems doubtful. II. 274, l. 9.

He ['Abdu-r-Rashid] used to listen to chronicles and write history.

heart the facts relating to the life of Muhammad and the Traditions [انار] and used to recite them from memory" Elsewhere, Minhāj again says of Malika-i-Jalāli, the daughter of Sultān Ghiyāsu-d-dīn Muhammad-i-Sām that she أخار شهات نامت در حنطه دائت (29, 1 1) He uses a similar expression at 85, l. 12. Baihaqi employs the synonymous phrase افار يفتر بيار ياد دائت for "I remember having heard". (36, l. 4, 52 last line) Irādat Khān Wāzih says of the Mughal Emperor Bahādur Shāh, Shāh 'Ālam I, that he "used to relate the traditions of the Prophet, in the number of which he excelled, as well as in a knowledge of the Holy Law." (E D. VII. 552).

II 276, l 8. Suddenly, some fleet messengers arrived with the intelligence that the accursed Tughril has been killed

Raverty insists that the right reading is not مرعان, as in the printed text, but مرعان 'Murghān' means' birds,' but he interprets it as 'carrier-pigeons' He urges in support of this lection that Saladin is known to have established a pigeon-post for the conveyance of news and that a victory of the Saracens over Baldwin, Count of Tripoli, in 1179 A. C. was announced at Cairo by carrier-pigeons. (Tr. 101 and note) But مرعان is repeatedly used in at least six other places by Minhāj (172, 1 4 f. f, 245, 1. 8, 277, 1 2 f f.; 375, last line; 421, 1 13 and 423, 1 11) The synonymous عاصدان is used at 288, 1. 14, and in every one of the six passages, Raverty himself renders the word by "swift messengers". (Tr 622, 740, 793, 1082, 1217 and 1228) Baihaqi also uses the word frequently, e g مشران مسرع (3, 1. 6 f. f.), غامدان مسرع (3, last line; 275, l 1), مشران مسرع (17, last line; 299, 18; 497, 1 21, 808, 1. 16).

See also F (I. 25,1. 10). There is nothing to show that carrierpigeons were ever employed by Mahmud or any of his descendants and there is no reference to them in any of their chronicles

II. 276, l 17. Farrukhzād was proclaimed king on Saturday, the 9th of Zī-l-Kada 443 H.

The Ind. Ephem. make this Friday, 13th March 1052 A.C. The discrepancy indicates that the author is giving the Rūyyat and not the Hisābi date. The Sultān must have been proclaimed on Saturday, 14th March, if the week day is correct F. (L. 47, L. 16) says Tughril was assassinated while sitting on the throne in the Darbār held on the Naurūz-i-Sultāni, that Nūshtīgn arrived some days later and placed Farrukhzād on the throne. The Naurūz fell in that year on 3rd March 1052 A.C. (Cowasjee Patell's Chronology), just eleven days before Farrukhzād's coronation. The date given by Minhāj is thus corroborated

II 276, l 10 from foot. The country of Zāwulistān was in a state of desolation from disease and murrain

in Text, 19, L 2. See Criticisms, Vol. VIII, p. xv. Raver-

ty's rending عوارض و مونات (T.N. Tr. 102 and note) is not free from doubt. The meaning also is not quite certain. وارض و مونان does mean 'diseases' and مونان 'any deadly distemper,' or 'epidemic', not 'murrain' only as he contends. But عوارض signifies 'taxes' and موادض 'supplies,' also. May not the true reading be موادض و موانی , a collocation which occurs frequently and means "adverse circumstances and impediments or untoward events and hindrances." عوارض و موانی is used in this sense. (T. A. 298, last line). II. 277, 1.5. And on Monday, he [Ibrāhim] auspiciously ascended the throne.

Minhāj gives the week-day, but leaves out the day of the month. The omission is made good by Baihaqi who gives the precise date as Monday, 19th Safar 451 H. (Text, 467, l. 3 f.f.). The Julian correspondence of 19th Safar was Tuesday, 6th April, 1059 A.C. Raverty has a discursive note on the year of the death of Farrukhzad, in which he cites the mutually discordant statements of several later compilers. The gist of it is that Hamdulla, Fasih and Yaf'ai put his death into 450 H., while the Muntakhabu-l-Tawarikh is in favour of the year following. He refers also to a sentence from Baihagi in which Farrukhzad is said to have been alive in Zi-l-hijja 450 (Text 207, I. 9 = E. D. II. 88), and suggests or surmises that he must have died in that very month in 450—as his demise was sudden. (Tr. 102 Note). He has apparently overlooked the passage which I have cited, as well as another at Text, 350, 1. 5, from which it is clear that Farrukhzād was alive in 451 H. Minhāj gives 451 H. (276 ante). Ibnu-l-Athīr also explicitly states that Farrukhzād died in Safar 451 (Kāmil, Bulāk Edit, X. 2, 1, 3), and they are quite right. The date given in the C. H. I. (III. 34) is March 1059, which is a good shot and near the mark, but not quite in the bull's eye.

II. 277, l. 13. Ibrāhīm was born at Hirāt in the year of the conquest of Gurgān, 424 H.

Gurgan or Jurjan (the ancient Hyrcania) and Tabaristan were conquered by Mas'ud and taken from the Ziyarid Prince, Dara bin Minuchihr in 424-5 H. = 1084-5 A. C. (Gardezi, Z. A. 99; T. A. 12, l. 1; F. I. 41, last line; Khwandamir in E. D. IV. 196; Browne, L. H. P. II. 169). The capital of Gurgan, in our own times, is Astrabad.

II. 278, l. 5. He (Ibrāhīm) died in the year 492 H. at the age of sixty. Sic also in the Text (21, 1. 11) and in Raverty's Ms. and Tr. 105. But as Minhāj has just stated that the Sultān was born in 424-5 H., he must have been 67, not 60 years old at the time of his death. The exact date of his demise is given as 5th Shawwāl 492 H. (25th August 1063 A.C.) by Ḥamdulla (Tār. Guz. 404, Tr. II. 81), who is followed in the C.H.I. (III. 35). T. A. (17, 1. 2) and F. (I. 49, 1. 12) give 481 H. as well 492 H. without pronouncing any opinion on the correctness of The numismatic evidence is in favour of 492 H. (J. R. A. S. IX. 354 II. 278, l. 10. In the days of (the Khalif) Al Mustazahan 1993.

son of Muktadar.

Sic in the text (21, last line), but the father of Mustazahr was Muqtadi (Rauzatu-s-safā, Jild III, p 225, l. 7) He reigned from 468 to 487 H (Muir, Caliphate, 577) Coins struck by Ibrāhīm in the name of Mustazahi (487-512 H) are extant (J R A S IX 364, XVII 280) Muqtadir was Khalīf from 295 to 320 H

II 278, l 3 from foot Malik Ai slan Abu-l Malik ascended the throne A H 509 (A D 1115)

The printed text has اولاوک (22, 1 4 f f), which is manifestly erroneous Raverty gives the patronymic as 'Abdu-l-Mulūk in his Translation, but surely, the Sultān would not style himself 'Servant of (other) Kings' The correct 'Kunya' must be Abu l-Mulūk, 'Father of Kings,' which is found in some of the authorities he cites (T N Tr-107 Note) Mirzā Muhammad Qazvīni also states that the Kunya was Abu-l-Mulūk (J R A S 1905, p 710) It may be permissible to note that a Hindu king, Mallikārjuna of the Shilāhāra dynasty of Thāna (circa 1156 A C) assumed a somewhat similai title, Rājapitāmaha, 'Grandfather of Kings' (I. A. XII 150, B G XIII Pt 11, p 426, J B B R A S XV 278-9) Arslān's grandfather Ibrāhīm styles himself 'Onequeror of Kings', on one of his dirhams (Cat of Oriental Coins in the British Museum, II No 558, 171) 'Abdu-l-Malik' given in the C H I. III. 35 is a conjecture devoid of any authority

The exact date of Arslan's accession is not given by any of the chroniclers, but it can be recovered from a contemporary Qasida of Mas'ud-1-S'ad-1-Salman He gives it as Wednesday, 6th Shawwal 509 A H = 23rd February 1116 A C (Mirzi Muhammad Qazvini in J R A S 1905, p 705) According to the Ind Eph, Wednesday, 23rd February 1116 A C, was 7th Shawwal, but the difference of a day is not unusual and 6th must be the Hilali or Ruyyat date, and 7th the Hisabi or Book-rule date

The date of this Sultān's demise given by Minhāj is 511, but 'Awfi records the date of his first defeat as Wednesday, 14th Shawwāl, 511 AH = 8th February 1118 AC (199 ante) and Ibnu l-Āthīr states that he was expelled from Ghazna again and killed in Jamādi'u-l-Akhir, 512 H (Bulāk Edit X 179, 15) Minhāj has left out Kamālu-d-daula Shīrzād, who was the immediate successor of his father 'Alāu-d-daula Mas'ūd II He was deposed or murdered a few months after accession in 509 H 1116 A 'C (Khwāndamīr in E D IV 206 and Note 6, B I 38, Tr 55, F I 49, 1 22) The contemporary poet Mas'ūd-i-S'ad-i-Salmān also styles him Shirzād Shāh (Ibid)

II. 280, l 2 He (Bahlim) with his ten sons fell on the day of battle into a quagmire

Dowson says the Text here has some unintelligible words. The words are בנרמים לים (24, 1 11) The right reading seems to be בנמים לים (11). The last word פנים [recte פנים Būrīni] is a conjectural or variant reading which the copyist had found transcribed in the margin and inserted or

transferred by error into the text. U. or U. or U. means 'a ditch, marsh, a place where water stagnates'. (Richardson's Dict.). F. (I. 50, l. 5) substitutes the synonymous in his paraphrase of the passage. Abu-l-Fazl employs the latter word in the Akbarnāma (Text. I, 277) and Mr. Beveridge says that it means 'morass, collection of water, bog, quagmire'. (Tr. I, Errata, p. xxviii).

II. 281, l. 6 from foot. They put Khusrū Malik to death in the year 598
A.H.

Sic in the B. I. Text, 27, 1.3, but Minhāj himself puts the event into 587 H. at p. 295, and also at p. 300 post (Text, 74, 1.8 and 118, 1.4), which must be correct. The C. H. I. (III. 37) gives 1192 A. C. (588 H). In the section on the Khwārizmshāhis also, Minhāj declares that Sultūn Shāh was defeated by the Ghori Sultans after the contest between them had gone on for about a year, in 587 H. (Tr. Raverty, 248-9). Sultān Shāh died soon after his discomfiture in 588 H. (Ibid).

II. 282, l. 7. When the founder of the house of 'Abbās, Abu Muslim .

Marwazi revolted.

Muslim was not the 'founder' of the house of 'Abbas, but only a purchased slave of the family, who became their most capable agent, emissary, missionary or propagandist. (Muir, Caliphate, 422). The Founder or First Khalīf of the 'Abbāside dynasty was Abu-l-'Abbās Saffāḥ. Abu Muslim was a sort of king-maker, but not king himself. He was afterwards put to death by the ungrateful Khalīf.

II. 283, l. 16. Owing to the inaccessibility of the mountains of Rāsīāt, which are in Ghor.

tops of mountains' occurs in 'Utbi's chapter on Mahmūd's invasion of Ghor. (Delhi Lith. 306, l. 8). Yazdi uses راسات جبال and رواسخ جبال and رواسخ جبال in his description of the mountains which stand as a natural wall in defence of Kashmīr. (Zafarnīma, II. 180, l. 4 and 178, l. 4). جبال راسات is again used by Minhāj himself (Text 332, l. 2) for 'precipitous mountains,', 'mountain precipices' or 'mountain-peaks.'

II. 285, l. 2. And the fifth mountain is Faj Hanisār.

See Criticisms in Vol. VIII p. xvii and Corrections Ibid. xxiv. The variant 'Khaisār' is, most probably, right. Richardson says zi means 'a broad way, especially between two mountains, a pass.' Baihaqi also uses i or i for a 'mountain pass.' (350, 1.3 f. f.). Raverty (Tr. 319 note) speaks of Khaisār as a well-known place, without stating where it is to be found. But it appears from Istakhri (Ed. Goeje, 285, 1.10) that it was two stages distant from Herāt and about nine from Khasht, which was just on the frontier of Ghor. Baihaqi's 'Bazghurak (127 ante) seems to be really is or if the soft Ghūrak'.

II. 286, l. 9. (6) Amir 'Abbās bin Shis bin Muhammad bin Suri.

The early history of Ghor is exceedingly obscure. Baihaqi says Ghor was invaded twice in Mahmūd's reign, viz in 401 H and again in 411 H 'Unsuri speaks in one of his Qaqīdas of "the capture of the son of Sūri and the conquest of Ghor". (Dīvān, Lucknow Lith. p. 58). Abul-Hasan Khalaf and Shirwān were the chiefs of Ghor in 411 H. and 422 H. according to Baihaqi (Text, 128, ll. 8, 14 and 274, l. 6 = 111 ante). When Sultan Mas'ūd passed through Ghor in his flight after the defeat at Dandānqān in 431 H, the country was ruled by Abul-Abbās, the son of Abu-l-Hasan Khalaf (Text, 795, l. 10), who may be the Amīr 'Abbās (No. 6) of Minhāj. Mas'ūd-i-S'ad-i-Salmān also states that when Sultān Ibrāhīm Ghaznavi invaded Ghor, the ruler was Muhammad 1-'Abbās. (Trans in E. D. IV. 519) There can be little doubt that he is No 7 of Minhāj. These corroborations from contemporary sources indicate that Minhāj is not writing without book.

II. 286, l. 12 from foot Revenge for the death of Sultan Sûri, King of the Jabal.

Insert 'and the 'between 'Suri 'and 'King'. cf. the BI. Text (54, 1. 13) See also 288 and 291 post Sultan Suri had the laqab Saifu-d-din. The name of the Maliku-l-Jibāl was Qutbu-d-din They were brothers, Qutbu-d-din being the elder. 'Jibāl' is here used as the specific designation of the hilly country on the northern parts of Ghor and Bāmiān which lies to the south-east of Herāt The King of the Jibāl was poisoned, Sultān Sūri was captured and gibbeted on the One-arched bridge of Ghazni.

II. 289, last line Some emissaries of the Mulahidatu-l-Maut came to him

Correctly Malahidat-i-Alamut, the Heretics of Alamut Mulahidatu-l Maut is nonsensical or misleading. They were emissaries of the Malahida, also called Qarāmitā, Bātınıya, Ism'ailı or Assassıns, who had their headquarters in the stronghold of Alamut, 20 miles from Qazvin It had been captured by Hasan-i-Sabah in H 483 By an extraordinary coincidence, this date represents the Abjad value of the letters ... Elliot (574 infra) and others say that 'Alamut' signifies 'Eagle's Nest,' or 'Eagle's Find,' while Browne thinks that Ibnu-l-Athir is right in deriving it from Aluh, an old Persian word for 'eagle' and am'ut, ie 'Amukht', 'taught'. The name thus signifies 'Eagle's Teaching'. Houtum-Schindler, however, challenges this opinion and maintains that 'Eagle's Nest' is "more natural and probable," and has the support of the best Persian Dictionaries, e. g the Burhān-ī-Qāti'a, the Farhang-i-Rashīdi and the Shāmsu-l-Lughāt He states that one of the Dā'is, " reached the summit of a rock while in pursuit of game, and finding the position favourable, built a castle upon it and called it 'The Eagle's Nest', because eagles build their nests on high places" (J R. A. S 1909, pp 162-164, see also Ibid. 1907, p 460) The fortress was destroyed by Hūlāgū in 1256 A. C. (L. H. P II. 203-4, 311 and 458).

11. 290, l. 2. He paid great honour to these heretics, inviting them into

II. 293, last line.

all parts of the kingdom.

.63, أ. 63 ; ايشان را اعزاز كرد ويهرجا از مواضع غور در يسر دعوت كردند

It was not 'Alāu-d-dīn who invited the Ism'āīlis into all parts of his kingdom. What Minhāj says is that the emissaries of the sect secretly [عريا] invited the residents of all the villages in Ghor to join their creed. They carried on an insidious propaganda with a view to convert or pervert the Ghorians and 'Alāu-d-dīn was guilty, in so far that he permitted and encouraged them to make proselytes. The phrase عن العربية used again in the T. N. at 65, 188, 189, 289 and 329, in the same sense.

II. 291, 1. 2 from foot. The horsemen of Bahrām Shāhovertook them in the neighbourhood of Sang-i-Surākh.

Raverty states that Sang-i-Sūrākh signifies 'Perforated Rock or Stone' and that there are three or four places bearing this name. He locates this Sang-i-Sūrākh near the Helmand river, north-north-west of Ghazni, on the route from that city and from Kābul also to Ghor. (Tr. 441 note). A Surkh-Sang Pass, N. W. of Ghazni, is shown in Constable, 22 C c and 24 B a.

II. 292, 1. 3. The horsemen captured them, bound them hand and foot, and conducted them to Ghazni.

: 113, l. 3 from foot ; اورا بعهد و دست راست بگرفتند و بدست آورده

"They seized him and brought him into their power by giving promises and [confirming them] by pledges with the right hand." (See also my note on Vol. II, 315, 1.8 infra).

II. 293, 1. 7. He assigned to him the countries of Kasr-i-Kajūrān and Istiya.

There is a place called Istiya in the Kurram Valley, now the Kurram Agency of the North-West Frontier Province. Kurram corresponds to the Upper Bangāsh of Akbar's historians, while Kohāt is their Lower Bangāsh. (I. G. XVI. 49). This Istiya lies five Kuroh or Kos from the Peiwār Kotal, which is about ninety miles south of Kābul. (N. A. 77, 80). Qaṣr-i-Kajūrān may be what is now called Kajūri Kach, which is about fifteen miles from the western boundary of Bannu district. (I. G. XI, 202; I. G. Atlas, 33, A 3). But Raverty says that this Istiya was in Ghor and a mountain between Ghazni and Herāt. (T. N. Tr. 339 Note).

II. 293, last line. It has been written by some that these Sankarāniāns have been called martyrs, in agreement with the declaration of the Kurān but as they etc.

چنان تقریر کرده اند که آکثر طائفه سنکرانیان ظامر آیت ِ قران خوان بوده اند که شهادت .7. 116, 1. بافتند

"Some people have argued that as the great majority of these Sankarāniāns were outwardly Musalmāns (lit. reciters of the Qurān) and were put to death, they are entitled to be called martyrs." Minhāj denies their claim to any such honour. They had, he says, rebelled against their

lawful sovereign and had been not unjustly put to death, although the sentence had been passed, not in accordance with the religious law, (شرع), but with "political necessity" مسرورت سياست ملكي كشه شدند It was an act of executive or administrative justice

Minhāj is giving here a fativā—a legal opinion pronounced obiter, as Chief Qāzi of the Empire. He, his father and his grandfather were all jurists by profession and the Law was, so to say, in his blood. These Sankarāniāns were 'recitors of the Qurān', i.e. men who professed Islam. Now no Muslim can, according to the Shari'at, be put to death except for one of three offences, Murder, Blasphemy and Apostasy. These men were rebels, but rebelhon did not come within the purview of the Canonical Law, and was not punishable under it with death. Their execution could be justified, however, on grounds of political exigency or necessity—the necessity of maintaining law and order in the State on the principle, Salus populi suprema lex

II. 294, l 6 The Rai of Nahrwala Bhim-deo was a minor

All the Musalman historians speak of Bhīma as the King of Gujarāt who defeated the Ghori Sultīn. But the local chroniclers record the event in the reign of his predecessor, Mūlarāja and in many Chālukya inscriptions also, Mūlarāja is praised as "the conqueror of the difficult-to-be-conquered King of Garjana", i e Ghazna (Ind Ant VI. 194, 198, 200, 201) He is known as Bāla Mūlarāja, 'Mūlarāja the Boy', and is said to have "dispersed the Turushka army even in childhood', in two of the Jaina chronicles quoted in the B. G Pt I. 195 The mistake may have originated in the fact that Mūlarāja's reign was a very short one and he was succeeded by his brother Bhīma II, who was also very young at the time and had a long reign of 62 years (1179-1241 A C).

The site of the battle is said, in the Hindu accounts, to have been at Gādarāra Ghatta—and the Sultūn's defeat is stated there to have been partly due to a sudden fall of rain (Merutunga, Tr Tawney, 154, B G I Pt. 1. 195, Epig Ind IX 77) It has been recently suggested by two scholars acquainted with the locality, that Gādarāra must be the village called Kāyadrā in Sirohi State which lies at the foot of Mount Abu. (D R Bhāndārkar, Epig Ind XI, 72, R R Haldar in Ind. Ant LVI, (1927), p 47 note)

II. 295, foot note 2 The text has Tarāin, but Firishta gives the name as Nārāin and says it was afterwards called Tirauri

There is no doubt that the battlefield was somewhere near what is now called Tirauri, which lies about ten miles north-west of Karnāl and 14 south east of Thānesar, but no village actually called Tarām or Nārām can be now traced in the vicinity. It is true that Cunningham speaks of "Nārām, lying on the banks of the Rākshi river, four miles south-west of Tirauri and ten miles north of Karnāl", but the existence of any such village is denied by Raverty (Tr 459 Note) and others

In the Official Gazetteer of the Karnāl district, (1918), p. 10, the correct name is given by the local expert who compiled it, as Nardīna, a village in the Nai Wafi in Nardak, twelve miles south of Thānesar and three miles from Tirauri. Raverty's contention that the real name of the village was 'Tarāin' (Tr.) thus lacks confirmation and Cunningham's 'Nārāin' must be an error for 'Nardina'.

Tirauri or Talāvari is apparently, a modern name signifying 'a small, lake, tank or pond.' Its Muhammadan alias 'Azīmbābād, was given because Aurangzeb's son 'Azīm was born here. There is a great 'Ribāṭ' or fortified Sarāi in the place. (I. G. XXIV. 390). The vernacular Tāl or Talāv, Pers. IV, means 'a pond or lake.' 'Talāvdi' or 'Tarāvadi' is its diminutive. The phonetic resemblance between 'Tarāin' and 'Tirauri' seems fortuitous.

There is a strange lack of concord among the authorities in regard to the chronology of the reign of Mu'izzu-d-dîn Muḥammad-i-Sām, and it was the subject of a somewhat acrimonious controversy between Raverty and Blochmann in the J. A. S. B. The two oldest authorities, Minhāj and Ḥasan Nizāmi, frequently give discrepant dates. Nizāmu-d-dīn Almad, Firishta and Budāuni merely copy the older authors accurately or inaccurately. It may be therefore worth while to cite the dates given by a third contemporary source—the Tārīkh-i-Fakhru-d-dīn Mubārak-shāh—which has seen the light and has been edited very recently by Sir E. Denison Ross.

These dates are as follows:-

Defeat of Rai Kaula Pithaura.	588 H.	p. 22.
Qutbu-d-din's conquest of Kuhrām.	588 H.	p. 22.
Conquest of Delhi and Ranthambhor.	588 H.	pp. 22-3.
Defeat of Rai Jitchand.	590 H.	р. 23.
Conquest of Ajmer.	591 H.	p. 23.
Conquest of Thankir.	592 H.	p. 23.
Conquest of Nahrwäla.	593 H.	p. 23.
Conquest of Būdāun.	594 H.	p. 24.
Conquest of Chantarwal [Chandawar],		F. 22
Qanauj and Sarwa [Sarju-pār].	595 H.	Ibid.
Conquest of Mālwa.	596 H.	21
Conquest of Gwaliar.	597 H.	17
Conquest of Kālanjar.	599 H.	99
Conquest of بدور	600 H.	p. 25.
Qutbu-d-din goes to attend upon the		_
Sultān at Parshāwar.	601 H.	Ibid.

This is misleading. The persons into whose hands he fell were not the 'infidels' or Khokhars who were defeated in the battle described above. The assassins are explicitly said by Minhāj to have been فدائى ملاحد. (124, 1.3) the fanatical desperadoes of the Malahidā, i.e. Qarāmata or Ism'āili

sect,—the Malahida of Alāmūt, as they are called by Minhāj, on p 289 ante q v Note) Hājji Dabīr states that the assassins were Ism'āili Malahida ملحد من الاساعلية (Z W. 682, 1 16) and so also Hasan Nizāmi II. 299, l 16 He was not comely in appearance His little finger was broken from his hand, and he was therefore called Arbah. 'maimed in the hand.'

اما بطاعر حالی مداشت و انگشت خسر او ار دست شکستگی داشت مدآن سب اورا ایسك شل 138.14 f f کمتندی

The meaning of this passage has been the theme of acute controversy Raverty contends that 'Ibak' in Turki means 'finger' and 'Shil' or 'Shal' signifies 'soft or paralysed' in Persian and that the real name of Qutbu-ddin was not and could not have been Ibak, but Ibak-1-Shal, signifying "Powerless-fingered" (TN Tr 513-14 and Notes) On the other hand, Thomas (C P K D 32 note) and Blochmann (JASB 1875, XLIV, pp 277-8) agree in holding that 'Ibak' or 'Aibak' by itself was the original Turki name (derived probably, from the Turki Az, 'moon' and 'Bak', 'Lord'), and that 'Shal' or 'Shil' was a nickname signifying 'withered, maimed, disjointed' They maintain that 'Toak' is stated in the Turki dictionaries, to mean, not 'finger', but 'a crest or a comb' and that in the Shamsu-l-Lughat, 'Ibak' is given as the synonym of مبر ماه 'Lord of the Moon.' In other words, 'Shal' is neither the explanation of 'Aibak', nor the name of the tribe to which he belonged, but his nickname The TA (20, 19), F (I 60 last line) and B (I 54, Tr 1 77), all state that "he was called 'Aibak' because his little finger was broken," but this seems to be founded on some misunderstanding or mutilation in the text of Minhaj which was available to Nizāmu-d-dīn Ahmad F and B have only copied the sentence word for word from the T A

The name 'Ibak' or 'Aībak' was borne by several other Turki slaves at this time One of them who was purchased at the same time as Iltutmish had the sobriquet of Tamghāj The name of his native district or province was appended to his name just as 'Shil' or 'Shal' was suffixed to that of Qutbu-d-dīn (322 infra) A second namesake was, with a view to distinction or differentiation, styled Bahtū (ib., 334), a third Sanjān or Khitāi (ib., 354, 356), a fourth Bārbak or Kishli Khān (ib., 359, 368), a fifth Khwāja (T N. Text 213, 1 5), and a sixth was called Yaghāntat. (Text, 238, 1 6 f f) Still another person named Ibak is mentioned by Minhāj elsewhere, as the chief Inkstand-bearer of the ill-starred Khalīf Must'asım (Text, 425, 1 2 f.f.) Another Ibak Hājib is known to have been commander of the army of Amir Nūh Sāmāni of Bukhārā (Tān īkh-1-Yamīni, Tr Reynolds, 121 and note)

It is not possible that all these 'Aībaks' were so called, because they were 'moon-lords' or had 'broken-fingers' or bore some resemblance to the 'Combs of cocks' Ībak was a name just like any other, like Chingīz, Timūr, Aītigīn, Aītamar or John, James, Paul or Peter It may have possessed some sense or meaning or raison d'étie at first, but it had, in

course of time, been given to all sorts of individuals so frequently and so very much at random, that it had, by this time, lost all significance or meaning. It thus bore no relation at all to the qualities, physical, mental or moral, or the circumstances, general or particular, of the person designated by it.

II. 300, l. 2 from foot. On Tuesday, the 18th of the month of Zi-l-Ka'ada [602 H.], he [Qutbu-d-dīn] mounted the throne.

This date is repeated in the T. A. (20, l. 4 f. f.) and F. (I. 63, l. 7). The Julian correspondence of 18th Zī-l-q'ad (Hisābi) was Monday, 26th June, 1206. This 18th must be therefore the Ruyyat date. Fakhru-d-dīn Mubārakshāh states that Qutbu-d-dīn arrived at Lāhore on the 11th of Zī-l-q'ad, 602 H. (Ed. Ross, p. 31). The coronation must have taken place exactly a week later.

II. 304, l. 9. On Tuesday, the 27th of Jumada-l-awwal, the fort (of Ucch) was taken.

The dates which Minhāj gives for the siege and capture of Uchch are inextricably confused and self-contradictory. Here, the siege is said to have commenced on the 1st of Rab'ī I, 624 H., and to have terminated after 2 months and 27 days on Tuesday, the 27th of Jumādi I, 624. [Raverty also has 27th, but Saturday; Tr. 544]. Then on pp. 325-6 infra. Minhāj himself states that the fortress of Uchch capitulated on Tuesday, the 29th of Jumādī II, 625 H., and that Qubācha drowned himself in the same month. But in Raverty's Mss., this date is Tuesday, 27th or 28th Jumādī I, 625 H. (Tr. 613). Again, Minhāj avers here that the news of the fall of Bhakkar arrived at Uchch on the 22nd of Jumādī II, 624 H., and that Qubācha's suicide took place about the same time. But Muḥammad 'Awfi, who was himself besieged in the fort along with Qubācha and was, as Elliot observes, 'well acquainted with all the details' (155 ante), gives the date of Qu'bācha's death as the night of Thursday, 19th Jumādī II, 625 H. (202 ante).

Now 19th Jumādi II, 625 H., was Friday, 26th May, 1228 A. C., 27th Jumādi II, 625, Saturday, 3rd June, 1228, and 29th Jumādi I, 625 H., was Saturday, 6th May, 1228. The conclusion would appear to be that the death of Qubācha took place on 19th Jumādi II, 625 H., and that Uchch had fallen some days previously on Saturday, 29th Jumādi I, 625 H.

624 H. is irreconcilable with another statement made by Minhār regarding his own life-history. He tells us that he arrived at Uchcharusday, 26th Jumādi I, 624 H. (Friday, 14th May, 1227) and was appahead of the Firūzi College there in Zī-l-hijja of that year. (Textila 3=303 ante). He also states that he paid his respects to Iltura Wednesday, 1st Rab'ī I, 625 H.=Wednesday, 9th February.

with 27th Jumadi I, 625 It was a Thursday.

11 305, l 4 He obtained Sahlat and Sahli in Jaghir.

Variants, Salmat, Sahlast Raverty's Mss read 'Bhagwat and Bhuili' They are, he says, two parganas situated between the Ganges and the Karamnāsa—the latter river being the boundary of the Bihār territory. (T. N. Tr. 550 and note) Blochmann accepted the identification and it may be taken as satisfactory Bhuīli is mentioned in the Āīn as a pargana in Sarkār Chunāi (Tr II 165) Elliot says, Bhagwat was also known as Hansa (Races, II. 119). Both parganas are situated to the south of Banāras and east of Chunār. (Blochmann, J. A. S. B. 1875, p. 281 and note) Thornton says 'Bhoelee' is 10 miles east of Chunār and 15 south of Banāras, Lat 25°-6' N., Long 83-3 Bhagwat, Bhuili, Ahraura, Chunār and Kariāt Sikhar are listed in the I.G. as the five parganas of the present Chunār Tahsīl (X. 332)

II. 305, l 2 from foot Districts of Munn (Monghyr) and Behar.

no Text, 147, 1 6. The gloss is wrong Munīr (or Maner) is not the same as Monghyr Maner is about twenty miles west of Patna Monghyr is about one hundred south-east of it (Secley, Road Book of India, p 3) The town of Bihār, Lat 25°-11' N, Long 85°-31' E is byrail 18 miles to the south of Bakhtiārpur, which is 28 miles south of Patna

II. 308, l. 3. In that country (Bengal), the current money is Kaudas (Kauris) instead of chitals

In all the passages in which these coins are mentioned by Minhaj, the name is spelt in the BI Text as جتل Chital (149, 12f f., 168, 12f f., 197, 1 2, 237, 1 11, 247, 1 6, 295, 1 3, 452, 1 4 f f) Barani's spelling also is نجل (B I Text 116, 1; 118, 1. 2 f f , 195, 1 2 f f; 204, 1 4 f. f, 212, 1 13), though Raverty and others call them 'Jitals, and that spelling also is found in Mss The numismatists have not thrown any light on the derivation of the word though some think that it may be Turki be permissible to suggest a connection with the picture of the 'Bull' and 'Horseman,' which is found on the Dehlivals, another name by which these Chitals are called, eg by Hasan Nizāmi (242 ante) The word is perhaps the Sanskrit Chitrala, "variegated, painted, pictured." In Hindi, Chital is used for 'the spotted deer,' and also for 'a species of large snake which has spots' The reptile is described in the Tuzuk-1-Jahangiri as about 21 Mahi gaz (about seven feet) in length, twelve inches in girth and large enough to swallow a hare (Text, 369-370) The bangles made of conch shells which are coloured and engraved with all sorts of designs,' are also known by the same name. The Chital or chuda was the mark of a married woman and was broken only when the husband died. The leopard [Hind Cheeta, Sanskrit 'Chitraka'] is so called because of the spots with which he is marked

II 308, l 6 from foot Most of the Brahmans and many chiefs (Sāhān) went away to the country of Sanknāt.

Barani uses Sāhān wa Sari āfān (546, 1 6) and Multanian wa

Sāhān (120, 1, 7). The Hindi word really means 'wealthy merchants, respectable men of the commercial classes.' 'Sīh' is generally derived from 'Sīhu,' Sunskrit 'Sīdhu,' 'pure, honest, of immaculate integrity.' The word is also found in Ibn Bayūja who explains that the great merchants of Daulatībād who dealt mostly in pearls were called Sāh. Defrémery traces it to the Sanskrit Sārthavāha, Pāli Sātthavāha, which is pronounced Sāttvah' or Sātthah! (IV. 49), but the Gujarāti and Hindi dictionaries give the first of those etymologies.

Dowson notes that 'Sanknāt' is also written 'Sankāt' and 'Saknāt' and he asks if it is not 'Jagunnāth'. But Minhāj states a few lines lower down, that Lukhmaniya himself fled to Sanknāt and Bang "and that his sons are to this day rulers in the territory of Bang." (Text, 151, l. 14; 309 infra). Now Vanga or 'Banga' is the specific name of Eastern Bengal, and we possess epigraphic evidence of Lukshmanasena's descendants having ruled for at least three generations at Vikrampur near Sonārgaon in Dācca. Sanknāt may be a mistake for Sonārgaon [or Songāon]. A still nearer phonetic approach would be Sugāon (Dāca), and it is possible that Minhāj who knew little or nothing of Bengal geography has confused the two names. Hoogly district in which Satgāon lay was under Hindu rule for long after the Muhammadan conquest of Lakhnauti.

H. 310, l. 1. The one is called Kuch, the second Mich and the third Tiharu. They all have Turki features.

Mr. Crooke tells as that "the Tharas have still their headquarters in the Himalayan Tarai and colonies in Gorakhpur division and Northern Oude. The Meches resumble them in habits and features and inhabit that portion of the Tarai which separates the plains of Bengal from the hills of Sikkim......The Tharas still retain in their features strong marks of a Chinese or Mongol origin, although these marks are somewhat softened......The most probable opinion is that the Tharas are originally a Dravidian race, who by alliance with the Nepalese and other hill tribes, have acquired some degree of the Mongolian physiognomy." (T. C. IV. 389-5). According to the I. G. (VI. 44) also, they are of Indo-Chinese origin and of a marked Mongolian type. The author of the "Alamgirnāma says of the Mee'i that "they are to be found in Küch Behär, are very ugly and look like the Qalmāqs [Calmucks], having a steel-blue complexion." (B. I. Text, 692).

II. 310, 1.8. He led him to a place where there was a city called Mardhan-Kot.

Westmacott suggested (J. A. S. B. 1875, XLIV. p. 188) that this is Bordhankoti in Dinājpur, about 35 miles south of Rangpur town and 20 miles due north of Bogra. Lat. 25°-8′. Long. 89°-25′ E. He thought that the original Sanskrit form was Varddhana-Kūti and sought to connect that name with Paundra Varddhana or Pundra-desha, which comprised Dinājpur, Rangpur and Kūch-Bihār. Westmacott's suffering was accepted by Blochmann (J.A.S.B. 1875, p. 282) and it has

by the writer of the article on the subject in the I G More recently, Mr E H. Stapleton announced, in a paper read before the Royal Asiatic Society, that Westmacott's identification has been confirmed by subsequent research (Report in the Times of India of 24th April, 1934)

In Dowson's translation, this city is said to have been built by Gurshāsp, at the time when he returned from China and came to Kāmrūd Raverty says that some of his Mss. read 'Garshāsib' and others 'Gushtāsib' and he contends that 'Gushtāsib' only can be right, because the latter's son, Isfandyār, is said, in Irānian tradition, to have conquered Hind and also invaded China (561 Note) But the T A (24,14), B (I.58=Tr I 84), and F. (II 294, 16) agree in reading, 'Gershāsp' There is no mention in Firdausi's Shāhnāma of any invasion of India or China, either by Gushtāsp or by Gershāsp But the reference here is not to the great Iranian Epic, but to the "Gershāsp Nāma" of the younger Asadi (son or nephew of Asadi, the teacher of Firdausi), in which there is a lengthy account of the hero's deeds of dorring on Hind and Chin (Rehatsek's Cat M. F. L 164, Mohl, Le Livre des Rois Repr 1876, I. Preface. lxiii-lxix, Rieu, B.M. Cat IV. 127, 133, 137, Ethe, I O Cat 558)

M. Clement Huart has recently edited a portion of this romance and Gujarāti translations of this Epopéo, as well as the Barzo Nāma, Farāmarz Nāma, Jahāngīr Nāma etc have been printed The 'Gershāspnāma' is cited as an authority in the Mujmalu-t-Tawārīkh (E. D I 102) and also by Mīrkhwānd. (Tr Shea, 118) Abu-l-Fazl says it "narrates his invasion of India" and the exploits he performed there (Aīn, Tr III, 328) Gershāsp is the 'Keresāspa' of the Avesta (Yasht XIX 38-44)

II 310, l. 10 Before the town, there runs a stream which is exceedingly large. It is called Bangamati

The river flowing in front of Burdhankot, which is here called Bangamati and supposed by Dowson to be the Brahmaputra, is believed by others to be the Karatoya, "which formed, for long, the boundary of the Muhammadan kingdom of Lakhnauti and Kāmarūpa, Koch Bihār and Koch Hājo. The Karatoya was probably connected at the time with the Tīstā, which then flowed west of the Karatoya, joined the Atrāi and fell into the main branch of the Ganges, the Padmī' (Blochmann in JASB 1875, pp. 282-4) [Sir] Edward Gait (JASBLXII 1893, p. 280 note) takes the same view and he is sure that Muhammad-i-Bakhtyār did not cross the Brahmaputra at all, either near Gauhāti or elsewhere or that he ever entered Āssām He thinks that Muhammad merely marched northwards along the Karatoya (See also his History of Āssām, p. 34)

On the other hand, Raverty contends that the river must be the Tista It seems scarcely worth while to dispute about the matter, as the changes in the courses of these rivers preclude the possibility of determining the channels in which they actually flowed in the thirteenth century. The uncertainty which exists every where in India in regard to the popular nomenclature of rivers also aggravates the difficulty. The

Karatoya is, in parts of its course, even now, called the Burhi or Old Tistā. It is also certain that at the time of Major Rennell's Survey, i. e. about 1780, the main stream of the Tistā flowed south, down the bed of the Karatoya (instead of south-east, as it does at present), and joining the Atrāi, fell into the Ganges. But in 1787, it forsook this old channel and cut a new one, by which it found its capricious way to the Brahmaputra. Early in the 19th century, it again altered this course for a more direct one eastwards. (I. G. XXIII. 404). Most modern experts are also agreed that the Bangamati of Minhāj cannot be the Brahmaputra, though the statement about its having been "three times greater than the Ganges" can apply only to that great river.

The site of the bridge also is quite uncertain. Blochmann thought that it was somewhere near Dorzheling, the modern Darjeeling, for the not very convincing reason that, at the present day, the boundary separating the Meches from the hill-tribes is about 12 miles south of Darjeeling. Dalton (J. A. S. B. 1851, XX. p. 291) suggested that the bridge was the one still existing at Sil Hako near Gauhāti and Ranking (B. Tr. I. 84 note) was inclined to favour that location, but Raverty (T. N. Tr. 563-5) has shown this hypothesis to be untenable in an elaborate note. He does not, however, make any attempt to determine its situation himself.

The fact is that the details mentioned by Minhāj are so scanty as well as vague, that it is extremely hazardous to make any positive statements in regard to the route followed by the invader or the distance to which he penetrated. Minhāj, besides, had little or no knowledge of the geography of the country and he has merely repeated the random gossip and hearsay reports which he picked up at Lakhnauti, during his sojourn in that town, forty years after the catastrophe. Mr. Vincent Smith has suggested that Muḥammad-i-Bakhtyār marched through the modern districts of Bogra and Jalpaiguri and crossed the Karatoya, although he was unable to proceed beyond a certain point to the north of Darjeeling (O. H. I. 224), but he admits that this is only a conjecture.

II. 310, last line. One night in the year 641 (1243 A. C.), he halted at a place between Deokot and Bangawan.

There is a good deal of confusion here. The person who halted was the author Minhāj, not Muḥammad-i-Bakhtyār, as the above rendering makes it out. (See Criticisms in Vol. VIII. p. xviii and Corrections. *Ib.* p. xxv).

Deokot or Devikot is now in the Bālurghāt sub-division of Dinājpur district in Lat. 25°-11′ N., Long. 88°-31′ E., near the ruined fort of Damdama, on the left bank of the Purnabhabā, south of Dinājpur town. It is about seventy-five miles north-east of Gaur and lies close to Gangārāmpur, where one of the oldest Muhammadan inscriptions in Bengal (that of Kaikāūs Shāh, dated in 1297 A. C.) has been found. (Blochmann in J. A. S. B. 1873, XLII. 211; Thomas, C. P. K. D. 149). Deokot contains the shrine of 'Atāulla, who is said to have been the spiritual guide of Muhammad-i-Bakhtyār and an inscription in an

old ruined mosque in the town is dated, in 1293 A, C, (Blochmann, J. A. S B 1872, p. 102; Arch. Survey of India Reports, XV, 95-104; I G. XI, 275). Reverty reads the second name as 'Bekānwah' (T. N. Tr 565), but Blochmann says that 'Bangawān' is the name of a well-known place near Deokot. The local tradition is that Deokot was the citadel of Bānnagar, the fortress of an Asura named Bān Rājā (I. G. XI 275) and Blochmann is most probably right in accepting 'Bangāwan' or 'Bangāon' (village of Bān) as the right reading.

II. 311, l, 4 from foot. The inhabitants of it are Brahmans and NunisThey profess the Buddhist religion.

Variants. ونان or ونان. Raverty also leaves the word 'Nuni' untranslated, but Quatremère has shown that the correct reading is 'Tūinān' and that it is the Mongol name for 'Buddhist priests' (Histoire des Mongols de la Perse, p. 198 note) Juwami, the author of the Tarikh-r-Jehān Kushā, states that Christians were called by the Mongols 'Arcouns' and; Buddhist monks 'Tournes.' Rubruguis states that 'Tourn' is the Mongol word for Buddhist ecclesiastics (Yule, Cathay, 1st Edition, I 241 and 83 notes see also Tārīkh-1-Rashīdi, Tr. Ney Elias and Ross, 290 note. D'Ohsson, Hist. des Mongols, II 264) Steingass also tells us that 'Tūīn' means 'Buddhist priest, a Liama.' It is said of these 'Nunis' that they "profess the Din-1-Tarsat," and Raverty renders the latter phrase in his text, as "the pagan-religion", but he suggests, at the same time in a note that the reference must be to Christianity or Manichaeism. (Tr. 567 note). Quatremère, however, is right in understanding it as the "tenets of the Lāmās" Juwaini explicitly declares that "the idolators (ت برستان) called 'Touins' pretend that in the times anterior to the advent of Islam in Mongolistan, they could converse with the idols, but that since that time they (the idols) had been annoyed and remained dumb "

و در رعم حاعت منرویان مت برستان که ملعت ایشان توب خواسد آست که بیش ار امامت مسلمان با ایشان خشم (I 10, 1 6). This shows that the Din-i-Tarsar was identical with 'the religion of the Tūins or Lāmās' Elsewhere, Minhāj says that the 'Nūīns' are رسان ست برست or رخاد بت برستان خس or رسان ست برست (383, 1. 14, 402, 17) See also my Note on the meaning of Tarsa, II. 163, 1. 3 ante II. 315, 18. 'Ali Mardān contrived to ingratiate himself with the Kotvāl.

by some device, got the Kotwal to pledge his right hand, te. to enter into some sort of compact or engagement with himself (and promise him safety). The same phrase is used again 16. See also my note on 357, last line post cocurs at Text, 224, 1 5 f. (See also 223, 1 9 and 264, 1 12)

II. 315, l'10 from foot. Quarrels afterwards broke out among these chiefs in the neighbourhood of Makida and Mantus.

'Maksīda' and 'Santūs' in Hājji Dābīr. (Z. W. 959, l. 8). The correct forms are 'Masīdhā and Santosh'. These two places lie in adjacent parganas south-east of Deokot in Dinājpur. Santosh, now called Mahiganj, is on the eastern bank of the Atrāi river in Thāna Potnitala of Dinājpur district. Raverty's identification of Makīda [Masīdha] with Maqsūdābād (Tr. 576 Note) is quite untenable, as the latter toponym is not older than the 16th century. In Hunter's Statistical Account of Bengal, Debikot (Deokot) is registered as Pargana No. 28, Mosidali as Pargana No. 58, and Santosh as Pargana No. 68 of Dinājpur district. (Blochmann in J. A. S. B. 1875, pp. 284-5 and 290).

II. 317, l. 16. He had with him some travellers' bread.

in it is a some such condiment (savoury, relish, kitchen or seasoning), as is usually carried on a journey." S'adi writes in the Būstān (Chap. VI, Story 8th), "One had no other condiment than an onion." Barani also says of the ascetic Sīdi Maulā, that while he gave sumptuous feasts to all those who came to his monastery, his own diet was extremely plain and consisted only of rice-bread and some simple relish or seasoning. المن برنج و النحورش سهل خوردى (T. F. 208, l. 13). Dowson in his rejoinder to Raverty suggests that the right reading is Nān-i-Khurish-i-Safriyana, that is, 'Bread for travelling-food,' (Vol. VIII. p. xx), but النخورش به is a frequently-used compound with a definite meaning of its own.

II. 317, 1. 2 from foot. And built a fort for his residence.

و حمار بسكوت (بسكونة (variant في الكرد (بسكونة)). "He built a fort at Basankot." (See Vol. VIII. pp. xxi-xxv). 'Basankot' is again mentioned in association with Lakhnauti at page 320 infra (Text, 180, 1. 4 f. f.) and once more at Text, 243, 1. 2. The place has not been traced.

II. 318, l. 18. And his name was mentioned in the Court of Ghiyasud-din.

'Tazkir' is rendered by him as 'Ode'!

II 318, l. 3 from foot. That to the west [of Lakhnauti] is called Dal, the eastern side is called Barbanda

Variants ازال and درائد. At Text, 243, 1.4, the reading is ازال r.e. Rārh or Rādha. 'Barbanda' or 'Barānd' must be 'Bārınd' (Vārendra or Bārendra). Hamilton informs us (Hindustan, I. 114) that Bengal was divided in olden times into five districts, (1) Rarh or Radha, the country west of the Hugh and south of the Ganges; (2) Bagdi, the delta of the Ganges: (3) Banga, the country east of and beyond the Delta; (4) Barind or Barendra, the country to the north of the Padma and between the Karatoya and Mahananda rivers; and (5) Mithila, the country west of the Mahananda river. (apud Blochmann, J A. S. B. XLII 1878, p 211) Barendra was the name given to the ancient Hindu kingdom of Paundra or Paundravarddhana-which included the Rangpur. Dinappur. Purnea, Malda, Rajshahi. Bogra and Pahna districts of our times, (I. G. XX. 244). According to the same authority, Rarh is the ancient Karna Suvarna, which lay west of the Bhagirathi (the old channel of the Ganges) and included the modern districts of Burdwan, Bankura, Western Murshidābād and Hugh. (XXI, 237).

II. 318, last line. From Lakhnauti to the gates of Lakhnaur, and on the other side of the river as far as the city of Deokot, embankments (pul) have been raised, which extend for ten days' journey.

Blochmann (J A.S B 1873, p. 212 note) thought that Lakhnaur must be Lakarkuda in Birbhum, about 85 miles south of Gaur. Lat. 23°-18' N, Long 87°-15' E. Deokot is about 75 miles north of Gaur Stewart suggested that the correct reading must be 'Nagore,' :. e. Rajnagore, the capital of the Hindu Rajas of Birbhum. Raverty laughs at Dowson's objection to Stewart's suggestion on the ground of its being "right away from the river." He maintains that this is just what is required in the case and is a proof of the identification being, not unsound, but sound. (Tr. 585 Note). An entrenchment, wall or embankment extending in an irregular and broken line for a distance of 32 miles is still extant in the vicinity of the town, though rapidly decaying "The gateways have fallen and many parts of the wall itself have been washed away," but enough remains to demonstrate its former existence (Hunter, Stat 'Acc of Bengal, IV 335, Arch Sur Rep. VIII, 146-7 apud I G XXI, 78-9). Elsewhere also, it is stated that "the Pathan rulers of Bengal constructed a road from Deokot in Dinājpur through Gaur to Nagore in Bîrbhum." Nagore is in Lat 23°-57′, Long 87°-19′ (I G. VIII. 241)

In this connection, it may be noted that there are some coins of Illutmish minted at a place, the name of which was read by Dr Hoernle as Lakhnauti (J R A S 1900, p 482), but by Thomas as 'Nagor' (C.P.K.D Coin No 59, p 78). Mr Nelson Wright supposed that the place meant by Thomas must be Nagor near Jodhpur, and questioned

the deciplerment on the grounds that "Nagor has the initial a long and that it is surprising to find a coin of Ghori pattern issuing from a mint in Rajputana." (I. M. C. II. Introd. p. 6). But these objections would lose their force, if the mint name was deciphered as Nagore [in Bīrbhūm]. Mr. Wright himself read the name then as 'Lakūr' and he adheres to that lection in his later work on the "Coinage and Metrology of the Sultans of Dehli." (p. 20; Coin No. 52 A). He thinks that the mint was somewhere in Bengal, but does not tell us where this Lakūr is to be found. II. 320, l. 8. Sultan Abu-l-Muzaffar Altamsh.

Budāuni unwittingly set a ball of discord rolling when he averred that 'Altamish' or 'Iltamish' was so named because he was born "on the night of an eclipse of the Moon". (I. 62, Tr. I. 88). Neither Minhāj nor 'Awfi nor Ḥasan Nizāmi hazards any conjecture in regard to the meaning of the name and the T. A. and F. are also wisely reticent. On the coins of this Sultan, his name is variously inscribed as 'Ilitimisi' and liminal. The Nāgari transliteration is 'Ilitimisi' or 'Lititimisi'. (Wright. Coinage, p. 30; Thomas, C. P. K. D. 44 and note). 'Altamash,' 'Altmash' or 'Iltmish' is said to mean 'sixty' in Turki, and Khwāfi Khān (II. 876, 13) uses the word, for the advance guard of the centre of an army.

Mr. Stanley Lane Poole assures us that 'Iltutmish' signifies 'handgrasper, supporter, upholder.' Mr. Redhouse, another Turkish scholar, was at first in favour of reading the name as 'Iltimish' المنتش and supposing it to mean 'kidnapped' or 'carried off,' [Scil.] 'the slave who had been carried off.' But he was not sure that it was not used in the active sense of 'carrier off' or 'kidnapper', [Scil.] 'the ravisher (of hearts).' (Catalogue of the Coins of the Sultans of Delhi in the British Museum, p. xxix). But when Thomas drew his attention to the passage in Budauni. Mr. Redhouse changed his mind. He suggested that the J had been displaced and the name wrongly inscribed on the coins. He opined that the correct form must be 'Aitutulmish,' which might mean 'The moon was eclipsed' or 'Eclipse of the moon.' But he also thought it not unlikely that Budāuni's dictum was only "one of those Eastern remarks one so often meets with and really beside the mark." Dr. Barthold has lately re-examined the question and he agrees with Mr. Lane Poole and holds that the correct form is Iltutmish, signifying "Maintainer of the Kingdom." (Zeitschrift der Deutschen Morgenländischen Gesellschaft, 1907, p. 192).

'Altamash' was a not uncommon name among the Turks. Malik Firūz Shāh Altamash, Shāhzāda of Khwārizm, is mentioned by Minhāj himself as one of the grandees of Sultan Shamsu-d-dīn. (T. N. Text, 177, l. 7; Raverty, Tr. 625). Another man of the same name, who was an adherent of Tīmūr, is said by the latter's historian, Ibn 'Arabshāh, to have been imprisoned by the Sultān of Egypt. (Tr. Manger, II. 275, quoted by Beveridge, Tr. A. N. I. 210 note). A Ḥājji Altamash (or Iltmish) was sent as his ambassador by 'Abdulla Khān Uzbeg to Akbar in 979-980 H. (A. N. II, 368, Tr. II, 534). Cf. also the names, Tugh-timish, Qal-timish

(Raverty, T. N Tr. 183 note), Süyurgh-timish, Adku-timish, (Z A. 21), etc The name appears to be made up of 'timish' or 'timish' with another word profixed This may be Illi, Illiu or Alli. Bailiagi speaks of a Salyūg inider named Olis 3! (Text 709, 1. 8), Illi or Alti Salmān (143 supra) and another man named 'Altūtigin' or 'Iltūtigin' is also mentioned by him. (Text 272, 1 1. 1 = 110 supra). We also know that an Amīr named Iltutimish-al-Turki was governor of Al-Rayy in A. H. 289. (Zambaur, Manuel de Chronologie pour l'histoire de l'Islam, p. 44; H. N. Wright, Coinage and Metrology of the Sultāns of Dehli, 70).

Here, as in the case of Albak, the soundest conclusion seems to me to be that the name should be taken, just like any other name which has no topical or qualificative significance, and that whatever its meaning, it has no connection with either abduction in childhood, power of ravishing hearts, real or supposed birth on the night of an eclipse of the moon or "seizing, upholding or maintaining" kingdoms. Every one is agreed that the name was given to him at birth, and surely those who did so could not have known that he would be the maintainer or upholder of a great kingdom.

II 320, l 16 Sultan Shamsu-d-din was ... from the tribes of Albari Sir E. Denison Ross thinks that "the real name must be 'Alpari' from 'Alp-ar,' brave man,' a name given to the Turānian Afrāsiāb, from whom the Turks claimed descent (Vide Kāshghari, Divān-i-Lughati-Turk) An Alp-ar Khān is also mentioned in Juwaini's account (Tār Jehān Kushā, Text, I. 92) of the siege of Samargand by Chingiz Khān.' (Hājji Dabīr, Z W III. p. lv) Minhāj says that Balban also was descended from the Albari Khāns [Khānān, not Khāqāns, as at 360 infra; Text 281, l. 6]. The Qarā Khānid dynasty of Turkestān to which Ilak Khān—the contemporary of Sultān Mahmūd of Ghazna—belonged is often described as that of the "Afrāsiyābi Maliks" Barani also assures usthat Balban claimed descent from Afrāsiāb. (T. F. 37, l. 7). II 323, l. 14 'Ali Ism'ail who had charge of Delhi.

المبرالمدل Dabir calls him المبرالمدل W. 687, I. 18). He was the Amir-i-dād of Dehli, i v. the chief judicial officer of the state, a sort of Lord Chancellor or Justiciary See p. 327 infra=T N, Text 175, I 8 f. f, where the phrase is correctly rendered as 'Chief Justice' by Dowson himself See also Text 274-5, where Malik Saifu-d-dīn Shamsi is called 'Dādbak' and also Amīr-i-dād. Another noble, Amīr Dād Hasan, is mentioned in the Tāju-l-Maāsir. (233 ante, q. v. my note).

II. 326, l. 10. Malik Sinānu-d-dīn Habsh

The sobriquet is written in various ways, Hasrar, Jaisar, Jaisi, etc. See Elliot's note at E D I. 490, where he opines that it must be Chanesar In the Notes to his Translation of the T. N., which was published in 1881, Rayerty hesitated between 'Jatisar', 'Chatisar' and 'Chanisar' (pp 614-5), but in his Essay on The Mihran of Sind and its Tributaries' in the J.A.S.B.

1892 (326 Note), he speaks of him as Sinānu-d-dīn Chanīsar. The TABAQAT-I-NASIBI Tuhfatu-l-Kirām and Muntakhabu-t-tavārīkh, the authors of which were Sindhis, also write Chanesar. (E. D. I. 345, 485). Sir W. Haig prefers Chatisar' (C. H. I. III. 54), is not supported by either reason or authority. Chanesar is the theme of many tales and ballads still recited by the common people in Sindh, and they may be trusted to know better than any outsider, the correct pronunciation of the name of their tribal or national hero. "The Loves of Chanesar and Lila have been sung by more than one Sindhi poet." (E. D. I. 263, 347). Chatīsar has no meaning. 'Chanesar' appears to be the Sindhi form of 'Janesar,' as 'Chach' is that of 'Jajja.' 'Janesar' is derived from 'Yajneshvar', one of the epithets of the god Vishnu. (Vishnu Purāna, Tr. Wilson, II. 313; III. 183; V. Pt. i. 200, 253). Janesar (Janeshwar) is still a not uncommon personal name in Bengal. Chanesar is also a place-name and Raverty maintained that the real name of the place to which Jaisiya, the son of Dahir, fled was not 'Jaipur' or 'Jitur,' but 'Chanesar', and he located it at a village which still exists twenty miles west of Ghausgarh in Bhāwālpur. (Mihrān, 242 n.). See also E. D. I. 176 and 179 note, where the name of the place is said to be written as 'Chanesar' in Dowson's Mss. II. 326, l. 22. On Monday, the 2nd of Rab'i-u-l-avoval 626 H.....

The text has '22nd' (174, l. 6) and so also Raverty. (Tr. 616). The Tāju-l-Maāsir says it was the 23rd. (243 ante). 22nd Rab'i I, 626 H., corresponded with Sunday, 18th February, 1229 A. C., and 23rd to Monday, the 19th. Minhāj would appear to have again given the Ruyyat date. Hasan Nizāmi has the Hisābi or Book-rule date. 8th February 1229 as given in the C. H. I. III, 54 is a misprint for 18th or a miscalculation. It was, moreover, a Thursday and must be wrong.

The city (Dehli) was not 'adorned by the presence of the envoys' [1.23]. It was beflagged and decorated, triumphal arches were erected nd the gates were hung with silks, as was usual on such occasions, II. 326, l. 5 from foot. Balka Malik.

Some authors, e. g. Sir Wolseley Haig (C. H. I. III. 54), following Raverty's translation (617 and 626) say that Balka or Bilka Malik Khalji was the son of Husimu-d-din 'Iwaz, but no such statement is found anywhere in the B. I. text of the T. N., where he is called Balka Malik Khalji at 174, l. 12, 237, l. 5 f. f. and his full name given as Ikhtyāru-d-dīn Irān Shāh Balkā Khalji at 178, l. 14 in one manuscript.

But there is a coin on which Balkā styles himself 'Shahinshāh' 'Alāu-d-dīn 'Abul M'aāli [or Abu-l-Ghāzi] Daulatshāh bin Maudūd.' The date can be read either as 627 or 629 H. (J. R. A. S. 1873, p. 367; Wright, Coinage, p. 21). This numismatic evidence would show that he was not the son of Husamu-d-din, though he might have been a relative or even his son-in-law, as غويش is loosely used in both those senses.

11. 327, 1.3 Milak Dev, the accursed son of Basīl the accursed

Raverty proposes to read the names as 'Mangal Bhava Dec son of Mal ديوال . Deo.' (Tr. 619 and note). The T.A. has ملك ديو بايل (21, 1. 18) and F. (I 66, l. 15). Sir Wolseley Haig calls the Raja 'Mangal Bhava Deva, the son of Maldeo or Birbal Deo' (CHI, III 55, 533). But 'Mangal Bhava Deva 'is an impossible name for a Hindu and Raverty's conjectural and fanciful restoration cannot be accepted by any one acquainted with Sanskrit. 'Milak', re. 'Melag' or 'Megal' is a name which occurs in the dynastic list of the Chudasama rulers of Junagadh. (Duff, C I. 284; Burgess, Arch. Survey of Western India, II 164, Tarikh-i-Sorath. Tr. Burgess, 139; B. G VIII, (Kāthiāwād) 488, 498) Burgess points out that the name of Melak, the son of Mugat and father of Javasınha Chudasama occurs also in an inscription dated 1416 A. C. (Ibid, note), Hājji Dabīr also calls this Raja of Gwalior Melagdeo, the son of Baisil (Z W 699. ll 2 and 7) Amīr Khusrau gives the name of the Rājā from whom the fort of Mandu was taken by 'Amu-Mulk Multanı in 705 A H. as Mihlak Deo (Khazāin-al-Futūh, Text, 60, 1 5, E.D III 76), which is really the same name 'Mokal' also occurs and was borne by a Rana of Chitor in the 15th century (Duff, C I. 235, 249, 254) The name which follows 'Melak' is probably 'Bīsal' [Visala Deva] We know from inscriptions that a Parihar, who is called Visaldeva (and also Parimal Deva), captured Gwallor from the Kachhwahs in or about 1129 A. C. and that the Parhars ruled there until they were expelled by Iltutmish (Cunningham. Arch. Survey Reports II 312, IV 27. 51, I. G XII 441, Vaidya, H M. H I III. 305, 357; Elliot, Races, I. 159, Crooke, Tribes and Castes. IV 88) When Minhai says that Melag was the Jul'son' of the accursed Bisal, he probably means merely that he was the descendant of Bīsal (or Parimal) who was the founder of Parihār dominion in Gwallor. The forms 'Birbal,' 'Pilpal,' Balbal' must be perversions of the alternative form, Parimal.

II. 328, l. 2. A halt of five days was called here.

Minhāj uses a similar expression in, at least, four other places. (Text 76, 1 16, 192, 1 8, 198, 1 9, 253, 1 3 f f) In the first of these, he states that when the Khalīf Nāsiru-d-dīn-i-Allah sent a rich Khil'at to the Sultan Ghiyāsu-d-dīn Muhammad-i-Sām, ومن المرابع "the Sultan ordered the Royal Naubat to strike five times" In the second, we are told that Ikhtiāru-d-dīn Itgīn, the regent of Mu'izzu-d-dīn Bahrām Shāh, gave great offence to that Sultan by keeping an elephant and ordering the Naubat to play three times a day at his gate" (338 infra) An almost identical statement is made of another over-ambitious minister, Nizāmu-l-Mulk Muhāzzibu-d-dīn (343 infra) "The playing"

of the Naubat at the King's Gate was originally a jealously-guarded TABAQAT-I-NASIRI rcyal privilege. It was subsequently granted to or usurped by provincial governors and other persons in power. The old rule appears to have been to strike it five times in the nyethemeron, four times during the day and once at night." (Siyaru-l-Mutāākhirīn, Tr. I. 3 note). It appears to have been played eight times—once at the end of every pahr or Watch in Akbar's times (Ain, I, Tr. 51), but this may have been one of that Emperor's innovations.

The phrase 'Panj Naubat' occurs in Nizāmi's Sikandar Nāma (Canto XI, verse 11; Clarke's Trans, 95) and the Ghiyāṣu-l-Lughāt explains that Sultan Sanjar Seljūqi was the first sovereign to order the Naubat to be played five times at his gate and not three only, as had been the rule or custom before. F. also informs us that Muhammad Shah Bahmani ordered the 'Naubat' to be played five times, soon after his accession. (I. 282, l. 4 f. f.).

It appears to have been an ancient Hindu custom also. It is stated in the Chachnama, that when Chach had conquered all the provinces of the old Kingdom of Sind upto the frontiers of Kashmir and Kerman, he, "in accordance with the Hindu custom, ordered a naubat of five musical instruments to be played every evening and morning." (E. D. I. 152). II. 328, l. 5. A temple which was three hundred years in building

بنانه که مید مال بود که آزرا عمارت کردند ; نخانه که مید مال بود که آزرا عمارت کردند

equivocal.

The Tārīkh-i-Mubārakshāhi has از سعد سال بر آورده بودند (Text, 20, l. 5). Budāuni's paraphrase is 39 to leave and leave (I. 67) and Ranking's translation is, "which had been built six hundred years previously." (I. 95). B.'s dain, 'six hundred', must be a mistake for dam "three hundred." Alberuni says that Bhilsa was so called after the temple of the god Bhaillesha (the Sun-god), who was worshipped there. (Tr. Sachau, I, 202; E. D. I, 59). The temple demolished by Iltutmish was probably one of those erected in the palmy days of Paramāra rule in Mālwā by Munja or his nephew, the renowned Rījī Bhoja, who reigned about the end of the 10th and beginning of the 11th century. (Duff. C. I. 300). This would make it more than 200 years old in 1234 A. C., though it cauld not have been the same as that referred to by Alberuni. T. A. (29, 1. 8 f. f.), F. (I. 66, 1. 11 f. f.) and B. apply the remark, not to the temple at Bhilsī, but to that of Mahākāl in Ujjain, which must be wrong. II. 328, l. 13. In A. H. 636, he led the armies of Hindustan towards

Banian, is mentioned by Wassaf (E.D. III. 36), who says that it was in the Jud hills. Barani speaks of a Maulana Hamidu-d-din Baniani (363, 1. 16). Minhāj states elsewhere that it was the place from which Saif-ddin Hasan Qarlugh invaded Ucheha. (Text, 238, l. 1). Raverty's opinion was that it was situated somewhere between Kurram and the Jhelum,

and near the hills of Jūd But he was not sure of the actual site and thought it might be either Banian, which lies nine miles south east of Khanpur of the Gakkhais, or Panian, another village, situated about six miles south-west of Haripur in Hazara district, N W. F. Province (N. A. 281-2) This Haripur is shown in Constable, Pl 24 E a But Banian was a place of great note and not a mere village and the I G may be right in identifying it with the much better-known Bannu in the N.W F Province (XVI 49) Mr. Longworth Dames also is of the same opinion Coins struck by Iltutmish at Banian are known (JR AS 1908, pp 3901, Wright, Coinage, 34, 75) Minhaj afterwards speaks of the expedition as the Sultan's "last campaign from the Indus and Banyan." (330 infra) II 329, 13 He sent to hell the accursed Bartūh (2), under whose sword more than 1,20,000 Musalmans had received martyrdom

It is surmised in the C H I. (III 54) that he was a Rājā of Kāmarūpa, but no evidence is cited in support of the conjecture. The real name was probably 'Prithu' and I venture to propose an identification which has occurred to me. Local traditions in Rangpur tell of a great Rājā named Prithu, who was ruler of Bhitirgarh in the Jalpaiguri district of Eastern Bengal, some time in the thirteenth century, and who drowned himself in a large tank in his capital to avoid pollution from the touch of the Kichakas (Musalmans) who invaded his country from the north. The extent of his power can be judged from the fact that the ruins of his capital near the town cover an area of four miles in length and two in breadth. They are described at considerable length in Montgomery Martin's Eastern India, III 433-446. See also I G VIII. 117 and XXI. 224 Rangpur formed the western outpost of ancient Kāmarūpa

II 331, l 30 Tāju-d-dīn Muhammad, Bahāu-l-Mulk Husain Ash'arī and other confeder ate officials killed the Tāzīk

This is all topsy-turvy (Text, 183, 16ff) "And [the Turki nobles and other personal attendants revolted and] put to death unjustly [lit made martyrs] Tāju-l-Mulk Muhammad, Bahāu-l-Mulk Husain Ash'ari, et cetei a, along with the other civil officials [or administrators] who were Tāzīks', i.e Persians and not Turks See Text, 261, 19, (Raverty, Tr 761), where Minhāj mentions the matter again Tāju-l-Mulk and the other persons named were not the murderers, but the persons murdered by the Turki nobles There is an 'izāfat' after كرداران The T A (31, 114) and F (L 67, 12ff) have also misunderstood the passage and made "a terrible blunder" here, as Raverty puts it (Tr 635 Note)

II 334, l 13 In the neighbourhood of Bābul and Nakwān

Bābul' is a misreading of Jh' Pāīl', now in Patiāla State Lat 30°-40' N, Long 76°-5' E Nakāwan, which Raverty leaves unidentified, (Tr 640 note), is a small town or village in its neighbourhood Pāīl is 34 miles north-west of Patiāla town, Pāīl and Nakāwan are both mentioned in the I G (XIX 316).

II. 334, 1. 16. She conferred the office of wazīr on an upright officer.

يود باك نظام اللك بود يخواجه مهذب داد كه ناك نظام اللك بود of Wazir to Khwaja Muhazzib who had been the deputy of Nizamu-l-Mulk." This Khwaja Muhazzib is again mentioned at 338, 341, 342 and 313 infra. He is also called Nizīmu-l-Mulk Muhazzibu-d-dīn Muhammad. He was put to death by the Turki nobles in 640 II. (343 infra). A Mulla Mazhab (recte Muhazzib) is mentioned in the Memoirs of Babur also. (E. D. IV 284 q. v. my note).

II. 335, l. 11 from foot. Some of the officers on the frontier supported him.

185, l. 5 f. f. They were not ; و در سرّ بنضي از ام، اي حضرت با او بار بودند officers 'on the frontier'. They were the Amirs who were leagued or confederate with him in secret. The phrase is dar sirr, and is again used at Text, 189, 1. 6, where the Qurimitas are said to have sworn oaths of sidelity or allegiance in secret among themselves, در سِرَ بِيتَ كردند, See 336 infra. is again used in this sense at 289, 1.2 f. f.

II. 335, 1. 2 from foot. The Karmatians and heretics of Hindustan being seduced by a person who was called Nur Turk flocked to him in large numbers.

This passage has been the subject of considerable speculation in connection with the history of the Ism'aili or Khoja community in this country. The Khojās are, as Mr. Enthoven says, "Ism'āīlians of the Nizirian sub-division of the Must'ailian branch, who separated from the latter in 1094 A. C. on a question of succession to the throne of the Fatimite Khilafat. The most noted leader of this sect was Hasan Sabah-the Old Man of the Mountains-who founded the order of the Fidais or Assassins and concentrated his power at Alamut in Dailam. Another Hasan-the fourth ruler on the pontifical throne of Alamut (C. 1163 A. D., 559 A. II.)—is said in the traditional history of the sect, (as related in the Gujarāti history, Khojā Vrattānt, p. 155), to have sent a missionary to India, whose real name was Nuruddin or Nur Shāh and whom the Khojās call Nūr Satāgur, "the Teacher of Pure Light". Nūruddin is said to have paid two visits to Gujarāt and converted the Raja, who is, by a gratuitous conjecture, supposed to be Bhima II (R. 1179-1242 A. D.). He was killed by Chach, one of his two leading disciples, when he was "absorbed in a Samādhi or trance." Mr. Enthoven cites this passage from the T.N. and Minhīj's account of the Malahida riot under the leadership of Nur Turk, in his article on the Khojās and seems to suggest that 'Nur Turk' is no other than 'Nur Satagur,' the first Khoji missionary. (Tribes and Castes of Bombay, II. 217-201).

But there is little else except the name on which any identification can be founded. The chronology is indubitably shaky and the legendary accretions, the conversion of Bhima II, Nur's miracle of bringing a dead man to life and his matrimonial alliance with another Raja named Surchard do not inspire confidence, though the statement about the rioters having come from Gujarat and Sind is intriguing

Minhaj states that the *émeute* occurred in the reign of Raziyya, but the T. A. (30, 1 15) and F (I. 67, 1 8) transfer it to that of Iltutmish and make no mention of any such riot in her own The C. H I. (III 55, 59) has turned this into two outbreaks, one in each of these reigns, but this eclectic duplication seems to be uncalled for The assertions of Nizamu-ddin and F who has servilely copied the T A, cannot weigh against the explicit statements of Minhaj, the primary and only contemporary authority known Moreover, if these Sectarians, whom Minhaj detested so bitterly and whom he has denounced so vehemently, had been ever guilty of an attempt on the life of Iltutmish, he would have been the first to seize the opportunity of holding them up to the execuation of posterity. In this connection, it may be worth while to recall the following severe, but not quite unjust, verdict of Raverty on the earlier part of Nizāmu-d-din's Chronicle. "I had some faith in the Tabagat-1-Akbar1, before I compared its statements with respect to the Shamsi dynasty I found it amere transcript with verbal alterations of our author's [Minhaj's] statements plus the geographical and other blunders I have before referred to." (Tr 698) II 337. l 12. She [Raziyya] had reigned three years and six days

The variant reading مال و شر ماه (Text 190, footnote) is more correct. As she was placed on the throne on 18th Rab'i I 634 H (331 ante) and defeated on 24th Ramazān 637 H, she must be taken to have ruled for 3 years, 6 months and 6 days, which is just what is found in the best Mss (Raverty, 648) The T A (33, 1.6), F (I 69, 13) and B (I.85=Tr 122) all agree in making it three years, six months and six days II. 337, 1. 14 Sultān Razīya was killed on the day following

The body must have been brought to and buried in the Capital, as the Empress's tomb still exists in Dehli, at the point where the Sitā Rām Bazār ends Ibn Batūta says that it was a place of pilgrimage in his day and that it was situated on the banks of the Jumna at a distance of about a parasang from the city of Delhi (Defremery, III 167-8=593 infra) It is mentioned also by Shams, as having been included within the limits of the New City of Firūzābād (303 infra) See also Fanshawe, D P P. 60, Thomas, C P K D 106 note, Āsār, Part II. 15). B tells us that the army of Ghāzi Malik Tughlaq was encamped in the vicinity of the tomb of Sultan Razīyya (I. 220, Tr I. 294)

II 340, l. 19 He had lived for some time quietly in the Sultan's water-palace

مدتی در نصر حوس سلطان باعتگاف شسته (195, 17) "He had lived in monastic seclusion for a time in the palace near the Hauz-i-Sultān [the Sultān's Reservoir]" The Hauz-i-Sultān was the Hauz-i-Shamsi, the great Tank built by Iltutmish It is called Hauz-i-Sultān by Amīr Khusrau, as well as by Barani. (See my note on Vol. III, 104, 1, 18), There was a palace

there and this Darvish must have lived in one of the cells of the Mosque or Khangah attached to it. Ibn Batūta thus describes this Qasr-i-Hauz-i-Sultān. "Outside Dehli, is a large reservoir named after the Sultān Lalmish [Iltutmish], from which the inhabitants draw their drinking water.....In the centre, there is a great pavilion built of squared stones, two stories highInside it, is a mosque and at most times, it is occupied by mendicants devoted to the service of God." (Gibb, l. c. 196: Defrémery, III, 154). The palace in the centre of the Hauz with its fine terrace is described in the Qirānu-s-S'adain also by Amīr Khusrau. ('Aligarh Text 32: 525 infra).

II. 341, l. 18. He sent the Shaikhu-l-Islam Saiyid Kutbu-d-din to allay the outbreak.

Nigāmu-d-dīu Ahmad (T. A. 34, 1. 7), F. (I. 70, 1. 3) and B. (I. 87) identify this Shaikh Qutbu-d-din with the renowned saint Qutbu-d-din Bakhtiār-i-Ūshi, after whom the Qutb Minār is said to have been named. But this conjecture must be founded on some inadvertence or error, if the recorded date of the Saint's death is correct. Abul Fazl (Ain, Tr. III. 363) and Beale (Miftahu-t-tawarīkh, 58) give it as 14th Rab'ī I. 633 and F. himself states in another part of his work, that the saint died on that identical day and month in H. 634, (II. 383, 1. 10 f. f.). In either case, and whichever of the two discrepant years is correct, the saint could not have been alive at this time (639 H.), and this Shaikh' Qutbu-d-din must have been some other person of the same name. It is not unlikely that the Shaikhu-l-Islam Qutbu-d-dīn, who is mentioned as one of the leading conspirators and adherents of Qutlugh Khan in 655 H., is identical with this Qutbu-d-din of 639 H. (Text, 223, 1. 6=357 infra).

On 1.5 f. f. 'Farkhi' is an error for 'Farrukhi'.

II. 343, l. 4. Kāzi 'Imādu-d-dīn Shakūrkāni was appointed.

The variant 'Shafurgani' gives the right reading. Shafurgan, Shabargan (q.v. 142 ante, 577-8 post, and E. D. VII. 81) lies about ninety miles west of Balkh (Yule, Tr. Marco Polo, I. 149) and was at one time the seat of government of Juzjan or Juzjanan, Minhaj's native district. (Le Strange, L. E. C. 426). A Nizāmu-d-dîn Sharkāni is mentioned at His sobriquet also must have been 'Shafūrqāni' or 'Shabūrqāni.' It is shown as 'Shībarkhan' in Constable, 22 A b. The original Pahlavi form may have been Shahpurgan, 'the city of Shahpur', but it is supposed to be 'Asapuragan,' 'city of the Asagartii', in Houtsma. (IV. 360). II. 343, l. 6 from foot. And the office of Lord Chamberlain was given to Dāru-l-Mulk Bāligh Khān.

أَنْ عَانِ مَعْظُم خُلْدَ الله دُولَتُه مَعْوض كَشَتَ (199, 1. 6). "And the office of Hajib of the Palace (lit. Capital) was assigned to Ulugh Khan the Great (May God perpetuate his good fortune!)." The person referred to is no other than Minhaj's great patron, Ulugh Khān, who afterwards became Sultān Balban. 'Dāru-l-Mulk Bāligh Khān' is an impossible collocation.

II 344, l 3 from foot. The accursed Manhūta (Mangū Khān).

The explanation in the parenthesis is a manifest error. Mankūtā the Nūyin (Prince or General) and Tāir Bahādur are again mentioned (Text, 235, l, 8 f f) Mankūta was only one of the favourite officers of Chingīz Khān. Mangū[or Mongke] Khān was the son of Tūli, the youngest son of Chingīz. The error is committed again at 363 infra.

II. 347, l 21 In the neighbourhood of Kanauj there is a fortified village called Nandana

Variants, 'Talanda' and 'Talsanda' (Text, 210, 291 footnotes). Hājji Dabīr reads 'Tasanda'. (Z. W 713, 1 21) Most of Raverty's Mss are in favour of 'Talsanda,' but he notes as variants 'Talanda', 'Talbanda' and 'Bīsīda' (Ir 679 and 816 Notes). Cunningham, relying on the reading Nandana, thought that it must be Nava-Deokāli, near Rājgīr—the fort of the legendary heroes Alha and Udal—four miles south-east of Qanauj (See Thomas, C. P K D 125 Note) But it is not likely that the stronghold of this contumacious Rājā could have been in such close proximity to Qanauj, where the Musalmans had established themselves permanently, ever since the defeat of Jayachand, and which they must have held in great force.

Minhaj vaguely states here that this fort was در حدود قدوع, within the boundaries (-**) of Qanauz district, (not town), below the Ganges Jumna Duab (Text 210.1 14, 291, 1 12) Thornton mentions a Dursenda or Dulsenda as a pargana and town on the river Bighin, a tributary of the Jumna, seven miles south-west of its right bank and 39 miles east of the town of Banda Lat. 25°-27' N, Long 80°-57' E It is situated just in the sort of country in which the Rija is said to have entrenched himself, in which "the defiles were arduous, the mountains rugged and the jungles manyi and which no Muslim army had ever penetiated" Banda is 35 miles N W of Kālanjar (I G. XIV 307) Darsenda is shown in Constable 28 B c There is a place called Bhaisunda also in this neighbourhood. Lat, 25°-17' N Long 80°-53' E, It lies about twelve miles south-west of Dursenda and is one of the Chaubé Jagirs in Central India, I. G. Altas, Pl 38, D 2, See also Thornton, s n Bynsont or Bhysondah. But the closest phonetic approach seems to be to Tilsanda, a village near Campore, q v the Post Office Guide, and there I must leave the matter II 348, l, 10 from foot a Rāna who was called Dalki There was wa malki

One explanation of this name which has been suggested (Thomas, CPKD.65-6) is that it may be a corruption of Trailokyamalla. A Chandella king so called was the successor of Parmardi or Parimal, from whom Kālanjar was wrested by Aibak It can be urged in favour of this view that this Trailokyamalla is actually described in an inscription of his son, Vīravarman, as "the uplifter of the land from the ocean of disasters caused by the Turushkas," and he does appear to have driven out the Muslims during the feeble regime of the successors of Iltutmish and regained possession of

a considerable portion of the old Chandella territory. (Epigr. Ind. I. 327). It is also clear from his inscriptions that he reigned between 1205 and 1245 or 1247 A.C. (Duff. C.I. 177, 201). Inscriptions at Kālanjar itself prove that it was temporarily recaptured by the Hindus (Ind. Ant. XXXVII, 128-9; Vaidya, H.M.H.I. III. 184; H. C. Ray, D.H.N.I. 722-730).

Mr. Vincent Smith, however, rejects this suggestion and, following Mr. W. C. Bennett, who first proposed the identification in the Indian Antiquary (I. 265), declares, with perhaps greater confidence than is warranted in the circumstances, that Dalki and Malki were the Bhar Rajas, Dal and Bal, who are also called Tiloki and Biloki and who are credited in the local traditions with the conquest of the whole of Southern Oude. (J. A. S. B. 1881, pp. 35-38). But this surmise is largely invalidated by the fact that Minhaj speaks of Dalkimalki or Dalakiomalaki in the singular, and as one person only and not two. (Text, 210-11; 291-2; see also Dowson. 366-7 infra; Raverty's Tr. 680-682 notes). Moreover, just as Mr. Smith champions the Bhar Rajas, so Cunningham is for sponsoring the Baghels. He states that Dalki Malki were not the Bhars, Tiloki and Biloki, but the two Baghel chiefs, called Dhalkeshwar and Malkeshwar. (A. S. R. XXI. 605). Mr. Crooke (Tribes and Castes, II. 3 and I. 52), however, is equally sure that the Bhar hero Dal is mythical and Mr. C. A. Elliot is of the same opinion. (Chronicles of Unao, 20; see also the Rae Bareli Settlement Report, 15). Sir Wolseley Haig holds that there was only one Raja, whose name was either Dhalki or Dhalki of Mahalki (C.H. I.III. 67 and note), but this gets us nowhere. All that can be said with any approach to certainty is that Dalkiomalki constitutes the name of one individual and not two. In that case, neither the Bhīr theory nor the Baghel hypothesis can be sustained, even if the tribal heroes named are not as legendary as the Knights of the Round Table or the Paladins of Charlemagne.

II. 349, l. 3 from foot. The Sultān......gave his daughter in marriage to the son of the Khān [Ulugh Khān].

What Minhāj really says is

أملكة جهان كشت (Ulugh Khān) فرزند او (213, l. 11. "His [Ulugh Khān's] daughter became the Malika-i-Jahān, 'Empress of the World'."

Sultan Nāṣiru-d-dīn Maḥmūd was only about seventeen years old at the time of his accession in 644 H., as he is explicitly said to have been born after the death of his eldest brother, which took place in 626 H. (326 ante). He could not, therefore, have had a marriageable daughter at all in 647 H. The T. A. (36, l. 4), F. (I. 72, l. 3) and B. (I. 91, Tr. I. 129) all agree in saying that it was the Sultan who married Balban's daughter. The error cries for correction, as even Thomas has been misled by Dowson's translation and speaks of the Sultan "having given his daughter in marriage to the son of the Khān.' (C. P. K. D. 125).

II. 350, l. 8. He [the Sultān] was graciously pleased to give her one hundred beasts of burden.

"slaves". In another account of the same transaction (Text, 271, 1 3), Minhāj speaks of them as שלאים 'slaves'. On 295, 1 7, he again states that 'slaves' forty slaves' were given to him. Slaves from India were, at this time, the most easily vendible commodities in the markets of Khurāsān Baihaqi also uses the word ישי in this sense, and states that when the fort of Hānsi was captured by Mas'ūd Ghaznavi, the women and children of the garrison were made slaves על נייני וישלי כו על ביל לעל (Text, 665, 19). Fakhru-d-dīn Mubārak Shāh uses the word in the same sense (Tārīhh 28, 17). Dowson himself translates ישי הוא 'prisoners' at 371 infra, by which he probably means 'persons captured in battle and enslaved' II 350, 14 from foot. The author, passing by the fort of Marūt (Mīrat) to Sarsuti and Hānsi, arī ized at Dehli.

The parenthetical gloss is unauthorised and misleading. The place meant cannot possibly be Miiat, though it may be Marot, now in the Khairpui tahsil of Bahāwalpur State, 60 miles cast of Bahāwalpur town Lat 29°-5′ N, Long 72°-40′. (Th) "Marot was a place of some importance in the early Muhammadan period on account of its lying on the direct road from Multān to Delhi, via Sarsuti or Sirsa'' (I. G. XVIII, 210 See also Raverty, Tr 688 Note). It is again mentioned in juxtaposition with Sarsuti at 361 infina. Captain Arthur Concily travelled by the same route, via Marût, from Dehli to Multān in the company of an Afghān caravan, so late as 1830 A C (Mihrān, 168)

II 351, l. 18 and foot note. Jahir Deo was the greatest of the Ranas of that country.

The text has 'Jahirajar,' with the variants 'Jahirajad' and 'Jahawārjār.' (215 note). Hājji Dabīr calls him 'Rāi Jāhar Ajār" (Z W 716, 1,16) Every body is agreed that the name of the Raja was Chahad, but 'Azar'has severely taxed the ingenuity of the commentators Cunningham thought that Ajarı was a corruption of 'Asavarı,' which appears on some coins struck by Chahad Deva who was supposed by him, to be the Raja of Rantambhor, as well as of Narwar (Coins of Mediaeval India, 91-92) Thomas's explanation was that 'Ajāri' stood for 'Achārya', 'spiritual guide,' and he sought to substantiate it by the argument that "many of the chiefs of these Rajput tribes, in later days, affected hierarchical honours, calling themselves mahants etc and that the famous Samarsi was designated as the 'Regent of Mahadeva'" (CPKD 69-70) This problematical elucidation has been accepted by Raverty (T N Tr 690 note) and also in the CH.I (III p 68) But the statement on which it is They did style themfounded is true only of the Ranas of Chitor selves 'Priests of Eklingji' or Mahadeva, but this was only on account of a somewhat dubious legend or tradition connected with the origin of their dynasty No other Rajput chiefs have ever 'affected hierarchical honours' or pretended to be 'Mahants' And if they have, how is it that not one out of the scores of Hindu Rais and Rajas who are

mentioned by Minhāi himself and other Musalman chroniclers is styled 'Acharya', as 'Jahir Deo' is supposed by him to have been? The fact is that 'Ajāri' has nothing to do either with 'Achārya' or 'Aheriya', that is, Gehlot, [which is another explanation hazarded by Thomas], or with the invocation to 'Asavari on the coins of Chahad Deva. with which Cunningham seeks to connect it. Chāhad Deva's territory was in the neighbourhood of Gwalior and Chanderi and he is also stated to have built or repaired the fort of Narwar, which is said to have been his birth place. Minhāj speaks of him as رأة أجار i.e. 'The Rāna of Ajār' (296, l. 8), in another place as رائة اجارى, 'The Ajāri Rāna' (296, l. 13; 297, l. 2) and in a third as مندوك اجارى, 'The detestable Hindu of Ajār' (297, 1.5). This may indicate that 'Ajar' was the name of a place and the suggestion may be offered that it is meant for Arjar, a fairly well-known town or village lying about 18 miles east-south-east of Jhansi and about eleven miles south of Orcha. It is now a station on the Jhansi-Manikour branch of the G. I. P. Railway. There is a big lake here and it is shown in Constable's Atlas, 28 C c. Minhāj states that when Nusratu-d-dīn Tābasi (or Tāeshi) was returning laden with booty from Kālanjar to Gwālior, he was encountered by this 'Rana of Ajar', who seized upon the defiles of the river Sindh, which lay upon the route of the returning army and that this "Hindu fellow of Ajar fell upon him as a wolf falls upon a flock of sheep." (Text, 297, 11. 1-6 = 369 post). Narwar stands on the right bank of the Sindh, which often overflows its banks during the monsoon and causes swamps. (Th.). It is 44 miles south-west of Gwalior and about twenty west of Jhansi. Arjar is therefore about forty miles south-east of Narwar. It would seem that Chahad had taken up his station and lain in wait for Nusratu-d-din at or in the neighbourhood of the swamps or lake near Arjar, and that this is the reason for his being described as the 'Rana of Ajar' and this 'Hindu fellow of Ajār'. Chāhaddeva is said in some Rajput accounts to have been a brother or relative of Prithyi Raja Chauhan (Ind. Ant. VII. 59) and the supposition is, to a certain extent, corroborated by the recent discovery of an inscription of a Mahrājākumāra Chāhada Deva, in which his genealogy seems to be traced to Arnoraja and Prithvi Raja III. (Epig. Ind. XII, 221-224). But the inscription is fragmentary and its purport not free from doubt. Others have maintained, on the contrary, that he was not a Chauhan, but belonged to the Jajjapella or Yajvapala family and two epigraphic records discovered near Narwar have been put forward to support this theory. (Ind. Ant. XLVII, 1918, pp. 221-224). Chāhāda Deva's coins also dating from about V.S. 1291 to 1311 [1234 to 1254 A.C.] have been found, but Cunningham has imported a good deal of confusion into the numismatic aspect of the matter, by mixing him up with his contemporary Bihad Deva of Ranthambor. (Coins of Mediaeval India, 89-93). The guardian goddess of the Chauhans was Asapuri Devi (I. G. IX. 79) and the true explanation of the name, Asawari, which is inscribed on his coins, may be that it is an invocation to that deity.

II 352, l 15 His estates in the Siwalik hills and Hansi

Here as well as on pp 297, 324, 325, 355, 358, 371, 375 and 380 of this volume, Dowson makes Minhäj speak of the "Siwälik hills," but there is nothing to warrant the interpolation of the second word and in the text Siwālik only is mentioned as a district or tract of country and not as a mountain range See my note on II 375, 15 infra

II. 352, l 18 (The Sultan) returned to Dehli and directed his attention to the nobles and public affairs

باكرو شابها كشت ; 217, 16. "And there was a great change in the temper of the leading nobles and alterations were made in regard to offices (at court)"

II 352, last line His fief of Hansi was, through the Lord Chamberlain, bestowed upon Prince Ruknu-d-din

"And the fief of Hānsi, along with the office of Lord Chamberlain, was assigned to Prince Ruknu-d-dīn." Balban held the fief of Hānsi and also the office of Lord Chamberlain and both the fief and the office were transferred to the name of the infant Prince.

II. 353, l 14 Victories were gained in the vicinity of the mountains of Bardar and Pinjor

The mountains of 'Bardar' are mentioned also at 334 ante, where the form is '[Sarmand] Bardar' and F.'s reading also is 'Sirmur' Bardar' looks like and may be a miswriting of Hardwar Raverty reads the second name as 'Bijnor' and is sure that [Pinjor] is an error for بعدود [Bijnor] Hardwar is situated at the southern base of the Siwalik range (Th 389) The hills of Sirmur are generally known as the Siwaliks Bijnor town lies about 40 miles south of Hardwar and Bijnor district is "an irregular triangle of which the apex points directly northwards. and which stretches like a wedge between the valley of the Ganges and the hills of Garhwal" (I G VIII Mayapur, which is mentioned only two lines lower down, is one of the suburbs of Hardwar and is one of the names by which that place of pilgrimage is mentioned by Hiuen-Tsang, (Tr. Beal I 197). Sharafuddin Yazdı (ED III. 514) and other old writers Raverty lays stression the fact that every one of his nine Mss reads Bijnor, not Pinjor (696 note) As one Ms. of B also reads Bijnor (Ranking, Tr I 130 note), it may be correct If Bijnor is the right reading, Bardar may be Hardwar If Pinjor is preferred, Bardar may be a miswriting of נינ זו נניג or נינ, the Rudra Himālāya, q v Constable,

II 353, l 19 The Sultan ordered an attack to be made on Kāithar (Kaithal)

in the Text, 218, l. 12, is an error for کتبر, Kāther, the old name of the, district now called Rohilkhand Kaithal or Kīthal is a very different place near Jhind and Karnāl in the Punjab

II 355, 1 7 from foot. He proceeded into Maicas.

This word 'Mawas' is said, in the I. G. (XV, 402), to signify 'the troubled country 'and to be a "name given by the Malirattas to the Western Satouras, a reminiscence of the time when the Korkus were notorious robbers and freebooters". Elsewhere, however, in the same publication, it is derived from 'Mahivāsi', 'dweller on the Mahi' and stated to have been "imported in Mughal times into Delhi and used by Muhammadan writers as a general term to denote hill chiefs and those living in mountain fastnesses". (XVII. 12). But both these derivations are devastatingly exploded by the fact of the word having been used by Minhai, Barani and Amir Khusrau, long before the Mahratta or Mughal domination in India. The last of these authors writes in reference to 'Alau-d-din's raids upon Bhilsa and other districts in Malwa that "wherever in the forest or by the bank of the river, there was a Mawas, whether in cultivated land or in wilderness, he trod it under foot with his army". (Text, Khazāin, S, l. 11. Tr. Habīb. 5).

Rayerty's rendering, "they sought shelter among the independent (Hindu) tribes" (Tr. 705 and note) is, notwithstanding his lengthy justificatory note, of doubtful validity. I venture to say that mawas does not signify a person, " a tribe or a tribal chief", but a district or tract of country. The plural form selwis which frequently occurs in the T.N. (247, l, 2 f, f,; 259, l, 1; 260, l, 15; 280, l, 17; 285, l, 3 f, f,; 287, l, 10; 291, 1. 9: 294, 1. 4 f. f.: 306, 1. 6: 312, 1. 2) indicates that it is a neuter noun, employed to designate a place and not a person. If all the passages in which it occurs are examined, it will be found that the word is associated with tracts of broken country, regions covered with jungle or cut up by glens, ravines or impracticable defiles, in which mounted troops and cavalry charges are ineffective. Thus, in the first of these passages (Text, 247,) the reference is to the Mawāsāt on the frontiers or outlying tracts of Oude and Tirhūt, in the fourth (p. 280) to the hilly region round Mayapur (Hardwar) and Rurki, in the fifth (p. 285=361 infra) to Rewari in the mountainous district of Mewat, in the sixth (p. 287 = 362 post) to Jalali and Deoli in Etawa district with its intricate and dangerous ravines, in the seventh (p. 291 = 366 post) to the country of Dalkimalki, the "arduous defiles, rugged mountains and numerous jungles" of which are particularly noted, as if to justify the application of the term to it. In the eighth and last (Text, 306=375 post), "the of Bishnupur (?) on جنگلها و بورهٔ مضابق of Bishnupur the frontiers of Tirhut are also characterised by the appellation. In the passage under notice (Text, 221, 1.2 f. f.), the hills of Santur in Sirmur are associated with a Mawas (in the singular).

The word in both forms, in the singular as well as the plural number, is used in the history of Barani in two passages which are crucial, inasmuch as neither can be construed so as to support Raverty's conjectural interpretation. At p. 182, l. 4 f. f., Barani writes that when the rebel Chhajju was routed, he and his followers crept into an adjoining Mavās, and the chief (معنّد) of that Mavās sent them, after some days, to Sultān Jalālu-d-dīn [Khalji]. For Dowson's rendering see E.D. III 138. هم دران بردیکی مواسی بود در آن خریدند و سد از چند رور مقدم آن مواس او را بر سلطان حلال الدین و سناد.

Again at 491, last line, he states that when 'Ainu-l-Mulk was routed and his rebellion scotched, those of his adherents, cavalry as well as infantry, who fled across the Ganges fell in the Mawasat there into the hands of the Hindus, who despoiled them of their horses and arms For و آی سوار و یادهٔ اشان از کسک سلامت Dowson's rendering see E. D III 249 There are two . يرون آمده در مواسات مدست هدوان امتاد و اسب و سلاح باد داد passages in the Tārīkh-i-Mubārakshāhi also which are quite decisive Its author tells us that Muhammad Tughlaq's project of introducing a token currency failed, because "the Hindus and strife-mongers of the Mavasat of the Imperial territory openly constructed mints in every village and و هدوان و معدان مواسات و موالات ولايت در " struck copper muhrs there B. I Text 103, 12; see also Thomas, C. P K D 245 n) Elsewhere, the author states that the Sayyad Sultan Mubarakshah "crossed the Jumna at the ford of Nuh and Patal and attacked the village of Haroli and then marched to the Qasba of Atroli" (Text 207, 17; E D IV 63) This passage is copied in the T A 140, I 10 and also in F I, 165, 1 3 f f in which the sentence runs thus.

سلطان میارك شاه آب حون را عیره كرد ه موضع هرتولی را كه از مشاهبر مواس اود تاخت و ار آنجا نتر ولی رفت

B also tells us that Ibrahim Lody raided Bhungaon and "settled the disturbances in those Mawas", و آن مواسهارا باك كرد, (I 326.1 17,431 Tr See also T A. 175, 1 7 f f, F I 189, 1 16) This clinches the point. In another passage, B states that the place called Babuli [or Beoli], where Sultan Firuz Tughlaq built a town called Firuzpur is better known as Mavas. (Text, I 252 Tr I. 335-6) All this shows that Mavas was a tract or district which was a sort of sanctuary or place of refuge on account of the physical features which made it a natural fastness places. Baghelkhand, Tirhut, Etawa in the Duab, Bundelkhand and Sirmur, the more martial tribes among the indigenes had retreated after their expulsion from their old homes by the Muhammadan invaders and here they formed nuclei of national sentiment, perpetual centres of passive hostility which blazed forth into open revolt or aggression in times of Muslim weakness or disunion The physical features of Etawa district, which was a notorious Mauas, are thus described in the L.G. "The net-work of ravines which borders the Jumna and the Chambal in the north-west and south-east of Etawa district presents an inextricable maze which can hardly be equalled in the plains of India" (XII. 38) Of another natural fastness of the same type, which lies in the present Jalaun district, the writer states that it is indebted for its form to "the

intricate reticulation of ravines which fringes the rivers Jumna, Betwa and Pāhūj." (I. G. XIV. 18).

II. 355, l. 6 from foot. He reached Santur.

The explanation in the foot note is badly off the mark. The place meant is the Suntour Garh of Thornton, the old capital of the Rājās of Sirmūr. It lies on the route from Dehra [Dun] to Kunāwar about eight miles north of the former. Lat. 30°-25′ N., Long. 78°-5′ E. It is now a mere village, the capital having been removed to Nāhan in the seventeenth century.

II. 357, l. 10. They alighted at their gardens outside the city.

The text has المنافرون المنافر المنافرون المنافرون المنافرون المنافرون المنافرون المنافرون المن

There is really nothing 'contrary to truth' in what Minhāj actually says. It is the note of the Editors that is wrong. It is of course true that Baghdād fell ultimately and that the last pageant of the House of 'Abbās was put to a cruel death. But Minhāj is referring not to the final catastrophe, but to a preliminary skirmish at the commencement of the siege, in which the Mongols had sustained a defeat. "In this first trial of strength which took place at Takrīt", writes Browne, "the Caliph's soldiers succeeded in destroying the bridge by which Bajū Noyān intended to cross the Tigris. In another encounter which took place at Dujayl on or about January 11th, 1258 (4th Muharram, 656 H.), the Caliph's army achieved a trifling success in spite of the numerical inferiority of their forces". (L. H. P. II. 461). It is to this 'trifling success'

that Minhāj is referring. The regular siege began only on 22nd January and the Caliph gave himself up on or about the 10th of February He was wrapped in a carpet and beaten to death with clubs. (Ibid 462-3, see also Habību-s-Siyar II. iii. 81). It would appear that the tidings of the final disaster had not reached Dehli when Minhāj wrote this paragraph—a striking illustration of the tardiness with which intelligence travelled in those times and of the ignorance of one part of the world of epoch-making revolutions which were taking place in another

Rieu also adverts to the matter and has pointed out that the death of Must'asim is actually mentioned by Minhāj in a passage added some time later, in the chapter devoted to the history of the 'Abbāsides' (Folio 57 a in the British Museum MS of the T.N., Catalogue of Persian Manuscripts, I. 72) The passage he refers to will be found in the B. I. Text at pp 430-33

II 359, l 13 from foot. Ulugh Khān was sent to chastise the rebel inhabitants of Mewāt and to intimidate their Dec.

عراى دوم مساد متردان ميوات كه ديو ار ايشان در هراس باشد يو براى دوم مساد متردان ميوات كه ديو ار ايشان در هراس باشد suppress the turbulence of the rebels of Mewat, of whom the demons themselves must stand in horror"

The date, 16th of Ramazān, (1 19) is a slip The text reads 16th Safar, which is proved to be correct by what Minhāj himself says on pp 381-2 infra, where the advance guard is stated to have marched on 4th Safar and the whole army to have returned to the capital on 24th Rab'i I. II. 362, 1 2 from foot. The rebels of Jalāli and Deoli, and the Mawās in the Duāb between the Ganges and Jumnā.

Raverty reads 'Jarāli and Datoli' (Tr 809), though he admits that some of his Mss have 'Deoli' I venture to suggest with some confidence that Deoli is quite correct. It is Deoli-Jakhan in Etāwa. We learn from the Tārīkh-i-Mubārakshāhi that Khizr Khān, after suppressing the rebels in Kol, advanced into Etāwa and there destroyed "the village of Dehli, the strongest place in the possession of the infidels" (E.D IV 52, qv my note). It is the Duhlee of Thornton, who locates it in Etāwa, Lat 27°-2′N., Long 78°-52′E Jalāli may be Julowlee which he locates thirty-five miles south of Fatehgarh, but it is more probably what Seeley calls 'Joolee', and places fourteen miles south of Saket and ten north of Mainpuri on the route from 'Aligarh to Etāwa (Roadbook of India, Ed. 1825, pp. 20-21) The word used by Minhāj here is not Mawās but Mawāsāt, "Lib, the neutral plural. This proves beyond any doubt that places or localities and not persons or tribes are meant

II. 363, 1. 9. He laid siege to Uchh, one of the most renowned fortresses of Sindh, and equal to Mansura.

و ارض منصوره در بندان داد ; 287,1.7 from foot. ارض منصوره در بندان داد tory 'and the real meaning is that Ucheh was included in the territory or the province of Mansūra. Similarly, Ḥāfiz Abrū says that the river Sindh (Indus) "runs from the western sides of the mountains (of Kashmīr) into the country of Mansūra." (E. D. IV. 4). Minhāj himself says elsewhere that the army of Khilj and the forces of Khwārizm invaded in 623 H. "the lands of Mansūra [ادائي منصوره] one of the cities of Siwistān." (Text, 143, 1.3 f.f.; Dowson, 303 ante).

II. 364, 1.7 from foot. The numerous fissures on the bank of the river rendered the way impassable for the army.

289, 1. 3. Raverty contends ; الشكر اسلام را ال كثرت جر بركنار آب راه نباشد that جائر is wrong and that it is a truncated mistranscription of which is the right reading. He goes further still and avers that ... does not mean 'fissure' at all and that this 'supposed' meaning of the word is without authority. He understands by jazāir, "long narrow banks of sand or islands on the bank of the river." (Tr. 812 and note). But he is contradicted by Richardson, who gives 'crack, cleft, rent or fissure, particularly in the ground," as the meaning of the word. A 'Jarr' is really a ravine or a deep cleft formed in the ground by the action of a torrent. The Emperor Babur uses the word in this identical sense and explains it in such a way as to leave no doubt whatever on the matter. "While I rode carelessly along the ravine [in the Turki original as well as in the Persian Translation, 234, l. 2 f. f.] of the river, my horse got to where it was fissured and had begun to give way. I leapt off at once and flung myself on the bank; the horse also did not go down; probably however, if I had stayed on its back, it and I would have gone down together." (B. N. Tr. Beveridge, 655). Baihaqi also uses the word and says that the distorrents and خويها و جرها و مرا torrents and ravines.' (Text, 563).

II. 367, l. 15. At the beginning of Shawwal, the force returned to the camp with their booty.

The words in the text (292, l. 10) are سلخ شوال, which mean 'the end or last day of Shawwāl.' Compare 348 ante also, where it is stated that the fort of Dalki-Malki was taken on Thursday, the 24th of Shawwāl. The force must have 'returned' after that date.

II. 368, l. 11 from foot. Passing over the Jumna, it [the Royal army] encamped and engaged in operations against the Mawas.

As this passage is important in connection with the meaning of the word. Mawas, I may quote the original:

294, l. 4f. f. و كذارة جون لشكرگاه شد بنزو و جهاد اطراف مواسات مشغول كشتند The other side of the Jumna became the camping ground and they were engaged in holy war against all sides of the Mawāsāt." See my note on 355, 1 7 f. f. ante.

II. 369, l 1. The army of Islām was sent. .. against Kālinjar and Jamū

Raverty thinks 'Jamū' must be an error for Dāmoh, which lies, he says, 46 miles east of Saugor, Lat. 23°-52′ N., Long. 79°-25′ E. (Tr. 824 note). As Kālanjar is in Lat 25°-5 N, Long 80° 22 E, the two places can hardly be said to be in close proximity. Jajmau is phonetically a much nearer approach, but it is, in fact, almost equally remote. The closest phonetic approach would be Mau, an old town ten miles west of Chhatarpur, "once the seat of the Parihār Rājputs, where there are some remains and an inscription of about 1150 A C." (I G X 199-200) Chhatarpur lies about forty miles south-west of Kālinjār. But perhaps, Mahoba is meant

II. 370, l 7 from foot Bahar Deo Rai of Rantambhor.

Raverty calls him 'Nāhar Dīw' (Tr pp 818 and 828 and note) He admits that Bāhar is found in the Mss, but he contends that it is incorrect The fact is that this Rājā was named Vyāghra Deva or Vāgh Bhata Bāhar (Bāghar) is the vernacular form of 'Vyāghra' and Vyāghra Deva or Vāghbhata does not appear to have been ever called Nāhar Deva. We may be therefore sure that Minhāj wrote 'Bāhar' and not 'Nāhar'. The Hindu chronicle of Hammīradeva Chauhān leaves no room for doubt on the point Sir Wolseley Haig follows Raverty and calls him Nāhar Deo

"The Muslim historians," he writes, "style Vagbhata Nahar Deo. confusing him perhaps with a Meo chief who had probably allied himself to Vagbhata" (CH.I III, 516, the Italics are mine) But there is no warrant whatever for assuming any such confusion The existence of a Meo chief so named is highly problematical, if not altogether imaginary, and the probability of any alliance between him and Vagbhata is too shadowy for serious consideration. The name of the Raja of Ranthambhor is uniformly written 'Bahar Dev' in the BI text of Minhaj (292, 1, 2 f. f, 299. 1. 9) and its correctness is further shown by the fact that Amīr Khusrau also spells it in exactly the same way in a passage in the Khazārnu-l-Futūh He states that after the sack of Ranthambor by 'Alauddin Khaljı,' Jhain also was captured, which was an iron fort and an ancient abode of idolatry The temple of Baher Deo and the temples of other Deos were all razed to the ground" (E D III, 75-6 q v my note) Here, 'Bahır Deo' refers, most probably, to 'Vyaghra Deva' or Vaghbhata, the Raja who was the builder of the shrine and whom Minhaj describes as "the greatest and most illustrious of the princes of Hindustan." Bāhad 18 a name which occurs elsewhere also, e g in Bāhadmer (Bārmer) in Jodhpur and in a Nadole grant of V S 1213, 1156 A C (Ind Ant XLI 1912, pp 202-3). It was also borne by a son of Udayana Deva, the Minister of the renowned Siddha Raja Jayasinha (Merutunga

II. 375, l. 5. The soldiers of the Siwālik, of Hānsi, Sarsūti, Jind, Bar-233

Barwāla is about nineteen miles north of Ḥisār-Firūza. (Hunter, Imp. Gaz. II. 170; Jarrett, Āīn, Tr. II. 294). Constable 25 B c. Lat. 29°-22, N., Long. 75°-59, E. (Thornton). The reference to these places is important, as it shows that they were all included in Ulugh Khān's Jāgīr in the Siwālik, i. e., the old Sapādalaksha country. At 352 and 355 ante, the Siwalik is again associated with Hansi and at 297 with Hansi and Sarsūti. At p. 380, Hariāna is spoken of conjointly with the Siwālik. Hānsi was the capital of the old Chauhān kingdom of Sapādalaksha. Sawālak, lit. one lak and a quarter, is the vernacular form. II. 375, l. 16. They had, however, got a good start.

But the text has جون تفرقه بديشان راه بانت (306, 1. 3) and the meaning is that they [Qutlugh Khān and the other nobles who were being pursued] had separated from one another, i.e. formed straggling parties, been broken II. 375, l. 13 from foot.

Ulugh Khan joined the royal army at

Kasmandi is a small town in Lucknow district, five miles north-east of Malīḥābād, which latter is about fifteen miles north-west of Lucknow by rail. Malīhābād is shown in Constable, 28 B b. Kasmandi is again mentioned by Minhaj along with Mandiana (Text 260, 1. 6), i.e. Mandiaon, which was a Mahal in the Sarkar of Lakhnau. (Ain. Tr. II. 170). Kasmandi is an ancient town containing many old mosques and a cemetery called 'Ganj-i-Shahidan,' in which a great number of Musalmans, who were killed in a battle with the Hindus, some centuries ago, are said to be buried.

II. 378, 1. 7 from foot. And the forces of the fort of Multan fell back. 310, l. 10. "And the battlements of the fortress of Multan were demolished" (lit. 'swept off'). The fortifica-

From the hills of Balāla and Mankāla.

The names are variously written in the Mss. Balāla may be 'Bugiāl' which lies under the lofty hills of Balnath near Nandana in the Salt Range. Cunningham assures us that "Bugial is still occupied by the Gakkhars, who are also found in Gūliāna near Gujar Khān." (A. G. I. 132). Gūliāna, Gujar Khān and Jogi Tilla (Balnāth) are all marked in Constable, 24 E a. Babur says that he passed through "the village of the Bugiāl—a Gakkhar clan—which was near the hill of Jūd below Balnath Jogi (Nandana)". (E. D. IV. 240). But it is more probably Baganwāla, about fourteen miles east of Chhoa Sadan Shāh, near which the outer Salt Range makes a remarkable dip. There is a steep rocky hill here which has absolute command of the route across the range. (Gazetteer of Jhelum District, 46-47). 'Mankāla' may be Makhiāla, "one of the names by which the Salt Range, the hill system in the Jhelum,

Shāhpur and Miānwali districts, was known to the old historians, the other name being the Koh-i-Jūd'' (I G XXI 412) Makhiāla is registered in the Āīn as a Mahāl in the Sindh-Sāgar Duāb, which had a stone fort on a hill and also a salt mine (Tr. II 324) Makhiāla and Girjhāk (the old name of a place near Jalālpur) are mentioned as places in which Jāhāngīr used to hunt. (T. J II Tr. 181-2 Text 317, 1 9 f f.). But Mankāla may also represent 'Mangla', which lies about 15 miles north of Jhelum town Cunningham states that the Tilla, Jogi Tilla or Balnāth range is about "30 miles in length and occupies the west bank of the Jhelum from the east bend of the river below Mangla, to the bed of the Bunhār river, 12 miles north of the Jalālpur''. (A G I 164) Mangla is shown in Constable, 24 E a

II 398, l 6 from foot Burāk Hājib was in Kermān and had fortified himself in the city of Bardasīr

"There is some confusion," writes General Houtum-Schindler, "with regard to the names of Kirman, both as a town and as a province or kingdom, and we have the names Kerman, Kawashir and Bardasir original name of the whole country was Kermin A province of this was called 'Kurch-1-Ardeshir,' District of Ardeshir', which being contracted, became 'Kawashir,' and is spoken of as the province in which Ardeshir, the first Sassanian monarch, resided A part of this 'Kureh-i-Ardeshir' was called Bardasir or Bard-1-Ardeshir, and the present city of Kerman 'is situated at its north-eastern corner This town, during the middle ages, was called Bardasir" (JRAS XIII 491-2, Yule Tr Marco Polo, I 91-2) Bardasir and Kawashir are said by Yaqut to lie between Sirjan and the desert, two marches from the former (Barbier de Meynard, Dictionnaire Geogi aphique de la Perse, 93) Le Stiange says Bardasīr is the same as Kirman, but gives a different derivation, according to which the city founded by Aideshir was called 'Weh or Beh-Ardeshir', "the Good Place of Ardeshir," which the Arabs pronounced 'Bardasir' and the Persians 'Gawashir' (L E C 300-303)

II 399, l 18 The Sultan went to Parwan on the borders of Bamian, where many roads converge

This Parwan or Barwan was situated on the Bārān or upper portion of the Lohgar river and lay five or six manzils north of Ghazni, between Ghazni and Bāmān It should not be confounded with the Parwan or Parian defile in the Hindu Kush, which is mentioned in connection with Taimūr's invasion of the Siyāhposh country That Pariān (or Parwan) lay about eight miles north of Chārikār and is mentioned by Alberuni also (Tr Sachau I 259 = E D I 47 q v my note)

II 464, l 3 from foot Kirāt, Nūr, Lohkot and Lāhore

Nūr and Qirīt are the names of two rivers of Kāfiristān, which lies to the north of Lamghān Bābur speaks of the Nūr valley as "one of the two bulūks (divisions) of Lamghān. "Its fort is on a beak in the mouth of the valley and has a torrent on each side. It can be traversed only

by one road. It has the orange, eitron, and other fruits of hot climates. Its wines are those of Lamghan that have reputationThese people used to keep swine, but they have given it up in our time." (B. N. Tr. 210).

Elsewhere, he writes that "another tumān of Lamghān is Kūnār with Nūrgal. It lies somewhat out of the way, with its borders in amongst the Kāfir lands. The river of Chaghānsarāi (Scil. the Kūnār) enters it from the north-east, passes into the bulūk of Kāma, there joins the Bārān water (Scil. the Kūbul river) and with that flows east. The orange, eitron and coriander abound here. Strong wines are brought into it from Kāfiristān." (B. N. Tr. 211). In another place, he tells us that Ningnahār, Mandrāwar, the Nūr Valley, Kūnār, Nūrgal and Chaghāniyān were given by him to his half-brother, Nāṣir Mirzā as Jāgūrs. (Ib. 227). See also Ibid. 344, where these places are again mentioned in juxtaposition. The Nūr Valley is shown in the Map attached to Biddulph's "Tribes of the Hindu Kush."

The rivers Nūr and Qirāt are mentioned by Alberuni also as affluents of the Ghorwand (or main Kābul river), which they joined at Darūnta. (Sachau. I. 259). As Darūnta is near Jalālābād, these rivers must be looked for in the region to the north of the latter town and the valleys of the Nūr and Qirāt must be situated in the tracts drained by the Kunār, viz. in Swāt, Bajaur and some parts of Kāfiristān. The Kāfirs of the 'darrah' (valley) of Nūr are stated by Mu'atamad Khān to bave come to pay homage to the Emperor Jāhāngir when he was at Jalālābād. (Igbālnāma-i-Jāhāngīrī, B. I. Text, 268-9).

Sir Thomas Holdich thus explains the reasons for Maḥmūd's invasion of these inhospitable regions. "The Kunar valley," he tells us, "is of exceptional interest for many reasons. The ancient high road from Kābul to India through the Lamghān valley ran across to Bajaur. Consequently, former conquerors of India, (Alexander and Bābur for instance), who advanced from Kābul and were always much concerned in reducing the hill-tribes before they entered the plains of India, knew it well. It was, in fact, a necessity of their advance that the powerful coalition of the hill tribes who have ever dwelt between the Kunar and the Indus should be well thrashed before further operations in the direction of Lāhor and Delhi could be undertaken." (The Indian Borderland, 244). It was not Alexander and Bābur only who took care to see that the tribes occupying these valleys were "well thrashed." Tīmūr also led a punitive expedition against the Kators of Kāfiristān before invading India.

II. 469, l. 20. So he [Maḥmūd] left Ghazni [for Somanāth] on the 10th of Sh'abān 414 A. H.

The correct date is 10th [recte 22nd] Sh'abān 416 H. The year is given as 416 in the Text of Ibnu-l-Athīr. (Ed. Torbberg, IX. 241). 414 is an inadvertent error in this translation. The year given by Alberuni (S. II. 9), Gardezi (Z. A. 86-7), the T. A. (9, 1, 15) and Khwāndamīr (E. D. IV. 180) is 416 H. Firishta (I. 32, 11, 2, 6] says Maḥmūd started on

10th Sh'abān 415 and his error has misled Elphinstone (H I, 334) as well as Mr. Vincent Smith (O H I, 193) and Sir W Haig (C. H. I, III 23) who put the sack into 1024 or 1025—22nd Sh'abān 416 H. corresponded with Monday, 18th October 1025 A. C. The fort of Somanāth fell on Saturday, the 16th of Zī-l-q'ad 416 = 8th January 1026 (Ibnu-l-Athīr, IX 242) The fact that both the above week-days work out correctly is proof presumptive that the year was 416 H. Firishta's assertion on the point cannot outweigh the authority of Alberūni who declares not once but twice, that Somanāth was destroyed in the Hijri year 416, which the Hindus compute as the 947th year of the Shakakāla (II. 9 and 103). Now, Shaka 947 began on 2nd March 1025 and ended on 21st March 1026 A. C., while 416 Hijri ended on 21st February, 1026 A. C Qazvini also in his chapter on Somnāt states that Mahmūd arrived there in the middle of Zī-l-q'ad 416 H. (Āsāru-l-Bilād, Text in Gildemeister, 64, Tr. 207, see also E. D I 98).

II. 469, last line Yamînu-d-daula started from Anhilwara for Somnat etc

The route followed by Mahmud from Anahilwad to Somanath is mere matter of conjecture He is supposed by one writer (B G I.166 note) to have passed through Modhera to Mandal, thence by the Little Ran to somewhere near Patdi and Bajana and thence by Jhalawad and Gohilwad to Delvada and Somanath Major Watson thought that he marched by way of the Bhal, the country between Wadhwan and Vala, to the sea-coast and thence to Delvada and Somanath (B G. VIII. Kathiawad, 610) Whatever the real route, the images which are said here to have served as the Heralds of Somanath and were styled Shartans by the iconoclast, were most probably those in the great tank at Modhera This town lies in the Vadavli taluka of Kadi prant, 18 miles south of Pátan or Anahilwad It contains several monuments of Hindu architecture, one of which, popularly known as Sītā's Chāvdi, is very richly carved. (I G XVII. 381) The great tank or kund also with a large number of "small niched shrines" still exists. Modhera is mentioned as the place where the idols were found in the Qasidas written by Farrukhi on the subject, which is reproduced entire in the Majm'au-l-Fusahā (I 452-3). The stages in the itinerary from Multan are there's given as Ludrava [Lodorva near Jaisalmir], Chikudar, Nahrwala, Mundhër [Modhera] and Dewalwara (Delwada) There is a good illustration of the porch of the temple at Modhera in the Ras Maia, (Ed. 1924, I 104). See also Burgess, Architectural Antiquities of Northern Gujarat, 243-4, I G. XVII, 381

II. 473, last line. When Mahmud resolved upon returning home from Somnāt, he learned that Parama Dev one of the greatest Rājās of Hindustān was preparing to inter-

The Raia who is said to have made preparations to intercept

Maḥmūd's retreat from Somanāth is called Param Dev by Gardezi (87, 1. 5.) and the T. A. (9, 1. 22), but Bīramdev by B. (I. 18, Tr. I. 28). Firishta (I. 34, 1. 9 f. f.) asserts that he was the Rājā of Ajmer, but Ajmer was not in existence at this time. In the C. H. I. (III. 25), the name of the Rājā is cautiously withheld and he is merely called Rājā of Sāmbhar. The progress of Hindu epigraphic research now enables us to solve the riddle and say that the name of the Rājā was not Param Dev, but Vīrama or Vīryarāma Deva. He was the great-great-nephew of Vigraharāja II, the Chauhān ruler of Sāmbhar, and he is known to have been reigning about 1030 A. C. (Duff. C. I. 277; Epig. Ind. II. 116; H. M. H. I, III. 146; H. C. Ray, Dynastic History of Northern India, II. 1069).

We may then take it that the right reading is Loran (Vīrama) Deva and not Param Deva, as in the modern copies. Dr. Nāzim is mistaken in calling him Param Deva and speaking of him as the ruler of Abu. (M. G. 119). The names of the Paramāra chiefs of Ābū also are known to us and no such name as Paramdev is found in the list of the dynasty. (Ray. D. H. N. I. 928-9). Moreover, they were mere feudatories, whose resources in extent of territory, man-power and sinews of war in general were so exiguous, that they would not have dreamt of defying a great ruler like Maḥmūd. The name 'Vīrama' occurs in other dynastic lists also, c. g. those of Dholkā, Gwālior and Mārwād. (Duff. C. I. 185, 306, and 297).

Alberuni tells us that Mahmud destroyed the capital of Gujarāt which was called Narāna or Narāin. (E. D. I. 58). 'Utbi also mentions an expedition to Narāin. (36 ante). As this kingdom of Gujarāt was, almost certainly, identical with that of Sapādalaksha which was ruled over by the Chauhāns, it is easy to understand Vīram Deva's action. He was only paying off old scores and gratifying an ancient grudge.

II. 486, last line. In this matter, Shamsu-l-Kāh Khwāja Ahmad Hasan was made mediotor.

Shamsu-l-Kāh is nonsense. His title was Shamsu-l-Kufāt, شفش الكفات ('Utbi, Text, 346, l. 8; Browne, L. H. P. II. 105; Siyāsatnāma, Bombay Lith. Pt. i. Ch. vii. 51, l. 12; Part ii, Ch. xl. p. 53, l. 13).

II. 490, l. 8. The origin of my quarrel with him [Hasan Sabbāh].

This story is now rejected as unhistorical on account of the country.

This story is now rejected as unhistorical on account of the chronological difficulties in which it is involved. The 'Wasāya' is more or less sophisticated and it is known to have been compiled not earlier than the 15th century, though Ethé is inclined to think that "it rests on a real basis of tradition and to concede to it greater authority" than Rieu docs in his B. M. Cat. 446. See also Mr. H. Bowen's article in J. R. A. S. 1931, p. 771. But however that may be, this anecdote about the 'Three Schoolfellows' is now discredited by almost all scholars. "Its fundamental assumption is that two persons (Hasan-i-Sabbāh and 'Umar Khayyām) who died at an unknown age between 517-518 A. H. (1123-24 A. C.) were at school with Nizāmu-l-mulk who was born in 408 H. (1017 A. C.) and was murdered in 485 H. This is hardly, if at all likely, and Houssmanns.

has suggested that this Nizamu-l-mulk was not the famous minister of Malik Shah, but Anushirvan bin Khalid, who bore the same title and was the Vazīr of Muhammad bin Muhammad bin Malik Shāh who reigned from 1117-1131 A.C. This Anushirvan bin Khalid is known to have been acquainted with Hasan-i-Sabbah in his youth and this legend is therefore another illustration of the Oriental story-teller's habit of 'transferring remarkable stories from one remarkable man to another'." (Browne, L H P II 191-2) The actual date of Hasan's birth is not known, but he was apparently very young in 1071 A. C (464 H), when he first took the Ism'aili oath. He was sent to Egypt in 1076 A C and returning to Islahan, founded the 'New Propaganda' in 1080 A C (Ibid 202-3 See also Browne's art 'Yet more Light on Omar Khayyam' in J R A S 1899, p 499, Houtsma E I II 276) Lawrence Lockhart, who has lately re-examined the question in the Bulletin of the School of Oriental Studies (V Part IV), thinks that Hasan was not born earlier than 1053 or 1052 A C and that he died on 23rd May 1124 A C Though it is possible to say, in the light of recent research, that the story is found in some older works than the Wasaya, e g in Rashidu-d-din's monumental Jām'iu-t-Tāwārīhh, and the still earlier Sarguzasht-1-Sayyıd-nā (an old Ism'āīlı Biography of Hasan), "the glaring disparities in easily verifiable dates are absolutely fatal and rule out the possibility of this picturesque compact"

II 499, l 16 When Khwija Ahmad was dismissed, Khwaja Hasnak Mishkāti was appointed in his place

'Mishkāti' is an error for 'Mikāl' or 'Mikāili' (Khwāndamīr in E D IV 151) Hasnak's real name was Ḥasan bin Muhammad-al-Mikāili (Z A 96, l 6 f. f , F I 38, l 11 f f.) Mishkāti (recte Mushkān or Mishkān) was the surname of Abu Nasr who was also a minister of Mahmūd and Mas'ūd, but a very different person altogether.

II 500, l 7 from foot The Story of Dabshilim

This story of the two Dābshilīms has exercised the ingenuity of many modern authors and several explanations have been suggested Tod advanced the conjecture that the reference was to the Dābhis—a tribe which is said by some to be a branch of the Chāwras, or Chāpotakas, and that the name is composed of 'Dābhi Chāwra' (A A R, I 122 and note) Elphinstone (H I 337 Note) and Sir Wolseley Haig (C H I, III. 503) have accepted this not very tenable theory, but the Dābhis are a very obscure and insignificant sept and they have never been of any account or played a notable part in the history of Gujarāt A rival hypothesis that the name is derived from Durlabha and Vallabha Solanki seems to me to be more plausīble Mūlarāja Solanki died in or a little before 998 A C and was succeeded by Chāmunda who abdicated after some years and went on pilgrimage He had three sons, Durlabha, Vallabha, and Nāga Rāja Chāmunda abdicated and installed Vallabha himself, but the latter died soon afterwards of small-pox. Durlabha then ascended the throne.

He reigned from circa 1010 to 1022 A. C. and Bhīma, the son of his brother, succeeded him. Hemachandra states that "Durlabha, wishing to retire from the world, offered the kingdom to Bhīma, that Bhīma declined in favour of his father, Nāga Rāja, that Nāga Rāja also refused and that both the brothers persuaded Bhīma to accept it, after which both of them 'ied together. Such a voluntary double suicide is evidently most unlikely and points to Bhīma having secured the succession only after a complicated system of intrigue." (B. G. I. i. 162-3).

It was common at this time for disgruntled, discomfited or unambitious princes who were in the line of succession, to ostensibly adopt the religious life and become ascetics, with a view to disarm hostility and avoid the risk of poisoning, assassination or imprisonment. The solitary survivor of "the most eminent family of Dabshilim who was serving and worshipping God in the habit of a saint" was either Durlabha himself or a son, legitimate or illegitimate, or some near relative or connection of Durlabha who had turned anchorite, because he had been persecuted and "seized several times by his brother." The other Dabshilim, who was still "the chief of a principality" was another cadet of the reigning house, but his relationship to the most recent occupant of the throne was so distant or indirect, that it did not count for much and he could not be regarded as a dangerous rival or competitor. He was thus secure and had not thought it necessary to become a Sanyāsi. Such claims as he had were derived from Vallabha, while the pretensions of the ascetic were founded upon his propinguity to or identity with Durlabha. ولب or ولب can be easily mis-جاورا than to شانكي is certainly nearer to شلبم and شابع is certainly nearer or even شاورا. The story itself is undoubtedly unhistorical and the details imaginary. The chronology also is impossible, as Mahmūd is known to have returned to Ghazni in 417 II. The name Dabshilim is only a literary fiction or reminiscence from the Kalila wa Dimna and the dénouement is merely an edifying tale of poetic justice, an apologue to inculcate and point a moral of the 'Biter Bit' type.

II. 504, l. 14. Nigāristān, the name of the work, expresses by the abjad, the date of its composition, A. H. 959.

This is a miscalculation. The abjad value of الكرستان [Picture-gallery] is only 782 (50 + 20 + 1 + 200 + 60 + 400 + 1+50). The date of composition can be obtained only when the word واقع [Events] is added to تكارستان. The value of واقع (6+1+100+70) is 177; 782 + 177=959. This is what is stated in the versified chronogram with which the work concludes. (Rieu, B.M. Catalogue, I. 106; Muqtadir, Bānkīpur Catalogue, VI. 45). II. 508, l. 11 from foot. Mas'ūd repents of his avarice.

This story is translated by Elliot at second hand from the Zīnatu-l-Majālis, but it is one of those borrowed by its author from 'Awfi. (III. Chap. xvi. No. 1696; J. H. pp. 62, 225). The Tārīkh-i-Nāṣiri quoted by the author is the work of Baihaqi, in the published text of which the anecdote will be found related at length. (pp. 311-5). The

immediately preceding story of 'Abdu-r-Rahman Khal is also from 'Awfi. (HI xix No 1735, J H pp 82, 229)

II. 510, l. 1 Ibrahim's lack of qualified officials

This anecdote also has been lifted by the compiler of the Zinat from 'Awfi (I vii 406, J.H. p 155) The story which follows is also from the same source (I. vii 405, J. H. Ibid) Ibrāhim is said to have written a book entitled Dastūru-l-Wuzarā, a Handbook of Political Science, for the guidance of his ministers. It is one of the ninety-three works cited by 'Awfi as his authorities. (J. H. 67-68 and 224)

II. 512, l 15. The Khwaja made a report of the facts which he addressed to Abu-l-Fazl, the financial minister (Sāhib-i-dīwān-i-risālat)

This Abu l-Fazl was Abul Fazl-ī-Baihaqi, the historian. He was not the 'Financial Minister', but the Head of the Department of Correspondence or of the Diplomatic Chancellery, which is the real meaning of Dīwān-i-Risālat At 197 supra, Baihaqi himself tells his readers that he was in charge of the Dīwān-i-Risālat in the reign of 'Abdur-Rashīd. (Text, 122) The Sultān's correspondence with foreign princes, governors of provinces and other high officials was conducted by this minister, who also received the secret and confidential reports from the Barīds and Mushrifs as well as other diplomatic agents

II 549, l 23 Sultan Jalalu-d-din Mankbur ni

The orthography, pronunciation and signification of the sobriquet are alike the subject of controversy D'Ohsson says that it is 'Mankbarni' and derives it from 'Mangou,' Eternal, and Birti,' or 'Virdi,' given, e God-given (Histoire des Mongols, I 195). Von Hammer-Purgstall thinks it means 'flat-nosed' Raverty and Ranking are in favour of 'Meng', mole and 'būrūn', nose, e e having a mole on the nose (T. N. Tr 285 and 299, Budāuni, Tr. I 91 note) As the epithet is inscribed also on his coins, and spelt there as Are the epithet is inscribed also on his coins, and spelt there as Are the epithet is inscribed also on his coins, and spelt there as Are the epithet is inscribed also on his coins, and spelt there as Are the epithet is inscribed also on his coins, and spelt there as Are the epithet is inscribed also on his coins, and spelt there as Are the epithet is inscribed also on his coins, and spelt there as Are the epithet is inscribed also on his coins, and spelt there as Are the epithet is inscribed also on his coins, and spelt there as Are the epithet is inscribed also on his coins, and spelt there as Are the epithet is inscribed also on his coins, and spelt there as Are the epithet is inscribed also on his coins, and spelt there as Are the epithet is inscribed also on his coins, and spelt there as Are the epithet is inscribed also on his coins, and spelt there are the epithet is inscribed also on his coins, and spelt there are the epithet is inscribed also on his coins, and spelt there are the epithet is inscribed also on his coins, and spelt there are the epithet is inscribed also on his coins, and spelt there are the epithet is inscribed also on his coins, and spelt there are the epithet is inscribed also on his coins, and spelt there are the epithet is inscribed also on his coins, and spelt there are the epithet is inscribed also on his coins, and spelt the epithet is inscribed also on his coins, and spelt the epithet is inscribed also on his coins, and the epithet is inscribed also on his coins, and the epi

It may be therefore permissible to invite attention to a passage in which Minhāj seems to me to throw welcome light on the matter and provide the clue to a new and less unsatisfactory explanation. In his account of 'Izzu-d-dīn Kabīr Khān-i-Ayāz, he states that as that most renowned hero was known to and spoken of by the common people as Ayāz-i-ḥāzār marda, Sultan Shamsu-d-dīn Īltutmsh bestowed upon him the Turki title of Mangīrni (or Mangbirni), and that Ayāz became famous thereafter as Kabīr Khān-i-Mangbirni (TN Text, 234,1 10) This means that the Turki

Mangbirni (or Mangirni) is synonymous with the Persian Hazārmarda, i.e., a hero or paladin who was a match for a thousand braves. It is scarcely necessary to stress the fact that this is just the kind of elacidation that is wanted and which would meet the requirements of the case. It is certainly more appropriate than any of the others and it is just the sort of honorific title that we might expect Jalālu-d-dīn himself to assume, or his subjects to bestow upon their intrepid prince and the outside world to endorse with shouts of acclamation and approval.

'Hazārmard' appears to have been a common title for a renowned pahlicān or warrior. Bilādūri mentions 'Umar son of Hafs, son of 'Usman-i-Hazārmard as Governor of Sind under the Khalif Mansūr. (E. D. I. 127, 445; Murgotten's Tr. II. 231; Dust, C. I. 67). In the Siyāsatnāma also, it is said of 'Ali Nūshtigīn who was a Sipahsālār of Maḥmūd of Ghazna, that he 'was a very great hero and regarded as a match for a thousand men'. او دا با هزاد مرد تهاده بردند. (Pt. I. Ch. vi. p. 49, l. 3).

VOL III. THE SLAVE, KHALJI AND TUGHLAQ DYNASTIES.

III 6, l. 3. He [Rashīdu-d-dīn] follows 'Utbi implicitly taking out not only the facts, but giving a literal translation even to the images and similes.

The statement stands in need of qualification Rashid has not taken his account of Mahmud from the original Alabic of 'Utbi, but bodily conveyed to his own pages the Persian version of Jurbadhaqani. The "literal translation of the images and similes," for which Sir H. Elliot gives him credit was made, in the first instance, by Jurbadhaqani. Rashid has merely appropriated it all without acknowledgment and ploughed with another man's heifer (Barthold, Turkestan Tr. 50) Mirkhwand also has pilfered entire passages almost word for word from the Persian Tanjuma-i-Yamīni (Nāzim, M.G. 10, 12, 171-3)

III 21, l 24 and foot note All at once an enemy oppressed both Turks and Arabs

Dowson complains in the footnote that "the meaning of the words ترك عت كرد is not obvious" But that is only because the copyist has interpolated the wāv or conjunction without warrant. The true reading must be رك الري عدت كرد "plundered, ravaged, sacked, burnt and harried the country as the Turks were wont to do" The phrase is used by Minhāj در مقاله سلطان ترك تار ميكرد و عليجي لشكر را رحت مداد (T N 74, 1.6), which Raverty renders thus "and in opposing the Sultans, used to make irregular attacks and harass the foragers of the Sultan's army" (Tr 378) Nizāmu-d-dīn Ahmad says that after the death of Muhammad Tughlaq ميكردند (T A 112, 1 5 f. f.) Elsewhere he quotes this couplet ميكردند (120 كني ميكردند) عنوان خود تركناري كني - كه كسيشك اشي و اري كني حر دليه تركناري كني - كه كسيشك اشي و اري كني حر دليه عيال ناطلش در سامد (264, 1, 6 f f.) Other examples will be found in the Maāsti -t-'Alamgīri, المرابع خود تركناري أرك تار سياه صرت المش معرى حر دليه عيال ناطلش در سامد (286, 1, 4 f f), Maāsti u l-Umarā, (B.I Text), I. 419, 1 3 and Yazdı, Zafarnāma, (II 122, 1, 11)

Steingass says ترکتاری or ترکتاری means "a plundering excursion conducted with rapidity" It is, in fact, a lightning raid, marauding incursion or predatory foray in the Turk or Tatar style

III 24, l 2 Tazjiyatu-l-Amsār wa Tajriyatu-l-Āsār.

Dowson gives the title as above and says it means 'A Ramble through Regions and the Passing of Ages,' but Rieu (B M Cat, I 161) as well as Sachau and Ethe (Bodleian Cat No 147, Col 84) and Muqtadir (Bānkīpur Cat VI. s n) read it as "Yearly at Tājzīyatu-l-Amsān wa Tazjīyat-l-A'asān This has been translated by Sir Gore Ouseley as "Fates of Cities and Events of Ages," (Biographical Notices of the Persian Poets, 230) Dr Barthold is in favour of rendering it as "Division of Provinces and Passing of the Times" (Turkestan, Tr 48 note), and E G. Browne of "Allotment of Lands and Propulsion of Ages" (Li H

WASSAF

P. III. 67). All of them read it just as Rieu does.

III. 29, 1, 11. White amber is the dregs of its sea etc.

'White amber,' also called 'Grey amber,' and 'grisamber' (Milton, Paradise Regained, II. l. 344) is the same as ambergris. Red Bakkam wood (l. 12) is known as Bresil, Brazil or Sappan wood. It is the wood of Caesalpinia Sappan, from which a ruddy dye was prepared. (Yule, H.J. s. v. Brazilwood). The "fragrant wood of Mandal" is Eagle-wood or Aloewood. Mandali is said by Abul Fazl to be the specific designation of the best kind of aloewood. Other varieties which he mentions are 'Jabali, Samandūri, Qumāri, Qāquli, and Chīni (Chinese) or Qasmūri [recte, Fansūri, from Pansūr, a town in Sumātrā]. (Āīn. Tr. I. 80; see also Yule, H. J. 151).

III. 31, l. 8. Siwālik contains 125,000 villages and Mālwā 1,893,000 towns and villagesGujarāt contains 70,000 villages and towns.

These figures are staggering in their magnitude. But similarly inflated and absurd estimates are found in Hindu literature. In the 39th Chapter of the Kumāra Khanda of the Skanda Purāna, which appears to have been composed about the 10th century, the total number of villages in all India is given as 96 krors and 76 laks! India is there divided into 75 provinces and Malwa is given 118,180, Sapadalaksha 125,000, and Gurjarāshtrā 70,000 villages. (Vaidya, H.M. H. I. II. 39-40). It will be observed that exactly the same number is assigned to the province of Gujarat by the Puranic writer and by Wassaf. The coincidence is curious and worth noting. Wassaf got it probably from Rashidu-ddin, whose account of India was composed with the help of a Kashmiri hermit named Kamalashri (Barthold, loc. cit. 45). Another instance of similar exaggeration is found in the Lokaprakāsha. Here, the number of villages in Kashmir is put down by Kshemendra - an author of repute who wrote about 1050 A.C.—as 66,063, whereas the actual number. according to the census of 1891, was only 2870. (Stein, J. A. S. B. 1899, p. 137 and note).

III. 36, l. 15. Jāsi Banadri......Hajnīr.

'Jāsi' is a manifest misreading of 'Ḥānsi', but it is not easy to say whether 'Banadri' stands for 'Indri' near Karnūl town (Lat. 29°-53′ N., Long. 77°-5′ E.), or Pundri in Kaīthal. Indri is frequently mentioned in the historical literature. (E. D. IV. 28, 242; V. 485). Indri was included in Sarkār Sahāranpur and Pundri in Sarkār Sirhind in Akbar's rentroll. (Āīn. Tr. II 291, 295). Pundri is now in the Kaīthal taḥṣīl of Karnāl district, and is in Lat. 29°-46′ N., Long. 76°-34′ E. (I. G. XX. 244). It was one of the strongholds of the Pundīr Rajputs who held Thānesar and Nardak. (Ibid). For Ḥajnīr see my note on I. 62, l. 10.

III. 49, l. 6. He ['Alāu-d-dīn] despatched Malik Nabū, Zafar Khān and Nānak Hindito conquer....Telingāna.

'Malik Nabū' must be Malik Nāib Kāfūr. 'Nabu' was probably the familiar or short form of 'Nāib' and the name by which he was addressed.

by 'Alāu-d-dîn Khālji Wassāf's summary of Dehli history is, as Dowson notes, of little value and the insertion of Zafar Khān's name here is an anachronism, as he had been killed several years before in repelling Qutlugh Khwāja's invasion of 697 H. 'Nānak Hindi'may be a miswriting of Malik (Alb) Nāyak [Ākhūrbak], who is said by Barani (320, 1.12), T A (80, 1.12), and Amīr Khusrau (72 infra,) to have been sent by 'Alāu-d-dīn to repel the invasion of 'Ali Beg and Turtāq But he is not mentioned by any historian in connection with the invasion of Telingāna or the Dekkan. Kāfūr's colleague in that compaign was Nasīru-l-mulk Khwāja Hājji, who may have been a Hindu convert, as he is called Panchami by Khusrau in the 'Ashīqa. (551-2 infra) The prefix 'Nāyak' probably accounts for his being styled 'Hindi' by Wassāf Pancham Sīngh is a Hindu name even now.

III. 50, l 6 He [the Rai of Madura] delivered up to Malık Kafur the country of Arikanna, as a proof of his allegiance.

The addition of a single dot to the fifth letter of the toponym would turn it into 'Arikatta,' [Arkāt or Arcot]. It may have been the Arcot near Vellore, where Clive first burst into fame But Yule (H J. s. v Arcot) points out that there is another town of the same name, which is in Tānjore Ibn Batūta speaks of a place called 'Harkātu,' which he reached on the first evening of his march inland after landing from Ceylon some where on the shallow coast of Madūra or Tānjore (Defrémery, IV. 187-8) There are several other places also called Arkāt.

III. 52, l 7 from foot Every crore being equal to a thousand laks.

Dowson suggests, with a view to exculpate Wassaf from a palpable error, that signify is a copyist's slip and that we should accept the variant, is a capacious earthen vessel calculated to contain a hundred lacs.' But this is very far-fetched and will not bear examination. Wassaf had no knowledge of the Indian vernaculars and there is no reason for being surprised at his misconception of the meaning of the Hindi Kror. Several otherwise well-informed European travellers of the seventeenth century can be charged with even more egregious blundering in regard to this identical word. Tavernier who visited India five or six times in 25 years (1642-1667) says that "a Kraur is equal to one hundred thousand laks" (Travels, Tr. Ball, I. 28) and exactly the same mistake is found in his contemporary, Thevenot (Voyages, Eng. Tr. of 1687, p. 52), as well as in the English chaplain Ovington. (Voyage to Suratt, Ed. 1696, p. 189).

A simple calculation will suffice to prove that Dowson's special pleading is futile. A thousand laks of coins would weigh 1000,000,000 grains, even if each coin was so small as to weigh only 10 grains. No potter could possibly make an earthen jar capable of holding and standing the weight of thirty five hundred maunds of forty pounds each.

III. 53, 1 12 from foot. He conveyed some of the royal treasures

MI. 63, 1. 1.

Dowson suggests in a note that this may be Namkill or Namakkal,

Dowson suggests in a note that this may be Namkul or Namakkal, He but Dr. Aiyangar objects that it is too "far out for the purpose," there thinks the name stands for some place called 'Mangalam', Imhuskily there but Dr. Alyangar objects that it is too tar out for the purpose. there thinks the name stands for some place called 'Mangalam'. Unluckily, there times the name grands for some place called mangalam. University, there are at least three places so called near Madura, Mela Mangalam, are at least three places so called near Moston Chota and Mangalam in the Weston Chota and Mangalam. are at least turee places so called near Mangalam in the Western Ghats and Mangalam on the Western Ghats are hone to coince the control of these hone in the control of the control o Mila (Lower) mangalam on the Western Grats and Mankil,

Sattur talique. Any one of these, he opines, may his fother Rut of the which Sundara Dandua manahad after mundaning his fother to which Sundara Dandua manahad after mundaning his fother to which Sundara Dandua manahad after mundaning his fother to which Sundara Dandua manahad after mundaning his fother to which Sundara Dandua manahad after mundaning his fother to which Sundara Dandua manahad after mundaning his fother to which Sundara Dandua manahad after mundaning his fother to which Sundara Dandua manahad after mundaning his fother to which Sundara Dandua manahad after mundaning his fother to which Sundara Dandua manahad after mundaning his fother to which Sundara Dandua manahad after mundaning his fother to which Sundara manahad after mundaning his fother to which Sundara manahad after mundaning his fother to which Sundara Dandua manahad after mundaning his fother to which Sundara manahad after mundaning his fother to which Sundara manahad after mundaning his fother to which Sundara manahad after mundaning his fother mundaning battur tatuqu. Any one of these, he opines, may have been the But as to which Sundara Pandya marched after murdering his father. to which Sunuara rangya marched after muruering his Tather, Dut as he admits his inability to choose between these three and determine he admits his inability to choose between tradic and Habrana Mahamadan

ne auming in chouse perween these three and determine the locality, we are no nearer a solution. (South India and Her Muhammadan, 10 cality, we are no nearer a solution to the property of and Note: and also him to the property of and Note: and also him to the property of and Note: and also him to the property of and Note: and also him to the property of and Note: and also him to the property of and Note: and also him to the property of the pr Tocality, We are no nearer a solution. (South more and the Khazainwi-Futidi, Invaders, 97 and Note; see also his Introduction to the Khazainwi-Futidi, ma Duct Hobib a greeni)

Tr. Prot. Paoid. p. XXXVII).

111. 54, 1. 1. Manar Barmul, the son of the daughter of Kales Dewar.

Raina at that time at Kanamhati near Kanamhati. heing at that time at Karamhati near Kalul Tr. Prof. Habib. p. xxxvii).

This name is not easily restored. The Raja referred to may be Ravivar man Kulashékharadeva Perumal of Kerala.

Tang name is not easily restored. The Kaja referred to may be kayivat have been man Kulashékharadeva Perumal of Kerala. man Kulasneknaradeva Perumut of Kerala. He is stated to have princess, born about 1266 A.C. (1188 Shaka), to have married a himself Lord born about 1266 A.C. (1188 Shaka), to have married a himself Lord born about 1266 A.C. (1188 Shaka), to have married a princess, and a state of the state orn about 1200 A.C. (1100 Shaka), to have married a randyan princess, taken possession of Kerala in 1299 A.C. and proclaimed himself Lord taken possession of Kerala in airding a defeat man a Dandya princess, to have married a randyan princess. taken possession of Aerala in 1229 A. C. and proclaimed himself flows Panadount in 1312 after inflicting a defeat upon a 142 Morate Paramount in 1312 after medical raid and TV 145 142 Morate Paramount in 1312 after inflicting a defeat upon a 142 Morate Paramount in 1312 after inflicting a defeat upon a 142 Morate Paramount in 1312 after inflicting a defeat upon a 142 Morate Paramount in 1312 after inflicting a defeat upon a 142 Morate Paramount in 1312 after inflicting a defeat upon a 142 Morate Paramount in 1312 after inflicting a defeat upon a 142 Morate Paramount in 1312 after inflicting a defeat upon a 142 Morate Paramount in 1312 after inflicting a 142 Morate Paramount in 142 Morate Param Paramount in 1912 after inmering a defeat upon a randy prince a defeat upon a randy Wassar's named Vira (Duff. C. I. 203 apud Epig. Ind. IV. 145, the denotic title of the amed Vira (Duff. C. I. 203 apud Epig. Ind., the denotic title of the amed Vira (Duff. C. I. 203 apud Epig. Ind.) named Vira (Duff. C. I. 203 apud Epig. Ind. IV. 145, 148). Waṣṣāf's the Barmul' looks like a miswriting of 'Perumal,' the dynastic title of the 'Barmul' looks like a miswriting of Wāra' or 'Manār Barmul' may be 'Māra' or 'Manār Barmul' may be 'Māra' or 'Manār Barmul' ha Mārabaranan (Māravarman)

be Mārabarman (Māravarman). I adar Jaipāl, who was killed 412 Hijri III. **59,** l. **6**. And after him be Marabarman [Maravarman].

It will be seen from this that Banakati (or Fanakati) has understood beruni's statement about Trilochanapala in the same way as Reinaud and Derum & Statement about Trinochanapaia in the same way as nematically defend the word which is responsible for the Grant Roll of the Romanapaia.

He has read the word which is responsible along that Romanapaia.

Li Goo my rote on R D TT 10 This along the Romanapaia. acnau. The has read the word which is responsible for the Banakati's and not is. See my note on E. D. H. 12. It is also clear that Banakati's and not is. See my note on E. D. H. 12. It is also clear that are constant of the constant of th ınd not المعلقة المعل Is an error for which has been deciphered as Brahmanpal the suggestion that the name which has been deciphered. tne suggestion that the name which has been deciphered as Drahmanpal as (Tarjinpal). No such name as (Tarjinpal) is a mistranscription of الرحنال) is a mistranscription of الرحنال) is a mistranscription of الرحنال) الرحسيان) Is a mistranscription of المرحسيان (Tarjinpai). No such name as Persian Brahmanpāl occurs in Jurbadhaqāni or any of the other Arabic or Persian histories of Mahmira

His Mahmua's Features were very ugly.

(Tar. Guz. 395, 1.8). But

Hamdulla's own words are 39. Italy

Hamdulla's own words are 39. Italy

The her are 39. Italy III. 63, 1. 1. His [Mahmud's] features were very ugly. F. who has copied the story puts it more mildly. F. who has copied the story puts it more muchy. Use devoid of outward with the Sultan [Maḥmūd] was devoid of outward. "The Sultan [Maḥmūd] was devoid of Nizāmu-l-mulk, "The Sultan [Maḥmūd] was devoid of outward. The sultan [Maḥmūd] was devoid of outward. (or physical) beauty and grace. (1092-3 A.C.), and appears to be the earliest which was completed in 485 H. (1092-3 A.C.), and appears to be had not a which was completed in all that is said is that the said is histories of Mahmid. which was completed in 455 H. (1092-3 A.U.), and appears to be the earnest he had not a was completed in 455 H. (1092-3 A.U.), and appears to be the earnest he had a not a he had some face in 455 H. (1092-3 A.U.), and appears to be the earnest he had not a he had not a he had appears to be the earnest he had appears to be the earnest he had appears to be the earnest he had appears to be the had not a he had not a he had not a he had appears to be the had not a he had appears to be the had not a he had not a he had appears to be the had not a he had not a he had appears to be the had not a he had not a he had appears to be the had not a he had appears to be the had not a he had appears to be the had not a he had appears to be the had not a he had appears to be the had not a he had appears to be the had not a he had appears to be the had not a he had appears to be the had not a he had appears to be the had not a he had appears to be the had not a he had appears to be the had not a he had appears to be the had not a he had appears to be the had not a he had appears to be the had not a he had appears to be the had not a he had appears to be the had appears to be the had not a he had appears to be the had not a he had appears to be the had not a he had appears to be the had appears source or this anecdote, all that is said is that you you, go, ne had Nazim handsome face. (Ed. Schefer, 44; Bombay Lith. Pt. i. p. 49, 1. 9). Thousand another from Thousand and the insinuation that Mohanid manufacture the insinuation that nandsume lace. (Eig. Scherer, 44; Bombay Lith. Ft. 1. p. 49, 1. 9). Dr. Parimire repudiates the insinuation that Mahmud Was ugly and quotes that anthor Athir's Kamilu-t-Tanarikh (VIII 924) a research in which that repuulstes the msinuation that Manmud Was ugly and quotes from Lundrig Athir's Kāmilu-t-Tawārīkh (VIII. 284), a passage in Which that author

states that he had "a fine complexion, handsome face, small eyes and a firm round chin covered with a scanty beard" (M G 151 Note).

III. 64, l. 8 It is a rule among the Hindus that a King who has been twice made prisoner by Musulmans ought no longer to reign.

This 'twice' appears to be an interpolation or embellishment of Hamdulla's. It has been copied by Firishta. (I. 24, 1 12). But all that 'Utbi says is, 'If any (king) is taken prisoner by an enemy, ... it is not lawful for him to continue to reign ". (E D II 27)

III. 69, l. 14. His ['Alāu-d-īn's] accession to the throne on the 16th of Ramazān, 695 H. (July 1296)

In the 'Alīgarh Lithographed text of the Khazāin edited by Syed M'uīnu-l-Haq, the 16th of Ramazān is said to have been a Wednesday and 22nd Zi-l-hijja, 695 H., on which he "again mounted the throne" is stated to have been a Monday (p 11, l 10; 12, l 10, Tr Habīb, 6, 7). 16th Ramazān, 695 H., was Wednesday, 18th July, 1296 A. C., but 22nd Zi-l-hijja (Hisābi) was Sunday, 21st October, 1296 A. C. The discrepancy regarding the week day is not material 'Alāu-d-dīn must have reached Dehli on the 22nd Hilāli or Ruyyat = 22nd October, 1296 A. C, which was a Monday

III 71, l 9 [Ulugh] Khān sped swift as an arrow. . until he reached the borders of Jāran Manjhūr, the field of action.

These toponyms have not been identified, although the names are written in much the same way in the 'Ashīqa, ('Alīgarh Text, p 60, l. 1), the Tārīkh-i-Mubārakshāhi (Text, 72, l. 10), the T. A. (69, l. 10) and B (I 184, Tr. 249)

Some confusion has been introduced by an error in the B I Text of Barani, where 'Jālandhar' has been substituted (250, 1 11), but it may be safely dismissed as the interpolation of some ignorant scribe, though Dowson has followed it. (162 infra) He notes, however, that the Mss have 'Jadawa wa Manjur' and 'Jarat-mahud' It stands out clearly from the original that the battle took place close to the banks of the Sutley. Amir Khusrau tells us that Ulugh Khan "ordered the standardthey turned their bearers to bind their standards to their backs. faces towards the Sutley and without the aid of borts, they swam over the river, striking out their hands like oars impelling a boat. The Mughals seemed very brave before the victorious army had plunged into the river, but when the wave of Muslim troops reached the middle of the stream, they gave way . . . and fled desperately ?' (Trans. 23, Text. 36, last line) This means that the struggle between the two hosts centred round the passage of the river and the invaders were routed because the Dehli army was able to force it.

T venture to suggest that san error; for Machhūr [Machhwar] or Mechhūr, [Mechhiwar], e. Machiwārā or Machiwāra, which lies 27 miles east of Ludhiāna

It is a very old town and now lies "about four miles from the left bank of the Sutlej which formerly [i. e. before 1800 A. C.] flowed close to the town." (Thornton, 573). Its situation on the river has always made it a place of strategic importance and it was Humāyūn's crushing defeat of Sikandar Sūr at Machhiwāra which enabled him to reconquer the Punjāb. 'Alīwāl also, where the battle which decided the First Sikhi War took place, lies about forty miles west of Machhiwāra.

'Jāran Manjhūr' is once more mentioned in the $T\bar{a}r$. Mub. in connection with a later Mongol invasion of the Punjāb. In the Chronicle of the year 834 H., the author says that Shaikh 'Ali, the governor of Kābul, crossed the Sutlej at Tirhāra, made the inhabitants of the whole district from Jālandhar to Jāran Manjhūr his prisoners and returned along the banks of the Biah.' (Bibl. Ind. Text, 218, 1.4). Elsewhere, he states that in 753 H. Sultan Firūz Tūghlaq went out for Shikār in Manjhūr. (Ibid, 124, 1.1).

'Jāran 'may be the town of 'Jāgraon ' باكرن which lies 22 miles south-west of Ludhiāna. (Constable 25 Ab). A village called 'Chāhlan' or 'Chālan,' also lies about ten miles from Machhiwāra.

An alternative identification is also possible. 'Jāran' may be 'Zīra' and Manjhūr' Makhū,' (Constable 35 A b; I. G. Atlas, 32 D 2) in Firūzpur district, but the phonetic resemblance between the names seems slight.

III. 71, l. 17. Some Mughals were captured on Thursday, the 22nd of Rab'iu-l-Ākhīr in the year 695 H.

The year is palpably wrong. In the Text (37, 1.4) and new Translation (p. 23), the date is given as Thursday, 22nd Rab'iū-l-Akhīr, 697 H. The Julian correspondence of this date, 6th February 1298 A. C. was, according to the Indian Ephemeris, a Thursday. Barani (249, 1.1 f. f.), the T. A. (69, 1.10) and F. (I. 102, 1.18) put this invasion into the 2nd year year of the reign, i.e. 696-7 H. The correct year must be 697 H. 22nd Rab'ī II. 695 is impossible, as 'Alāu-d-dīn murdered his uncle four months later, in the Ramazān of that year.

III. 72, l. 14 from foot. Malik Akhir Beg, Mubashara.

The reading of the sobriquet in the 'Aligarh text is Malik Akhurbak-i-Maisara, Master of the Horse of the Left [Wing] (Text. 41, l. 1; Tr. 26), which may be correct, as Barani in his list of Sultan Firuz Tughlaq's grandees mentions a Sar-salāhdār-i-Maisara, and a Sarjāndār-i-Maisara, as well as a Sar-salāhdār-i-Maimana and a Sarjāndār-i-Maimana. (527, ll. 14-16). We also learn that Ṣafdar Malik Sultāni was Ākhurbak-i-Maisara under Muḥammad Tughlaq (Ibid, 454, l. 12), while Haibat Khān had occupied the same post under Balban. (24, l. 10). Amīr Khusrau also mentions a Qarā Beg-i-Maisara. (Kh. F. Text 96, l. 5, Tr. Ḥabib. 65).

III. 72, l. 10 from foot. He obtained victory over them [Turtāk and 'Ali Beg] on the 12th of Jumāda-s-sāni, A. H. 705.

The week-day is not given by Elhot, but it is stated to have been Thursday in the Lithograph, (p. 41, 17, Tr. 27) and it is correct. The Julian date was 30th December, 1305 A. C.

III. 74, l. 1. Invasion under Igbal Mudbir and Mudabir Tai Balwi

The first name appears in the 'Ashīqa also as Iqbāl-1-mudbir, (Text, 62, 1.1) and Elliot himself renders it as 'Ikbāl the stubborn,' at 548 infra. Barani calls him Iqbālmand, which literally means 'fortunate' or 'lucky.' The fact is that Khusrau is punning upon the name. He abuses him as Iqbāl-i-Mudbir, 'Iqbal the Unlucky' So the name of the second leader is written as Mudābir Tāi Balwi. 'Mudābir' signifies 'one who turns his back or runs away in a battle', i e a coward. Elliot's Tāi Balwi is, as I shall presently show, a misreading of Tābūi

Persian authors are inordinately fond of antithetical jingles upon words Budāuni, for instance, speaks of Mallū Iqbāl Khān, who betrayed Nāsiru-d-dīn Nasrat Shāh and was afterwards defeated and slain by Khizr Khān, as 'Iqbāl Khān-1-Mudbir' (Tr. I 268) Nizāmu-d-dīn Ahmad also puns upon the name of M'asūm Kābuli and calls him M'asūm-1-'Āsī. 'M'asūm' means 'sinless' and 'Āsī' means 'sinful.' (E.D.V 415). Similarly, Yazdı describes the commander of the fort of Loni whose name was Maimūn (Auspicious), as Maimūn-1-Maishūm (Maimūn the Ill-omened). (Zafarnāma II. 86, l 11, 495 infia). Elsewhere, Yazdı says that a Rājā whose name was Bahrūz (Fortunate) was really Badrūz (Unfortunate) (Ibid Text. II. 151, l 4 f. f.). He speaks of Nusrat Khokhar, as بعد مدر دیگر (Ill. 57, 1.5 f f). Baranı also uses the phrases مدر دیگر (543 last line; 545, l. 9).

The name of the second leader of this invasion is read as 'Tāi Balwi' in Elliot's translation, but the correct form is 'Tābūi' or 'Tibūi' [باوی or عابوی] and this is proved by the following couplets in which Amīr Khusrau plays upon the name

III.74, l 20 The Sultan despatched Ulugh Khan for the destruction of Somnath on 20th Jumada-l-awal 698 H

Here again the 'Aligarh Text differs from Elliot's The date it gives is Wednesday, 20th Jumādī-l-awwal, 699 H (Text 50, 18, Habīb's Tr. p. 35). The invasion of Gujarāt is put by Barani (251, 1 10) and the T. A.

(69, l. 17) into the beginning of the 3rd year (697-8 H.). F. gives 697 (I. 103, l. 1), but B. has 698 (I. 189=Tr. I. 255). 20th Jumādīu-l-awwal, 698, was Monday, 23rd February, 1299; 20th Jumādīu-l-awwal, 699=Friday, 12th February, 1300. But 20th Jumādīu-l-awwal, 697, was Wednesday, 5th March, 1298. This would indicate that 697 is the right reading. 699 must be due to the usual confusion between — and — in the Semitic script. Hājji Dabīr has 697 H. (Z. W. 784, l. 18).

III. 75, l. 4 from foot. On the...3rd of Zi-l-K'ada A. H. 700, this strong fort [Ranthambhor] was taken.

This date, 3rd Zî-l-q'ad, 700 II., corresponds to 10th [or 11th July], 1301 A. C. According to the Hammira Mahā Kāvya. the fortress was stormed on a day in Shrāvan of the 18th year of Hammira, whose reign is stated to have commenced in V. S. 1340=1253 A. C. (Ed. Kirtane, Introd. 27; 47). It appears from the Tables in Pillai's Hindu Chronology, that 1st Shrāvan Amānta (as well as Purņimānta), 1358 V. S., corresponded to Thursday, 6th July, 1301 A.C. The month and year given by the author of the Kāvyā thus seem to be correct and the stronghold must have been stormed on the 5th (or 6th) of Shrāvan, 1358 V. S. The week-day is not stated in Elliot's translation, but it is given as Tuesday in the Text, (58, l. 8; Tr. 41). Calculation shows that 10th July, 1301 A. C., fell on a Monday. The discrepancy indicates that Khusrau's 3rd is again 3rd Ruyyat. If the week-day is right, the real date was the 11th of July.

III. 76, l. 2. The temple of Bahir Deo, and the temples of other gods, were all razed to the ground.

Aligarh Text 58, last line. ; اول بتخانه باهر ديو كه باهر ديو بدان استعانت داشت بشكست This may mean that the temple was dedicated to Bhairava Deva, i. e. to Shiva or to Bhairava, one of the 'ganas' or inferior manifestations of Shiva or Mahadeva. Abul Fazl says that there was an idol eighteen cubits high of Kāla Bhairav in the fortress of Kālinjar, (Aîn, Tr. II. 159) and this idol still exists there. (Hunter, Imp. Gaz. III. 336). 'Bhairava' literally means 'terrible' and is one of the epithets of Shiva himself, as Bhairavi is that of his wife. (Dowson, Dictionary of Hindu Mythology, s. n.), Shiva is also called Mahākāla. But 'Bhairava' does not much resemble 'Bāhir.' Khusrau, who was well acquainted with Hindi, is not likely to have spelt it as باهر Another explanation, therefore, may be that the temple had been founded by Bāhir Deo, who was Rājā of Ranthambhor, during the reign of Sultan Nāṣiru-d-dīn Maḥmūd, (T. N. in E. D. II. 367, 370. Text. 292, 1. 2 f.f.; 299. 1.8), for imploring aid from the gods. The Hammira Mahā Kāvya states that Bahad Deva or Vagbhata was succeeded by his son Jaitra Sinha who abdicated in favour of his son, Hammīra, in or about 1340 V.S. (1283 A. C.). (Kirtane's Introd. 26-7).

III. 76, l. 5. Rāi Mahlak Dez, of Mālwa and Kokā his Pardhān.

Hājji Dabīr also gives the name of the Rījā as Mihlak Deo. (Z. W. 788, l. 12). F. (I. 115, l. 4) asserts that Koka was the King of Mālwā, but Wassāf agrees with Khusrau. He informs us that the country was in a

state of civil war on account of the intrigues of an over-ambitious minister who aspired to supreme power. Melaga or Megala (Mekala, or Mokala) is a name which occurs in the inscriptions of the Chudīsammā rulers of Junāgadh. (B. G. VIII 488, 498; Buigess, A. S. W. I., II. 164, Duff. C. I. 284) F. is followed in the C. H. I. (III 111), and the Rājā is spoken of there as Koka or 'Haranand' Khusrau is most probably right in stating that Koka was his *Pradhān*, or *Wazīr*, as he says in the 'Ashīga (550 infi a)

III 76, l 6 from foot This event [the conquest of Maliva] occurred on Thursday, the 5th of Jumada-l-awwal A. H 705.

Dowson throws doubt on the accuracy of this date and avers that it must be either wrong or "the event taken out of chronological order" But Khusrau narrates the events in groups and not in the *strict* sequence of time. The 'Aligarh Lith is in agreement with Elliot's Ms (Text 63, 1-13, Tr 46) 5th Jumādi I (*Hisābi*), 705 H., corresponded with Tuesday, 23rd November, 1305 A. C

B puts the conquest into 700 H (I 196,=Tr I 264) F. (I 115, I 5) gives 10th Jumādīu-l-awwal, 704 H Hājji Dabīr says Mandū was taken on Wednesday, the 2nd of Jumādī I 705 (788, I 13) The C H I (p 111) gives 9th December, 1305 H, which synchronises with 21st Jumādī I. 705 Sir Wolseley Haig has taken the year from Khusrau, but miscalculated the Julian correspondence

III 76, last line On Monday, the 8th Jumāda-s-sāni 702 H. the army started with a view to the capture of Chitor

The Julian equivalent, 28th January 1303, was a Monday.

III 77, l 3 The fort [Chitor] was taken on Monday, the 11th of Muhari am A H 703

11th Muharram, 703 H (Hisābi), corresponded to Sunday, 25th August, 1803 A C Khusrau seems to have again given the Ruyyat date, and if Monday is right, the exact Julian correspondence must be 26th August, 1803 A. C

III 77, l 8 from foot He [Kāfūr] arr wed there [at Deogir] on Saturday, the 19th of Ramazān A H 706

The Hisābi or Book-rule date synchronised with 24th March, 1307 A C and was a Friday This again proves that Khusrau's reckoning is in accordance with the *Hilāli* or *Ruyyat* method As the week-day is most probably correct, the Julian equivalent must be the 25th of March, 1307.

III 78, l, 4 On Wednesday, the 13th of Muharram, A H 708, the king set out on his expedition against Siwana

Hājji Dabīr gives the identical date and year, (788, 1 20), and the 'Alīgarh Text is in agreement with Elliot's Ms (p 74, 1.8), though the year is 710 H in the Translation (p 53) But it is again stated that "the dead body of the savage Satal Deo was brought before the lions of the imperial threshold" on Tuesday, the 23rd of Rab'iu-l-awwal, 708 H. (p 77, 1 12).

13th Muḥarram, 708 H., was Wednesday, 3rd July, 1308 A. C. 23rd Rab'iul-l-awwal, 708 H, was Tuesday, 10th September, 1308 A. C. This calculation proves that 708 is right and 710 H. wrong. The compiler of the $T\bar{a}r\bar{i}kh$ -i-Alfi, who has used Khusrau's, work, also gives 698 Rihlat (= 708 Hijri). (E. D. V. 166).

F. (I. 118, l. 11) puts it into 706 and the T.M. (78, l. 5) and B. (I. 196=Tr. 264), into 700 H., which shows how unreliable the chronology of these compilers is.

III. 78, l. 11. Malik Kamālu-d-dīn Garg.

The sobriquet is transliterated here as 'Garg'. Ranking has 'Kark' (B. Tr. I. 265, 267) and 'Garg,' (Ib. 282), while Sir Denison Ross writes 'Kurg.' (Z. W., Index, lxi). 'Karg' means 'rhinoceros' and 'Kurag,' a head rendered bald by the disease called scald head.' The correct form is really 'Gurg' (wolf). Khusrau puns on the by-name and says that Kamālu-d-dīn "excelled in killing lions as much as the wolf excels in killing sheep." (Text, 76, l. 2; Tr. 54). Elsewhere, he writes that "'Alāu-d-dīn, the just protector of his subjects, entrusted the flocks to the 'Wolf,' in order that he might guard the young she-goats from the thorns of his territory." (Text, 78, l. 5; Ibid. 55).

This word-play indicates that the nick-name was 'Gurg'. Kark, Garg and 'Kurg' are all demonstrably erroneous. Ibn Baṭūṭa, who was personally acquainted with Kamālu d-dīn's son, Malik Hūshang, explicitly states that the sobriquet 'Gurg' signifies 'Wolf'. (Defrémery, III. 143, 144, 335). This settles the matter. This Malik Hūshang is mentioned at 619 infra, as having rebelled and fled to the infidel Prince Burabrah, whom I have identified with the Koli Chief of Jawhār in Ṭhāṇā district. Hūshang's revolt is mentioned also in the Tārīkh-i-Mubārakshāhi. (Text, 106, l. 8).

III. 78, l. 7 from foot. The army.....arrived at Mas'ūdpur, so called after the son of King Mas'ūd.

The derivation is philologically impossible and there must be some error or inadvertence. Mas'ūdpur can only mean 'City of Mas'ūd' and the town was named, most probably, after Sultan 'Alāu-d-dīn Mas'ūd, the son of Iltutmish, and not after his son. There must have been some confusion in the mind of the author as regards the meaning of 'pūr'. It signifies 'son' in Persian, but it seems absurd to foist any such meaning upon the word, when it occurs as a suffix in the name of a town in Hindustān. But the fault may lie with the Text.

III. 79, l. 1. The army crossed the five rivers, the Jūn, the Chambal, the Kunwāri, the Niyās and Bahūji.

Elliot notes that the name of the fourth river can be also read as 'Bambās' and surmises that "the Niyās and the Bahūji must be the rivers now known as the Sind and the Betwa." He makes no attempt to restore the true readings, but this can be done, as two very similar names, Niwāj and Pahūj, are found in our Gazetteers. Thornton tells us that the Nivāj is

one of the tributaries of the Kāli Sind, the two streams meeting 35 miles below the Mukundra Pass (Gaz 479, 524) The Chambal is a tributary of the Jamnā The Kunwāri (Ib 514), Nivāj and Pahūj are all branches of the Sind which itself is an affluent of and falls into the Chambal. The Pahūj rises in a lake about twenty miles south-west of Jhānsi in Lat 25°-18' N, Long 78°-25' E and falls into the Sind. It is crossed by ford on the route from Gwälior to Kālpi in Lat 26°-6' N., Long 79°-5' E (Gaz s v Pohooj, p 771)

According to the Imp Gaz, the Pahuj and the Betwa are both tributaries of the Jumna The Pahuj runs from south to north, while the Betwa flows from west to east (XIV. 17-8) The two rivers are in fact sister streams and not unlikely to be confused with each other

Elliot and Dr Ayyangar can make nothing of the name 'Bahūji' and suggest that it must be an error, as the Betwa is the river that is meant Dr Ayyangar even seeks to explain it away by the supposition that the "Betwa was perhaps known as the Bhoji in Khusrau's day, because it was by damming the upper course of the river that the great Bhojpur lake near Bhopal had been formed" (Kh F. Introd xxiv) As there is no evidence in support of the conjecture, the more probable conclusion must be that Khusrau meant to write 'Pahuj' The designations by which rivers are known to the common people are often discrepant, the same river is known by different names in different parts of its course and the tributary is sometimes confused with the principal stream or vice versa Khusrau had no personal acquaintance with this part of the country, and had no special qualifications as a geographer His topography is not always in exact accordance with facts, and he seems to have mixed up the names of rivers When everything is considered, it seems that his 'Niyas' is meant for the 'Niwaj' and his 'Bahuji' intended for the 'Pahuj'

III. 79, l 3 They arrived at Sultanpur, commonly called Ingpur,
where the army halted four days

This Irijpur is an unsolved puzzle I venture to suggest that it is Irich. It is a place of considerable antiquity and its geographical situation is such as to give it great military importance. Thornton says that it "lies at a strategic point and the British army under the Marquis of Hastings was encamped here in 1817, when it advanced on Gwalior to intimidate Scindia. It has on the southern bank of the Betwa, on the road from Saugor to Gwalior and is sixty five miles south-east of the latter. Its former consequence and possession of a large Musalman population are manifested by the numerous mausoleums surmounted by domes around it " (Gaz s n Erich or Irej). It is mentioned by Baiani (323, 1-14), Shams-i-Sirāj (T. F 237 last line), the Emperor Bābur (B N Tr 590) and also in the Continuation of the A N (E D VI 108) and the Bād Nām (Ib VII 7) Dr Ayyangar, misled probably by a guess or gloss of Firishta's, identified it at first with Ellichpur (S I M I p 88), but he has since abandoned the opinion, and now proposes to locate it somewhere near Bhilsā and Bhopāl,

"a little more to the north than Bhilsī, a good deal less to the south than Bhopāl." (Kh. F. Tr. Introd. xxv.) But this is too vague to be satisfactory or helpful. He thinks that the last of the five rivers crossed by the army, the Bhoji or Bahūji, the river which was passed just before reaching Irijpur, must be the Betwa. (l.c. xxiv). Now Irach is situated on the Betwa. The fact is most significant in this connection and clearly indicates that Irijpur may be located with much greater certainty at Irach. The close phonetic resemblance also is in favour of the identification.

It may be also observed that Bhīlsā and Bhopāl take us much more to the south than is warranted by Khusrau's directions. He informs us that Irijpur was reached after fifteen marches in all—9 from Dehli to Mas'ūdpūr and 6 from Mas'ūdpūr to Irijpūr. As a day's march is reckoned by Dr. Ayyangar himself at about 15 miles, this means that Irijpur was about 225 miles southwards of Dehli. Now.

Dehli is in Lat. 28°-38' N., Long. 77°-12' E. Bhopāl in Lat. 23°-16' N., Long. 77°-36' E. Bhilsā in Lat. 23°-32' N., Long. 77°-51' E.

There is thus a difference of about 5_{10}^{3} degrees of Latitude between Dehli and Bhilsā, i. c. a map-distance of about 360 miles, at least, at 69_{6}^{3} miles to a degree of Latitude—which is considerably in excess of 225. If the difference in Longitude also is taken into account, it would be nearer 400 than 360. On the other hand, Irijpur is in Lat. 25° -47' N., Long. 79° -9' E. The difference in Latitude is nine minutes short of three degrees, i. c., about 200 miles, that in Longitude 1_{10}° degrees, that is, about 120 miles or about 235 miles altogether, as the crow flies. Again, as Irich is 65 miles south-east of Gwālior and as Gwālior is 175 miles south from Dehli, the total distance of Irich from Dehli works out at about 240 miles.

Dr. Ayyangar is sure that Irijpur was somewhere near Chanderi, where a muster of the army was held according to Barani. Indeed, he suggests that the four days' halt at Irijpur which is recorded in Khusrau's itinerary was probably made for this muster or review. Now Chanderi and Irich are in fairly close proximity to each other. Irich lies 65 miles south-east and Chanderi 105 miles south of Gwālior (Th). Chanderi and Irich are bracketed together by Barani in his list of 'Alāu-d-dīn's territories. (Text, 323, 1. 14). Shams also mentions Mahoba, Irich and Chanderi in juxtaposition. (T.F. Text, 237 last line).

III. 79, l. 4. Thirteen days [after leaving Irijpur].....they arrived at Khandhār.

The name is written 'Khāndā' in the Lith. (82, 1.5; Tr. 58), and phonetic resemblance points to Khandwa, which is a very old town and supposed to be mentioned by Alberuni also in one of his itineraries. (E. D. I. 60. q.n. my note). Dr. Ayyangar was at one time disposed to identify it with Khandhār, somewhere north of Bīdar in the Deccan, (S. I. M. I. 89), but his second thoughts incline towards Khandwa. (Kh. F. Introd: xxv). The difficulty is that the context which follows clearly

indicates that the Narmadā was crossed after and not before 'Khāndā' was reached The army is said to have arrived there on the 1st of Rajab, halted for fourteen days, and "advanced again" It then "passed through torrents and water courses Every day it arrived at a new river There were means of crossing all the rivers, but the Nerbadda was such that you might say that it was a remnant of the universal deluge" (See also Habīb's Tr 58) This seems to invalidate the proposed identification, as Khandwa is several miles south and not north of the Narmadā

III 79, last line. They arrived at a place within the borders of Bijānagar, which was pointed out as containing a diamond mine. It was in a Doāb, one river being the Yashar, the other Barūji

'Basīrāgarh' in the Lith (87, 1 2, Tr 60), where the rivers are called 'Yashahar' and 'Būji,' but it is noted that 'Yashahar' may be read also as 'Bishnahr' or 'Yasnahr' (Ibid) There can be little or no doubt that 'Basīrāgarh' is a misreading of 'Baīrāgarh', i e Wairāgarh It is now in the Garh-Chiroli tahsīl of Chānda district, CP, and is situated very close to the left bank of the Wain Gangā on a tributary of that river, called the Kobrāgaihi, about 80 miles south-east of Nāgpur, Lat 20°-27' N', Long 80°-10' E Constable, 32 B a

The diamond-mine of Wairagarh is mentioned by Firishta, who says it was in the Kallam district, which was conquered by Ahmad Shāh Wali Bahmani from the Rajā of Gondwāra, to whom it then belonged (I 323, 1 4) Garcia da Orta also was not ignorant of its existence. (Ball, Tr Tavernier, II 452, 460) Abul Fazl, too, states that Bairāgarh had a diamond mine and that the Gond Rajā of Chāndā, named Babjeo, had wrested it only a short time before he wrote, (1595 A C) from another chief (\$\overline{Ain}\$ T1. II, 230)

The names of the rivers which formed the Duāb or interamnia are manifestly corrupt A possible restoration of Level is Level. Bardahi or Bardahā, i e the Wardhā Yashar looks like a mistranscription of Level Bain [or Wain] 'Bishnahi 'may be read as Level Pashnahi The old Hindu name of the Wain-Gangā was Payoshni (Bhāgvata Purāna, V xix 17) III 80, l. 4 He arrived at the fort of Sarbar, which is considered among the provinces of Tilang

Sarbar must be Sirpur-Tāndur, now in 'Ādilābād district, Haidarābād State Constable's Atlas, Pl 32 A b In the corresponding passage of his History, F states that Kāfūr halted at Indūi (now called Nizāmābād), on the borders of Tilang, (I 119, l 4) and the statement is repeated in the CHI (III 115), but it does not seem to be correct Warangal lies due south of Sirpur, Indūr lies south-west of it and a march from Sirpur to Warangal via Indūr would have been an unnecessary detour. Sirpur was, at one time, a place of much greater importance than it is now. It was the capital of the Southern Gond Kingdom before

Ballālpūr. Ballālpūr was superseded by Chāndā, after which place, the kingdom itself came to be called and it is always mentioned under that name in the Mughal histories.

III. 80, l. 23. On the 14th of the month [Sh'abān], they arrived at Kūnarpal.

Kūnarbal in the Lith. (90, l. 5). Dr. Ayyangar is of the opinion that this place was in close proximity to Warangal and must be the village named Kunar, a little to the S. S. W. of that town. (l.c. xxviii). But there is no such implication in Khusrau's own words. All that he says is that a reconnoitring party was despatched from Kūnarpal to Hannamkonda. Nothing is said about the distance and the place meant may be Gūrapalli in the district of Elgandal or Karīmnagar. (I. G. XII. 5). Elgandal is less than 30 miles due north of Hannamkonda. Khusrau's 'An Makinda' (l. 27) is Hannamkonda, which was the capital of the Kākatiya Rājās before Warangal. Constable, 32 A b.

III. 83, l. 10. And cries of huzza huzz and khuzza khuzz, the acclamations of the triumph of holy warriors, arose.

Dowson notes that this is an early Eastern use of the familiar English 'Huzza', but there are several instances of its use in older authors, e.g. in Baihaqi, whose History was written between 448-455 A. H. (1056-1063 A. C.). e.g. هزاهن در دلها افتاد (Text, 139, l. 5); هزاهن در دلها افتاد (Text, 176, l. 3); و هزاهن سخت بود (Text, 176, l. 3); و هزاهن سخت بود (Text, 279, l. 6 f. f.). The word مزاهن occurs also in Gardezi (Z. A. 88, l. 5 f. f.), and Barani (T. F. 199, l. 16).

III. 83, l. 21. He [Laddar Deo] sent a golden image of himself, with a golden chain round its neck in acknowledgment of his submission.

F. differs here from Khusrau and asserts that it was the Rājā of Siwāna, and not Laddar Deo of Warangal who sent a golden image of himself as a token of submission. (I. 118, l. 13). He has been followed by Sir W. Haig. (C. H. I, III. 114). But these averments appear to be erroneous and founded on some misunderstanding. In the 'Ashīga also. Amīr Khusrau explicitly states that it was the Rājā of Warangal who made an attempt to placate the ruthless invader by sending him 'a golden idol' of himself. (550 infra; 'Alīgarh Text, p. 69). The confusion is, perhaps, due to the fact that in this poem, the account of the siege and the capture of Siwana is followed immediately by that of the invasion of Warangal. F. is not infrequently an inaccurate copyist and he must have read the lines hurriedly or carelessly. It may be noted that the Rājā of Siwāna is explicitly said by Khusrau to have been killed fighting, while Rudra Pratip saved his life by abject submission. discrepancy between the two statements is undoubtedly glaring, but the authority of the later compiler cannot, in any case, outweigh that of the contemporary annalist from whom he has confessedly borrowed his account.

III. 84, l. 6 from foot. On Tuesday, the 24th of Muharram, 710 H.

The corresponding Christian date, 23rd June, 1310 A.C., was a Tuesday. (Ind. Eph.).

III. 87, 1.5 The sea-resembling army moved . to Ghurganw.

Dr. Ayyangar at first identified Ghurganw with a village called Kharegam, a little to the SW. of Indore and E of the road to Dhar and Ujjain. (SIMI 101, 194) He is now inclined to place it somewhere between Burhanpur and the Tapti (sic) But as he is unable to find any place called 'Ghurganw' on the maps, in this vicinity, he leaves the exact situation undecided (Kh F Tr Introd xxix). I venture to say that it is 'Khargon', now in Nimir district Constable, 31 Ca. It lies on the Kundi river, a tributary of the Narmada, in Lat. 21°-50' N. Long 75°-37' E (I.G XV. 251). Thornton describes it as a decayed town with a wall and a fort in Nimar zilla, lying sixty miles south of Indore It was situated on the old high road from Hindustan to the Dekkan and Akbar halted here on his way from Agra to Asirgarh It was here also that Abul Fazl had an interview with him in regard to the conquest of Asir. (AN III. 768=Tr. 1148, see also ED. VI. 136, 1 7 and my note there) Khargon lies about 25 miles from the strong fortress of Bîjagarh and Khwafi Khan states that Bijagarh was also called Khargon. (ED VII. 499) It is situated about 25 miles south of the spot where the Narmadā is forded without much difficulty and Malik Kāfur did what most wayfarers did in those times, when he encamped here after crossing the river It was a place of considerable importance and F records the tradition that Ghargun (Khargon), Bijagarh and Handiya were all built by the renowned Raja Bhoja [Paramara] of Dhar (L. 13, 1 7 f f=E D VL 559)

Khargon is mentioned in many of the itineraries of the old European travellers. Finch passed through it on his journey from Burhānpur to Āgra (E T I 140) and so did John Jourdain in 1611 AC, when he travelled from Sūrat to the same town. (Journal, Ed Foster, 147) See also De Laēt, who calls it a big town lying on the route from Mandū to Burhānpur, at a distance of 24 Kos from the former and 37 from the latter. (Tr. Hoyland, 31)

III. 88, l. 5 [The Muhammadun army]. . after five days arrived at Bandri in the country (ikt'a) of Paras Deo Dalvi.

Dr. Ayyangar thinks this is Pandharpur and he may be right, though the phonetic resemblance between the two toponyms is slight, if not shadowy. Bāndri is said to have been reached five days after leaving Deogīr, and after the Sīna, Godāvary and Bhīmā had been crossel. The road taken is supposed by Dr. Ayyangar to have started from Bārsi along a familiar and frequented route, which is mentioned in an inscription of Vīra Someshwara Hoysala He assures us that Pandharpur was the frontier station between the Yādava and Hoysala kingdoms at this time (Kh. F Tr Introd xxx)

III 90, l. 15. The Rai Bir . fled to Kandur.

Sir Wolseley Haig supposes this to be Kadūr in Kadūr district, Mysore (C. H. I. III, 116), Constable, Pl. 34, C c. But Dr. Ayyangar is sure that it is Kannanūr, about five miles north of the island of Shrīrangam. He says that Kadūr in Mysore is too distant from Madura, Birdhūl and the Pāṇdya country and will not fit into the context. (S. M. M. I. 72; Kh. F. Tr. Introd. xxxv). Kannanūr lies about eight miles north of Trichinopoly town and was the Hoysala capital in the Cholā country in the thirteenth century. It lies south of Samayapuram in Trichinopoly tāluk. Lat. 10°-56′ N., Long. 78°-45′ E. (I. G. XXII. 3-5).

The names of the other places mentioned in this section—Tabar [Toppur Pass?], Sarmali [Sirumalai?], Birdhūl [Viruddhuvalli or Viruddhachalam?], Jālkotā, Kham [Kambam Valley, q. v. I. G. XX.109?] are corrupt and written in various ways. They have not been satisfactorily identified and there seems to be no prospect of reasonably certain conclusions being reached in regard to them, as there are no clues and no data to guide us. III. 90, l. 6 from foot. He had heard that in Brahmastpuri, there was a great idol.

Barmat-purī' in the 'Alīgarh Text, 169, l. 1; 102. This has been supposed by some authors to be meant for Rāmeshwaram, partly on account of the partial phonetic resemblance between the two names and partly because F. states that Kāfūr built a mosque in that "sacred city of the infidels". (I. 119, l. 1 f. f.). Sir W. Haig subscribes to the opinion, though he is not sure whether the mosque was erected in the island of Rāmeshwaram itself or on the mainland opposite to it. (C. H. I. III. 116). Dr. Ayyangar thinks 'Barmastpuri' must be Chidambaram, because Chidambaram has a golden ceiling and is known also as Brahmapuri, but he is not prepared to reject the identification with Rāmeshwaram and think sit also possible that the temple of Shrīrangam may be meant, as it also has "a golden roofing". (S. I. M. I. 108-9; Kh. F. Tr. xxxvii-vii). III. 91, l. 5 from foot. The Rāi had fled, but had left two or three elephants in the temple of Jagnār

Elliot's suggestion that the temple was dedicated to Jagannāth, i. e., Vishnu, is discountenanced by Dr. Ayyangar, who assures us that 'Jagnār' is a corruption of 'Chokkanāth', which is one of the alternative Tāmil names of Shiva or Sundaresha, the patron deity of the town of Madura. The Tāmil 'Chokka' has the same meaning as the Sanskrit 'Sundara'. (S. I. M. I. 96; Kh. F. Tr. xxxii). The great temple of Sundareshwara is still the outstanding monument of the city. Vijayaranga Chokkanāth was the name of one of the Nāyaks or later Kings of Madura in the 17th century. The name is pronounced 'Sokkanāth'. See also I. G. XXIII. 108.

(Jagannāth).

III. 91, last line. The elephants amounted to five hundred and twelve.

The number of the elephants is variously stated by the chroniclers. Khusrau puts it down as 512 in this passage, but has 500 in the

"Ashīga, (551 infra). Barani raises it to 612. (204 infra). In F. (I 120, 1.7) and B. (I. 197=Tr 265), it is whittled down to 312, but this is most probably due to a copyist having written بيصدو دوارده, instead of 312 is almost certainly wrong, though it is accepted in the C H I. III, 116. In the Khazāin, Amīr Khusrau explicitly states that 108 were captured at Kandūr, 250 at Barmastpuri and 2 or 3 at Madura This makes 360 or 361 at the ledst, even if the 36 taken from the Rājā of Dvāra Samudra (Barani, 333, 1 6) are not reckoned.

III 92, l 5 On Sunday, the 4th of Zn-l-hijja 710 H Malik Käfür returned towards Dehli and arrived on Monday, the 4th of Jumāda-s-sāni 711 H

4th Zi-l-hijja, (Hisābi) 710 H, was Saturday, 24th April, 1311 and 4th Jumādi II 711, Monday, 18th October, 1811 A C In the Translation, (p 108), it is stated that 'Alāu-d-dīn held the Darbār on Monday, 14th Jumādīu-s-sāni, 711 H. (p 108), but it must be a slip, as the corresponding Julian date, 28th October 1311 A C, was a Thursday The Lithograph reads the date correctly as Monday, 4th Jumādi II (181, 1 3 f. f)

III 98, l 23 [Sultān Nāsıru-d-dīn] passed much of his time in making copies of the Holy Book

What Barani really says 18 مشتر سة خود ار وعة كسات مصعب ساحق, 26,17 f f 'He supported himself mostly from what he earned by the transcription of the Holy Book 'Ibn Batūta (493 infra), the TA and F say that the Sultan made two copies of the Quiān every year, and that his own food was paid for out of the money obtained by selling them They also tell a story in this connection. On being informed that unduly high prices were paid for these copies by one of his courtiers, he took care to see that they were put on the market without revealing the name of the august scribe The actual words used by both Nizāmu d-dīn and Firishta are بای آن در وجه قوت حاصه حود مصروف داشتی (T.A. 37, 1 10 f f, F I. 54, I 3). See also B (I 90 = Tr 128)

III 102, l 10 Some of the old Shams: slaves who still occupied exalted positions, often said to him [Balban]

תרלות פנית בור חות אלות פנית היים לא ור דוף ווע בור חות היים ווע בור חות היים ווע בור חות היים ווע בור חות היים ווע בור ווע

III. 104, l 9. In the neighbourhood of Dehli, there were dense jungles, through which many roads passed.

65, 1 13. "In the environs of , در حوالی دهلی حنگلهای کش و انوه رسته اود

Dehli, thick and numerous jungles had grown up." Here is not a noun meaning 'road', but the participial form of "to grow." They would not have been "dense jungles" in the real sense of that word, if "many roads had passed through" them.

III. 104, l. 18. The Miwāttis would often come to the Sar-hauz and assault the water-carriers and the girls.

ومجال نبودي كه كسى بعد از نهاز ديگر . . . برسر حوض سلطان رود . . . و بارها مبوان بر سر حوض مي آمدند; 56, 1, 5 f.f. Dowson remarks in the Footnote that " the printed text and the Mss. say Miwans, but Firishta has Miwattis, and he is no doubt right. The copyists must have misunderstood the name." But the printed text is quite correct in speaking of them as موان Mewan, i. e. Meos and Hajji Dabīr also reads ميوان (731, 1, 21). 'Mewatti' is an alternative form, and there are large numbers of 'Meos' still in the State of Alwar and Gurgaon district. Mewat, in fact, is the country of the 'Meos.' The Meos used to come to the banks [-] of the Reservoir built by Sultan Shamsu-d-din Iltutmish, which is mentioned on the immediately preceding line as حوض سلطان, 'the Sultan's [Iltutmish's Reservoir.' This tank is frequently spoken of also as the 'Hauz-i-Shamsi' and distinguished from the 'Hauz-i-Khās' or Hauz-i-'Alāi constructed by 'Alau-d-din Khalji at a later date. The 'Hauz-i-Shamsi' is called 'Hauz-i-Sultani' by Amir Khusrau also in the Kh. F. (Text, 31, 1. 11; Tr. Habib. 19).

III. 105, l. 19. Kampīl, Pattiāli and Bhojpur had been the strongholds of the robbers.

Bhojpur is a very common toponym in India. This is the Bhojpur which lies about eight miles south-east of Farrukhābād and about thirty miles north-west of Qanauj. Pattiāli is now in Etāh district and Jalāli (1.29) may be the place of that name in that of 'Aligarh. Kateher (last line) is a somewhat indefinite geographical expression. It is strictly speaking, the tract lying between the Ramganga, Sharada and Khanaut rivers, but is loosely employed for what is now called Rohilkhand. Mr. Crooke derives the name from Kather, "a brownish loam of a thirsty tenacious nature requiring copious rain for irrigation," of which the soil of the district is chiefly composed. (Tribes and Castes, III. 176). But the alternative derivation from the Sans. Kāshtha, 'wood,' Hindi Katheri, 'woodman, or 'carpenter,' (Elliot. Races. I. 313-4) is at least equally probable. And the countries of Badaun, Amroha, Sam-III. 106, l. 9 from foot. bhal and Kānwari continued safe from the violence of the people of Katcher.

In the C. H. I. III. 77, it is proposed to identify Kānwari, Kānori or Gānori (كَانُورى) with Gunnaur, in Budāun district. Constable, Pl. 27, D a. But Barani speaks of Kānaudi (كَانُورى) which can be also read as Kānori, again at 288, l. 8. Thornton mentions a Genori or Genouri in Bulandshahr, 55 miles south-east of Dehli. Lat. 28°-20′ N., Long. 78°-4′ E. Gunnaur is his Goognour, Lat. 28°-15′ N., Long. 78°-30′ E., which he

locates 44 miles north-west of Budāun town. The identity of 'Kānwarı' with Gunnaur is made still more doubtful by the fact that Barani speaks of 'Gunnaur not as 'Kānwarı' or 'Kānaudı' (کانودی or کانودی), but as 'Ghanūr (کهنودی), a few pages below. (121 infra, Text 106, last line). Balban is there said to have "crossed the Ganges at the ferry of Ghanūr," on his return to Dehli by way of Budāun

III 110, last line [S'adi] sent some verses in his own hand

الله علم خود ورستاد; Text 68, 1. 12 "Sent a casket, or collection (lit boat) of Ghazals in his own handwriting." This phrase عب عرل محلط خود ورستاد

درس رمانه رميتي كه خالى ادر خال است صراحى مى مات و سعيمه عمل است (Bombay Lithograph, 1267 A. H. No 69, Jarrett's Edition, No 47) III. 113, 1 19. Ambition had laid its egg in his head.

Barani was well-read in the historical literature and this is a conscious or unconscious reminiscence of 'Utbi, who speaks of Satan having "laid an egg in Jaipāl's brain and hatched it" (E.D II. 19). Nizāmu-d-dīn Ahmad says of Buhlūl Lody that "the bird of Imperial sway had laid an egg in his brain" (T A 149, last line) and Budāuni writes that "the crow of conceit had made its nest in the brain of Shāh 'Abu-l-M'aāli" (I 462=Tr I 586)

III 114, l. 3 Abtigin "the long-haired" who was known as Amir Khān. The B I Text of Barani also reads the name as Abtigin (83, 1 15), but the correct form is most probably 'Aztigin'. The name of Ikhtayāruddīn Aitigin the Long-haired, occurs in the T. N. 294, 1 6 f f in 657 A H. (E D II 368). The name was not uncommon and had been borne by another great noble who was assassinated by the orders of Mu'izzuddīn Bahram Shāh. (T N Text 187, 192 Ibid, E. D II 334, 338). Raverty always calls him 'Aet-kīn' (Tr 642, 648, 650, 651) His title is given by Dowson as Amīr Khān, but it is spelt as Amīn Khān in the B. I Text of Barani, (83, 115), as well as in the T M. (41, 1 13), T A (44, 1 3 f f), F (I. 79, 1 2 f f), and Hājji Dabīr, (966, 1 8) 'Ai' occurs in other Turki names also, e g, Ai-bak, Ai-tamur, Ai-dakū, Ai-tim, etc, and is said to mean 'Moon', and 'Tigīn,' 'valorous' (Sachau, loc cit II 340 Note) III 114, l 5 from foot Sent another army under a new commander

The name of the leader of the second expedition against Tughril is not given by Barani F following the Tārīkh-i-Mubārakshāhi (Text 41, 15ff), speaks of him as Malik Tarmati Turk (I80, 13). This name is changed into Targhi in the CH I. (III, 79), but Tarmati appears to be correct A Malik Tarmati was Shahna-i-pīl, 'Commander of the Elephants,' in the reign of Balban's successor, Mu'izzu-d-dīn Kaiqubād (Barani, Text, 126, 18). Another Malik Mahmūd Tarmati was governor of Qanauj in 809 AH (1406-7 AC) (TM. Text, 175, 1.5ff.=ED. IV. 41: T. A 131, 15, BI. 275=TrI 363)

III 121, l. 6 from foot The Sultan ordered gibbets to be erected from Budaun to Tilpat (Pilibhīt)

As the Sultan is said to have entered Dehli already, and as the punishments were carried out in the capital, the erection of gibbets from Budāun to Pilībhīt is obviously unthinkable. What Barani actually writes is نرمان داد که از دروازهٔ بداون تا تلت دارها دو رویه نرو برند (107, 1. 4). "He gave orders for planting the gibbets on both sides of the road from the Budāun Gate [of Dehli] to Tilpat."

Tilpat was the first stage on the road from Dehli to Oudh and is mentioned frequently. (203, 525, 528 infra). It is said by Amīr Khusrau to have been seven Kos distant from the capital. (557 infra). The actual distance is about twelve English miles to the south-east. (Fanshawe, D.P.P., 227). The Budāun Gate of Dehli is again mentioned at 135, 148, 160 and 198 infra by Barani and also by Ibn Baṭūṭa. (590 ibid). The error is due, most probably, to the word *cele* [Gate] having been dropped out in the Ms.

III. 122, 1.23. He proceeded to Lahor to oppose the accursed Samar.

The correct form is 'Tamar' or 'Tamūr.' (Barani, Text, 109, 1.6 f. f.). In the contemporary elegy of Mir Isaan, he is called Aitamar. (B. I. 132; Tr. I. 189). The T. A. (47, 1.5) and F. [I. 82] speak of him as 'Taimūr,' which is practically identical with 'Tamar' or 'Tamūr' and is said to mean 'iron.' Elsewhere, Barani states that the Amīr Qatbugha-i-Amīr Muhān—one of the great nobles of Muhammad Tughlaq—was the grandson of Tamar, in fighting against whom, the Khān-i-Shahīd had lost his life. (545, 1.2). 111. 124, 1.1. In the management of kingdoms, questions are constantly arising and dangers threatening.

ت در کردش ملك کارها بكردد و از هرطرن بلاها بزايد ; p. 121, l. 7. "For with a change in the Kingship (i. e. when it passes from one person to another), great alterations [or revolutions] take place in affairs also and calamities are engendered." Barani again uses the phrase كردش ملكها on l. 18 of this very same page, for 'Revolutions in Kingdoms.'

III. 124, l. 19. But what can I do? Mahmud [Bughrā Khān] has shrunk from the work and people shut their eyes at him.

.4. 122, 1. چه کنم محودکه از وکاری آید و مهدمان از و چشم زنند در لکهنونی رفت

"What can I do? Maḥmūd who can effect something [who can manage affairs] and of whom people stand in awe has gone off to Lakhnauti." عني وشع occurs again in Barani, Text, 254, 1. 6, and Dowson renders it there by 'do not heed him.' (159 infra). Level is found again at 411, 1. 14, and is translated thus: 'they had no awe of any maliketc.' (224 infra). See also Text, 399, 1.10, where Barani says خروفان از أيثان از أيثان المناف المناف

III. 124, l. 3 from foot. The corpse of Sultan Balban was buried in the house of rest.

House of rest' may signify 'grave, tomb,' in general, but that is not the meaning here. What Bai am says is that they took him to the Dāru-l-Amān was the specific designation of the Mausoleum built by Balban for himself in his lifetime. Ibn Baiūta explicitly tells us that Balban was buried in a house to which he gave the name of 'Abode of Security,' the i aison d'être of the appellation being that it was a sanctuary for insolvent debtors and other delinquents (593-4 infra) Sultan Firūz Tughlaq also states that he "had the Dāru-l-Amān of Balban repaired, as it was "the bed and resting place of great men" (Futūhāt-i Fīrūzshāhi, 384 infra) It is also mentioned in Abul-Fazl's account of the monuments of Dehli (Āin Tr II. 279). The building still exists (Fanshawe, D. P. 278) Balban's favourite son, the Khān-i-Shahīd, was also buried here (Ibid)

In this connection, Barani mentions the curious fact that after the death of Balban, the nobles and other men of note slept on the bare ground in the tomb of the Sultan for forty days, while the Sultan's special favourite, the Great Kotwal Fakhru-l-Mulk kept up this rite of mourning for six months (123, 1 10)

III 126, l 2 Malık Kawamu d-din who held the office of secretary. ملك قوام الدن علاده دير عمدة اللك و مانس وكيل در شد . عمدة اللك و مانس وكيل در شد

III. 129, l. 1 Every day, he made some new move in the game and sought to remove the Khaljis who were obstacles in his path to sovereignty.

و هر رور در تحت شطر نح پادشاهی پیادهٔ دیگر میراند و روزگار عدّار برای سلطنت خلعیان مزاحمان ملك المنی را از دست او دمع کرد و فلك بر ریش و سلس تطام الدین خام طبع خنده ها میرد .£ 1.3 ق. 1.3 ق.

"Every day, he played forward a new pawn on the chess-board of sovereignty and deceitful Fortune caused the enemies of the Balbani dynasty [lit Kingship] to be destroyed by his means, with a view to [facilitate] the foundation of the empire of the Khaljis. The Heavens laughed at the beard and mustachios of the half-baked and ambitious Nizāmu-d-dīn" It will be seen that the meaning of the second clause is turned almost upside down

III 131, l 1 I have no inclination to pay homage to my son.

The real sense of this passage is also inverted in the translation.

.4. [.4 برا در خدمت کردن ِ پسر هیچ اکفتی در خاطر نمیگذرد

"There is no objection [or reluctance] at all in my mind [or heart] to pay homage to my son." Dowson's manuscript appears to have read , but '! is shown to be right by what Bughrā Khān says immediately afterwards. He has no qualms or scruples in regard to the matter, he states, because "my son sits upon the throne of Dehli in my father's seat." III. 134, l. 4 from foot. Poured out of the twelve gates of the city.

Here, the Dehli of Mu'izzu-d-dīn Kaiqubād's days is said by Baraņi to have had twelve gates. But Amīr Khusrau says in the Qirānu-s-s'adain that there were thirteen. (524 infra). Ibn Baṭūṭa tells us that in the reign of Muḥammad Tughlaq, the three cities of Dehli had twenty-eight gates in all. (590 Ibid). Sharafuddīn Yazdi makes the total number thirty. He notes that Old Dehli [the Dehli of Mu'izzu-d-dīn Kaiqubād] had ten gates, but three others are said to have opened from Sīri ('Alāu-d-dīn's city) towards Jahānpanāh [Muḥammad Tughlaq's city]. (448 and 504 infra and Note). It would seem that Old Dehli had thirteen gates and not twelve at this time. Ibn Baṭūṭa gives the names of several of the gates.

. p. 259, 1.2 کلمانی که بر چهار کن جامه خانه بیچیده و یاکیزه توان کمفت در صحرا نبرد F. has paraphrased Barani correctly, and he says that Mu'izzu-d-din was rolled up in a "Jāmkhāna, that is, Carpet" (جامخانه يعني كليم). (I. 88, 1. 12). He also cites several couplets from a Masnavi in which the poet laments that the Sultan's body was rolled up in a (جامخانه) or carpet and kicked to death. (Ibid. I. 13). Musta'sim, the last Khalif of the House of 'Abbas, had been put to death by the Mongol Hulagu about thirty years before, in nearly the same barbarous manner. He was 'tied up', says D'Ohsson, "in a sack and trodden under foot by horses." (Histoire des Mongols, III. 243 apud Thomas, C.P.K.D. 254 Note; Price, Retrospect of Mahomedan History, II. 252). This inhuman mode of execution is explicitly said to have been adopted, because the Mongols had a superstitious dread of allowing royal blood to be spilt upon the ground. This fear was carried to such lengths that even in opening the veins of a Royal patient, great care was taken that the blood should not fall upon the Earth. Manucci tells us that when he bled the prince Shah 'Alam Bahadur Shah, the blood

taken was carefully weighed and buried in the garden after the performance of several ceremonies (Storia IV 225). The contemporary historian Minhai says that some well-meaning Muslims in the camp of the Mongols had, with a view to save the Khalīf's life, told those savages that if his blood was shed and fell on the ground, there would be such a tremendous earthquake that they would all perish to a man in the cataclysm. But these good intentions were unexpectedly frustrated, as some other Muslim traitors warned Hulagu that if the Khalif was kept alive. there would be a general rising or mutiny. To avert these threatened disasters, Hulagu had recourse to this peculiar mode of execution and ordered his poor victim "to be carefully enclosed in carpets and his sacred تا اورا در محافظت حامعامها در بحيدند "person kicked until life was extinct The use of the word) ولكد مرتى مارك او ميردند ما هلاك شد by Minhaj also is decisive Wassaf (Tr Von Hammer, 75-76, quoted by Yule in Tr Marco Polo, I 67-68) and Ibn-al-Furāt (Le Strange in J R A S 1900, p 298), give a very similar account of the Khalif's death III 135, last line Sultan Jalalu-d-din ascended the throne ... 2n688~H

The exact date of Jalālu-d-dīn's accession is given by Amīr Khusrau as Tuesday, 3rd Jumādī II, 689 H (536 infra) Barani gives 688 H, but it is demonstrably erroneous The Tānīkh-i-Mubārakshāhi says Mu'izzu-d-dīn was put to death on 19th Muharam, 689 H, (Text 59, 13 f, f See also Thomas, C P K D 141 Note) and this statement is copied by Budāuni (I 165=Tr I 228) The numismatic evidence is clearly against Barani and in favour of Amīr Khusrau All the known coins of Shamsu-d-dīn Kaiumaras are dated in 689 H. (H N Wright, Coinage and Metrology of the Sultāns of Dehli, p 66, Numismatic Supplement No II to the J A S B. (1904), art No 9, p 229, Lucknow Museum Catalogue, No 177)

The earliest known coins of Jalalu-d dīn also are of 689 H. (H N Wright, Catalogue of Coins in the Indian Museum, II No 175) 3rd Jumādī II, 689 H, corresponded with 13th June, 1290 A C, and fell on a Tuesday, just as Amīr Khusrau says F (I.88, 1 11 from foot) states that Mu'izzu-d-dīn ceased to reign in the last days of 687 H. and Jalalu-d-dīn ascended the throne in 688 H (I 89, 1 2), but both these dates are wrong III 136, l 22 Kilūghari then obtained the name of 'New Town'

If this means that the name was given to Kilūghari or Kilūkhari by Jalālu-d-dīn or after his accession, it is not correct, as Kilūghari is spoken as which was completed in 658 H.=1260 A.C (Text, 317 = E D 382, and Text, 318, 1 10)

The saint Qutbu-d-din Bakhtyār-1-Kāki is said to have settled in Kilūghari in the reign of Iltutmish (F II 379, 1 7 f f). B observes that the ruins of Kilūghari were to be seen in his own time on the bank of the Jumna near the ford of Khwāja Khizr (I. 157 Tr I. 220) It was situated about eight miles distant from Dehli, south-east of Humāyūn's tomb and north-by-west of Khizrābād. (Blochmann, JASB.

XXXVIII, p. 184 Note). Jalalu-d-din merely followed up the plans of Mu'izzu-d-din and extended the New City which had been styled Shahri-Nau 30 years before. The C. H. I. only propagates a demonstrable error when it states that it was Jalalu-d-din who "named Kilokhri Shahr-i-Nau". (III. 91). Mr. Vincent Smith had made the same mistake. (O. H. I. 230).

III. 138, l. 10. The most noted of them [rāwats and pāiks of Hindustān] received betel from him [Chhaju] and promised to fight against the standards of the Sultan.

The real point is not brought out quite clearly in the translation. از پیش ملک چهجو ببرهٔ پان برگرفته بودند و دعوی کرده که برچتر سلطان جلال الدین خواهیم زد (182, l. 9). What Barani is referring to is the ancient Hindu custom of picking up in the court or public assembly a packet of betel to symbolise the undertaking, even at the risk of certain death, of some extraordinarily difficult or dangerous enterprise. These swash-bucklers had not merely 'received betel' passively from Chhaju. They had picked it up voluntarily or thrown out a challenge and boasted that on the day of battle, they would encounter the Sultan himself, strike down his umbrella and hurl it off from its place over his head. Elsewhere, Barani says that the Pāiks of Bengal who were perpetually bragging of their valour 'had picked up the betel of self-immolation' in the presence of the Bengal و يَا يِكَانِ معروف بِنكَالِهِ Sultan, Shamsu-d-dīn Ilyās, the Bhang-eater. كَهُ خُودُ رَا مَرَدُ هَا ميكويانبدند بيرة جانبازى از پيش الياس بهنكى برگرفتند .2 593, I. 2 There is a graphic description of the ceremony in Tod's 'Rajasthan.' When Sarbuland Khan revolted against Muhammad Shah in 1730 A.C., all the great nobles of the State were, say the Rajput chronicles on which he relies, hastily summoned by that Emperor to a Durbar. "The bīra was placed on a golden salver which the Mīr-i-Tūzuk bore in his extended arms, slowly passing in front of the nobles ranged on either side of the throne, but in vain he passed both lines; no hand was stretched forth none cast an eye upon the bira The Rathor prince [Abhaya Sinha of Jodhpur] saw the monarch's distress, he stretched forth his hand and placed the bira in his turban." (II. 1039). Elsewhere again, Tod speaks of Sur Singh Rathor, Raja of Marwar, "having taken the pan against the king Muzaffar of Gujarat, when the latter rebelled against Akbar." (Ibid. II. 989).

This allusion in Barani shows that the custom is of respectable antiquity. There is a reference to it in Muhammad Jaisi's beautiful Hindi poem, entitled 'Padmāvati,' which was written about 1540 A. C. See [Sir George] Grierson's Analysis in J. A. S. B. LXII. Pt. i. (1893), p. 197. The Bira was not taken by the man from the hands of the king. It was picked up by the volunteer himself, like the 'gage' of the Knight in European Chivalry.

III. 138, l. 5. With yokes on their shoulders, their hands tied behind their necks.

The word in the text is cells. The 'Doshākha' is defined in the Burhān-i-Qāti'a as a piece of wood with two branches, placed on the neck of criminals. It seems to have borne some resemblance to the Chinese 'Cangue', which was a sort of neck-halter, "a square wooden board which was made to rest on the shoulders without chafing the neck" (Hobson Jobson, s v Cangue) The word is again used by Barani at p. 601, 1 11, and Dowson has rendered it more correctly there by "wooden collars on the neck." (268 infra) It was really a kind of 'portable pillory' rather than a 'yoke' Steingass and Richardson give 'Pillory' as its meaning III 139. 1 18. Malik Ahmad Chap, deputy lord chamberlain

جب This sobriquet occurs frequently in Barani and is always spelt (I. 174, 177, 180) and F as حيب (I. 97, 1.9). 'Hab' and 'Habib' are errors or silly emendations of the copyists and the right reading seems to be 'Chap,' as Hājji Dabīr also calls him Chap (Z W 757, 1 18, 779, 1 14) and the T M favours the same spelling (56, 62, 69, 70, 72) The raison d'être of the appellation is an enigma. means 'left' and چپ دست 'left handed' (Rich) Ahmad may have been so called on account of this physical peculiarity or because he was, as we know him to have been, gauche-a person blunt in speech, who often said right things just at the wrong time or in the wrong place another explanation also can be offered. Ahmad was the deputy lord chamberlain, Naib-1-Amīr-1-Hāgib (249, 1 16) and it is possible that 'Chap,' 'Jab' or 'Jib' is the tail or short form of 'Hazib.' We are told elsewhere that Mubashshar, who was the Hajib of Sultan Muhammad bin Firuz had this identical sobriquet, which is written 'Chap' by B (I 261=Tr 344), 'Jab' in the T M (149,1 10, E D IV 24) and 'Hab' in the T A (123, 1 18) See my note on E D IV. 24, The coincidence is not unworthy of note Ahmad Chap's exact relationship to the Sultan cannot be determined Barani merely says that his father was a near relation قرات رديك (186, 18) of Jalalud-din F states that he was the son of the Sultan's sister (I 89,1 11), but if so, it is wrong to call him 'cousin' as in the C H I, III 95

III 141, l 24 Some 'thags' were taken in the city about a thousand being captured

This is perhaps the earliest reference in Muslim historical literature to the 'Thugs,' in the specific sense which the word has now acquired That the Hindi word is used here by Barani, not in the general signification of 'cheat, rogue, knave or swindler', but in the secondary one of a peculiar class of highway robbers and murderers, is shown from the fact that in the corresponding passage of the TA, it is paraphrased by the Arabic 'inghway robbers' (59, 17 from foot) Another early reference to these miscreants is found in the 'Padmāvati' of Muhammad Jaisi (written about 1540 AC) There, Rāghava, who complains of having been robbed, compares Padmāvati's glances to "a Thug's poisoned sweetmeats" ([Sir] George Grierson in JASB. 1893, p. 108). Theyenot also

mentions them (Voyages. V. 123) and Fryer has left it on record that fifteen were executed at Surat about 1673. (New Account, 97). Mr. Vincent Smith may be right in stigmatising Sultan Jalālu-d-dīn Khalji's action as 'particularly silly,' but when he asserts that it was the origin of the river-thuggee which is still prevalent in Bengal, (O. H. I. 231), he is guilty of a gratuitous assumption. Equally unwarranted and baseless is the suggestion that Sidi Maulā was 'a patron and pensioner of the Thugs.' (C. H. I. III. 94). A similar accusation had been preferred against Nizāmu-d-dīn Awliyā also by Mr. H. G. Keene in the first Edition of his 'History of Hindustan,' but he had the good sense to withdraw the calumny in later Editions.

III. 144, l. 5. He presented Amir Khusrū with twelve hundred tankas.

"And the twelve hundred tangas which were the (annual) allowance of Amīr Khusrau's father, he settled [or confirmed after the father's death] upon Amīr Khusrau." Amīr Khusrau's father was a Khiṭāi Turk named Lājīn, who had taken refuge in India and had received from Iltutmish, the title of Amīr Saifu-d-dīn-i-Shamsi. He was killed in battle when his son was only seven years old. (Rieu, Persian Catalogue, I. 240-1).

III. 144, l. 11: Sidi Maulā was cast under the feet of an elephant, after which event the Jalāli throne and family began to decline.

Sīdi Maulā was neither "a pensioner of the Thugs" nor a proficient in alchemy or magic and thaumaturgy (كبيا و سبيا). He was, probably, the tool and stalking-horse of one of two factions at Court which were hotly engaged in a succession-feud. He appears to have been well-known for his intriguing proclivities and the kindly "bit of advice to beware of intimacy with Maliks and Amirs" which Shaikh Farid-i-Shakarganj is said to have given to him indicates that he had flirted with politics in the past also and was an old hand at that dangerous game. Sultan Jalalud-din's great age made it advisable for all parties in the state to be prepared for the political crisis which would be the immediate consequence of his demise. His two sons were both claimants for the succession and each was busy collecting adherents. Khān-i-Khānān, the eldest son, had for this purpose, allied himself with the ecclesiastical party headed by the Qāzi Jalāl Kāshāni, and also with a section of the old Balbani bloc. The members of the latter party had learnt from experience that they had, in his rival, Arkali Khān, their most deadly foe, as it was he who had taken the leading part in scotching the rebellion of Chhajju, the nephew of Balban, and had brought him and his followers in chains and halters to Dehli. The sumptuous feasts and open house kept in the name of the Sīdi for the people of Dehli were part of his propaganda and the aim and object was to secure thereby the allegiance and active support of the proletariat of the capital. This lavish hospitality was really financed by the Khān-i-Khānān and the disaffected Balbani Amīrs. The bill was

footed by them and the gold mulirs which were found in corners and under bricks and coverlets really came from their coffers. So long as the eldest prince was alive, the leaders of the faction had nothing to fear and were not molested. His untimely death put an entirely different complexion on the matter. The conspirators had now no legitimate head and no powerful protector at court. It is also possible that they were divided among themselves as to the choice of a successor. The plan to marry Sidi Maula to a daughter of Nasiru-d-din Mahmud must have emanated from or was a compromise with the Balbani wing. The plot to assassinate the Sultan at once and precipitate a revolution was that of the hotter-headed men in the party. These dissensions naturally resulted in the discovery of the conspiracy. We may be sure that Arkali Khan, who was now the undisputed heir of his father, had all his own way and used all the influence he possessed with the Sultan to unravel the plot and bring to condign punishment, his old enemies, the men who had plotted with his brother to deprive him of his birthright. We read that it was he who egged on the Mahout to drive his elephant over the Side and trample him to death. Barani who was a Sayyad by birth appears to have been horrified by the capital punishment, without trial or proof, of a venerated Darvish and the manner in which he speaks of the dust-storm (Indh) and the famine which followed the catastrophe indicates that he looked upon the Sidi as a sort of martyr story, as he himself and others relate it, clearly indicates that there was a conspiracy and that the Sidi was deeply implicated in it

III 145, l 6 from foot Shaikh Abu Bakr Tusi was present with a number of his followers

Shaikh Abu Bakr Tūsi is said by Barani to have been a Haidari Qalandar The sobriquet refers to the founder of the order, Najmu-d-dīn Tūsi The Sarāi of Shaikh Abu Bakr Tūsi in Dehli was existing in the reign of Sultan Firūz Tughlaq (Shams-i Sirāj, 303 infi a) The Qalandars shave off the hair on the head and face and even the eyebrows The Shaikh's follower, Bahri, was able to whip out at once the razor with which he gave the first cuts to the Sīdi, because it was habitually carried about by the sect for their tonsorial operations "Qalandars and Haidais" are again mentioned by Barani. (Text, 546, 558, 573)

III 146, 1 18 and note. He took the of Jhain

תנילים אוני בין ייי כן אלפים, 213, 1 4 Dowson says he does not know what commons. The word is used again by Barani in two other passages, in which also he has left it untranslated. It signifies "immediately on going there," "as soon as he went there or reached the place" At p 333, 18, Barani says that ישוב על היי ליי ליי מוד אוני מוד אוני מוד אוני של אוני

III. 148, l. 6. Ghiyaspur, Indarpat and Talūka.

The name 'Ghiyāṣpur' has fallen into oblivion, but it is what is now known as 'Nizāmu-d-dīn.' Barani says that Nizāmu-d-dīn Auliyā resided at Ghiyāṣpur in his lifetime (396, l. 11), and B. tells us that the saint's tomb is situated in Ghiyāṣpur. (I. 173=Tr. 236). The name may have been derived from Sultin Ghiyāṣu-d-din Balban, of whom Abul Fazl states that he also built a fort in Dehli. (Aīn, Tr. II. 279). Mughalpūr (l. 7) is still the name of a village near Dehli and it is shown on the map prefixed to Thomas's Chronicles. Talūka ot cannot be identified.

III. 149, l. 1. The Sultan.... thought that 'Alāu-d-din was so troubled by his wife and mother-in-law.

The B. I. Text reads the sentence with a negative, which has been overlooked by Dowson or was dropped out in his manuscript. The context which follows shows that the particle cannot be dispensed with. It is stated only a few lines lower down, that "Alāu-d-dīn was averse to bringing the disobedience of his wife before the Sultan." Jalālu-d-dīn did not know that 'Alāu-d-dīn was so "troubled by his wife." The nephew had been ashamed to speak openly about his domestic unhappiness to his wife's father. Nizāmu-d-dīn Aḥmad (T. A. 63, l. 13) and F. (I. 94, l. 2f. f.) have paraphrased the sentence correctly and both explicitly state that 'Alāu-d-dīn had not dared to say anything about his griefs to the Sultan on account of the great ascendancy (استلای) of the Malika-i-Jahān.

III. 149, l. 13. He was afraid of the intrigues of the Malika-i-Jahān who had a great ascendancy over her father.

Here, the mother is confused with the daughter. 'Father' must be a slip for 'husband'. The 'Malika-i-Jahān' 'Queen of the World' was the most honoured or most favoured wife of the Sultan and not his daughter. Vide 143 supra, where she is described as "the mother of his children" in Dowson's own translation.

III. 153, l. 16: He embarked on a boat at Dhamāi and proceeded towards Karra.

chai in the Text, 231, 1. 5. It is the 'Dubhāi' of Thornton, who says that it lies on the route from Budāun to Dehli, sixty miles south-east of the latter. Lat. 28°-12′ N., Long. 78°-16′ E. It is now in Anupshahr tahṣīl, Bulandshahr district, and lies between the two head-branches of the Chhoiya Nāla or river. (I. G. XI. 341). In the Aīn, the name is spelt Dambhai or Dhundai, (an older form of the name), and it is registered as a Maḥāl in Sarkār Kol, Ṣūba Agra. (Tr. II. 186). It is the Dibai of Constable, Pl. 27. Dibāi is now a station on the East Indian Railway, thirty-three miles north-east of 'Alīgarh.

III. 154, l. 3 from foot. All.....began to repeat the chapter [of the Quran] appropriate to men in sight of death.

This is the مورة يس Sūra-i-Yāsīn, the thirty-sixth Chapter of the Holy Book' of the Muslims. Muhammad is said to have described it as

the "Heart of the Quran" (Sale's Trans, 330 Note) Herklots says that "when a person is about to die, any learned reader of the Quran is sent for and requested to read with a low voice the Soorah-e-Yaseen, in order that the spirit of the man, by the hearing of the sound, may experience an easy death, for they (Muslims) conceive that the living principles of the whole system become concentrated and shut up in the head, when death is the consequence" (Qanoon-e-Islam 2nd Ed 277 and Note).

III. 155, l 7 The Sultan took 'Alau-d-din's hand, and at that moment, the stony-hearted traitor gave the fatal signal.

As this rendering implies that it was 'Alāu-d-dīn who gave the signal, it is misleading F (I 99, 1.9 f f) and the C H I (III. 98) assert this positively and indict 'Alāu-d-dīn, but all that Barani states here (234, 1 3 f. f) "The signal of the stony-hearted traitors [in the plural] was translated into action" A few lines lower down on this very page, he is more explicit and declares that it was Nusrat Khān, [and not 'Alāu-d-dīn], who was "the giver of the signal", as Dowson himself puts it. He is called ישתר שלו ושותר בילי ושותר ביל

Barani is describing what is called آئيں سدى Qubba means 'dome, vault, arch, cupola' Shams describes these Qubbas as 'wooden pavilions hung with fine fabrics of different colours' (T F Text 88,1 3f f.) "When the Sultan returns from a journey", writes Ibn Batūta, in his account of Muhammad Tughlaq, "the town [Dehli] is decorated, and wooden pavilions (45) are built several stories high and covered with silk cloths, and in each story are singing girls, wearing magnificent dresses and ornaments, with dancing girls among them In the centre of each pavilion is a large tank made of skins and filled with syrup water, from which all the people, natives or for agencies, may drink The walls of the streets which the Sultan passes, som the gate of the city to the gate of the palace, are hung with silk cloths "(Gibb, Selections, 200-201, Defrémery, is thus described in the Taju-l-Maasir. اأس سدى is thus described in the Taju-l-Maasir. "The city [Dehl1] was decorated like the garden of Iram and the gates and walls were adorned with the gold tissues of Chin and the brocades of and the glittering of the light-Rum and triumphal arches were raised which were suspended round them inspired terror ning of the swords

in the spirit of the beholder." (E. D. II. 222).

III. 165, l. 22. The Sultan also looked askance at him.

is the phrase which is wrongly translated as "people shut their eyes at him" on 124 ante, q. v. my Note; F. paraphrases Barani's expression by the words ازو در حاب شد (I. 103, l. 6 f. f.), i.e. 'Alāu-d-dīn felt that he was a man to be reckoned with, a man who might, one day, be dangerous as an adversary. Steingass says از کسی بردن or حساب از کسی داشتن or حساب از کسی بردن signifies 'to fear, or be afraid of'. One of the many meanings of جشم زدن also, according to him, is 'to fear'. Nizāmu-d-dīn Aḥmad roundly says that 'Alāu-d-dīn was jealous and afraid of Zafar Khān, در غبرت و در يم بود (71, l. 5). III. 166, l. 1. Katlagh Khwāja, son of the accursed Zūd.

The name of Qutlugh Khwāja's father was, as Dowson says, (ante, 42 Note), Dūā or Dawā. Waṣṣāf calls him 'Dūā' and B. 'Duā Khān.' (I. 184—Tr. I. 250). He reigned from 1273 to 1306 A. C. and is said, in the Mongol histories, to have "possessed himself of Ghazni, and from that stronghold as a base, to have made several expeditions into India and ravaged the Punjab and Sind at different times between 1296 and 1301 A. C." (Ney Elias and Ross, Tr. Tārīkh-i-Rashīdi, Introd. 35-36). 'Qutlugh' as a word, is said in Turki dictionaries, to mean 'auspicious,' prosperous,' 'blessed.' (Blochmann, J. A. S. B. 1869, p. 211 Note).

III. 166, l. 2 from foot. 'Alāu-d-dīn marched from Sīri to Kīli and there encamped.

Dehli antiquarians are not agreed as to the site of Kīli. Mr. Keene locates it about 10 miles north of the capital. (History of Hindustan, I. 76). Others identify it with what is now known as Khirki and which is marked as 'Kherhee' on the map of Dehli prefixed to Thomas's Chronicles. Muḥammād Tughlaq's fortification called 'Jahānpanāh' is said by that eminent archaeologist to have "formed an enceinte of five miles and to have enclosed the space from the Qutb, by Khirki (or Kherhee), Chirāgh-i-Dehli and Shāpuri (or Siri)". (Op. Cit. 261). The village of Khirki in Jahānpanāh still exists and contains a fine mosque attributed to Jauna Shāh, i.e. Khān Jahān II, Vazīr of Firūz Tughlaq. In an old 'Handbook for Delhi,' written by Mr. Frederick Cooper in 1868, Kherhee or Khirki is located two miles N. E. of the Qutb. (p. 86).

III. 167, l. 6 from foot. The Mughals, thus on that day gained the advantage.

. 261, 1. 6 ; منل در آن روز بحیله شب کرنتند

'The Mughals were, by a trick, just able to carry on through the night-time,' that is, they just managed, under the shades of night, to make a stand and cover their retreat. They contrived, somehow, to escape without suffering a crushing defeat. They did not "gain the advantage," as they are said to have been so discomfited that they did not stop in their flight or draw rein until they had put a distance of thirty kos between themselves and their yietorious pursuers.

III. 168, l. 2 If their [the Mongols'] cattle refused to drink, they used to ask if they saw Zafar Khān.

This savours more of folk-lore than of fact. It is exactly the old story about Richard the Lion-hearted and the horses of the Saracens, which is told by the French chronicler, De Joinville (Elliot's Note, I. 532-3). Another close parallel is found much nearer home in an anecdote told by Scott Waring about the Mahrattas "When a horse refused to drink and started at his own shadow, it was, say the Mahratta chronicles, a common noke among the Moghals to ask him why he was afraid- 'One would think you saw Dhunnaji (Jadhav) in the water'" (Quoted by Grant Duff, History of the Mahrattas, 179 note) Enlarging on his theme. Joinville further states that the name of the English king "acted as a powerful sedative upon the children of the Saiacens" There is a variant of this supplementary detail also in a Sindhi chronicle of the 17th Century Mubarak Khān, the minister of the Jam Nanda, is there said to have so thoroughly subjugated the turbulent tribes of Kich [Kej] and Makran and inspired such terror, that prognant women miscarried if they heard of his approach, and the words 'Silonce, the terrible c'iteftain is coming,' were enough to stop the crying of a wayward child" (Tr Tārīkh-i-Tāhiri, in E D I 276) Still another arresting analogue, or rather, picturesque Oriental metaphor expressive of extreme fright, is to be found in one of the yarns spun by Manucci. He says of Ruy Freire d'Andrade, (who was the Portuguese Governor of Ormuz in 1622 A C) that "among the Arab women of Muscat, it was customary to pronounce his name to pacify any restless or crying child and suppress and subdue the noise". (Storia, Tr Irvine III 222). Lastly, Khwasi Khan tells exactly the same tale of the Mughal general, Aghar Khan His name was such a terror among the Afghans, that mothers used to repeat it to frighten and send to sleep fra etious and weeping children. (Muntakhabu-l-Lubāb. II 246, 1 7 f f) III 171, last line Hamir Deo, grandson of Pithaura

The word used is (Text, 272, 12), which is often loosely employed for a distant descendant also Hammira Deva was the son of Jaitrasinha, the son of Vägbhata or Bähad, the son of Prahlāda, the son of Vallana, or Bilhan, the son of Govindarāja, the [son or] grandson of Prithvirāja This is the pedigree given in the Hammira Mahā Kāvya, a Sanskrit epic composed in the reign of Vīramadeva, Tomar raja of Gwalior, by Nayachandra Sūri in the 15th century A C (V J Kirtane's Ed Introd passim) also are similarly used for 'distant descendants' HI 174, l 10 Akat Khān rushed out of the tents and fled to Afghānpur

Afghanpur is said, at 235 infi a, to have been three or four kos from Delhi B speaks of it as three or four kos from Tughlaqabad (I 224—Tr I 300) A village named Aghwanpur still exists about five miles to the south-east of Tughlaqabad It is also mentioned in the Qiranu-s-S'adain of Amīr Khusrau in Juxtaposition with Tilpat, which lies about twelve miles of Delhi. (528 infra) Blochmann says' Ikit Khan' means the Young

Khān.' Mrs. Beveridge states that 'Yigît' signifies 'young'. (B. N. Tr. 16).

III. 174, footnote. Firishta says, each man filled his bag with sand and cast it into the trench (darra), which they call Rāran.

ر درو که از ارن میکویند انداختنه (I. 108, 1. 10). "They threw them into the valley, which is called Ran." What F. really states is that the 'Darra' or Valley was called 'Ran', not 'Raran.' Dowson appears to have understood the preposition $R\tilde{a}$ as a part of the place-name. His error is clearly shown by the following quotation from 'Abul Fazl. He tells us in his narrative of Akbar's siege of Ranthambhor that "Ran is the name of a high hill which overtops it, and people say that while all other forts are naked, this is mail-clad, because it is in the middle of the hill country." (A. N. Text, II, 335; Tr. II. 490). And Jahangir writes thus in his 'Memoirs': "There are two hills close to each other. They call one Ran and the other Thanbur. The fort is built on the top of Thanbur, and putting these two names together, they have called it Ranthambur.The hill of Ran is a specially strong fortress (in itself) and the capture of the fortress depends upon the possession of this hill." (Tuzuk, Tr. II. 58. Text, 256, l. 15). B. also informs us that the hill called 'Ran' commands the fortress. (II. 107, Tr. II. 111). The fact is that Ranthambor stands on an isolated rock, 1578 feet above sea level, at the head of a gorge which can be very easily defended by a handful of men. (I.G. XXI. s. n.). The derivation given by Jahangir is an example of folk-etymology. The old Hindu name of the place is not certainly known. In the Hammira Mahākāvya, it is always written as 'Ranastliambhapura', 'City of the Pillar of the Battlefield', and this form occurs also in an inscription of the thirteenth century. (Ind. Ant. XLI. 85 ff; Epig. Ind. XIX. 48 ff.) Some Hindu scholars, however, identify it with Rantipur, which was the abode of Rantideva, Rijā of Maheshwar, whose sacrifice of cows is mentioned in the Mahābhārata and is alluded to by Kālīdāsa in the Megha-dūta. (N. Dey, Geographical Dictionary of Ancient and Mediaeval India, s. n. Rantīpura). 'Raņasthambliapura' may or may not be a Sanskritised form of some indigenous name, but the restoration proposed by Colebrooke, "Ranasthambhabhramara", "Bee of the pillar of War" (J. R. A. S., I. 142) is, almost certainly, factitious and inadmissible. In this connection, it is worth noting that the name is always written (تنبور [Recte, تنبور] Rantapūr, in the T. N. (Text, 179, l. 13; 213, l. 5; 293, l. 1), and also in the Persian Tuzuk-i-Babari, (Text, 179, l. 2 f. f.; E.D. IV, 261), while in two Afghan chronicles, the spelling is 'Ranthur,' (E. D. IV. 395 note and 478). Edward Terry, Sir Thomas Roe's chaplain, also spells the name as 'Rantipore' (E. T. I., 293) and De Laet writes it in exactly the same way. (Tr. Hoyland, 36).

III. 175, l. 23. He was charged with the guard of the exchequer.

رتول داشت; 278, 1. 8 from foot. There is the variant برتول داشت, which Dowson says is unintelligible. F. asserts that Ḥājji had occupied

the post of the سرشجه (Chief Police Officer ?) of Dehli in the reign of Jalalu-d-din Khalji. (I 107, 1 8 f. f). Barani's words really mean that he was 'superintendent or manager of the Khālisa lands' in some district. looks like the name of a place and by a slight transposition of the diacritical points, may be read as أودل Narnol. Narnaul is about 86 miles south of Dehli, and we know that it was one of the districts usually included among the Khālisa, i. e. the Exchequer lands, in the time of Akbar (A N. II. 199, Tr. II. 309) But Narnaul is always written with an alif by Barani and almost all other writers. I suggest that the right reading is رَو ل Rataul, a small town lying about fifteen miles northeast of Dehli which still exists and is now included in the Bighpat tahsil of Mirat district It is about 12 miles south of Baghpat town and 26 miles S. W of Meerut. Major Fuller's Ms of the Barani's Tarikh also read the name as' Rataul' and his rendering was 'Superintendent of the Crown lands of Rataul' (J. A. S. B. 1869, p. 216), though neither he, nor his editor and annotator, the learned Blochmann, could say where Rataul was. We know from Barani that Dehli and the Ganges-Jumna Duib, together with part of what is now Northern Robilkhand, were included in the Khalisa lands, e lands which were managed by the Discan-i-Vizarat or Chief Revenue Minister in Dehli through officials who were in direct relations with the peasants. Their proximity to the capital made this the most natural and convenient arrangement and we may be sure that Rataul was included in the Khālisa lands under 'Alaū-d-din (T F 306, 1 1 See also Moreland, 'A S N I, 38) Hājji Dabīr who had an excellent copy of Barani's Chronicle also reads 'Rataul' حالمه رتول أي حوالته (Z W 804, 1 7)

III. 176, l 7 from foot. There was an 'Alux (descendant of 'Ali)
in Dehli who was called the grandson of the
Shāh Najaf

This is a crabbed and doubtful passage and the popular designation of the unfortunate Sayyadzida is written in all sorts of ways by the later compilers. The T A says that he was known as the 'Muhtasib' (I 107. last line), and B عنست (84, 1 10) F.'s reading is 'Shāhinshah' styles him - i (I. 193 = Tr I. 260) These are due to copyists' blundering attempts to correct what they did not understand It seems to me that the reading in the B. I Text of Barani co 'Descendant of the Shah-i-Najaf' is correct as well as straightforward and there need be no difficulty in accepting it 'Shah-i-Najaf' is 'Ali, the son-in-law of the Arabian Prophet He hes buried at Najaf, which is about a hundred miles south of Baghdad, and four miles westward of the ruins of Kufa, in the mosque of which town he was assassinated The Mashhad or shrine of 'Alı at Najaf is said to have been built about 175 H Kerbela, the Mausoleum of his son Husain, is eight leagues north of Kufa and marks the site of the battle in which Husain was slain, with nearly all his family (Le Strange, L E C 76-78) Beale tells us that Shah 'Abbas the Great went on pilgrimage to the tomb of the 'Shāh-i-Najaf' in 1032 H

The T. A. reads this as Amīr-i-Kūi (74, 1. 12) and is followed by B. (I. 194, 1. 4), who says that Ḥamīdu-d-dīn " held the office of Chief of the Streets", though Ranking speaks of him as 'Amīr-i-Koh' in his translation (I. 261), probably because he could make nothing of But the Tārīkh-i-Mubārakshāhi says of the Sayyad Sultan, 'Alāu-d-dīn 'Ālam Shāh that he gave the office of 'Shaḥna' (Chief of Police) of Dehli to one of his brothers-in-law, and that of 'Amīr-i-Kūi' (Prefect of the Roads) to the other. The two men quarrelled in his absence and the latter was put to death at the instigation of the Shaḥna, upon which the inhabitants rose in revolt and killed the Shaḥna. (E.D.IV. 87, q. v. my note). 'Amīr-i-Kūī' may be right.

III. 177, l. 7. They proceeded towards the gate of Bhandar-kāl.

Sic also in the C. H. I. III. 105, but it has no meaning and the correct name is, most probably, Bhadrakāli, one of the names of the goddess Durgā, otherwise called Pārvati, Māyā, Bhavāni, Kāli, etc. The name may have been given, either because a temple dedicated to her was situated in the vicinity or because this gate led to it. The still-existing Mandir of Kālikā in the village of Bahāpur which lies about six kos south of Shāhjahānābād (Āṣāru-s-Ṣanādīd, Pt. 1. p. 15) is known to be of great antiquity and the gate may have been named after this temple. The 'Bhadra' or Citadel in Aḥmadābād is so called because there was a temple of Bhadra Kāli on the spot in pre-Muhammadan times.

III. 179, l. 11. And the angel of destiny took him to the blessed city.

و قضا اجل در آمد اورا بوفت آوردن شهر مبارك دريافت; 283, l. 8 f. f. Barani can hardly mean that the Angel of Death took Ulugh Khān, whose perfidy and inhuman cruelty he has denounced so frequently, to Paradise. Elsewhere, he speaks again of the event thus:

229, l. 6 f.f. والنخان را زحتی حادث شد و در آوردن شهر میان راه در منزلی نقل کرد. The sentence first quoted means that "the Angel of Destiny approached

and seized him [Ulugh Khān] when he was being brought to the auspicious city", i. e. Delhi The second signifies that "Ulugh Khān was taken ill, and died at a halting place on the way, while being brought to the city." According to the T A., Ulugh Khān was seized with illness, soon after the capture of Ranthambhor, and died en route to Delhi در راه والت يأت (Tō, 1 1) F, as usual, copies its very words در راه والت يأت (I. 108, 1 16). B. also states that he died while on the road (I 194=Tr I 261) This rendering of تم مارك by Blessed City' is equivocal and not unlikely to be misunderstood. It means only 'auspicious city' and is nothing more than an honorific epithet of Delhi Hājji Dabīr states, on the authority of Husām Khān's Tabaqāt-i-Bahādurshāhi, that Ulugh Khān was poisoned while returning from Ranthambhor to Delhi (Z. W. 811, 1 11)

III 180, l 1. Nobles dared not speak aloud even in the largest palaces

284,1.11. Barani is ملوك را در مهار ستون امكان سحن كشاده كمَنَّن بانده اود not speaking of 'large palaces' in general, but of the Palace built by 'Alaud-din for himself in Siri, which was known as the Hazar Situn, 'The Thousand-pillared,' because it possessed a capacious Hall of Audience which had an indefinitely large number of columns Muhammad Tughlaq raised another Hazār-Sitūn in Jahānpanāh, which Ibn Batūta describes as "an immense chamber called 'Thousand Columns', the pillars of which were of varnished wood and supported a roof painted in the most admirable style" (612 infra) Abul Fazl also says of Muhammad Tughlaq that he "raised a lofty pile with a thousand columns of marble in the New City which was founded by him" (Ain, Tr II 279). 'Abul Fazl's description is evidently 'embroidered' The Hazār-Sitūn of 'Alāu-d-din is frequently mentioned in Dowson's own translation of Barani's history. (209, 222 infra) It is also referred to by F (I 112) The ruins of the Hazar-Stiin of Muhammad Tughlaq can be still seen S W. of Jahanpanah The date of its completion, 727 A H, is recorded in Badr-1-Chach's Arabic chronogram, أدخاوها, 'Enter then her gates' (B I 222 = Tr I. 296) excavations at the Bijaya Mandal in Old Dehli have brought to light the stone bases of the pillars of Muhammad Tughlaq's Hazār-Sitūn

III. 180, l 6. He prohibited wine-drinking and wine-selling, as also the use of beer and intoxicating drugs

The word rendered as 'beer' is (Bagni or Bugni). It is defined in the Burhān-i Qāti'a and other Persian lexicons, as a kind of light or unintoxicating wine, which is placed by the theologians in the same category as 'w' Nabīdh, an unfermented infusion of dates, raisins etc, which can be lawfully imbibed by the orthodox (Hughes, Dict of Islam s. v. Nabīdh) But Steingass says that 'Bagni' is malt liquor or beer, and that 'Bagni-i-arzan' is beer made from millet In that case, it would be the same as or very similar to the convert's burning zeal for 'total prohibition,' appears to have classed Bagni with the unlawful and intoxicating drinks and gone

further than the theologians.

III. 182. 1.9 from foot. From the Khûta to the Balahar.

Blochmann was puzzled by the first of these words. He thought that it was the Arabic -; 'a fine strong man.' Steingass states that the primary meaning of the word is 'a limber twig' and the secondary sense 'a corpulent man, yet handsome and active.' But 'Khūt' is admittedly used by Barani for 'a landowner, village head-man or zamindar,' and it is not easy to understand the transition of meaning and say how a 'limber twig' or 'corpulent man' could have come to denote 'a rural chief or land-holder.' The fact seems to be that Khūt is, just like Balahar, one of the numerous vernacular vocables which Barani interlards so freely with his Persian. It seems to have nothing to do with the Arabic is and the phonetic resemblance is purely accidental. Landholders called 'Khots' are to be found still in Gujarāt and the Dekkan. The word may be derived from the Sanskrit Kūta, 'chief. head.' The village headman is called Gramakuta in more than one grant of the Kings of Valabhi. 'Grama' means 'village' and 'Kūta' (or Kuda), 'chief, leader'. Compare the dynastic title Rashtrakuta. (Bom. Gaz. I., l. S2, 119. See also H. M. H. I., I. 157, III, 460). Another possible derivation is from Mahratti, Kheta, field.

Mr. W. H. Moreland upholds Blochmann's hypothetical derivation, but his conjecture or assumption that " the Arabic Khut passed from Delhi to the Dekkan" at the time of 'Alau-d-din's conquest and became naturalised there as 'Khot' (A. S. M. I. 226) seems to be largely invalidated by the fact that Gramakata, of which 'Khot' looks like a short or decapitated form, was the designation of the village headman or landowner even in the seventh century. He does not lead any historical evidence to support the conjecture and the linguistic argument by which he seeks to reinforce it appears to me to be untenable. He lays great stress on the point that "Barani writes the word with two Arabic letters, and this fact makes its derivation from any Sanskritic language highly improbable." (Ibid, 225). This argument is easily answered. In the first place, it is exceedingly doubtful if t is an 'Arabic letter' at all All the Arabic and Persian grammarians include only eight signs of their alphabet in this category, viz. ث- و- ف- ف- ف- ع- فـ Budīuni also gives exactly the same list of Arabic letters. (II. 307, Tr. 316), Khā (*) is even called the Persian Ha, in Richardson's Dictionary But granting that it is an Arabic letter and that ico of them. it would be easy to show that this does not at all preclude the possibility of its "derivation from a Sanskritic language". There are severe views in Arabic which are spelt with two of these letters and reference monstrably loan-words, vocables which are derived from Santal or Latin. Witness the following:

منظر و Patriarch عطريق : Astrolibe اصطرلاب ; Stable اصطبل

Colocynth, طریاق (Gr. Theriakon), فیراط (Gr. Keration), طریاق Quintal, (from Lat Centum), الرابطا (Gr. Parakletos); فرطاس (Gr. Khartes, leaf of papyrus) Paper منطری (Sansk Chaturanga); یطار (Lat. Veternarius), نقط (Gr. Naphth, Zend. Napta); منطنیق (Gr. Klima), منطنیق are examples of loan-words which have one Arabic letter

I am aware that the derivation of 'Khot' from Kūta is not without difficulties, but in any case, it seems to me fairly certain that the word is not of Arabic origin and that it did not "pass from Dehli to the Dekkan" in the 14th Century

III. 183, l 10 Sharaf Kāi, Nāib-wazīr, rigorously enforced his demands
In the Manuscript belonging to Major Fuller, the sobriquet is written
Qāīni إلى and Blochmann had no doubt that it was correct (J. A S B
1870, p 8 and note) Elsewhere in the Bibl Ind. Text of Barani, (337, ll.
4 and 5), Sharaf is styled 'Qāīni' and the identical spelling is found in
Hājji Dabīr (Z W 824, l 16) A man named Abu Ibrāhīm Qāīni was
the Kadkhuda (Steward or Manager) of Khwāja Ahmad Hasan Maimandi,
the Vazīr of Mahmūd of Ghazna, and another called Abu Muhammad
Qāīni was his secretary (Baihaqi, Text, 178, E. D II. 70-1) Qāīn and
Tūn are the chief cities of Quhistān The district is also known as 'Tabas
and Tūn' Qāīn is marked in Bartholomew's Every Man's Library Atlas,
Map. 45 Lat 33° N, Long. 59° E Qāīni is, most probably, right

'III 184, l 21 The glorification of Islam is a duty and contempt of religion is vain

have been read wrongly and the real meaning consequently obscured. What the Qāzi really says is that the humiliation of the Zimmi and the throwing of the dirt (Recte, spittle, خوک) by the tax-collector into his mouth redounds to "the honour of the Religion of Islam which is true and to the degradation of the Creed which is false, viz the Creed of the Hindus" There is a parallel expression in 'Utbi which is so striking that it may bear quotation After describing the crushing defeat of Trilochanapāla by Mahmūd near Nandana in 1013 A.C., he writes "Slaves were so plentiful that they became very cheap and men of respectability in their native land were degraded to the possession of slaves of common shopkeepers. But this is the goodness of God, who bestows honour on His own religion and degrades infidelity" (E. D. II 39)

III 185, l 2. Karı (house-tax) and Charı (pasturê-tax)

The first word is variously spelt as Son - Row be little doubt that it should be pronounced Ghari, Son, from the Hindi of house, residence Shams-i-Sirāj gives its Persian and Arabic synonyms as it and son, i.e (Ground-rent, Rent of land by which the owner makes a profit) (Text, 375, 1 13, 363 infra) B speaks of this 'Ghari' as identical with the Son 'House-tax' and of 'Charāi' as the same as the Solidantical with t

III. 188, l. 4. Extortion I punish with the torture of the pincers and the stick.

عال مطالبه بزخم انبر و جوب مبطلبم بعلم عاليه بزخم انبر و جوب مبطلبم 295, 1.4. "I exact all moneys due to the state with pincers and the stick." مال مطالبه does not mean 'extortion,' but the taxes, revenue cesses, and all moneys or arrears due to the State from the cultivator, tax-collector, fief-holder or any other individual. The words and مطالبة occur frequently in Barani's History (107, 1. 8; 418, 1. 4; 480, last line; 574, 1. 20) for 'demand, exaction, mode of recovering moneys', and also 'arrears due'. Dowson renders the phrase as ' heavy demands and oppressive exactions of the revenue ' in دفترهای مطالبه و جم خرج , the third of these passages, (243 infra). In the second can only mean "Ledgers of Outstandings due and of Revenue and Expenditure." It has been the universal practice of Oriental as well as Occidental administrations to regard all debts due to the State as the first charge on the assets of the individual who was liable for them, and it was customary to spare no coercive measures and no mode of punishment in recovering and exacting the very last denier from a debtor or defaulter. Mahmud Ghaznavi and many other princes had been as inhuman as 'Alau-d-din and made as cruel use of the whip, the pincers and the rack to enforce their claims. (Baihaqi, Text, 146). The only new thing about his proceedings was that he avowed and flaunted his barbarity with such a flamboyant disregard of law as well as equity, that even Barani has punctuated the report of his speeches with marks of horror and amazement.

III. 193, l. 12. In the country dependent on the New City, half the Sultan's portion (of the produce) was to be taken in grain. In Jhāin also, and in the villages of Jhāin stores were to be formed.

The New City, i, stands here not for Sīri, but for the 'New Town' founded by 'Alāu-d-dīn near Jhāin. Barani means that the grain collected in this 'New City' and its dependent villages was to be stored in granaries in the district itself, so as to be easily available for conveyance to Dehli in time of need. Barani has said before that when Ulugh Khān died, 'Izzu-d-dīn Būr Khān became Vazīr of the New City, Shahr-i-Nau, (near Jhāīn), and that the tribute of the 'New City' was assessed, by actual measurement, at a certain rate per bisva, i.e. 1/20th of a Bingha, just as in the environs of the Capital. (188 supra). This leaves no doubt that the 'New City' of this passage is the 'Shahr-i-Nau' near Jhāin and not Sīri. III. 195, l. 3 from foot. If in such a season, any poor reduced person went to the market and did not get assistance.

و اکر در امسائے باران از هجوم خلق کسی از مسکینان و ضعفا زیر بای آمدی و موازنه 309, 1.3. "And if in years of deficient rainfall, any indigent or old and feeble persons were trodden under the feet [and killed] on account of the rush of the populace and if adequate arrangements were not made in regard to the due proportion or average of people allowed to enter inside the market."

III. 197, l 4 from foot That one or two horsemen would tie by the neck and bring in ten Mughal prisoners and one Musalman horseman would drive a hundred Mughals before him

یك دو اسیه ده معل را رشته دركردن انداخته ی آورد و یك سواز مسلمان صد سوار معل That one Douspale (the groom or follower " 7 320, 17" را بش كرده میدوانند who led the second, spare or relay horse and was paid only seventy-eight tangus per annuml would bring in ten Mughals, having thrown r rope round their necks, and a single Musalman trooper [sucur] would drive a hundred Mughal horsemen before him". This passage is important in connection with the real meaning of the word 'Doasna' He is placed here evidently in a much lower grade than the Sucar-the fullyequipped horseman. (or مرتب) It is clear from what Barani cays that this 'Doasna' was only a follower, lightly armed, a sort of adjunct or attendant of the Sugar. He was probably the groom who led the spare horse, the sumpter or relay. In that case, there should be no difficulty in understanding why the 'Donspa' was to be paid only 78 tangas, while the allowance of the Suicar, Murattab or fully-equipped trooper was 234 tangas It would seem that the 1 ak aspa or 'one-horse trooper' was paid 156 tangas Barani does not make any specific reference to the allowance of the Yak aspa, but Firishta explicitly states that 'Alau-d-din fixed three scales of or soldier's pay First class, 231 Tangas; Second, 156 Tangas, and Third, 78 Tangas (I 114, 1, 17) I take the meaning to be that the Murattab with two horses was in the First class, the Yak-aspa or trooper with one horse in the Second, and the Doaspa or the groom who led the relay in the Third. It is possible that the meaning of the word 'Doaspa' in the days of 'Alau-d-din, or as used by Barani, was very different to what it was in those of Akbar If this interpretation is accepted, the paradoxical statement at p. 192 ante, (q. v. Dowson's Note on 625-6 infra), explains itself and becomes perfectly intelligible

III. 201, l. 12. He kas to come to an arrangement and retire....lest Laddar Deo should get the better of him. If he could not do this, he was for the sake of his own name and fame, to bring the Rai to Dehli.

و در سد آن مناشی که رای لدر دیو بر تو آید یا برای نام و آواره برابر خود کرده معلی آری برای دا بدهلی آری (۱ مناشی که رای دا بدهلی آری (۱ مناشی که یا که که برای دا بدهلی آری (۱ مناشی که برای دا بدهلی آری (۱ مناشی که برای دا بدهلی آری (۱ مناشی که برای داد مناشی که در که برای که برای که در مناشی که در که برای که در که د

'Alau-d-din appears to have been alluding to what had been done in the expedition of the preceding year Kāfur had then compelled Rām Deva to accompany him to Dehli and 'Alau-d-din had had to send that ruler back to Deogiri after a six months' detention in the capital. Before despatching him on this second expedition, the Sultan

specially warned Kafur against the repetition of such impolitic proceedings.

III. 201, l. 17. Malik Nāib Kāfūr marched to Rābari, a village in the fief of the Mālik.

Rāpri has disappeared from most of our modern maps, but it was a place of considerable importance in the old days, on account of its commanding one of the fords on the Jumna. (Elliot, Races. I. 26). It is frequently mentioned in the Tārīkh-i-Mubārakshāhi, (E.D.IV. 47, 64, 65, 68) and also in the Bābur-nāma. (Trans. 523, 581, 582, 598,643). Is is now a ruined village, about forty-four miles south-west of Mainpuri town in the Shikohābād taḥṣīl of Mainpuri district. (I. G. XXI. 236). It was near Chandawār, another old town which has sunk into insignificance and been supplanted by Firūzābād. Lat. 26°-58′ N., Long. 71°-36′ E. (I.G. XIII. 34).

III. 202, 1. 9. When Malik Kāfūr arrived in Tilang, he found the towns and villages in his way laid waste.

were looted, sacked and devastated by the invading host with a view to inspire terror, and not 'laid waste' by the people of those parts. F. says that when Kāfūr arrived at Indūr on the frontiers of Tilang, he gave orders "for plundering and ravaging the country and killing and enslaving the inhabitants, who were plunged thereby into indescribable consternation." (I. 119, l. 4).

III. 204, last line. He was desirous that all the business of the state should be concentrated in one office, and under the officers of that office; and that the control of all matters should be in charge of men of his own race (Zāt).

according to Richar الماحت . 5 . 336 , در شهر ااحتیان و بودهگان پیدا آمدید son, means 'license, licentious men' Hughes defines 'Ibahiyah' as " a se of libertines who consider all things lawful". (Dictionary of Islam, s F informs us in his paraphrase of the passage that these 'Ibahatii belonged to a society of which the members, males and females, used assemble on a certain day every year and indulge in promiscuous sex intercourse (I 120, 1 8 f. f) For this explanatory gloss, he is indebted Amír Khusrau, who writes thus of the 'As'hāb-r-Ibāhat' of 'Alāu-d-di days "It was discovered that among these shameless wretches, mothhad cohabited with their own sons and aunts (mothers' sisters) with th nephews, that the father had taken his daughter for his bride and the had been connection between brothers and sisters" (Khazāinu-l-Fut Text. 21, 1.7; Tr 12) Prof Habib thinks that the reference is to t Ism'aili heretics and he may be right, as they are "indiscriminately call Qarmatians, Bātinis, Malāhidas and even Mazdakians in Persian literatur (Browne, L H P I 172, 312) Shahrastānı notes that ın Khurāsān, t 'Bātınıyas' were known as 'Ta'alimites' and 'Malahıda', but in 'Iraq 'Qarāmita' and 'Mazdakis'. (Kītāb-ī-Millal wa Nahal, Ed. Cureton 14 1 8 See also Houtsma, E I, I 670). The last designation indicates tl they were accused, wrongly or rightly, of holding the abominable co munistic doctrines associated with the name of the heresiarch Mazdi As the Ism'ailis claimed to have been emancipated by their gospel from the obligation to observe the moral and religious code of Islam, they we believed by their detractors to be capable of every kind of wickedness at dissolute antinomianism and accused of "permitting marriages within t prohibited degrees and practising incest in their secret assemblies"] Clement Huart assures us that towards the end of his career, Qarmat d demand from his followers community of wives and property (Houtsn E I IL 246) The Zikris and Maulais of Makran and Chitral a Ism'ails and they have also been accused, by their enemies, of incestuo practices (I. G VII 291). In the Futuhāt-a-Firuzshāhi, the Ibāhati and Malalida are mentioned in juxtaposition and almost assimilate together and their real or alleged orgies of lust and libidinous excess as described in almost identical terms (368 infra)

presents greater difficulty and Blochmann confessed that I could make nothing of the word. (J A S B 1870, p 51 note) I ventue to suggest that the 'dāl' should be read as a 'rā 'and that the right lections ورهكان I suggest that the reference is to the Borahs who are a branch of the Ism'āīlis They also are reckoned by the Sunnis among the Rāfizis, is Heretics They belong, in fact, to the Musta'ālian division of the Ism'āīli or 'Sect of the Seven' and are a sub-division of the Malāhida, with who the Ibāhatiān are associated and identified by Sultān Firūz Just as 'Utlicharges Dāūd of Multān with Ibāhat (263, l 1 f.f) and Ibnu-l-Athīr with Ilhād (Kāmil, Bulāk Ed, IX 64, l, 25, E D II 248), so Borahgān and Ibāhatiān are here bracketed together by Barani, The laws of marriage

divorce and inheritance, etc. of the Borahs are opposed, in several points. to those of the Sunnis. They have also cut down the five daily prayers which are obligatory on all Sunnis practically to three. They pray also like all Shi'as with their arms straight by their side, while the Sunnis do so with the arms folded. (Enthoven, Tribes and Castes of Bombay. II. 226). The Fatimide or Ism'aili Khalif Mustansir who reigned from 1036-1094 A. C. had two sons, Must'ali and Nizār. Their rival claims divided the sect into two rival branches, a Western (Egyptian or North African) and an Eastern (Persian and Syrian). The Borabs belong to the former or Musta-'ālian section, the Khojas or followers of Hasan-i-Sabbāh to the latter or Nizārian. (L. H. P. II. 199, 204, 210, 460). According to the traditional history of the sect, Abdulla, their first Da'i, Missionary or Apostle, is said to have landed at Cambay in A. H. 460=1067 A. C. and a second propagandist named Muhammad 'Ali to have arrived in 532 H .= 1137 A. C. (Enthoven. loc. cit; Houtsma, E. I., I. 738-9; J. B. B. R. A. S. New Series, IX. 1933, pp. 42, 45). Ibn Batūta met at Gandhar near Broach the wealthy Musalman shipowner Nākhodā Ibrāhim, the son of Khoja Bohra. (Defrémery, IV. 58). Both these sects were persecuted by Aurangzeb as heretics. III. 207, l. 1 from foot. This eunuch and minion had the chief place in his regards.

و آن مجبوب وابون را سری در خاطر متکن کشت; 368, l. 7. 'And in the heart (or mind) of that eunuch and catamite, the desire of becoming the Head [of the State] was implanted' [or became fixed]. F. (I. 122, l. 5 f.f.) says of Kāfūr that "the vain ambition of imperial sway had taken root in his head". هواي ملك در سرش انناده بود. Elsewhere, Barani states of Malik Nizāmuddīn, the minister of Mu'izzu-d-dīn Kaiqubād who aspired like Kāfūr, to the throne, that ملك نظام الدين را هوس سرى در سر افتاد (T. F. 132, l. 2) and Dowson's paraphrase is "His head was filled with ambitious designs." (126 ante).

III. 208, l. 2. Their feud involved the whole state.

و سر جله بر افتاد ملك علاي از عدادت ايشان خاست; 398, l. 9. It did not merely involve the whole state. It uprooted and brought about the fall of the dynasty. "And the gist of it all is that the overthrow of the Kingdom of 'Alāu-d-dīn resulted from the feud between them."

III. 209, l. 8 from foot. While he was thus engaged in endeavouring to remove all the family of late Sultan.

In this connection, Barani mentions a curious and interesting detail, which is left out by Dowson in the translation. He informs us that Kāfūr used to retire after business-hours to the 'Khurramgāh' which had been erected for him on the terrace of the Hazār-Sitūn palace and "play Kodis" there with other eunuchs. با خواجه سراي چند دركوري باختن مشغول شدى (375, l. 1). In the corresponding passage, the T. A. (86, l. 1 f. f.) and F. (I. 124, l. 1) employ the phrase تو ير باختن and explain that 'Chaupar' is a game akin to Nard or Backgammon and a mode of gambling. The game

of 'Chaupar' is described in the \$\frac{3m}{n}\$ (Tr. I 803-4). It seems to me that Baiani is referring not to Chaupar, but to the old Hinfly game of Pachisi which was then in much greater vogue and is also more ancient. It is necessary to make use of 'Cowire shells' in playing Pachisi, but this is not the case with Chaupar (Herklots, Qanoon-1-Islam, Ed. Crooke, 333-4). The great antiquity of Pachisi is proved by the fact that it is represented in a painting in the Iganta caves (Bom Gaz XII 528).

III 211, I. 2 Sultan Kuthu-d-din . . ascended the throne in the year 717 II

The correct year is that given by Amir Khusrau. 716 II (557 infra) The date of his assassination is given by F as 5th Rab'iu-l-awwal, 721 II (I 128, I 18 f f). But there can be no doubt that the year is wrong and that the event took place in 720 II., as the J A (95, I 18) and B (I 216 = Tr 290 and 221 = Tr 296) state. The error is due to Firishta having followed Barani, in post-dating the death of 'Miu-d-din by a year. That Sultan died on the 7th or 5th Shawwal, 715 II. Kifur was murdered 35 days later, i.e. about the 12th or 13th of Zi I-q'ad, 715 II, and Quibu-d-din, after noting as regent for about two months, ascended the throne on 21th Muharram, 716 II. (557 infra). He ruled for four years and four months altogether, as F himself avers (I 130, I 1). The true date of his assassination must therefore be 5th Rab'i I 720, not 721 II. Again, as Khusrau's usurpation endured for only four months and some days, the accession of Ghiyāsu-d-dim Tughlaq could not have taken place later than 1st Sh'aban, 720 II.

The numismatic evidence on the point is decisive and the coins provide a continuous and irrefragable chain or series of dates for determining the chronology. The latest coins of 'Alāu-d-din are dated in 715 H. All the known coins of Shihābu-d-din 'Umar exhibit the identical year. The earliest coins of Quitu-d-din Mubārak were struck in 716 H, the latest in 720 H. All the monetary issues of Nāsiru-d-dīn Khusrau bear the date 720 H, which is also the year inscribed on the money put forth by the founder of the House of Tughlaq in the initial year of his reign (See H. N. Wright, I. M. C. II. 41-47, Coinage and Metrology of the Sultans of Dehli, 112-115, Thomas, C. P. K. D. 158, 176-192)

F (I 129, l. 4 f.f), misled by the author of the Tārīkh-i-Mubārakshāhi (Text 92, ll 2 and 12), fixes the accession of Ghiyāsu-d-dīn Tughlaq on Saturday, 1st Sh'abān 721 H but 1st Sh'abān 721 H corresponded to Wednesday, 26th August 1321 A C The correct date must be 1st Sh'abān 720 H Its Julian synchronism was Saturday, 6th September 1320 A C Barani explicitly states that the battle between Khusrau and Ghāzi Malik was fought after the Nimāzi-i-dīgār on a Friday. (420, l 9) The week-day on which the accession took place must have therefore been a Saturday. The T A gives the year of Tughlaq I's accession correctly as 720 H (95, l 13)

III 212, l. 2 from foot. The wages of labourers rose twenty-five per

cent, and servants who had received ten or twelve tangas now got seventy or eighty.

: 385, 1. 5. "The wages of labour grew و اجرت مزدور مها مكر مجهار شد from one to four". i. e. rose four hundred per cent and not twenty-five only. What follows about the corresponding increase in the allowances of domestic servants from ten or twelve tangas to seventy or eighty tangas may be also urged in support of the contention that such is the literal meaning of Barani's words, though both these averments are obvious solecisms or exaggerations. Like many other old authors and orators. Oriental as well as European. Barani sometimes indulges in hyperbolical expressions. For instance, he talks light-heartedly of a 'ten times', a 'hundred times' or even of a 'thousand times' increase (30, 1. 10; 130, 1. 18; 568, 1.6 f. f.) and 'a hundredth part' or 'a thousandth part of this or that. (482, 499, 554, 556). But such comparisons should not be understood literally. They are only stock phrases or similes employed for capturing the attention or imagination of the reader or hearer. The author himself would probably be the first to disown any intention of formulating arithmetically correct equations.

III. 214, l. 3. An army was sent to put down the revolt of Alp Khān who had slain Kamālu-d-dīn Garg.

This is putting the saddle on the wrong horse.

III. 215, l. 2. Deogir had been taken possession of by Harpal Dao and Ram Deo.

So also in the B. I. Text, 389, l. 13. But it is frequently corrupt and wrong, as Blochmann has shown in his notes to Major Fuller's Translation. (J. A. S. B. 1870, pp. 3, 28, 37, 39, 50). Dowson also remarks that it is very faulty. (97 ante). Rāma Deva had died at some time during the reign of 'Alāu-d-dīn. Harapāla was the son-in-law [class] of Rāma Deva and the conjunction or wāv between the two names in the text must be an error of the copyist who has inadvertently dropped.

III. 217, l. 4. Malik Shāhīn one of his vile creatures.

There is no warrant in the text for such detraction and defamation. What Barani says is that Malik Shāhīn was the Sultan's father-in-law. عبر او بود 395, 1.5 f. f. Elsewhere, Barani says that Sanjar, who was given the title of Alp Khān was the Sultan's خبر بوده, the son of his father-in-law, i.e., wife's brother (Text, 242, 1.7; 157 supra) and that Jalālu-d-dīn was 'Alāu-d-dīn's خبر (378 l. 6). Dowson or his Ms. must have inadvertently confused خبر with

III 218, l 9 A Gujarāti named Tauba was supreme in his palace and this low-born bhand would call the nobles by the name of wife or mother

The name is probably 'Thobo', which I have often heard in Kāthiāwād It is not easy to say what 'calling the nobles by the name of wife or mother' means These words are a too literal rendering of ملوك را ام , 396, l. 5 What Barani wants to say is that this Thobo used to abuse the wives and mothers of the great Amīrs, دشأر رن و مادر ميكت. He probably uttered some of the filthy and brutal terms of vihication which are used only too often by the vulgar in India He called them dirty names. Steingass says ما المعالفة المعالف

Here the phrase used in the BI Text is رادر مادر (396, 1 & f f.), but it must be an error for עור כ אורע, as only two lines lower down and no less than four times on the page following (397, ll 7, 9, 15 and 17) and also on pp 408 and 410, he is called 'the brother' وادر of Khusrau Khan by Barani himself Unfortunately, بادر مادرى also seems to have more than one meaning It is used for a brother on the mother's side only, i. e a 'half-brother' and for a full brother also The T. A. speaks of Hisam in one passage as the "brother" and in another "as brother on the mother's side," برادر ار حاسي مادر (90, 1 1, and 93, 1 17) F (I. 125, last line) styles him برادر مادرى, but he must mean 'full brother', as he employs in the sense of 'step brother', 'brother by a different رادر عبر مادرى mother' (I 7, 14 ff) B states (I 216=Tr I 290) that Hisām was Khusrau's 'brother on the mother's side', but the phrase he elsewhere employs is دادر احالي، e half-brother or step-brother (I 211=Tr L 285) Ibn Batuta is content with stating roundly that he was Khusrau Khan's brother (605, 607 infra) The uncertainty of the relationship is further accentuated by the fact that יرادر itself is often loosely used for a 'cousin' For instance, Malik Asadu d-din is spoken of in one place by Barani as Outbu-d-din Mubarak's brother, بادر (392, 1 14), but on 1 3 of the identical page, he is more precisely described as the son of Yaghrash Khān-the uncle of 'Alāu-d-din On the whole, Hisāmu d-din would appear to have been the half-brother or cousin of Khusrau. He was certainly not his maternal uncle

It may be noted that Barani speaks of a maternal grandfather as وادر عمى or عند مادري (32, 1 18, 119, 1 13), and a cousin as رادر عمى (65, 1.16) Minhāj uses وادر ابي و امي for 'full brother' (T N 278, 1 13)

III 218, l. 7 from foot Malik Wahīdu-d-dīn Kuraishi who in compari-

son was a worthy man

ده بازی و میتری داشت بازی هم بازی و میتری داشت بازی سروری و میتری داشت بازی سروری و میتری داشت

well as by (nobility of) descent, was fit for command and leadership?. Barani means that he was capable as well as nobly born. This is indicated by the 'nisba' Quraishi. Shams also tells us that he was a Sayyad and his son had the title سند الحجاب (T. F. 445, l. 16). Barani uses the phrase صحت نسب وبزركي حب again in connection with Sayyads. (111, l. 10). مناوي مناوي عناوي مناوي عناوي عن

III. 219, l. 3. Malik 'Ainu-l-Mulk, Tāju-l-Mulk and Yamkhīru-l-Mulk were sent as Governors and assistants to Deogīr.

The reading of the last name in the B. I. Text is 'Mukhiru-d-din' (398, 1, 2). 'Yamkhīru-l-Mulk' is an impossible name and I venture to suggest that the right reading here is Mujīru-l-Mulk or Mujīru-d-dīn. 'Mujīr' signifies 'Protecting against oppressions'. Malīk Mujīr-i-Abū Rijā is mentioned by Shams-i-Sirāj (T. F. 451, 1.10) as the uncle of the notorious Shamsu-d-dīn Abū Rijā, who was Mustaufi-al-mamālik in the reign of Firuzshah Tughlaq. Shams says that Mujir was put to death by the orders of Malik Kabīr who was regent at Dehli in the last year of the reign of Muhammad Tughlaq. (Ib. 451-454). Malik Mujīr, the son of Abū Rijā, is said by Ibn Batūta also to have been one of the Amīrs of Muhammad, who was very arrogant and tyrannical. (Defrémery, IV. 5; see also III. 230, 318). Mujīr-i-Abū Rijā is mentioned by Barani as one of the twelve evil counsellors and unscrupulous sycophants of Muhammad Tughlag. (472, l. 11). His name arrests attention in another corrupt form as جبر ايورجا [Jajar], in Barani's list of the Pillars of that tyrant's State (454, l. 10), but it is correctly written by him as Mujir at Ibid, 472, l. 11. Moreover, the T. M. (101, 1, 5 f, f) and B. (I, 228; Tr. I, 235) inform us that Muhammad Tughlag entrusted to Mujīru-d-dīn-i-Abū Rijā the task of destroying completely the fort of Kalanor, after the invasion of Tarmashirin. Hājji Dabīr also avers, citing Barani as his authority, that in 718 H., Sultan Qutbu-d-din appointed 'Ainu-l-Mulk to the امارت (Governorship) of Deogir and Mujīru-d-dīn-i-Abū Rījā to the Deputygovernorship. (Z. W. 157, l. 2). This shows that his copy of the Tārīkh-i-Firūz-Shāhi had the correct reading. He repeats the statement at 844, l. 16. This should settle the question. The name of Fakhru-d-din-i-Abū Rijā is entered in the B. I. Text of Barani (379, 1. 14) in the list of Sultan Qutbu-d-din Mubārak's grandees, but here also Fakhru-d-din may be an error for Mujiru-d-din and it can be easily accounted for by the in the Semitic script. فخر and نفر in the Semitic script.

III. 219, l. 7. When Khusrū Khan marched from Deogir to M'abar, he acted in the same way as Malik Naib Kālūr had done.

The T. M. gives some additional details about this expedition which are interesting. The author declares that after defeating the Rājā of

Tilang, Khusrau proceeded to invade the country of Maithili, where he acquired 20 elephants and a diamond weighing six dirhams, after which he entered the country of M'abar (Bibl Ind. Text, 85,13) Both these statements have been copied by B (I 212, Tr. I. 286) and F (I 126, 112)

Maithili is Motupilly, a very old town near the mouth of the river Krishna It is now only a fishing village in the Bāpatla t'aluqa of Kistna district, Madras (I G XV. 321) Constable, 34, E b It was a great centre of trade in the northern part of the kingdom of Warangal Marco Polo writes. "When you leave Mabar and go in a northerly direction, you come to the kingdom of Mutfili" He goes on to say that it had been ruled for forty years by a queen, a lady of great discretion, who was a lover of justice, equity and peace." He then describes its diamond mines and states that the most delicate buckrams were wrought there, which look like spiders' webs (Tr Yule and Cordier, II 359 63) The queen was Rudrammā Devi, the grandmother of Rudrapratāpa—the Laddar Deo of Amīr Khusrau and Barani

III 219, l 8 from foot Khusrau made some advances to them

He did no such thing He was greatly afraid of them "בת و عاں !ל. 399, 1 10 "And Khusrau Khān stood in awe of them "See my note on III. 124, 1 19 ante Barani again uses the phrase at 411, 1.9 f. f. ביי של אינ ביי ביי מועט ביי מו

III 221, l 6 [Khusrau] begged that he might be allowed to send unto Bahlawāl and the country of Gujarāt for some of his connections

'Bahlawāl', الموال (Text, 402, 16), looks like a mistranscription of المروال, Nahrwāla, to which Hisāmu-d-dīn is said to have gone with the Amīrs and officers who were placed under him on 218 ante F. says Hisāmu-d-dīn went to Gujarāt and collected his friends and relations who were in Pattan (which is also called Nahrwāla) and its neighbourhood (I. 126, 12) But Barani spells it as الموال 's correctly (218 ante, 396, 121) If is what he wrote, and Hājji Dabīr also has الموال is what he wrote, and Hājji Dabīr also has الموال is what he wrote, and Hājji Dabīr also has الموال المو

III 221, l 22 They might then, after the deed was done, call the maliks and amīrs together and make them accomplices, or kill them on their refusal

The B I. Text reads کردگاں سارند, 403, 1 5. The word occurs again at 409, 1 6, and in both these places, Dowson has read it as کردگاں and rendered it by 'accomplices' See 223 infra But the right reading must be

III. 222, l. 18. Randhol, the maternal uncle (nīyā) of Khusrū.

The penultimate letter is a consonant and not a vowel and the correct pronunciation is Randhaval. The name of Randhaval Puār [Pāramāra] is mentioned in the Rās Mālā. (Ed. 1878, p. 90 note). Vīradhaval and Yashodhaval also occur. (Ibid, 201, 202, 181; Duff, C. I. 176, 179, 183). Rāidhaval arrests attention in Tod, (A. A. R. II. 242). So Jāhariya is the contemptuous form of 'Chāhaḍ,' a name borne by the great Hindu Rājā of Narwar and many other persons also, e.g., one of the ministers of Kumārapāla Chālukya of Gujarāt. (Rās Mālā, Ib. 144). Pratāpadhaval is another combination of the same class. (I. G. XXI. 322).

III. 224, l. 8. 'Ainu-l-mulk Multani ... was entitled 'Alam Khan.

as 'Alim Khān, 'The Learned Khān.' There is this to be said in favour of the reading 'Alim, that 'Ainu-l-Mulk was one of the most erudite men in the country. (See 369, l. 17 infra and my note there). Barani elsewhere states that Maulānā Burhānu-d-dīn, the father of Muḥammad Tughlaq's teacher and Wazir, Qutlugh Khān, was given the title of the, which can be read either as 'Alam Malik or 'Alim Malik, by Ghiyāṣu-d-dīn Tughlaq I. (423, l. 2 f. f.; 424, l. 10; 428, l. 11).

The T. M. states that Maulānā Nizāmu-d-dīn, the brother of Qutlugh Khān, was given, after his father's death, this identical title, which appears as the fie in the Text at p. 111, l. 2, but as the at Ibid, p. 98, l. 8 f. f. The fact that the title title is written by Firishta also, (I. 140, ll. 1, 8, and 141, l. 2 f. f.) may indicate that the first word is hot fie. 'Alamu-l-mulk would be nonsense.

III. 225, l. 9 from foot. But Fakhru-d-din, the hero of Īrān and Tūrān reached Sarsuti.

The son is strangely confounded here with the father. Malik Fakhrud-dīn Jūnā or Jaunā—afterwards Sultan Muḥammad Tughlaq—is spoken of by Barani and rightly as تبت ذادة ايران و نوران; 414, l. 15. "Son of the Tahmtan [an epithet of Rustam, the Achilles of Firdausi's Shāhnāma]

the Qazi of Cairo. (Defrémery, III. 428). He may mean the حرير محترع

Budāuni's assertion that the lady thus illegally married was his also proves that he had several wives and may indicate, if correct, that she was the most honoured one, i.e. the senior wife, the wife first married. Mrs. Hassan Ali assures us that a Muslim's first wife is his most honoured wife (حرم بحترم). "The first wife is always considered the head of his female establishment. Although he may be the husband of many wives in the course of time and some of them prove greater favourites, yet the first wife, the wife by the first marriage, takes precedence in all matters where dignity is to be preserved". (Observations on the Mussalmans of India, I. 340). Now there can be no doubt that Deval Devi was not the Sultan's first wife. F. asserts that Deval Devi was taken into his harem after the murder of Khizr Khan. But even if such was the case, there is not a word, not a particle of anything deserving to be called evidence, for assuming that the particular wife who was married to Khusrau Khān contrary to law and custom was the ill-fated heroine of the 'Ashiga.

III. 232, l. 10. 'Ubaid the poet . . . fanned the strife.

Firishta inserts here one of his guesses or glosses which are more often wrong than right and asserts that this man was the 'famous poet 'Ubaid.' and that he was the 'satirist' (عبيد شاعر مشهور) and 'ribald (lit. impudent) bard of Rākān' (شاعر بيباك داكاني), who had then recently come to Hindustan. (I. 131, l. 17). Ranking observes in a note that in one of his Mss. of Budauni's Muntakhab also, this 'Ubaid is described as 'Ubaidi-Rākāti. These asseverations indicate that F. and perhaps B. also imagined that the 'Ubaid of the text was identical with one of the greatest Persian poets of the 14th century, viz., 'Ubaid-i-Zākāni, as 'Rākāni' or 'Rākāti' is an evident blunder for 'Zākāni'. But any such identification is quite out of the question. Any one who reads Daulatshāh's account of 'Ubaid-i-Zākāni' (Tazkiratu-s Shu'arā, Ed. Browne, 238-294) or the admirable appreciation in Browne's History of Persian Literature, (III. 230-257) must be convinced that the two 'Ubaids are entirely distinct. Barani, B. and F. all concur in stating that this 'Ubaid was put to death in 723-724 H. But we know from Hamdulla Mustaufi's Tārīkh-i-Guzīda (I. 846. Tr. II. 235) that Khwāja Nizāmud-dīn 'Ubaidulla the Zākāni was alive in 730 H. (Browne, loc. cit. 230). We also possess works known to have been composed by 'Ubaid-i-Zākāni in 740 and 750 H. (Ibid, 235), and he seems to have lived up to 772 H. or 1371 A. C. (Ibid). See also Houtsma. E. I. IV. 984. The T. M. says that this (ملازمان و خدمتگاران) Ubaid was one of the attendants and domestic servants" of Shaikh Nizāmu-d-dīn Awlīyā and tells a story of a cruel and dirty practical joke played by him upon a simple-minded Hindu admirer of the Saint. (95, l. 1). Budauni states of this ill-starred poetaster, who paid the penalty of his mischievous activities with his life, that that he was the rival and envious detractor of Amir Khusrau, against whom he vented his spite in

not more, after 18th Rab'ī-l-ākhir, 725 H., as some time must have elapsed between the date of the Saint's demise and Shaikh Ruknu-d-dīn's arrival in Dehli.

But this is not all the evidence available. The British Museum possesses a very old copy of the Tabaqāt-i-Nāṣiri (Add. Ms. 25785), which, Dr. Rieu assures us, contains on folio 316, "a summary account of the successive usurpers of the threne of Dehli from the time of Ghiyāsu-d-dīn Balban to the defeat and death of Khusrau Khān. The interesting fact about this fragment is that the anonymous writer appears to be no less a personage than Malik Fakhru-d-dīn Jūna, afterwards Sultan Muhammad Tughlaq Shāb, for he speaks in the first person of his flight from the degrading yoke of the Hindu's child (&£ e) and of the subsequent defeat of the same by his (the writer's) father, Ghāzi Malik, afterwards G hiyāsu-d-dīn Tughlaq, who is stated in the last line, to have reigned subsequently four years and ten months." (Persian Catalogue, I. 73-74).

It is scarcely necessary to stress the importance of the statement made at the conclusion of this most 'interesting' postscript. As Ghiyāṣu-d-dīn ascended the throne on 1st Sh'abān 720 H., his death must have taken place at some time in Jamādi I. (if not Jamādi II) 725 H., if he reigned, as his son and successor explicitly declares, for 4 years and 10 months. This is just the conclusion to which we are driven by the facts derived from other sources and Rab'ī I must be therefore rejected. The first day of Jamādi I. 725 H. corresponded to 15th April 1325 A. C.

III. 236, l. 8. He was well acquainted with the Būm-i Salīm Nāmal in the B. I. Text, 463, 1.3 f. f., is a short form of 'Abı المعالم الماء الما Muslim Nama 'or 'Qissa-i-Abu Muslim', i.e. the History of Abu Muslin for Bu Muslim! who was the صاحب الدعوته العباسة (q. v. T. N. Text, 34, 1. 14 Rayerty's Tr. 311; E.D. II; 282). Abu Muslim (719-754 A.C.) was "the mai who raised the House of Abbas upon the ruins of the House of Umayya The leading figure of his age, he changed, by his wisdom, zeal and general ship, the whole outlook of Islam." (Muir, Caliphate, 446; see also Nöldeke Sketches from Eastern History, 111; Nicholson, Literary History of the Arabs, 252). The قصه بو مسليم is again mentioned by Barani at 468, 1. 8 see also Hājji Dabīr, (Z. W. 887, l. 4). F. states that Muhammad had the 'Qissa' of Abu Muslim and that of Amīr Ḥamza" on the tip of his tongue' or "at his fingers ends". (I. 133, l. 16). B. informs us that this Qissa was a favourite book of Akbar's and that it was bracketed with the Shah-nama. the Jām'iu-l-Hikāyāt and the Qīssa-i-Amīr Hamza among the Persian classics which were regularly read out to him. (II. 320; Tr. II. 329).

III. 238, l. 11. He [Sultan Muhammad] thought he ought to get ten or five per cent more tribute from the lands of the Doab.

ور دل سلطان افتاد که خراج ولایت میان دواب یکی بده و یکی به پیست میبایدستد ; در دل سلطان افتاد که خراج ولایت میان دواب یکی بده و یکی به پیست میبایدستد 473, 1. 2. "It occurred to the Sultan that the Khirāj (land-tax) of the territory of the Duāb should be raised from one to ten or from one to twenty."

There can be little doubt that such is the meaning of the words as they stand. It the Khirāj had been raised by only five per cent or even by ten or twenty per cent, it would not have broken the backs of the peasantry or given rise to the political turmoil and economic chaos which ensued But it is also extremely unlikely that an augmentation amounting to 2,000 or even to 1,000 per cent should have been contemplated or considered as even remotely feasible by any ruler who had not gone absolutely out of his senses The Bibl Ind Text of Barani is frequently corrupt and it is not at all improbable that this palpably absurd statement may be due to some blunder of transcription F (I 134, l. 16) asserts that the increase was and Hajji Dabir agrees ده سی و ده چهل کرداید) Dabir agrees with him (Z W. 877, l 12) B. states, in one passage, that it was only doubled, ده يست مقرر ساريد (I 228). In another place, he quotes the words used by the author of the Tarīkh-1-Mubarakshāhi, to the effect that the Khiraj was doubled, يكى نده بيست قرار يافت (Text, I 237), which literally mean that it was raised in the ratio of ten to twenty, or just doubled In the circumstances, it is quite possible that what Barani really Wrote was not یکی بده بست but یکی بده و یکی به بست In other words, may have been interpolated by some copyist بكى and the second و and the second و and thought he یکی ده بیت and thought he knew better than the author Mr. W H. Moreland thinks that the phrase used by Barani is rhetorical and not arithmetical and that it has no precise numerical significance at all He takes it as a mere mode of locution which signifies nothing more than that the enhancement was 'huge', 'marvellous', or 'enormous'. (Agrarian System of Moslem India, 48 Note) This looks like cutting the knot and not untying it, but the conclusion may, nevertheless, be sound &

III 241, last line The sixth project ... was the design he formed of capturing the mountain of Karâ-jal

Ibn Batūta says that the mountain of Karāchīl was ten days' journey from Dehli (617 post) and B states that it was also known as Himāchal and situated between Chīn and Hindustān (I 229 = Tr 306) The latter repeats the fable which he had read somewhere that heavy clouds form and rain pours in torrents on these hills at the sound of men's voices or their shouts and the neighing of horses The TA speaks of it as Himājal (102, 1 10). It seems to me that the reference is to the mountains of Garhwāl and Kumāon, "the outer range of tertiary hills, which runs parallel to the foot of the Himalayas, separated from it by valleys or Dūns". It is the Sub-Himalaya of modern geologists The name Qarāchal has been supposed to mean "black mountain", from the Turki 'Qarā' and the Sanskrit 'achal', but such hybrid derivations are suspect and unworthy of credit.

I venture to suggest that it is a corruption either of Kurmāchal, the old Hindu name of the province of Kumāon, derived from the Kurmāvatāra, (Grierson, Ind Ant. XL 1911, p 150), or of Gārgāchal. We are told in the Imperial Gazetteer that Gagar is the name of a range of mountains

in Naini Tāl and Almora districts, U.P., which forms a portion of the outer Himalayan range. It is also known as Gārgāchal, from the legend that the Rishi Gārga once dwelt in it. It presents a line of higher elevation than any range between it and the main ridge of the Central Himalayas (I.G. XII. 121). It is impossible not to be struck by the resemblance between Kurmāchal or 'Gārgāchal,' and 'Qarāchal.' It may be noted that this name Gārgāchal assumes another more perverted form in the 'Kūkā' hills of the Zafarnāma and the Malfūzāt. (E. D. III. 514, 464). I have suggested elsewhere that is a mistranscription of is a mistranscription of is a Karkā [chal] or Gargā [chal], the 're' having been read wrongly as a 'wāv'.

The real objective and purpose of this expedition has been grossly misunderstood by Elphinstone who makes the fanciful statement that Muhammad dreamt of conquering China and "filling his exhausted coffers with the plunder of that rich monarchy." (History, p. 404). Elphinstone has been followed by Mr. Vincent Smith, (O.H. I. 241) and also by Sir W. Haig. (C. H. III. 155). This is all due to an uncritical acceptance of the highly sophisticated and imaginative narrative of F. (I. 135). There is not a word about any intention to invade China or even Tibet in either of the two contemporary authorities-Barani or Ibn Batūta-and the T. M. (Text, 103-4), T. A. (102, 11. 9-13) and B. (I. 229=Tr. I. 307) are also equally silent. All that Muhammad aimed at seems to have been the conquest of Kumaon and Garhwal, which are "bounded on the north by south-western Tibet." (Th. 365). We know that Akbar also tried and failed to subdue these regions and an expedition sent by Shah Jahan under Nijābat Khān in 1645 A. C. met with a fate almost as disastrous as this invasion of Muhammad Tughlag's.

III. 243, l. 4 from foot. Warangal, where cholera (wabā) was prevalent.

'Wabā' means 'any kind of epidemic disease, plague or pestilence,' and not necessarily the specific disease we know now as cholera. Khwāfi Khān uses it for the 'bubonic plague' which broke out in the Dekkan about 1685 A. C. (E. D. VII. 337). Epidemics of cholera in India are described by Correa, Garcia d'Orta and other Portuguese writers in the 16th century and they were probably known also in much earlier periods, but there is nothing to show that the particular visitation mentioned here had any connection with that disease.

III. 245, note. Subjugation of the rānas of the hills; the carrying away of the village chiefs and headmen, Bīrāhas, Mandāhars, Jats, Bhats and Manhis to Dehli.

ومنهان و منداهران و جوان و بهنان و منهان و منداهران و جوان و بهنان و منهان و

32, 33). In the B I Text, the third name is written as 'Jīwān' [Recte, Jatwān], but in the corresponding passage in the T A. (104, 18) and F (I 137, 14 f. f), the reading is رمان 'Chauhān' Bhats is an error for 'Bhattiān' and Manhiān must be meant for the 'Maī' or 'Maīn', who are "a branch of the Bhattis, and live in the Punjab as landholders and highway robbers'' (M U II 24, 116) Malik Firūz Maīn, Kamālu-d-dīn Maīn and Dā'ūd-1-Kamāl Maīn are frequently mentioned in the T M (E D IV 22, 28, 29, 32, 40, 54), along with Khulchain Bhatti and Hansu Bhatti, his son "Jats, Khokhars, Bhattis, Mīnas [Maīns?] and Mandāhars" are mentioned in association with one another as notoriously refractory and turbulent tribes at 109 ante (Text 65, 14 f f) خصافی seems to be used here as a synonym of معتدهان and معتدهان heads, or leaders, [who were bad guides]'

III 245, last line One of the relations of Kanyā Nāyak whom the Sultān had sent to Kambala apostatised from Islām

Dowson says he cannot 'discover the place' and suggests that it may have been identical with Kampīla in the Ganges-Jumna Duāb—It is in reality the Kampīla or Kampīl of 236 and 239 ante, where it is mentioned along with 'Tilang' Kampli lies 8 miles east of Anegundi in Hospet tāluka, Bellāry district It has an ancient history, having been a Chālukya capital in the 11th century and still possesses an old fort Lat. 15°-25'N, Long. 76°-36' E (I G. XIV, 328, XVII, 203)—Constable, 34 C b Kanyā [Krishnā] Nāyak was probably the Rājā of Warangal who had been permitted to succeed to a reduced and dwindled principality after the death of his father Rudra Pratāpa (F. I 138, I 9, see also Duff, C I 292)

III 246, l 19. He halted near the town of Khor on the banks of the Ganges. Khor was an old town, the ruins of which lie about three miles from Shamsābād in Kāimganj tahsīl, Farrukhābād district There was a ford here on the Old Ganges or the Budh Gangā Shamsābād itself is situated in the marshy tract on the right bank of the Ganges, eighteen miles northwest of the modern town of Farrukhābād Lat. 27°-39′ N, Long 79°-28′ E (Th) Ibn Batūta says (619 infra) that the Sultan was encamped on the Ganges, about ten days' journey from Dehli The actual distance is about 170 miles Shamsābād is said to derive its name from Shamsu-d-dīn Itutmish, who founded it after destroying Khor, about 1228 A C (I G XXII, 229).

III. 246, l. 9 from foot 'Annu-l-Mulk held the territory of Oudh and Zafarābād.

Zafarābād lies on the old road to Benares about 4 miles to the south-east of Jaunpur. It was named after Zafarkhān, the third son of Sultan Ghiyāsu-d-dīn Tughlaq I An inscription of that ruler dated in 721 A. H. has been found in the town (Führer, The Sharqi Architecture of Jaunpur 64-66) Zafarābād is supposed by Dr. Vost to stand on the site of an older town called Manaich and Manaich is further identified by him with the Munj said to have been captured by Maḥmūd of Ghazni

(J. R. A.S. 1905, pp. 131-142), but these suppositions are highly problematical. Ibn Batūta also mentions Zafarābād in his account of this rebellion. (Defrémery, III, 342).

III. 247, l. 10 from foot. That of Shahāb Sultāni He had misappropriated about a kror of Tankas from the revenue.

What Barani really says is that this Shihāb was a Jt. (grain-dealer or merchant?) who had taken the Revenue farm or Ijāra of the entire district of Bīdar for a period of three years and undertaken to pay one crore of Tangas annually for the same. As he was unable to realise from the district and pay into the State Exchequer one-third or even one-fourth of the stipulated amount and knew the penalty which he would have to pay for his default—not misappropriation—he rebelled. The man was only a reckless speculator, a former slave of the Sultan, who had no stake in the country, and possessed neither administrative experience nor knowledge of the revenue capabilities of the district. He had taken the Ijāra merely on the off-chance of squeezing a much larger amount from the peasantry and coining power into money.

III. 248, l. 22. And a force came from Ahmedābād.

So in the B. I. Text also, 489, l. 4 f. f., but it must be a copyist's blunder for Aḥmad Ayāz. Cf. Text 491, l. 11, where Aḥmad Ayāz is mentioned in connection with this revolt. The T. A. reads in the corresponding passage (105, l. 3 f. f.) and F. also says that Khwāja-i-Jehān [Aḥmad Ayāz] came up with the army of Dehli (I. 139, l. 12) to the Sultan's assistance. Aḥmadābād in Gujarāt was not in existence at this time. It was founded only in the fifteenth century by Aḥmad Shāh I who came to the throne in 813 A. H.

III. 248, l. 7 from foot. They crossed the Ganges below Bangurmu.

Bangarmau is now in Safipur tahṣil, Unāo district, and lies at the crossing of two old thoroughfares, the road from Qanauj to Faizābād (Ayodhyā) and the road from Dehli to Benares. The town contains the tomb of a saint called 'Alāuddin, which bears an inscription dated in 1302 and another tomb erected by Firūz Shāh Tughlaq in 1374 A. C. (I. G. VI. 380). It is mentioned by Bābur also (B. N. Tr. 601) and marked in Constable, Pl. 28 B b. Thornton says it is 43 miles west of Lucknow and four miles distant from the west bank of the Ganges, which explains why the rebels are stated to have crossed below Bangarmau, not at it.

III. 250, l. 10 from foot. The officers entrusted with the distribution of the loans from the public treasury.

The word used in the text (498, 499) for 'loans' is the vernacular "Sundhār", which occurs also in the $T\bar{a}r\bar{i}kh$ -i- $Fir\bar{u}zsh\bar{a}hi$ of Shams. (92, 11. 3, 11; 93, 11. 4, 14). It is said by Elliot to be synonymous with another Hindi word, "Harauri" (lit. ploughing), which he explains, is "an advance of about two rupees in money and two maunds in corn given to a ploughman when first engaged." (Races, II. 345). Nizāmu-d-dīn

Ahmad and F. have employed in the counterpart passage the now familiar Arabic term 'Taqāvi' (T A 107, l. 13, F. I. 140, l. 15). The total amount lent is said by Barani to have been seventy and odd lakks of tangas, but Shams laises it to two krors (loc. cit Ibid). The discrepancy is glaring and not easy to explain. It has been suggested that the lower figure relates to the advances made during the first two years only and that Shams's 'two krors' include the amounts which may have been disbursed in subsequent years (A S.M I, 50 Note). But the scheme was a failure from the first and no further advances are said to have been made. Another explanation may be that Shams wrote fifty years after Barani and that distance in time had lent more imposing proportions to the aggregate amount in the popular memory or imagination. In the C H I. (III 161), Barani's figure is swelled to 'secenty millions of tangas,' but this must be due to a slip or confusion between 'lak' and 'million'

III 253, l 6 'Azīz Himār, the Nāīb-wazīr of Gujarāt

The sobriquet of this ruffian can be read as - ass, ass, assdriver and , wine-seller. The T A. (108, 1 105), F. I (140, 1. 10) and Hālli Dabīr (Z W 874, 875, 879), give the preference to the last and they are followed in the C H I., (III, 166 note), but the B I. Text of Barani invariably reads of (503, 505) It may be said in favour of 'Himar' that it was formerly borne by a much better-known individual, the last Umayvad Khalif. Marwan II, who was universally so styled In that case, however, the nickname is said to have been given, not by way of derision or contempt, but in admiration of his great powers of physical endurance (Muir, Caliphate, Ch. lviii, p. 429) But Ibn Batuta, who knew 'Azīz personally and had been appointed by the Grand Vazir as one of the members of a Commission to inquire into and submit a report on a violent altercation between 'Azīz and one of his colleagues, repeatedly speaks of him as the "Khummar" or "Seller of Wine" He agrees with Barani in giving him a very bad character and says he was a notorious tyrant and cruel oppressor of the poor (Defremery, III 364, 436-440)

III 254, l. 8 He proceeded to Sultanpur, about fifteen kos from Dehlt This Sultanpur must be the place of that name which is now in Gurgaon district, and lies about twenty-five miles south-west of Dehli Constable, Pl 27, C a

III 254, l. 11 from foot I have no pleasure in these revolts.

these revolts " الرجس متما التماتي بست means "anxiety, uneasiness, care, worry, perturbation" Elsewhere, ما منت حاطر (Text, 520, 1 13) is rendered by Dowson as 'disheartened' (262 infra) and التماتي (Text, 447, 1 14) as 'uneasiness' (232 supra) Barani again uses مشوش as synonymous terms at 439, last line ماتن خاطر occurs in the T N also (Text, 40, 1 11) and Dowson's rendering there is "his mind was much disturbed" (E D II 285)

 in general, but to a certain Chronicle in particular. The book quoted is the Tārīkh-i-Kisravi, a History of the Sasanian and other ancient sovereigns of Persia. The work is mentioned by Barani in his Preface also, along with other well-known classics, e. g. the Tārīkh-i-'Utbi, the Shāhnāma of Firdausi, the Tāju-l-Maāsir, Tabaqāt-i-Nāsiri and others. (p. 14, l. 8). A book with a somewhat similar title, a Tārīkh-i-Khusravi or 'History of the Ancient Kings of Persia,' written by Abul-Hasan Muhammad-i-Sulaiman-al-Ash'ari, is mentioned by Mirkhwand in his list of authorities (Rauzatu-s-Safā, Bombay Lith. I. p. 8, l. 7 f. f.) and also arrests attention in the formidable catalogue of Arabic and Persian chronicles bodily 'conveyed' by Abul Fazl without acknowledgment, from the Rauzat, in the Ain (Tr. II. 35). A Tārikh-i-Akāsira also is quoted more than once by Muhammad 'Awfi in the Javam'iu-l-Hikāvāt. (Nizāmu-d-dīn, J. H. 55, 560, 214). But Barani's Tārīkh-i-Kisravi is neither the Tarikh-i-Khusravi nor the Tarikh-i-Akasira. It is, most probably, the history written by Musā bin Isā Al-kisrawi which is cited by Alberuni more than once in his discussion of the chronological difficulties relating to the history of Ancient Persia. (Sachau's Tr. of the Atharu-l-Baqiya, or Chronology of Ancient Nations, 122 127, 208). III. 256, l. 23. Man Deo, chief of the mountains of Salir and Malir.

This was the Rāṭhor Rājā of Baglāna and Sālher and Mulher were his strongholds. His name is said in the C. H. I. (III. 167) to have been Mān Singh, but this form is, really, even less correct than Barani's 'Mān Deo.' A Sanskrit poetical history of this dynasty which was composed by Rudra Kavi in Shaka 1518—1576 A. C. has been recently published in the Gāikwāḍ's Oriental Series. It appears from this work that the name of the Rājā, who was contemporary with Muḥammad Tughlaq, was neither 'Mān Deo' nor 'Mān Singh', but Nāna Deva. He is said to have secured the fort of Shālāgiri (Sālher) and Mayūragiri (Mulher) and built the town of Jaitrāpuri (Jaitāpur), now a ruined village near Mulher. (Rāshtraudhavansha Mahākāvya, Introd. iii, xvi-xvii; Text, 17-18).

It is pertinent to note that Ḥājji Dabīr has somehow got the name quite right and calls him بانديو. (Z. W. 880, l. 13).

The name Nānya Deva occurs in other places also. It was borne by the founder of the dynasty which ruled at Simrāun in Nepāl from 1097 to 1322 A. C. (I. G. X. 139; XIX. 31-2; Ray, D.H.N. I. 203, 393). III. 257, l. 11. Pisar Thānesāri, the vilest of men, went to Deogīr.

"Pisar" is not a part of the name and means "son". The person denounced was the middle son of Rukn-i-Thānesari, who is mentioned just two lines higher up. Barani says that this Rukn-i-Thānesari had three sons, every one of whom was an unmitigated scoundrel. He holds them up to execration along with the twelve infamous counsellors who formed the camarilla which abetted and encouraged Muḥammad in his diabolical cruelties and ferocious executions. (472, l. 9). 'Rukn' is the short form of Ruknu-d-dīn and F. calls the father Ruknu-d-dīn-i-Thānesari. (I. 141,

1.6 f.f)

III. 257, 1 12 Zin-bandawho was called Majdul-Mulk.

The T. A. (101, l. 8) and F (I 141, l. 6 f f) agree in speaking of this man as Zainu-d-dīn Hājji Dabīr calls him حن كن كان Zain-i-Rinda, (880, l. 19) and in F he is styled 'Zainu-d-dīn-i-Rind', ie Zainu-d-dīn, the debauchee, drunkard, reprobate, rascal or knave. Barani describes him here as من المنافق المناف

III 257, l 9 from foot But At the end of the first stage [they revolted]

Barani does not state where the *émeute* took place, but F (I 142, I 2), locates it at the Darra-1-Mānik-dūn B, copying from the T.M., (111, I 12), calls it the Pass of Mānikganj (I 235, Tr. 313) and Hājji Dabīr has 'Mānikbanj' (Z. W. 158). I suggest that it is the Pass of Mānikpunj in Nāsik district, about forty miles north-west of Daulatābād. It is about six miles south of Nāndgāon and two or three miles from the Kāsarbāri Ghāt or Pass There is a ruined old fort still in the vicinity. (B G XVI (Nāsik District), 456) The old trade routes from Gujarāt and Mālwā enter the Deccan at the Manmād and Kāsarbāri gaps and Mānikpunj lies west of the latter (I G V 134) Nāndgāon is marked in Constable, 31 C a

III. 258, 1 8 from foot. And on New Year's Day all the Musalmans of the place went to wait upon the Sultan

Musalmans who were in Devgir, to the City [Dehli] in the company of [i.e under the military escort of] Nauruz-1-Kargan and the report of the victory at Devgir [the defeat of Mal or Makh or Fath Afghan] was despatched along with him to the City of Dehli "Naurūz-i-Kargan is said by Barani (533, I 14) to have been the son-in-law of Tarmashirin Khān. Naurūz had entered the service of Muhammad Tughlaq and been greatly favoured by him This statement is repeated by F (I. 144, l. 13). Hājji Dabir calls him ورود كركر, Naurūz Karkız (892,12) In the corresponding passage of the T. A (109, last line) and F (I 742, 1 17), it is explicitly said that the Sultan sent most of the inhabitants of Deogir back to Delhi with Amir Nauruz Kargan or Gurgin as they write the second name, taking it to be the name of his father But Law be only the Mongol 'Gurgan', meaning 'son-in-law', and he may have been so called because he stood in that relation to the great Padishah of Turkestan, Tarmashirin Taimūr was called 'Gurgan' for a similar reason (Barthold's Art. on Gurkhan in Houtsma, E I., II 184). But it may be another way of spelling the Mongol name Qarghan See my note on III. 264, 1 11, infra.

III. 258, last line Taght had been a slave of the general, Malik Sultant. كه سدة صعدر ملك سلطايي بود , 515, I. 3 f. f. " A slave of Safdar Malik-1-

Sulfani." Here, 'Safdar' is not a common noun signifying 'general', but is a part of the title of his master. Safdar Malik's name occurs in the list of Muhammad Tughlag's Amirs and he is said to have been Akhurbak-i-Maisara-Master of the Horse of the Left Wing, (Barani, 454, l. 13). Ibn Batuta calls him مندرماك and says his real name was Qiran and the T. M. also tells us that Malik Qiran was given the title of Safdaru-l-mulk at the accession of Muhammad Tughlag. (98, 1.5 f.f.). Ibn Batuta explains that 'safdar' means 'He who marshals (aligne) the soldiers.' (Defreméry, III. 332). The sobriquet 'Sultani' indicates that he had been, like 'Imadu-l-Mulk Sartez-i-Sultani, originally a slave of the Emperor. Ibn Batuta explicitly states that 'Sartez,' the meaning of which he explains as 'sharphead,' was a 'Mamlük' of Muhammad Tughlaq. (Ibid. III. 94; S. Lee's Trans. of 1832, p. 100). F. speaks of him not as 'Safdar Malik' but as 'Safdaru-l-Mulk,' and adds that he had been a slave of Ahmad Ayaz (I. 142, l. 11 f. f.), but this trifling discrepancy proves beyond doubt that 'Safdar' was part of his title. Hājji Dabīr also states that the rebel Taghi was a slave of Safdaru-l-Mulk-al-Sultani. (Z. W. 881, 1. 21). The epithet 'Sultani' was in fact a much coveted title of honour. Another 'Imadu-l-Mulk, whose original name was Bashir, is often called Bashîr-i-Sultani, as he was a personal slave of Sultan Firuz Tughlaq. (347, 372 infra). Still another Amīr entitled Safdar Khān-i-Sultāni is mentioned in the T. M. (Text, 149, l. 15; E. D. IV. 24).

III. 259, l. 7. If I had sent him as a memorial to the King of Eden.

Dowson can scarcely mean the Eden of the Book of Genesis, which has been located in Mesopotamia, Arabia or the Nile Delta. It is not the Garden in which Adam and Eve dwelt in "blissful solitude", but Aden. Marco Polo mentions it and says that the ships which came from the West, as from Hormos, and from Kisa [Kish], and from Aden and all Arabia, laden with horses and other things for sale, used to touch at Kāyal. (Tr. Yule, Ed. Cordier, II. 370). Ibn Batūta speaks of Aden as "the port most frequented by the people of India. Great ships arrive there from Cambay, Tāna, Kaulam, Calicut, Fandarāina et cetera." (Defrémery, II., 177). Aden was one of the most ancient and celebrated ports in the Indian Ocean. "Its position in the Gulf, commanding the entrance of the Red Sea, gave the power holding it control over the whole trade of the East, which passed to Europe by way of Egypt...........Allusions to it in the mediaeval Arab chroniclers are frequent." (Dames, Tr. Barbosa, I. 53, Note).

The Text reads ثرة "Kadah-Bati" (518, 1.2 f.f.), which is a miswriting of "Kadi Paṭṭan", i. e. Kadi near Paṭṭan. Paṭṭan or Pāṭan is the old Nahrwāla or Aṇahilvāḍ. Kaḍi is now the chief town of a district in the Gāikwāḍ's dominions. It is frequently mentioned in connection with military operations in Gujarāt in the reign of Akbar. (E.D.V. 179, 431). The Ţ. A. (110, l. 14) and F. (I. 142, l.2 f. f.) call the place f or f or f in their summaries of Barani.

III 261, l. 8 Taghi . proceeded to Kant-barāhi

'Kant-barabi' is a toponym belonging only to the realm of phantasy It does not exist and will not be found in any map or atlas. Dowson's reading and interpretation is followed in the C H I III, 170 and the place-name is there supposed to represent or misrepresent Khambhāliya in Jampagar, Kathiawad, though there is little or no resemblance, even in sound, between the two names The fact of the matter is that the translation is not correct Barani's words are در کت راهی رفت (519, 1 14). which really mean that Taghi " went to Kant by some road for route] " Barahi is not a part of the place-name at all. It is merely of see, rah road, with the preposition ba prefixed Dowson has, somehow, fallen into an exactly similar error in connection with a place called 'Karcha,' which has been read by him as 'Karchabarah' in E D VII p 62, l. 14 The T A. understands Barani to say that Taghi" went towards Kant, in the province of Kachh, after clossing the waters of the Rann " ارآب رن گدشته محاب کست ار ولات كچه رفت (110, 1 20). F (I. 143, 1 3) takes exactly the same view and copies these words Hājji Dabīr also states that Taghi fled to Kānth. (Z W 883, 1 15) This consensus should settle the matter and both 'Kantbarahı' and 'Khambhalıa' must be rejected. Kant or Kanth may be "Kanth-Kot" in Vagad in the east of Kachh There is an old fort there on the top of an isolated rocky hill. Mularaja the Solanki (or Chalukya) King of Anahilvad is said to have sought refuge there, when pursued by Tailapa about 950 A C Muzaffar I of Gujarat also besieged it in 1410 A. C and it is mentioned by Abu-I-Fazl as one of the two strongest forts of Kachh (Ain. Tr II 250, B G. Vol V, (Cutch), p. 227)

If Kant-barāhi is supposed to be a real toponym, Kothāriā or Kanthāriā, which are both the names of places still existing in Kachh (I G XIV. 405), and Kāthiāwād (I G XVI 2) respectively, would be more plausible emendations or restorations than Khambāliya Kothāria in south-west Kachh is situated about twelve miles south-east of Jakhau (B G V Cutch, 231) Kanthāria is now in Babāriāwād under Junāgadh, and lies about eight miles north of Jāfarābād (B G VIII. 505)

III 264, l. 4 Khankhār and the Rāna of Karnal being taken prisoners, were brought to the court

"Extirpation and eradication of the Sumras" on 524, 1.7.

The history of the Chuḍāsamā Princes of Karnāl, i.e. Girnār or Junāgaḍh, is now fairly well-known from epigraphic sources, the Jaina Chronicles of the Chālukyas of Gujarāt, a Sanskrit poetical history called the Māndalik Kāvya and other local records. The name Khengār occurs five times in the dynastic list of this family and the Khengār, in whose reign Girnār was besieged by Muḥammad Tughlaq, was the fourth of that name and the son of Mahipāla. (See B.G. I. Pt. i. 231; Ibid, VIII. 497; Tārīkh-i-Sorath, Tr. Burgess, 114, 129; Burgess, Antiquities of Cutch and Kāṭhiāwāḍ, in the Arch. Surv. of Western India Reports, II, 164; Duff, C. I. 284). He is mentioned in two inscriptions also in the temples on Mount Girnār as the repairer of the great shrine of Somanāth after its desecration by the army of 'Alāu-d-dīn Khalji. (B.G. I. i, 190; B. G. VIII, (Kāṭhiāwāḍ), 497).

In this connection, it is necessary to state that the author of the T. A. is responsible for the dissemination of another error. He has interpolated by way of gloss, the statement that Khengar was the Raja of Kachh (111, l. 12) and this has been copied from him by F. (I. 143, 14) and from the latter, by many other writers, including Sir Wolseley Haig. (C. H. I. III, 172). The origin of this extraordinary imbroglio appears to be that Khengar happened to be the name of the Raja of Kachh in this author's day. That Khengar took a prominent part in the Gujarat Revolt of 991 H., which Nizāmu-d-dīn assisted in putting down. The fortuitous coincidence of the names seems to have led him to jump to the conclusion that Khengar was the dynastic title of the Rulers of Kachh and that the Khengar of Barani must have been so called because he was the king of that country. The local history of Kachh in the mediaeval age has been put together from the records of the Bhats and Charans and the dynastic list of the Jadejas may be found in the fifth Volume of the Bombay Gazetteer. It appears from this that the Khengar who was king of Kachh in the days of Akbar was the first ruler of the whole province who had borne that name. He does not appear, at least so far as our knowledge extends. to have had any namesake of note among his predecessors. It is not impossible that some outlying districts of Kachh may have been overrun or harried and plundered by the Musalman troopers during Muhammad's stay in Gujarāt or in his march to Sind, but there was nothing bearing even a distant resemblance to a conquest of the country and there is not a tittle of evidence to indicate that the Raja of Kachh appeared before Muhammad to make his submission or acknowledge him as his overlord. The only reliable authority on the Muhammadan side is Barani and it is significant that even the name of Kachh does not occur anywhere in his History. The guesses and glosses of the subsequent compilers and their reiteration by modern European authors should not mislead us.

III. 264, l. 7. This [Gondal] is a place in the direction of Tatta, Sumargan, and Damrila,

stood 'Sūmargān' as the name of a place and has registered it as a place-name in his Geographical Index. (VIII. p. xxxvi). But تَ رَبِي كُلُ اللهِ اللهُ اللهُ اللهِ ال

In the B.I. Text of Barani, what Dowson calls 'Damrīla' is, in this passage, written مريك Marela' (523, 1 11) and so also at 269, 1 11, and 348, l. 5. But it is spelt 'Damrila' on 519, l. 16 The place has not been identified and even Raverty was unable to make up his mind about it. He tells us that the ruins near Shakarpur [or Shah Kapur], about 28 miles east of Thatta, may be those of Damrila (Mihran, 229 Note), but elsewhere in the same monograph, he opines that the petrified city near Lighri Bandar mentioned by Ibn Batūta may stand on the site of Damrīla. (Ibid 323 Note). He postulates that Damrila must have been in close proximity to Thatta, because they are mentioned together by Barani, but this assumption is neither necessary nor warranted and it is quite possible that Thatta and Damrila are named and bracketed together as the southern and northern limits of the kingdom of the Sumras It may be also pointed out that the ruins near Shah Kapur are believed by Elliot, General Haig and Mr Cousens to be those of Muhammad Tur and not of Damrila Elliot's extracts from the Tārīkh-i-Jahānkushā, the name of this place appears on one and the same page as Darbela and Damrila (E D II 398), while the Text has 'Marila' It is not impossible that 'Damrila' may be an error by metathesis of 'Darbela,' a fairly well-known place which lies about ten miles north of Naushahro Constable, Pl. 26, B b

But if the right reading is Marela and Hājji Dabīr also spells it (Z W 885, 1 4), it may be Matelo or Mathelo, a very old town near Ghotki railway station ($q \ v$ my note on Vol I 231) or some other place of the same name in Southern Sindh

III. 264, l. 13 from foot He was there joined by Altūn Bahādur with [reinforcements] sent by the Amīr of Farghan

ورستادة امير ورستادة امير ورستادة امير ورستادة امير ورستادة المير ورستادي المير ورستادي المير (111, 124, 112, 114) and so also F (I 143, 16f f.) The T M. (118, 19) and B explicitly state that Amīr Qarghan (variant Qazghan) was the regent (سيال of the Pādishāh of Khurāsān (I 240, Tr I 320), which indicates that they knew him to be the all-powerful minister of Sultan Qāzān Hājji Dabīr has "Qazghan" (Z W 885, 1 13) It is clear from the histories of the Mongols also that the right reading is Qarghan. According to the Shajrat-al-Atrāk, Sultan Qāzān ascended the throne of Māwarāu-n-Nahr in 733 A H One of his most powerful nobles, Amīr Qarghan rebelled against him and was defeated in the first battle, but was victori-

ous in the second and Sultan Qāzān was slain. Qarghan then raised two puppet-princes successively to the throne and remained the virtual ruler and king-maker until his assassination in 760 II. by Tughlaq Tamūr, his own brother-in-law. (Tr. Miles, 374-377. See also Oliver's paper on the Coins of the Chaghat ii Mongols. J. A. S. B. LX, p. 10). According to Ney Elias and Ross (Tr. Tārīkh-i-Rashīdi, Introd. 49), Sultān Qāzān reigned from 744 to 747 A. II. (1343 to 1346 A. C.). Erskine also states that Qāzān Khān was slain in 747 II. in a revolt headed by Amīr Qazghan. (H. B. H. I. 540).

III. 272, l. 16. It was decided that Tughlik Shāh should proceed to the villages (talwandi) belonging to Rāna Mall.

Elliot says (ante 70 note) that talwandi or talwara is "a common name for a village in many parts of the Upper Punjah." It may be therefore worth while to observe that its original signification in the 14th century is thus stated by Barani himself. I so to a signification in the 14th century is thus stated by Barani himself. I so to a signification in the 14th century is thus stated by Barani himself. I so to a signification in the 14th century is thus stated by Barani himself. I so a signification in the cellicon in the cellicon in the cellicon in the century of the peasants carry with their cattle to those spots in the wilderness where a moderate quantity of water is said to be obtainable. They take up their residence in those carts, with their wives and children, all the year round (lit. for twelve months in the year)". Barani's 'talwandi' would therefore appear to have been very similar to the 'Laager' of the Boers of South Africa, which is defined in Chambers' Twentieth Century Dictionary as "a camp made by a ring of ox-waggons set close together, the spaces beneath being filled up with the baggage of the company".

Should we not read the name of the father of the girl as 'Ranmal Bhatti' instead of 'Rana Mal Bhatti'?

III. 273, l. 20. The author's great grandfather used to say that he had given Firoz Shāh a cup of milk.

The word used in the text is نرجد، which means 'great grand mother'. She is said to have "put a cup of her own milk into the mouth of the infant Firuz". ن جام شير خود در دهان مبارک ساطان نيروز مبدادم. (Text, 39, 1. 6 f. f.). What Shams really says is that his great grand mother had sometimes suckled Firuz, as her own son had been born at about the same time as the Sultan. She had acted as a sort of foster-mother or wet-nurse at times. III. 274, l. 12. The Sultan [Ghiyāṣu-d-dīn Tughlaq] was engaged for four years and a half in travelling about his dominions.

علمان تناق جهاد و نيم سال در ملك جولانكرى نود ; 41, 1.6 f. f. " The Sultan Tughlaq galloped upon [or displayed his skill in riding] the steed of sovereignty for four years and a half", which really means that he ruled the state and wielded the powers of a sovereign during that period. We may be sure that the Sultan was not and could not have been "travelling about his dominion;" all this time and we know that almost the only

occasion on which he is recorded to have left Dehli was in connection with the expedition to Lakhnauti in the last year of his reign. Shams is very fond of this metaphorical expression and it occurs very frequently in his pages در ریر سایه چند شاهی و پادشاهی (182, 1. 1), در مقامات و حت حولانکری عود ند ارحلهٔ سلاطین (242, 1. 2) در مدر عر ت حولانکری عود ند ارحلهٔ سلاطین (242, 1. 2) در مدر عر ت حولانکری عود ند وانیدس است means حولان (255, 1. 7) که در زمین حولانکری عود ند the Ghryāsu-l-Lughāt

III. 277, l. 3 from foot. The first act of Firoz Shāh was to invest Shīr-ābrū-chashm with the duties of 'Imādw-l-Mulk.

"Shīr-ābrū-chashm" is impossible as a collocation and nonsensical as a name. سلطان فيرور اول در روز حلوس إين امر كرد و كمت شيرا برو حشم را كرد و الله الله او يادت سلطان فيرور اول در روز حلوس إين امر كرد و كمت شيرا برو حشم را كرد و الله الله او يادت (48, l. 11) "The first order issued by Sultan Firūz on the day of his accession was this He said 'Bashirā, go and bring together [collect, arrange in proper order, or marshal] the troops' [who had been dispersed and scattered after the death of Muhammad Tughlaq]. On account of this [the assignment of this duty to him], he obtained the office or title of 'Imādu-l-Mulk'

On page 61, l. 7, of the Text, Shams speaks of this man as Malik 'Imādu-l-Mulk Bashīr, on 216, l 11, he is called "Bashīrā, that is, 'Imādu-l-Mulk'' At 285, l 4 f f, it is explicitly stated that Sultan Firūz conferred the office of Commander-in-Chief (Sar-lashkar) upon his slave Bashīrā and gave him the title of 'Imādu-l-Mulk, soon after his accession Dowson himself calls him "'Imādu-l-Mulk Bashīr-i-Sultāni" (347 and 372 infra).

III. 284, l. 7 Accordingly, he [Khwāja-i-Jahān] started from Dehli on a Thursday and on the same day arrived at Ismā'īl, which is twenty-four Kos distant. On the next day, being Friday, after prayers, he proceeded to the Hauz-i-Khās-i-'Alā.

There is something amiss here Khwāja-i-Jahān could not have arrived at a place 24 Kos distant from Dehli on a Thursday and also left Dehli and "proceeded to the Hauz-i-Khās," which was very near Dehli, on a Friday There is no such confusion in the Text, which clearly states that it was Qucāmu-l-Mulk, Khān-i-Jahān who had left Dehli and reached Ism'āil on the Thursday Khwāja-i-Jahān followed him as soon as he knew of his departure, on the ensuing day—Friday—and proceeded to the Hauz-i-Khās outside the city Cf the Tārīkh-i-Mubārakshāhi also which states that when Khān-i-Jahān left Dehli with all his followers on Thursday, the last day of Jamādi II, 752 H, Khwāja-i-Jahān was, of necessity, obliged to follow on the next day (Text, 122, I 9 f.f.)

III. 285, l 16 His turban off, a tālīka (?) on his head

ویک ارسراو مرود آورده وطاقیه برسرخود بهاده, 70, 1 5 f f The right reading is "Tāqia" not "Tālīka" It means a skull-cap, fillet or head-covering which is used by Dervishes and Faqīrs and the humble poor who cannot afford the expense and were not permitted the luxury of a turban.

By the upper classes, it is concealed and worn under the turban. As Khwāja-i-Jahān appeared before the Sultan as a criminal who knew that his life was forfeit, he doffed his turban in token of his abject condition. But as he had entirely shaved off his hair and as it would have been a gross breach of court etiquette to appear bare-headed before His Majesty, he covered it with the skull-cap commonly worn by tonsured recluses and ascetics who have renounced the world.

III. 285, l. 20. He sent his own Chaudol to convey him to the grass-plot, where he promised to meet and converse with him.

The B. I. Text has غورا کاه بود (71, 1. 10) and one of the Mss. reads The real meaning of the word the Khurramgāh is explained by Ibn Batūṭa as "a kind of room constructed of planks hung with cloths". He says Malik Kāfūr used to sleep in a Khurramgāh on the terrace of the Hazār-Sitūn palace and that he was assassinated there shortly after 'Alāu-d-dīn's death. (602 infra). It was in fact a wooden tent or pavilion and the بركاته سراي were, no doubt, the "pieces of cloth", or hangings mentioned by Ibn Batūṭa. Barani also tells us that a 'khurramgāh' was pitched for Kāfūr on the terrace of the Hazār-Sitūn, where he used to hold secret consultations and play 'Koḍis' with his adherents and associates. (374, 1. 2 f.f.). In the counterpart passage, the T. A. (86, 1. 3 f.f.) and F. (I. 124, 1. 5) use the shorter and more modern form خراه Steingass says that خراه is the same as 'a large tent'.

III. 286, last line. The Sultānmarched in great state from Karoda towards the city. After several stages, he arrived at Hānsi.

The text reads (78, l. 10) , Akroda or Agroda. We have only to read the 'dāl' as a 'wāv' to get the real name, I, Agrowah, a very old town which lies about twenty-seven miles north of Hānsi. Thornton says Agrowa lies on the route from Hisār to Sirsā and 12 miles north of the former. He also states that Hānsi is 89 miles and Hisār 104 miles north-west of Dehli. This I, i. e. Agrowa has been mentioned before also by Shams (Text, 70, l. 6), as the place near Dhānsūr, where Khwāja-i-Jahān had alighted before appearing in the presence of Firūz Shāh in

his camp near Ikdár or Fathábád According to the I. G, 'Agrowah, which is now in the Fathábád tahsíl, lies 13 miles north west of Hisár (V. 91) Constable, Pl 25, A e Lat 29°-20′ N, Long 75°-38′ E Dhansûr is Dhánsûr, eight miles north of Hisár It is now a station on the North-Western Railway

Sir Wolseley Haig says "Agroha is now Hissar" (C H I. III 153), but this is hardly correct, as the two towns are entirely distinct and 13 miles distant from each other and are separately shown in Constable's Atlas Agrowa is mentioned also by Barani, who says that Sultan Muhammad Tughlaq went from Sunnam to Agroha and thence to Dehli (245 ante = Text 483, 1 8) Ibn Batūta speaks of it as lying between Sarsūti and Hānsi and calls it (Defrémery, III. 372)

III 287, l 13 The Sultan, in reverence of the Shaikh, promised to abstain from hunting

He gave no such promise or undertaking Indeed, it is common knowledge that hunting continued to be his favourite diversion upto almost the end of his long life and that he remained passionately and almost inordinately fond of it. What he really did on this occasion was to give an evasive reply. Its purport was to beg the Shaikh to kindly pray to Allah that that "He might draw him away from this thing" pray to Allah that that "He might draw him away from this thing" of the Shaikh tookthis polite refusal to repent in great dudgeon and was so aggrieved, that he forthwith left the Sultan's presence and declined to accept a costly robe which was sent to him as a present or souvenir on the ground that it was made of silk

III 290, l. 10 from foot The Sultān and Khudāwand-Zāda used to sit down together in the robe room

سلطان ميرور شاه و حداوند راده هم دو در حامه خانه مي نشستند , 100, last line "Sultān Firūz Shah and Khudāwand-zāda sat down on the same carpet"

As Khudawand-zāda was the daughter of one Sultan and the sister of another, whom Firuz held in the greatest veneration as his patron and honofoston on expention was made in hon forcers and also extend the patron and the present of the property of the property of the property of the property of the parton and the patron a of another, whom rifuz nero in the greatest veneration as his patron and the enjoyed the benefactor, an exception was made in her favour and she enjoyed to benefactor, an exception was privilege of sitting on the same carpet as the Sultan, while her husband had to stand and har con to eit habind han privilege or sitting on the same carpet as the Sultan, while her husband had to stand and her son to sit behind her. It would be easy to cite any number to stand and her son to sit behind her. of attendance the table of attendance the table of attendance the table of attendance the table of attendance to table of table of attendance to table of table o III. 291, 1. 10. of instances illustrative of this rule of etiquette. Denote and number information when Hambarian was a reference in that when Hambarian was a reference in the rule of etiquette. of instances mustrative of this rule of enquette, Januar the Attanemi informs us that when Humayun was a refusee in Persia and paid his informs us that when riumayun was a refugee in rersia and paid his carpet, so that no one could last visit to Tahmasp, the Shah folded up his carpet, so that no one could share a refugee in rersia and paid in the shah folded up his carpet, so that no one could be a refugee in rersia and paid in the shah folded up his carpet, so that no one could be a refugee in rersia and paid in the shah folded up his carpet, so that no one could be a refugee in rersia and paid in the shah folded up his carpet, so that no one could be a refugee in rersia and paid in the shah folded up his carpet, so that no one could be a refugee in rersia and paid in the shah folded up his carpet, so that no one could be a refugee in rersia and paid in the shah folded up his carpet. siase visie to Landasp, the Shan Indiced up his carpet, so that no one could share any portion of it and Humayin would be forced either to stand or significant the hara ground A Marshal named Haiii Mahamad kad the country of the hara ground A Marshal named Haiii Mahamad kad the country of the hara ground A Marshal named Haiii Mahamad kad the country of the hara ground A Marshal named Haiii Mahamad kad the country of the hara ground A Marshal named Haiii Mahamad kad the country of the hara ground A Marshal named Haiii Mahamad kad the country of the hara ground A Marshal named Haiii Mahamad kad the country of the hara ground A Marshal named Haiii Mahamad kad the country of the hara ground A Marshal named kad the country of the hara ground A Marshal named kad the country of the hara ground A Marshal named kad the country of the hara ground A Marshal named kad the country of the hara ground A Marshal named kad the country of the hara ground A Marshal named kad the country of the hara ground A Marshal named kad the country of the hara ground A Marshal named kad the country of the hara ground a kad the country of t snare any portion of it and riumayun would be forced entier to stand or sit on the bare ground. A Mughal named Hājji Muḥammad had the presence on the bare ground. A mughal har tooming of the commental comments of the comme on the pare ground. A magnal named rall munianmad had the presence of his of mind to save the gituation, by tearing of the ornamental cover of his morning of mind to save the gituation, by tearing of the ornamental cover of his morning of the ornamental cover of his of mind to save the gituation, by tearing of the ornamental cover of his of mind to save the gituation, by tearing of the ornamental cover of his of mind to save the gituation, by tearing of the ornamental cover of his of mind to save the gituation, by tearing of the ornamental cover of his ornamental or mind to save the gituation, by tearing on the ornamental cover of ms diver and spreading it out, so as to improvise a seat for His it out, so as to HRH IT one one out. Quiver and spreading it out, so as to improvise a seat for his master.

(Stewart's Tr. Reprint, 106; Erskine, H.B.H., II. 293-294). Colewart's Ir. Reprint, 100; Direktine, H.D.H., Li. 200-204). Really Dadit tells us that when Asaf Khān, one of theigreatest nobles of Bahādur formand tells us that when Asaf Khān, one of theigreatest nobles of the most formand tells us that when Asaf from Maline Coulting Maline Coulti tells us that when Asar Khan, one of theigreatest nobles of Bahadur Shah of Gujarāt, returned from Mekka, Sultān Mahmūd Latīf went forward and ambroard him mhom then art down or Gulardt, returned from Mekka, Sultan Manmud Latit went forward and embraced him. They then sat down on the same carpet and the title of Walfill and embraced him. They then sat down on the same and the title of Walfill and the forthwith appointed Regent with full common and the title of the same forthwith appointed Regent with full common and the title of the same forthwith appointed Regent with full common and the same same carpet. and emuraced mm. They then sat down on the same carpet and Asat Makitan was forthwith appointed Regent with full powers and the title of Vakitan (7 W 200) Another anecdote exemplifying this feature of the Oriental code of Minan waking i-Mutlag. (Z.W. 290).

Another anecdote exemplifying this reature of the Oriental Fahim.

manners is told in the Madsirul Umara, in the Life of Miyan his food

To in good to have remain abroad and an Paga Bilmomerate to his food manners is told in the Maastru-t-U mara, in the Life of Miyan Fanim.

He is said to have roundly abused Sundar, Rajā Bikramajīt, to his face,

Tinda had had the imparator to sit on the name of the head had the imparator to sit on the name of the head had the imparator to sit on the name of the head had the imparator to sit on the name of the head had the imparator to sit on the name of the head had the imparator to sit on the name of the head had the imparator to sit on the name of the head had the imparator to sit on the name of the name o De is said to have roundly abused Dundar, roals Dikramaja, to his lace, because he, a Hindu, had had the impudence to sit on the same leave with Doroh Whom the grander of the grander of Doroh Whom the grander of t with Darah Khan, the grandson of Bairam Khan. (I, 712, I, 6). With Darab Khan, the grandson of Bairam Khan, U, (12, 1. 6). Khudawand111. 291, 1. 9. The Sultan paid his accustomed visit [to] Here again, the author's words are minimised as usual.

They

Here again, the author's words are down on one and the same carpet, hadding, but Gultane and Sulfane a sat down on one and the same carpet, This word with is understood and rendered in the C.H.I., III. 87, as and rendered in the C.H.I., the converse on hadding. and rendered in the U.H.I., III. 87, as bedding, but Sultan's Barani uses the daughters do not sit down to converse on beddings. daughters do not sit down to converse on beddings. Barani uses the "Figured and variegated carpets." بسلطهای منتش و جامه خانهای ماون Phrase ماون

Davan Malik, son of Khudawandzada, but by another husband than the base Khusru Malik, sat behind. Shans does not tell and perhaps did not know the name that Damen (T.F. 32, 1.9). III. 291, 1, 10.

busband, but Barani clears up this mystery.

Malik's father were Cari Colonial Colon nusuanu, uut barani clears up this mystery. He says that Dawar Malik's father was Qazi Sadru-d-din-l-Arif, who was the son of the Malik's father was Qazi Sadru-d-din-l-Arif, who was the outboard and the code of Malik's father was Qazi Sadru-d-dm-1. Arii, who was the son of the author of daughter vision of the Sadr-i-Jahān Minhāj-i-Jūzjāni—the author of the Sadr-i-Jahān him that Sadru-d-din-i-Arif was the Trahmant i-Nāciai daugnter v. or the Sadr-1-Jahan Minhad-1-Juzjani—the author of We learn from him that Sadru-d-din-i-Arif Was the Tabaqat-i-Nasin'i. We learn from him that (947 | 15. 251 | 19). the Yabaqat-i-Naşîrî. We learn from him that Sadru-d-din-1 Arii Was chief Qāzi and Sadri-i-Jahān under Alāu-d-din. which states that make is corresponded to a contain action by the TM which states that enier Van and Saur-r-Jauan under Alau-a-ain. (241, 1. 13; 501, 1. 12), This is corroborated to a certain extent by the T.M., Which states that This is Malik was the title bestowed on Manlana Vient by Milanana. This is corroborated to a certain extent by the T.E., Whiten states that Davar Malik was the title bestowed on Maulana, denoted the problem and that Mahammad's denoted was given to a certain extent by the T.E., which was given to a certain extent by the T.E., which was given to a certain extent by the T.E., which was given to a certain extent by the T.E., which was given to a certain extent by the T.E., which was given to a certain extent by the T.E., which was given to a certain extent by the T.E., which was given to a certain extent by the T.E., which is a consistent of the title bestowed on Maulana at his according to the title bestowed to the title Dawar mank was the title pestowed on maniana Yusur by was given to Tughlad at his accession and that The anithat Maniana coame to support him in marriage (most Q2 1 1A) The anithat Maniana coame to support him in marriage. Tugniaq at his accession and that munianmad's daughter was given to support him in marriage. (Text, 98, 1.14). The epithet Manland seems to support him in marriage. (Text, 98, 1.14). mm in marriage. (Text, 95, 1. 14). The epithet Mandana seems to Sultan's Barani's statement and this Yusuf must have been chosen as the is some parants statement and this Yusuf must have been chosen as the justants some is some son-in-law because he was his sister's son (nephew). confusion in Dowson's translation about the parentage of Dāwar Malik At page 276 ante, he makes Shams say that Dāwar Malik was Khudāwandzāda's son by Khusrau Malik, though there is nothing in the text to warrant the assertion. (Vide Text, 45, 1 11) Its erroneousness is also shown by the categorical denial in the passage under notice and the point is further placed beyond doubt by the statement I have cited from Barani F makes Khusi au Malik the son of Muhammad Tughlaq's sister and states that he was the commander of the Qarāchal expedition and one of those who met their death there (I. 135, 1 14). This is all utterly wrong and flatly belied by the authorities of weight. III 291. 19 from foot Rāi Bhirū Bhatti remained in attendance.

He is said in the Text (103, 1.5 f f) to have been the L. Binā of the Sultān, which has no meaning and must be a perversion of L. mother's brother, maternal uncle Barani says that Muhammad Maulānā was the L. of Sultān Qutbu-d-dīn Mubārak (381, 1 5 = 211 supra) Richardson says L. Nīyā, means grandfather, but the Ghiyāsu-i-Lughāt adds that it is also used for the maternal uncle, who is styled Māmūn in Hindustān. Steingass gives both these senses Elsewhere, Barani speaks of Randhaval as the L. of Khusraū Khān (408, 1 10, 410, 1.12, 222 supra) The real name is most probably not 'Bhīru' but the Punjābi Pheru Cf. Pherushahr, the original and correct name of the place now called Ferozeshāh (Hobson Jobson, 350)

III 293, l 2 Two names were selected to be mentioned after that of Firûz Shāh, viz 1 Muhammad bin Firoz Shāh, 2. 'Alāu d-dīn Sikandar Shāh, and till the end of the reign, these names were mentioned in the prayers

There must be something wrong here How could the name of 'Alāu-d-dīn Sikandar Shāh, who ascended the throne five years after the death of Firūz Shāh have been mentioned, in the *Khutba* upto the end of the reign of Firūz, ie. while he was alive? But Shāms does not really say any such thing His words are

دو تأحدار مرکریده حصرت ودود را خطه سمد از سلطان صرور قرار یافته یکی سلطان محمد می میروز شاه دوم سلطان علا الدین سکندر شاه می الحمله نا غایت ایام خطبا مای خوش کلام خطه سام این تاحداران ... میحواسد .(5 1 ,707)

"The Khutbas of two crowned heads, the chosen of the Almighty, came to be established after [the death of] Sultan Firūz, viz., of (1) Sultan Muhammad bin Firūz Shāh and (2) of Sultan 'Alāu-d-dīu Sikandar Shāh In short, eloquent Khatībs have been reciting the Khutba in the names of these ruleis upto the present time" (lit upto the end of these days, i. e the time of writing).

This passage must have been indited at some time during the short reign of 'Alau-d-dīn Sikandar Shāh between Rab'ī I and Rab'ī II, 795 A.H = January-March, 1894 A C. Thomas also was puzzled by it, because he misunderstood it (C. P. K. D., 306 note), having taken to

mean " End of the reign [of Firuz]" like Dowson.

III. 294, 1. 12. And the Sultan followed by way of Champaran and Rachap.

As Dowson could make nothing of 'Rāchap', he has noted the variae المطان The B. I. Text rends جادن دوج and جادن داوع .. The B. I. Text rends Sultan Firuz bestowed an umbrella ".(111,).13) أبروز شاء واي جالان واجتر داده (conferred the honour of carrying one) upon the Raja of Chaparan." Jiaran in the B. I. Text, is an obvious miswriting of Oder 'Chaparan.' Barani says that when Firux marched through Kharosa and Gorakhpur, the Rajas of those districts did him homage and paid up all the arrears of tribute. In return, the Sult in gave the Raji of Gorakhpur, who was " a very great Rai, an umbrella, (Ft), a diadem and a dress of honour." (587, l. 16). Now, we know that early in the fourteenth century, one of the local chiefs had "founded a kingdom which extended over a considerable area in both Gorakhpür and Champaran." (I.G. XII, 333; Ray, D. II, N. I. 203). The Rājā of Kūrakhur [Recte, Gotzkhpur] is said, in the T. M. also (Text, 124, last line : E. D. IV. S), to have waited upon the Sultan, offered a tribute of twenty lacs of Tangas with two elephants and to have been received into favour. His name is also given as Udi Singh. It seems to me that Barani's Rijā of Gorakhpur must be identical with the 'Rājā of Chapiran' of Shams and there can be little doubt that the B. I. Text gives the clue to the right reading. The Sultan threw up batteries (Kungura) and dug 111. 294, 1. 14.

somewhere near Pandua in the midst of swamps and that there was a river at a distance of seven Kos from it. Westmacott identified it with the village of Ekdala in the Dhanjar pargana of Dinappur district. This place lies about twenty-three miles north of (Hazrat) Pandua in Malda district. forty-two miles north of Lakhnauti or Gaur, and 15 miles west of Ghoraghat on the Malda side of the river Tangan (J. A S B 1874, pp 244, 245) Westmacott's identification has been confirmed and upheld by later research Mr H E. Stapleton recently declared in a paper read before the Royal Asiatic Society of London that " Ekdala occupied an area of about 25 miles in the present Dinappur district. It was enclosed within a broad most which was formed by linking up the Chiramati and Buliya rivers The site of the battle between Shamsu-d-din Ilyas and the Dehli Sultan must have been the plain that stretches to the south of the southern moat for ten or twelve miles, almost to the present boundary of Malda district" (Report in the Times of India, 24th April, 1934) See also I G XIX 392, where the same view is taken

In the C H I (III, 176), Ikdāla is described as "a village situated on islands in the Brahmaputra and protected by the dense jungle which clothed the river's banks," but a glance at the map must show that any reference to the Brahmaputra in the Mālda or Dinājpur district is unthinkable and must be founded on some inadvertence or misapprehension

III. 294, foot note. Barant says.. that the Sultan's march was through Got akhpur, Kharonsa and Tirhūt

Abul Fazl says Kharonsa was a Mahāl in Sarhār Bahrāich, Sūba Awadh, and that the town had a stone fort in his day (Aīn, Tr II 176) There is a village named Khorasa in the Gondā district of the U P It has a branch post-office (vide the Post Office Guide) and lies about five miles distant from the modern town of Gondā

III 296, l 21 Tātār Khān cried, 'O Shams-i-Siyāh (Black Sun), whither art thou flying?'

'Black Sun' is meaningless and can have no application in this context What l'ātār Khān really said was يا شس سياء رو كا ميروى (1 11) "O black-faced Shams u-d dīn], whither art thou wending?"

Black-faced' has, probably, a double meaning It refers primarily to the dusky complexion of the Bengal Sultan who was not fair and ruddy like the Turks It is also employed as a term of reproach or revilement, signifying a coward, dastard or poltroon, whose face had been blackened or disgraced by flight The inhabitants of Bengal are contemptuously called by Barani also, who says in his account of Firūz Shāh's invasion that "heaps and heaps of those black-faced ones were slain"

(عُ £ 1 £ 592, 1 كنه شدگان آن سباه رويان خرمها و تود ها بر آمد

III 297, l 14 For Bengal was a land of swamps

رمين سكاله رمس رحاله است, 119, 1 5 f f. Dowson says in the footnote that three Mss. agree in reading رحاله مرحاله words which have no appropriate

meaning. He has therefore read the word as die. But die is quite correct. It means 'virile or stalwart fighting men, infantry.' It has the same signification as the Persian' Piada', the Hindi Paik, and the English 'Foot'. Shams uses the word more than onco in this sense. For instance, he says that Shamsu-ddin Ilyas attacked Firuz Shih " with a large army and innumerable footsoldiers". بالشكر فراوان و رجاله بي بابان (114, l. 1 f.f.). Elsewhere, he writes, The King. of و شاه بنگاله با نمام رجاله درون جزائر آکداله حصاری شد Bangala entrenched himself in the islands of Ikdala with all his footsoldiers" [4]. It is also said of Zafar Khan that he had "a countless در تبغ او رجاله بنگاله بسیار و .''number of Bengali foot-soldiers in his train " several رجاله (207, 1.1). B. also employs the phrase بشار بود is found also in the T. يادة رجاله is found also in the T. A. (236.1.2 f.f.). رجل means 'a man, a man of intrepidity'. It also signifies the being or standing on foot and Jes is the plural form (Richardson). F. speaks of رجالهٔ اردو (1. 49, 1. 5) اردو لشكر و رجاله (1. 73, 1. 17). راجل Brave warriors" also occurs. (I. 50, 1.2). Hājji Dabīr uses داجل for 'infantry'. (Z. W. 906, 1.18). Turmuz was called المدينة الرجال 'The City of Mon', because it was 'a virgin city' and had never been captured by any enemy. (Miles, Tr. Shajrat-al-Atrak, 147 and 148 Note). Barani repeatedly speaks of the martial spirit and truculence of the Paiks of Bengal who are the color of this passage. (Text, 63, 1. 2 f. f.; 593, 1. 2). They were, in fact, "the landed militia of the province, who combined with the most profound barbarism, and the blindest devotion to the will of their chiefs, a fervency and unquietness of disposition which rendered them an important and formidable class of the population". (Stirling Account of Orissa. 1810, p. 38). What Shams means is that the province was difficult to conquer, because its kings could command an inexhaustible supply of man-power in these Paiks.

III. 298, last line. In that country, there is no other village than the Kharak.

published by the Nagari Pracharini Sabha called Hindi Shabda Sagar says it means 'a cattle-shed or enclosure', but it is also said to be used for 'a field in which cattle can graze', te lands which are not culturable, but good enough for pasture, and that may be the meaning here

III. 300, 1 5. That [the canal] from the Jumna was called Rajiwah and the other [that from the Sutles Alagh-Khani

Raverty proposes the emendations, 'Rajirah' and 'Aghamani' (Mihran. 267), but these names carry no meaning with them The right readings seem to me to be 'Rajabwah' and 'Ulughkhanı' The designations were given. I think, in honour or commemoration of the Sultan's father and his cousin. The former's name was Salar Rajab and the latter had the title of Uluah Khān [not 'Alagh Khān '], before he became Sultan رحبواء ' Rajabwāh ' means "the Wah or Canal of Rajab" Mīr-wah, Khan-wah, Magsuda-wab are well-known canals in Sindh. Sultan Firuz himself has left it on record that when he founded two new gasbas near the village of Maluh or Malcha. he gave one the name of Salarpur and the other that of Tughlappur (Futuhāt, 381 infra) There is a Sālārpur in Alwar and a town called Raiabpur is mentioned in the Zafarnama of Yazdı and the Malfuzat. in connection with the invasion of Timur (492 and 428 infia) There is another Rajabpur in Morādābād district, U.P. also (Post Office Guide)

III 300, 18 The author's father held the office of Shabnavis

Dowson has not explained the meaning of 'Shabnavis' and it is not easy to say what it means or to describe the duties of the office The words in the text are عبدة شد ويسى خواصان داشت which may mean that he "held the post of Night-clerk of the Khawwas", i e of the body of special slaves, servants or courtiers, who had to be in attendance upon the Sultan by turns. As the author's father is said to have been employed in the and to have been one of the درون محل, it is not unlikely that he was the clerk who kept the muster-roll of the Khawwas and registered the attendance of those who were bound to do night-duty Elsewhere also, Shams declares that his father was included among the special attendants of the Court مان حواصان درگاه خدمت ميكرد (138,13ff) This word 'Shabnavis' occurs also in the T.M, where it is said that Khwaja Hāju Shabnavis was made Nāib-i-'Arz-i-Mamālik (Text, 83, 1 5), but this is the only other instance of its use that is known to me

Kasbas of Janid and Dahatrath and the town of Hansi III 301. 7 9 and its dependencies

'Janid' must be an error for 'Jind' or 'Jhind'. Dhatrath hes about ten miles north-east of Jhind Dowson seems to have read شهر هاسی و تعلقه, but the B.I Text has " قصه هاسى و تعلق بور عرف سيدم City of Hansi and Tughlaqpur aleas Sapidam [Safidon]", which seems correct Jind, Dhitrath and Tughlagour are all registered in the Ain as Mahāls in the Sarkār of Hisār Firuza. (Tr IL 294) Tughlaqpur and Aspandi (Safidon) are both mentioned in the Zafarnāma of Yazdi and the Malfūzāt-1-Timūri. Safīdon was seven Los from Kithal and Tughlaqpur six Kos from Safidon. (431,

494 infra). Safidon is about 15 miles north-east of Jhind and shown in Constable, Pl. 25 B c. The name is said to be derived from Sarpadamana, 111. 305, l. 3 from foot. "the Wholesale destruction of serpents" by Janamejaya to avenge the death of his father Parikshit, which is said to have taken place on this

spot. (I. G. XXI. 349).

· Barani mentions Malik Yār Parān among the holy men who lived in III. 303, l.5. The Sarāi of Shaikh Yār Parān. the reign of Ghiyasu-d-din Balban. (112, l. 9). See also Dorn, History of the Afghans. (II. 12). Abul Fazi includes the Tomb of Malik Yan-i-Piran [Friend of the Saints?] among the architectural monuments of the Dehli

III. 303, l. 11 from foot. The fare of a carriage was four silver. Jitals. There is nothing corresponding to the word "silver" in the text (136, of his day. (Ain, Tr. II. 279). 1. 6) and it is an interpolation which is calculated to mislead the reader. The Chital, Jital or Jaitil was a copper [or billon] coin of small value. Its weight is not definitely known. It was either about 144 or 172 grs. in weight and it is a moot point whether 50 Jitals or 64 were equal in value to the Tanga of silver, which weighed about 175 grs. The question is discussed at length by Mr. H. Nelson Wright and Mr. H. R. Neville in Art. 248 of the Numismatic Supplement No. XXXVIII to the J. A. S. B. (1924). He [Zafar Khan] received 30,000 tankas to

افته شستن افته ; 141, 1.4. This curious phrase or custom finds an echo in the Travels of Ibn Batuta who declares that soon after his arrival III. 304, l. 3 from foot. in Dehli, the Vazir Ahmad Ayaz made him a present of two thousand "dinars, saying "This is to enable you to get your clothes Washed". (Lee's Tr. 139; Defrémery, III. 381; Gibb, 206). Elsewhere, he states that whenever a stranger of position pays his respects to the Sultan, the latter gives him "a robe of honour and a sum of money to Wash his head according

to their custom". (Gibb, 200; Defrémery, III. 226). Manueci says of the Mughal princesses "that in addition to their fixed allowances and pensions, they often receive from the King, special presents in cash, under the pretext that it was to buy betel or perfumes or shoes." (Storia, II. 341). He also states that "the Revenues of the City of Surat which are said to have amounted to twelve lacs of Rupees had been given by Shah Jahan to his daughter, Begom Saeb, to meet her expenditure on betel". (Ib. I. 65). Baihaqi Writes that Sultan Mas'ud gave ten thousand dirhams to the Khalif's

ambassador to go to the gar mabeh, i.e. the bath. (Text 456, 1.4 f. f.). There were.....iwo tents for cooking and domestic work. There were also one hundred and eighty standards of various kinds. III, 305, l. 3 from foot.

word 'Maratib' is here rendered by "tents for domestic work", when it occurs again (Text, 225, 1.3; 247, 1.13), it is translated as "titles". (329 and 336 infra). It is clear from other passages in which it is used that both the above explanations are wrong and that it really signifies "drums, trumpets and banners" or other 'emblems of rank or dignity'

For instance Shams writes (275, 1 17)

آن شابهای مراثب دولت را در علمهاهٔ خاص کرد می آوردند اصطب علمهاه تواتر مراثب در محل درون مترصه (4-363,1) حصرت خلیمه چند شاهٔ مراثب خویش نیر ترانز داد (5-271,1)

Ibn Baiuta informs us that when he sailed down the river Indus with 'Alāu-l-Mulk, the governor of Lahri Bandar, two out of the fifteen ships carried the Amīr's Marāth He then explains that they consisted of "banners, kettle-drums, trumpets, clarions and flutes" (Defremery, III 110=Gibb 186) Elsewhere, he states that such Marāth, ie "kettle drums and banners" "kettle drums and banners" were conferred only on the great Amīrs (Defremery, III 106) The drums and trumpets appear to have gone with the banners, the standards of which may have been fixed or attached to the musical instruments. Minhīj states that in Chingiz Khīn's army, there were 800 (or 600) ple, ie banners or standards and one thousand horsemen were enrolled under each banner (T N 338, 12, Raverty's Tr 968). As Sultan Firūz is said to have marched with ninety thousand cavalry under just one hundred and eighty alternated in the firm of these insignia for every troop of one thousand

In the Mughal period, the Māhi-Marātib, the Fish-banner or standard was one of the highest honours. A fish of gilt copper, about four feet in length, was placed horizontally on the point of a spear and borne on an elephant or a camel, along with two gilt balls (Irvine, A. I. M. 31, 33)

III 307, l 14 The Sultan bethought him that they were not near Hisar-Firozah, the neighbourhood of which was in a disturbed state

شاه میرورگمت که مقطع حصار مروره آین حالب بیست که درآن سبت تشویش ِ ملاء ن سیار of Hisar Firuza, است , 148, 1 2. The meaning is that as the fief-holder [مقطع] of Hisar Firuza, te the Amir who held charge of the district on behalf of the Sultan and was responsible for the preservation of law and order in it, was not at his post, it was necessary to depute a specially qualified officer who could cope with the 'accursed' Mongol hosts and prove an efficient Warden of the Marches against their aggressive inroads and predatory violence. In the Tārīkh-1-Mubār akshāhi (Text, 127, 1 5 ff, E D IV 9), Tatār Khān is said to have been appointed Governor of Multan to guard the Ghazni frontier and after his death, Malik Mardan Daulat to have been sent there because there was no other Amir capable of putting down the assaults of these accursed foes. (Ibid Text, 133, 1 9, Tr E D IV 13-4) این حالت [lit this side] is a periphrastic phrase like 'undersigned' The author of the Maasirul-Umara states that after Aurangzeb's death, the prince Muhammad 'Azam Shāh wrote to his son Bīdār Bakht to stay in Mālwa until his own arrival آن جات and اسحاب (III 659, 1 II) که نا رسیدن این حاب یالوه امامت تاید and آن جات and این عدود or عدود and آن حدود and ناید دود ما

person addressed' in the Inshā-i-Harkaran. بانجاني also occurs in a letter of Bābur quoted by F. (I. 192, I. 9).

III. 308, l. 2 from foot. During the night, the "King of the Blacks" mounted the eastern roof and urging his Bengalis to work energetically, they laboured all night and restored the ruined fort.

This is very different from the real meaning. What Shams writes is got in the real meaning. What Shams writes is got in the real meaning. When the shams writes is got in the real meaning. "When the night came to an end and the King of the Wanderers, (or the Planets, i. e. the Sun) mounted the balcony of the East, [when the Sun rose], the people of Bengal rebuilt the bastion of the fort in a single night by [dint of] the most strenuous labour and mutual co-operation".

Dowson seems to have read شاه سیاه but the right reading is شاه سیارگان. The phrase occurs again in Shams' account of the Thatta campaign. The phrase occurs again in Shams' account of the Thatta campaign. مداره و شاه سیارگان بر آسان بر آمد و شاه سیارگان بر آسان بر آمد for the 'planets' in the Qirānu-s-S'adain ('Alīgarh Litho. p. 88, last verse). And Sharafu-d-dīn Yazdi writes: خسرو سیارگان از بحر مغرب و خنا عبود (Z. N. II. 154, l. 14) خسرو سیارگان و ظهور بر افراخت (See also Ibid, 116, l. 7; 122, l. 11). Steingass says سیاره signifies the Sun.

III. 311, 1. 2. Malik Kabūl, otherwise called Torābānd.

This Amīr is mentioned by Barani also in his list of Fīrūz Shāh's principal officials and courtiers. (528, 1.5). The sobriquet is especially mentioned, because there was another Malik Qabūl who was entitled Qurān-Khuān and Amīr-i-Majlis. (Ibid. 527, 1.14; Shams, 454, 1.5 f.f.; T. M. in E. D. IV, 14). Still another Malik Qabūl, who was styled Sar-pardahdar (Head Chamberlain), is said by F. (I. 146, 1. 5 f.f.) and the T. M. (E. D. IV.9) to have been sent with an army to repel a Mughal invasion in 759 H. 'Torābānd' perhaps means 'Binder on of the Tora.' In Hindustāni, 'Tora' signifies 'a cluster, or bouquet of flowers,' and also 'a jewel, pendant or ornament made of gold and silver ribbons and gems, which is tied to the turban.' This Malik Qabūl was perhaps the Lord-in-Waiting whose duty it was to tie the 'tora' on to the Emperor's turban. But he may have been so called, also because he was personally distinguished for the beauty and stylish manner in which he wore the 'tora' himself.

III. 312, l. 8. Sultan Firoz, then to the joy of his friends, went back to his garden.

عضرت فيروز شاه از آن منام بكام دوستان بسوى بوستان خود باز كشت; 162, 1. 3 f. f. As the Sultin was encamped in a hostile country in the midst of swamps and jungles, he could not have had any garden of his own to go to. The fact is that the phrase بسوى بوستان has really no meaning and is inserted merely as a jingle to rhyme with كام دوستان. Shams is very fond of interpolating

stilted phrases and hackneyed rhetorical expressions merely for their cadence or sonorous effect. His style, when he waxes eloquent, is a degenerate imitation of the مستح or "rhymed prose, which is so common in ornate writing in all Muhammadan languages." (Browne, L. H. P. II. 21). It will suffice to quote here two other gems of similarly hombastic writing to exemplify the meaningless exuberance of this Persian Euphemism to exemplify the meaningless exuberance of this Persian Euphemism مشران مملكت چنين داستان چون قانون ماستان در آن بوستان مثل اهل دوستان بار سودند 206, 1 10 And again, عاي صور تكري بانواع بوستان برودق دوستان بگذرند , 374, 1 7 It is needless to say that a literal rendering of بوستان of bathos and absurdity Other specimens of this florid fustian will be found at Text, 49, 79, 114, 123, 182, 358, 390

III. 312, l 5 from foot. At that time, the Rai of Jajnagar, by name Adaya, had deemed it expedient to quit Banarasi.

در آن امام ادسر مام رای حاحمگر ارسب مصلحتی سکوت سارسی ترك داده (4 1 .164) The name of the Raja is given as Adesar or Udesar in the body of the B I Text and the variant is relegated to a footnote. In the corresponding passage of Dowson's translation of the Tarikh-i-Mubarakshahi, Adaya is said to have been taken captive at a place called 'Sikra' or 'Sankra' or 'Satgahra' along with Shakar Khātūn, the daughter of the Rājā of that place, who is there called Rai Sadhan (E D IV 10) At the same time, the name of the Rājā of Banārasi itself is given as 'Pirbahān-dev' or 'Bīrbhāndev' (Ibid 11) Now, we know from contemporary inscriptions that Vīrabhānudeva III was ruling in Orissa from Shaka 1274 to 1300=1352-1378 A. C. This engenders the suspicion that the interjection of the name of 'Adaya' here may be founded on some error. Moreover, the T A, F. and B, who have copied their accounts almost word for word from the T M, say nothing whatever about 'Adaya' and Hajji Dabir states that Shakar Khātun was captured with her nurse, مرصم , the Arabic equivalent of the Persian 412. (Z W. 897, 1, 20) An examination of the now published Text of the Tar Mub (129, 1.5), also shows that he is right 'Adaya' in Dowson's rendering is due to a mistranslation of old " with a nurse"

Fîrozābād and on the domes of the Kūshk-i-Nuzūl. The correct name of the first of these palaces is Kūshk-i-Shikār. Seg

Dowson's own translation on p. 303 supra. The B. I. Text has it right: در مارت کوشك شكار و دور كنبدهاي کوشك نزول و مارت منارة سنگين که در کوشك در مارت در صرت روس سر و دور سیدهای روست برون و سرت سره سین در روست اند داشته اند دا hunting-box situated on what is now called the Ridge. 'Ray' (in 'Shikārray') is an excrescence or intrusive error due to the scribe having misread or misunderstood the words درون and درون which occur after in the

III. 317, 1. 6. After the lapse of two half years every man returned. This is a mistake for 'two years and a half.' جون اشكر بعد از دو نيم سال ناز : 178, l. 5 f. f. See Dowson's own translation, 315 ante, where he tells us that the Sultan "stayed two years and seven months in these territories." (Text, 172, l. 5). See also Ibid. 250, l. 1, where the statement is repeated and the phrase used is J. According to the T.M. also, Firuz marched against Lakhnauti in 760 H. and returned to Dehli in Rajab, 762 H. (Text, 127, 130; E.D. IV. 9-11). See also the T. A. (115-116) and F. (I. 146-7), where the same statement occurs. Barani uses of for 'seven and a half' (305, l. 11) and ياء نيم for 'one and a half'. (310, l. 12). III. 317, l. 14. One day, the Sultan Firoz went hunting and having

separated from his followers, went to a garden where he met a woman etc.

The whole passage has been misunderstood and the real sense obscured. The king who went out to hunt and met a woman in a garden was ot Firuz, but some unnamed ruler of olden times. What Shams says 181, l. 12 f.f.) is that he had read this "anecdote about bygone sovereigns" (حکات للطن يشنن) in the Khairu-l-Majālis, which is a collection of the Discourses or Table-talk of Shaikh Naṣīru-d-dīn Maḥmūd, Chiragh-i-Dehli, made by a disciple named Hamīd. (Houtsma, E. I., I. 862).

The story is, in fact, an ancient folk-tale which is fathered in Firdausi's Shāhnāma on the Sāsānian Emperor Bahrām Gaur. (Ed. Macan, III. 1514; Rogers' Trans., 410). It is told also in Burton's Translation of the Alf Laila (Book of the Thousand Nights and a Night, Vol. V. 87-88, Nights 389-90), where the hero is Naushīrvān-i-'Adil. Still another variant is the Adventure of an unnamed King with a Gardener's Daughter which is related by Jahangir in his Tuzuk. (Text, 251, 1.8 f. f.; Tr. II, 50-2=E.D. VI, 364). In the Shāhnāma version, the drink offered is the milk of a cow; in the Alf Laila, it is the juice of a sugar-cane and in the Tuzuk that of a pomegranate. Two different versions of the same saga arrest attention in the Akhlāq-i-Mulsini of Husain Wāīz Kāshifi, Chap. XV (Justice). In one of them, the king's name is given as Qubad, the father of Naushīrvān, and the drink is cow's milk; in the other, it is Bahrām Gaur and the liquid pomegranate juice. In the anecdote as it is repeated by Shams, it is the juice of a bunch of grapes. III. 318, l. 1. And passing by the valleys of Nakhach nuh garhi, he arrived with his army at Nagarkot.

820

ار دغلی سنت قلمهٔ نکر کوئ رخ آورد - سمت خربیان زمیندار ٔ تأجیح نه گرهی تر آورد 186, 1. 2

This is a somewhat difficult passage, but whatever the precise meaning of Nuhgirthi may be, it is certain that 'Nāchakh i-nuh-garhi' ('Nākhach of the Nine Forts' in the Footnote) is not a toponym at all, and mitst exist only in the country of Nowhere Nāchakh means 'spear'. Shams employs the identical phrase in his narrative of Firuz Shāh's Bengal campaign.

اگاه هدرین میان شاه سگالیان رسید، اجت به گرهی کشیده سوی لشکر حصرت مروز شاه دوید 114, 1. 14. "In the meantime, the King of the Bangalis came up all of a sudden and drawing the Nāchahh-2-Nuhgerihi, rushed towards the army of H. M. Firūz Shāh?".

"Nāchakh", says Richardson, means "axe, halbert, mace", the Farhang i-Jahāngīri states that it is it, an axe carried on or tied to the saddle, and the Ghiyāru-l-Lughāt speaks of it as a 'small lance' بزدُ كُوچك, e. a javelin

is used along with مشير or أبي by Baihaqi, 141, 17, 399, 16 f f, and also by Barani أبي و يره و المجتل (253, 15 f f) and أبير و المجتل به كرهمي (329, 18 f. f). Shams, in fact, has borrowed the phrase المجتل به كرهمي from his favourite poet, Nizāmi, who says in the Sikandur-nāma.

چان رد بر و باچیم ِنه کره ۔ که کالبد سفهٔ شد و هم روه

(Sikandar-Nāma in Khamsa-i-Nizāmi, Bombay Lith 1265 A H p. 31) Capt Clarke translates the couplet thus

"Drove against him the long spear of nine joints in such a way,

"That both his [Palangar's] body and his coat of mail were pierced" (Canto XX, couplet 36, p 213) This word 'Nāchakh' or 'Nājakh' is used on this page in four other couplets also and is rendered either as 'spear' or 'short spear' (Ib pp 211-212) It occurs again in Canto XXX, couplet 67 (Khamsa, p. 51, last verse), and the English equivalent there is "battle-axe" (Trans. 338) "Girih" means 'joint, knot,' but it is also used for the 1/16th part of a tailor's 'gaz' or yard (Ain, Tr. I. 88 note) Nine girihs may thus mean 9/16th of a gaz or yard, approximately, eighteen inches. The sentence must be therefore translated thus "He hurled the battle-axe [or spear] of nine girihs against the warriors (lit fighting-men) [عربان] of the Zamindārs [the Hindu Rājās or Chiefs] of the districts he passed through [on his way to Nagarkot]"

"Nine girths" must refer to the handle or shaft of the spear or battle-axe. If the Nāchakh was a long spear, it might mean that the shaft was made of a strong cane or bamboo of nine joints. If the Nāchakh was a javelin or a battle-axe, it might signify that the handle was about half a tailor's yard in length

III 318, l. 11 from foot. Other infidels have said that Sultan Muhammad Shah bin Tughlik Shah held an umbrella over this same idol

an بود بود إلى عتر بر سر آن بت نهاده بود ; 187, l. 10. Lit. " had placed [not 'held '] an umbrella on the head of the idol." The real meaning seems to be that he was said to have presented as a gift or offering an umbrella which was to be placed over its head. Neither Barani nor any of the later epitomists speaks of Nagarkot having been conquered by Muhammad Tughlaq, though the fact is mentioned in the Qasida written by the contemporary poet Badr-i-chach, who says that the event took place in A. H. 738, when the Sun was in Cancer. (570 post). This would indicate that the great army which was despatched about this time for the conquest of the Qarachal [Kurmāchal or Gargāchal], i. e. the sub-Himālayan range in the districts now known as Kumãon and Garhwal, advanced as far as Nagarkot and compelled the Raja to nominally acknowledge the supremacy of Muhammad and hold the fortress as his vassal. A. II. 738 began on 30th July, 1337 and ended on 19th July, 133S. The event must have taken place about June 1338, as the Sun was then in Cancer. It was during the return journey that disaster overtook the army of invasion. The monsoon rains are very heavy in those regions.

III. 319, l. 13. The Sultan [Firuz] with much dignity placed his hand on the back of the Rāi [of Nagarkot].

It may be worth while to note that in a poetical chronicle of the Katoch Kings, written by or under the patronage of a Raja of Kangra named Manik Chand in V. S. 1619 (1562 A. C.) which is called Dharma Chand Nātaka, there is a reference to the surrender of Kangra fort to Sultan Firuz and the writer explicitly states that the Raja went out to meet the Sultan and the Sultan placed his hand on the Raja's back. The poet says:

'Rupchandar barkar charho Dileswar Surtan Bahut helkar pag paro pith hāth leī Sān'.

'Rupchandar went forth to meet the Sultan, the Lord of Dehli, and bowed very low down to his feet; the king put his hand on his back.' (J. Hutchison and J. P. Vogel's art. on The History of Kangra State in the Journal of the Panjab Historical Society, VIII. (1920), p. 35). This Rupachandra's coins also have been found. (Cunningham, C. M. I. p. 105). Jahängir tells in his Tūzuk another anecdote in connection with Firūz's visit to Nagarkot. It was related to him probably by some one who had taken part in the conquest of the stronghold by his own army in 1030 A. H. (Text, 318, l. 2 f. f.; Tr. II. 184).

III..321, l. 1. When the muster was called, four, ten and eleven fold

of irregulars (Ghair-wajh) appeared.

و جون استقداد موجود کشت حشم غیر وجهی جهارگان دهیازده یافت; 193, l. 2 f. f.

Dowson observes that he has "translated the passage somewhat doubtfully with the light of the context." The real meaning is that the ghairwajhi—the soldiers who were not on the feudal establishment and were paid, not by regular jagirs or lands held on condition of military service but by assignments on the land revenue or in cash,-obtained (as an advance) four dah-yazdah, four one-tenths, that is, four-tenths or 40 per cont

of their annual allowance. For the meaning of dah-yāzdah, see my note on II 76,120 Barani also uses dah-yāzdah for 'one-tenth' (429,121) Dowson has rendered it wrongly as "one in ten or one in eleven" at p 230 ante III. 321, 16 March of Firūz Shāh to Thatta

This invasion is put by the C. H. I (III 180) into 1362-3 A C (763-764 A H) But this is more than doubtful, and there is no authority for it in the Chronieles All that the T M (Text, 130,18, E D IV 11), the T A (1167) and F (I. 147-148) state is that Firūz returned from Lakhnauti in Rajab, 762 A H (May-June, 1361 A C), that he had the Sirhind Canal excavated "some time afterwards," that he marched subsequently against Nagarkot and "after conquering it, he proceeded against Thatta" (T M Text, 131, 11, E D IV p 12) The next event that is recorded is the death of Khān-i-Jahān in 772 A H (131, 1. 12)

Now, Shams explicitly declares that "four whole years passed after the Sultan's return from Lakhnauti, during which he stayed at Dehli and attended to the affairs of his people" (319 ante, Text, 191, 1 2) Firuz, then, could not have left Dehli for Nagarkot before Rajab, 766 H. (March-April, 1365) As that stronghold is said to have held out for six months (319 ante), he could not have reached Thatta before the middle of 767 H (February 1366) The rainy season of that year was passed in Gujarāt The conquest of the town (after the protracted military operations of the second campaign and the arrival of fresh reinforcements from Dehli) could not possibly have taken place before the middle of 768 H. (March 1367 A C) The embassy from Bahram Khan Mazandarani which is said to have arrived when the Sultan was in Gujarat must be therefore put into the latter half of 1366 A C We know from the Bahmani chronicles that Bahrām Khān rebelled about 767-8 H (F I 292-4, Briggs' Tr. II. 319-323) He must have solicited the intervention of the Dehli Sultan only when he knew that the unequal contest between himself and his suzerain must terminate most disastrously for himself, if he was not reinforced by some other first class power

III. 325, l 18 If a lethal weed had been wanted, it could not have been found

What Shams really means is a tooth-pick اگر خسی برای خلال طلبد بیاسد. 209, l 4 f. f "If a thorn (or thistle) was wanted for cleaning the teeth, it would not have been found "خلال " is a toothpick

III. 327, l. 6 The irregulars having received six, ten and eleven (tankas?) from the kindness of the Sultan, in a short time they were all horsed

عیر وحهی را ششگان دهبارده دهانیده طائنه عیر وحهی ارمرحمت ِ سلطان در زمان سوار شدند (220,18).

'The general sense' is certainly not 'obvious' here and it is very insufficiently and imperfectly indicated by this rendering. What Shams means is that the 'Irregulars' obtained advances of six-tenths or three-fifths of their fixed allowances in cash from the Sultan's treasury and

were thus able to purchase new mounts and equip themselves. Cf. my Note on III. p. 321, l. 1, ante.

III. 328, l. 4. The officers of Government should be strictly enjoined to do them no harm, so that something might come to the soldiers.

ينجانب شود ينجانب ثود ينجانب ثود ينجانب ثود ينجانب ثود ينجانب ثود officers] should be peremptorily ordered not to worry them [the Wajhdars. who had received advances in cash from the Treasury] until the people on this side (i.e. the Sultan himself and his army) arrived at Dehli." انتجانب is used here again as a periphrastical expression for the person speaking or writing, for the Sultan himself. Shams uses the phrase again at 236. and خانجهان وزيريست كه در فرمايش اينجانب يك لحظه اهمال بخود راه ندهد : 1. 4 f. f. also on 224, l. 9. See my Note on III. 307, l. 14, ante.

III. 330, l. 10. The people of Thatta made a verse,....saying, 'By the will of God, Sultan Muhammad Tughliq died in pursuit of us and Sultan Firoz Shah has fled before us.'

The ipsissima verba of the vernacular 'bait' are printed thus in the Bibl. Ind. Text. برکت شبخ تهیا - ارك موا ارک تها 231, l. 2 f. f. I venture to read this mutilated and corrupt distich thus: برکت شبخ بتها - یك موا یك بهگا Barkat-i-Shaikh Paṭṭḥā—Ek muā, ek bhagā. "By the blessing of Shaikh Pattha, one [Muhammad Tughlaq] died; one [Firuz Tughlaq] fled."

Shaikh Pattho or Pir Pattho is the patron saint of Thatta. His shrine in the Makli hills near the town has been for centuries a noted place of pilgrimage (Tārīkh-i-Tahīri in E. D. I. 274), and it is so still. The author of the Maasiru-l-Umara writes that "his real name was Ibrāhīm and his 'laqab' Shāh-i-'Ālam. He was the disciple and deputy of Shaikh Bahau-d-din Zakarriya of Multan and his shrine near Thatta is visited every week by the high as well as the low." (B. I. Text, III, 311). According to the local tradition, he was a contemporary of the poet S'adi, (Wood, Journey to the Source of the Oxus, Ed. Yule, p. 5).

III. 330, l. 13 from foot. When the Sultan arrived, he perceived that the inhabitants had destroyed all their spring crop.

دید که تمام خلائق ایشان غلهٔ ربیع کاشته . They had done nothing of the sort 232, l. 8. "He saw that ; يراى زراعت كوشش بيش كماشته غاه زراعت إيشان دلل شده all their people had sown the spring crop and taken great pains with it; the crop (the grain) was just then only half-ripe." (Vide 1.8 f. f. below). because the new grain had not yet, 'because the new grain had not yet arrived at maturity' or "the crop was not yet ripe," as Dowson puts it. J's, according to Steingass, is 'unripe grain, vetches or pulse in the pod,' and the same explanation is given in the Ghiyasu-l-Lughat.

· The fact of the matter is that when Firuz first invaded Thatta from the Dehli side, he arrived late in the season, after the crops had matured and been reaped and garnered by the Sindhi cultivators. His supplies were

1 (

thus cut off and the army suffered from famine. The tables were just turned in this second campaign. As the Sindhis never imagined that he would return, they had toiled hard in his absence in tilling the soil and raising the Rab's crop This time, Firuz took care to arrive early, just when the crop was only half-ripe and had not been reaped The Sindhis fled, descrited their homes and took refuge in the earthen fortifications on the other side of the river The invaders then reaped and gathered what the indigenes had sown and profited by the latters' labours. It was now the turn of the inhabitants of Thatta to feel the pinch of hunger and the garrison had to surrender for want of provisions See 333-4 infia The people of Thatta did not "destroy their crops on the bank of the Sindh", when they heard of the return of the Sultan, as Dowson states, on 1 18 They only deserted their homes, leaving the villages on the bank depopulated, قادای که مر اسر آب سنده بود خراب کرده (232, 1. 6) and fled to the other side of the river If they had 'destroyed,' all their spring crop, Firuz and his army would not have lived in clover as they did and he would have had to retire discomfited, just as before, for lack of food and forage

III. 338, l 7. The Jam and Babinia had a residence appointed for them near the royal palace

But the words in the text are ". 253, l. 12 "Adjoining the Caravanseral of the Queen" The Sarāi was, like the Hauz-i-Rāni, (The Rāni's Tank), a work of public utility erected by the Hindu consort of some former Sultan 'The land of the Sarāi of Malika' is said by Shams (303 ante) to have been one of the eighteen villages and Qasbas which 'were acquired' for the town-planning scheme connected with the foundation of Firūzābād (Text, 134, l 1 f f). But ". also means" palace" and it may have been the private residence of the lady

III 338, l 3 Invention of the Tās-i-Ghariyāl (a clock or bell to tell the time)

Almost every word here is wrong. The Sultan did not 'invent' the Tas, and the Tas-i-Gharyal was neither a clock in the modern sense of that word, nor a 'bell' Bells are taboo in Islam All that Firuz did was to order that the hour of the day should be publicly announced The Tas-1-Ghariyāl was not a 'chiming clock', as Fanshawe states, (D P P 58), but a 'gong', and it is thus described by the Emperor Babur "A body of Ghariyalis is appointed in all the considerable towns of Hindustan They cast a broad brass (plate) thing, perhaps as large as a tray call a Ghariyal, and hang up in a high place Also they have a vessel perforated at the bottom like an hour-cup, and filling in one ghas i (i e. 24 minutes) The ghar iyalis put this into water and wait till it fills. When it fills the first time, they strike the gong once with their mallets, when la second time, twice and so on till the end of the watch" (B. N. Tr 516-7, Persian Trans 203) Abul Fazl also informs us (Ain, Tr Jarrett, III. 15), that the 'Ghariyal' " is a round gong of mixed metal, shaped like a griddle, but thicker . . . and suspended by a cord " He then

gives an elaborate account of the Hindu method of measuring time and of the metallic vessel or 'water-instrument' employed by them for that purpose. There are similar descriptions of the 'Ghariyāl' in the Voyage to East India of Sir Thomas Roe's chaplain, Edward Terry (E. T. I., 317), Fryer, (New Account of East India and Persia, Ed. 1698, p. 138) and other European travellers of the seventeenth and eighteenth centuries.

It will be observed that the word 'Ghariyāl' alone is used by Bābur and Abul Fazl for the Gong or brass plate and not for the vessel of water. Shams speaks of the Gong as the Tās-i-Ghariyāl. The real meaning of this phrase seems to be not the brass plate of the 'Vessel of water' or 'clepsydra', but' the brass plate (Tas) which was (i.e. used as) the Gong (Ghariyāl)'. It may also be noted that according to the Hindustāni dictionaries, the word for the 'instrument' which measures time is Ghari, e.g. Ret-ghari, Sand-glass, Dhūp-ghari, Sun-dial, Pan-ghari or Pāni-ghari, water-glass or clepsydra. According to them, it is the Gong which is called 'Ghariyāl.' The use of this word for a clock or watch is obviously recent.

Shams himself does not say anywhere that Firuz 'invented' the Tās. All that he speaks of is the direction "The placing (fixing, establishment) of the Tās-i-ghariyāl". It is clear from the prosy disquisition in which he sets out the seven merits of the innovation, that the fundamental aim and object was the announcement of the hours of the day and night for the benefit of the prayerful and religious-minded Muslim. Its principal advantage, he states, was the resolution of the doubts of devout Musalmans in regard to the exact time of reciting the five obligatory prayers and other optional or supererogatory devotions and the commencement and termination of the daily fast during Ramazān. According to the local tradition, Firūz Shāh's Ghariyāl was placed in "the Observatory which stands on the highest point of the Ridge", in the building now known as the Pîr-i-Ghaib. (Fanshawe, D. P. P. 58).

III. 338, l. 16. On court days,.....they [the Jām and Bābiniya].....
sat on his [the Sultan's] right hand, in the second
room of mirrors, below the Chief Judge.

below the Chief Justice (or Lord Almoner)". This word أَا اللهِ is again used by the author in the chapter in which he relates how Sultan Firuz "sat in State". After describing how and at what distances on the right of the Imperial throne, the three highest dignitaries, viz., the Prime Minister Khān-i-Jahān, the Amīr Mu'azzam Ahmad Iqbāl and Nizāmu-d-Mulk, the Deputy Vazīr sat, he informs us that on the right side, but behind Khān-i-Jahān, a carpet (إله على) was folded and spread, at the head of which the Qāzi Ṣadr-i-Jahān took his seat and Bābiniya [Recte, Bāmaniyo] sat next to him...... On the left side also, a similar carpet was folded (دونو) and spread, at the head of which Zafar Khān

the son of Zafar Khān sat. (Text, 280, last line). See also 469, II 8-9; 475, II. 4-5, and 514, list line, where theword cannot bear any other meaning The name Bābīniya is written in a bewilderingly large number of ways and he is called Māh in the C II. I (III 180). For the correct form, (Bāmaniyo), see my note on Vol I 226, I 9 from foot.

III 339, l 7. Kurbat Hasan Kângũ was hing in M'abar

Variant قري Qur ba and Qarib mean "relation", "kinsman " and also is also called على قريب Thus حويش "son-in-law", like its Persian synonym على قريب and is said to have been the son of Ayal (or II) Arslan, the of Sultan Mahmud Gharnavi. (Gai dezi, 78, 92, T A 10, 1 6 f. f., F lere to mean "father-in law" (B Tr I.33 حويش here to mean "father-in law") note), but it is loosely used for any relation, especially by marriage (E D. IV 193 Note) Raverty sneaks of this 'Ali 'as 'Ali Qurbat' (T N Tr 89) Baroni uses خوش و قرات for "relations and kindred" (402, 1 5) and for 'near relation', (184, 1 8 and 186, 1.8) Shams says that this relative of Hasan Kangu was not only taken prisoner, but put to death by Bakan This' Bakan 'may be Bukka Rai of Vijayanagar Bukka I was the son of Singhana I, the earliest ruler of the dynasty and was associated with his brother Harihar I (1339-1354 A C) in the establishment of the power of the family. Bukka Rii himself reigned from 1354 to 1379 A.C (Duff, C I, 219, 309). But كن may be a miswriting, by transposition of the consonants, of J Gopanna, the general of Bukka. who is known to have defeated the Sultan of M'abar in 1371 A C

It will be observed that this relative of Hasan Kanga is explicitly said by Shams to have been King of M'abar and the ambassadors are also stated to have come from and returned to M'abar (the Coromandel Coast and Madura) In the C H I (III 181-2), this embassy is stated to have been the second sent by Bahram Khan Mazandarani, the first having arrived when the Sultan was recruiting his forces in Gujarat after the retreat from Thatta But this must be due to some inadvertence or confusion Shams clearly states that the first embassy was despatched by Bahrām Khān, but the second by Qurbat-1-Hasan Kāngū Bahrām Khān was never ruler of Madura and had nothing whatever to do with it. The Sultans of M'abar belonged to an entirely different dynasty Moreover, Bahram Khan is said by the T A (409, 1 13), F (I 293-4) and the author of the Bur han-1-Maaser (Tr King, 27) to have been pardoned, after the failure of his rebellion, by Muhammad Shah Bahmani His life was spared by that Sultan at the intercession of Shaikh Zainu-d-din, but he was banished from the kingdom and died in exile in Gujarat. The fate of Qurbat-1-Hasan Kangu-his capture and execution after the conquest of M'abar by the Hindus under Bakan (Bukka I or Gopanna)-as related by Shams, was so very different that the two individuals could not possibly have been one and the same Briefly, the identification of Bahram Khan, who is variously described as the adopted son (F L 293, 1. 2), or brother's son and son-in-law of Hasan Kangu, with Qurbat-1Hasan Kängu is founded on error.

Who then was this mysterious Qurbat-i-Hasan Kangu? I suggest that he may be Sultan Fakhru-d-din Mubarakshah of M'abar. We possess a large number of the coins of the Sultans of M'abar, dating from 734 or 735 to 779 H. These numismatic records have enabled us to compile a fairly satisfactory dynastic list of these rulers. We know that Fakhru-d-din succeeded in or about 760 H. His earliest coin is dated in that year (Num. Supp. No. XLV to J. A. S. B. 1934, p. 68), his latest in 770 H. and these dates are found successively during these eleven years with the exception of the years 762 and 766 H. (Rodgers in J. A. S. B. LXIV, 1895, 49-50; Hultzsch in J. R. A. S. 1909, p. 681). We also possess an inscription dated 1371 A. C. (773-4 H.) in which it is recorded that Gopanna, the general of Bukka I, inflicted a crushing defeat upon the 'Turushkas' of Madura, (Epig. Ind. VI. 331). We may then fairly conclude that the reference is to some battle in which Fakhru-d-din was routed and perhaps captured and put to death by the Hindu general in 1371 A.C.=774 A.H. This disaster, however, does not appear to have extinguished the dynasty's power. Fakhru-d-din was succeeded by 'Alau-d-din Sikandar Shah, whose earliest known coin was struck in 774 and latest in 779 H. (1377-8 A.C.). That year probably marks the year of the complete eradication of the sway of the Sultans of M'abar. III. 339, l. 12. And made himself notorious for his puerile actions.

Dowson has bowdlerised the passage. و اورا با اماردان انسال قبيح بصريح بصريح; 261, last line. What Shams really charges him with is something much more culpable and flagitious than puerility. It is pederasty, or homo-sexual vice.

III. 339, l. 10 from foot. The ambassadors were sent back with assurances of his forgiveness.

ي گلدسته معذرت بدست شان داد ; 263, l. 6 f. f. 'He gave into their hands the bouquet of an excuse.' He did not "assure them of his forgiveness". He put them off with an excuse, alleging the hardships which his army had recently undergone, as a reason for not complying with their request. He did not reject their appeal rudely but he did not also fail to remind them of their former rebellion and contumacy and declined firmly, but in courtly terms, to come to their assistance.

III. 341, last line. There was a separate jāo-shughūri and deputy jāo-shūghuri and a distinct dīwān for administering the affairs of the slaves.

an Amīr of Qutbu-d-dīn Mubārak (*Ibid*, 379, 1 12) and Malik 'Izzu-d-dīn Ghūri was in the service of Sultān Mu'izzu-d-dīn Kaiqubād (126, 1 11). Minhāj also includes a Malik Nāsiru-d-dīn Mīrān Shāh, son of Muhammad *Chāwūsh-i-Khalji* in his list of the grandees of Iltutmish. (*I. N.* Text, 177, 1 13) The meaning may be that the *Chāwūsh* or officer in charge of the slaves belonged to the Ghūri tribe.

III 342, l 7 Bandagān-i-Māhīli riding on male buffaloes

Cf Text, 327, 16, where the word is spelt did Bāheli Shams explains that they accompanied the Sultān in the chase. Some of them spread the nets for trapping deer, while others rode buffaloes with spears and lances in their hands. When a tiger was roused by the beaters from his lair, the buffaloes were made to interlace their horns so as to form a ring or cordon and the beast was speared and killed by the buffalo-riders

The correct reading appears to be Bahili Mr W Crooke assures us that 'Bāheliya' (Sanskrit, Vyādhi) is "one who pierces, or wounds, a hunter The Baheliyas are a class of hunters and fowlers and are probably relies of some Non-Aryan tribe, which still adheres to the primitive occupation of hunting, bird-trapping and collecting jungle produce" (Tribes and Castes, I 104) The Emperor Jehängir also speaks of the employment of buffalo-riders in the accounts of his tiger hunts us that when the beaters brought news of a tiger in the vicinity of Rahimābād, he gave orders to Irādat Khān and Fidāi Khān to take the buffaloand make a cordon round the forest He himself proceeded at once to the spot, and despatched with a single shot the biggest tiger he had ever killed (375, l 11. Tr II 284) Mr Beveridge reads اهل باتش but it must be wrong Manucci writes thus of Shah Jahan "The order in which the King moves (while out hunting tigers) is as follows front go the buffaloes, sometimes more than one hundred in number, all in a row On each one is mounted a man with his legs guarded by leather and having a broad sword in one hand and holding with the other Behind them comes the King on an elephant" (Storia the reins Tr Irvine, 1 191) Abul Fazl also mentions this mode of hunting tigers "An intrepid experienced hunter gets on the back of a male buffalo and makes it attack the tiger The buffalo will quickly get hold of the tiger with its horns and fling him violently upwards so that he dies" (Ain, Tr I 283) In the Hindustani Dictionary of Duncan Forbes, and the Hindi Shabda Sagar also, 'Baheliya' is said to mean 'hunter' or 'fowler'

III 343, l 8 It was also called the Mahal-r-drkh or the Mahal-r angur or Palace of Grapes

Mughal Emperor's palace in Agra was so called for a similar reason. (Fanshawe, D.P.P. 35; Keene, Guide to Agra, 12). The alternative name is read by Dowson as Mahal-i-Salin-gilin and he renders it conjecturally as "the palace of the clayey quadrangle", but it is scarcely likely that the Imperial residence where the Sultan used "to sit in state" was marked by any such homely feature and the true reading is, probably, Mahl-i-Salin-i-gulin, i. e. the "palace with the quadrangle or courtyard of flowers," i. e. floral designs, or flower-pattern decorations.

III. 343, l. 7 from foot. Malik Nizāmu-l-Mulk, Amīr Husain, Amīr Mīrān, who were deputies of the Wazir sat near the throne.

The verb should be in the singular. Nizāmu-l-Mulk was the title of Amīr Ḥusain-i-Amīr-i-Mīrān. He was also styled Maliku-sh-sharq. (326 ante). He was at one time governor or fief-holder of Gujarāt, but was transferred and appointed Naih-i-Vazīr after the campaign against Thatta. He was married to a sister of Sultan Firuz and is frequently mentioned by Shams. (Test, 280, 282, 419). Ḥājji Dabīr speaks of him as نظام الك نيكنام (898, 1.5). His father Sayyad Amīr-i-Mīrān is said by Shams to have been one of the great officers of the Khairāt-Khāna or Charity Department. (350, 1.8). Dowson himself explicitly states at p. 326 ante, that Amir Husain was the son of Amir-i-Mîrān the Mustaufi. (Shams, Text, 219, last line). See also the T. A. (114, l. 1) and F. (146, l. 1) where the same statement occurs. The title Amīr-i-Mīrān indicates that he was a Sayyad of the Sayyads, a man whose noble descent was undisputed. Jehängir also had a courtier so called who was the great grandson of Shih Ni'amatulla Wali, a renowned Sayyad and spiritual teacher, to whom Shāh Tahmāsp Şafavi had given his favourite sister Jānish Khānum in marriage. This Mir-i-Miran's mother also was a daughter of Shah Ism'ail Khūni, (T. J. 150, l. 3, Tr. I. 305). Sayyads are often called Mirs. III. 350, l. 3. Transport of stone obelisks.

This description of the devices employed to transport the monoliths is not without interest. An old European traveller has given another account which is helpful in understanding what Shams says. He states that "after the first course was laid, a slope of earth was placed against it, up which the stones for the second course were rolled; when they were laid, more earth was added to raise the slope again, in order to roll up the stones for the third course and so on. When completed, the building was surrounded by a mountain of clay which had then to be removed." (Grandpré, Voyage in the Indian Ocean and to Bengal, 1803, I. 169). There are more recent and highly technical Monographs on these old mechanical devices in the Rurki Professional Papers on Indian Engineering, 2nd series, 1878, Vol. III; Selections from the Records of the N. W. P. Government. New Series V.316. (See Ball's Note to Tavernier, I, 153-4). Sir John Marshall remarks that it was "a remarkable featof engineering, considering the indifferent mechanical appliances than

available," but he also observes that this pillar could not have weighed more than 40 tons, a "very insignificant bulk compared with the 700 or 800 ton blocks handled by the Romans at Baalbek or the still heavier ones of the ancient Egyptians" (C H I III 590)

III. 350, l 6. One [of the two obelisks] was in the village of Tobra in the district of Salaura and Khizi ābād

The real name of the village is Topra It lies seven miles southwest of Jagadhrı in Ambala district (Arch Survey of India Reports, XIV 78, V Smith, E H I 157 note, Fanshawe, D P P 222, Fleet, J R. A S 1906, p 407 note) Khigrābād and Sadhaura were both Mahāls in Sarkār Sirhind, Suba Dehli in Akbar's reign (Ain, Tr II. 296) Khizrābād is now in Jagādhri tahsil, Ambālā district, and lies near the debouchement of the Jumna from the hills and the present head of the Dehli Canal, about 15 miles north of Jagadhri town and 20 miles east of Sadhaura Sadhaura is now in the Nārāyangarh tahsil of Ambala district It lies on the route from Buriya to Nahan in Sirmur It is situated near the base of the Sub-Himalaya, close to the left bank of the Markanda, twenty-six miles east of Ambala town (J A S B 1844, p 214 note) Constable 25 B b It may be as well to state that there are two places called Khizrābād in Ambālā district. That in Jagādhri tahsīl is known as Mashrige (Eastern) The other is in Kharar tahsil and distinguished as Maghirbi (Western) The latter is about 7 miles north of Kauriali Railway Station and 7 miles south of Rupar

III 351, l 3 from foot At this time, the author of this book was twelve years of age and a pupil of the respected Mur Khan

This 'respected Mūr Khān' never existed in the flesh and is only a figment of the brain در آن ایام این مو رح خوشه چس خوان مورحان بك نام سر 310, 1 5 f. f "In those days, this writer, who is a picker-up of crumbs [or gleaner] from the tables of renowned historians (muwarrikhān) had reached the age of twelve years"

This personal reference is not without interest. It shows that Shams was born about 756 H as Sultān Firūz returned from Thatta about 768 H. We do not know when he died, but it appears from other references to the ruin and desolation of Dehli consequent upon the invasion of Tīmūr that he lived upto at least 801 A. H.

III 352, l 9 from foot The height of the obelisk was thirty-two gaz, eight gaz was sunk in the pedestal and twenty four gaz was visible

"The Golden Pillar is a single shaft of pale pinkish limestone, 42 feet 7 inches in length, of which the upper portion, 35 feet in length, has received a very high polish, while the remainler is left quite rough. Its upper diameter is 253 inches and its lower diameter 388 inches." (Cunningham, Arch Surv Rep 1862, p 17) Fanshawe says that the height of the Firūzābād Lāt above the platform is 37 feet, the circumference at

the base $9\frac{1}{3}$ feet and at the top $6\frac{1}{2}$ feet. (D. P. P. 224). These modern measurements indicate that the 'gaz' of Shams is the dar'a or cubit of about eighteen inches and a half. (Barthold, Turkestan, 84 note). If 24 gaz=37 feet, the gaz must have measured $\frac{444}{24}$ =18.5 inches.

III. 352, 1. 5 from foot. Many Brahmans and Hindu devotees were invited to read them but no one was able.

The word which is translated as 'Hindu devotees' is — 'Sewrās'. This is the Sanskrit 'Shrīvara' and the general designation of the ascetic order among the different gachchhas or sects of the Jainas. Abul Fazl says that "two Seorās or Jaina asceties had made, from astrological knowledge, a correct prediction" regarding the result of Akbar's invasion of Gujārāt. (Akb. Nām. Text, III. 68; Tr. III, 94). Elsewhere, he observes that "the Seorās are preeminent in all the countries of India for austerities, asceticism and science". (Ibid. I. 53=Tr. I. 147). See also the Dabistān. (Tr. Shea and Troyer, II. 210-216).

III. 353, l. 3. The other obelisk was somewhat smaller than the Mināra-i-Zarrīn.

Cunningham wrote in 1862 that "the second of Asoka's pillars was lying in five pieces near Hindu Rāo's house on the top of the hill to the north-west of Shāhjahānābād. The whole length of this piece was 32\frac{3}{2} feet; upper diameter 29\frac{1}{2} inches, lower diameter 33.44 inches". (Arch. Surv. Rep. 1862, p. 19). Fanshawe states that it was broken by an explosion in the eighteenth century. (D. P. P. 57). The broken pieces have since been joined together and the completed pillar stands again on the Ridge, where it had been placed by Firuz. Both monoliths contain the Pillar Edicts of Asoka and there is also an inscription of the Chauhān Visaldeva dated 116\frac{1}{2} A. C. on the Khizrābād Lāt. (Ibid. 224; E.H. I. 157 note).

III. 354, l. 15. Bands: Fath Khān, Mālja, into which he threw a body of fresh water, Mahpālpur, Shukr Khān etc.

Mālja or Mulcha was near the grove or Gardens of Tāl Katora, 8 miles from Shāhjahānābād. It seems to have been in the vicinity also of the Kālkā Mandir, an ancient place of worship, which is about 7 miles south of the city near the Khiẓrābād grove and between the shrines of Nizāmu-d-dīn Awliā and Naṣīru-d-dīn Chirāgh-i-Dihli. (Cooper, Guide to Dehli, 1863, p. 92). Shaikh Rizqallah Mushtāqi, who lived in the 16th century, speaks of Mūlcha as a village near Dehli, where parties of pleasure were held and nobles used to go for Shikār. (E. D. IV. 544).

The village of Mahpālpur still survives. "Some three miles to the west of Old Dehli", writes Hearn, "in Malikpur, now within the limits of Mahipālpur, is the tomb of the son of Altamsh who died in Bengal in A.D. 1229. The term Sultān-i-Ghāri given to the tomb by the common people means 'the Cave King'............Close by are the tombs of Ruknu-d-dīn Firūz and of Mu'izzu-d-dīn Bahrām Shāh, sons and successors of Altamsh. Firūz Shāh records the repairing of these tombs, the domes of the two

latter having fallen" (Seven Cities of Dehli, 101-2) Mahipalpur and Mahikpur are both shown in the map prefixed to Thomas's Chronicles. Fath Khan and Shukr Khan were two sons of Firaz Shah and these Bands must have been named after them

III 354, l 11 from foot. These one hundred and twenty buildings were full of guests on all the three hundred and sirty days of the year

The real point seems to have been missed in the translation ماوران جون الدن مكان ايد در هر حالكاء كسان سه رور مهمان شوند در صد و ماوران جون الدن مكان ايد در هر حالكاء كسان سه رور سهان شوند در صد و الله With this view [or object] that when a traveller came to one of these houses, he could stay as a guest for three days, so that they [the homeless poor from foreign parts] could remain as free lodgers (lit guests) in the 120 Serais for all the three hundred and sixty days of the year"

As every traveller was allowed to stay free of charge in any one of these Sciāis for three days at a time in one year, the good Sultan erected exactly 120 Sciāis with the deliber ate object of providing free accommodation for a poor stranger all the year round during each period of twelve months or 360 days

III 354, l 5 from foot Abdul Hakk, otherwise Jähir Sundhär, was the deputy [of the chief in chitect] and held the golden ase

The words in the text also are \$\int_{\int}\chi_{\int}\

III 356, l 6 Some of them were in receipt of a regular payment (rāyati), others had no fixed income

The text has (10) (387, 110), which is decidedly preferable visually, says Richardson, means "salary, stipend, pay" and "any one's lot or provision of the necessaries of life". The meaning seems to be that fixed or definite amounts were allotted in the annual budget for those Kārkhānas, the requirements of which were not hable to variation from year to year.

din

ŢŖ

[Besides] the monthly salaries of the accountants and other officers which amounted to 1,60,000 tankas. عرب دیگر عرب می است. می است می است و اصحاب دیگر عرب دیگر عرب دیگر عرب دیگر عرب دیگر عرب دیگر در اشده و اصحاب دیگر 333 all the copyists write and which makes no sense and that and, an accountant, is the correct reading. But all garmy and followers" occurs frequently in Gardezi's Zainu-l-Akhbār, (20, 1. 4 f.f.; 79, 1.4 f.f.; 104, 1. 7 f. f.) and also in Baihaqi (30, 55, 70, 140, 489) and Barani (55, 1. 11). Richardson and Steingass say that the means "men of inferior rank, followers, attendants", and the term is used and explained lucidly by Ibn Batūta. He informs us that when he was appointed Guardian of the Tomb of Sultan Qutbu-d-din Mubarak by Muhammad Tughlaq, he

appointed Muezzins, Imams, Readers of the Quran and other superior officials who were called Al-Arbāb, or 'Gentlemen' in India. He also made arrangements for the subordinate class of attendants, e. g. footmen, cooks, runners, etc., who were called Al-Hāshīya, i.e. menials [domestiques]. (Defrémery, III. 433, 1. 2). The phrase کارداران occurs in the T. N. also (114, l. 2) and عاشية و لشكرش in the Siyāsatnāma, Bombay Lith. Pt. I, 49, 1.9.

III. 357, l. 12. The camel establishment was.....in the district of Dublāhan is Dubaldhan. Beri-Dubaldhan was a Maḥāl in Sarkār Dehli, Sūba Dehli. (Āīn, Tr. II, 286). Beri is now in Rohtak district. Constable, Pl. 27 Ca. Rohtak town lies about 42 miles north-west of Dehli on the road from Dehli to Hānsi (Th.). Beri is 15 miles south of Rohtak on the direct road from Dehli to Bhiwāni (I. G. VIII. 4), and Dubaldhan or Dobaldhan is five miles south-west of Beri. The camels were sent out to graze there, so as to be within easy call in an emergency. And a quarter jital called bikh was [ordered to be بند خواند (344, 1.5 f.f.). This word 'Bikh' or 'Bika' has puzzled the Numismatists. Adhā is plain sailing, but it is more difficult to say what 'Bikh' stands for. Thomas's solution or surmise seems to be badly off the mark. He thought it was 'Bhikh' is 'alms, obolos'.

(Chronicles, 281). But this is evidently strained and far-fetched and has convinced nobody. I venture to suggest that the right reading is not Bikh or Bhīkh but & Paika, from Pā, Pāi, Sans. Pāda, Pāduka, a fourth, a quarter. This Paika was the quarter-jītal, as the 'Adha' was its moiety III. 358, l. 12. When the Sultan ordered the coinage of the Shashgani, or six jītal-piece, Kajar Shāh was Director of the Dowson's version of the passage is liable to convey an erroneous impression to the unwary reader. It implies and may be not unreasonably understood to mean that these Shashgānis were ordered to be struck

only or for the first time by Firūz Shāh. A glance at the original is sufficient to show that there is no warrant for any such inference or implication. All that Shams says is در حاوس سلطان مرور شاه دارالصر به مهر (344, last line) "At the time of the accession of Firūz Shāh, Kajar Shāh was the Superintendent of the Department in which Shashgānis were stamped", [lit of the Shashgāni Mint] It will be seen that the author does not say anything about Firūz having ordered the coinage of Shashgānis. As a matter of fact, these fractional pieces must have been struck by Muhammad Tughlaq, as their relative value is explicitly stated by Shihābu-d dīn Dimishqi in his account of the Coinage of that Sultān (582 infra) "Shashgānis" and "Dūgānis" are also mentioned by Barani in his account of the "Forced Currency" of that tyrant (476, 17=240 ante) In the next line also, Dowson speaks of the Shashgāni as the "new coin," but there is nothing corresponding to "new" in the text Mr. Nelson Wright seems to have been misled by Dowson's translation (C M. S D 220) It was not "introduced as a novelty" by Firūz

III 359, l 5 from foot. He [Kajar Shāh] accordingly made a full and to ue report to the Sultān

"The full and true report" of the Superintendent was not made to the Sultan, but to the all-powerful Prime Minister, or the real state of affairs was revealed, not to the Emperor, but to his astute and wily Vazīr The context shows that the well-meaning but weak-witted Firūz was hoodwinked and deceived, just as much as the public, by a collusive and preairanged plot between the Minister and the mint-master of collusive and preairanged plot between the Minister and the mint-master [Gujar Sāh?] found on inquiry that the allegation was correct, he made a clean breast of the matter to the Vazīr The two men put their heads together and cunningly devised a fraudulent scheme to withhold the real facts from the Sultan As a public exposure would have discredited Khān-i-Jahān and his administration, the Minister countenanced and abetted a fraud to save the reputation of the Dār ogha and uphold the prestige of his own government

The name of the Dārogha is written Kajar Shāh in the C.H I also (III 185-6), but the correct form is, probably, Gujar Sāh This Sāh is not the Persian 'Shāh', but the vernacular 'Sāh', a respectable merchant of great integrity Barani speaks of ملتابال و سامال (120, ll 8, 11) See my note on II 308, l 6 f f. 'Shā' is still used in this sense in Gujarāt

III. 362, l 12 The Sultān showed great respect to Shaikhu-l-Islām 'Alāu-d-dīn and Shaikhu-l-Islām Farīdu-d-dīn Ajodhani

Neither of these two saintly personages was really alive at this time, ie during the reign or after the accession of Firūz They had both been by that time gathered to their fathers Shaikh Farīdu-d-dīn-i-Shakarganj of Ajodhan was born in or about 584 H and died on the 5th of Muharram 664 or 665 H. (Beale, Miftāli, p. 63, Aīn, Tr III. 364 and note) Shaikh

'Alāu-d-dīn was his grandson and lived in the reign of 'Alāu-d-dīn Khalji. He is the subject of a panegyrical Qaṣāda in the Bāqiya Naqiya of Amīr Khusrau, which was composed between 701 and 715 A. H. (535 infra), and he is also mentioned in Barani's catalogue of the great men of that age. (Text, 347, l. 4). His son, Shaikh Mu'izzu-d-dīn was appointed Nāib-i-Wazīr of Gujarāt by Muḥammad Tughlaq (Ibid. 508, l. 4 f.f.) and was put to death by the rebel Taghi. (Ibid. 588, l. 7). Shaikh 'Alāu-d-dīn himself had died before and Muḥammad Tughlaq erected a tomb over his remains. (Āīn, Tr. III. 372). The Mausoleums of Shaikhs Farīd and 'Alāu-d-dīn at Ajodhan are described in the J. A. S. B. 1836, pp. 637, 638. The real meaning is that Firūz had become the Murīd, i.e. spiritual disciple of Shaikh 'Alāu-d-dīn Ajodhani at some time in his youth.

تالمان فيروز شاه ارادت بر شيخ علا الدين نبيسه شيخ فريد الدين داشت ; 371, 1. 7. The word الدان is used in this sense elsewhere also. Shams says of Ahmad Ayāz, Khwāja-i-Jahān, the minister of Muḥammad Tughlaq, that he was the murīd [lit. had the irādat] of Shaikh Nizāmu-d-dīn Awliyā. خواجه جبان ارادت بندكي شيخ الاسلام شيخ نظام الدين داشت that when Sultān Firūz visited Ajodhan soon after his accession, he bestowed Khil'ats and In'ām lands on the grandsons of Shaikh 'Alāu-d-dīn of Ajodhan, as that noble family was then in an extremely impoverished condition at the time. (543, 1.13).

III. 363, l. 4 from foot. The Rozi was an impost upon traders.

The Editors of the Bibl. Ind. Text give preference to the reading and relegate دورى which occurs in only one manuscript to the footnote as a variant. (375, last line). Dowson has rejected eccause he did not understand it and adopted دوزى because he fancied it was and he has given it the meaning of "one day's labour". But the derivation and the meaning are both untenable conjectures and he has overlooked or misunderstood the very different explanation which is given by Shams himself. Shams says that the old bricks of the seven fortifications of Dehli had become duri [دوری کشته] and that the officials used to insist upon every beast of burden taking one load of the broken bricks (or dūri) from Old Dehli to Firūzābād for making mortar [مبود] out of them .376) بك دفعهٔ خشت دورى در ستوران بار كرده در شهر فنروز آباد براى كهور ميرسانيدند 1. 8). I cannot find that the word (roz) occurs anywhere in this passage, as it is printed in the B. I. edition. The phrase used there is 'took by force' بزور میکرفتند took by force) یك روز not یك دفعه and not دوری has no meaning, either وری has no meaning, either in Persian or Hindi, and I venture to suggest that the right reading is neither but Rūri دورى nor دورى but Rūri دورى . Rora in Hindi and Gujarāti means broken bricks or stones, rubble or 'Kunkur', from the Sanskrit rudh, hard, rough. Raverty connects the name of the town of Rohri (near Bhakkar) with the Hindi Rurh or Rora, "rough, stiff, rugged, hard and also stone, rock or fragment of either". (Mihran, 210 note). Rohri does "stand on a rocky

only." (تنگه پنجاه گاني). The standard silver tanga of the Dehli Sultans weighed about 175 grs. and appears to have been reckoned as equal in value to sixty-four jitals. But Muhammad Tughlaq is known to have struck a silver tanga weighing only about 140 grs., which was known as the ينكه ينجاه كاني, 'the (silver) tanga of fifty jītals'. Shams informs us that the assessment of the lowest grade was ten tangas, i.e. ten standard tangas of sixty-four jitals each. But as the Brahmans pleaded poverty and inability to bear the burden, the Sultan compassionately allowed them all to be placed in the third or lowest grade and, as a further concession, he did not demand from them ten tangas of the higher value or denomination, each of which had an exchange value of 64 jītals, but ten lighter pieces of the lower denomination, valued at only 50 jitals In other words, each Brahman would have had to pay only 500 jītals or only 1400 grains' weight of silver, whereas a layman or Non-Brahman of the lowest grade could not get off for less than 640 jitals or 1750 grains' weight of silver. Mr. Vincent Smith states that they were "assessed at a reduced all-round rate," which is right, but when he asserts that the rate was "ten tangas and fifty jaitals" (O. H. I. 251), he is merely copying Dowson and reiterating his error, which seems to ينجاه كاني and ده تنكه and و ينجاه كاني and و ينجاه كاني by the copyist.

III. 367, l. 5 from foot. When Sultān Muhammad sent the Rāi of Telingāna to Dehli, the Rāi died upon the road.

As the fate of Rudra Pratūpa, the last independent Rājā of Warangal, is not mentioned by Barani or any of the epitomists, this incidental reference to it in a contemporaneous author is both valuable and interest-It is confirmed, besides, by a Telugu historical writing entitled "Pratapa Rudra Charitam," in which it is recorded that this king's death took place at Mantenna on the Godavary, But Dr. K. S. Ayyangar who has unearthed this fact puts the event into 1328 A. C. (S. I. M. I. 180, 202), which seems to be chronologically open to exception. Pratapa Rudra was taken prisoner and sent to Dehli with his relations and dependents after the second invasion of Warangal by the Prince Ulugh Khān in the reign of Sultan Ghiyāsu-d-dīn Tughlaq. Barani explicitly says so and adds that Malik Bidar and Khwaja Hajji led the escort and were the custodians of the prisoners. (Text, 450, 1, 2 and 233 ante). Warangal was thus annexed to and incorporated in the Sultanate of Dehli. some time before the accession of Muhammad Tughlaq and there is no reference to Pratapa Rudra in the annals of Muhammad's reign, because the Rājā had died, as Shams states, on his way to Dehli in or about 1823 A. C. It is true that Shams speaks of "Sultan Muhammad having sent the Rai to Dehli", but it is customary with him to style the heir-apparent Sultan by anticipation and he has followed the same course in regard also to his successor, whom he calls Sultan Firuz repeatedly, even when recording the events of his childhood and youth. Mantenna is Manthani, now in

Karīmnagar district, Haidarābād State Lat 18°-39' N, Long 79°-40' E (IG. XVII. 203). I. G. Atlas, 49 C 2, Constable, 32 A b

III. 369, l 3 The Sultan was often heard to say that Khan Jahan was the grand and magnificent King of Dehli

mean 'grand and magnificent' He is styled 'Azam Humayun at Text, 291, 1 14, 292, 1.1 "'Azam Humāyūn " was one of the titles, الناك, of Khān-1-Jahān. Hājji Dabīr and Barani both say so (Z W 896. 1 22: T. F. Text. 578, l. 18, 596, ll 4 and 8) It appears from other passages in Shams's chronicle that Khwaja-1-Jahan and Malik Kabir, the ministers of Muhammad Tughlaq, had both borne this title (63, 1.18, 454, 1.3) Buhlul Lody bestowed it upon his grandson, and during the reigns of Sikandar and Ibrāhīm it was conferred upon the most powerful nobles. "In Hindustan," Babur writes, "they give permanent titles to highly favoured Amirs, one such being 'Azam Humāyūn, one Khān-i-Jahān, another Khan-i-Khanan Fath Khan's father's title was 'Azam Humayun, but I set this aside, because, on account of Humayun, it was not seemly for any person to bear it and I gave Fath Khan Sarwani the title of Khān-1-Jahān" (B. N Tr 537) The title was revived by the Sūri Sultans but again discontinued by Akbar.

III. 369, l. 17 One of them is the 'Ainu-l-Mulki, a popular and approved work

یکی از آن ترسل عن البلکی ست که در حهان نهر یک زنان معروف و مشهورست 408, 1 10. "One of them is the Tarassul-i-Anu-l-Mulki, which is wellknown and famous throughout the world" A copy of this treatise, which is also called Inshā-i-Māhrū, was in the library of Tīpū Sultān and it is now in the collection of the Asiatic Society of Bengal. Dr W. Ivanow was the first to draw public attention to it and his Note on the subject in the J. R. A. S 1922, pp 579-580, was followed up by a much fuller description and resumé of its contents by Maulavi 'Abdul Wali, in an article in the J. A S B 1923, pp 253-290. It is really an olso of Epistles written by Māhrū to several eminent persons and private individuals, 'Arzdashts, ne Petitions or Memorials addressed by himself or others to the Court and Manshurs, Misals and Nishans, i e various kinds of Orders, Letters Patent and official documents drafted by 'Ainu-l-Mulk in the name of the Sultan or the Government It appears to have been extensively read at one time and to have been looked upon as providing models or masterpieces of epistolary diction (loc cit 271, 253) One of the most interesting documents incorporated verbatim in the collection is the Proclamation issued by Sultan Firuz in 1353 A. C., justifying the first invasion of Bengal on the ground of the tyranny and injustice of Hājji Ilyās All classes of men are then invited to desert the usurper and promised rich rewards if they join and co-operate loyally with Sultan Firuz

III. 370, 1 7. The Sultan . . told 'Arnu-l-mulk that he would himse If

receive his reports and that his books would be sufficient.

طنبه على انتد مسروع باشد - كنبه شها كانست does not mean 'books' but 'signature, endorsement, initials, or other token or mark of assent or sanction in writing'. According to the Ghiyāṣu-l-Lughāt, it means 'written' and also 'writes'. When a person signs a document, he writes this word أحنبه first and then puts down his name.

III. 371, 1. 5. 'Ainu-l-Mulk replied, that he hoped that all misgiving would be removed from the mind of the minister; he had spoken warmly for him notwithstanding their old feud.

The real import of the reply is turned upside down in the translation. What 'Ainu-l-Mulk really said was: "Thou shouldst dispel from thy mind the notion that I have given this favourable opinion for thy sake [i. c. out of any regard for thee]. The strife and enmity between me and thee remains just as it was. I have said this only for the good of the Sultan's kingdom." المن عن المن المن المن عن المن عن

III. 371, l. 13. He died in the year 770 H. 1368 A. D. in the eighteenth year of the reign of Firoz Shāh.

Here the date of Khān-i-Jahān's death is given as 770 H., but at page 358 ante, he is said to have been alive in 772 H. by Shams himself. The T. M. (Text, 131, l. 12; E.D. IV. 12) and the T. A. (117, l. 17) also put his demise into 772 H. F. makes it two years later still, or 774 H. (I. 148, l. 8) and he has been followed by Sir W. Haig, who gives the Christian year as 1372-3 A. C. (C. H. I. 182). If Shams is right in stating that the event took place in the 18th year of the Sultan's reign, both 772 and 774 H. must be wrong and 770 only correct, as Firūz ascended the throne in Muḥarram 752 H. Elsewhere also, Shams states that Khān-i-Jahān the Second, the son of this Khān-i-Jahān, was the Prime Minister of Firūz for twenty years after the death of his father, (426, l. 9). As Khān-i-Jahān II was Vazīr upto Rajab 790 H. (E. D. IV. 15), this also would indicate that his father must have died in 770 H. Similar discrepancies arrest attention in connection with the dates of the death of Zafar Khān and the rebellion of Dāmghāni. See my note on Vol. IV. 12, l. 10 f. f.

III. 374, l. 2. Futūhāt-i-Firozshāhi.

This autobiographical record is also mentioned in the lists of authorities prefixed to the T. A. and F. and the document is said by Nizāmu-d-dīn Ahmad to have been inscribed on an octagonal tower in the Jām'i Mosque at Firūzābād. It contained, he says, eight chapters, each of which was engraved upon one side of the octagon. (120, l. 8; F. I. 150, l. 6 f. f.). Shams tells us that the Sultan ordered a complete account of his acts and proceedings to be engraved on the Kushk-i-Nuzūl which was in front of the Audience-hall at Firūzābād. He eites also the purport of the section

which stands first in Dowson's version and quotes a couplet which corresponds to the minth and tenth lines of Dowson's metrical translation of the poetical quotation (p. 376 infra=T F Text, 20-21)

III. 377, l 5 In former reigns, they used to collect frivolous, unlawful and unjust cesses at the public treasury I had all these abolished

The good Sultan gives a list of 23 imposts which is most interesting, but of which neither translation nor explanation is provided here, probably because many of the names are corrupt

The Mandau-i-Bark (Recte 'Barg', lit leaf) was the toll levied in the vegetable market The vernacular word Mandavi, means 'market,' 'market dues or tolls' and also 'toll-house' The vegetable market in old Dehli is still known as the 'Sabzi Mandi', 'market for greens' or 'the produce of the kitchen garden' Dalālat-i-bāzārhā was the brokerage on the transactions in the market Jarari (Recte, Jazzari) was the tax on butchers which is mentioned by Shams on 368 ante It was twelve Jitals for every cow or bullock killed. It is the Qassābi of the Ain (Tr. II 67) Amīri-i-Tarab seems to have been a cess which had to be paid to an officer who was appointed by the State to regulate festive gatherings in connection with marriages, dances, musical soirces, and entertainments There was a similar tax in Akbar's reign The officer was called Tur Begi and he was to get 5 per cent on the amount paid as tax by both parties to a marriage (Akbar Nāma, Text III 396=Tr. 585) Gul faroshi was a tax levied in the Flower-market There is a 'Ful ki-Mandi' even now in Dehli Jai iba [Recte, Zarība or Darība أصريه i-tambol was the tax from Pān shops, i e the betel-leaf market Chungi-i-ghalla was the octroi oi town duty on grains and cereals of all sorts 'Chungi' literally means 'a handful' Kitābī was perhaps a tax on book-sellers or scribes, Bilgari (Recte, Nīlkār i) a cess on indigo-making, Māhi-faroshi on selling fish or fishing rights, Sabūn-kāri on soap-making, Rīsmān-fai oshi on selling yarn, or perhaps rope-making, Raughan-kāri on oil or ghee making, and Nukhūdbiryan on roasted grain or chickpeas. The last six items were all taxes on handicrafts and bore some resemblance to our license taxes Tah Bāzārī cannot be explained Qīmār-khāna was a cess exacted from gambling-houses Dad-banki (Recte, Dadbegi) was a tax on the value of the property involved in a civil suit, which was levied by the Dad-bak or judge Minhaj says it was legally ten per cent ad valorem, (T N. 275, 1 18), but unscrupulous judges frequently exacted more 'Jhaba' might be meant for 😓 Chhāpa, a duty on stamping Kotwāli was the fee paid to the police magistrate, and Ihtisabi the perquisite of the Muhtasib who was the superintendent of weights and measures and was also a censor who regulated markets and public places in accordance with the Religious Law. Kai hi (Recte, Garbi or Ghari) means house-tax, Charai, grazing tax and Musadarat, fines and pecuniary penalties of sorts

There is a similar and even longer list of thirty-eight taxes, called

Abreāb, or Sāir Jihāt, which are said to have been remitted by Akbar in the Āin, (Text, 301; Tr. II. 66-67). Charāi is there called Gāu Shumāri. Jazzāri is Qaṣṣābi, Rismāni is San [lit. Hemp], Qimār-khānais Qimārbāzi, Raughan-kāri is Raughan, but Kitābi seems to be written as II seems to be written as II seems to be written as II seems to duty on rough or approximate estimates. as opposed to Wazani which is also mentioned and was the duty or charge for actual weighment. (Revenue Resources of the Mughal Empire, 17-18). In another passage of the Āin, the Collector of the Revenue is forbidden to take any perquisites like Chaukidāri, Rāhdāri, Mandavi, Māhūgūri, Dastūr-i-Raughan-i-zard and nine other cesses. (Text, 287, 1. 4 f. f.; Tr. II. 47).

III. 377, l. 2 from foot. The Sect of Shi'as.....had endeavoured to make proselytes.

The Khudābakhsh Khān Library at Bānkīpur, Paṭna, contains a manuscript History of Firūz Shāh written about 772 Å. H., entitled Sīrat-i-Firūzshāhi. The name of the author is not known, but it appears to be a contemporary record. In this also, it is said that Sultān Firūz suppressed the Shī'a heretics, punished them severely and burnt their books. (Folio 63 a. Abdul Muqtadir, Catalogue, VII. 30).

III. 378, 1.4. On the most zealous [Shi'as], I inflicted punishment (Siyāsat) and the rest I visited with censure (t'azīr) and threats (tahdīd) of public punishment (tashhīr-i-zijr).

'Sināsat' has a technical meaning in Islamic Jurisprudence, which is very inadequately represented by the English 'punishment'. It is used here as the Persian synonym of the Arabic 'Hadd', which in Law, is restricted to the punishments of which the limits (حدّ) have been defined by Muhammad, either in the Quran or the Hadis. These punishments vary according to the nature of the crime, e. g. for adultery, stoning to death; for fornication, a hundred stripes; for drinking wine, eighty stripes; for theft, the cutting off of the right hand; for highway robbery, the loss of hands or feet; for apostasy or blasphemy, death. So the Sultan says again at p. 380 infra that the blaspheming Mullāzāda [or Maulāzāda] of 'Ain-i-Māhrū who used to say 'Ana-l Haqq' 'I am God', was condemned by him to ساست, which can only mean that he was put to death as Mansur-i-Hallāj had been by the Khalīf Muqtadir. "T'azīr نزي is the chastisement which may be lawfully inflicted for any offence for which 'Hadd' or 'Siyasat' has not been appointed, whether the offence consist in word or deed. In 't'azīr', nothing is fixed or determined and the degree of the chastisement is left to the discretion of the Qazi, because the design of it is correction. It must vary according to the dispositions of men. Some men require confinement or even blows, while in other cases, admonition or reprimand or threats only (tahdid) may be sufficient." (Hughes, Dictionary of Islam, s. v. Hadd and T'azīr). Tashhīr is public exposure. The offender is made to ride on a cow or donkey with his face to the tail. It may be compared to the old English punishments of the stocks, the pillory and the cucking-stool Barani speaks of Balban inflicting the punishment of T'azir on certain political offenders by ordering them to be mounted on buffaloes and paraded through the streets of Dehli. (108, 1 15). But this is also called Tashhir

III 378, l. 9. There was a sect of heretics (Mulhid) and sectarians (abāhatiyan) They met by night etc

See my note on III 203, 1 12 Both these words 'Mulhid' and 'Ibahatian' are often loosely used, but the description which follows indicates that these persons belonged to the Vama-Margi or Vama-chari (let of the Left-hand Path) section of the Shaktas The Tantras constitute the scriptures of this sect and the essential requisites of Tantrie worship are the five Makaras, wine, flesh, fish, mystical gesticulations and sexual intercourse These Vama Margis or Vamacharis worship the female principle in creation, not only symbolically. but in the actual woman and promiscuous intercourse is said to constitute a necessary part of the orgies The 'garment' mentioned by the Sultan is the female devotee's Choli or Kanchuli, ie bodice (H H Wilson, Religious Sects of the Hindus Works, Ed Rost, I 254-263) Mr Crooke says that one division of the Vama Mai gis is known as the 'Choli Mai gis', because they make the women place in a par their bodices, the owners of which are then allotted by chance to the male worshippers The ceremony is known as the Bhairavi-chalia, (Tribes and Castes, I 136-137) These 'Choli Margis' are said to exist even to-day in Gujarat and Sindh and are known as the 'Kanchaliya-panth' Manucci speaks of similar lascivious cults in the southern part of the peninsula He calls them 'Multiphers' and their Scripture 'Emperumalavedam', which may mean "Veda of our great Lord Vishnu" Dr L. D Barnett, whom Mr Irvine consulted on the point, thought that the reference must be to some degraded form of Rimanujan Vaishnavism (Storia, III 145, IV 444 Note) See also Monier Williams, Brahmanism and Hinduism, 182 and E Sellon's paper on "Indian Gnosticism or Sacti Paja, the Worship of the Female Power" in the Memoirs of the Anthropological Society of London, II 264-272) Mr Crooke observes that "this brutal form of so-called worship is spreading in Upper India and that at the last Census (1891), 1576 persons avowed themselves worshippers of the left-hand path". (loc cit 137, see also I.G. I 427) A similar sect called 'Sahan Bhanan' is said to exist still in Assam (I. G VI 47)

III 379, l 2 from foot One of the pupils of 'Ain Mahrū

The words in the original are אל גונ אל גונלט בי הואף but the right reading probably is יאט וניפלט יסופליט יס

'Ainu-l-Mulk's father which is written by Ibn Batūta as ماهر Māhar. (Defrémery, III. 342, l. 4). This 'Ain-i-Mahrū is the great scholar and statesman, 'Ainu-l-Mulk Multāni of Barani and Shams. See also 369 ante.

III. 380, 1.6 from foot. In the village of Malūh, there is a tank which they call Kund [where they held fairs].

This Malūh (or Malūch) is probably identical with Mālja or Mālcha which is mentioned by Shams as one of the spots where Sultan Firūz constructed a Bund and enclosed a large quantity of water. (354 ante). The 'Kund' of which Firūz speaks here still exists. Hindus and 'graceless Musalmāns' still assemble there just as they did in the times of the Tughlaq and the Lodi Sultāns. It is situated near the temple of Kālikā which is of very great antiquity and is situated about six kos south-east of Shāhjahānābād, near Okhla. (Āṣār, Part i. 15). It is worth noting that three hundred years after Firūz Shāh, Aurangzeb issued similar orders for putting down Hindu fairs in a village called Malwah near Delhi. (Sarkār, Aurangzeb, III. 279).

III. 381, l. 12 from foot. Some Hindus had erected a new idol temple in the village of Kohāna.

There are two places known as Kohāna or Gohāna. Abul Fazl mentions a Kohāna or Gohāna in Sarkār Rewāri, Ṣūba Dehli, (Āīn, Tr. II. 293) and also a Gohāna in Sarkār Ḥiṣār Firūza of the same Ṣūba. (Ibid, II. 295). This latter is probably the place referred to by the Sultan. It lies about fifty miles north-west of Dehli. Lat. 29°-8′ N., Long. 79°-42′ E. Constable, Pl. 25 B c. It is now in the Rohtak taḥṣīl, 20 miles north of Rohtak town and contains "two temples in honour of the Jain Tirthankar Pārasnāth at which an annual festival is held." (I. G. XII. 340).

III. 382, l. 1 from foot. The details of this are fully set forth in the Wakfnāma.

This 'Waqfnāma' or Trust-deed of Endowments is mentioned in Nizāmu-d-dīn's summary of the 'Futūḥāt' and seems to have formed part of the Introduction or First Chapter of that Record. (T. A. 120, l. 12). But there is no trace of it in Dowson's version, although he says that he has "translated the whole of it with the exception of a few lines laudatory of the Prophet." (374 supra). It would seem as if there was more than one recension of the 'Futūḥāt,' or that this 'Waqfnāma' had been left out in Dowson's copy.

III. 383, l. 13. The Mināra of Sultān Mu'izzu-d-dīn Sām had been struck by lightning. I repaired it.

This fact and the repairs executed by the orders of Firūz are mentioned in a contemporary inscription on the fifth storey of the Qutb Minār. (Asiatic Researches, XIV, 488; $\bar{A}s\bar{a}r$, Pt. I. 55, Thomas, C. P. K. D. 283 Note).

It may be noted that the Sultan ascribes the foundation of the Qutb to Mu'izzu-d-dīn Sām, while Amīr Khusrau and Shams put forward the

rival theory which attributes it to Illutmish. This shows that opinion on this vexed question was just as divided five centuries ago as it is now

III 383, l. 10 from foot The columns of the tomb (of Shamsu-d-din Iltutmish) which had fallen down, I restored better than they had been before

Modern archaeologists think that there is some mistake here, as the description does not apply to what is now known as the Mausoleum of Illutmish They declare that the monument referred to by Firûz was not the tomb of Shamsu d-dîn himself but that of his son Nāsiru-d-dîn, who died in Bengal in 626 A II and whose mortal remains he buried in what is known as the 'Sultân Ghāri'—about two miles distant from the Qutb "That Mausoleum has," Faushawe observes, "columns in the grave-chamber, corners to the enclosure and steps upto the domed gate leading to this, and the Sultân Ghāri has all the appearance of having been restored in the middle Pathān 'yle of the severer type" (D P P 274 hote) Sir John Marshall entertains the same opinion (C H I III 580) III 387. I 2 from foot He [the Khalif of Equal also bestored upon

111 387, I 2 from foot He [the Khalif of Egypt] also bestoiced upon nie a robe, a banner and a footprint as badges of honour and distinction

The footprint is the Qadam-i-Sharif or Qadam-i-Rasūl, the Footprint of the Arabian Prophet It lies opposite the Parāna Qilla' and to the south-west of the Lāhore Gate After the death of his eldest son, Fath Khān, the Sultīn built a fine mausoleum and the footprint was placed over the grave of the Prince in a trough of water (Fanshawe, 57, 63, 325, Carr Stephens, Archaeology of Dehli, 147, Āsār, 92) Abul Fazl says that the footprint was brought by the renowned Sayyad Jalālu-d-dīn Bukhāri, called Makhdūm-i-Jihāniān-i-Jihāngasht (died 785 H), but the statement is not supported by other authors

In the abstract or summary of the Futuhāt which is found in the T A (121, 1 11), the Sultān is made to say that poison had been administered to him twice by his enemies, but that it had done him no harm. It may be observed that there is nothing corresponding to this statement in Dowson's version of the document. This also points to the existence of more than one recension. The statement itself is well-founded, as Barani, in his fragmentary account of the reign of Firuz, does mention a plot of the observed of the palace to poison the Sultan and the execution of some of the culprits (Text, 552, 19)

Nizāmu-d-dīn has also appended to his summary, a catalogue or inventory in which the number of the public works and benefactions of Firūz—the bunds, mosques, colleges, monasteries, palaces, inns, tanks, hos pitals, mausoleums, baths, pillars, wells, bridges and gardens, constructed by his orders, is meticalously recorded (T A 121, 1 7). If these details also were borrowed from and constituted part of his copy of the Futūhāt, it must follow that Dowson's manuscript was more or less mutilated or incomplete F.'s list of the Sultan's public works which is men-

tioned by Dowson (E. D. IV. 18 note) and is copied in Elphinstone's History (p. 412), and other manuals is really a dropsical and not quite accurate version of that of the T. A. Thomas, however, looks upon the latter also with suspicion and he is apparently justified in remarking that "Nizāmu-d-dīn's totals, though not so obviously exaggerated as Ferishta's, are clearly fanciful, especially in the number of even hundreds they display ". (C. P. K. D. 291). Here, as elsewhere, F. is merely "the ape of Nizāmu-d-dīn" as Raverty calls him.

III. 390, l. 6. The fact of its being a genuine work.....can, however, be proved upon more certain evidence.

Dowson's attempt to bolster up the *Malfūzāt* is not a success. It has failed to convince either Rieu or Ethé or Beveridge or Browne. The first declares that its "authenticity is open to serious objections." (B.M. Catalogue, 1. 178). The second speaks of it as "the alleged autobiographical Memoirs of Tīmūr', (I. O. Cat. Col. 84), the third stigmatises it as 'apocryphal' and 'forged' (J. A. S. B. 1921, pp. 201, 203), while the fourth categorically states that these "so-called Memoirs are generally, and I think properly, regarded by the best judges, as apocryphal." (L. H. P. III. 183). More recently, M. Bouyat has declared, in his article on Tīmūr in Houtsma's Encyclopaedia of Islam, that "the authenticity of the Memoirs and the Institutes is very doubtful." (IV. 779).

The British Museum possesses a Zafārnāma in prose (Add. 23980) which was composed in 806 H. It is, the only History of 'the great Tartarian' that was written during his life time. It is, as Prof. Browne says, "much more concise and less florid than the work of Sharafu-d-dīn and seems to have formed the basis of the later work." (L. H. P. III. 183). The author Nizām-i-Shāmi, tells us that Tīmūr sent for him and directed him to revise and put into proper shape and order the records hitherto kept by the official writers attached to his person. The Manuscript is said to be unique and was transcribed in 838 H. (Rieu, Pers. Cat. 169-71). I have been able, thanks to the courtesy of the distinguished numismatologist, Mr. John Allan of the British Museum, to obtain a photographic facsimile of the section relating to India and have made frequent use of it in these Notes.

Krors of rupees In this connection, it may be worth noticing that according to the Majālisu-s-Salātīn (E D VII. 138), the revenues of the Mughal Empire at the end of the reign of Jahāngīr and the first decade of that of Shāh Jahān were about six 'Arbs and thirty Krors of dāms The Malfūzāt is said to have been 'discovered' just about the time when the Majālis was written (1038 A H) and this coincidence in the numerical figures engenders the suspicion that the 'discoverer' may have substituted 'misqāls' for 'dāms', as he must have known that "dāms' were unknown in the days of Tīmūr

III. 398, l 13 The government of Kunduz and Bakalān and Kābul and Ghazni and Kandahār was vested in him

Baqlān or Baghlān lies in the valley of the Surkhāb or Qunduz river, about thirty-five miles south of Qunduz itself Constable, 22 C b It is directly on the route between Balkh and Indarāb (Holdich, G I 90) Qunduz is also known as Kataghān Constable, 22 C b Istakhri says that Baghlān was six stages distant from Balkh (Ed Goeje, 286) Ibn Batūta journeyed along the same route as Tīmūr and gives his own itinerary thus Qunduz to Baghlān, then to Andarāb, Parwān, Panjhir, Chārikār and the Indus (Gibb loc cit 178-181, Lee's Translation, 97-99)

III 398, l 10 from foot Mallu, the elder brother [of Sarang] lives at Delhi

Here Mallū Iqbāl Khān is called the elder brother of Sārang Khān But in the Zafar nāma (II 14, 1 2 f f, 480 infra), Sārang is said to have been the senior It is not easy to say which statement is correct, but it would appear from the T M that Sārang was ennobled and made governor of Dīpālpur by Mahmūd Shāh Tughlaq very soon after his accession in 796 H. (E D IV 28) Mallū's name occurs for the first time in that chronicle somewhat later in the order of time and he appears to have been indebted for his title and the not very important appointment of castellan of Loni to the fact of his having been the brother of Sārang (Ib 31) Indeed, another brother of Sārang's named Kandhu is stated to have received the title of 'Ādil Khān, some time before the promotion of Mallū (Ib 30) It would seem as if Yazdi was right and Mallū was the youngest of the three III 399, l 3 from foot. Tīmū Khwājah, the son of Amīr Ākūghā

The correct form is \$\text{Aq}\$ Bughā, (\$Zafai nāma\$, Text II 14, 1 13 and 15, 1 4) '\$\text{Aq}\$ ' signifies 'white' and \$Bughā 'champion' in Turki In speaking of Khudāi Birdi Tīmūrtāsh, who was one of his father 'Umar Shaikh Mirzā's Begs, Bābur notes that he was the descendant of a brother of \$\text{Aq}\$ Būghā Beg who was governor of Herāt under Tīmūr (B N Tr. 24 note) \$\text{Aq}\$ occurs frequently in Turki names, \$e\$ g. "\$\text{Aq}\$ Sultān" A Hamzaitaghī Būghā is mentioned below at p 410 and Rustam-i-Taghi Būghā at 450, 506 The name of this man, Tīmūr Khwāja-i-\$\text{Aq}\$ Būghā again occurs (\$Z\$ N II 83, 1 7 f f, 98, 1 22). The name, 'Akbugha' is found in Ibn 'Arabshāh also (\$Tr\$ Sanders, \$p\$ 63) For Sār Būghā, see \$Z\$ N 34, 1 14. III 400, \$l\$ 6 \$I\$ appointed the Prince 'Umar, the son of Prince

· Mirzā Shāh, my viceroy in Samarkand.

Mirzā Shāh is an error. Prince 'Umar was the son of Mīrān Shāh, the third son of Tīmūr. (Z. N. II. 18, l. 6). The Emperor Bābur was descended from Mirān Shāh. Tīmūr had no son named Mirzā Shāh. His four sons were Jahāngīr, 'Umar Shaikh, Mīrān and Shāhrukh. (Beale, Miftāh, 108). III. 400, l. 11. I crossed [the Jihūn] and encamped at Khulm.

Old Khulm lay about 50 miles east of Balkh, and about five miles north of modern Tāshkurgān. Constable, 22 B b. (Holdich, G. I. 270). Ghaztīk is, correctly, 'Ghazniyak', (Z. N. II, 19, l. 4) and is shown as 'Ghaznījak''in the Indian Survey Map of Afghānistan. It lies about 20 miles south of Tāshqurgān and forty north of Samangān. Samangān (l. 14) is not in modern maps. It is the old name of Haibak and lies 40 miles south-west of Baghlān and about a hundred and ten miles N.W. of Andarāb. (Moorcroft, Travels, II. 402; Burnes, Travels, 1st Ed. I. 201-5; Holdich, G. I. 272). Haibak is shown in Constable, 22 C b.

Undarāb, Indarāb or Andarāb, Lat. 35°-40′ N., Long. 69°-27′ E., is shown in Constable, Pl. 22, C c. Istakhri gives the following itinerary: Balkh to Khulm, two days; Khulm to Samanjān, two; Samanjān to Andarāba, five; Andarāba to Panjhīr, four; Panjhīr to Parwān, two. (Ed. Goeje, 286).

III. 401, l. 7. I left him [Prince Shāhrukh] in charge of the remaining forces and baggage in Tīlāk Ghunān and Dīktūr, while I myself set my foot in the stirrup to chastise the infidel Kators.

in Z. N. II. 20, l. 1. These place-names have hitherto defied elucidation. 'Tīlak' is almost certainly an error for Turki بلاق (Yaīlāq), 'Summer pastures, summer quarters' or يالق (Bailāq) 'Spring. fountain or camping ground.' (Beveridge, Tr. A.N. I. note). In his account of the return journey, Yazdi says that Timur marched from Surkhab to Kābul, then to the Māhīgīr Canal, Ghurbān غربان and Shibartu. (Z. N. Text, II. 186-7). This Ghurban (q.v. 32, l. 12 also) must be Ghorband, but Ghūnān or Ghūbān is, probably, Hūpiān, a very old town lying a little to the north of Charikar at the entrance of a Pass over the north-east end of the Paghman Range. (Beal, l. c. II. 285 note). There is no toponym resembling 'Diktur' in the maps. Paryan [Parwan] Ess about 8 miles north of Charikar. Constable, 22 C c. Khawak (last line) is shown in Constable, 22 D c. The Khawak Pass "leads from the valley of the Panjshir to that of Indarab. It is one of the lowest and most accessing of the Hindu Kush Passes. It is probable that it was used by Alexander on his march from Bactria and it was certainly the route by with Hienen Tsiang returned from India in 644 A. C. (So Clements Months) in Proc Royal Generalian Society 1572 -- 72/ 53

of this Ulūs [tribe] had shown such a lack of energy and courage since the days of Chingiz Khān" (407 post) By Ulūs, the writer means 'the descendants of Chingiz' In the Z N (II 22, 1 3), Burhān is said to have belonged to the tribe of Qiyāt أور قات 'Qai,' plural Qiyāt, is the name of a Mongol tribe and Amīr Khusrau makes an unsavoury pun upon the name (529 infira and Note)

were let down in the same manner III 403. 1. 9 Some of the horses Raverty says (Notes on Afghanistan, 136) that this mode of lowering horses and ponies is still practised in these parts. He thinks that the river 'crossed by Timur was that rising from the Waman Darra and that the mountain is the Tiraj Mir or Sarovar Range (Ind, 137, 145) The narrow defiles mentioned on p 406 infra, he identifies with the tract now known as Giwar (Ib 101 and 137) The Tiraj or Tirakh Mir is shown in Constable's Atlas, Pl 22, F b It lies north-west of Kashkar Giwar is mentioned by Babur, who says that Alingar is one of the five divisions (tumāns) of Lamaghān and the part of Kāfiristān nearest to it (Alingar) is Gawar, out of which its river, the Gau or Kau issues (B N Tr 210) Raverty supposes Timur to have marched due east into that part of Kāfiristān called Kashtūr or Kashtūz, and Burhān Ughlān to have been sent towards the south-eastern tract occupied by the Siyah posh or Tor-Kafiri (Black-clad Kafirs) According to him, the Kators are the Safed-posh or Spin-Kafir or White-elad Kafirs (N A 136 note), but other authorities state that the principal tribe of the Siyāhposh is still called Katīr (Kator) and trace the name to a title used by the later Kushan emperors, in whose territories Kāfiristān was included (Houtsma, E I., II 620)

ill 404, l 7 Shaikh Arslan Aztūmān Kabak Khān who is a lion in the day of battle.

Aziūmān الاتوال is not part of the name or the sobriquet of the Shaikh Az means 'from' and the meaning is that Shaikh Arslān belonged to the Tūmān [brigade, division, or corps of nominally ten thousand fighting men] which bore the name of Kabak or Kapak Khān The reading in the Z N (II. 23, 17) is الومان كيك على وش with the Tūmān of Kīpak Khān' Nizāmi-Shāmi has الراهل ولشكر حويش with his followers and division' (MS 126 a, 15) The point of the complimentary description lies in the fact that 'Arslān' means 'lion' in Turki.

The Z N (II 23,1 17, 38,1. 12, 103, 1 19 and 647, 1 11) always styles Mūsa, Jo, 'Ragmāl,' which has a meaning and signifies 'masseur, champooer, bone-setter' The man was a pahlwān, wrestler, gymnast or athlete The Oriental methods of bone-setting require great physical strength and the art is still practised by pahlwāns Mīr Husain's sobriquet is given by Yazdi as io octavit in the setting require great physical strength and the art is still practised by pahlwāns Mīr Husain's sobriquet is given by Yazdi as io octavit in the setting require great physical strength and the Husain's or ictavit in the setting require great physical strength and the Husain's or ictavit in the setting require great physical strength and the Husain's of the Qūr' in that is 'Mīr Ḥusain of the Qūr'

Pir Muhammad Khān Shirwāni is said to have ordered the poor man to be thrown down from a tower and then said that he had "become a victim to his name" nomen et omen (Lowe, Tr II 16). The pun and the deed are both equally atrocious. The Turki name conting to do with the Persian victim signifies 'tower' Another man of the same name, Būrji Tawāchi, is mentioned in the Tārīkh-i-M'asūmi (E.D I. 241).

III 413, l 4. Sunday, the 21st of the month, [Muharram]

There is again some error in the week-day here If the 12th was a Tuesday, the 21st must have been a Thursday A few lines lower down, the 28th is put down as a Wednesday. Here again, the Z N has Wednesday, the 27th, which is serially correct (II 53,14) Nizām-i-Shāmi has 24th, Sunday (130 a, 1 15) If the 24th was a Sunday, the 21st must have been a Thursday.

III 413, l. 5 I came to a place in which the rivers Jamb and Chinad (Chinab) unite.

The name of the place where the junction took place is not given in the Malfūzāt or the Z N, but Nizām-1-Shāmi calls it –ec (Folio 130 a, 1.15), by which he must mean Shor or Shorkot It lies 26 miles northwest of Tulamba. Lat 30°-50′ N, Long. 72°-7′ E (Th) Constable 24 E b, see also E D V 469 note The two rivers meet now at Trimmu, ten miles south of Maghiāna in Jhang district, and about 26 miles north of Shor or Shorkot (I. G XVI. 161, Mihrān, 332)

III 413, l 2 from foot Tulamba is about seventy miles from Multān The distance is stated as thirty-five Kuroh in the Z. N (II. 54) Tulamba lies fifty-two miles N E by N of Multān in Lat 30°-22′ N, Long 72°-18′ E according to Thornton Dowson has, throughout this translation, taken the Kuroh as equal to two miles, but Tīmūr's Kuroh would appear to have been the short Indian Kos of about 1½ miles So at 428, 492 infra, it is-stated that Fathābād is 18 Kos from Sarsuti (Sirsā), the actual distance is 26 miles.

III 414, l 8. My wazīrs had fixed the ransom of the city at two lacs of rupees

All that Yazdı says is compared to the context of the period It is non-sense to talk of 'Rupees' in 1398 A C or in this context. The word was not known and is never used in any other chronicles of the period. It must have been interpolated either by Abu Tālib Husaini or by Dowson. In the counterpart passage in the Z N at 484 infra also, all that is said is that "a ransom of two lacs was demanded." If the word occurs in the original, it would be an almost decisive proof of the spuriousness of Abu Tālib's work

III. 415, l 13 from foot I halted at Shāh Nawāz, a populous village on the bank of the Biyāh

Shāh Nawāz seems to have disappeared and cannot be now traced on

our maps, probably on account of the changes which have taken place in the courses of the rivers. But it is mentioned in the Itinerary of Sayyad Ghulām Muḥammad, who was sent by Warren Hastings on a mission to Kābul in 1786 A. C. He speaks of it as the second stage, 15 Kos from Multān, on the route from the latter to Derā Ism'āīl Khān. The third stage was Shāhpur, ten Kos from Shāhnawāz, and the fourth Tulamba, ten Kos from Shāhpur. (Raverty, Mihrān, 282 Note). 'Shāhnawās' is shown also in Rennell's Atlas on the eastern bank of the Rāvi in Lat. 30°-5′ N., Long. 72°-0′ E.

III. 417, l. 10 from foot. The rain kept continually falling, [at Multan] so that most of the horses......died..... and scarcely a horse remained among us.

Raverty, commenting on the loss of the Prince's horses, remarks that "the rainy season must have been very severe, though now there is no rainy season hereabouts, as the monsoon does not extend its influence so far west." He then indulges in some apparently hazardous speculations regarding the climatic changes that may have taken place in Sind since the days of Timur and Alexander the Great. (Mihran, 282). A more recent writer, Mr. Abbott, has echoed these sentiments and let his imagination run riot in a somewhat similar fashion. (Sind, A Reinterpretation, 16). But there can be no real grounds for entertaining any supposition of 'great climatic changes' from a solitary instance. According to the T. M. (Text, 163, l. 3=E. D. IV. 33), Multan was taken in Ramazan 800 H. (18th May-16th June 1398 A. C.), i.e. just about the beginning of the rainy season. Though the average annual rainfall in Multan is only about seven inches, there have been several years, even in recent times, when cyclonic bursts have occurred and the rainfall has approached twenty inches, as it actually did in 1902. Multan is liable to be visited by severe floods also as it was in 1893-4 and 1905. (I.G. XVIII. 24). Similar torrential downpours are, likewise, not uncommon in Sind. In Karāchi town. which has an average annual rainfall of only five inches, twelve fell in not more than 24 hours in 1902. (I. G. XXII. 394). The mortality among the horses was most probably due to the outbreak of some epizootic disease in consequence of the Prince's camp having been laid under water by the rain or the floods in the river.

III. 419, l. 20. Janjān which was stated to be eight miles from Multān. The distance is given as "It forty Kurch' from Multān in the Z. N. (II. 61, l. 8), which must be correct, as Tulamba is said to have been thirty-five Kurchs—seventy miles, according to Dowson, p. 413 ante. 'Eight' must be meant for 'eighty.' If 'eight' is correct, it may roughly represent the distance not between Multān and Janjān but between Tulamba and Janjān. Janjān, Sahwāl and Asiwān have not been identified. They are believed to have disappeared on account of the changes in the courses of the rivers. (Raverty, Mihrān, 283 and note).

III. 421, l. 10 from foot. I left Ajodhan.....on my march to Bhatnir,

and passing by Rudanah, I halted at Khālis Kotali.

Cf. the corresponding passage in the Z N at 488 infra and Dowson's note there. The existence of any place named Rudanah seems doubtful, as no one, not even Raverty, who stands up for this reading, has been able to spot it on any map or say where it is to be found The alternative reading, اد روده کند عنه. " without crossing or passing over the river " is also, as Dowson points out, manifestly wrong, as 'the Gharra or Ghara runs between Ajodhan and Kotalı and must be crossed on the road to Bhatner' I suggest that دودخانه is a copyist's error for رودخانه River In the B ارآب احوده ی که از معطمات انهار Text of the Z. N the sentence runs thus "Having crossed the river of Ajodhan, هد است كدشه حد خالص درود آمد which is one of the greatest rivers of Hindustan, he alighted within the precincts of Khālis (Kotali)." Nizām-i-Shāmi has almost the same words (Folio 133 a, 1 1) It seems to me that this tangle is due to some copyist having read the word دودخان عطيم The phrase رودخان عطيم. The phrase is rendered at 485 unfi a as 'a strong river fortress', but really signifies 'a great river' دود خاه in the sense of river or river-bed occurs often in the Z N. (II. 49, 19, 54, 17) Raverty says Khālis Kotali is now known as Pīr Khālıs (Mıhrān, 394 note), F calls it Khālis Kol (I 156, last line) He [Dul Chain] had assembled a body of Rajputs, a III. 422, l 10

class which supplies the most renowned soldiers of India

This mention of Rajputs here and on pp 423, 426, 433 and 472 infra is exceedingly suspicious. There is no reference to Rajputs either in

This mention of Rajputs here and on pp 423, 426, 433 and 472 infra is exceedingly suspicious. There is no reference to Rajputs either in Yazdi, Nizām-i-Shāmi, Mirkhwānd, Khwāndamīr or any other old history of Tīmūr The tribal designation is not used in any Persian history or chronicle which can be proved to have been written before the 16th century. Dowson says that he has not translated these extracts from the original Persian version of Abu Tālib Husaini, but from the later recension or revision made by Muhammad Afzal Khān It is therefore not easy to be sure that these references to Rājputs were not interpolated by Afzal Khān If they can be proved to exist in the first, i e Abu Talib's own recension of the Malfūzāt, they would furnish convincing internal evidence of its fabrication Tīmūr could have known nothing of Rājputs III 426, l 3 from foot. Auzān Mazīd Baghdādi,

It is 'Auzān' also at 491 infra, but الادون Auzūn in the Z N. II 75, l 3 f f The word means 'tall, long' The man was so called probably on account of his unusual height His real name must have been Mazīd.

III. 427, 1 10 And passing by the fort of Finoz, I arrived at a town called Sarsūti

This is not 'Hisar Fīrūza', but a place called Fīrūzībād which was situated only a few miles west of Sarsūu (or Sīrsī), Tīmūr's next stage Hisar Fīrūza lies at a distance of about sixty miles E. S E. of this

Firūzībād. (Mihrān, 288, 267 note). Barani also tells us that Firūz Shāh Tughlag built a fort near Bhatner, which was called Fīrūzābād (566, 1, 11). and it is the place which is called Firuzabad-i-Harni Khera by Shams-i-Siraj. (354 ante). According to the T. M. also (126, l. 4; E. D. IV. 8 and note), one of the Sultan's canals was carried from the Ghaggar to Sarsuti (Sirsa) and thence to Harni or Harbi Khera. Here, 'Harbi Khera' is an error for 'Harni Khera'. The village of Firuzībād-i-Harni Khera still exists and lies about twelve miles west of Sirsa, according to the Hissar District Gazetteer.

III. 428, 1. 14. I marched from Fathābād and passing by the fort of Rajabpur, halted in the vicinity of Ahruni.

Rajabpūr or 'Qil'a-i-Rajab', as it is called in the Z. N. II. 78, is said by Elliot to have been partly in Ratia and partly in Fathabad. (Races. II. 132). Ratia is shown in Constable 25 A c, and lies about fifteen miles north-east of Fathabad. Raverty thinks that Rajabpur must be the village of Ryepoor. 11 miles N. E. of Fathabad on the route from Fathabad to Ahroni. (Mihran, 288 note). None of these identifications is quite satisfactory, as neither 'Ratia' nor 'Ryepoor' bears much phonetic resemblance to Rajabpūr. Ahroni was a Mahāl in Sarkār Hisār Firūza, Sūba Dehli, (Ain, Tr. 293). It has now reverted to its original name 'Ahirwan', the wav being pronounced as a consonant and not as a vowel. The name is said to be derived from the Ahir tribe. (Elliot, Races, II. 133). A village called 'Ahrawan' still exists at a distance of about five miles from Ratia and it is provided with a Branch Post Office which is subordinate to Fathābād, Tohāna (l. 23) lies about 20 miles east of Ratia. It is now a station on the N. W. Railway.

III. 438, l. 5. [It had been said] that in the battlefield, they [elephants] could take up the horse and his rider with their trunks and hurl him into the air.

The writer has evidently in mind a passage in the Tārīkh-i-Yamīni of 'Utbi, who describes how in the battle with Ilak Khan, one of Sultan Mahmud of Ghazna's elephants seized the Khan's standard-bearer in his trunk, flung him up into the air and then catching him on his tusks, tore him into two pieces, while other riders were hurled down from their mounts and trampled to death. (Lähore Lith. 283; see also Habību-s-Siyar in E. D. IV. 172). Yazdi has a direct quotation from Jurbadhaqani's Translation of 'Utbi. (Z. N. II. 146, l. 3). See Dowson's note to 512 infra.

III. 439, l. 8. His right wing was commanded by Mu'inu-d-din, Malik Hādi etc.

The command of the right wing is given in the Malfuzāt to Mu'inud-din and Malik Hadi and of the left wing to Taghi Khan and Malik 'Ali. The positions of the commanders are just reversed in Dowson's version of the Zafarnāma. Mu'īnu-d-dīn and Hāni (or Hāti) Khān are stationed on the left, while Taghi Khan and Malik 'Ali Hauja are placed on the right. (498 post). The B. I. Text agrees with the Malfuzāt. (100, l. 4). Mu'inu-ddīn and Hāni Khān cannot be identified, but Taghi Khān (or Tughān Khān, as Nizām-i-Shāmi calls him, at Fol. 140 a, l. 9), may be Taghi Khān Turkbacha-i-Sultāni of the T M (Text. 170, l 9, E D IV 38)

III 443, l 11 Fazlu-llah was Vahil and Naib of Mallu Khan

Fazlulla Balkhi is mentioned in the T M (Text, 160, 18, E D IV 31), T A (127, ll 1-3) and F (155, 18), as one of the partisans of Nāsiru-d-dīn Nusrat Shāh, the rival of Sultān Mahmūd Tughlaq, who bestowed upon him the very high title of Qutlugh Khān Shams-i Sirāj says Fazlulla was Nāib-i-Mustaufi, Deputy Accountant-General or Auditor-General, in the latter part of the reign of Firūz Shāh Tughlaq (482, 17 f. f).

III. 444, l 20 The Khutba, with my name, was repeated in the pulpits

He does not say that coins were struck and Yazdı also is silent on the point. If any were stamped, they must have been exceedingly few Rodgers assures us that no gold or silver pieces have been ever found. The only coin he had ever seen was a small copper piece or 'Damii', as he calls it, with the words on the obverse and on the reverse. He states that the 'Damii' is now in the British Museum Collection. (J. A. S. B. XLII (1883), Pt. 1. 59, 62, 63).

III 449, l 6 'Alau-d-din Naib-Karkarı retui ned to my camp

اب شير كوكرى (Z N II 127, 1 5 f f), i e. envoy, deputy, rakil, representative of Shaikh [ā], the Kūkar Cf 505 post, where he is spoken of as "the deputy of Shaikh Kūkari" Dowson's 'Shaikh Kūkari' is really 'Shaikhā Khokhar' [or, perhaps, 'Gakkhar'] The confusion is due to the common error of reading a 'vāv' as a 'ie'

III 449, l 13 Bahādur Nāhu sent to me two white parrots which could talk well They had belonged to Sultān Tughlik Shāh and had lived at the courts of the Sultāns ever since

"A white parrot with black beak and legs," probably a grey African parrot or cockatoo, had been brought from over the seas as a present for Sultan Firuz Tughlag (Shams, Text, 387, 1 2) The two birds sent by Bahadur Nahar must have come into his possession along with the other belongings of Abu Bakr Shāh, the ill-starred grandson of Sultan Firūz 'Abu Bakr had to fly from Dehli and take refuge at Kotila in Mewat, with this Khanzada leader, who had the baseness to surrender him to his enemy in 793 H (T M Text, E D IV. 25) The 'Tughlik Shah' mentioned here must be Ghiyasu-d-din Tughlaq I and not Tughlaq Shah II The latter was a pageant who reigned for only six months, just ten years before Timur's invasion and there would be little or no point in the statement, if applied to him Cf Yazdi, who states more explicitly that the birds had sur vived from the time of Sultan Tughlag Shah (505 infi a) آن دوطوطي ار عهد طعلق شاه بار مانده بوديد و مدنها در معالس شلاطين سعبوري شكر حاعي كرده. Z N II 128, 1 3 Parrots have been known to live for sixty and even a hundred years The English newspapers reported some time ago the case of a parrot which had passed its century

III. 449, 1. 10 from foot. I arrived at the village of Katah.

The distance from Dehli is stated as about 14 Kos. Katah (l. 23) is Katha in Bāghpat. 'Alīu-d-dīn Khalji erossed the Jumna at Katha. (Barani 246, l. 2). Katha lies about 20 miles north of Dehli. Bāghpat or Bhāgpat, which is mentioned a few lines lower down, is about 30 miles south-west of Mīrat and about 35 north of Dehli. (I. G. VI. 190; E. D. VIII. 149 note). It is shown in the I. G. Atlas, 31 A 2. Asār is Asāra or Asaura, a village about ten miles north of Bāghpat. (See the Post Office Guide).

III. 449, 1.9 from foot. Bahādur Nāhir with his eldest son, named Kalnāsh.

Dowson notes that the Z. N. reads 'Kaltāsh' and 'Katāsh.' I propose to transpose the second and third letter in Qaliāsh and read 'Qailāsh', a not uncommon Hindu name even now. Bahādur Nāhar was a recently converted Jādon Rājput (I. G. XII. 401; Crooke, T. C. III. 233), and it is not at all unlikely that his son had a Hindu as well as a Muḥammadan name. This 'Kailāsh' may be identical with Iqlām or Iqlīm Khān, son of Bahādur Nāhīr. (T. M. Text 175, 179, 181=E. D. IV. 41, 44, 45). Thornton mentions a place called 'Iklimpoor' in Gurgāon district, which may have been named after this Iqlīm Khān.

III. 450, l. 9. Ilyās Afghān and his son, Maulānā Ahmad Thānesari.

The B. I. Text of the Zafarnāma gives the names as "Ilyās Afghān and the son of Maulānā Aḥmad Thānesari" (II. 129, l. 10 and 140, l. 4 f. f.) and Nizām-i-Shīmi has exactly the same reading (Folio 142 a, l. 10), which must be correct, though Dowson again erroneously speaks of Maulānā Aḥmad as the son of Ilyās Afghān, in his translation of the Z.N. at 506 post.

This Ilyas Aighan is, most probably, the Malik Ilyas [or Ilmas] who had been a slave of Sultan Firuz (T. A. 127, 129; F. I. 155, 159; B. I. 267=Tr. 362) and was an adherent of Nasiru-d-din Nusrat Shah. He was posted in the Duab and is said to have joined Nusrat Shah after Timur's return. (T. M. Text, 160, 161, 167=E. D. IV. 31, 32, 36). Maulānā Ahmad Thanesari also can be identified. He was one of the most learned men of the time of Sultan Firuz and is mentioned in Shaikh 'Abdul Hagg Dehlavi's "Memoirs of the Poets and Philosophers of Dehli" as a distinguished literary character whose poems in Arabic bore convincing testimony to his eminent talents and genius. (E. D. VI. 487). He was a pupil of Shaikh Nașīru-d-dîn Chiragh-i-Dehli. His Qaşîda-i-Dâliya is universally recognised as a classic. He was in Dehli when it was sacked by Timur and is said to have been taken prisoner but afterwards released. He died in 820 A. H. and is buried at Kilpi. (Houtsma, E. I., IV. 738). This leaves no room for doubt and shows that it is absurd to speak of the Maulana as the son of Ilyas [or Ilmas] Afghan, the quondam slave of Firuz.

III. 452, l. 13. I arrived at Pirozpur.

Elliot says that this Pirozpur was a town or village in the pargana of Hastinapur in his time and lay on the bank of the old Ganges or Budh Ganga. The Ganges has left its old bed and does not now flow past

Pirozpur, which is stated to have been about twenty Kos below, i e south of Tughlaqpur (Races, II, 28 and 130). But it may be the place which Thornton mentions as 'Ferozepoor', in the district of Muzaffarnagar, half a mile from the right bank of the Ganges Lat. 29°-30′ N, Long 78°-2′ E There is another 'Ferozepoor' in Sahāranpur district also, 45 miles N W of Mīrat, Lat 29°-37′ N, Long 77°-31′, but it is too far north and too far also from the Ganges and cannot be the place meant

III 452, 8 from foot I marched up the river for a distance of fifteen Kos towards Tughlikpur.

This Tughlaqpur is not the Tughlaqpur before mentioned which was near Safidon This place was in another and different district Tughlagpur which is mentioned as a Mahal of the Sarkar of Saharanpur in the Ain (Tr II 292) Elliot states that the chief town of the pargana of Tughlaquur in his days (circa 1840) was Nurnagar and that it was so called because Nur Jahan was said to have resided here for some time He adds that the par gana was also known as Gobardhanpur (Races, II. 181) There is a 'Noornagar' on the route from Muzaffarnagar to Hardwar, 22 miles north-east by north of the former town Lat 29°-41' N. Long 77°-59' E (Thornton) Gobardhanpur is now one of the five parganas in the Muzaffarnagar talisil of Muzaffarnagar district (I G XVIII 92) Tughlaqpur and Nurnagar are now included in the pargana of Pur Chhapar in the same talisal They lie just on the borders of the pargana of Gobardhanpur I am informed by a local authority that the villages of Tughlagpur, Nurnagar and Gobardhappur lie 17, 22 and 28 miles respectively north-east of Muzaffarnagar town

III 453, l 13 They put every living soul to the sword, thus sending them through water to the fires of hell

This pl rase occurs again a few lines lower down and Dowson observes in his Note that "Timūr was evidently proud of this savage jest" But the 'jest' is not Timūr's at all and there is nothing to be proud of about it. It is only a hackneyed, rhetorical tag, a translation of an old Arabic epigram, '[occlet]', which is found in the Qurān. (XXVI 25) Pharach and his army are there said "to have been drowned and made to enter fire" for their sins. The identical expression is used by Minhāj (T. N 169=E D 323) for the Khokhars who were drowned in the Jhelum after the battle with Sultān Mu'izzu-d-dīn-1-Sām. Amīr Khusrau says of the same invader that the sword which he struck against the Rāi of Qanauj drowned him in the water through waves of fire

And the hemistich נה עני עני עני אין אין "By that same watery way, he went to hell", is cited twice by Budauni He quotes it once in his account of the fate which overtook Kulchand of Mahaban after his defeat by Mahmud (I 14, Tr. I 24) and again in connection with the catastrophic termination of the meteoric career of Pir Muhammad Khan

Shirwani in the waters of the Tapti after his sack of Burhanpur. (Text, II. 51=Tr. II. 47 and E. D. V. 275 note). This eatchpenny antithesis or metaphor occurs also in Yazdi who says of the Gabrs of Mīrat that all of them "went by the ford of the water of the sword to the fires of hell". المعنى المعنى

III. 463, 1. 11. I encamped at the village of Bahrah, in the country of Miyapur. Next day, I marched four Kos and halted at the village of Shikk Sar.

Mayāpur is the name of an old ruined town or suburb between Hardwar and Kankhal, south of the former. It is called 'Moyu-lo' by Hieun Tsang [or Yuan-Chwāng]. (Beal, l. c. I. 197-8). Cunningham derives the name from the old temple of Māyādevi which it contains. (A. G. I. 352). It is mentioned in connection with the hills of Bardār (Hardwār?) and Bijnor [or Pinjor] in the T. N. in E. D. II. 353. Sec also *Ibid*, 334.

Bahrah is spoken of as "a dependency of Bakri, well-known as the country of Miyāpur". (513 infra). Bakri is most probably the modern Bhogpur. Bhogpur and Baghra are mentioned as parganas in the Sarkār of Sahiranpur. (Āin, Tr. II. 291). The town of Bhogpur lies about ten miles south of Hardwār and the pargana of Bhogpur comprised the eastern portion of Jwālipur, including Hardwār itself, in Elliot's time. (Races, II, 129). The village of Baghra which was four kos from Shikk-Sīr is not easily identified. It may be 'Badhera', a village which lies about five miles south-east of Sarsīwa, 'Shikk Sīr' is Shiqq-i-Sarsāwa. The town of Sirsīwa lies about ten miles west-north-west of Sahīranpur on the route to Ambīla. Lat. 30°-2′ N., Long. 77°-29′ E. Constable, 25 B c. Shiqq is not a part of the proper name, but a common noun signifying "a geographical or territorial division or administrative area".

III. 464, l. 7. Then I again mounted and on the morning of the 15th, I found myself between two mountains, one the Sivalik mountain, the other the Kūkā mountain. This was the valley (darra), and it was exceedingly strong.

I venture to suggest that 'Kūkā' 'S' is a miswriting of SKarkā, i. e. Gargā. It is the Gagar range of our Gazetteers which is also called Gargāchal or Gārgāchal. It runs long the districts of Almora and Kumāon and presents a line of higher elevation than any ranges between it and the main ridge of the Central Himalayas. (I. G. XII, 121). The 'Darrah' or valley between the Siwālik (the Sub-Himalayas) and the Kūkā or Gargā hills (the Outer Himalayas) was, probably, Dehra Dūn or the Kyārda Dūn in the south-east portion of Sirmūr State. (I. G. XXIII. 21).

III. 469, l. 3. After marching six Kos [from Mansar], I encamped at the village of Bāila.

Mansar and Baila still exist as villages and lie north-east of the modern town of Jammu. I am indebted to the Governor of Jammu f

the information that Bāila is about ten and Mansar thirteen Kos from Jammū itself. Both lie on the route from Kāngra to Old Jammū, which was situated about one Kos north-east of the modern town. An old fort still stands on the ancient site

III 470, l 4. Mullā Nūru-d-dīn had returned to the village of Jabhān The reading in the B I Text (II 164), is ir Recte, Chibhān, the old name of Bhimbar (Cunningham, A G I 184, Āīn, Tr II 347 n.te). Chibhān or Chibhāl is the country of the Chibhs, which extends from the Manāwar Tāwī or Malikāni Tāwī to the Jhelum. (I. G XV 100)

III 471, l 19. I commanded that they should attack and plunder the town of Jammu and the village of Manu

'Manū' is a misreading of 'Bāo' 3h Jammū and Bhāo or Bāo lie on opposite banks of the Tohi or Tawi, a small stream which joins the Chenāb at the foot of the hills They are said to have been founded by and named after two brothers (Cunningham, A G I 183). Bāo is shown in Constable, Pl 25 A a

III 475, l 10 from foot. He [Khizr Khān] took refuge with Ahodan governor of Bayāna

also in the Z N II. 175, l. 8 f f, but the person referred to is اهردى, Shams Khān Auhadi, who was Amīr of Bayāna from about from 800 to 819 H (T M in E D IV, 37, 49) His descendants continued to rule in Bayāna for many years and are frequently mentioned in the histories of the period. The 'nisba' may be derived from Auhadu-d-dīn.

III' 482, l 1 An account of the victory was engiaved upon stone, with the date of the month Ramazan 800 H, together with the date used in the locality

Sharafu-d dīn does not say any such thing at all Timūr could have known nothing of the "date [or special era] used in that locality," or the peculiar chronological system of the Kāfirs or Kators, even if they had possessed any The words of the Zafarnāma are المعالم الم

Masson was inclined to think (Journeys in Balochistan, Afghanistan, etc I. 200-1) that a structure which was in existence in his time, a little to the north of Nājil (in Kāfiristān) and known as the 'Timur Hisar',

was the fort on the river which Timur destroyed after it had been abandoned by the Kāfirs and that the inscription must have been engraved near this place. See also Holdich, Gates of India, 357.

III. 487, l. 17 from foot. Shaikh Munawwar and Shaikh S'ad.

Sharafu-d-dīn (Z.N. II. 65, l. 1) and Nizām-i-Shāmi (Folio 133 b, l. 3) state that Shaikh Munavvar was a grandson [•] of some Shaikh called Nūru-d-dīn. I venture to identify the latter with Shaikh Nūru-d-dīn of Hānsi who was the spiritual preceptor and guide of Shams-i-Sirāj. (T. F. 81, l. 3). Nūru-d-dīn was the son of Shaikh Qutbu-d-dīn-i-Munavvar and Sultān Firūz once paid him a special visit, with a view to persuade him to transfer his abode from Hānsi to the newly-founded city of Ḥiṣār-Firūza. (Ib. 131; 302 supra). An anecdote connected with Firūz's interview with Qutbu-d-dīn, the father of Nūru-d-dīn, is also related by that author. (Ib. 78-82; 287 supra). Shaikh Munavvar of Yazdi was, most probably, named after his ancestor, Qutbu-d-dīn-i-Munavvar of Hānsi, q. v., Āīn, Tr. III. 372-3. In the Malfūṣāt (421 ante), 'Munavvar' is called, by Dowson, Manuā ;, but this may be due to the 're' having been wrongly read as an 'alif', or it may be a contemptuous diminutive. Shaikh S'ad or S'adu-d-dīn was a descendant of Shaikh Farīd-i-Shakarganj.

III. 488, l. 1. [The fort of Bhatner] is surrounded by the desert of Chol.

بجانب دست راست و اطراف و جوانب چواست; II. 67, l. 4. "On its right hand and on its sides, there is a Chol"—a wilderness or uncultivated waste. 'Chol' is not the name of the desert but a common noun signifying, as Yazdi himself declares, (II. 47, l. 13) بان "an arid or waterless tract". Cf. Dowson's own translation at 421 ante, where the Chol is said to "extend for many miles around."

III. 488, l. 14. Khālis Kotali, two Kos from Ajadhan.

ten Kos' in the Z. N. (Text, II. 67, last line) and also in the Malfuzāt (421 ante) which must be correct. ها منه has been wrongly read for ها. F. calls it 'Khālis Kol.' (I. 156, last line). Kol or Kolāb means 'pool' or 'lake', but Yazdi speaks of it as a نله (68, 1. 2).

III. 490, l. 3. He presented three Arab horses with golden saddles. إلى المنافرين المنافرين والمنافرين المنافرين المنافر

III. 490, l. 18 and footnote. All the Mss. agree in giving this Muhammadan name to his brother.

Here as well as in a Note to 425 ante, Dowson expresses surprise because one brother is said to have had a Hindu name and the other a Muhammadan lagab. But it is common knowledge that this was not at, all unusual in those times. The Hindu Bhattis were, during the 14th century, being gradually proselytised under the influence of Muslim saints and Sultans. It often happened that while one brother embraced, for worldly considerations or from inward conviction, or indifference in

matters spiritual, the dominant religion, another held back and continued to adhere to the old faith Mr Crooke states that large numbers of these tribes were converted in the times of 'Alāu-d-dīn Khalji and Qutbu-d-dīn Mubārak and that in Sirsa, which lies in the old Bhattiyāna, the term Bhatti is commonly applied to any Musalmān Jat or Rajput, from the direction of the Sutley, as a generic term (T C II 14)

But Kamālu-d-din is called 'Maīn' and not 'Bhatti' in the T M. (Text, E D IV 22, 28, 29) Dowson suggests (IV 22 note) that the Maīn are the same as the 'Minās', but the latter are 'Meos', found, generally, in Gurgāon and Rajputāna. The Maīn are a branch or sept of the Bhattis The word 'brother' is used here, most probably, in the loose sense of 'cousin' or 'relative'

The author of the T M must have known that the Bhattis were not identical with the 'Mains,' as he calls Khulchain [Dulchain of Yazdi] and his son Hansu [Hansrāj?] 'Bhattis', while Rāi Kamālu-d-din and his son Dāūd are invariably styled 'Mains' (Text E D IV 22, 28, 29, 32, 40) Barani also mentions Bhattis and Mains (483, 1 5 f f, 245 Note, supra) III 493, 1 20 Amīr Sulaimān marched from the vicinity of Mung to the neighbourhood of Samāna

Mūng is Mung-1-A'alā or Moonuk of Thornton, who says that it is on the Ghagghar on the road from Dehli to Ferozepore, 140 miles northwest of the former Lat 29°-49′ N, Long 75°-57′ E It lies north-east of Fathābād. (Raverty, Mihrān, 439 and Note) Samāna is in Lat 30°-10′ N, Long 76°-20′ E, and about 17 miles south-west of Patiāla (I G)

III 495, l 17 This fort [Loni] is situated in the Doāb between the rivers Jumna and Halin The latter is a large canal which Sultan Firuz Shāh brought from the river Kālini

This 'Halin' is written in the Z N (II 86,17) and is meant for the Hindan (algorithm Andrews). Thornton states that the Hindan "rises at the south-west base of the Siwālik range. Its course is divided from that of the Jumna by slight elevation of the surface along which the Doāb canal extends. It falls into the Jumna after a course of 160 miles in the north-western corner of Bulandshahr district." The Kālini is the Kālinadi (West), which is its chief tributary. "Its channel forms an important link between the Ganges and the Jumna and water can be passed into the Hindau from the present Upper Ganges Canal." (I G XIII. 135)

III 495, l 22, Maimun Maishum

'Maimun' only is the name 'Maishum' is an expletive and antithetical jungle 'Maimun' means 'auspicious,' Maishum' signifies 'unfortunate, perverse, execrable', an epithet of revilement which is appended here only for rhetorical effect

III 495, 2 from foot. He gave orders that such of the servants of Naukar Khān and of the inhabitants of the place as we we Muhammadans should be set aside

[&]quot;Naukar Khān" is, like Mūr Khān, a fiction

فرمان داد که از نوکران ملوخان و متوطنان آن فلمه هم که از زبور اسلام متحلی بود نرمان داد که از نوکران ملوخان و متوطنان آن فلمه هم که از زبور اسلام متحلی بود II. 87, I. 6. "He gave orders that such of the servants of Mallū Khān and of the residents of that fort as were adorned by the jewel of Islam should be set aside". "Naukar Khān" is a mythical personage. The people referred to were the servants—Naukar—of Mallū Khān. The copyist of the Ms. must have missed out the word Mallū. "The servants of Mallū Khān" are mentioned a few lines higher up on this page.

III. 498, 1.7. The soldiers by way of precaution, entrenched their camp which was near a little hill called Pushta-i-Bihāli.

Fanshawe thinks that Tīmūr's camp was on what is now known as the Ridge, and that the battle took place on the plain traversed by the high road from Safdar Jang's tomb to the Qutb Minār. (D. P. P. 58). Ghiyāsu-d-dīn Tughlaq had routed Khusrau on the same spot. (Ibid, 250-1). III. 498, l. 11 from foot. The right was commanded by Taghī Khāń, Mir 'Alī Hauja and others.

Mīr 'Ali Hauja must be 'Ali Malik of Uccha. He is so called because he held that town for Sārang Khān, when Pīr Muḥammad Jahāngīr besieged it. After he had been beleaguered for a month, Sārang sent Malik Tāju-d-dīn to his relief, but the Tātār fell suddenly upon this reinforcement and signally defeated Tāju-d-dīn who was compelled to fly to Multān. (T. M. 102, l. 7=E. D. IV. 32-3). 'Hauja' (Z. N. II. 100, l. 4) is a puzzling perversion of 'z).

III. 502, l. 2 from foot. A number of soldiers collected at the gate of Dehli and derided the inhabitants.

This is watering down the meaning so very much as to leave nothing of the substance. What Yazdi really says is that they assaulted the people of Dehli and "fell upon the inhabitants just as wild beasts of prey fall upon a herd of deer or as strong vultures pounce upon a flock of feeble birds". چون سباع شکار جو برگله کور و اهو افتد و مانند عقاب شکوه مند که قصد مهان ضعف

بنیت کنند بر مردم حمله می بردند و متعرض رعایا می شدند . 121, 1.4

According to the Malfuṣāt also, a party of "fierce Turk soldiers...... laid violent hands on the goods of the inhabitants." (445 supra).

III. 503, l. 2. The wife of Jahān Malik 'Āghā and other ladies, etc. در آن علل حضرات عالیات چلیان ملك آغا و دیگر خواتین بعزی تباشای هزار ستون بشهر در آمدند II. 121, l. 10. "At that time, their Exalted Highnesses Chalpān Malik Āghā and other princesses went into the city, with the intention of seeing the Hazār-Sitūn". Chalpān [or Jalbān] Malik 'Āghā was one of the wives of Tīmūr himself and is again mentioned by Yazdi. (II. 186, l. 6 f. f.). She is said to have been a woman of rare beauty and was executed afterwards for some imaginary fault. (Houtsma, E. I., IV. 779). Another consort of Tīmūr's named Tūmān Āghā is spoken of at Z. N. II. 188, l. 4.

III. 504, l. 4 from foot. Jahānpanāh has thirteen gates, six to the north-east and seven to the south-west.

The bearings are very differently stated in the original. The B.I. Text

Here again, the B I. Text has the right reading 'City of Kūtila' (II 127,14ff) See also the Malfūcāt (449 ante) This Kotila is often mentioned in the T.M, TA, F and B as the stronghold of the Mewāti chief, Bahādur Nāhar (ED IV 24, 25, 27, 32, 53, 75) See also the Āin (Tr II, 193), where Kotla is said to have been a fort in Sarkār Tijāra, Sūba Āgra 'Kūpila' is a very different place It is the old name of Hardwar or Mayāpur

III. 506, l. 8 [The people of Mirat were] boasting that Tarmsharin had attacked the fort but was unable to take it

Tarmsharin was the son of Dawa or Dua Khan, and belonged to the Western branch of the Jaghatai Khans of Transoxiana He reigned from 722 to 730 or 734 H. (Tar ikh-1-Rashidt, Tr Ney Elias and Ross, Introd 49) B (I 223, Tr I 305) and F. (I 134, 1 2) both mention the invasion, but the former puts it into 729 and the latter into 727 H (See also Ain, Tr III 345 Note) As there is no reference to the incursion in Barani, F accuses him of having deliberately suppressed the fact with a view to curry favour with Sultan Firuz Tughlaq, but the imputation is not at all warranted, as Barani has mentioned two Mughal invasions in his account of Firuz's own reign, (268 ante=Text, 601-2) while F himself, the T A. and all the other compilers who have copied their accounts of Firuz from the T M speak of only one such irruption, All the Mughal inroads of 'Alau-ddin's reign are described by Barani, and he has even recorded one or two which are left out by F or some of the later chroniclers. An invasion in the reign of Ghiyasu-d-din Tughlaq I, to which there is no reference in any of the compilers is also mentioned by him (Text, 450, 1 8 f f) All the other calamities and disasters of the regime of Muhammad, the famines and economic chaos, the revolts and rebellions, the invasion of Kumāon and the abortive projects of agricultural reform, are registered in full by him; the ferocious cruelty and blood-lust which turned the portico of his palace into a shambles, the insane profusion of his largesses and the crazy adulation of and abject submissiveness to the Khalif are also described with brutal candour In the circumstances, it seems difficult to resist the conclusion that this particular omission must be due to carelessness or inadvertence

III 514, l 9 Ratan Sen had assembled a great number of Hindus

The BI Text absurdly makes specific mention of the Majūs here also مان کثیر از محوس و اصاف هدوان از اطراف و حواب بهم بوسته اند II. 155, I 2.

The territory of this Ratan Sen was, probably, somewhere in Dehra

The territory of this Ratan Sen was, probably, somewhere in Denra Dun or the Kiarda Dun in Sirmur (I G. XXIII 21). It is not likely

that the Raja had a large number of Majus.—Magians or Persian Zoroastrians-among his subjects. These apparently unmistakable allusions to the existence of colonies of Parsis or Iranian fire-worshippers in the remote regions of Northern India are unhistorical and founded on the loose and confusing use of 'Majūs' as synonymous with 'Gabr.' Musulman authors huddle together under the term 'Gabr' not only Hindus but all infidels. Christians included. The word is foisted in here merely for that 'alternation of diction' to which Persian authors attach such undue importance and which is chiefly responsible for their turgidity and bombast. There is no mention of Majús in the counterpart passage of the Malfuzāt. (463-5 ante).

III. 518, l. 2. Ulja Tamūr Tūnkitār and Fūlād and Frince Rustam's confidant Zainu-d-dîn.

اولجه تدور توقتار و قولادو ال . The B. I. Text reads the clause differently الدين الدين

"Ulja Tamur Tunkitar and Quladu belonging to the contingent of Amīr-zāda Rustam and the trustworthy, Zainu-d-dīn." Nizām-i-Shāmi reads the names in the same way. (Folio 149 a, I. 15). 'Tungitar' is said to mean 'a night-guard, a man who repeats a prayer aloud when a prince is mounting.' (B. N. Tr. 464 n.). Zainu-d-din was the confidential agent of Timur himself and not of Prince Rustam.

III. 518, l. 11. The officers of the Exchequer had called for a contribution of 100,000 durusts of gold, each durust weighing two and a half miskals.

. N. II. 164, l. 21 ; صد هزار نـُرست زر هر يك بوزن دو مثقال و نيم

The Malfuzāt makes this "one lak of silver tankas, each tanka weighing two and a half Miskāls," (470 ante). As the Misqāl weighed between 70 and 72 grs., the Tanga and Durust must have both turned the scale at about 175 or 180 grs. One of the meanings of ذرست is 'coin of standard value' (Steingass) and the word is used in the Badishahnāma of 'Abdul Flamīd Lāhori (II. 396, II. 16, 18) for the Muhr, as well as the Rupee of full weight (q.v. my Historical Studies in Mughal Numismatics, 99). In the Kashmir chapter of the C. H. I. (III, 279), the money tribute demanded from Sultan Sikandar is put down as 'one hundred thousand golden dirhams', but this is not in accordance either with the Malfuzāt or the Zafarnāma, as the dirham did not weigh 2½ misgāls (about 180 grs.) but was a coin of which the ponderary value varied from about 45 to 55 grs. It was, generally, reckoned at about $\frac{7}{10}$ ths only of a misqāl. F. (II. 340, 1.7 f. f.) states that the tribute demanded was 'one hundred thousand 'Alai ashrafis' or gold Muhrs.

This place [the pool] is three Kos from III. 522, l. 10 from foot. Barūja.

in the Z. N. II. 182, l. 4, 'thirty Kos' not 'three.' The context shows that 'thirty' is correct. Timur was riding post haste and 'making all possible speed. In the *Malfuzāt*, he is said to have started from Barūja after noon-day prayers and reached the lake after about six hours, at evening prayer (477 ante), which also proves that the distance must have been much greater than "three Kos"

III. 522, l 8 from foot. The officers who had been appointed to guard the way from Naghaz to Bānū had built a bridge

Bābur writes — "Four roads lead from Kābul from the Hindustān side, one by rather a low pass through the Khaibar mountains, another by way of Bangash, another by way of Naghr (var Naghz) and another through Farmūl' (B N Tr 206). Naghz is also mentioned along with Farmūl by Abul Fazl in the Āin (Jarrett, Tr. II 399) The name is not found on modern maps but the place appears to have been situated on the Iryāb and was close to, if not identical with, Baghzan (or Bazghan), which is said to have been about 35 Kuroh south south-east of Kābul (Raverty, N. A 68) Hamilton (East India Gazetteer, Ed 1815, p. 618) says 'Nughz' is about 100 miles S E of Kābul in Lat 33°-17' N, Long. 69°-28' E See my Note on Vol II 147, l 9 f. f

III 524, l 5 from foot Mu'izzu d-din Kaikūbad, King by virtue of three descents

According to Elliot's rendering of this passage, Iltutmish was the grandfather of the grandmother of Mu'izzu-d-dīn Kaiqubād and Nāsiru-d-dīd Mahmūd was the father of his grandmother But the T A (35, 1.17 and 36, 14) and F, who quotes these very couplets, (I 71, 15 and 83, 14 f f), agree in stating that Balban was married to a daughter of Iltutmish and Nāsiru-d-dīn Mahmūd to a daughter of Balban Subsequently, a daughter of Nāsiru-d-dīn married Balban's son, Bughra Khān and she was the mother of Mu'izzu-d-dīn Kaiqūbād. Iltutmish must, therefore, have been the grandfather of Mu'izzu-d-dīn's mother (and not of his grandmother) and Nāsiru-d-dīn was the father of his mother and not of his grandmother See also B (I 89=Tr I. 126, 90, Tr I 129).

III 524, last line. Praise of the Masjid-i Jām'a and its lofty minaret built by Shamsu-d-dīn

Here, as well as in the Khazāin (ante 69), Khusrau speaks of the Masjid-i-Jāmi'a of Dehli and its lofty minaret (the Qutb) having been built by Iltutmish and a similar statement is made by Shams i-Sirāj (304, 16=353 ante). 'Awfi also avers that the Masjid-i-Jāmi'a, which he calls Masjid-i-Alfi or the 'Mosque of a Thousand Arches' was erected by that Sultan On the other hand, both these monuments are ascribed in the Futūhāt-i-Firūzshāhi to Mu'izzu-d-dīn Sām (383 ante), while Ibn Batūta associates them erroneously with the name of Mu'izzu-d-dīn Kaiqūbād (597 infi a) These asseverations are apparently conflicting, but they are not quite irreconcilable. The Masjid and the Pillar were both begun by Qutbu-d-dīn in or soon after 1193 A. C, when he was viceroy of Dehli under the Ghūri Sultan The first was considerably enlarged and the second really complet-

ed by Shamsu-d-dīn. In the inscriptions on the lowest band of the first storey of the Minār, Qutbu-d-dīn is referred to only as the Sipāhsālār (Commander-in-Chief) and there are eulogies also of his master and suzerain, Mu'izzu-d-dīn and of the latter's brother, Ghiyāṣu-d-dīn. But the work was only begun by him, and experts are not quite sure that even the first storey was quite finished at his death. The second, third and fourth storeys belong entirely to Iltutmish and each of them contains inscriptions which bear witness to the fact. (Sir J. Marshall in the C. H. I. III. 576-578; Thomas, C. P. K. D. 21-24, 79, 286 and note; Fanshawe, 256-64; T. W. Arnold in Houtsma, E. I., II. 1168).

III. 525, l. 6 from foot. His elephants occupied a breadth of three miles at Hapur.

The 'Aligarh text (52, couplets 5 and 6) reads 'Bahāpur' and this must be the correct lection. The error is due to the initial letter of the toponym having been misunderstood as the preposition 'ba'. The context requires all the places mentioned to be in the near neighbourhood of Dehli. This is true of Sīri, Indarpat and Tılpat, but it can scarcely be predicated of Hāpur, which is situated about thirty-three miles north-east of Dehli. It is now a station on the Dehli-Murādābād Railway and is shown in Constable, Pl. 27 C a. Bahāpur is mentioned more than once by Barani (134, 135 ante) and a village of that name seems to be even now extant. It is said to be about six Kos south of Shāhjahān's Dehli (Āṣār, I. 15; Cooper, Handbook for Dehli, 1863, p 92), that is, about a mile south of the Okhla Railway Station.

III. 527, l. 2. Bārbak Khān-i-Jahān [was sent against the Mughals].

His full name is given as Hizabr Khān, Malik Shāhak Lashkar Khān by Barani (126, l. 3). The leaders of the Dehli army are spoken of as Malik Bārbak Bektars and Khān-i-Jahān in the T. A. (51, l. 8), and F. (84, l. 2 f.f.). B., following the T. M. (53-54), states that Malik Shāhak Bārbak was given the title of Wazīr (Recte, Hizabr?) Khān at the accession of Mu'izzu-d-dīn and that of Khān-i-Jahān, when he was appointed commander of the expedition sent against the Mughals. (I. 157=Tr. I. 220). Amīr Khusrau also speaks of him as "Bārbak, the swordsman" (نَحُ خُونَ) and "Khān-i-Jahān Shāhak, the breaker of armies" (لَشَرُ حُونَ) (Text, 64, couplet 4). In the C. H. I. (III. 184), the commander of the army which was sent to repel the Mughal invasion is said to have been Malik Muḥammad Baq Baq, but this Malik Baq Baq was an entirely different person. See Barani, 126, l. 6, who mentions Malik Baq Baq and Malik Shāhak separately. This Malik Shāhak Khān-i-Jahān [or Azabr or Hizabr Khān] was put to death soon afterwards. (Barani, Text. 134, l. 5: T. M, 55-6).

III, 528, l. 8 from foot. The Jumna was crossed at Jewar.

Jewar is in Bulandshahr district on the route from Koil ('Alīgarh) to Dehli and 36 miles north-west of the former (Th.). It is now in the Khurja taliṣīl and lies 20 miles west of Khurja town. Lat 28°-7′ N., Long. 77°-34′ E. (I. G. XIV. 102). Constable, 27 C a. It is most probably the place. the

name of which has been (wrongly) read or written as 'Chitūr' at 346 ante III. 530, l 1 He sent Shamsu-d-dīn Dābū with a message inviting to peace.

Dabū (๑٠٤) is an error for 'Dabir' אָב', secretary He is called Shams-1-Dabīr in the Qurānu-s-S'adam. (Text, p 102, couplet 3). Barani also says that Shams-1-Dabīr was ordered by Nāsiru-d-dīn Bughrā Khān to bring pen and inkstand and write down the counsels which he gave to his son, the Sultan Mu'izzu-d-dīn (9ɔ̃, 1 4). Badāuni tells us that Balban made Shamsu-d-dīn secretary (๑٠٤) of the kingdom of Bengal, when it was assigned to his son Nāsiru-d-dīn Bughrā He also cites one of his Qaṣīdas, and adds that Amīr Khusrau has spoken in the highest terms of the virtues and excellences of Shamsu-d-dīn the Dabīr in the Preface to the Ghurratu-l-Kamāl and in the Epilogue to the Hasht-Bihisht. (I. 94=Tr I 134-135)

III 532, 1 12 The army encamped at Kautpur

The reading in the 'Aligarh text 18 کستور Kantpur and this is also the form found in Cowell's abstract translation in J A S B XXXIX (1860)

The right reading may be کستور Kantitpur, and the place meant Kantit, now in Mirzāpur, where there is a ford on the Ganges Sikandar Lody is said to have crossed the river here (Tārīkh 1-Khān Jahān Lody in E D V 94, 95, T A 162, 15, F 181, 1 13 ff, B I 316=Tr 416)

III 534, 1 13 Which bears the seal of the Tarkhan prince, Jani Beg, being, therefore, about one hundred and fifty years old

"One hundred and fifty" must be due to some error in calculation If Elliot means Jāni Beg Tarkhān—and he can hardly mean any one else—the manuscript must have been 250 years old and not 150 only, when Elliot wrote Jāni Beg died in 1009 A H=1600-1 A C (E D I 252, A. N Tr III. 1172 and Note, Āīn, Tr I. 363)

III. 538, 1 11 The rebel [Chhajū] took the road of Jūbāla

Read 'Chūpāla', i e Chaupla It was a Mahāl in Sarkār Budāun, Sūba Dehli (Aīn, Tr II 290) There was a ford here on the Rāmgangā (B II 154, Tr II 158=E Ď V 507) Elliot says (Races, II 137) that Rustam Khān Dakhani founded Rustamnagar in this place and that in the time of Farrukhsiyar, the name was changed to Murādābād According to the I G (XVII, 429), the name was given by Rustam Khān himself in honour of the Prince Murād Bakhsh Budāun, where Sultān Jalālu-d-dīn is said by Barani to have encamped, (138 ante) is about 50 miles south of Murādābād

III 538, l 3 from foot Victory over Alp Ghazi

This was not the personal name of the man but his title He is the theme of several panegyrics in Amīr Khusrau's second and third Divāns, the Wasatu-l-Hayāt and Ghurr atu-l-Kamāl He is there styled Alp Khān-i-Ghāzi and his father's name is given as Azhdar Malık (535) Barani gives his laqab as Malik Ikhtyāru-d-dīn (116, l. 4 from foot) Alp-i-Ghāzi appears to have been an old Turki title and Minhāj says it was borne by Malik

Nāṣiru-d-dīn, son of Qizil (or Qara) Arslān Saljūqi, nepliew of Sultan Ghiyāṣu-d-dīn and Sultan Mu'izzu-d-dīn-i-Sām. (T. N. 125, l. 2 f.f.; 121, l. 14; 50, l. 14; Raverty's Tr. 490). Alp or Alb is said to mean in Turki 'mau, hero, champion, brave'. Alp-ar, 'Brave man', is said to be the title by which Afrāsiāb is called in Turki and an Alp-ar Khān is mentioned by Juwaini. (Tārikh-i-Jehān-Kushā, Text, l. 92. Vide Sir E. D. Ross's Note to Ḥājji Dabīr, Z. W. III. Index, lv). See also Barthold, Turkestān. 412, 413.

'Baglāna' (last line), which is said to have been near the Ganges, is a miswriting of 'Pachlāna' ' (q. v. my note on Vol. IV. 50, l. 14).

III. 541, l. 12. Malik Khurram, 'Ariz-i-Mamālik, the Chief Karībak.

This "Karībak" must be an error for فيربك "Qīrbak." Malik Tājud-din-i-Qirbak is mentioned by Barani as one of the courtiers of Mu'izzud-din Kaiqubad (126, l. 10) and there is a Malik Qirbak in his list of the great officers of 'Alau-d-din Khalji (Ib. 241, 1, 8) as well as Ghiyasud-din Tughlaq. (424, 1.6). In another place, he speaks of a Malik Qirbak holding fourteen offices in the reign of Qutbu-d-din Mubarak (379, 1.12), but elsewhere he calls this great pluralist and dignitary ملك قرايك (396. 1. 2). In another passage again, he writes that Haibat Khān was the slave and Qarabeg (or Qirabeg) of Sultan Balban. (49, l. 19, 101 ante). In the Tārīkh-i-Mubārakshāhi also, it is stated that Sultan Jalālu-ddin Khalji appointed his brother's son 'Izzu-d-din Qarbeg-i-Maimana and Malik 'Iwaz Qarbeg-i-Maisara (Text, 62, 1.9; see also Ibid, 69, 1.3). It would seem that "Qīrbak", "Qarbeg", "Qarābeg" or "Qirābeg" were synonymous or interchangeable and that none of them was a personal name. It was the title or designation of some high military official, which existed down to the times of Firuz Tughlag as Malik Jalau-d-din Dudahti or Dūdahi is said to have been 'Qīrbak' in that reign. (Ib. 527, l. 3 f. f.). The word may be قوريك or قريك. 'Ali Tabâtabā, the author of the Burhān-i-Maāsir, says that "Alāu-d-din Ḥasan Shāh Bahmani appointed ". which Major قوريك ميمنه and Mir Saku قوربيك ميسره which Major King renders as "Commander of the Left Wing and of the Right Wing." (Trans. 6).

III. 542, l. 6 from foot. Malik Jandarbak · Ahmad.

"Jāndārbak" is the same as 'Sar Jāndār' 'Head of the Bodyguards or Lifeguards.' He is called 'Ahmad Sarjāndār' on the immediately preceding page. (541, l. 13). These Jāndār's are mentioned by Ibn Batūta in his description of Muḥammad Tughlaq's public audiences. "At the Sultān's back, stands the great Qabūla with a flywhisk in his hand to drive off the flies. A hundred armour-bearers stand on the right and a like number on the left, carrying shields and swords and bows." (Gibb, 199). These 'armour-bearers' are the 'Jāndārs'. Baihaqi explicitly states that 'Jāndār' signifies 'signifies' sword or scimitar-bearer'. (141, l. 14). Barani also speaks of Sarjāndār-i-Maimana and Sarjāndār-i-Maisara, Commanders of the Bodyguards standing on the Right and of those standing on the Left. (454, l. 7). The Jāndār's appear to have also carried out the

sentences of capital punishment and acted as executioners (Barthold, Turkestan. 228, 312 and note, 378) Just as 'Jāndārbak' means 'Chief Jāndār', so 'Shikārbak' signifies 'Chief Huntsman' Malik Dihlān who is spoken of as the *Mir-i-Shikār* of Firūz Tughlaq by Shams, (Text, E D 295) is called 'Shikārbak' by Barani (582, 11 2 and 10)

III 544, l 10 from foot 'Ashīka of Amīr Khusrū

The title is sometimes written also as 'Ishqīya' We learn from Abul Fazl that this 'Masnavi' was one of the favourite books of Akbar and was frequently read out to him "On many occasions", the historian writes in his account of the Emperor's journey by boat to Bengal, "Mīr Sharīf, the brother of Naqīb Khān, read with a beautiful voice the Kitāb-i-'Ishqīya and His Majesty emerged many a time from behind the veil and showed tender heartedness (أَوْتَ مِعْرِ مُودِدُ) and had melted eyelashes" (A N Tr III 125, Text III 88) Mr Beveridge was not able to identify correctly the poem referred to He thought it was "some special book having this title, a Kitāb-i-'Ishqī which is attributed to Aristotle, or the Diwān of the poet whose pen-name was 'Ishqī" There can be little doubt that the Kitāb i-'Ishqīya which the great emperor could not hear without shedding tears was this fine poem on the tragic loves of Davalrāni and Khizr Khān

III 545, l 2 Khusrū says (infra p 555) that her [Daval Rānī's] hands were cut off, while she was clinging to her husband's body and implies that she was left among the slain, though he says not so distinctly Ferishta asserts that she was taken into Qutbu-d-dīn's harem

There must be an error here I cannot find in the 'Alīgarh lithograph of the 'Ashīqa any such statement about the severance of Davalrāni's hands during the struggle between Khizr Khān and his assassins. Neither F nor B says a word pointing to any such mutilation. Both assert that she was forced to enter Qutbu-d-dīn's harem, but this carries with it the implication that she was neither "left among the slain," nor mangled in the hideous manner alleged. It is also extremely improbable that the myrmidons who were sent by the fratricide with a view to gain possession of her person, should have been guilty of such barbarity and violence. The only couplet in which there is any reference to "the cutting off of hands" is thus worded. After describing the decapitation of Khizr Khān and bewailing the event in a long interlude, Khusrau exclaims

بریده دست آن بی مهر حوریر - که رد برگردن او حمص تیر

(p 230, verse 9) "May the hands of the cruel and blood-thirsty one who struck off his [Khizr Khān's] neck with the sharp dagger, be cut off!"

111. 545, 1 4 Firshta asserts that she [Davalrāni] was taken after Kutbu-d din's death by the villain, Khusrū Khān Barani who was intimately acquainted with the facts is silent upon the subject, so that it may be hoped that the high-born damsel escaped that union with the 'foul Parwari', which would have been worse than death

Firishta does not say any such thing at all either in the Bombay Text or Campore Lithograph. (I. 130, l. 16). The statement is only one of the many unwarranted and misleading interpolations in the Translation of Briggs, (I. 396). All that he, Barani, Nizāmu-d-dīn and Budāuni state is that Khusrau married "a wife" (زنى or زنى) or "most honoured wife " (حرم محترم) of Qutbu-d-din and that Sultan Tughlag afterwards severely punished the individuals who had taken active part in or abetted the illegal Nikāh or ceremony of marriage. But we know that Qutbu-d-dîn had several wives and neither F. nor any other author declares that the wife of Qutbu-d-din with whom Khusrau went through the ceremony of a marriage was Davalrāni or Devaldevi. It is not unlikely that she was, as he asserts, forcibly taken into Qutbu-d-din's harem (I. 125, l. 12 from foot), after Khizr Khān's assassination, but Amir Khusrau, the only contemporary writer who mentions Devaldevi, says nothing at all of her subsequent fate and there does not seem to be any warrant for indulging in these melancholy speculations and imaginings about her union with the "foul Parwari." Dowson is merely repeating the words of Thomas (C. P. K. D. 177 note), but that author's lamentations on her "after fate" of becoming "the enforced wife of two succeeding Sultans" and his sentimental surmises about "her proud Raiput blood having risen against her union with the foul Pariah" have more of the glamour of romance than of the dry light of history. Their only foundation is a strained and arbitrary interpretation and amplification of Firishta's words. In our own times. Sir Wolselev Haig has echoed these imaginary 'hopes and fears' and inveighed against 'the foul outcaste, her third husband' (C. H. I., III. 124). but both these averments are more than doubtful. There is very little to show that Khusrau was an "outcaste" and nothing at all to prove that he was her "third husband."

The real name of the tribe or easte to which Khusrau belonged is not known and cannot be ascertained. The variants in the Mss, have served only to mystify and mislead European writers. The form 'Parwāri'is, in reality, only a modern perversion. Dowson notes that the name is written Barwār [and Barwārān in the plural] in the B. I. Text and Barāv [or Barāwān] in his own Mss. of Barani. But Barāwān is found in the B. I. Text also. (490, 1.5; 519, 1.2). The T. M. has Barāv. (Text, 85, 1.6 f.f.). Hājji Dabīr spells it as Rāv and Budāuni has Barwār (B. I. Text. I. 212) but Barāv is found in the Mss. (Tr. I. 285, 288 Note). Parwār is found only in the T. A. and it is asserted there by way of gloss, that it is the name of a tribe resembling the Khidmatīyā of his own day, who were employed as guards or Chaukidārs of the palace by Akbar. (87, 1.16).

Guided or rather misguided by this spelling and the accompanying gloss, Briggs jumped to the conclusion that this 'Parwār' must be the same as 'Parwāri' and Edward Thomas, following his lead, fastened upon it the meaning assigned to 'Parwāri' in Molesworth's Marāṭhi Dictionary.

It is defined there as "an individual of low caste," and said to be synonymous with 'Dhed' or 'Mahār', the first [Parwāri] being "a courteous or conciliating term, the second a term of reviling and the third a mere appellative without implication". (C. PK D 184 Note). But it is impossible to subscribe to this opinion for several reasons

- 1 The name is not written "Parwāri" or even "Parwār' except by Nizāmu-d-dīn and his copyist Firishta Nizāmu-d-dīn was born and educated in Herāt. He was not well acquainted with any Indian vernacular and his opinion on a question relating to the intricate and obscure nomenclature of Hindu tribes and castes is of absolutely no value
- 2 Khusrau is stated to have himself come originally from Gujarāt, his family and relations to have resided in Bahlāwal or Nahrwāla (Barani, Text, 402, 16) and his followers are said to have fled to Gujarāt after their defeat (Ibid, 412, 12) There are no 'Mahārs' in that part of the country and the 'Dheds' are not known as and never called 'Parwāris' by the people of the province The Gujarāti dictionaries do not recognise it as a synonym of either 'Mahār' or 'Dhed' and the meaning assigned to it in the well-known 'Jodnīkosh', compiled by Mr D B Kālelkar and published by the Gujarāt Vidyāpith, is "a caste or tribe like the Bharvāds or shepherds." In the circumstances, the invocation of the authority of Molesworth on the meaning of a Gujarāti word seems out of place
- 3 Barani states that as soon as Khusrau's half-brother Hisām [or Husām] took charge of the governorship of Gujarāt, he gathered around himself his relatives and kindred and "all the renowned Barwārs of Gujarāt" (عرفان المراف ا
- 4 Firishta has copied Barani's statement and adds that Khusrau spent all his resources in mounting and equipping an army of forty thousand troopers (I 127, l 1) and Sir Wolseley Haig assures us that this "corps of forty thousand horse was largely composed of and exclusively commanded by members of his own despised tribe" (C H I III 123) It may be left to the reader's imagination to visualise the spectacle of 40,000 hastily-recruited *Dheds*, mounted and armed for the first time in their lives with swords instead of broomsticks, performing cavalry exercises and taking the word of command from Mahār captains and Bhangi colonels
- 5 In his account of Taghi's insurrection in Gujarāt, Barani states that in the battle near Kadi-Pātan, about one hundred of the rebels made a furious charge with naked swords on Sultān Muḥammad Tughlaq's own

bodyguard, like Barāwān Fidāi's, [heroes, braves, or paladins], who had taken their lives on the palms of their hands. (519, 1.2) بر طریق ندائیان (Surely, these 'Barāvān' or 'Barāv' Paladins could not have been the 'foul outcastes' whose "touch is pollution to a Hindu, whose occupation is that of scavengers and whose food consists largely of carrion"!

- 6. There is no doubt that Khusrau was able to effect a Hindu revolution, to seat himself on the throne and to command all the resources of the kingdom of Dehli for more than four months. He could have hardly done this even for a day without the support and co-operation of the temporal and spiritual leaders of the Hindu community or without having, at his back, an army composed, not of Dheds and Mahārs, but of the martial races of the empire. The idea of high-caste men paying homage to and acknowledging a Bhangi as Emperor of Dehli is simply unthinkable.
- 7. Indeed, Ibn Baiūtā states that "Khusrū Khān gathered a troop of Indians chosen from among the bravest and greatest; his brother, the Khān-i-Khānān was among them." (604 infra; Defrémery. III. 198). He, as well as the T. M. (Text, 91, I. 12) and B. (I. 220, Tr. 294), agree in declaring that his followers "fought with the greatest fury, defeated Tughlik's troops and pillaged his camp." Tughlaq, in fact, was able to retrieve the day only because he attacked Khusrau with a division which he had kept in reserve "just when his enemies were busy plundering and scattered, so that none remained near Khusrū." We may be sure that the men who routed Tughlaq's veterans were not the "forty thousand Mahārs" officered by "men of their own despised tribe." They may or may not have been "members of some of the many royal races" of this country, but they must have been certainly "men of good stock," and not 'outcastes' and 'scavengers'.

The uncertainty of the Semitic script makes it impossible to determine now the true reading of the caste-name. It has been suggested that may be an error for club, [Puār, Paramār], but this is a bare possibility and nothing can be built upon such an unsupported conjecture. But it may be safely said that the Parwāri theory is untenable and must be abandoned.

III. 546, l. 10 from foot. And took from him fourteen hundred elephants. The number of elephants is certainly overstated by the poet. The number given in manuscripts of the contemporary $T\tilde{a}ju$ -l-Maāṣir is one hundred or three hundred (E. D. II. 223), and Ibn-al-Athīr makes it only ninety. (Ib. 251). Fakhru-d-dīn Mubārakshāh, another contemporary authority, also puts it at one hundred. ($T\tilde{a}r\tilde{\imath}kh$, Ed. Ross, 23). But it is stated by Ibn-al-Athīr (E. D. II. 251) that Jayachand's treasure was so vast that 1400 camels were required to carry it. Perhaps the poet's memory has played him a trick and he has mixed up the number of the camels which carried the treasure with that of the elephants captured.

III. 548, l. 21 The two Turk Khāns were suddenly captured by a Hindu servant of the Court

The 'Hindu servant' was Malik Nāyak Ākhurbak, who commanded the Dehli army on this occasion (Khazāin, Tr 72 ante, Barani, 320,112, TA 8, 1.12). F is most probably wrong in stating (I 114,19ff) that the Dehli generals were Malik Nāib and Ghāzi Malik Tughlaq, though he is followed in the CHI. (III 110) The fact that this Malik Ākhurbak is styled Nāyak may indicate his Hindu descent or parentage

III. 548, l 6 from foot One [of the Mughal leaders] was I thu

The name is written $T\bar{a}b\bar{u}$ (var $T\bar{i}b\bar{u}$) in the 'Aligarh text, p 62, verses 1, 4 and 9 The paranomasia on \bar{b} and \bar{b} leaves no room for doubt as to the third letter being a 'be' and not a 'hā' See my note on Vol III 74, 1 1 ' $T\bar{i}h\bar{u}$ ' is, pelhaps, only a typographical error for ' $T\bar{i}b\bar{u}$ '.

III 550, l 7 from foot There was another Rāi in those parts [M'abai], whose rule extended over sea and land, a Brahmin, named Pandyā Gurū

The reading in the 'Aligarh text is very different and the word 'Guru' does not occur anywhere in it

بر آب و خاك فرمان تهامش ـ برهبی بیر تبدیا كرده بامش سی شهرش محشكی و بری هم ـ پش خوش كرده مهر هت پوری هم پتن را ساحة مبرل كهٔ خویش ـ بت و بتجا به در مهرهت پوری بیش

"On land and sea, he had full authority and he was a Brahman named Bîr Pandyā He had many cities on dry land as well as in the sea, and he had specially chosen Pattan and Mahrhatpuri [Madura] He had made Pattān his place of residence and the idols and temples were in Mahrhatpuri.' Elliot's Manuscript must have wrongly read of instead of in the first couplet. Sir Henry's translation is responsible for putting Dr Ayyangar on a false scent and tempting him to hazard conjectural identifications of this 'Pandyā Gurū' with some "other Pāndyan prince," or with "the Mahant or chief priest of the temple of Rāmeshwaram'' (S I M I 100 and note)

III 551, l 3 from foot. Rāi Karan . .fled to seek the protection of Sankh Deo, the son of the Rāi-Rāyān, Rām

The names of the two sons of Rāma Deva are given by Sir W Haig (C H. I III 113) and other authors, as Shankar and Bhīm. This is due to their having followed Briggs' translation of F, who calls them 'Shankal Dew' and 'Bheem Dew' (I 367), but in the 'Alīgarh text of the poem which is stated to have been prepared after collation with several Manuscripts, the elder brother is spoken of as 'Singhan Dev'

p. 85, verse 10 چوں سنگہی دیو پور رای رایاں - شد آگاہ ر آگاہی سرایاں And again,

ماه مرا مهد مدد ريرح خويش آن ماه را مهد p 86, verse 1. And Singhan's younger brother is not called Bhimdev, but Bhilam Dev.

by the poet.

برادر را که بهیلم بود نامش ـ بخوا ند و کرد حمّال پیامش بیامش بیامش برادر را که بهیلم دیو چون باد ـ بهمان راز مهمانی برون داد p. 86, verses 2-3.

Note that the metre also requires A: and the lines cannot be scanned if we read ref. There can be little doubt that Shankar, Shankal, Sankh and Bheem or Bhīm are all wrong and that the princes should be called 'Singhana' and 'Bhillama'. A reference to the Dynastic list of the Yādavas of Devagiri shows that one of the most distinguished and capable rulers of the family was named Singhana. He conquered almost the whole of the kingdom of his predecessors,—the Western Chalukyas—and reigned from 1210 to 1247 A. C. (Duff, 176, 191, 310). And it appears from the pedigree of their kinsmen and predecessors, the Yādavas of Seunadesha that Bhillama was a favourite name among them also and was borne by not less than five kings of that house. (Ibid., 310). In fact, Bhillama V of Seunadesha was the same as Bhillama I of Devagiri who founded the later dynasty about 1189 A. C. and was the fifth ancestor of Rāmadeva. (Ibid. 165; E. H. I. 392-93; see also I. G. XI, 200).

On. l. 17, 'Ulugh Khān 'is an error for 'Alf' or 'Alp' Khān. Ulugh Khān had died several years before.

III. 553, l. 16. The marriage of Khizr Khan with Dewal Rani.

Khusrau says that the younger daughter Daval Rani was only six months old when her mother Kauladevi was captured and sent to Dehli in 1298 A. C. دوم را عبرشش مه بود رفة که بود آن شش مههه ماه دو هفته Ashīga. 82, l. 13). He also states that she was eight years old when captured. (Text, 93, verse 5=552 infra). It is said in the C. H. I. (III. 113) that the marriage took place in the summer of 1307 A. C., that is, about Zi-l-q'ad 706 A. H., but there must be some error, as Devaldevi would have then been only a child of about ten and it would be absurd to ascribe to her at that age the sentiments which the poet puts into her mouth. The fact is that Devaldevi was married to Khizr Khān some months after his union with Alp Khān's daughter in Ramazān 711 H. and this stands out clearly even from Elliot's summary. Sir Henry does not mention the exact day or month on which the Vagheli beauty was married to Khizr Khan, because the actual date is not specifically recorded in the original poem, but the ceremony must have been performed after 1st Zi-l-hijja 711 A. H.=9th April 1312 ('Ashiga, 161, 167, 216) when she was about fourteen years old. The date 1307 A.C. (706 A. H.) is given by Khusrau and Firishta as the year of Kāfūr's first expedition to the Dekkan. Devaldevi was captured, F. says. towards the end of that year (I. 116-117), but he does not state anywhere that she was married to Khizr Khan in that year. The year of her capture would seem to have been confused with that of her nuptials.

III. 554, l. 1. When the Sultan recovered, Khizr Khān set out on his expedition to Hatānpur.

The place is called متنا :ور Hatnāpur, in the 'Alīgarh text. (236, verse

1) B. calls it 'Hatnipur' or 'Hastniwar.' (I. 107, Tr. I, 266 and Note) Ibn Bututa says—that Khizi Khan went to Sendapit, one day's journey from Dehli (E. D. III, 601), which may be Sonpat, 23 miles north of Dehli and 27 miles—routh—of—Panipet. Hatanpur—or Hatnapur—mit be meant for Hastinapur, which lies in the Mawana tahul of Mirat district, 22 miles north east of Mirat, on the right bend of the Buddi Ganga or Old bed of the Ganges. If stinipur—o epolen of as Hatni in the Mujmalute Town of the (E. D. I. 105). The name is written as 'Hatniwar' in the Iin (Tr. III. 70), but elsewhere it is spelt as Hestinipar—(Ibid. II. 258).

III 555, 1.7 from foot Khi r khan then ordered a confidential servant to place me near the narrative of his love

This paragraph has been misplaced on I dislocated from its context in this translation. It is about to acribe to or put into the months of Khar Khan and such order after the description of the monders of himself and his brothers and the record of the inhumation of their lifeless bodies. The passage really occurs towards the beginning of the poem in the chapter entitled and requested him to write a poem on the story of his loves and gave him and requested him to write a poem on the story of his loves and gave him a love or 'A Tale of Woe,' which was written not in Persian, but in Hindi. (p. 41, verses 9-15). This reference to the vernacular tongue gives him an opportunity for introducing the disquisition on the beauties of the language of the indigenes which follows here on p. 556. It also has been wrested out of its real position and pite iforked at the end of the story, though it is really a part of the Introduction or Prologue

The fact is that the description of the murder is the Supplement or Epilogue of the Love-Story and the 319 lines constituting it were composed after the completion of the original poem or Love Story itself in Zi-l-q'ad 715 II (p. 307, verses 1-3) As Khusrau states that he took four months and some days to compose this Masnaci, his interview with the prince must be dated in Jamidi II 715 II, when 'Aliu d-din was still alive. As Khizr Khin was murdered in 718 II, the Epilogue describing that tragic event must have been written about three years after the completion of the original poem

III 556, l 9 The prevalent languages of Rai and Ram

The 'Aligarh text has the better readings, which are "Rai" and "Rūm" ورعال راب المناور p 42, verse 2 The comparison is between Hinds, the mother tongue of the indigences, and Persian and Turk, the languages spoken in Rai and Rūm, the native lands of the rulers The rhyme also leaves no doubt that the right reading is Rūm Rai was the capital of the Medes and one of the most ancient cities on earth. It was said to have been the birth-place of Zoroaster's mother and was for long the chief seat of the Zoroastrian hierarchy. It was situated on, what has been for ages, the chief highway in Asia between the East and West, and its ruins he about ten miles south-east of Teherān. The Arab geographers speak of it as 'the mother of cities'

it is mentioned here as the archetype of the culture and civilization of Persia. Read $R\bar{u}m$ for $R\bar{a}m$ on 1. 3, p. 557 also.

III. 556, l. 4 from foot. He who has placed only guavas and quinces in his throat will.....say it is like jujube.

The words in the Text are [1, 43, verse 6], which mean pears and quinces. There are very good grounds for holding that the guava is an exotic fruit which was introduced into India only by or after the advent of, the Portuguese. There is also no doubt that the word itself is derived from the indigenous name of the fruit in the language of Guiana. Sir George Watt states that is the common pear, Pyrus Communis; is the apple, Pyrus Malus; and is the quince, Cydonia Vulgaris. (Commercial Products of India, p. 910). In the list of fruits given by Abul Fazl in the Ain, the lace of India among the "fruits of Tūrān". Blochmann in his Translation substitutes 'guava' (Tr. I. 65), but there can be little doubt that this is an inadvertent error, "a careless rendering of an ambiguous word", as Yule puts it. (H. J.s. v. Guava).

III. 557, l. 5 from foot. The accession of Kutbu-d-din Mubarak on Sunday, the 24th of Muharram 716 H.

Khusrau gives Sunday, 24th Muḥarram 716 H., as the date of Qutbuddin's accession. It was Sunday, 18th April 1316, according to the Indian Ephemeris. F. (I. 124, l. 13) gives 8th Muḥarram 717 which must be wrong. The C. H. I. gives 1st April 1316 (p. 291). Sir Wolseley has followed F. and taken the date as 7th (or 8th) Muḥarram, but the year as 716 H. 1st 'April 1316 was a Thursday, not a Sunday.

III. 561, l. 15 from foot. By sending the canopy (dūrbāsh).

The Durbash was not a 'canopy' but "a staff, club, mace, bludgeon, pole or baton with which they keep the mob from pressing too close in public solemnities." It literally means 'Have a care! Stand back! Begone! Give way! Keep at a distance!' So says Richardson in his Dictionary. The Ghiyagu-l-Lughat describes it as a double spear, a spear with two horns or branches which was used in ancient times for keeping the people at a distance during royal marches and processions. Manucci tells us that when the Begam Saheb (Shah Jahan's daughter, Jahan Ara) and other great ladies left their palaces, "they were escorted by cavalry and infantry and eunuchs who pushed on one side every one they found in front of them.....The men servants held sticks of gold or silver in their hands and called out, 'Out of the way! Out of the way!' "(Storia, I. 220). These men were in fact the 'gurzbardars' (mace-bearers) of Bernier and Tavernier. Barani states that the Durbāsh was borne by the servants of great men on the shoulders when their masters went out (136, 1, 4) and the T.M. speaks of it as a two-branched ornamented baton.

III. 563, l. 6 from foot. They can tell the future by the breath of their nostrils.

This is a reference to the Swara- $vidy\bar{a}$, a most curious method of divination which is mentioned only in Hindu literature, and seems to be

unknown elsewhere Abul Fazl describes it as "the extraordinary science of predicting events by observing the manner in which the breath issues from the nostrils." His disquisition on the subject extends to six pages in Jarrett's translation (Ain, Tr III. 232-237). There is a reference to it also in the Travels of the Italian, Pietro della Valle, who appears to have been greatly impressed by what he learnt about it "The Indian Gioghis", he writes, "have a curious way of divining by the breathing of a man, wherein they have indeed many curious and subtle observations, which I, upon trial, have found true." He informs his readers that "they have a book on the arts of divination, entitled 'Damerdbigiaska'", and that he hoped one day " to gratify the curious reader with a sight of it in a translation" (Travels, Ed. Gray, I 108, Old English Translation of 1665, pp. 55-56) His editor, Mr Gray, admits his mability to say what Damerdbigiaska' stands for and the name, as printed, is certainly corrupt I venture to suggest that it may be a muddle or perversion of 'Sāmudrikashāstra', the general designation in Sanskrit of the pseudosciences of Physiognomy, Palmistry, Auguries from birds and beasts, the breathing of a man and other modes of vaticination

III 564, l 26. The hellites who had accompanied him [Harpāladeva] also afforded food to the flames of the infernal regions

The mention of this custom by Amīr Khusrau is worth noting and confirms what is said about it by Sulaimān, Mas'ūdi and other old writers (See my note on E D I 9) This immolation of male servants and dependants appears to have taken place even after the fourteenth century and there is a reference to it in the Travels of Duarte Barbosa (c 1516). He observes that when the King of Narsynga (Vijayanagar) dies, four or five hundred women "throw themselves into the fire and many men who are his intimates are also burnt with him" (Tr. Dames, I 216-7) A still later example is recorded in the Maūstru-l-Umarā, the author of which notes that when the news of the death of Rājā Rāmdās Kachhwah in the Bangash province was received at Rangata near Agra in 1022 A.H., fifteen wives and twenty followers burnt themselves in the fire along with his turban (II:'156-7)

III 565, 1 5 He [Anangapāla] fixed a bell by the side of the two lions, in order that those who sought justice might strike it

The Bell of Justice is an institution associated with the name of the Sāsānian emperor Khusrau Anūshīrvān The Arab traveller, Sulaimān, says that it was a custom in China for every governor to sleep with a bell at his head, communicating with a handle at the gate, which any one claiming justice was at liberty to ring The statement is copied by Idrīsi (See Yule's Cathay, Ed 1866, p cvi) The Mughal emperors Hūmāyūn (Akbarnāma, I 361—Tr I 651), Jahāngīr (Tūzuk, Tr I 7) and Muhammad Shāh (Siyaru-l-Mutāakhirīn, Tr Reprint, I. 230) are all said to have imitated the practice Khusrau refers to the tradition that Anangapāla had revived the Persian custom Ibn Batūta makes the identi-

cal statement about Iltutmish (591 infra) and he also speaks of the lionstatues. Both legends are, probably, apocryptial, but this is just the sort of thing that makes a strong appeal to the Oriental imagination. Amīr Khusrau's fable of a famished crow ringing the bell and appearing as a complainant is found in different forms in the folklore of many lands. In a variant which is associated with Naushirvan's Bell of Justice, the suppliant is a donkey. (Siyāsatnāma, Ch. V. Ed. Schefer, 35-37; Bomb. Lith. Pt. i. 42-4; 'Awfi, Jawam'iu-l-Hikayat, I. vi. No. 390, J. H. p. 154). In the Gesta Romanorum, the animal which rings the Bell of Justice set up by the Roman emperor Theodosius, is a serpent which had been driven out of its hole by a toad. (Tale CV, Tr. Swan, II. 80; Bohu's Edit., p. 182). In another analogue, the redress is sought by jackals suffering from the winter's cold and the king is, according to Manucci's version, the Mughal emperor Jahangir (Storia, 1. 164), but in Tod's Rajasthan, the same story is told of Rāwal Lakhan Sen, a simpleton who sat on the throne of Jaisalmer from 1271 to 1275 A. C. (Ed. Crooke, II. 1210).

III. 584, last line. Each of them amassed a treasure amounting to seventy babins.

Dowson tells us that this babin must be 'Banbi', which in Hindi signifies 'a snake's hole' and in Hindu belief "snakes keep guard over hidden treasure." But it is not necessary to go so far afield for the real form or meaning of the word, which should be read as :: Baiin (also written Wain). i.e. tank, cistern. The Gujarāti form is Wav, the Hindi Bao and Baoli and all these forms are derived from the Sanskrit Wapi, i. e. a well, stepwell etc. This author has just told us that the Hindus are "accustomed to dig pits for the reception of their hoards and some of them form an excavation in their houses like a cistern for that purpose." This 'Babin', Recte 'Baiin', is that very pit or cistern. Indeed, his own definition of it as "a large cistern, into which there is a descent by a ladder on each of the four sides," leaves no doubt that what he means is not a 'snake's hole' but a tank or stepwell. Dimishqi's contemporary, Ibn Batūta, also writes thus: "Here there was a bain, which, in their language, means a very broad well with a stone easing and steps by which you go down to reach the water." (Gibb, 218; Defrémery, IV. 13). And the emperor Babur informs us that he "directed a large Wain to be constructed, ten gaz by ten. In the language of Hindustan, they denominate a large well having a staircase down it, Wain." (Memoirs, Tr. Erskine, 342). There is an earlier description in Alberuni's India also, which is, unfortunately, too long to quote. (Tr. II. 144). Ibn Batūta tells us that Ghiyāsu-d-dīn Tughlaq I had constructed in Tughlaqabid such a tank (or Bain) and had molten gold poured into it, which became a solid mass and was afterwards dissipated by his son Muhammad. (Defrémery, III. 214). 'Abdur-Razzāq also informs us that in the Treasury of the King of Vijayanagar, there are chambers with excavations in them, filled with molten gold, forming one mass. (E. D. IV. 109). These tanks or excavations must be the Baiins of Its

Batūta and the Babins of Dimishqi.

III 586, l. 4 But [Ibn Batūta] subsequently fell into disgrace for having visited an obnovious Shaikh

Ibn Batuta tells us that the name of the obnoxious Shaikh for visiting whom he unwittingly incurred the displeasure of the Sultan was Shihabu-d-din The Shnikh's offence, according to him, was that he had refused to take office under Muhammad and lived for years in an underground dwelling which he had constructed for himself near Dehli On being summoned again to court, he openly branded Muhammad Shah as a tyrant and when he refused to retract his statement, he was executed. (Gibb, 362 Notes, Defrémery, III 293-8) It is worth noting that the T. M (Text, 116, 1 5) and Budauni tell a very similar anecdote about the Shaikhzāda-i-Jām B has copied it from the T M and tells it thus "They say, that one day Sultan Muhammad came on foot into the Court of Justice of Qazi Kamalu-d-din, Sidr-i Jahan, and said, 'the Shaikhzada-i-Jam has called me a tyrant Scud for him that he may substantiate his charge of tyranny against me'. When the Shaikhzāda was summoned, he confessed to having said it and on being asked for the reasons, pointed to the Sultan's practice of "handing over to the executioners the wives and children" of offenders. The Sultan remained silent at the time, but ordered him soon afterwards to be bound and sent to Daulatābād in an iron cage He was afterwards brought back to Dehli and cut into two pieces in the Sultan's piesence". (Ranking, Tr I. 318, Text, I 239-40) There can be little doubt of the identity of the two stories and of the two men. This Shaikhzada-i-Jam is mentioned by Barani and he is said to have been hostile to the Saint Nizāmu d dīn Auliyā, whom Muhammad Tughlag held in the deepest reverence. It is also stated that he had been set up as a rival against Nizāmu-d-dīn by Quibu-d-dīn Mubarak (396, 17 f f). He was a descendant probably of the Saint, Shaikh Ahmad of Jam or Zam, a town in Quhistan, which hes about 96 miles S E. of Meshhed (L E C 356)

III 587, l 5 from foot The foot post is thus arranged Each mile is divided into three equal parts called dawsh, which signifies one-third of a mile

Ibn Batūta seems to have misunderstood the matter The Indian word 'D[h]āwa' does not mean "one-third of a mile" but 'runner' Barani tells us that in Sultān 'Alāu-d-dīn's time, and are runners, were posted at every half or quarter-mile (203 ante=Text, 331, 11) At page 244 again, he states that when famine prevailed in Mālwā, the posts [Dhāwa] had gone off the road (Text, 481, last line) This word 'Dhāwa' is used in the same sense in two other passages (Text, 330, 1.18 and 447, last line). Budāuni informs us that Muhammad Tughlaq "posted a chain of 'dhāwa,' that is to say, Pāiks or runners, as guards at distances of one Kuroh along the whole road from Dehli to Deogir' (Text, I. 226, Tr 302). Wassāf also declares that foot-soldiers (otherwise, pāiks) are called in the lan-

guage of the people of India 'dakk', [dhavak?]. (43 ante). 'Dhava' is the Marāthi form of the Sanskrit Dhāvaka, runner, from Dhāva, to run. I have suggested elsewhere that the Anglo-Indian "Dawk" may be derived from the same source. (See my " Notes on Hobson-Jobson " in Ind. Ant. LVIII, 1929, s. v. Dawk).

Ibn Batūta's error may have been due to his ignorance of the Indian in Arabic, De Goeje tells دعوه in Arabic, De Goeje tells us, is 'the distance at which the human voice can be heard.' (Ed. Khurdādbih, Text, 188, l, 11 and Notes, p. 211). This may be about one-third of a mile. It would seem as if the Moor had confounded the Arabic D'awa with the Marathi Dhava.

III. 587, l. 3 from foot The wall which surrounds Dehli is eleven cubits thick.

Yule complains (Cathay, Ed. Cordier, IV, 46) that the dimensions which Ibn Batuta gives of the Qutb Minar are absurdly exaggerated, but there is no over-statement here. Sir John Marshall bears witness to his accuracy and says that the fortifications of Jahanpanah are some twelve yards in thickness. (Monuments of Muslim India in the C. H. I. III. 587). The word which has been rendered as "Cubit" must therefore have been used for the Indian 'Gaz' or 'Yard'.

III. 588, l. 13. The people known by the name of Samirah do not eat with any one, and no one must look at them when they eat.

The reason was, most probably, the superstitious dread of the 'evil eye' of the 'liver-eater' or جگر خواد, q. v. E. D. I. 331 and my note. The author of the Maasiru-l-Umara says that this جكر خواد is also called Dāin. This is the Hindi form of the Sanskrit Dākinī, and the Gujarāti ين Dākan. (III. 313, 1. 3). The Sāmirah are of course the Sumras, but Ibn Batūta has mixed them up with and used the term also for their rivals,

III. 590, l. 15. The city of Dehli was conquered.....in 584 (1184 A. D.). $^{\sharp}I$ read the same date inscribed upon the mihrab of the great mosque of the city.

The exact date of the conquest of Dehli has been the subject of dispute for more than seventy years and is still a moot point. Indeed, two divergent dates, 1191 and 1193 A. C., have been sponsored very recently by Sir Wolseley Haig and Sir John Marshall within the covers of one and the same volume of the Cambridge History of India. (III. 42 and 575). But whichever of them, whether 587 H. or 589 H., is correct, it is certain that Ibn Batūta's 584 H. is wrong and impossible. Ibn Batūta must have read the inscription incorrectly from a distance and supposed the units figure to be ربع instead of سبع or سبخ. (C. P. K. D. 22-23 Note).

III. 597, l. 14 from foot. It was this prince [Mu'izzu-d-din Kaiqūbad] who built the minaret of the Northern Court of the great mosque at Dehli which has no equal in the world.

Here again, two similarly sounding names have misled the Moor The Minarctis, of course, the Quth, but Ibn Batūta has confused Mu'i//u-d-dīn Kaiqūbād and Mu'izzu-d-dīn Muhammad-i-Sām, whose viceroy, Quthu-d-dīn Aibak began and erected the first storey of the great Tower (Futūbāt, 383 infi a) Sir John Maishall (C II I III. 578 note) observe, that "two short Nāgari iecords of 1199 A D carved on the basement storey indicate that the Mināi was founded in or before that year"

III 598, 1 4 One of his neighbour s sent him [Mu'izzu-d-din] some food to appease his hunger, etc

A somewhat similar tale is found in the T M (59, 1 10) and is copied by B Mu'izzu-d-din is said to have died in captivity of hunger and thust It is further stated that the Sultan composed in prison a quatrain of which the last two lines are thus rendered by Ranking "My ego which used to see the gold of the mine and the invisible jewel, Today, alas! is blinded for lack of bread " (Tr I 228, Text, I 165) The anecdote and the verses also are most probably apocryphal Mu'127u-d-din is said by Barani as well as Ibn Batuta and the other chromelers to have been in the last stage of paralysis, for some time before his death. His excesses of all sorts had reduced him to a state of mental and physical imbeglity and his composition of a Ruba'i in such circumstances is unthinkable. The quatrain 'shricks forgery aloud', but it is interesting to note that the popular lumour which Ibn Batuta picked up in the 14th century was still circulating and wellremembered when Yahya bin Ahmad compiled his chronicle in the middle of the 15th. The story derives no additional title to credit because Ibn Batuta tells us that he had heard it from an "eye-witness of the fact" We may perhaps vouch for Ibn Batūta and postulate that he is not romancing, but who will vouch for his 'eye-witness'?

III. 598, l 10 He [Sultan Jal du-d-din Firuz Khalji] built the palace

If Ibn Batūta is referring to the palace which is styled 'Kūshk-i-Firūz (or Firūzi)' by the Dehli chroniclers, and called 'Blue Palace' in Dowson's translation, it may be said with confidence that the Tangici ine is again in error The Kūshk-i-Firūzi is said by Minhūj to have been the royal residence in the reign of Raziyya (Text, 185, 1-18, E-D II 333) It is also contain that it was in the occupation of Nāsiru-d-dīn Mahmūd as well as Balban (Ib 197, 1, 20, 208, 1-13, E-D II 342, 346). There was also a Kūshk-i-Sabz, (E-D II 345, 382), a Kūshk-i-L'al (Barani, 178, 1-6) and a Kushk i-Sufīd (E-D. II 306, 338, 340, 342).

III. 598, l. 13 from foot Deogir which is also called the country of Kataka

"Ibn Batuta's memory for strange names", remarks Mr Gibb, "was never of the best" (p 368) And Yule also observes that this Moorish traveller frequently "errs in regard to proper names and sometimes even confounds them in a most perplexing manner" (Cathay, IV 45) 'Kataka' appears to be a mistake for some such name as 'Karņātāka' or a mis-

writing of 'Kannakara' (). In the very next sentence, he avers that "Deogīr is the capital of Mālwa and of Marhata." The mention of Mālwa in this connection, also engenders suspicion, though the statement may be founded on the fact that before 1344 A. C., in which year Muḥammad Tughlaq reconstituted the administration of the southern part of his empire, Mālwa and the Dekkan provinces were under one governor, Qutlugh Khān, whose head-quarters were at Deogīr. Mālwa was then made an independent or separate province with its capital at Dhār (251 ante) and placed under the infamous 'Azīz Khummār.' Ibn Baṭūṭa had then left Dehli. III. 614, 1.9 from foot. Bahāu-d-dīn Gushtāsp.

"Gushtāsp" and "Girshāsp" are frequently confounded by copyists in Persian Manuscripts. See my Note on Vol. II. 310, l. S. B. speaks of him as Bahādur Girshāsp. (I. 226=Tr. 304). F. calls him Bahāu-d-dīn Girshāsp and says he was the son of Muḥammad's uncle and governor of Saggar. (I. 135, l. 18). Barani says just like Ibn Baṭūṭa, that Bahāu-d-dīn was the son of Ghiyāṣu-d-dīn Tughlaq's sister and was "Āriṣ-i-Mamālik" in the reign of that Sultan. (428, l. 8). Mr. Vincent Smith is mistaken in describing him as the sister's son of Muḥammad Tughlaq. (O. H. I. 241). He was not Muḥammad's nephew, but his cousin. (T. A. 96, l. 3).

III. 616, l. 1. His flesh was cooked with rice. Some was sent to his children and his wife.

Some of Ibn Batuta's stories are undoubtedly tall and his "rigmaroles" about Santons who lived for two hundred or more years and were present on one and the same day in Mecca and also Assim (Lee, 197; Gibb. 270) have been justly derided by Yule, Kosegarten and others. This bloodcurdling tale of Muhammad's malignity and vindictive rancour may appear incredible, but there are parallels in the written "annals of human devilry", as well as in popular folklore. The Buranjisor indigenous chronicles of Assam relate that the son of the Brahman Minister of Nilambar, the Khyen King of Kāmatāpur, seduced the queen. The king put his wife's paramour to death and immediately afterwards invited the father to a banquet, made him eat his son's flesh and then told him the whole story. (Gait, History of Assam, 42; see also Ibid, 74 and 160, where two other instances of this identical barbarity are recorded). It is also related of another homicidal maniac who sat upon a throne in Thatta, Muhammad Bāqī Tarkhān, that if any of his officers incurred his displeasure, "he was cut into pieces, which were placed in dishes and sent to his house, as a warning ". (Tārīkh-i-Tāhiri in E. D. I. 280). Similar narratives of equally diabolical modes of enjoying 'the luxury of revenge' are familiar to students of storiology. Legends and ballads relating how the Punjab hero Rasālu killed Rājā Hodi, the paramour of his faithless wife, Rāni Kokilan, and made her eat a fricassee of his heart and liver, are "on the lips of every bard in the Punjab". A European analogue may be found in the ninth Novel of the fourth Day in Boccaccio's Decameron, This novel is said by competent critics to be founded on fact, on a

real event in the life of the Provencial poet Cabestan, or the history of a crusader Knight named De Couci and the wife of the Lord du Fayel, (Clouston, loc cit II 188-195).

III. 616, l 21 He placed Sharkh 'Imadu-d-din who resembled him ... under the royal canopy.

The Shaikh 'Imādu-d-dīn, who is said by Ibn Batūta to have 'deputised' for the Sultān and acted as his double, must be the Maliku-l-Mulūk 'Imādu d-dīn of Barani, who tells us that Muhammad Tughlaq presented to him seventy laks of tangas on a certain occasion (454, last line, and 461, 17 f f). Ibn Batūta says that he was the uterine brother of Shaikh Ruknu-d-dīn Multāni and grandson of Shaikh Bahāu-d-dīn Zakariya (Defrémery, III 303, 323)

III 617, l 3 This [Karāchil] is a vast mountain ten days' march from Dehli

I have suggested elsewhere that this 'Karāchil' is either Kurmāchal, [the old Hindu name of Kumaon] or Gargachal, t e the Gagar hills which are a portion of the outer Himalayan range in Kumaon. The distance between Dehli and the mountain is put at ten days' journey, i.e. about 200 miles Dehli is in Lat 28°-39' N, Long. 77°-18' E, Almora is in Lat 29°-35' N, Long, 79°-42' E, which works out as a map-distance of about 175 miles Ibn Batuta says elsewhere that the country possessed mines of gold and gazelles which yielded musk (Defremery, III. 488-9) This also points to Garhwal, which has always been reputed for its auriferous deposits and its musk. There are gold washings in the Alaknanda and Bhagirathi valleys and along the Sona Nadi in the Path Dun. (U P Gazetteer, XXXVI, (Garhwal), pp 115-6) The district at the foot of the mountain which the hillmen owned but which they "could not cultivate without the permission of the Sultan," and paying tribute to him, was the Terai The two other toponym mentioned in this account, have hitherto defied elucidation, probably because they have been both spelt wrongly Ibn Batuta's Memoirs were written, not by himself, but dictated orally in 1356 A C., more than ten years after he had left this country, to an African amanuensis who was entirely ignorant of Indian geography. He was, at the time, in possession of no notes or memoranda, as all his books, papers and belongings had been totally lost in the two ship-wrecks which he had suffered on the west coast near Calicut "He relied," Mr Gibb remarks, "entirely on his memory and his memory was liable to slips and confusions He sometimes transposes the order of the towns in his itineiary" (loc cat 12). For instance, he places Dhar before Ujjain, instead of after it, and Ajodhan after Abohar, instead of before it. (Ibid. 361, 363). Elsewhere, Mr Gibb states that "the unfamiliarity of the names also often leads to strange perversions, especially as Ibn Batūta attempts to reproduce them from memory after a lapse of twenty years" (Ibid. Thus, he confuses Kaylukarı, a small port near Ramnad, on the Coromandel coast, with a place somewere in China and transports it to the

China Seas (*Ibid.* 366) and mixes up Narwar near Gwalior with Parwān near Kābul. In the circumstances, I venture to suggest that 'Warangal' is a perversion, by transposition of the consonants, either of J, Garhwal or of J, Dewalgarh, the old capital of Garhwāl in the fourteenth century. Ibn Baṭūṭa has, in fact, "rendered a strange name by one more familiar". (*Ib.* 33). So, Jīdīa may be a miswriting of 'Lai' 'Jandia' or 'Lai' 'Chandia,' i.e. Chandīpur, which is even now a well-known place in Garhwāl. It is also called Chandi and is mentioned as 'Chandi' in the Shāhjahān Nāma of 'Ināyatulla. It is there said to be a dependency of Srīnagar (the capital of Garhwāl), 'and to lie outside the Dūn of Kilāghar'. (E. D. VII. 107). Cunningham assures us that Chandpur or Chandīpur was the old capital of Garhwāl before the foundation of Shrīnagar. (A. G. I. 356; see also U. P. Gazetteer, XXXVI (Garhwāl), pp. 155-6). See also my notes on III. 241, last line and 464, l. 7. Chandīpur is shown in Constable, 25 C b.

III. 617, l. 4 from foot. Only three chiefs escaped—the Commander Nakbia, Badru-d-din Malik Daulat Shāh and a third whose name I have forgotten.

'Nakbia' is the Nikpai 'Sar-i-dawāt-dar (Chief Inkstand-bearer, i.e. Secretary or Record-Keeper) of Barani. (454, l. 6 f. f.). in Persian means 'of auspicious footsteps', but this man may have been a Mongol, as Nakpai was the name of one of the Chaghtāi Khāns of Turkestān. This Malik Badru-d-dīn Daulatshāh was the son of Malik Fakhru-d-dīn Daulatshāh and is mentioned by Barani as Ākhurbak, Master of the Stables, under Sultān Firūz. (527, l. 4 from foot). His father Fakhru-d-dīn was one of the great nobles of Ghiyāṣu-d-dīn and Muḥammad Tughlaq. (Ibid. 424, l. 6; 454, l. 11).

III. 619, l. 6. Amir Hushanj, when he heard this rumour, fled to an infidel prince named Burabrah who dwelt in lofty mountains between Daulatābād and Kūkan Tanah.

This Malik Hushanj cannot be traced in Barani, but his rebellion on hearing a false report of Muhammad Tughlaq's death is mentioned in the Tārīkh-i-Mubārakshāhi (Text, 106, l. 8) and it is still another point of contact between Ibn Batūta and Yahyā bin Ahmad. Ibn Batūta informs us that Malik Hushanj was the son of Kamālu-d-dīn Gurg and was governor of Hansi when he himself arrived in India in 1334. (III. 143). The district to which he fled after the fizzling out of his revolt is explicitly stated to have been near Thana, in Konkan. It was, I suggest, the small state of Jawhar. The petty prince also, with whom he sought an asylum and who delivered him up to the tender mercies of Muhammad, can be identified with a considerable approach to certainty, although I am not aware of any one having attempted to do so. The clue is found in the Imperial Gazetteer. We read there, that "upto 1294 A. C., Jawhar, which lies partly in the northeastern and partly in the north-western part of Thana district, was held by a Varli chief. The first Koli chief, Paupera, also known as Jayaba, obtained a footing in Jawhār, by a device similar to that of Dido. Jayabā was succeeded by his son Nimsāh, on whom the Sultān of Dehli (Muhammad Tughlaq) conferred the title of Rājā. So important was the event in the history of Jawhār, that June 5, 1343 A C, the day on which the title was received, has been made the beginning of a new era which is still used in public documents" (XIV 87-88) These facts, which are extracted from the local annals of the State, show that the Burabrah of the African globe-trotter can be no other than the Koli Pauper ah who first founded the dynasty still ruling in Jawhār. It was his son, Nīmsāh, who was recognised in 1343 by Muhammad, perhaps as a reward for the loyalty which his father had displayed a few years earlier, in handing over the rebel who had taken sanctuary with him

III 629, l 5 And before him [Sultan Muhammad], was carried the Ghashiya or saddle-cloth

However unsatisfactory Ibn Batūti may be when he "writes at second-hand or repeats what he had heard," he is accurate in describing what he had himself seen. Shams-i-Siraj mentions the "saddle-covering of a horse" among the 21 Sikkas or Insignia of Royalty which could be borne only by the Sultān (Text, 108, I. 3) Among the Seljūqs and Mamlūks also, the royal Ghāshiya—covering for a saddle—was carried before the ruler in public processions and was one of the royal insignia (Houtsma, E I., II 142, s v Ghāshiya).

VOL. IV. FIRŪZ TUGHLAQ TO MUḤAMMAD SŪR.

IV. 4, l. 1. History of the Kings.....as the events are related in the Zafarnāma and the Tārikh-i-Hazrat Saltānat Sh'uāri.

'Hazrat Saltanat Sh'uāri' is not a personal name, but an encomiastic epithet of Sultan Shahrukh. Its literal meaning is 'having the characteristics of a Sultan, or the qualities of a person fit for Imperial sway'. This Tārīkh-i-Hazrat Saltanat Sh'uāri was one of the three works which Hāfiz-i-Abru is known to have written. The first of them was a Geographical treatise or Description of the World, written between 817-823 H., in which a great deal of historical matter also was incorporated. The second was a General History of the World, dedicated to Sultan Shahrukh and coming down to A. H. 820. The third a was another General or Universal History entitled Zubdatu-t-Tawarikh, the compilation of which was begun in 826 H. and completed in 830. It carried the narrative upto 829 H. The Tarikh-i-Hazrat Saltanat-Sh'uari or Tarikh-i-Shahrukhi is the second of these three works and the first Edition of the Zubdatu-t-Tawārīkh or Tārīkh-i-Bāisonghori. The only portions which Hāfiz-i-Abrū himself wrote in both these works are the Continuation of Rashidu-d-din's History from 703 H. to the accession of Timur and that of Nizamu-d-dīn Shami's Zafarnāma from 806 to 819 H. or 829 H. (Barthold in Houtsma. E. I. II. 213; Turkestan, Tr. 55-56). All the rest is an example of the wholesale plagiarism which is only too common in Oriental Literature. The passages translated below are taken from a volume containing extracts copied from a Ms. of a portion of the Zubdatu-t-Tawārīkh which belonged to Mr. J. Bardoe Elliot. (Rieu, Persian Catalogue, 183, 421-4. 991; Supplement, p. 16).

Hāfiz-i-Abrū's works are referred to more than once in the Ain, (Tr. II. 36; III. 1, 212, 326), but Abul Fazl had a very poor opinion of them. He even states that he and Banākati "have indulged in vain imaginings and recorded stories that have no foundation in fact ". (loc. cit. III. 11). Judging from Dowson's extracts, in which the Biyah is said to "fall into the sea in the country of Kambaya" and the Jumna to join "the Indian Sea near Gujarāt" (p. 4 infra), the author may be said to have deserved these mordant remarks. It is due, however, to Hafiz-i-Abru to state that Dr. C. F. Oldham thinks that the passage about the Bivah is taken from some ancient work and refers to the time when the Sutlei and the Biyah jointly flowed to the Rann of Kachh, and the united stream was known as the Biyah. (J. R. A. S. 1893, p. 72).

Hāfiz-i-Abrū's lagab is given by Elliot and others as Nūru-d-dīn, but Dr. Barthold points out that this is a mistake due to a statement of Abdur-Razzāq's and that it was really Shihābu-d-dīn. (Turkestan, Tr. 55; Houtsma, E. I., II. 213).

IV. 7, l. 3 from foot. In the year 755 H., the Sultan marched...... against Lakhnauti.

Recte, 754, as in the T M. (B I Text, 124, 1 12) Firuz really left Dehli on the 10th of Shawwil 754 and returned on 12th Sh'abin 755 H. (Barani, T F 537, 596, T A. 114, 115, F I. 146, 1 4) The chronology of the Tārīkh-1-Mubārakshāhi is not infrequently at fault, in regard to the reign of Firūz Tughlaq. The dates of several events differ from those given by the contemporary historian Shams and some found in Dowson's extracts are, moreover, not always identical with those given by Nizāmu-d-dīn and F, although the last two authors have copied their accounts almost word for word from Yahyā

IV 7, last line. When he [Sultan Firuz] reached Kurakhur.

The name is wrong The correct reading is 'Gorakhpur', as in the B I. Text of Barani, 587, l. 13, as well as in the T A (114), F. (I. 146) and the T. M. (B I. Text, 124, last line) The person who is called Rājā of Gorakhpur here is probably identical with Shams-i-Sirāj's Rājā of Champāran See my note on III 294, l. 12

IV. 8, last line There [at Harbī-khir], he built a fortified place which he called Fīrūzābād

Barani speaks of this Fīrūzābād as a town near Bhatner. (566, 1 10) It is distinguished as 'Fīrūzābād-ī-Hārnīkhera' by Shams (E D III. 354) and is identical with the 'Fort of Fīrūz' of the Zafarnāma and Malfūzāt (E D. III 427, 491 q v my note) The village of Hārnīkhera still exists and lies about twelve miles west of Sīrsā This 'Harbi-Khīr', F.'s 'Sar Khetra', Briggs' 'Pery Kehra', Raverty's 'Bīrī Khera' (Mihrān, 269 note) and Dowson's 'Harī Khīrā' are all copyist's perversions or conjectural emendations which are of no value What Shams calls 'Larās' (E D III. 498-9) is turned into 'Arāsan' by the T M. (126, 1 1), 'Rās' by B I (I. 245=Tr 327) and 'Abāsīn' or 'Absīn' by F. I (I. 149, 1. 17)

IV 9, l 20 He was waited upon Malik Sharkhzāda Bustāmı who had left the country by royal command

He had been really banished from the country. He had been a partisan of the Khwaja-i-Jahan Ahmad Ayaz and had taken a prominent part in the abortive attempt to set up a real or putative son of Muhammad Tughlaq on the throne, as a rival to Firuz. (Barani, 543, 1.21, 545, 1.8) Barani says that he was the داماد خواص بي سلطان (488, L 1) and F. understands this to mean that he had married Muhammad Tughlag's sister's daughter or niece (L 138, 1 6 f. f.), but according to the T A (105, 1 3), he was the husband of the Sultan's own sister Sir W Haig has followed the T. A (C. H. I III 165) The word club is equivocally used in Persian for 'son-in-law' as well as 'brother-in-law', as the son-in-law of the father is the brother-in-law of the son. Gardezi speaks of Abul 'Abbis Māmūn Khwārizmshāh, who was married to Mahmūd of Ghazna's sister, as the Sultan's داماد (Z A. 73, 1 14) Mr. Beveridge also has pointed out that the Persian 'damad' is, like the Turki '1zna', used both for 'sonin-law 'and 'brother-in-law'. (A.N Tr. L Errata, p xu) This Shaikhzada may have been descended from the well-known saint Bayazid-1-Bistami

(known also as Taifur bin 'Isā), or from Jamālu-d-din Bistāmi, who had in the roign of Nacinu-d-din Mahmid and died in the roign of Nacinu-d-din Mahmid and died in UKNOWN also as Lairur din 1867, or from Jamened-din Mahmud and died in been Shaikhurl-Islam in the reign of Nasiru-d-din Mahmud and hore home been Shaikhurl-Islam in the reign this research name seems to hore home seems to hore home seems to home home home seems to home home seems to home home seems to home home seems to home home home seems to home home home home seems to hom 17, 11, 1, 13.

been Shakhu-1-Islam in the reign of Nasiru-a-ain manamu and used been 657 A. H. (T. N. in E. D. II, 359). His personal name seems to have been with the control of the cont DOI A. H. (J. N. III D. D. H., DOY). HIS PERSONAL NAME SEEMS TO HAVE DEEN 'Azamu-l-Mulk.

Hisāmu-d-din and he had the title of 'Azam Malik or 'Azamu-l-Mulk.

(T. M. 120. l. 10: 127. l. 18).

W. 9, 1. 6 from foot. from T line and the envoys Rasuldar' is only the title or designation of his office. His real Rasuldar is only the title or designation of his office. His real name was Sayyad Alau-d-din. (Barani, 580, 1.3 f. f.). Rasuldar non officer in about of content, Railboar non officer in about officer (T.M. 120, 1. 10; 127, 1. 18). name was Sayyad Alau-d-oin, (Barani, Sou, I. St. I.). Rasuldar signines the word envoy, ambassador or officer in charge of envoys.

envoy, ampassador or omcer in charge of envoys. Baihadi uses the word in the last sense. (353, 1.3; 360, 1.10). The Sayyad had been sent as the part of Firit from Dobli to Borgal and come head to Dobli along the part of Firit from Dobli to Borgal and come head to Dobli along the part of Firit from Dobli to Borgal and come head to Dobli along the part of Firit from Dobli to Borgal and come head to Dobli along the part of Firit from Dobli to Borgal and come head to Dobli along the part of Firit from Dobli to Borgal and come head to Dobli along the part of Firit from Dobli to Borgal and come head to Dobli along the part of Firit from Dobli to Borgal and come head to Dobli along the part of Firit from Dobli to Borgal and come head to be a sent as the part of Firit from Dobli to Borgal and come head to be a sent as the part of Firit from Dobli to Borgal and come head to be a sent as the part of Firit from Dobli to Borgal and come head to be a sent as the part of Firit from Dobli to Borgal and come head to be a sent as the part of Firit from Dobli to Borgal and the part of Firit from Dobli

in the last sense. (Dub, 1. 0; Dub, 1. 10). The Dayyau had been sent as the envoy of Firuz from Dehli to Bengal and came back to Delhi along with and in charge of the ambassadors from he reached Sikra, he attacked brains When he reached sikra, he attacked brains of the property of the pr the Rai took to flight. There Shakar Khatiun, and in charge of the ambassadors from Lakhnauti. the daughter of Rai Sadhan, with Adayah, was

The spelling of the place-name is uncertain and there are several ariants, Sankra, Sangra, Sangra, Sonkhora, 199 1 5 T venture ariants, Sankra, Tr. 329. 7. W. 897. 1.20. T. M. 199 1 5 T. 246=Tr. 329. 7. W. 897. 1.20. T. M. 199 1 5 T. 246=Tr. 329. 7. W. 897. 1.20. T. M. 199 1 5 T. 246=Tr. 329. 7. W. 897. 1.20. T. M. 199 1 5 T. 246=Tr. 329. 7. W. 897. 1.20. T. M. 199 1 5 T. 246=Tr. 329. T. W. 897. 1.20. T. M. 199 1 5 T. 246=Tr. 329. T. W. 897. 1.20. T. M. 199 1 5 T. 246=Tr. 329. T. W. 897. 1.20. T. M. 199 1 5 T. 246=Tr. 329. T. W. 897. 1.20. T. M. 199 1 5 T. 246=Tr. 329. T. W. 897. 1.20. T. M. 199 1 5 T. 246=Tr. 329. T. W. 897. 1.20. T. M. 199 1 5 T. 246=Tr. 329. T. W. 897. 1.20. T. M. 199 1 5 T. 246=Tr. 329. T. W. 897. 1.20. T. M. 199 1 5 T. 246=Tr. 329. T. W. 897. 1.20. T. M. 199 1 5 T. 246=Tr. 329. T. W. 897. 1.20. T. M. 199 1 5 T. 246=Tr. 329. T. W. 897. 1.20. T. M. 199 1 5 T. 246=Tr. 329. T. W. 897. 1.20. T. M. 199 1 5 T. 246=Tr. 329. T. W. 897. T. W. ariants, Sankra, Sangra, Satgnara, Sonknera, and Siknra, (J. A. 116, l. 10; B. I. 246—Tr. 329; Z. W. 897, l. 20; T. M. 129, l. 5). I venture

to suggest that the Rai was the ruler of what is now known as Sarangarh to suggest that the Kal was the ruler of what is now known as Sarangarn. States on the Bilaspur and Sambalpur States on State. It is situated between the Bilaspur are the Reignor the Reignor and Sambalpur and State. State. It is situated between the Bhaspur and Sambalpur States on the West and east, While the Mahanadi divides it from the Garages and the West and east, While the Mahanadi divides it from the Garages and the West and east, While the Mahanadi divides it from the Garages and the West and east, While the Mahanadi divides it from the Garages and the West and east, While the Mahanadi divides it from the Garages and the West and east, While the Mahanadi divides it from the Garages and the West and east, While the Mahanadi divides it from the Garages and the West and east, While the Mahanadi divides it from the Garages and the West and east, While the Mahanadi divides it from the Garages and the West and east, While the Mahanadi divides it from the Garages and the West and east, While the Mahanadi divides it from the Garages and the West and east, While the Mahanadi divides it from the Garages and the West and east, While the Mahanadi divides it from the Garages and the West and east, While the West and the W west and east, while the managar or the Zamindary of Chandanpur-Padampur on the north. Sarangarh town lies the Zamindary of Chandanpur-Padampur on the north.

the Lamindary of Unandanpur. Fadampur on the north. Sarangarn town Hes thirty-two miles north-west of Sambalpur. (I. G. XXII. 17). Constable, 32 thirty-two miles north-west of Sambalpur. (L. G. XXII, 17). Constable, 5% of Ca. Lat. 21°-36′ N., Long. Chiefe of the Sinks of Orices who had Sandarone Chiefe of the Sinks of Orices who had

U. a. Lat. 21 -367 N., Long. 83-47 E. Stirling mentions the Rajā of Who had Sarangarh as one of the Feudatory 21 Tominacina containing E1 forth of Managarh of Each and annual 21 Tominacina containing E1 Sarangarh as one of the Feudatory Uniets of the Nuba of Urissa who had a Mansab of 500 horse, and owned 31 Zemindaris, containing 51 forts.

(Account of Oniceo Sal Democrate translation of the research of the containing of the research of the count of Oniceo Sal Democrate translation of the research of the count of Oniceo Sal Democrate translation of the County of Oniceo Sal Democrate translation of Oniceo Sal Democrate a mansao of our norse, and owned of Lemindaris, containing of the passage is not quite (Account of Orissa, 65). Dowson's translation of the passage, it is not quite the passage is not quite the passage is not quite the passage. Correct. Adayah' is not a proper name, as he makes it, but is a proper name, as he makes it.

correct. Adayan is not a proper name, as ne makes it, put is visite. Haiji a daya, or nurse, and this is how the word has been understood by Haiji a daya, or nurse, and this is now the word has been understood by Tolian a daya, or nurse, and this is now the word has been understood by Tolian a daya. a aaya or nurse and this is now the word has been understood by rially agric or nurse. The young girl was taken prisoner with her had a man about the same a Dadir. (A. W. ogi, i. 20). The young giri was taken prisoner with her evidently. The name Shakar Khātūn, is evidently and the hour factors of the name of the state of the sta assigned to her by anticipation. It must have been given to her after convergion to Tolom Goo my Note on Tol TIT 210 1 E. o.

version to Islam. Dee my Note on vol. 111. 512, 1. 512, 1. 512. for peace.

1V. 11, 1. 9. Rai Bir Bhandeo sent some per sons to she for peace. assigned to Islam. See my Note on Vol. III. 312, 1. 5 f. f. A series of contemporary inscriptions Wine Phane Days III who A series of contemporary inscriptions which have been discovered in Devá III, who Orissa leave no doubt that this Raja was Vira Bhanu 1250.9 to 1070 of miled in Katali Control of from Chalco 1974.5 to 1200-1 or 1250.9 to 1070 of miled in Katali Control of the Chalco 1974.5 to 1200-1 Unssa leave no doubt that this Kaja was vira Bhānu Deva III, who ruled in Katak [Cuttack] from Shaka 1274-5 to 1300-1, or 1352-3 to 1378-9 ruled in Katak [Cuttack] from the Congo Kingo of Onice, T A & D 1009

ruled in Katak [Cuttack] from Shaka LZ14-5 to L5UU-1, or, 1552-5 to L5(5-9),

A.C. (M. M. Chakravarti, Raneriea, History of Orissa, I, 282-3). PP. 102; Danuarus Danersen, Library of Verban, L. 2009).

The Sultan fell back and hunted in Padmavati.

The Sultan fell back and Property of the Sultan fell b 11. 1. 13. The Sultan fell back and hunted in Padmāvati.
The T. M. reads "Padmāvati and Baramtalāvli", (129, last line), and
The T. M. reads "Padmāvati and Baramtalāvli", (7 9AF n. 200) but Param los "Padmāvati and Paramtalār", (7 9AF n. 200) but Param los "Padmāvati and Paramtalār", (8 9AF n. 200) but Paramtalār "Readmarati and Paramtalār", (8 9AF n. 200) but Padmāvati and Paramtalār "Readmarati and Paramtalār", (8 9AF n. 200) but Padmāvati. The T. M. reads "Padmāvati and Baramtalāvli", (129, last line), and Baramtalāvli", (129, last line), and "Param 'looks", (L. 247. Tr. 329), but 'Paramtalāv' may be "Padmāvati and Paramtalāv" (L. 247. Tr. 329), but 'Paramtalāv' may be like a duplication and misreading of 'Padma' and 'Paramtalāv' may be like a duplication and misreading of 'Padma' and 'Paramtalāv' may be like a duplication and misreading of 'Padma' and 'Paramtalāv' may be like a duplication and misreading of 'Padma' and 'Paramtalāv' may be like a duplication and misreading of 'Padma' and 'Paramtalāv' may be like a duplication and misreading of 'Padma' and 'Paramtalāv' may be like a duplication and misreading of 'Padma' and 'Paramtalāv' may be like a duplication and misreading of 'Padma' and 'Paramtalāv' may be like a duplication and misreading of 'Padma' and 'Paramtalāv' may be like a duplication and misreading of 'Padma' and 'Paramtalāv' may be like a duplication and misreading of 'Padma' and 'Paramtalāv' may be like a duplication and misreading of 'Padma' and 'Paramtalāv' may be like a duplication and misreading of 'Padma' and 'Paramtalāv' may be like a duplication and misreading of 'Padma' and 'Paramtalāv' may be like a duplication and misreading of 'Padma' and 'Paramtalāv' may be like a duplication and misreading of 'Padma' and 'Paramtalāv' may be like a duplication and misreading of 'Padma' and 'Paramtalāv' may be like a duplication and misreading of 'Padma' and 'Paramtalāv' may be like a duplication and misreading of 'Padma' and 'Paramtalāv' may be like a duplication and misreading of 'Padma' and 'Paramtalāv' may be like a duplication and misreading of 'Padma' and 'Paramtalāv' may be like a duplication and misreading of 'Padma' and 'Paramtalāv' may be like a duplication and misreading of 'Padma' and 'Paramtalāv' may be like a duplication and misreading of 'Padma' and 'Padma'

a perversion of 'Padmasthala' The jungle of Padmavati must have been somewhere near 'Padma Kshetra,' the old Hindu name of Konārak, the Black Pagoda, which is situated twenty miles north-east of Puri (Jagannath). There is a famous temple of the Sun there, which is said to have been founded originally by Krishna's son, Samba, who is believed to have been cured of his leprosy by the god, Sūrya (Stirling, Account of Orissa, p 143, Nundo Lal Dey, Classical Dictionary of Ancient and Mediaeval India, s a Padmakshetra) There is a pargana called Padampur, even now in Cuttack district Puri is 47 miles south of Cuttack Khurda is 25 miles south-west of Cuttack or 30 miles north-west of Puri and Konārak [Padma Kshetral is about 20 miles north-east of Puri As the Sultan is stated to have pursued the Raja for one day's march only and then retreated and hunted the elephants in the neighbourhood, the forest must have been at no great distance from Banārasi (Cuttack) It may be noted that Firūz is said, by Shams, to have gone on to Jagannath, which lies south west of Konarak, after the elephant hunt

IV 11, l 17 There was in the vicinity of Bardar a hill of earth through the midst of which a large river flowed and fell into the Satladar (Sutlej) This river was called Sarsuti

Var, Barwar. (T M. 130, L 9) Parwar, (F I 147, I 10 f f) Can be meant for رواد Rupar? "The Sutlej issues from the Siwalik hills into the plains at Rupar and the head-works of the Sirhind canal are at Rupar" (I. G XXIII 18) Thornton also states that at Rupar, the Sutlej breaks "through the low sand-stone range of Jhejwan" (p 952). Perhaps, this range is "the hill of earth" mentioned in the passage The Sarsuti "rises in Sirmur, and divides into two branches. the more easterly being called Chitang, the more westerly, the Sarsuti, and during great floods, unites with the Markanda, which is sometimes described as one of its offsets" The Markanda runs near Shahabad south of Ambala and Ranking thinks that the Salimah of this author is the Markanda, (B I 330 note), but the two names bear no phonetic resemblance is, perhaps, a misreading or miswriting of الملبة sānba or the Sonba. The Salima is said to have flowed "on the hither side of the mountain" and this fits in with the river Sonb or Sonba

IV. 12, l 10 from foot. In 773 H, Zafar Khān died in Gujarāt

The chronology is conflicting and not easy to fix The T A (117, 1 15) gives 773 and so also B (L 250=Tr I 333) and Hājji Dabīr (898, 1 8), but F (I 148, 1 9) puts the event into 775 H (June 1373-4 A C) F is followed in the C H I., where the date is 1373 A.C (p 182) The appointment of Dāmghāni as governor of Gujarāt is placed by Yahyā (p 13, infra), as well as Nizāmu-d-dīn (117, 1 17) and F (I 148, 1 11) into 778 H., but Shams dates his revolt in 782 H (497, 1 4 f. f) Sir W Haig does not specify any year, but puts the rebellion before 1377 A C that is, 779 A.H. (C H I 182). A possible explanation of the discrepancy,

may be that the revolt or its suppression took place some time after the appointment. It is stated by all the authorities to have been the result of his inability to fulfil his engagements. The feostees who rose against him did so, probably, after he had been some time in office and when they found his exactions intolerable.

IV. 12, l. 8 from foot. Prince Fath Khan died at Kanthur.

A slight change in the discritical points will turn this into Kithor, a well-known town in the Mawina talisil of Mirat district, 19 miles northeast of Mirat town. (I. G. XVII. 235). Constable, 27 C a.

IV. 13, 1. 7 from foot. The fief of Oudh ... was placed under Malik Hisāmu-l-Mulk and Hisāmu-d-dīn Nawā.

As only one man must have been appointed as governor, the conjunction is redundant and should be deleted. It is not in the B. I. Text. (133, 1.5). The name of the feoffee is given as Ilisāmu-l-Mulk only by F. also. (I. 148, 1.8 f. f.). Malik Nawā was governor of Multān under Muḥammad Tughlaq (Barani, 482, 1.14) and Mulik Ḥisāmu-d-dīn-i-Nawā is mentioned as one of the three great Amīrs employed as commanders of divisions by Firuz Shāh in his Bengal campaigns. (Shams, T. F. 115, 116, 117, 151=E. D. III, 295, 296, 308).

This Ḥisāmu-l-Mulk, the fiefholder of Oudh, may have been either Ḥisāmu-d-dīn-i-Nawā himself or his son. He appears to have died during the life time of Firūz and his son Saifu-d-dīn is said to have been appointed in his stead as governor of Oudh. (T. M. 134, l. 8). His sons are again mentioned as having joined Sultan Muhammad Shāh Tughlaq. (Ibid, 146, last line; Ţ. A. 122, l. 5 f. f.).

IV. 14, 1. 29. He built a fortress at Beoli, seven kos from Badāun.

The T. A. (118, 1, 10) reads the name as 'Bisauli' and so also F. (I. 149. 1. S). Hājji Dabīr has 'Siūli' (899, l. 1) and B. 'Babūli'. (I. 252-Tr. I. 335). Sir W. Haig thinks it must be the Firuzpur-Iklehri of the Indian Atlas. which lies about three miles from Budaun. (C. H. I. 183 Note). But this emplacement can hardly be correct, as B. corroborates. from personal knowledge, the statement of the T. M. as to the distance having been not three miles only, but seven Kos, i.e. about fourteen miles. He adds that he had seen the place and that it was, in his time, entirely ruined, though the old bricks and foundations still remained. (I. 252=Tr. I. 336). Such testimony is not easily invalidated and militates with decisive force against the proposed identification. 'Iklehri,' besides, bears very little phonetic resemblance to 'Beoli' or 'Bisauli'. It cannot be Bisauli, which is 23miles north-west of Budaun. (I. G. VIII. 247). Mr. H. R. Nevill suggests that it is Beoli, a village of pargana Satasi, which is = old site and nearer to the alleged seven kos from Budaun than Bismin (U. P. Gazetteer, XV. 137). On 1. 5, the Sultan is said to have extended the hills of Sahāranpur, after passing through Ambila and Shibitibut the B. I. Text of the T. M. (134. 1. 14) reads Santur, and in is undoubtedly correct, is 'Santourgarh' was the capital of

at this time. (See my Note on Vol II 355, l. 6 f f. ante).

IV. 16. l. 2. Khān-i-Jahān sought refuge with Kokā Chauhān at Mahāri.

The addition of three dots to the second letter will restore the name to Machāri, e. e Macheri, an old village 23 miles south of the town of 'Alwar (I.G XVI 224) The Khānzādas of Mewāt are said by Mr Crooke (Tribes and Castes, III 233), to be converted Jadon Rapputs Sultan Firuz Tughlaq is stated to have converted and given to one of their ancestors, who was named Lakhkhan Pal, the title of Nahar Khan and to another named Sumitra Pal, the dignity of Bahadur Khan. The descendants of these two men have come to be called Khanzadas (I G Art Gurgaon, XII. 401) Macheri may be derived from Matsyapurs, 'City of Matsya', the old name of the country of King Virāta of the Mahābhārata

IV. 17, l 1 from foot Amīr Husain Ahmad Iqbāl who had separated from the party of the prince [Tughlaq Shāh] was made prisoner. . and beheaded.

and so also B. که از محصوصان محمد شاه اود ,says (عام 17 با 119, ا 7 با 119, ا (I 255=Tr I 338) "Who was one of the special favourites of Muhammad Shah". F. says he had joined or united himself with the party of (I 150,1 11) The که سلطان ناصر الدین محمد شاه اتعاق کرده بود Muhammad Shah B. I. Text reads که از حمع شاهراده علیحده افتاده بود (140, 1, 3)

IV 18, l 3. Orders were also sent to seize 'Ali Khan

The B I. Text reads عالى حال عالى حال (140, l. 7), but عالى حال must be a mistake for Ghālib Khān, by which name he is called at 23, 28 and 32 infra The T. A (119, 1.7 f f) and F (I 150, 1 13) read 'Ghālib Khān' here, and so also the B I Text of the T M everywhere else.

IV. 18, l 5 from foot [Sultan Firuz died] after a reign of thirtyseven years and nine months

The T. A, B. and F. agree in making it 38 years and some months. As Firuz ascended the throne on the 24th Muharram 752 and died on 18th Ramazān 790 H, he reigned really for thirty-eight (lunar) years, seven months and twenty-four days Dowson's Ms may have wrongly read معت for مشت The B I Text has سي و هشت (141, l. 11), but the British Museum copy reads سى و هنت (Ibid, footnote)

IV. 18, Footnote. He [Firūz Shāh] was ninety years of age

This is another averment which is demonstrably erroneous B (I. 253 =Tr. I 336) and F (I. 150, l. 14) go one better and assert that he was more than ninety, at the time of his death But the contemporary chronicler, Shams, states that Firūz was born in 707 H (1307-8 A C) and was 45 at the time of his own accession, (E D III 275), fourteen at the accession of Ghiyasu-d-din and eighteen at that of Muhammad Tughlaq (Ibid. 274) He must, therefore, have been in his 84th lunar year at the time of his death in Ramazan 790 H or September 1388 A.C He really lived for only about eighty-one solar years. Elphinstone (p. 411) and many

'I. 18; 470, I 19) is explicitly mentioned by Shams as having succeeded his father in the office of Mustaufi (482, I. 2). The Junaidi family had supplied many great officials to the Dehli Sultans, since the days of Nizāmu-l-Mulk Junaidi, who had been the prime minister of Ibak and Iltutmish 'His son Ziāu-l-Mulk Junaidi was murdered along with other Tājik officials by the mutinous Turki nobles in 634 H (I'N in E D II 822, 325, 331) 'Azīvū-d-dīn Muhammad Junaidi, who was Chief Judge of Gwālior from 630 H to 635 H, is also mentioned (Ibid, 327, 335) 'Anu-l-Mulk Nizām Junaid wis made Vazīr in 651 H. (Ib 352)

IV. 21, l' 1 The length of the reign of Sultan Tughlik Shah was six months and eighteen days

As he was killed on the 21st of Safar 791 H, this implies that the date of his accession is taken by the author to have been the 4th of Sh'aban 790 H. But F (I 151, last line) says that he reigned for five months and some days He must have reckoned from 18th Ramazan 790 H, the day of the death of Sultan Firuz The T A gives him a reign of 6 months and 18 days (122, 12), reckoning, not from the day of the actual demise of Firuz, but from that on which he was placed on the throne with the consent and during the lifetime of his grandfather B makes it 5 months and 18 days (I 258=Tr 342)

IV. 22, l. 7 And Rai Sarvar and other rais and ranas soined the Sultan [Muhammad]

Dowson notes that the Ms he has used has with 'Sabīr', but that he has followed F who calls him 'Sarvar' here (I. 152, I IS) The T A has (123, I 4 f f.) and Hajji Dabīr with 'Sanbar' (902, I 2) 'Sarwar', 'Shīr' and 'Sanbar' are all impossible names for a Hindu and the correct form is with 'Sumer' See my note on 26, I 3 post F himself spells the name as with Sanbar at I 159, I 3 f f and with 'Sumer' at 160, I 10 See also Dowson's note on p 50 post Sumer, Samarsinha and Sumersinha are still common names Sumerpur is the name of a town in Jodhpur (P. O G) and of another in Hamīrpur district, U P (Th. 928)

IV 22, l 16 Abu Bakr Shāh encountered him at the village of Kundali

in the TA (122, last line) and F. (I. 152, l 7 f. f) is, probably, Kandhla It was a Mahāl, in Sai kār Dehli, Sūba Dehli (Āîn, Tr II. 287) Kandhla is now a station on the Dehli-Sahāranpur Light Railway, about 46 miles north-east of Dehli The place is called Khondli in the CH I III 190, but its situation is not indicated

IV 23, 1 8 The two forces drew up in battle array at the village of Basina near Panipat.

Recte, Pasina, a village still existing about six miles to the south of Panipat, as the Post Master of Panipat informs me

IV. 24, 1 9 Mubashir Hājīb-i-Sultāni tur ned against Abū Bakr Dowson notes that he has adopted 'Hājib', the explanatory gloss or conjectural reading of F. (I 153, 1. 5), but that the sobriquet is given as 'Jab' in his Ms. of the T. M., 'Chap' by B. (I. 261=Tr. 344) and 'Hab' in the T. A. (123, l. 18). It is \rightleftharpoons in the B. I. Text of the T. M. also. (149, l. 10; 150, l. 3). We have here, perhaps, another instance of the practice of abbreviating or contracting familiar titles or sobriquets. 'Jab' or 'Chap' seems to be an abbreviation of $H\bar{a}jib$, just as 'Janda' is of 'Junaid'. This may also explain why Malik Ahmad, the sister's son of Sultan Jalālu-d-dīn Khalji, was called 'Ahmad Chap'. We know from Barani that he also was Nāib-i-Amīr-i- $H\bar{a}jib$. (249, l. 16). The fact that both these men were $H\bar{a}j\bar{i}bs$ and that both had this unusual sobriquet of 'Chap' may be a mere coincidence, but it is nevertheless worth noting. Another arresting point of similarity between the two cases is that the epithet of Ahmad also is spelt 'Chap' by Barani (246, 249) and 'Hab' or 'Jab' in the T. A. (64, l. 5).

IV. 24, l. 13. So he [Abu Bakr Shāh] left Dehli, accompanied by

Malik Shāhīn, Malik Bahri and Safdar Khān Sultāni,
and proceeded to the Kūtila of Bahādur Nahir.

Sic in the B. I. Text (149, 1, 13) also, but according to the T. A. (123, 1, 20), F. (I. 153, 1, 3) and B. (I. 261=Tr. 344), these nobles did not accompany Abu Bakr but were left behind at Dehli by that prince to look after his interests in the capital in his absence. The Text reads دو المراجعة, but the compilers have

Dowson says in a footnote that Kūtila "seems to be used here as a common noun and not a proper name." But this must be an error, Kotla is mentioned as the name of a fortified town in Tijīra in the Aīn. (Tr. II. 193). On page 53 infra, Dowson himself speaks of it as "the fortress of Kūtila belonging to Bahādur Nāhir". B. also especially states that Abū Bakr fled to the "Kotla-i-Mevāt", i.e. the (place called) Kotla, which was in Mewāt. (I. 261=Tr. 344 and 345). Dowson's inconsistency and error are evinced by the fact that the Kūtila mentioned on this page and on page 25, l. 5, are both registered as place-names by himself in the Geographical Index (Vol. VIII, p. xxvi). Tīmūr is said to have sent envoys to the 'Shahr-i-Kūtila', 'City of Kūtila of Bahādur Nāhar' in the Zafarnāma of Yazdi (E. D. III. 505), as well as in the Malfūzāt-i-Tīmūri. (Ib. 449). This Kotla lies about eight miles south of Nūh in Gurgāon district. (Elliot, Races, II. 100). Nūh is shown in Constable, 27 C a.

IV. 25, l. 12. They had reached the town of Mahindwari.

This is probably identical with 'Rindwāri' in Mewāt in which Sultan Firūz is said by Shams to have erected one of his palaces. (E.D. III. 354). The Khānzādas of Mewāt are known to have been converted by him. (I. G. XII. 401). The palace of 'Hindwāri' is again mentioned at page 67 infra and seems from the context there, to have been situated in Mewāt. 'Mahindwāri' is, probably, Mandāwar, as both the place-names are vernacular forms of the Sanskrit 'Mahendrapuri' or 'Mahendrawāra'— 'Town of Mahendra'. Mandāwar is now in Alwar and lies about 40 miles

south-west of Kotla. It is shown in Constable, Pl 27 C b

IV 25, l 7 from foot. And arriving at Kūtila, he encamped on the banks of the Dahand

Here 'Dahand' is not, as the definite article prefixed to it would imply, the proper name of a river, for there is none such near Kūtila The word is the Hindi 'Dhāṇd', and it is employed here in the general sense of 'lake', or 'large pool of water' Ābul Fazl explicitly states of this Kūtila or 'Kotla' in the Sarkār of Tijāra, that it had a brick fort on a hill, on which there was a lake four Kos in length (Aīn, Tr II 193) The lake or 'Dhānd' still exists and extends nearly three miles by two and a half It lies partly in Nūh and partly in Gurgāon, where the two tracts join at the foot of the Alwar hills Vide Powlett, Gazetteer of Gurgãon, p. 7

IV 25, last line There [at Etāwa], the Sultan was waited upon by Nar Sing

Dowson says that his "Ms and the T A. [124, I 18] agree in reading it 'Bar Sing', which is an improbable name, that F has 'Nar Sing', which is perhaps right, though 'Harsingh' is possible' But really it is neither 'Nar Sing' nor 'Har Sing', but Bīr - (Vīra) Sing He was Vīra Sinha, the Tomar chief who had made himself master of Gwālior, soon after the devastating invasion of Tīmūr See 39 post Vide also Crooke, T C IV. 413. Cunninghām, Arch Surv Reports II 381 et seq

IV 26, l 3 Nar Singh above mentioned, and Sarvādharan and Bir Bahān, broke out in rebellion

Here again, the correct name is 'Bīr Sing' There can be little doubt also that Dowson's Ms of the Tār Mub is right in making two names out of this 'Sarvādharan' He says that it leads "Sabīr wa Adharan," two names, saying "Sabīr the accursed and Adharan" 'Sabīr' must be, as I have pointed out, 'Sumer' and 'Adharan' must be "Uddharan", two Hindu chiefs whose names occur elsewhere also in the Chronicles.

In his chapter on the manner in which Sultan Firuz used to sit in State, when he held a Court, Shams states that Rāi Sabīr () and Rāivat Adharan (12) were also permitted to attend and sit behind Zafar Khān Junior, not on a carpet, but on the bare ground (Text, 281, 1.8) Hājji Dabīr states that in 779 A H. Sultan Firūz Tughlaq had to march in person against the Rai Sābīr and Adharan who had rebelled in Etāwa and were, after a battle, compelled to submit (898, 1 16) The T M (134, 1 1) and T A (117, 1 1 ff) also mention this expedition and add that the wives and children of Rai Sabīr and Adharan were all carried away to Dehli and forced to reside there. See also F. (I 148, 1 6 ff) and B (I. 251=Tr I 334) who repeat this. There can be little doubt that they are the Rāi Sabīr and Rāwat Adharan, whom Shams saw sitting humbly on the bare floor, behind the other Musalman nobles in the Darbār Hall The prefix 'Rāwat' indicates that this Uddharan was the younger brother or son [of Vīra Sinha?] or a chief of the second class.

In this connection, it may be worth mentioning that local tradition has preserved the name of Sumer Sāh, who is said to have founded the Chauhān house of Partābner, which lies six miles west of Etāwah. The Rājās of Mainpuri claim him as their ancestor and he is said to have built the fort at Etāwah, because when bathing in the Jumna, he saw a goat and a wolf drinking water in one and the same place. (Mr. Drake Brockman, in the U. P. Gazetteer, Ed. 1908, Vol. XI. (Etāwah), pp. 129, 206, 220). The name 'Bīrbahān' also may be identified with that of 'Rāmbīrbhān', which occurs in the dynastic list of the Rājās of Mainpuri. (Ibid. p. 129 Note. See also N. W. P. Gazetteer, Ed. 1876, Vol. IV, p. 370).

IV. 26. 1. 11. Sarvadharan attacked the town of Balaram.

Dowson's Ms., as well as the B. I. Text, (152, 1.11), B. (I. 262=Tr. I. 346) and F. (I. 153, l. 6 f. f.) agree in reading "Balaram". I venture to say that it is right. The T. A. makes it 'Bilgram', and this is rejected in the C. H. I. on the ground that "the Hindus were attempting to establish themselves in the Doab, and it is difficult to see why they should have crossed the Ganges and attacked Bilgram." (III. 192 note). But Balaram (or Bilram) is entirely different from Bilgram and lies in the Duab, not outsit of it. It was a Muhal in Sarkar Kol, Suba Agra, in the days of Akba (Ain, Tr. II. 186). It is now in the Kasganj talisil of Etah district, U. (I. G. XV. 69), and is shown in Constable, Pl. 27 D b. It appears to ha been a place of note and is mentioned more than once in the Tabagāt $N\bar{a}siri$. (Text 226, l. 6 = E. D. II, 358) in juxtaposition with Kol at Gwalior; see also 265, l. 4 f.f.; 278, l. 7. A Malik Nasiru-d-din Balarami also mentioned. (Ib. 189, l. 4 f. f.=E. D. II. 339). Shaikh Burhān Balārāi is referred to by Barani. (516, l. 7). Bilgram is in another distri altogether, that of Hardoi. The emendation 'Talgram' which is advocate in the C. H. I. is devoid of Ms. authority and seems uncalled for.

On l. 13, the B. I. Text also reads $Biy\bar{a}h$. The T. A. Lithograph have in The Black River, i. e. the Kālīnadi. (124, l. 4 f. f.). If Dowson Ms. of the T. A. read "Etāwah", it must be a copyist's error. It is su gested that the Sengar is the river meant here, as it is said by traditio to have been at one time known as Besind' or 'Biyāh". (N. W. Provinc Gazetteer, (Ed. 1876). Vol. IV (Etāwa), p. 371; U. P. Gazetteer, Ed. 190 Vol. XI. 129 note). The in or Black River' is again mentioned by the author at 48 infra. Tāju-l-Mulk is there said to have marched from Chan wār, "along the Black River and chastised the infidels of Etāwa." See al 64 infra note, where Ibrāhīm Shāh is said to have advanced along the banks of the Black Water to Burhānābād in the district of Étāwa. Dowso says that it is the Kālīnadi and the Tārīkh-i-Dāūdi calls it the Āb-i-Siyê or Kālīnāi. (444 infra).

IV. 26, l. 27. But an infidel named Jājū, his brother's son, a bad fello with a spite against him, gave false evidence and Islā Khān was condemned to death.

Sic in the T. M. (Text, 153, l. 4), but the T. A. reads it thus

حاجه نام هندوی و برادر زادهٔ او که امدای او بودید بدروع در معرکه گواهی دادید 125, l, 2. "But a Hindu named Jājū and his brother's son who were his foes gave false evidence against him" F. (I 153, l 3 f f.) has almost the same words, which shows that their copies of the T. M must have read a " wav " between ליפ and צונע נוני As the noun and the verb are both in the plural, it would seem that there were two witnesses and not one. The evidence of a single witness to a fact or accusation is, in Muhammadan Criminal Law, invalid. The chief witness was the Hindu and as his statement was corroborated, as the law required, by Islam Khan's own nephew. it was held sufficient for the conviction and capital punishment of the accused. The testimony of a Hindu is, in Muslim law, subject to certain limitations and is not valid against a Muslim, unless it is corroborated قاصى مدوكواه راصى by that of a follower of the Prophet The well-known saying "The Qazi is satisfied with the evidence of any two witnesses", (q v Roebuck, Persian and Hindustani Proverbs, I 316), refers to this principle of the Criminal Jurisprudence of Islam.

IV. 27, l 12 But Rai Sar (vādharan) escaped, and enter ed Etawa.

The addition in brackets is an unauthorized interpolation. The B I. Text (154, 1 4) and the T. A. (125, 1 7) both state that Rāi Sabīr only escaped and this must be correct. A dharan (of whom we do not hear any thing after this) was murdered and disposed of for ever, along with the other chiefs mentioned, viz Jīt Singh Rāthor, Bīr Bahān [or Rāmbīrbhān] of Bhanūgānw [Bhūingāon near Mainpuri] and Abhay Chand of Chandū, [Recte, Chandwār near Firūzābād] F (I 153, 1 7 f f.) has turned 'Bhanūgānw' into 'Bhansor' and he is followed in the C H I (III. 192), but no such place is known Rāi Sīr or Sabīr [Recte, Sumer] who escaped lived upto 824 H (p 53 post) Bīr Sinha Tomar, who afterwards seized Gwālior was another of the confederate chiefs saved, because he had been cairied off by Islām Khān to Dehli before this perfidious massacre.

IV 29, l 6 Kahu a-Kanil

אפר לבעל, se Khor-Kampil, both of which place-names are mentioned correctly and in association with each other again at 47 infra Kampil lies 26 miles north-west of Fatehgarh, Lat 27°-37' N., Long 79°-21' E (Th) Khor is three miles from Shamsābād, which lies 12 miles north-east of Farrukhābād in Lat 27°-32' N, Long. 79°-3' E (Th) Their proximity to each other is thus manifest

IV 29, l 21 [Sarang Khān] crossed the Satladar (Sutley) near the town of Tirhārah, and the Biyāh near Duhāli

This is Tihāra in Lūdhiyāna district, Punjab Lat 30°-57' N, Long. 75°-25' E The name is said to be derived from ti, third and hāra, share, Tihāra being the low land by the river which paid one-third of the produce as revenue to the State, while the Chauhāi a tract paid only a quarter. (W H Tolbort in J A S B XXXVIII, (1869), p 88) Tihāra was a Malāl in Sarkār Sirhind, Sūba Panjab, and had a brick fort in Akbar's days (Āīn, Tr. II, 295) It is locally identified with the Vairāta

of the Mahābhārata, but many other places make the same claim and the old site has been now washed away by the Sutlej. (I.G. XVI. 200).

IV. 37, l. 16. Shams Khan who was at the town of Nuh o Batal.

Dowson notes that the second name is written as 'Patal' in Budāuni. The correct form is neither 'Batal' nor 'Patal', but 'Tappal'. Nūh is now in Gurgãon district. Tappal is a pargana in Khair, the northern talişīl of 'Alīgarh district. In Akbar's times, Nūh and Tappal were both in the Sarkār of Koil, Sūba Agra. (Āīn, Tr. II, 186). Both places are marked in Constable, Pl. 27, C a. Nūh is 40 miles south-west of Dehli and Tappal 31 miles west by south of 'Alīgarh (Thornton). Nūh is in Lat. 28°-7' N., Long. 77°-4' E., Tappal in Lat. 28°-2' N., Long. 77°-39' E.

IV. 37, l. 1 from foot. He encountered Rāi Sīr and other infidels with a numerous army [at Pattiāli].

(Sanīr) in F. (I. 159, l. 3 f. f.). B. has — (Sapar) at I. 288, 289=Tr. 380, 381. The right reading must, again, be — Sumer (Sinha). See Note on 22, l. 7 and 26, l. 3 supra. He is said here and also on 39 last line, to have been pursued to and to have taken shelter in Etāwa, because he was the Chauhān Rājā Sumer Sāh of Etāwa and his name is preserved in the dynastic lists of the Chauhāns. In the C. H. I., he is called Rājā Sarwar (205, 207, 209) or Sarwar Singh (210, 212), but the latter is an impossible name for a Hindu chief of the fifteenth century.

IV. 38, l. 17. A battle was fought [near Ajodhan] on the 9th Rajab, on the banks of the Dahandu.

Sic in the B. I. Text, (I. 170, 13). Raverty reads . Wahanda, and supposes it to be the Hakra. (Mihran, 275). But 'Dahand' or 'Dhand', means 'lake, river-bed, stream'. The Sutlej flowed at this time between Abuhar and Ajodhan, about 16 miles from the former and double that distance from the latter. Abul Fazl notes that the Sutlej bears several names in different parts of its course and is called "Harhari, Dand [Dahanda] and Nurni". (Ain, Tr. II. 326). This 'Dand' or 'Dahanda' is the specific name of a stream, which, leaving the main channel of the Sutlej to the east of Ajodhan, flows south-west and joins it again about 35 miles lower down ". (Jarrett's Note, Ibid). Ajodhan is shown in Rennell's Map of 1782 A. C. as lying upon "an island surrounded by the Sutlei to the north, and a tributary stream which left the main river to the eastward of Ajodhan, and flowing south-west joined it again some 35 miles lower down". (Ranking's Note in B. I. Tr. 362-3). According to the writer of the article on the Sutlej in the I. G. also, the Sutlej and the Beas flowed together up to about 1593 A.C. in the same channel under different names, as "Macchuwah, Hariāri, Dand, Nūrni, Nīli and Gharah." (XXIII, 179). Khizr Khān is said at p. 40 infra, to have defeated Iqbal Khān, five years later on the banks of this same Dahanda near Ajudhan.

IV. 38, l. 18. Taghi Khan fled to the town of Asahuhar.

The B. I. Text has 's 'Bahūhar'. (170, l. 15.) The T. A. reads 'Bahūdar' (130, l. 1) and B. has 'Bahūhar' or 'Bhūhar'. (I.273—Tr.???)

The place meant is Abūhar. It was on the road to Multīn and Ibn Batūta passed through it on his journey from Multān to Dehli (Gibb, 190). Constable, Pl. 24, E b

IV 39, l. 4 [At Kanauj], he expelled Malikzāda Harbūr

'Shāhzāda Harbūi' in the T. A (130, l 11), and Sy' Harīwi' in the B I Text (171, l. 8), but B calls him Shāhzāda Fath Khān Harwi (I 273 = 361) 'Harbūi' is an error for 'Harīvi' or 'Harīwi', i e of 'Herāt' See also 307 infra and E D. V 78, where another Amīr named Fath Khān Harwi is mentioned as having commanded the army of Sultan Mahmūd of Jaunpur and invaded Dehli at the head of 30000 horse and 39 elephants. Baiani speaks of Herāt as A. (T F 538, 12)

IV 39, l 10 Ikbāl Khān marched against Girālior which. had been wiested from the hands of the Musalmāns by the accursed Nai singh When Narsingh died, his son, Biram. Deo succeeded him in the possession

He is called 'Bar Singh' in the B I Text (171, 1 4 f f) and 'Harsingh' by B (I 274=Tr 360)', here also, but the real name is 'Bir Sing', e (Vîra Sinha) Bîram Deo [Vîrama Deva] was not his son but his grandson [or nephew?] Virama's father, Uddharan Deva, does not appear to have reigned, probably because he died during the lifetime of Vîra Sinha Sir Wolseley Haig speaks of Vira Sinha as 'Harsingh 'and Viram as 'Bhairon' (C H I. 202 and 533), while Briggs and Dowson turn the latter into 'Brahma Deo' These conjectural emendations are all proved to be wrong from the dynastic list of the Tomar rulers of Gwalior, which has been recovered from epigraphical records existing at Rhotas and Narwar (J A S B. VIII 693, XXXI, 404, Cunningham, Arch. Surv Reports, II 324) A pillar on which the names of the Tomar Rajas are inscribed still stands outside the fort of Narwar (I G XVIII, 397, Duff, C. I 306) As this dynastic list will have to be frequently referred to in these Notes, I give it below (1) Vira Simha (2) Uddharanadeva, son [or brother ? of 1 (3) Vīrama, son of 2 (4) Ganapatideva, son of 3 (5) Durgarendradeva, [Dungar] son of 4 (6) Kırtisımha, son of 5 (7) Kalvanamalla, son of 6 (8) Mana Sahı, son of 7 (9) Vıkrama Sahı, son of 8 (10) Rama Sahı, son of 9 (11) Shalıyahana, son of 10 Several other inscriptions of these princes have been also found. There are three of Vīrama Deva (1408-1410 A C), six of Dungar Sinha (1440-1453), five of Kirtī Sinha (1468-1478) and two of Man Sinha (1495-1500) (Cunningham, Arch Surv Reports, II 396)

IV 39, last line Rāi Sarwar, the Rāi of Gwālior, the Rāi of Jālhār, were shut up in Etāwa.

F. (I. 160, l. 10) reads the names as See also Ibid, I 162, l. 3 f. f. and 163, l. 13, where he is again called (Samer or Sumer). His name is again written on p 50, l 7 infra, as "Sarwar" by Dowson, who cannot understand why "he is still called 'Sabir' in his Ms. of the T M and why Firishta, who before spoke of him

as Sarwar "here names him Sambir'. On page 52 infra, 1. 23, Yahyā is made to say that Khizr Khan "marched against Etawa and besieged Rai Sarwar" and Dowson again remarks, "still 'Sabīr' in the Ms. and 'Sarū' in the T. A." The B. I. Text of the T.M. has Sabir here also. (172, l. 1 f. f.). IV. 40. l. 2 from foot. His head was cut off and sent to Fathpur.

This Fathpur lies about twenty miles north-east of Kahror. It is shown in Constable's Atlas, Pl. 24, E c. Lat. 29°-40' N., Long. 72°-10' E.

IV. 41, l. 22. The fief of Kanauj was then given to Ikhtiyar Khan, grandson of Malik Yar Khan Kampila.

'Malik Daulat Yar Kampila' in the B. I. Text (175, l. 1 f. f.), and so also in the T. A. (131, 1.9 f.f.) and B. (I. 275=I. 363.) The sobriquet indicates that Daulat Yar was in some way connected with Kampil in the Duab. He may be the Malik Daulat Yar who had been given the title of Daulat Khan and made 'Imadu-1 Mulk and 'Ariz in the year of Mahmud Shah Tughlaq's accession. (See T. M. Text, 156, l. 15=28 ante and T. A. 126, l. 1). Malik Daulatyār is said to have been Hākim of Qanauj. (T. A. 122, l. 4 f. f.). Kampil is 60 miles N. W. of Qanauj.

IV. 44, 1. 9. Khizr Khan plundered the towns of Tajarah, Sarath and Kharol.

Tijāra lies about 30 miles north-east of Alwar city. (I. G. XXIII. 358). Babur says that Hasan Khan Mewati and his forefathers had their seat in Tijāra, but left it andt ook to residing in Fort Alwar, when he (Bābur) took Lāhore and Debālpur in 930 H. (B. N. Tr. 578). It is shown in Constable's Atlas, Pl. 27, Cb. 'Sarath' (سرهته in the B. I. Text, 179, 1, 12) is 'Sarahta', four miles east of Tijara, under the border hills. "It is famous in the history of the Khanzadas, who are said to have come thence to Tijāra in the time of Teja Pāl—the first reputed Rājā of Tijāra." (Powlett, Gazetteer of Alwar, p. 134; Crooke, T. C. III. 234). 'Kharol' is 'Gahrol', a ruined town "which was formerly occupied by the Khānzādas and is situated at the foot of the path which leads up to Kotila. (Bahādur Nahar's stronghold), and thence on to Indor" or Andwar of p. 75 infra. (Powlett, Ibid. 134-5). The conjunction after 'Iklim Khan' (l. 8) seems to require deletion. Iqlim Khan was, most probably, the son of Bahadur Nāhar. (cf. 41 ante. and 45 post). Bahādur seems to have died before this time.

IV. 44, l. 13 from foot. He [Maḥmūd Shāh] was seized with illness in Rajab (815 H.) and died. He reigned twenty years and two months.

The other authorities agree, as Dowson observes, in putting his demise into Zī-l q'ad. The T. A. (133, l. 1) and F. (I. 165, l. 15) state that Mahmud went out for Shikar to Katehr in Rajab 815 H., was seized with illness on the return journey to Dehli in. Zi-l-q'ad and died soon afterwards. Yahya states that he went to Katehr in the first Jumadi and returned and died in Rajab.

The T. A., F., B. and even the C. H. I. (III. p. 204) mechanically repeat

the assertion of Yahyā about this Sultān's reign having lasted for twenty years, but it cannot be correct, if Mahmud came to the throne in Jumādi I. 796 and died in Rajab or Zī-l q'ad 815 H, as they themselves assert.

According to the C H. I (III p 192), Sikandar Shāh died on 8th March 1394 and Mahinūd in February 1413 (p. 204), and yet Sir Wolseley states that he died after "a reign of twenty years" February 1413 synchronised with Zī-l-q'ad 815 H and 8th March 1394 with 5th Jumādi I. 796 H The fact is that Mahinūd reigned only for 19 lunar years and 6 months, or about 18 solar years and 11 months, even if he died in Zī-l-q'ad and not in Rajab, 815 H.

IV 44, last line Sultan Ibrāhīm [of Jaunpur] was besieging Kādir Khān, son of Sultān Mahmūd Khān in Kālpi

This 'Sultan Mahmud Khān' was not the Sultan of Dehli, but (Nasīruddin) Mahmud Khān, son of the Malikzāda Firūz, son of Malik Tājuddin Turk, (q v p 19 ante), who is said to have held the Shiqq (division) of Mahoba and Kālpi, at p 37 ante. The history of this Mahmud Khān and of his descendants who ruled for nearly half a century as independent princes in Kālpi is of some numismatic interest and has been elucidated in connection with their exceedingly rare coins by the present writer in a paper on the "Unassigned Coins of Jalāl Shāh Sultāni" in the Numismatic Supplement, No XLII to the J A S B (1930), Art 289

IV 45, footnote 2 Firishta adds that for several years, he [Khizr Khān] sent appropriate tribute to Shāhrukh

Firishta (I 162, I. 10) has not cited any authority but this particular statement appears to be correct and is borne out by the contemporary historian and traveller, 'Abdur Razzīq He assures us that Khizr Khin sent an embassy to acknowledge the suzerainty of Shahrukh, as the son and successor of Timur The original passage is quoted from the Matl'au-s-S'adain by M Quatremère in an article in the Notices et Extraits des Manuscrits, XIV 196 We learn also from the T M that Malık Sıkandar Tuhfa-the general and minister of Mubarakshah-"paid to Shaikh 'Alı, [the deputy of Sultan Mas'ud Mirza, the ruler of Kabul], the money which he was accustomed to pay him annually and sent him away", (a e induced him to quit Lihore) in 834 A H. (Text, 218, 1 6= 70 infra) This ingenuous allusion or unconscious admission indicates that the Sayyids did annually pay some sort of blackmail, subsidy or tribute upto, at least, 834 H to the successor of Timur So far F is right but when he and the T A (184, 1 1) assert that Khizr Khan coined money also in the name of Timur, they are in error and the statement is a gratuitous conjecture or amplification, for which there is no warrant Modern numismatic research has conclusively proved it to be a myth (Thomas, C P K. D 328-9) Khizr Khan never struck money in the name of Timur What he really did, was to stamp posthumous coins in the names of Firuz Shah and his descendants, but the dates were altered so as to indicate the actual

years in which they were uttered under his authority. Several such issues in the name of Sultan Firuz ranging from 818 to 830 H. are known. Others of Muhammad Shāh (818 and 825 H.) and Mahmud Shāh (816 and 83-H.) are also in our Museums. (C.P. K. D. 326; Wright, C. M. S. D. 186, 201, 214). Khizr Khān's son Mubārak Shāh first issued money in his own name only in 832 H. and coins of all years between 832 and 837 H. have been found. (Wright, *Ibid*, 231-3).

IV. 47, l. 8 from foot. He chastised the infidels of Khor and Kambil and passing through the town of Sakīna, he proceeded to Bādham.

The addition of a single dot to the fourth letter will restore the third name. 'Sakīna' is a misreading of 'Saket' in Etāh. Saket lies on the direct route between Kampīl and Rāpri, 12 miles south-east of Etāh and 24 N. W. of Mainpuri. Constable 27 D b. The T. A. Lithograph states that he went to 'Maham' by way of the town of Saket (134, l. 11), but Nizāmu-d-dīn's copyist B. has 'Pādham' (I. 286=Tr. 377), which seems to be correct. 'Pādham' is the name of a very old village in Mainpuri district, where coins of the Satraps of Mathura (Circa 100 A. C.) and other ruling dynasties have been found. (Smith, I. M. C., I. 191; Arch. Surv. Rep. XI. 25, 38). It is situated on the highroad to Etāh, near the Arind river, 23 miles distant from Mainpuri and 18 from Shikohābād in Lat. 27°-20' N., Long. 78°-40' E. (Gazetteer of the United Provinces, (Ed. 1908), Vol. X. (Mainpuri), pp. 83, 146, 245-6).

IV. 49, l. 10. Khizr Khān proseeded to Bayāna, where Shams Khān Auhadi (amīr of Bayāna) also paid money and tribute.

So also in the B. I. Text, (186, I. 15) and the T. A. (134, I. 3 f. f.), but Shams Khān had been put to death in 803 H. more than fifteen years before this date by Iqbāl Khān. (p. 38 ante). The T. A. (129, I. 3 f. f.), F. (I. 160, I. 1) and B. (I. 273=Tr. 360) themselves state that Shams Khān had been slain by the perfidious Mallu. Sir Wolseley Haig has not escaped the error. (See C. H. I. III. 207 and 201). On the immediately preceding page (48), this author himself says that when Khizr Khān entered the country of Bayāna, Malik Karīmu-l-Mulk, brother of Shams Khān, gave him a grand reception. B. (I. 286=Tr. 378) and F. (I. 162, I. 19) say that it was Karīmu-l-Mulk who paid the tribute in this year also, and they must be right.

IV. 49, l. 16. Tughān.....who had besieged Malik Kamāl Badhan, representative of Khānzāda Mu'azzam, in the fort of Sirhind, went off to the mountains.

The "Khānzadā-i-Mu'azzam" was really the son of Khizr Khān himself, i. e. Prince Mubārak Khān, who succeeded him as Mubārakshāh. Cf. ante. 48, where Yaḥyā states that Malik Sadhu Nādira had been sent to Sirhind as the representative of Prince Mubārak Khān. Kamāl Khān was appointed to that office after the murder of Malik Sadhu. See also B. (F. 286=Tr. 378) and F. (I. 162, I. 14).

IV. 50, l. 14. He crossed the Ganges at the ford of Bijlana.

Sic in the T. A (135,16) and B (I. 287=Tr 379), but there is no such place 'Bījlāna' is a miswriting of 'Pachlāna' Pachlāna is mentioned in the Aīn as a Sarkār in Kol, Sūba Agra (Tr II 186) Elliot points out that the "Ganges is not crossed here at the present day, as the river has changed its bed" (Races, II 97) Pachlāna lies now on the Budh Ganga, "the Old Ganges", and is in Kāsganj tah sīl, Etāh district. (I.G. XV. 69) Yahyā says (126) that Khizr Khān crossed the Ganges near Patiāli, and Tāju-l-Mulk near Sargdwāri (48, I. 22) But Elliot observes that the Ganges cannot now be forded either at Patiāli or Sargdwāri (Races, II 30) Patiāli also lies on the bed of the Old Ganges

IV. 51, l 11 In the mountains of Bājwāra, dependent upon Jālandhar The B I Text (189, 17), T. A (I 185, 170 ff) and B (I 288=Tr. 380) all read 'Bājwāra', but F (I 163, 13) makes it 'Māchiwāra' Māchiwāra hes on the Sutley about 25 miles south of Ludhiāna It is a very old town and said to be mentioned in the Mahābhārata 'Bājwāra' is further north in the district of Hoshiārpur. Bājwāra seems to be correct Jath (15 ff) may be 'Chath' or 'Chahat' or 'Chut' which was a Mahāl in the Sarkār of Sirhind and lay on the Ghaggar (Āīn, Tr II. 296)

IV 52, l 13 from foot. [Tāju-l-Mulk] destroyed the village of Dehli, the strongest place in the possession of the infidels. From thence he marched against Etāna.

This 'Dehli' must be Deoli-Jākhan near Etāwa Deoli lies between the Sarsū and the Sangar rivers (Elliot, Races, II 86) It is one of the places in the United Provinces where the Chauhāns are still found in great strength (Ibid, I 13, 64) Jākhan is mentioned by Bābur as a pargana in Rāpri It lies about 18 miles north-west of Etāwa amongst the ravines of the Jumna (B N Tr 644 and note, see also Crooke, T C I 121 and my note on II 362, 12 f f) Deoli'is the 'Duhlee' of Thornton who says that it is in Lat 27°-2′ N, Long 78°-52′, about 20 miles north-west of Etāwa, which is in Lat 26°-46′, Long. 79°-2′ E It is the chief seat of the Bais Thākurs who have been always noted for turbulence. Gangā Singh of 'Dihūli' was in rebellion in the Mutiny of 1857 also It is now in the Barnahal pargana of Mainpuri district, while Jākhan is in Etāwah District (U P Gazetteer Vol X (Mainpuri), pp 94, 151, 204)

IV 54, l. 14. Sultan 'Ali, king of Kashmir, led his army into the country of Tatta

This obviously incredible statement is found also in the T A (136,15 f f), F (I 163,121) and B (I 289=Tr 381) No king of Kashmir is known to have invaded Lower Sind and 'Tatta' must be wrong. One suggestion is that it is an error for Tattakūti, a mountain pass in Kashmir and Sultān 'Ali is supposed to have been defeated, there by Jasrath Khokhar about 823 A H. According to the chronicles of Kashmir, 'Ali Shāh went on a distant journey or a pilgrimage, leaving his brother Shāhi Khān as regent. He soon repented of his folly and to retrieve his

orror, returned with an army provided by his father-in-law, the Rājā of Jammū, and expelled Shāhi Khān, who took refuge with Jasrath Khokhar. Jasrath then invaded the country and suddenly attacked 'Ali Shāh's army, when it had been exhausted by a forced march, in one of the mountain passes. 'Ali Shāh was killed or captured in the battle and Shāhi Khān ascended the throne under the title of Sultīn Zainu-l-'Ābidīn. (T. A. 600; F. II. 341-2). In the C. II. I. (III, p. 280), this is said to have occurred in the Tattakūti Pass. But as Yaḥyā and his copyists explicitly state that Sultān 'Ali was defeated when he was returning from an invasion of Thatta, it is just possible that 'Thatta' is an error for Tibet, i.e. Balti or Little Tibet. Shāhi Khān, who succeeded him as Sultān Zainu-l-'Ābidīn is actually credited with the subjugation of Little Tibet. (T. A. 601, 1. 5; F. II. 342, 1. 13). Their father Sikandar the But Shikan is also said to have conquered, i.e. invaded and raided that country. (T. A. 599, 1. 12; F. II. 340, 1. 10).

IV. 54, l. 7 from foot. [Zirak Khān] pitched his camp three Kos from the town [Jālandhar] on the banks of the Beni.

The name is written 'Pani' at 73 infra. The T. A. has 'Main.' (137, 1.2 and 143, 1.9). The stream meant is the Dhauli or Sufid, i. c. White or Eastern Bain, which "rises near Garhshankar and after a course through that tahṣīl, turns to the north and meanders along the Jullunder border". (I. G. XIII. 192 and XIV. 222). There is another river of the same name, the Kāli (Black) or Western Bain with which it should not be confused IV 56. 1.1

not the same as the 'Gakkhars,' but Jasrath was, most probably, a Gakkhar. Rankine suggests that 'Telhar' is Talwāra, a village on the right bank of the Chīnāb, just opposite the town of Riāsi. Lat 33°-6′N, Long 74°-52/E. (B. Tr I 384 note).

IV 57, l 5 He pitched his camp near the tomb of Shaikh Hasan Zanjāni

IV 57, l 6 from foot. Sikandar Tuhfa now arrived at the ford of Būhi

יرهی (T. A 137, 1 2) but برهی in F (I. 164, 1 12) Boh or Bopūr is about twenty-three miles above Machiwāra and about two miles west of Harīki Pattan It lies close to the old right or west bank of the Biyāh (Raverty, Mihrān, 278 and 395 note) It is the Baupur of old maps and the junction of the Biyāh and the Sutley takes place near it on the southern boundary of Kapurthala State (Āīn, Tr II, 310 and 326 and Notes) Harīki Pattan is in Lat 31°-11′ N, Long 75°-4′ E (Th) (A G I 222) It may be the 'Pohi' which is mentioned on 1, 9, p 77 infra F's 'Lühi' is a quite different place

IV 58, l 9 from foot. From thence, the Sultan crossed the Ganges and attacked the country of the Rahtors

ولايت رانه ومهومه تاخت So also F (I 164, l 19). But the T. A has (138, 1 11), "raided the district of Rath and Mahoba", while B says that he attacked "the country of the Panwars, which is in the neighbourhood of Khor or Shamsābād" (I. 201=Tr 384) B's بواران must be a of the T. A must دانيه و مهو به And (دا) متو دان of the T. A must be another factitious emendation of راتبوران The Sultan is said to have gone on from Katehr to the country of the Rathors and then to have left a strong detachment to suppress any fresh outbreak or recrudescence of their turbulence at Kampil 'Now Kampil and Khor are coupled together by this author on p 47 ante also Kampil was then and is even now occupied by a large number or Rathors (I G XIII 328) Khor also is known to have been founded by a Rathor descended from Jayachand of Qanau, about the beginning of the 13th century Iltutmish expelled the Rathors in 1228 A C, but they returned to Khor and afterwards took Shamsabad also, which lies about three miles from Khor (I G XXII. 229).

IV. 59, 1 24 Sharkh 'Ali, lieutenant of the prince, the son of Sar-atmash

Sūyūrghtimish Mirzā was the fourth son of Sultan Shāhrukh, the son of Tīmūr, and had been appointed Viceroy of Kābul and Zābul by his father. He died during Shāhrukh's life-time in 830 H. and was succeeded in the viceroyalty by Mas'ūd Mirzā, 'the Prince' whose name was not known to Yaḥyā. Shaikh 'Ali Beg was the son of Dānishmandcha, a descendant of Chaghatāi, the son of Chingiz. He was the Nāib or Deputy-governor of the province of Kābul under Sūyūrghtimish Mirzā and, after his death, on behalf of his son, Mas'ūd Mirzā Kābuli. (Bāburnāma, Tr. 382—E. D. IV. 233; Raverty, Mihrān, 366-7 Note). The name is transliterated as 'Sūyūrghatmish' (B. N. Tr. 382), 'Sūrghatmush' (Browne, Tr. Tārīkh-i-Guzīda, II. 134) and 'Saiyūrgh-timish', (Mihrān, loc. cit.).

IV. 61, l. 14. The Mewāttis......took refuge in [the mountains of] Jahra, which was their great stronghold.

The right reading is not easy to fix. It is perhaps the same name that occurs at p. 27 ante, where Bahādur Nāhar is said to have fled and hidden in 'Jhar', (T. M. 154, l. 13), when the fortress of Kūtila in which he had taken refuge became untenable. F.'s reading here (I. 154, l. 3) is (Panjahra), which may indicate that the locality referred to in both places is 'Jr.'. Tijāra is described by Bābur asthe original seat of the Mewāti and it is well-known for the strength of the hills surrounding it. (Powlett, Gazetteer of Alwar, 132; B. N. Tr. 578). 'Jr. can be easily mistaken for in Persian writing. On l. 9, the Ganges is said to have been crossed at Gang, but this is, probably, an error for Kanpil Ji. (Text, 203, l. 16).

IV. 61, l. 5 from foot. They took up a position in the mountains of Andwar.

The "Wāv" should be pronounced as a vowel. 'Indūr' is mentioned in the Aīn as one of the maḥāls in Sarkār Tijāra. Its fort which was situated on a high hill is also mentioned. (Tr. II. 192). "It is now a ruined town in Alwar State and lies about ten miles east of Tijāra. The fort is still occupied by a Rajput garrison." (Powlett, l. c. 134-5). Elliot says that it lies on the western brow of the Mewāt hills between Nūh and Kotila, which latter is eight miles south of Nūh. (Races. II. 100 and 88). 'Jallū' and 'Kaddū' are contumelious forms of 'Jalāl' and 'Qādir'. Jallū is called Jalāl Khān at 66, 67 infra.

IV. 63, l. 11 from foot. The forces of Ibrāhīm Sharki have attacked the town of Bhūkānū.

and the T. A. (140, l. 9) read not be a side of Bhungāon,' now in Mainpuri district, about ten miles north-east of Mainpuri town, at the junction of the Agra and Grand Trunk Roads. Bîrbahān Muqaddam (chief) of Bhanūgānw is mentioned by this author at page 29 ante. Rāi Partāb is said to have been ruler of Bhungāon in the reign of Buhlūl Lodi. (T. A. 153, l. 14). It is shown as Bhongāon in Constable, 28 Ab.

The Chauhans have been for centuries in great strength in Mainpuri and Etawa. Birbahan, (Vira Bhanu) and Rai Partab [Rudra] both belonged to this tribe and it is on record that the pargana of Bhuingaon was given as jägir to Rājā Jagman Chauhān in the 49th year of Akbar's reign. (A N. Takmila or Continuation, III. 832=Tr. 1247). Mainpuri town was founded by Jagannath, ninth in descent from this Partab (Rudra), and the present Raja of Mainpuri claims descent from Jagannath. (I G XIII 40-1).

IV. 63, 7 9 from foot attacked the village of Mubarak Shah Haroli, one of the well-known places of Maicas From thence he proceeded to Atroli

The T A. puts it thus: موصع مرتولی که از مشاهبر مواس اود تاحت (140, 1. 10) and F (I 165, 1 4 ff), copies the words Atrauli was a Malial in Sarkar Kol ['Aligarh], Suba Agra, in the days of Akbar (Ain, Tr 11.186) It is in Lat. 28°-2' N, Long 78°-18' E, and lies sixteen miles north-east of 'Aligarh (Hunter Imp. Gaz. I. 180) Constable, Pl 27 a. Haroli or Jaroli is Thornton's Jurowlee, a village on the route from 'Aligarh to Muradabad, 28 miles north-east of the former. Lat 28°-17' N., Long 78°-17' E The language here used shows that "Mawas" was a place and not a person Yahya writes elsewhere that in the reign of Muhammad Tughlaq, people left their homes and their cattle and crept into the Mawāsāt and places in the interior (Text, 112, I. 14). See my note on Vol II 355, 1 7 f f.

IV. 64. 1 14 There he [Sharqi] crossed the Jumna to Gudrang and marching on, he encamped at the river of Katehr

This 'Gudrang' is a puzzle. Perhaps we should read كدرك Barani uses the word (T. F 231, 122) The Sultan crossed the Jumna at the Ford or Ferry On p 65, 1 4, Sharqi is again said to have retreated towards the Jumna and crossed from Gudrang to Rapri, but here again, בנלא may be the right reading But another elucidation is that it may be كدرك, 'the ford of Narang' It is stated in the Mainpuri Gazetteer that at Narangi, the Jumna contracts to a width of about 150 feet only in the cold weather and there is a bridge also in the place (U P. Gazetteer X. 248-9) Narangi Ghat lies three miles from Batesar, which lies on the other side of the river. It is very near Rapri and 'Gudrang' may be a miswriting of كدرنرك 'the ford of Narang' The T. A. (140, l. 15) and F (I 165, last line) say nothing about 'Gudrang' and merely state that Sharqi crossed the Jumna near Rapri and went to Bayana F calls the river کستر (Kanthir) and so also Ḥājji Dabir (916, 1 3), but the right reading must be Sambhir Bayana lies "close to the left bank of the Gambhīr" (I G VII 137)

IV. 64, l 5 from foot Malik Jaman

The name is spelt 'Chaman' in the B. I Text (209, 1 1), T A (140, 1 6 ff) and also F. (166, 1 4) and this must be the correct reading He is again called 'Jaman' on p 84 post, but the true orthography 'Chaman'

is found at page 82. See note on 81, 1.3 f. f. infra. "Chaman" means 'garden,' pleasaunce' and Chamanlal, Chamanral are well-known Hindu names. Miyan Chaman is not unusual as a name among Muhammadans even now. Two Gujarat nobles named 'Chaman' are mentioned by Ḥājji Dabīr. (Z. W. 100, 480).

IV. 68, 1. 11 from foot. Sent Yusuf Sarub and Rai Hansu Bhatti.

'Sarūb' seems to be an error for 'Sarwar'. On page 71 infra, he is called Malik Yūsuf-i-Sarwaru-l-Mulk, which indicates that 'Sarwar' and not 'Sarūb' is the true reading. Yūsuf was the son of Sarwaru-l-Mulk. B. also reads Yūsuf-i-Sarwar, (I. 294=Tr. 388) and Yūsuf-i-Sarwaru-l-Mulk. (296, 297 = 390, 391). See also 76 infra. But the form -ccurs repeatedly in the best Manuscript of the T.M. (183, l. 14; 225, l. 3; 226, l. 8), and it is possible that he was a Hindu convert whose original name was Swarup and he is styled Malik Sarūp Sarwaru-l-Mulk at Ibid. 226, l. 12.

Rāi 'Hansū' is called 'Hīmū' at 40 ante. If 'Hansū' is the real name, it may be a short form of 'Hansrāj'. He was the son of Khulchain or Dulchain Bhaṭṭi. The name is again written 'Hansū' at 71 infra. B. also calls him 'Hansū'. (I. 294—Tr. 388).

IV. 69, l. 15. Pulad had said to himself.

What the Text says is و يش از ابن بولاد مذكور مى كفت (216, l. 5). F.'s words are و يش از ابن بولاد مذكور مى كفت (I. 167, l. 1). "The slave Fulād sent a message", which must be correct, as his object was to make his demands and conditions known to the Sultān, through 'Imādu-l-Mulk. He could have gained nothing by saying what he wanted only to himself. Mubārak Shāh then sent a message to Fulād with 'Imādu-l-Mulk. (B. I. 294—Tr. I. 388).

IV. 70, I. 14. Passing through Jālandhar, he went to Lāhore. There Malik Sikandar paid him the money which he paid to him annually and sent him away. From thence, Shaikh 'Ali proceeded to Talwāra.

This paragraph has been translated by Dowson from the abstract or summary in the T. A., as his own Ms. had lost a page here. But the original text in the T. M. is much fuller and may be rendered thus:

"He then crossed the Sutlej near Tirhāra, made the inhabitants of the tract from Jālandhar to Jāran and Manjahūr his captives and returned along the banks of the Biyāh. He then crossed the Biyāh in the month of Rajab and marched towards Lāhore. There Maliku-sh-Sharq Sikandar, its Amīr, offered him the customary annual tribute and turned him back. Thence, passing through Kasūr, he encamped at Talwārah opposite Dipālpur, the renowned city." (Text, 215, 1. 3).

Here Manjahūr is most probably an error for or Machhūr or Machhūr is most probably an error for or Machhūr or Machhūvar, i. e. Machhūvāra on the Sutlej, about 22 miles east of Ludhiāna. 'Jāran and Manjhūr' are mentioned by Amīr Khusrau as well as Barani, in connection with one of the Mughal invasions and this reference to them by Yaḥyā is of interest, as it is helpful in the solution of a difficult question. See my note on III. 71, 1. 9.

IV 70, 1. 21 Shaikh 'Ali crossed the Raw at Khatibpur

But spir (Text 219,1 1), and red red Khūtpūr also in B (I.295=Tr 389) It is the 'Khatpur' of the Ain. It was the chief place of one of the northernmost mahāls of the Multān Sūba and in the Bāri (Biyah-Rāvi) Duāb (Tr. II 329-30) [Sir] Edward Maclagan says that 'Khatpūr' is now an insignificant village, a few miles west of Saiāi Sidhū, through which the Rāvi now runs It is known as Khatpur-Sandhā from the Jat tribe of Sandhās (Abul Fazl's Account of the Multān Sarkār in J. A. S. B. LXX, (1901), p. 5) Sarāi Sidhū is shown in Constable, Pl. 24, E. b

IV. 70, 1 7 from foot And laying all waste along the banks of the Jhilam, which is well-known as the Jinab (Chinab), advanced towards Multan

"Such is", notes Dowson, "the extraordinary statement of the text and Firishta copies it" Raverty i emarks that there is nothing 'extraordinary' or erioncous in the statement Yahyā means the united Ihelam and Chināb, which is rightly called Chināb below its confluence with the Ihelam and after their union (Mihrān of Sind, 367 Note) The I G also explicitly states that the two rivers after their union "flow under the name of the Chenāb" (XI 189)

The T. A. (142, 1 7 f. f.) and B. (I 295=I 389) also say غيارت الله The T. A. (142, 1 7 f. f.) and B. (I 295=I 389) also say غيارت الله the says Sultan Shāh Lodi was defeated, not killed, though many of his men lost their lives, and others saved themselves only by flight As there was a lacuna here in Dowson's Manuscript of the T M, he has translated this passage also, as it is reproduced in the T A. The discrepancy is due to F having read أمادت instead of عبادت In the B I Text of the T M, Sulaimān [variant Sultan] Shāh Lody is explicitly said to have been killed المرابعة الله (219, 1 6) Sultān Shāh Lodi had the title of Islām Khān (p 64 supra) but at pp 71, 75 and 77 infra, (Text 220, 221, 226, 229), this author repeatedly speaks of Islām Khān or Islām Khān Lodi having been subsequently sent, on different military expeditions. If this is correct, this Islām Khān Lodi must be another person on whom the title had been conferred after the death of Sultān Shāh Sir W. Haig says Islām Khān was killed (C H I III 217)

IV 71, l 1. The Sharkh ['Alı] occupied Khairābād near Multān

So in the T A (142, 1 6 ff), and F (I 167, 1 11 ff), but it is called 'Khusrūābād' in the B I Text, (219, 1 3 ff) and this is the reading in B also (I 295, Tr I 389) As neither 'Khairābād' and 'Khusrūābād' can be traced in modern maps, it may be worth noting that Ibn Batūta tells us in the narrative of his journey from Sind to Dehli, that on the way from Ucch to Multān, he crossed the river of Khusrūābād at a distance of ten miles (by which he probably means Kos), from the latter (Defrémery, III 117) F puts 'Khairābād' at three Manzils or stages [farsakhs ?] from Multān

IV. 74, l. 5. Shaikh 'Ali retreated towards Bartot.

So also in Hājji Dabīr, (917, l. 21), but 'Mārtot' in the T. A. (143, l. 8 f. f.). The place meant, may, perhaps, be Mārot or Marwat, now a talişil in Bannū district, N.W. F. Province. It contains the town of Lakki (I. G. XVII. 213). Constable, 24 D a. Lakki-Marwat is now a Railway station, 37 miles south-east of Bannū.

IV. 75, l. 10. The Sultan marched towards the mountains of Mewat and arrived at the town of Taorū.

Tāorū was a Maḥāl in the Sarkār of Rewāri, Ṣūba Āgra, and the pargana town had a brick fort. (Āīn, Tr. II. 293). It is now a pargana in Nūh taḥṣil, Gurgāon district, Punjab, and is shown in Constable, Pl. 27 C a. It is situated about twenty miles east of Rewāri on a high plateau which is separated from the low-lying tract round Nūh by a low range of hills. (I. G. XIX. 231).

IV. 76, l. 4. Shaikh 'Ali marching quickly from Shor.....and after making prisoners many of the men of Sāhaniwāl,..... went on to Lāhore.

This Sāhaniwāl may be Sāhīwāl, the old name of the modern town of Montgomery which was founded in 1865 and lies between the Rāvi and the Sutlej. (I. G. XVII. 419).

IV. 78, l. 16. The sons of Kangu and Kajwi Khatri.

"Kajū" in the B. I. Text (232, l. 10) and the T. A. (145, l. 7). The real names of these miscreants were, probably, and for Gangū and Gujar. 'Kajwi' or 'Kajū' must be due to the 're' having been misread a 'wāv.' 'Gujar' is a very common personal name among Hindus in these parts and has been adopted also by Musalmans. It was borne, for instance, by a son of Quibu-d-dīn Muḥammad Khān Ātka in the reign of Akbar, (Blochmann, Āīn, Tr. I. 468) and also by the Commander-in-Chief of the army of Dāūd Kararāni. (Ibid, 399; Tārīkh-i-Dāūdi, 511-512 infra). See also my note on Vol. III. 359, l. 5.

IV. 79, l. 11 from foot. On Friday, the 9th Rajab 837 H. (19th January 1434), the Sultan reached Mubarakābād.

The week-day works out correctly. The Julian correspondence was Friday, 19th February, 1434 A. C. (not 19th January 1434, as is stated above by Dowson). 19th January 1434 A. C. was a Tuesday.

IV. 80, l. 5. He [Mubārakshāh] reigned thirteen years, three months and sixteen days.

So also in the T. A. (145, l. 17), B. (I. 299, Tr. 394), and F. (I. 169, l. 14 f. f.), but the arithmetic is demonstrably faulty. Mubārak ascended the throne, as Yaḥyā (53 ante) and all these authors themselves aver, on 19th Jumādi I. 824 H. He was assassinated on 9th Rajab 937 H. He reigned, therefore, for thirteen years (lunar), one month and twenty days.

IV. 81, l. 3 from foot. Ahar Miyan holder of Badaun.

Read 'Miyan Chaman, holder of Budaun,' as at 82 infra. The name of

the individual has been inadvertently omitted. See B (I 301=Tr 396), and T A (146, 19) The name is wrongly spelt as Jiman at 64 ante and 84, 15 infra Malik Allahdad Kala [not Kaka] was Amir of Sambhal and Ahar He was the uncle of Sultan Buhlul Lody 'Ahar Miyan' is a misprint IV 82, 16 from foot He crossed [the Ganges] at the ford of Kicha

The words in brackets are an unauthorized interpolation and are also misleading On p 41 ante, and also a few lines higher up on this very page, Kīcha is described as a ford on the Jumna (18) No place could be a ford on two rivers at the same time, unless it was situated at the point of their junction In Ni'amutulla, the name is spelt as 'Kanjh', but he also makes it a ferry on the Jumna (E D. V 87) B repeatedly states that Kīcha was a ford on the Jumna and at no great distance from Dehli. (I 276, 301 and 309=Tr 364, 396 and 406)

IV 86, 1 14 At length, in the year 849 H, Sultan Muhammad Shah died after a reign of ten years and some months

Dowson says in a footnote that the T A gives 844 H., B 847 H., F 849 H and that the correct date is the last These discrepancies in the manuscripts are due to the bewildering similarity between of and in the Semitic script. For another example, see my note on III 590, 1 15. The numismatic evidence is clearly in favour of 849 H Muhammad Shāh's billon and copper coins of every year from 837 to 849 are known (Num Supp No XXXV to J A S B 1921, Art 223) Thomas (C P K D 336 note) was in favour of 847 H., but coins discovered after he wrote prove that 847 is two years too early See also Mr Nelson Wright's C M S D, pp 236, 241. Muhāraks'hāh really reigned for twelve years

IV 87, l 13 He made one of his wife's brothers governor of the capital and to the other he gave the title of Amir

Dowson has translated this from the T A., but the lithographed text of that work (148, 1 7 f f), B. (I 305=Tr. 401) and F (I. 172, 1. 15) all concur in stating that the other brother-in-law was made Amīr-i-Kui, Prefect of the Streets, Police Chief, lit. Superintendent of the Highways There was an officer called Amīi-i Kūi in Ahmadābād also under the Gujarāt Sultāns (Mirāt-i-Sikandari, Text, 79, 1 2, Tr Bayley, 166, Tr Fazlulla, 44) The phrase is there explained as 'Kotwāl' or 'Police Magistrate' B (I 305) follows, as usual, the T A and Ranking renders 'Mīr i-Kūi' as 'Superintendent of the Roads' (Tr I 401) Hājji Dabīr states that one of them was made Amīr or Governor of the City and the other of the Environs [1-c] (Z W 920, 1 24)

IV 89. l 2 Matl'au-8-S'adain

This enigmatic and fanciful title, signifying 'The Rising of the Two Auspicious Luminaries' is derived from the fact that the work chronicles the events "from the date of the birth of the last great Mongol ruler of Persia to the year [1469 A C=873 H] of the death of his namesake, the great grandson of Taimūr" Both of them bore the name, Abū S'aid, and they are the two S'adain alluded to 'Abdur Razzāq notes also the

curious coincidence that the last great Mongol ruler of Persia died in the very year in which "Taimūr, the founder of the next great Tātār empire" was born, viz. 1336 A.C. (Browne, L.H.P. III. 429-30). The full title, however, is old the core, is also the year in which the work was first taken in hand. (40+9+30+70+1+30+60+70+4+10+50+6+1+30+40+3+40+70+1+30+2+8+200+10+50=865 H.). Dr. Rieu states that "in the body of the work 872 and 875 H." are incidentally mentioned. (I. 182). One of the copies in the Bodleian has a subscription stating that "the first volume was completed in 871" (Ethé, Catalogue, I. 91), while the second is said to have been finished in 880 H. (Rieu, I. 182). There can be little doubt that the composition of this voluminous work was spread over several years and it is not improbable that it was begun several years earlier in 865 H., the year indicated by the chronogrammatical title.

IV. 91, l. 9 from foot. It ['Abdur Razzāq's account of Tīmūr's invasion of India] proves to be a reproduction of Tīmūr's own narrative.

Dowson had pinned his faith on the authenticity of the *Malfūzāt-i-Tīmūri*, and he advances this as an argument in support of that view. But the assertion is decisively negatived by what 'Abdur Razzāq himself tells us in regard to the source of his summary of the world-conqueror's career. He makes no reference whatever to any Autobiography composed by the "Great Tartarian", and in two passages, which have been cited by Rieu, explicitly declares that he has derived all the facts of Tīmūr's history from the *Zafarnāma* of *Nizāmu-d-dīn-i-Shāmi*, "and speaks of him as his chief authority for that period." (Persian Catalogue, I. 172; see also Muqtadir, Bānkipur Catalogue, VI. s.n.).

In the Preface to this Volume, Dowson remarks that 'Abdur Razzāq "relates his own travels in the grand style, but the portions relating to Tīmūr's invasion are written in a plain, unpretending narrative remarkable by the contrast". (p. vi ante). But this plainness is really due not to his having copied the narrative, as Dowson imagined, from the Malfūzāt, but to his having transferred to his own pages the simple and comparatively bald account of Nizām-i-Shāmi, the whole of which had been incorporated by Ḥāfiz-i-Abrū also in the Tārīkh-i-Shāhrukhi or first edition of the Zubdatu-t-tavārīkh. (Barthold, l. c. 54 Note).

At the same time, it is due to Dowson to note that he was not greatly to blame for this error. It is clear from his cwn statements that he had never seen a complete copy of the Matl'au-s-S'adain. He possessed only "some extracts from the first volume", which were among Sir Henry Elliot's papers. He admits that he had never had any opportunity of reading "Abdur Razzāq's own account of his authorities". (Preface, p. vi ante; Appendix, 562 post). We now know that 'Abdur Razzāq used neither the Malfūzāt, nor the work of Yazdi, and that his real source was the earlier chronicle of Nizām-i-Shāmi, but this knowledge is derived

only from Rieu's Catalogue which was published after Dowson's death.

IV 95, l 21. I had an interview with the Amir who was on his return from plundering the province of Banpur

Recte, Bampur It is now in what is called Persian Baluchistān. Lat 27°-19′ N, Long 60′-15′ E. It is shown in the Every Man's Library Atlas of Asia, Pl 45, and also in the Map prefixed to Holdich's Indian Borderland But there is another town called Bam (and also Bampur), south of Kermān, and it may be the place meant. It is in Lat 29° 4′ N, Long 58°-20′ E. Khurdādbih says that it is at eight parasangs' distance from Narmāshīr, i.e. the town of Kermān (Goeje's Ed. Text, 196, 16, Tr. 153) IV 96, 19. [People bring commodities to Hormuz fi om] the coasts of Arabia as far as Aden, Jiddah and Jambo (?)

This 'Jambo' is 'Yanbū', which is the port or gateway of Medina, as Jedda is that of Mecca The name is sometimes written 'Livey' Al-Yanb'ū, with the Arabic article prefixed, and this accounts for the form 'Eliobom', which occurs in Barbosa's fravels and for 'Liumbo' which is used in the Commentaries of Albuquerque (IV 35) Ludovico Varthema calls it 'Yembo'. (Badger's Trans 24) It is a place of great antiquity and is mentioned by Ptolemy who speaks of it as "Iambia, the part of Jathrippa," i.e. Yathrib, the old name of Medina (Dames, Tr Barbosa, I 45 note) It lies a little west of Medina in the littoral of the Hijāz (Jarrett, Āīn, Tr. III 57 Note See also Houtsma, E. I, IV 1158)

IV. 97, 1. 1. The time favourable for proceeding to sea, viz the beginning and middle of the monsoon, elapsed

Tavernier who made six voyages to Persia and India gives the following explanation .- " The months of November, December, January, February and March are the only months in the year in which one embarks at Hormuz for Surat and at Surat for Hormuz with this difference. however, that one rarely leaves Surat later than the end of February, but for leaving Hormuz, one may wait till the end of March, or even till the 15th of April, because then the western wind which brings the rains to India begins to blow When you wish to go from Hormuz to Surat in fourteen or fifteen days, you must embark in the month of March or the beginning of April, because then you have the western wind astern all the way ". (Travels, Tr Ball I. 4) 'Abdur Razzaq arrived at Hormuz in the middle of Shawwal 845 H, i.e about the 26th of February 1442 A C As he was detained there for two months, i.e upto the very end of April, about a fortnight later than the 15th-the latest eligible date for starting, according to Tavernier, or the favourable season had passed. The day on which he saw the New Moon of Muharram 846 H was 12th May 1442

IV. 97, l. 20 I went from Maskat to Kariat

Karyāt or Curiat is on the north-east coast of Arabia between 'Rās al Hadd' and Masqat, 'Rās al Hadd' is the Cape Rosalgat of European geographers and map-makers. It means 'Land's End', something like Cape 'Finisterre' (Dames, Barbosa, Tr I 50 and 70 Notes, Miles, Coun

tries and Tribes of the Persian Gulf, 484). Curiat lies about eight leagues from Qalhāt. (Danvers, History of the Portuguese in India, II. 531). Its importance lies in the fact that it stands at the mouth of a Wādi, by which access can be obtained to the country behind the mountains. (Dames, Barbosa, I. 70 note).

IV. 97, 1. 7 from foot. The moon of the Muharram of 846 H. developed the beauty of her countenance.

This statement and two other references to the observation by the author of the New Moon of Muharram in 847 and 848 H. (112 and 125 infra) indicate that 'Abdur Razzāq's dating is founded on the *Hilāli* or Ruyyat method of calculating the age of the Moon.

IV. 98, 1. Ilaving learnt that in the neighbourhood of Kalahāt, there was a place called Saur, I embarked on a vessel to go to that place.

Marco Polo says that Calatu [Qalhāt] was "a noble city with a large and good haven." Dames states that "Saur and Qalhāt owed their importance to their position just north of Rās-al-Ḥadd, the first point in Arabia reached by vessels from India. They both lie on the southern coast of 'Omān, north-west of Rās-al-Ḥadd. Saur is the starting point of a well-marked route from the coast into the interior of 'Omān. Lat. 23° N., Long. 60° E. Idrīsi says that it was one of the oldest and richest towns of 'Omān, but its trade had suffered from the depredations of the pirate chiefs of Kīsh. (Tr. Jaubert, I. 152-3)". (Dames, I. c. I. 72 note). Ibn Baṭūta speaks of Saur as a town in a roadstead, from which Qalhāt, situated on the slope of a neighbouring hill, can be seen. (Gibb, 116; Defrémery, II. 229).

IV. 99, l. 11 from foot. Shortly after, the King of Bengal having complained of the hostilities he was suffering from the King of Jaunpur, sought protection from the Court of [Shāhrukh].

'Abdur Razzāq is referring to the invasions of Bengal by Sultan' Ibrāhīm of Jaunpur (R. 1401-1441 A. C.). A Hindu Rājā of Bhatauria named Ganesh or Kans is said to have subjugated the kingdom on accountof the youth and incapacity of Sultan Shamsu-d-din and begun to oppress the Muslims. A Muhammadan saint named Nur or Qutbu-l-'Alam then invited Ibrahim Shah of Jaunpur to come and succour his brethren in the Faith. Hostilities having continued for sometime, Ganesh agreed to a compromise and allowed his son Jaimal or Jadu to be converted to Islam and ascend the throne as Sultan Jalalu-d-din. Ibrahim was persuaded by the saint or thought it advisable to withdraw and peace was restored. (Riyāzu-s-Salātīn, Tr. 113-7; F. II. 297, l. 12). Numismatic evidence has been recently forthcoming which bears out this account. There can be little doubt that the coins of Danujamardana, which exhibit the Shaka dates 1339 and 1340 (820 and 821 A. H.), were struck by Rājā Ganesh. (Bhattasāli, Coins of the Early Sultans of Bengal, 109-116; Stapleton, Num. Sup. to the J.A.S.B. No. XLIII (1930), Art. 298, pp. 1-13). Some years afterwards,

e. in or about 834-5 H (1431 A C), Sultan Ibrābīm appears to have again invaded Bengal, when Shamsu-d-dīn Ahmad, the son of Jalālu-d-dīn, was on the throne and it was Shamsu-d-dīn who preferred the complaint to Shāhrukh of which 'Abdur Razzāq speaks here Shamsu-d-dīn is said to have reigned from 834 to 850 A H (1430 1446 A C.). (Riyāz, Tr. 118 note).

IV 100, l 1 from foot The blacks of this country go about with nearly naked bodies, wearing only languts

This is perhaps the earliest example of the use of this familiar vernacular word by a Persian writer The scanty clothing and semi nude condition of the poorer classes in India has been remarked by many travellers from foreign parts Alberuni writes thus of the Hindus of his day "They wear turbans for trousers Those who want little dress are content to dress in a rag of two fingers' breadth which they bind on their loins with two cords" (I 180) Ibn Batūta calls it "a scrap of stuff tied by a string round the waist" (E D III. 619) Babur not only describes the 'rag'. but calls it by its Indian name "Peasants and people of low standing", he states. "go about naked. They tie on a thing called lunguta, a decency clout which hangs two spans below the navel From the tie of this pendant decency clout, another clout is passed between the thighs and made fast behind." (B N Tr 519) Tavernier observes that "in India the peasants have for their sole garment a scrap of cloth to cover those parts which natural modesty requires to be concealed " (Travels, Tr Ball, I 391) Varthema (Tr Badger 113-4) and Nikitin (Major, India in the Fifteenth Century, Ch III. 8-9, p 9) had noted the fact long before Tavernier.

IV 103, l 3 It is said that the King of Bijanagar has 300 seaports every one of which is equal to Kālīkot.

A palpable exaggeration But 'Abdur Razzāq is merely repeating the random gossip he had heard in Vijayanagar Southern India has a very long coastline and is dotted with several ports. The Kingdom of Vijayanagar stretched far and wide and Devarāya II is styled, not without justice, Dak shina Samudrādhipati, Lord of the Southern Sea, in two contemporary inscriptions dated in Shaka 1362 and 1368=1440 and 1146 A C (Ind. Ant LVII 1928, pp 78-79) But Calicut has possessed, for ages, the reputation of being one of the greatest, safest and wealthiest harbours in India or perhaps the world. Many of the so-called 'ports' on the coast were only roadsteads and it is impossible to accept the statement that every one of the 300 'seaports' was equal in safety, extent and prosperity to the world-famed haven of Calicut India has many 'ports,' but very few really good harbours

IV. 103, l 25 At the distance of three parasangs from Mangalūr, he saw a temple which has not its like on the earth.

The whole is made of molten brass

This must be meant for the shrine at Kādiri, about two miles distant from Mangalore. It is still the chief seat of the 'Kānphāţīa' (split-eared)

Jogis, who are disciples and followers of Gorakhnāth. (Hobson Jobson, s.v. Jogi). The 17th century Italian traveller, Pietro della Valle, who visited it, has left a very long description of it. He states that the inner sanctuary, and in former times, the whole enclosure, was all covered with plates of brass, and he also describes a great brazen pillar and a huge brass candlestick of five branches. (Travels, Ed. E. Grey, 345-348). There is a more modern account in Eastwick's Handbook for India. Pt. I. Madras, 236.

IV. 103, l. 20. [I] departed from Kālikot and passing by Bandāna.....

arrived at.....Mangalūr.

'Bandāna' is Bandarāina or Fandarāina, the modern Pandarāni or Pantalyāni, an old port on the coast of Malabār, which was situated a little north of Quilāndi and opposite to the Sacrifice Rock of modern maps. Lat. 11°-26′ N., Long. 75°-50′ E. Koilāndi or Quilāndi has now supplanted it. Ibn Baṭūṭa says that "the Chinese junks in his day used to pass the winter (i. e. the south-west monsoon season) at Fandarāina, as it afforded an unexceptionably safe shelter for shipping". (Defrémery, IV. 88). See also H. J. s. v. Pandarani. Quilāndi is shown in Constable, A a, 35. It lies about twenty miles north of Calicut.

IV. 104, l. 13. I arrived at the city of Bidrur, of which the houses were like palaces. In Bidrur there is a temple so high that you can see it at a distance of several parasangs.

Dowson's proposed identification with Bednore will not bear examination. Bednore, also called 'Bidarūr' or 'Bidaruhalli', i. e. 'Bamboo village', was not a place of any note in the days of 'Abdur Razzāq. Its importance dates only from about 1640 A.C., when it became the capital of the Kelādi Kings of Ikkeri. (I. G. XVIII, 296). There is also no ancient temple at Bednore answering in any way to this description. The reference seems really to be to Belūr and to the Chenna Kesava or some other great shrine at Belūr in Ḥassan district, Mysore. (q. v. I. G. XIII. 64). Dowson notes that Langles reads "Beylour" and Quatremère "Belour". Major also (India, Ch. I. p. 20) has "Belour" and there can be little doubt that 'Belūr' is the place intended.

IV. 105, l. 17. Account of the city of Bijanagar and its seven surrounding fortifications.

"Surrounding" does not express the author's meaning. The words used in the original Persian text are 'check to 'check to 'Abdur Razzāq means that "the fortifications or walls were comprised one within the other." Elsewhere, he states that the city had 'seven fortified walls one within the other.' (p. 106 infra). At p. 109 also, he observes that the elephant stables were situated "between the first and second enceinte of the city". Nicolo Conti who paid a visit to Vijayanagar about 1420-1440 A. C. writes that the circumference of the city was sixty miles. (Major, India in the Fifteenth Century, II. p. 6). Some Hindu accounts and local traditions also reckon its superficial area as sixty-four square miles. 'Abdur Razzāq himself writes that the distance between the Northern gate of the

outer fortress and the Southern, and that also between the Eastern and the Western was two statute parasangs, that is, between seven and eight miles (p 107 infra). The existing remains at Hampi bear witness to the substantial correctness of his statements. "The ruins of the city", says Mr. Longhurst, "cover some nine square miles, but the fortifications and outposts included a far larger area. The whole site is dotted with barren rocky hills and up the sides of these hills and along the low ground between them, often in several lines, one behind the other, run the fortified enclosing walls of the old city" (Hampi Ruins, pp 1-3) Mr Sewell estimates that the fortifications extend from south to north for about 12 miles and from west to east for about 10 miles. (A Forgotten Empire, 83, 88-90).

The ancient Hindu standard of town-planning seems to have required every first class capital city or metropolis to possess seven concentric fortified enclosures. Bishnupur in Bānkūra district, the old capital of the kingdom of Karna Suvarna in the 8th century A. C., is said to have been surrounded by seven lines of fortifications (I. G. VIII. 248) 'Utbi (E. D. II. p. 46) states that when Mahmūd invaded Qanauj, he was able to take all the seven fortifications, i. e walls round that populous town, in one day. Another example of this ancient architectural canon or ideal is found in the great temple of Srīrangam, which "consists of seven enclosures, one within the other" (I. G. XXIII 103). Ginji or Jinji also is said to have had seven forts. (Maāsiru-l-Umāra, II. 96). Kāmatāpur in Kūch Bihār is also stated to have been surrounded by several enclosures, one within the other. (I. G. XIV. 327). The underlying idea of seven enclosures is of very great antiquity. Nineveh had seven walls which are said to have symbolised the seven spheres of the Geocentric Planetary System

IV 105, l. 5 from foot The army consists of eleven lacs of men

These mammoth figures may appear incredible, but similar estimates are found in several other authors of repute. The Portuguese writer, Paes, estimates the strength of the Vijayanagar army at a million fighting men (Sewell, F. E. 279). Nuniz states that an army of 7,03,000 infantry, 32,600 cavalry and 551 elephants was despatched by the King of Vijayanagar against Rāichūr. (*Ibid.*, 147, 326-7). Conti declares that the Vijayanagar army consisted of a million and upwards. Firishta tells us that Deva Rāy I invaded the Rāichūr Duāb in 801 A. H. (1398 A. C.), with an army of 30,000 horse and 900,000 foot. (I. 309, I. 17). Another Vijayanagar king is said to have led an army of nearly a million infantry and guiners against Ahmad Shāh Bahmani in 826 H. =1422 A. C. (*Ibid.* I. 320, I. 17).

Equally staggering figures are given by other travellers and historians for the numerical strength of the forces of their Musalman adversaries, the Bahmanis Nikitin notes that in 1442 A C the Sultan of Gulbarga, who attacked the Hindus, had in his train 900,000 foot, 190,000 horse and 575 elephants (Major, III. 27-8, Sewell, l c 105) Wassaf asserts that 'Alauddin Khalji maintained an army of 475,000 men (E. D III 50) and Barani

tells us that Muhammad Tughlaq raised a force of 370,000 horse for the invasion of Khurāsān. (*Ibid*, 241). Mr. Sewell gives it as his opinion that "there can be no reasonable doubt as to the large numbers, though they were not well-armed or well-trained or well-disciplined". (*Op. cit.* 150).

IV. 105, l. 10 from foot. Whose kingdom extended from the borders of Sarandip to those of Kulbarga and from Bengal to Malibar, a space of 1,000 parasangs.

The Vijayanagar kingdom was extensive, but these figures are, undoubtedly, inflated. 1,000 parasangs would, at the lowest computation, be equal to 3,000 miles. 'Abdur Razzāq cannot intend to say that the total area was only 3,000 or 4,000 square miles. But if he means that either the length or the breadth of the kingdom was 3,000 miles, it is an incredible asseveration. The total length of the Indian sub-continent is about 1,900 miles and its breadth 1,500. Most of such predications of territorial extent in Persian and Arabic writers are unverified repetitions of random guesses or popular clap-trap of no scientific value. The Vijayanagar kingdom, even at the zenith of its greatness, comprised only that portion of the Indian peninsula which lies south of the river Krishna.

IV. 109, l. 1. On the left of the palace there is the mint.

The ruins of the building seen by 'Abdur Razzāq appear to be still extant at Hampi. "On the south-west of the king's audience hall," says Mr. Longhurst, "is a large walled enclosure which is generally said to represent the ruins of the Royal Mint.....and this conjecture is probably correct." (Hampi Ruins, 70).

IV. 109, l. 7. Of pure silver, they make a coin equal to a sixth of a fanam, which they call tar.

'Abdur Razzāq's account of the Vijayanagar Coinage is not very correct. He speaks of the Varāha as weighing about one migqāl, i. e. about 72 grs., but the real weight of the specimens in our collections is nearer 50 than 72. No gold fanams of any of the Kings of the First Dynasty of Vijayanagar have been found. Nor has a single silver coin of Devarāya or any of his predecessors been discovered. (Hultzsch in Ind. Ant. XX. (1891), p. 301; Sir Walter Elliot, Coins of Southern India, 97-99 and Note).

Again, 'Abdur Razzāq says that the tār was one-sixth of a fanam, but Pyrard de Laval (Voyage, Tr. A. Gray, I. 344, 412), Claude Dellon (Voyages, Ed. 1711, p. 233), Fryer (New Account of East India and Persia, Ed. Crooke, I. 149) and several other authorities are unanimous in making sixteen tārs or tārés go to the fanam. It is possible that 'sixth' is an error for 'sixteenth'. (Dames, Tr. Barbosa, II. 52-53, Note). Sir Walter Elliot states that the tārés in his cabinet weighed only about 1.7 grs. each. (Coins of Southern India, 1885, p. 57).

IV. 109, l. 10 from foot. Opposite the minister's office are the elephant sheds.

Visitors to Hampi are still shown by the local cicerones the ruins of a structure which is locally known as the Elephant-stables. "It is

a long oblong building just opposite the Zenāna Enclosure (Queens' Palace), containing eleven roomy stalls or rooms with lofty domed roofs. Unfortunately, there is nothing but local tradition in favour of the attribution and the absence of any iron rings or bars embedded in the floors or walls for the purpose of chaining the animals "appears to largely invalidate the traditional identification. (Longhurst, op cit. 86) A plate showing the massive range of these buildings is given by Mr. Sewell, who quotes 'Abdur Razzāq's description, but does not express any doubts as to its having been the Hāthi Khāna. (F E 94)

IV 109, last line. The palace elephants are fed on Kichū [Kichri]

Balls of about two mans each are placed by the keepers in the mouths of the animals.

The Indian Man has varied so greatly from place to place and even from time to time in the same place, that it is not always easy to say what it stands for But there can be little doubt that the Man mentioned here could not have been equivalent to 40 or 28 or even 25 avoirdupois lbs No Mahawat or keeper could have lifted and thrust into the mouth of even the most docile tusker a ball of buttered Khichri of even half the weight Elsewhere, 'Abdur Razzāg informs us that while he was at Vijayanagar, he was daily supplied with five Mans of rice, one Man of butter and one Man of sugar (113 infra) As he does not appear to have had a large retinue, and does not refer to any followers, this Man also must have denoted some unit of low ponderary value As Abdur Razzaq came from Shirāz, his Man must be the Tabrīzī which is equivalent to about 67 lbs (Lockyer, An Account of the Trade in India, 1711, p 230 apud Yule, H J s v Maund) We have here perhaps the earliest example of the occurrence of the Hindi word Khichri in a Persian writer Jauhar calls it by the hybrid name Dal-Khushka (Stewart's Tr Reprint 108).

IV 110, l 9 from foot They tell the following story of an elephant that fled from his bondage, etc.

This traveller's tale extolling the sagacity and wariness of elephants who have been trapped and afterwards escaped from captivity is found "These people [the also in at least two European authors of later date elephant hunters in Mysore] told us," writes Tavernier, " an astonishing thing which is wonderful, if one can only believe it. It is that if elephants have once been caught and have escaped, if driven into the woods, are always on their guard and tear off a large branch of a tree with their trunks, with which they go along, sounding everywhere before putting down their feet, to see if there are any holes, so as not to be caught a second time It was this which made the hunters despair of being able to recapture the three elephants which had escaped from them" (Travels, Tr. Ball, I 274-5) Manucci tells the same tale, but perhaps he got it, like several others of his yarns, at second hand from the Frenchman. (Storia, III 78) Abul Fazl also relates two anecdotes of the cunning devices employed by some of these pachyderms for securing the release of their

captured young ones. (Ain, Tr. I. 123). Mas'ūdi repeats a curious story of the pudicity and humanity of an elephant belonging to the King of Manṣūra. (Sprenger, I. 387). The well-known story of the elephant and the tailoralso seems to be of Indian origin. It is found in the Javāmi'au-l-Ḥikāyāt of 'Awfi, who says that he had heard it from a friend who had practised the physician's art in Nahrwāla. (Nizāmu-d-dīn, J. Ḥ. p. 253).

IV. 110, last line. One of the keepers mounted a tree under which the elephant was likely to go.... and threw himself down on the back of the animal.

This extremely hazardous trick or method of mastering these huge beasts is mentioned by Shams-i-Siraj in his account of Firūz Shāh Tughlaq's elephant-hunt in Jājnagar. (T. F. Text, 169=E. D. III. 314). The Emperor Jahāngīr also has left it on record that his intrepid father Akbar had often controlled and tamed in this way "Mast elephants, which had, in their fits of rage, killed even their keepers. He would place himself on a wall or tree near which a mad elephant was passing and throw himself on its back and thus, by mere mounting, bring it under control and tame it. This was repeatedly seen." (T. J. Tr. I. 38; Text, 18, 1.3). IV. 111, l. 9 from foot. The policemen's pay is derived from the proceeds of the brothels.

This was one of the most notable features of the "Ancient Hindu Polity" and is distinctly mentioned in all the Sanskrit works on Rājniti. (Kauṭilya, Arthashāstra, Bk. II. xxvii; Tr. Shāstri, 153-5). It is referred to by Alberūni also (India, Tr. Sachau, II. 157), and Waṣṣāf. (E.D. III. 33). The old Soolāi Bazār or 'Dancing Girls' Street' of Vijayanagar is still pointed out at Hampi to visitors by the guides. (Longhurst, 110). Tavernier (Tr. Ball, I. 157-8), and Thevenot (Travels, Tr. 1687, Part III. 97) have left graphic descriptions of the system of licensed prostitution which was maintained for revenue purposes by the Quṭb Shāhi Sultans of Golkonda. IV. 112, 1. 3 from foot. Interview with the King of Bijānagar.

The King whom 'Abdur Razzāq saw was Devarāya II, the son of Vijayarāi or Bukka, and the greatest emperor of the First Dynasty. He reigned for about twenty-five years from Shaka 1342 to 1368 (1420 to 1446 A.C.). His greatest minister and general was Lakkanna Dandanāyaka, who conquered Ceylon and invaded Gulbarga. 'Abdur Razzāq states that Devarāya encouraged Arab merchants to bring good horses and paid handsomely for them. This is borne out by a contemporary inscription from which it appears that Devarāya had a cavalry force of ten thousand Muslims, mounted on Turkish horses, and he seems even to have erected a mosque for them in Hampi. (Ind. Ant. 1928, pp. 77-81).

IV. 114, l. 14 from foot. Delicacy forbids me to expatiate on its invigorating and approaching virtues.

This statement about the aphrodisiac properties of the humble betel-leaf may sound strange in modern ears but it is affirmed as an undoubted pharmacological fact by several of the old Arab travellers, e g. Mas'ūdi, (Prairies, II 84) and Alberuni (Tr II. 152). Ibn Batūta also states that it sweetens the breath, helps the digestion, elevates the spirits and stimulates to venery. (Tr Lee, 59). Sir T. Roe assures us that "it accords rheume, cools the head and strengthens the teeth, and is all their phisicke". (Journal, Ed Foster, I 19).

IV. 116, last line and footnote. The person who had brought the invitation of coagulated milk was also put to death

Dowson under کسی که دعوت حرات آورده بود Dowson under stands the phrase to indicate that "it was customary among the Hindus of Vijayanagar to send coagulated milk with the invitation." But the words used by 'Abdur Razzāq do not lend themselves to any such inference or is nothing more than a Persian دعوت خرات is nothing more than a idiom, a façon de parler, originating in the usages of the Tatar conquerors of that country. Curdled milk was the staple food of those nomads and when a Tatar or Mongol was "invited to dinner," he was invited to a feast of 'Jaghrat' or curdled milk Just as the Englishman 'on hospitable thoughts intent' asks a friend to come over some day and 'cut mutton' with him, the Mongol giving an entertainment spoke of it as a friendly summons "to drink a bowl of Jaghrat" In the Court ceremonial of the Uzbeg princes. Dr. Barthold tells us, "the drinking of Qumis (soured milk) was treated as an important affair, it is described minutely, how it has to be poured from skins, how the cups are to be taken, who are to take the first cups, who the other cups, etc" (Houtsma, E. I s v. II 1116) An invitation to drink this Qumis or Jaghrāt, "soured milk", was, in fact, an invitation to a banquet. Mr. Major translates the sentence thus "The man who had brought the letters of invitation was put to the last degree of torture" (I 35) In this connection, it may be worth while to note that the contemporary author of the Intikhāb-i-Jahāngīr Shāhi, (E D VI 449) says that the Emperor "used to give feasts every Friday to about one thousand destitute Muhammadans and that he always ordered curds to be given to them while they were cating their dinner." Compare also the old English word 'junkets' and the secondary or derivative use of 'junketting' in the sense of 'entertainment, picnic, feasting '.

There is no reference to this assassination plot in the inscriptions of the Vijayanagar dynasty, but the Portuguese Fernão Nuniz tells a story which bears a striking resemblance to it in many particulars. Only, he relates it, not of Deva Rāya II, but of his son and successor. "A nephew whom he had brought up in his house like a son" invited the king and all the principal nobles to his wedding-feast, had all the ministers and captains murdered just in the same way, in separate rooms by assassins, whose task was made easy because "it is the custom there to place the food on the table and there is no one present except those who are going to eat". The conspirator then went to the king himself with a present, wounded him in several places with a poisoned dagger, but the king freed himself.

at last from his assailant, despatched him with a sword and came out of the palace, holding his nephew's head in his hand. "Dreadful punishments were inflicted on the traitor's accomplices, but the king himself died of his wounds, six months later". (Sewell, F. E. 303-4). Though some of the details here are different, it is, as Mr. Sewell says, substantially the same story and 'Abdur Razzíq's version may be even "the more reliable, because he was a contemporary witness." (Ibid. 72).

IV. 117, l. 7. The celebration of the Mahaninci [at the full moon of Rajab].

Alberuni thus describes this festival: "On the eighth of Ashvayuja, when the Moon stands in her 19th station, Mūla, begins the festival of the Mahānavmi, the wife of Mahīdeva, when they offer the first fruits of sugar and all other things to her image, which is called Bhagwati. They also give much alms before it and kill kids". (Tr. Sachau, II. 179-80). Nicolo Conti who visited Vijayanagar about 1420-40 A. C. speaks of the people celebrating certain feasts which correspond to the Dīpāvali, Holi and the Dashahrā. The last of these three is identical with the Mahānavmi. (Major, II. 28-9). Nuniz who wrote about 1530-1542 A. C. states that the Mahānavmi was celebrated in September, "when for nine days they make great feast" and he gives a long description of the ceremonies. (Sewell, F. E. 376-8). Paes also states that he witnessed it from 12th September in 1520, A. C. (Ib. 263). The Tibba or platform from which the kings watched the festival is still pointed out by the guides to visitors. It faces "the wonderful expanse of ground" of which 'Abdur Razzāq speaks on 1.5 f. f.

The Hijri date given by 'Abdur Razzīq for the celebration of the festival appears to be wrong. The 1st of Rajab 817 A. H. corresponded to 25th October 1443, while the 1st of Ashwina in that year synchronised with the 24th of September and 1st Kūrtika was 24th October. If the festival described by him was the Mahānavmi, Rajab must be an error for the preceding month, Jumādi II. If the month was Rajab, the festival must be that of the Dūcāli or New Year. (See Sewell, loc. cit. 93).

IV. 117, l. 5 from foot. The full moon of Rajab (September, 1446).

The Julian correspondence given by Dowson in the parenthesis is not correct. The Hijri year must have been 847. 'Abdur Razzāq tells us that he left Persia in S45 H. He was in Kirmān on the 18th of Rajab of that year (p. 95 ante), at Quriāt in Muḥarram 846 (p. 97), and in Kālikot from Jumādi II. to the middle of Zī-l-ḥijja (p. 102). He reached Vijayanagar at the close of Zī-ḥijja, 846 (p. 105). He was there on the 1st of Muḥarram 847 (1st May, 1443 A. C.). The first day of Rajab S47 H. corresponded to 25th October, 1443 A. C. and the full moon of Rajab must have been therefore observed on or about the 6th of November, 1443, not in September 1446 A. C. In this connection, attention may be drawn to Dowson's note on p. 122 infra, where it is said that the expedition to Gulbarga, which is described a few lines lower down, is recorded by Firishta in the ann als of 847 A. H. (Briggs, Tr. II. 403). Later on, Dowson

himself states that Ramazīn 847 corresponded to January 1444 and 1st Muharram 848 to April [20th] 1444 (pp. 124 and 125 infra).

IV. 122, l. 4. The King had appointed as a temporary substitute of the Brahman Danāik a person named Hambah Nūrir, who considered himself equal to the Wazīr.

Major (loc cit. I p. 41) reads 'Nimeh-pezīr' which is not a whit less cryptic or unintelligible than 'Hambah Nūrīr' I suggest that what is intended is the Malayalam Nambyadiri or Nambiyatiri, which means "a general or prince" (Logan, Malabar, I 121) 'Abdur Razzāq speaks as if it was the personal name of the Danāik's deputy It was in reality, only the designation of his office, a general epithet or title It may be as well to say that this word is entirely distinct from Nambūdiri or Nambūri, a Malabar Brahmin. (Hobson Jobson, s v Nambeadarim and Nambooree). 'Danāik' is the Canarese form of the Sanskrit Danāanāyaka.

IV. 123, l. 3. Fath Khān, one of the descendants of Sultan Firozshāh also sent a Deputy.

This Fath Khān must be the person mentioned by the author of the Tārīkh-i-Mubārakshīhi (Text, 208, 1.16, 220, 1.11=E D IV 64 and 71) as the Khān-i-'Azam Fath Khān, son of Sultān Muzaffar [the First] of Gujarāt He was not 'a descendant' of Firūzshāh Tughlaq himself, but of one of that Sultān's nobles The error is excusable in a casual sojourner like 'Abdur Razzāq The original title of Sultān Muzaffar I was Zafarkhān, and he was the son of Wajīhu-l-Mulk, who is said to have been originally a Hindu named Sahāran or Sadhāran, whose sister had, under romantic circumstances, become a wife of Firūz. (Mīrāt-i-Sihandari, Bombay Lithograph, 1831, p 7, 1 5, Bayley's Tr p 67; Tr Fazlulla, 1-3)

IV 124, l. 17 We arrived on the 1st Ramazan (January 1444)

The Julian correspondence is not quite correct It was 23rd December 1443 A C.

IV 124, l 5 from foot. [From Mangalūr], I went to the port of Hanūr.

The wav is a consonant and the name should be read as 'Hanawar', te 'Onawar' in Canara It is called 'Honore' or 'Onore' in old maps and in Forbes' Oriental Memoirs (2nd Ed II 455 et seq) It is the 'Hinaur' of Ibn Batūta, who says that "all the Musalman women of the town had the Qur'an by heart and that it contained 23 schools for boys and 13 for girls, such a thing as he had seen nowhere else in his travels' (Tr Lee, 165-166, Defrémery, IV 64-67) It is Rashīdu-d-dīn's (E. D. I 72) Hawāriūn, which can be read as Hanāwār if the letters are transposed

IV. 124, last line. I consulted the book, of presages compiled by Imâm
J'afar Sādīk

'Abdur Razzāq is referring to the 'Ilm-i-Jafi', a cabalistical mode of divination which is in great favour with the Shi'as, as it is supposed by them to have been studied and perfected, if not invented, by their great Imām, J'afar-i-Şādiq Tippu Sultān's Library contained a large quarto

(

MIRKHWÄND written in the Naskhi character, entitled جنرجامي, about which Stewart says that the cabalistical tables and diagrams in it are supposed to have IV. 135 l. 6 from foot been originally constructed by 'Ali and are believed to prognosticate all important events in the history of the world and especially of Islam. (Catalogue of Tippoo Sultan's Library, p. 104. See also Macdonald's art. on Djafr in Houtsma, E. I., I. 994-5). Budāuni speaks of a Sayyid Mirak Ispaliāni having attempted to give a demonstration of his skill in this art by foretelling the defeat and death of Daud Kararani in 983 A. H. In a caustic note on the subject, he cites with approval the poet Jami's satirical verses on this pseudo-science and gives it as his own opinion that it is naught else than forgery and fabrication and that 'any one who has a little thinking power can invent the like of it. (II. 177=Lowe. Tr. 180; see also T. A. Text. 317, l. 10; E. D. V. 376). Elsewhere, Budāuni mentions another professor of this system of sortilege, named Khwājā Maulānā Shirazi. (Text, II. 287). Lowe (Tr. II. 295) has not understood the meaning correctly, as he describes this person as 'the heretic of Jafrdan', as if Jafrdan' was the name of the place he came from or belonged to. really signifies "the heretic who was proficient in the art of Jair."

The vessel after leaving Maskat, arrived at the port of IV. 126, l. 1.

Khur-i-fakan was on the open sea, south of Cape Mussendom (Musandam) and not very far from it. It was a thriving town, until Albuquerque sacked and burnt it in 1507 A.C. The name is derived from the Arabic 33-, an estuary or creek. It is shown in the Map appended to the second volume of Lord Curzon's Persia. (Dames, Tr. of Barbosa, I. 72.73 Note). Ibn Batuta says Khor Fakan, Qariyat and Sohar are all

IV. 135, 1. 12 from foot. Amir Kazi, Nuh bin Mansir. towns of 'Oman. (Defrémery, II. 229).

'Amir Kazi' is wrong. The right reading is Amir co', 'Razi' or Rizā'. It was the after death title of Amīr Nuh bin Mansur-i-Sāmāni, who came to the throne in 365 H. (Rauzat, Jild, IV. 29, 1.9; Gardezi, Z.A. 48,58). He is called Mir Razi (or Rizi) in a Qasida of 'Unsuri. (Lucknow Lith. of 1922 A. C., p. 55, couplet 3). Utbi calls him Riza Nuhibn Mansur. (Tr. Reynolds, 44, 128). The after-death titles of the Samani Amīrs are meticulously recorded by the historians. Mirkhwand says that Ahmad bin Ism'ail was styled 'Sultān-i-Shahid', Naṣr bin Aḥmad 'Amīr-i-S'aid', Mansur bin Nuh, 'Amīr-i-Sadīd'. (Rausal, IV. 16, 17, 21; see also Gardezi, Z. A. 22, 25, 47, 48, 58; Raverty, T. N. Tr. 33, 40, 44; Alberuni, Athāru-l-Bāqiya, Tr. Sachau, 131).

IV. 135, l. 6 from foot. Sultan Mahmud departed from this perishable world.....on Thursday, the 23rd of Rabin-lakhir, A. H. 421, in the sixty-third year of

There is some discrepancy among the later compilers about the date. but 23rd Rab'i II Hisabi or 22nd Ruyyat must be correct, as it is in accord not only with the statements of Alberūni (Tr Sachau, II 2 and 358), Baihaqi (Text, 11-12), and Gardezi (Text, 92, 1 11) but also the inscription on Mahmūd's sarcophagus at Ghazni (J A S B. XII 76-7) Raverty gives (T N Tr 87 note) 14th Rab'ī II. 421 H, on the authority of the Muzmil-i-Fasīhi and this is followed in the C H I (III 26), but it must be wrong Fasīh's chronology is, as Dr Barthold has pointed out, often faulty (Turkestan, 251 Note) The Julian equivalent of 23rd Rab'ī II, 421 H., was Thursday, 30th April, 1030 A C. Sir W Haig gives 21st April 1030, but it cannot be correct as it was a Tuesday Fasīh's and Raverty's 14th Rab'ī II cannot be right as the 14th was not a Thursday, but a Tuesday

IV. 136, l 3 It was a great blemish in his character that he was exceedingly covetous

E G Browne points out (L H P II 119) that these animadversions on Mahmüd's greed for gold and the story of the unjustly accused citizen of Nishāpur have been copied by Mirkhwänd from Ibnu-l-Athīr Browne himself goes so far as to say that Mahmūd was not a patron of poets at all, but "a great kidnapper of literary men like Avicenna, Alberūni, Firdausi and others, whom he treated in the end scurvily enough" But this judgment or rather denunciation is unduly severe

IV 137, l. 17. In the spring, he [Mas'ūd] assembled a very large army and marched towards Khurāsān for the purpose of expelling the Salyūhis

What Mirkhwand really says is that Mas'ud intended to assemble, in Hindustan, a large army in the ensuing spring and then march towards Khurasan for the purpose of exterminating the Seljuqs, who had defeated him in the preceding year. It was not an accomplished fact, but only a part of a project or plan of operations. He never assembled the army and never marched again to Khurasan Cf Baihaqi in E D II 149-50, 152 It may be as well to cite Mirkhwand's own words.

سبت آنکه در آن حدود قالاق کند و موسم سار سپاهی یش از شار ترتیب داده (Rāuzāt, Jīld, IV 53)

IV 141, l. 6 It [the Khulāsatu-l-Akhbār] was written by Mirkhond's son. Khondamīr

Dr Rieu has conclusively shown (Cat of Pers Mss I 96, III 1079) that Khwāndamīr was neither the son nor the nephew of Mīrkhwānd, but the son of his daughter Khwāndamīr himself explicitly says so in the Habību-s-Siyar, (Bom Inth Jild, III Juzu 3, 171, 178, 198) and the same statement is made by Sām Mirzā in the Tuhfah-i-Sāmi, and by Amīn Rāzī in the Haft Iqlīm See also Muqtadir, Bānkīpur Catalogue, VI 25

IV 142, l 28 He [Khwāndamīr] resided at Basht, a village in Georgia. Rieu points out that Basht is not in Georgia, but in 'Gharjistān' (op cit I 96, Supplement, 19 See also Houtsma, E I, II 899) 'Gharjistān' and 'Gurjistān' are often confused together Gharjistān lies on the upper course of the Murghāb in the vicinity of Ghūr. Gurjistān is east of the Caspian Even Raverty confounds the two toponyms

(T. N. Tr. Index, p. 189). Khwāndamīr died in 942 H. not 941, as Elliot says (143 infra). B. I. 343; Tr. 450; H. Beveridge in Houtsma, II. 399. IV. 148. l. 2. Dastūru-l-Wuzrā.

The date of composition is not mentioned in Elliot's bibliographical notice. It is 915 H. and the title itself is a chronogram. (4+60+400+6+200+1+30-6+7+200+1=915). (Rieu, loc. cit. I. 335; Muqtadir, VI. 26). Elliot observes that there is a later work on the same subject entitled Irshādu-l-Wuzarā, but 'Awfi says that Sultān Ibrāhīm Ghaznavi wrote for the guidance of his own ministers, a Dastūru-l-Wuzarā and he cites it as the source of one of his anecdotes. (Nizamu-d-dīn, J. H. 67-8, 224). Khwāndamīr had written before this, the Maāsiru-l-Mulūk, a similar work on the institutions, foundations and wise sayings of Kings. It is mentioned a few lines lower down and there is a copy of it in the British Museum. (Rieu, Supplement, p. 18). Shams-i-Siraj also in his Tārīkh-i-Firūz-shāhi quotes a passage from a Dastūru-l-Wuzarā. (Text, 283, last line).

IV. 151, l. 7. He [Ahmad bin Hasan Maimandi] died in 444 A. H.

The Bombay Lithograph of the Rauzat (IV. 52) gives the date as 424 H. which is correct. See also infra 196 and F. (I. 38, l. 18) where he is said to have died in 424 H. Baihaqi gives the exact date as 25th Muḥarram 424 H. (Text, 454, l. 9). The T. A. (11, l. 4 f. f.) and Budāuni (I. 22—I. 35), following Gardezi (98, last line), give 423 H. In any case, 444 is undoubtedly wrong and due most probably to a typographical error. As Mas'ūd came to the throne only about the middle of 421 H., Aḥmad was not his Vazīr 'for a long period', but only for a little more than two years.

IV. 152, l. 19. Abū-l Husain Akbali.

The copyist has dropped one of the two dots of the third letter of the nisba. The correct reading of the sobriquet is 'Uqaili as in Baihaqi. (E. D. II. 74). 'Uqail is explicitly stated by that contemporary chronicler to have been the name of Abu-l-Ḥusain's grandfather. (183, l. 4 f. f.). 'Uqail was the name of the ancestor of Muḥammad bin Qāsim—the conqueror of Sind. (Bilāduri in E. D. I. 119 and Chachnāma in Ibid, 157; Ranking, Tr. B. I. 11 note). The anecdote itself is related by Baihaqi in much greater detail, though with some variations. (Text, 453).

IV. 161, 1. 9. [Subuktigin] ordered that he [Abul Fath Busti] should be appointed professor of the "belles-lettres".

issued orders for appointing him Head of the Department of Correspondence." The 'Diwān-i-Inshā' seems to have been another name for the 'Diwān-i-Risālat' of Baihaqi. (Text, 122; see also E. D. II. 512). The chief duty of the head was to write the Sultān's letters to foreign princes, provincial governors and other great officials. He also deciphered all secret or confidential reports and submitted them to the Sultān. (Barthold, Türkestan, 230; Nāzim, M. G. 141).

IV. 163, l. 15 and foot note. Subúktigin declared Ism'ail, who was born of the daughter of Alptigin, his successor.

The lithographed text of the Habību-s-Siyar has سرة دختر البكيري (Vol II Pt iv., p 19) Dowson suggests that we should read المرابع instead of مره دخري instead of المره دخري instead of المره دخري و grandson on the daughter's side 'The phrase is used in this sense in the Persian translation of the Bāburnāma, (Bombay Lith 204, 1 14) and also in the Maāsiru-l-Umarā (III 241, 1 9) Richardson says in means a daughter's son and المرابع والده دخترية 'a son's son' The historian Ziāu-d-dīn Barani says of himself that he was the المدادة عند المدادة المدا

IV. 167, l 11 His [Mahmūd's] age was sixty-three years and he reigned thirty-one

This is copied from Hamdulla's Tarihhi-Guzida (401, 1.13) If Subuktigin died in Sh'aban 387 H, and Mahmūd in Rab'i II, 421 H, as Khwāndamīr himself says, there must be some error in the computation The T A, and F assert that Mahmūd reigned for thirty-five years, which is also inaccurate Dowson makes the Tabaqāt-i-Nāsiri say that he died after a reign of thirty-six years (E D 270, Text, p 11, 1.14). But Raverty points out that the reading in the best manuscripts is 'thirty-three'. (Tr. 88) As some time must have elapsed before Mahmūd was able to defeat and dethrone Ism'ail, the length of his reign must have been about thirty-three lunar years 'Thirty-one', 'thirty-five' and 'thirty-six' are all miscalculations

There are three opinions about the date of Mahmūd's birth Minhāj gives Thursday, 10th Muharram 361 H (T N Text, 9, 1, 2, Raverty's Tr 76, E D II 269) in the 7th year of the rule of Bilkātigīn But Hamdulla, Mīrkhwānd, Khwāndamīr, Firishta and others say the year was 357 or 360 H, with the same date and month and week day The Sultān's age at his death is stated to have been 60 or 63 accordingly As calculation shows that 10th Muharram 361 H 2nd November 971 A C was a Thursday, the former date is presumably correct 10th Muharram 357 H.=16th December 967 was a Monday 10th Muharram 360 H=13th November 970 A C was a Sunday.

IV. 169, l 5 Tähir bin Rust, and other Amīrs of Sīstān

"Rust" is evidently wrong The reading in the Bombay Lithograph is 'Zainab' (II Pt iv, p 21, 12) and this is found also in Reynolds' translation of Jurbidhaqāni (p 285) Dr Nāzim, following 'Utbi (Dehli Lith 194, 13 f f), calls him 'Yazīd' (M G 68), but and bear a close superficial resemblance to each other in the Semitic script, if the diacritical points are carelessly marked or transposed and seems to be the correct lection can hardly be mistaken as in Persian writing IV. 170, 1.4 In the Rauzatu-s-Safā it is written.

But Mirkhwand has borrowed the entire passage, which his grandson IV. 177, 1. 14. quotes, almost word for word from the Tarjuma-i-Yamini or the Persian paraphrase of 'Utbi's History made by Jurbadhagani. A comparison of Reynolds' translation of the latter (pp. 315-6) with Elliot's version will

Ilak Khan then craved help from the King of Khutan prove this beyond a shadow of doubt. IV. 171, l. 14.

The title of this potentate is somewhat uncertain. 'Utbi, Gardezi (Z. A. 82, 1. 13) and Baihaqi (E. D. II. 92) all write Qadr Khan, but Mustaufi speaks of him as Qaidū Khān. (Tār. Guzīda, 396, 1.2 f. f.). Dr. Barthold says that the correct pronunciation is 'Qadir Khan' and that it signifies in Turki 'most despotic among kings'. (Turkestan, 273 note). The Khan's Musalman name appears to have been Yusuf.

IV. 173, last line. The wealth obtained [from Bhimnagar] consisted of 70,700 mans of gold and silver utensils.

The Bombay Lithograph of the H. S. has مناد مزار درهم و هنتصد هزار יי וועם נניי פ ביייי (II. Pt. iv. 22), "Seventy thousand dirhams and seven hundred thousand Mans of gold and silver vessels."

'Utbi says: "The stamped coin amounted to seventy thousand thousand royal dirhams and the gold and silver ingots amounted to seven hundred thousand four hundred mans in weight". (E.D. II. 35). F. has "seven hundred thousand dinars of gold and seven hundred mans of gold and silver". (I. 27, 1.1). This shows how the original statement of 'Utbi has been mutilated and distorted by the copyists.

IV. 177, l. 1. After the death of Abu 'Ali, his brother Mamun bin

The correct name of this ruler was Abul 'Abbas ibn Mamun. (Baihaqi, Text, 837, 838; T. A.7, l. 8; F. I. 29, l. 1). Māmūn lin Muḥammad bin 'Ali con quered Khwarizm about 885 H. and was succeeded, on his assassination in 387 H., by his son Abul Hasan 'Ali, who reigned upto 399-400 H. He was followed by his brother Abul 'Abbas bin Mamun, who was murdered on Wednesday, middle of Shawwal 407 H., 18th March 1017 Á. C., at the age of thirty-two. (Baihaqi, 848, 1.5). He married Mahmud's sister Kah Kalji, who had been the wife of his brother Abul Hasan 'Ali also. (Barthold, Turkestan, 147, 269, 275; M. G. 56-7).

IV. 177, l. 14. The general of the army of Khwarizm, Binaltigin. He is called 'Alptigin' by Gardezi, (74, l. 5), Baihaqi (847, 851), Hamdulla Mustaufi (T. G. 400), Nizāmu-d-dīn Ahmad (T. A. 7, 1. 15) and F. (I. 29, 1. 6), which may be correct. The Bombay Lithograph of the Habibu-s Siyar reads Niyaltigin which is also the form found in 'Utbi. (Lahore Ed. 301). Dr. Barthold prefers Alptigin. (Turkestan, 277). Bināltigin [Yanāltigin] is also found. There is some confusion in some of the later compilers about the dynasty ruling in Khwarizm at this time. The Tarikh-i-Guzida and the Nusakh-i-Jahanara speak of it as Farigh unid, but the latter were rulers of Juzjan or Juzjanan, not of Khwārizm. Raverty has followed them (T N Tr. 232 Note) and others have been similarly misled. (Houtsma. III 224)

IV. 179, 1 12 There were sapphires which weighed 600 dirhams.

Khwāndamīr does not say that this was the aggregate weight of several sapphires. He explicitly states that there was only one 'blue ruby' and that its weight was 400 misqāls ورسي ديگرنطنگ باتوت كبود بود بود بود بود الله (Habību-s-Siyar IL Pt. iv p 23, 1 3 f f) Mīrkhwānd also says that there was only one باتوت الردق Gardezi also speaks of only one weighing 450 misqāls (p 76) and 'Utbi agrees with him. (E D. II 45) Nizāmu-d-dīn (T A. 8, 1 2), Firishta (L 29, 1.3 f f.) and B. (I 15, Tr I 25) all declare that there was but one stone and that it weighed 450 misqāls It is open to any one to question the truth or correctness of the assertion itself, but there can be no doubt as to the reading, and there is no justification for altering and rationalising its meaning to fit in with some preconceived opinion See my note on E. D. II. 45, 1 2.

The weight of the stone is here stated as 'six hundred dirhams', because Jurbādhaqāni, from whom Khwāndamīr is copying, speaks of the stone as "a sapphire (or hyacinth) in one solid piece, of azure water, weighing four hundred misqāls, each misqāl equivalent to one dirham and a half" (Reynolds, Tr 456)

18th Sh'abān (l 18) must be an error for 8th Sh'abān q.v 'Utbi in E D II. 45

IV 190, l 12 from foot They would recite three verses, to which it would be difficult to find a fourth etc.

This story of the rhyming match between Firdausi and the poetical trio is found in Daulatshah (Browne's Edit. p 51) and almost all later Tazkiras But it is really more famous than true. In the first place, there is no trace of it in either of the two oldest extant biographies of the Iranian Homer—those of 'Awfi and Nizāmi 'Arūzi In the second, it is founded, as Nöldeke has pointed out, on the supposition that there does not exist in the Persian language any fourth rhyme ending in 'shan', except 'Pashan'. This primary postulate or assumption is false, as 'Dashan' and 'Jasha' may be found in any Dictionary. (The Iranian National Epos, translated in the Journal of the Cama Oriental Institute, No 6 (1925), p 43) E G Browne also (L H P II. 130) has discussed the question fully and rejects the anecdote as spurious.

IV. 191, 1 3 from foot He [Maimandi] repeated several verses out of the Shahnama etc

This story may be true as it rests on the respectable authority of Nizāmi 'Aruzi, who says that he heard it when he visited Nīshāpūr in A H. 514=1120 A C (Chihār Magāla, Tr Browne, 83) The verses repeated by the minister were

اکر حزیکام من آبد جواب من وکرر و مبدان و اوراسیاب

Nöldeke justly says that the "forceful vigour of the lines cannot be rendered by any translation" He observes that he has found the second hemistich in the $Sh\bar{a}hn\bar{a}ma$, but the first line has not yet been traced in the great Epic. (loc. cit. 50).

IV. 192, l. 12. Afzalu-l-Anāmi Maulānā.....Jāmi has written these lines at the end of this story.

Afalu-l-Anām is not a part of the name of Jāmi, but only a laudatory epithet signifying "most learned or excellent of men". Thus, the Arabian Prophet is often called Khairu-l-Anām, "the best of men", and also Afalu-l-Mursalin, "most excellent of the Prophets" by his followers.

IV. 193, l. 11. He [Sultan Muhammad] arrived at Nagīnābād, which was in truth Nakbatābād (i. e. the abode of calamity).

We have a word-play or jeu de mot here. There is a تعين or between أكنا أد or تكنا أد and الكنا . The bodies of the letters of the words are identical; the difference lies only in the number or position of the nugtas or discritical points.

IV. 194, l. 4. Hasnak had one day said that before Mas'ūd should become King, it would be right to make war.

What Khwandamir writes is كه هر كاه مسعود بادشاه سئود حسنك را بردار بايد (H. S. Bombay Lith. II. Pt. iv. p. 29, l. 1).

"That when Mas'ud became king, Hasnak would be (or should be) hanged on a gibbet". Cf. what Khwāndamīr says in the Dastūru-l-Wuzarā, according to Elliot's own translation on 153 supra." He [Hasnak] expressed his apprehensions that when Sultan Mas'ud ascended the throne, he would impale him". See also Baihaqi, who tells us that Hasnak once spoke to 'Abdūs thus: "Tell your lord (Prince Mas'ud) that all I do is in obedience to my master's order. If hereafter the throne devolves upon him, he must cause Hasnak to be executed". (E. D. II. 90). Elliot's manuscript probably read instead of inste

Sic in the Bombay Lith, of the H. S. II. iv. p. 29, last line, but it is a copyist's slip for 'Purtigin'. Baihaqi (683, 696, 713—E. D. II. 146, 151), Gardezi (105, l. 4) and the T. A. (12, last line), all speak of him as Purtigin. The error is evidently due to a transposition of the dots. Dr. Barthold takes the correct form to be 'Buri-tagin'. Buri, he says, significatively.

ın Tarkı. Hıs full name was Tamghāch Khān, Abu Ibrāhim bin Nasr. (Turkestan, 300 Note)

IV. 198, l 5 from foot Ahmad went to the fort and in the year A. H 433 murdered that king [Mas'ŭd]

The year of Mas'ud's death is given as 433 H by Khwandamir, who seems to be following Hamdulla's Tarikh-1-Guzida (403, 15), where the event is put into the first Jumadi of that year and F also has the same date (I 44, 1 3) But the authority of the contemporaneous chroniclers is clearly in favour of 432 H Baihagi states that Mas'ud was taken captive at Mārigala and put to death before Sh'aban 432 H. (867, 11 7-15) Gardezi declares that he was murdered on 11th Jumadi I 432 (110, 1 4) Nizāmud-din Ahmad has followed Gardezi (T. A 14, 1 10) and B copies the T A (I 29,=Tr. I. 44) The T N also gives 432 (Text, 15, 1 6, E D II. 271) It is not easy to decide, but 432 appears to be the more probable date. Baihagi records that the Sultan left Ghazni on 7th or 8th Rab'i I 432 H =15-16th November 1040 A C (E D II 151-3) He must have reached Mārigala about the end of that month or the first week of Rab'ī II, as there are examples of the journey having been accomplished in about twenty days There can be little doubt that he was a prisonel at Kiri in Rab'ı II. and as there is, in such cases, but one step from the prison to the grave and as Muhammad's second reign is said to have lasted for only four or five months, (T N in E D II 273), it is not unlikely that he was murdered on 11th Jumadi I 432 H (17th January, 1041 A C) Ibn-al-Athir also states that Mas'ud started from Ghazna in Rab'iu-l awwal 432 H. (Ed Bulak, IX 167, l 15 f f, Tornberg, IX 281-283) The slaves revolted on 13th Rab'iu-l-ākhir=21st December 1040 (Ibid. 167, 1 11 ff) and Muhammad was defeated by Maudud on 3rd Sh'aban 432 H [8th April 1041] (Ibid. 168, 1 7 f f, Tornberg IX 331-332) The winter had arrived, the roads were blocked and military operations were impossible His enemies must have therefore thought it advisable to take occasion by the forelock and despatch him for ever before succour arrived Dr. Barthold also gives January 1041 A. C which corresponds to Jumadiu-lawwal 432 (Turkestan, p 303).

IV. 200, l 6 Maudud died on 20th of Rajab 441 H

Khwāndamīr is following his grandfather's Rauzat, which gives the 20th (Bombay Lith Jild, IV 52), but the T. A (16,14), F (I 46,18ff) and B. (I 33=Tr I 49) agree in making it the 24th day of that month and it corresponds to 22nd December, 1049, which is adopted in the C. H. I (III. p 33)

iV. 202, l 10 'Abdu-r-Rashid was the son of Mas'ūd, but according to the Guzida he was the son of Mahmūd

He was not the son of Mas'ud, but of Mahmud The divergence of opinion in regard to the parentage of this Sultan which Khwandamir and others leave undecided can be settled on the authority of the contemporary historian, Gardezi, who speaks of him as سلطان مسطم عرالدوله و ربن الله

سيف الله معن دبن الله ابو منصور عبد الرشيد بن يبين الدوله و امين اللته ابى الناسم محود (Z. A. 61, l. 3 f. f.). See also Ibid, 111, l. 8, where he again states categorically that 'Abdu-r-Rashīd was the son of Maḥmūd himself. His book was entitled Zainu-l-Akhbār, because 'Abdu-r-Rashīd was styled 'Zainu-l-Millat' and was his patron.

IV. 203, l. 16. When Jarjirheard of the murder of 'Abdu-r-Rashid.

This name appears in several forms. The T. A. has حرحر (16, l. 17). F. calls him أوشتكين كرجى (I. 47, ll. 6 and 17). The Tārīkh-i-Guzīda speaks of him as وشتكين شرواني (403, l. 4 f. f.). 'Jarjīr' or 'Jurjīr' may be the Arabicised form of the 'Gurji' of F. Hamdulla's 'Shirwāni' may indicate that his origin was from Shirwān. Shirwān and Gurgān (or Jurjīn) are both east of the Caspian and adjacent to each other.

IV. 204, 1. 16. Jākar Beg Saljūki sent his son Alp Arslan to encounter Farrukhzād.

The correct form is 'Chaghar Beg', as in the Tār. Guz. (402, 1.13), and Lane Poole, (Muḥammadan Dynusties, 152). F. (I. 44, 1.3 f. f.) has 'J'afar Beg' and Elliot notes the variants 'Bajr' and 'Bajū' Beg, but they are all wrong. Similarly, 'J'afartigīn' at 171 ante is an error for 'Jaghartigīn' or 'Chaghartigīn'. This name 'Chaghar' was afterwards borne by the famous Balūch chieftain, Mīr Chākar (Recte Chaghar) Rind, q.v. 398 post. Several other Turki names also, e. g. Sinjar, Ghāzīn, Zangi etc., are still found among the Balūch. (Dames, Baloch Race, 13). In Houtsma's E. I. al 10; (II. 909), the name is written as "Chaghri Beg."

IV. 205, l. 13. Sultan Ibrāhīm died in 492 H.... ..but other historians say he died in 481 H. But God knows all things.

Elliot has noted the discrepant statements and errors of various compilers in regard to the duration and year of the termination of Ibrāhīm's reign. According to the $T\bar{a}r\bar{\imath}kh$ -i-Guzīda (401, l. 14), Ibrāhīm died on 5th Shawwāl 492 H. (25th August 1099). This is the most probable date. As Baihaqi gives the date of his accession as 19th Sıfar 451 H. (vide my note on II. 277, l. 5), the most tenable view must be that he reigned for about 42 lunar years. The T. A. (p. 17) and F. (I. 49) give both 481 H. and 492 H., without stating which of the two is correct, but at the same time, they aver that his son 'Alāu-d-diula reigned for sixteen years and died in 508 H., which proves that 492 H. must be right.

IV. 205, l. 4 from foot. [The poets] Abū-l-Farah and Arzaki.

'Faraḥ' (حَ) is an error for فَى. He is correctly called 'Abu-l-Faraj' in the H. S. (II. iv. p. 32), as well as by B. (I. 37) and F. (I. 49, l. 14). His sobriquet is said by B. and others to have been 'Rūni', but Ḥamdulla calls him 'Zauzani'. (T. G. 815, l. 3 f. f.). 'Abdul Ḥamīd or 'Abdul Majīd bin 'Abdu-s-Ṣamad—the subject of his panegyrics—was the Vazīr of Sultān Ibrāhīm Ghaznavi. The situation of Rūn is also matter of controversy. B. asserts that it was a village near Lāhore (I. 37), but other authors locate.

it near Nishāpur (Ranking, Tr I. 54 note) He is styled Abu-l-Faraj Rūni in Houtsma (E. I III. 1059) and described as a great master of the Qasīda The name of the other poet mentioned on p 206, l 1, was not Arzaqi, but Azraqi. Many modern scholars deny that he was the author of the Alfīya or that he perpetrated such pornography. (Houtsma, E.I. I. 542) See also Chihār Maqālā, Text, 44, 170

IV. 207, l 15 Arslan Shah . sent his mother with 2000 dinars . and proposed a reconciliation

which is the reading in the lithographed text of the H S (II. iv. p. 33), as well as of the Rauzat, (IV 56) and F. (I. 49, I 1 f. f.). The dinār was a gold coin weighing about seventy grains and 2000 dinārs would be too paltry a sum to be offered to or accepted as an indemnity by the rapacious Seljūq Elliot himself states (208 note, infra) that Sinjar carried off all the treasures of Ghazni He is even said, in the Seljūq histories, and also in Mīrkhwānd's encyclopaedic compilation, to have imposed upon Bahrām, as the condition of his restoration, a daily tribute of one thousand dinārs (Rauzat, IV 127, Browne, L. H. P. II 297-8).

IV 209, l 17. Shaikh Sanāi Abul-Majīd bin Adamu-l-Ghaznīvi [the poet]

Majīd خين is one of the names of God and Abu-l-Majīd cannot be correct The poet's name was 'Abdu-l-Majīd Majdūd bin Ādam. (H.S II. iv p 35, F I 51, l. 8 f. f, Browne, Daulatshāh, 95; Browne, L H. P II. 317). Ranking (B Tr I 35 Note) gives the patronymic as Abu Muhammad, but this must be due to a slip (محبة for محبة)

IV. 209, 1 24 Where a certain darwesh experienced in misfortunes was saying to his cupbearer, 'Fill a cup to the blindness of the contemptible Mahmud Subuktigin'

بكى ار محدوبان مشهور بلاى خوار (H. S II iv p 33 last line) Rather, "a half-demented Santon, who was known as Lārkhwār, re 'Drinker of the dregs of wine'" The story is to be found in the Tazkiratu-s-Shu'ara of Daulatshāh, who speaks of its hero as "a madman who was called Lārkhwār, because he collected together in liquor shops the lees of wine and drank them off in the baths" دوانه بود که اورا لاي خوار کشدي که همواره "(Ed Browne, 95-6)

The man was what is called a عدور خرائى "a favern-haunting santon or inspired idiot, a lunatic or natural who was believed to have come under Divine influence" In Daulatshah's version of the tale, the anachronism animadverted upon by Khwandamīr is got rid of by associating the drunkard's diatribe with the name of Ibrahim Ghaznavi and not his ancestor, Mahmūd Browne discredits the whole anecdote and opines that it is not worthy of attention in connection with Sanai's conversion to the higher life. (L. H. P. II. 317). In F's version of the story, the Sultan is Mahmūd and not Ibrahīm, but the Majzūb is there also, invariably called

درد آشام (I. 51; II. 7, 6, 5 f. f.). This word is synonymous with لأى خوار 'Lecs-drinker', which is so frequently found in Hafiz, S'adi and other poets. The translator has wrongly read الای خواد instead of الای خواد The initial φ is the preposition.

He made a translation of a panegyric which had been IV. 211. 7. 3. written in honour of His Holiness and read the verses before the Prophet's holy sepulchre.

According to the Bombay lithograph of the Habibu-s-Siyar, this poet. Hasan Ghaznavi, recited a Tarji'a or Tarji'aband, which he had comnosed in praise of the Prophet. ترجيمي در نعت آن حضرت كفنه (II. iv, p. 34). Khwandamir does not speak of Sayyid Hasan having made a translation occur in the oldest version رجه) of any poem, nor does the word, ترجه of the anecdote, as it is related in the Tarīkh-i-Guzīda of Hamdulla Mustaufi, who avers that when the poet went on pilgrimage "he recited a tarji'a in praise of His Holiness." بنعت آن حضرت ترجيعي كمنة (Text, 817, 1.5 f.f.). A Tarjī'a, Tarjī'aband or 'Strophe-Poem' is "a peculiarly constructed form of verse which is made up of a number of couplets in the same metre, but having a different rhyme which recurs at regular intervals, but not for more than seven times in all". (Ranking, Tr. B. I. 62 and 196 Note. See also Browne, L. H. P. II. 39-40). The commentaries of Babar.....vere translated into IV. 218. l. 6.

Persianby 'Abdu-r-Rahim Khan Khanan.

There is an older Persian version of the Memoirs also which was not known to Elliot or his editor, Dowson. It was begun in 994 A. H. by Mirzi Payanda Hasan Ghaznavi and continued by a Muhammad Quli Mughal Hisari. It is unfortunately not complete, but Mrs. Beveridge says that it is "careful, likeable and helpful by its small explanatory glosses". (Bāburnāma, Tr. Pref. xliii. See also Rieu, B. M. Catalogue, II. 799: Ethé. India Office Catalogue, No. 179: Sachau and Ethé, Bodleian Catalogue, No. 215 A). Mr. H. Beveridge denies that the Khān-i-Khānān 'Abdu-r-Rahim was the real author of the Persian translation of Babur's Memoirs. (Asiatic Quarterly Review, 1900, pp. 114-123, 310-323). The author of the Darbar-i-Akbari also ridicules the notion of this 'busy man of affairs' shouldering the drudgery inseparable from such a task. He is sure that it was performed under his guidance by some of the litterateurs who were in attendance upon him. (p. 642). Mr. Beveridge suggests that the version which passes under the name of 'Abdu-r-Rahim existed in Humāyūn's time (loc. cit. p. 124; A. N. Tr. I. Errata, p. xiii). but the conjecture is founded only on the colophon of a manuscript in the Mahārājā of Alwār's Library, the authenticity of which is exceedingly doubtful. Sir E. D. Ross does not appear to have been impressed by the weight of his reasoning and accepts the authorship of the Khān-i-Khānān. (C. H. I., IV. 20). M. Clement Huart also does not question it. (Houtsma, E. I., I. 548).

IV. 221, l. 18 We come upon several countries in this range of mountains connected with Kashmir, such as Pakhali and Shamang [which are now independent of Kashmir]

Mrs Beveridge leaves this 'Shamang' unidentified. (B N 484) Perhaps, it is a mistranscription of 'Punshk' or 'Punshk' (Punch or Puntsch) The letters appear to have been jumbled by the copyists Abul Fazl tells us that Buliāsa (Peliasa of the maps) is the end of the country of Kashmīr and the beginning of the territory of Mashtang, which is the name of the country lying between the Kishangangā and the river of Pakhli, i e the Siran He then gives the itinerary of Akbar's march from Buliāsa to Dudhiāl through Pakhli (A N III 559, Tr 850) Mr Beveridge notes that in the Mss of the Akbarnāma, this name Mashtang is variously written as 'Shahbang', 'Shahsank', 'Pushang' etc Buliāsa or Peliāsa is said to be six marches from modern Abbottābād, from which Dudhial is 25 miles distant towards the north-east Constable, 24 D a can be easily misread as Shamang, Shahbank or Shahsank, Pantshank, or Puntshk

IV 230, l. 3 from foot When I reached Makam, several of my principal adherents advised me etc

Mrs Beveridge takes 'Makām' as the name of a place, but as the maps do not show it, suggests that Bābur has given the name wrongly and we should read 'Mardān' and not "Makām" (B N Tr 377 and Note) But the word مقام seems to be really used here (as in other passages on this page), by Bābur as a common noun in the sense of 'halting place', 'stage on a journey,' or 'the spot which had been chosen for staying in after a march' The passage under discussion stands thus in the Tūzuk-z-Bāburz (Bombay Lithograph, p. 140, l. 9 f f) در قد در ود آمدن مقام بعضي دولتواهان سرس A few lines higher up on this very page, Bābur writes—

C (140, 1 8) در مان مقام درود آمده شد (140, 1 8) در آن مرال مقام کردیم منزل دو دو سه سه رود مقام می آید (165, 1 16) در آن مرال مقام کردیم اید در هم منزل دو دو سه سه رود مقام می آید (165, 1 16) در آن مرال مقام کردیم اید در هم منزل دو دو سه سه رود مقام می آید (165, 1 16) در آن مرال مقام کردیم اید در هم منزل دو دو سه سه رود مقام می آید (150, 1 16) در میان مقام کردیم اید در هم منزل دو دو سه سه رود مقام می آید (150, 1 16) در میان مقام کردیم اید در هم منزل دو دو سه سه رود مقام می آید (150, 1 16) در میان مقام کردیم اید در هم منزل دو دو سه سه رود مقام می آید (150, 1 16) در آن مرال مقام کردیم اید در هم منزل دو دو سه سه رود مقام می آید (150, 1 16) در آن مرال مقام کردیم (172, 1. 1) See also 214, 1 6 f f.

Similar expressions occur very frequently in the Tūzuk-i-Jahāngīri, (170, ll 2, 11, 27, 171, ll 1, 6, 13, 173, ll 15, 23), and even the English factor, William Finch, uses the Persian word "The unseasonable thunder, wind and raine, with my disease, almost made an end of me, which made us make Mukom, on the third and fourth [February 1610]" (Early Travels in India, Ed Foster, p 138) Once more he says "The twelfth [February 1610], we made Mukom" (Ibid, 142)

IV 231, l 8. I myself set off for Sawātr, which they likewise call Kark-Khāna

The dots are misplaced This is the Swabi of the I G Atlas, Pl 33, C 2 It is now in Peshawar district It is the eastern-most tahsil of the district and forms with the Mardan tahsil, the Yūsufzai division (I G XXIII 183). The second name indicates that the rhinoceros was hunted

there.

IV. 231, l. 9 from foot. Saiyid Kāsim, Ishak Āghā.....cut off their heads.

'Aishik Aghā, literally means "Lord of the Gate." (B. N. Tr. 379). Morier says Ishik-āgāssi means "Master of the Ceremonies". (First Journey to Persia (1812), p. 108). Steingass states that اشبك إغاضي باشي signifies 'Chief Usher.'

IV. 232, 1. 8. Chaniut had long been in the possession of the Turks.

Dowson states in his note that this place cannot be found, but it is in almost all the maps. It is now in Jhang district and lies about 60 miles due south of Bhera. Lat. 31°-43′ N., Long. 75°-0′ E. Constable, Pl. 24 F b. Khūshāb is about 40 miles south-west of Bhera, Khūshāb is now in Shāhpur district. (Constable, E a 24). Lat. 32°-18′ N., Long. 72°-22′ E. (I. G.) S'ad-u-lla Khān, the renowned minister of Shāh Jahān, was a native of Chaniūt.

IV. 234, l. 1 and footnote. People were always saying [that ambassadors should be sent to Ibrāhīm Lody].

Dowson objects "that there is not a word of this paragraph in the Chaghatāi", but it is in the Turki text, translated by Mrs. Beveridge. (B. N. Tr. 384). Pavet de Courteille has a sentence instead which is differently worded, but has the same meaning. (II. 62).

IV. 235, l. 5. Their [the Gakkhars'] places of strength are situated on ravines and steep precipices.

means آبکند و جره هاست (Pers. Tr. 145, l. 5). The word) جای محکم ایشان آبکند و جره هاست 'river bed, pool of water, or hollow channel excavated by the rushing of a torrent.' - signifies 'crack, cleft, fissure, particularly in the ground.' (Richardson and Steingass). Mrs. Beveridge translates the sentence thus: "Torrent beds and ravines are their strongholds." (B. N. Tr. 387). Dowson again speaks of 'precipices' on the following page (236, 1. 18), but the word there also is 's - (T. B., Bombay Lith. 146, I. 7). Erskine says of the Gakkhar country that it is "rugged, mountainous and intersected by rugged ravines and dells which make it easily defensible" (H.B.H. II. 425) and Mr. Vincent Smith also speaks of the 'intricate ravines of the Salt Range'. (E. H. I. 77). We learn from the I. G. also that in the northern part of the Salt Range, the drainage is into small lakes, but southward, the streams flow through barren and stormy gorges and the country is cut up into tiny glens and ravines by a net work of ridges and connecting spurs." (XXI. 413). The small lakes and streams are the 'Abkand' and the ravines are the 'Jarr' spoken of by the observant Emperor.

IV. 235, l. 6. The name of Tātār's stronghold was Parhālah.

It is now called Pharwāla and lies twelve miles east of Rāwalpindi. (Delmerick in J. A. S. B. 1871, p. 85 note). It stands "at the eastern entrance of a wild and rocky gorge at the spot where the Suhan river quits the hills." (B. N. Tr. 452 Note). See also my note on IV. 56, l. 13, ante. IV. 237, l. 17. Among them were Amīn Muhammad Karāshi and Tar-

khān Arghūn.

The names and sobriquets are dislocated here. 'Karāshi', recte Qarācha, was not the sobriquet of Amīn Muhammad and 'Tarkhān Arghūn' cannot stand as the personal name of an individual The true reading is "Amīn Muhammad Tarkhān Arghūn and Qarācha''. (B N Tr. 390, P de Courteille II 72) The double sobriquet signifies that Amīn Muhammad belonged to that branch of the Arghūn tribe which bore the specific designation of Tarkhān, on account of its descent from Shankal Beg Tarkhān, who was sixth in descent from Arghūn Khān. (Aīn, Tr. I 361) See also Elliot's Note at I 303 Amīn Muhammad Tarkhān Arghūn is again mentioned in the B N Tr 415 Qarācha's name also occurs frequently in the Memoirs (B N Tr. 602, 638, 650, 659)

IV 237, l 10 from foot. Hati Galkar slew Malik-hast's father

Malik Hast was the chief of the Janjuhas Babur explains that his real name was 'Asad', but "as Hindustānis sometimes drop a vowel, e g say 'Khabr' for 'Khabar' (news), they had said "Asd" for "Asad" and this went on to 'Hast'" (B N. Tr 380, T B 141, 1 19)

'Andarābah' (1 22) is a miswriting of 'Adrānah', "a town or village in the Fath Jaug tahsīl of Rāwalpindi district'' (Delmerick, J A S B 1871, p 85 note) Mrs. Beveridge spells it wrongly as 'Andarāba' and she leaves it unidentified The name is clearly written which in the T B 147, ll. 3 and 23, and there can be little doubt that it is the 'Adrānah' of our maps, though the Chaghatāi text and Pavet de Courteille also calls it 'Enderābeh' (Mimoures de Baber II. 73).

IV. 240, l 3 [We encamped] close by the hill of Jūd, below the hill of Bălināt Jogi on the banks of a river at the station of Bakiālān

بابان کو المانی حوکی درکمار رود حای بودن مکیالان آمده منزل کرده شد (T B 165, I. 15) "We halted at the foot of the hill of Balnāth Jogi by the side of a stream, in a spot inhabited by Bugyāls" (near Nandna, q v E D. II 450) 'Bakiālān' is not the name of a place, but the plural of Bugyāl—the name of a Gakkhar clan Jahāngīr states that these tribesmen who were kinsmen of the Gakkhars were settled in the district between Rhotās and Hatya, when he passed through this region on his march to Kābul (Tūzuk, 47, Tr. I 97=E. D VI 309)

IV. 244, l 4. Dilāwar Khān came on by way of Sultānpūr and Kochi So also in the Persian translation (167, l 16) and l' de Courteille (II 144), but Mis Beveridge renders the Turki differently and says, "he went to his family [Kūch] in Sultānpūr" (B N Tr 457) and this may be correct as it has not been possible to trace any place called 'Kochi'

This Sultanpur which is said to have been founded by Tātār Khān Lody Yūsūf Khail, is the town of that name in Kapurthalā State (Tolbort's Art on the District of Ludhiānā in J A S B 1869, p 89) Constable, 25 A b It lies sixteen miles north of Kapurthalā town (I G.

XXIII. 138). Tātār Khān Yūsuf Khail was Daulat Khān Lodi's father. IV. 245. 1: 19. We crossed the river Biyāh opposite to Kanwahīn.

Kānw-wāhan was a Mahāl in Sarkār Batāla in the Bāri Duāb. (Āīn, Tr. II. 110 and 369). The pargana town is about thirteen miles northwest of Dasūyah in Hoshiārpur district. Wāhan or Wāh signifies 'a canal or water-channel.' (Raverty, Mihrān, J. A. S. B. 1892, p. 372 note). Dasūya lies 25 miles north-west of Hoshiārpur town. (I. G. XI. 194). Kānwāhan lake is now included in Gurdāspur district, Punjab. (Ibid).

IV. 247, l. 9. Marching thence and passing the small hill of Abkand by Milwat, we reached Dun.

"Having marched thence and crossed the low hills and torrent-beds near Malot, we entered the Dūn". Cf. P. de Courteille, II. 151. Dowson has understood "Ābkand" here as a place-name, but it is so often used as a common noun in the sense of 'river-bed, pool of water, water-hole', that there is no warrant for assigning to it any other meaning. The word is employed in this sense by Jahāngīr also in the Tūzuk. (Text, 154, l. 20; Tr. I. 315). See also the Note on p. 235 ante, where Dowson has given its English equivalent as "ravine". This 'Milwat' must be 'Malot' in Hoshiārpur district. Lat. 31°-50' N., Long. 76°-0' E. (I. G. XIII. 194). There is another place called Malot near Bhera in the Salt Range, Jhelum district, which lies about nine miles west of Katās. Lat. 32°-42' N., Long. 72°-50' E. (I. G. XVII. 95). The Dūn (dale or valley) which Bābur speaks of having entered must be the Jaswān Dūn.

IV. 247, l. 17. To the north-east [of the Dūn], is a castle called Kūtila This may be Kotla, which is situated on a steep ridge about thirteen miles eastward of Nūrpur and twenty-two miles north-west of Kāngra. (Pandit Hirānand Shāstri's Art. on the Gūleria Chiefs of Kāngra in the Punjab Historical Society's Journal, 1912, p. 141). Kotla, Kāngra and Gwāliyar (Gūler) were all Maḥals in the Bāri Duāb Sarkār in the days of Akbar. (Āīn, Tr. II. 319; Cunningham, A. G. I. 136). Kinkūta (l. 5 f.f.) is the 'Gangot' which was in the Beth (or Bist) Jālandhar Duāb. (Āīn, Tr. II. 317).

IV. 248, l. 8. The detachment advanced against Harūr, Kahlūr and the forts in that part of the country.

The reading of the first name in the Persian Translation is 'Hindur' (170, 1. 13) and this may be correct. Hindur and Kahlur are two States which lie in close juxtaposition and are both shown in Constable's Atlas, Pl. 25 B b. Kahlur is now generally known as Bilāspur. Hindur (now called Nalagarh) is about thirty miles north of Rupūr (in Ambālā), to which latter place Bābur says he marched from the Dūn Valley. But the Turki text and de Courteille (II. 154) also read 'Harūr' (B. N. Tr. 464), which may be an error for Harīpur, though Harīpur is further north near Kāngra.

IV. 248, l. 5' from foot. I' sent back a Sawadi Tinkatar along with him.

Dowson says in the footnote that "the office of Tinkatār is not well ascertained." Tunqitār, according to Mrs. Beveridge, is a "word of many meanings in Turki and signifies "a guardian in war of a prince's tent, a night guard, a man who repeats a prayer aloud while a prince is mounting etc." (B N. 464 Note). A man named Kichkīna Tunqitār is mentioned in the Memoirs as having been sent with orders to the Tramontane Begs (B N Tr 406) The name of 'Ulja Tamūr Tunqitār' occurs also in Yazdi's Zafar-nāma (E D. III 518)

IV. 249, l 1 We halted on the banks of the stream of Banur and Sanur. They call it the stream of Kagar. Chitar stands on its banks.

Banur hes about 15 miles north-east of Patiālā town and about the same distance south-east of Sirhind. Constable, 25 D b. Sanūr or Sanaur is four miles south-east of Patiālā. It is an old town and "in the time of Bābur, Mahk Bahāu d-dīn the Khokhar was the chief of Sanaur with 84 circumjacent villages, whence the pargana was known as Chorāsi". (I. G XXII 27). It is now one of the four tahsīls of the Karamgarh Nizāmat of Patiālā State (Ib XV. 48) The Kagar is the Ghaggar or Gaggar 'Chitar' may be 'Chhatr' or 'Jhat' which was the chief town of a mahal in the sarkār of Sirhind and is said to have been on the Ghaggar in the Āīn (Tr. II. 296) or 'Chhapar', another town on the Ghaggar near Bannūr and Fathpur

IV 251, l 5 After reviewing it [the army], I performed the Vim.

Mrs Beveridge reads this Turki word with a 'dāl' and writes 'Dīm', admitting at the same time, that the spelling varies in the Manuscripts But however uncertain the orthography and orthoepy may be, the meaning is fairly clear, as the custom of using a whip for the approximate determination of the numerical strength of an army is well known and of respectable antiquity. Baihaqi says of Sultān Mas'ūd Ghaznavi that he held a review of his troops on 8th Sh'abān 426 H and a count was taken by means of a whip معرف من المعرف المعرف , 598, 17 f f. It is also mentioned in the Siyāsatnāma of the great Seljūq minister Nizāmu-l-Mulk. (Bombay Lith I. 17, 17, Tr. Schefer, 22) "We do not exactly know how the count was made, but it has been conjectured that in the march past, the whip was held by the teller 'to keep his place' and "the troops were measured off as so many whip lengths" (B N Tr 154 and 468 notes)

IV 254, l. 11. I stationed Walt Kizil to act as a Tulughmah

"Qızıl' means 'Red' The sobriquet having reference to a physical trait was given to this "Wali' probably to distinguish him from his namesakes Another 'Wali' is styled 'Khazānchi' (Treasurer) and also "Qarāqūzī" 'Black-eyed'. (B N Tr 566; see also Ib 335, 472, 475). A third Wali 'Pārschi,' i e. Wali, the Cheetah-keeper, is also mentioned (Ib 633) Mrs. Beveridge vocalises the Turki word as Tūlghuma (B N 473)

IV 256, l. 11 Tāhir Tabari, the younger brother of Khalifa cut off Ibrāhim's head.

Tāhir Tabri [or Tibri or Tiri] was not Khalifa's brother, but his brother-in-law. (B. N. Tr. 475). P. de Courteille has beau-frine. (II. 170). See also page 267 infra, where he is correctly described in Dowson's own IV. 265, 1.1. translation as the maternal uncle of Muhibb-i-Ali, the son of Khalifa, المان عن على عن المان ا (1. 23) is really the "Hauz-i-Khās" or 'Hauz-i-'Alāi,' the great reservoir constructed by 'Alau-d-din Khalji in or about 1293 A. C. The Shamsi tank is the Hauz-i-Shamsi—the one excavated by Shamsu-d-din Iltutmish. IV. 261, l. 5 from foot. From the mansion of hostility which [Chauderi] had long been, I converted it into the mansion

The phrases used in the original text are city, and in the original text are The phrases used in the original text are "philotopic and philotopic and the Ghiyasu-l-Lughat, Diru-l-harb' is any last line). According to the Ghiyasu-l-Lughat, country belonging to infidels which has not been subdued by Islam. In the country peronging to innuers which has not occur subjuct by islaid. In the Fatawai 'Alamgiri, it is laid down that a 'Dāru-l-Ḥarb', becomes a Daru-l-Islam, on one condition, viz. the promulgation of the edicts of

Islam. (Hughes, Dict. of Islam, 69. See also Ibid, 277, 710).

IV. 263, l. 13. And in Kalpi 'Ali Khan [was the governor]. In the Persian translation of the Memoirs, he is called 'Alam Khan' (206, 1. 18) and so also in the B. N. (Tr. 523). This 'Alam Khin, who was the son of Jalal Khan Jigat, should not be confused with 'Alau-ddin 'Alam Khān-i-Lodi, one of the sons of Sultan Buhlul and uncle of Sultān Ibrāhim. 'Ālam Khān of Kālpi afterwards joined Bahādur Shāh of Gujarāt, was left in charge of Mandu after that Sultan's flight and was hamstrung and put to death by Humayun when the stronghold was was namedrung and put to death by managen when the satisfication is 342 H. (Mirat-i-Sikandari, Tr. Bayley, 366 note. Hajii Dabīr, Z. W. 232, 233). Jalāl Khān Jigat, his father, is difficult to identify, but may be Jalal Khan, the son of Sikander Lody, (Erskine, H.B.H., I. 469 note), who is explicitly stated to have given Kalpi to

'Alau-d-din 'Alamkhan-i-Lodi lived several years longer and was killed by the orders of Sultan Mahmud Latif of Gujarat in 950 H. (Mirati-Sikandari, Tr. Bayley, 277 Note. Hajji Dabir, Ibid, 326). He was the him as a Jagir. (468 post). uncle of Sultan Sikandar and may have been the granduncle of this other 'Ali (or Alam) Khān of Kālpi. A third 'Alam Khān-i-Tahangari [of Tahangarh near Bayana] who was the brother of Nizam Khan of Bayana

is also mentioned. (B. N. Tr. 538, 539, 547). Recte, as in Budāuni. (I. 338=Tr. I. 444). Makhkhan (Butter) is a not uncommon name among Hindus as Well as Musalmans, e. g. Makhkhan Lāl, Miyān Makhkhan.

A Shaikhzāda or Miyān Makan or Miyā Makhan is mentioned more than once by Ni'amatulla (E. D. V. 98, 101, 104), the T. A. (165, l. 8; 166, l. 10 from foot), and Ahmad Yādgār (E. D. V. 16-19). He was one of the great officers of Sikandar and Ihrahim. Lody. This Hasan may have been his son.

IV. 266, l 9 from foot [Humāyūn] waited on me in the garden of the Hasht-bihisht.

'Hasht-bihisht', 'Eight Paradises', is the title of one of the Mamavis of Amīr Khusrau The name of this Āgra garden is said to have been afterwards changed to Ārām Bāgh and that to Rīm Bāgh by the Mahrāttas It is now generally known as Rām Bīgh Jahāngīr gave it away to Nūr Jahān and it is identified by Mr Keene (Guide to Agra, 38, 39) with the 'Nūr-Afshān. Garden' of his Tūzuk. It appears to have been known also as the 'Gul-Afshān' Garden. It lay on the eastern side of the Jumna and opposite the Fort (Beveridge's Note to A N Tr I. Errata, p xii).

IV. 268, l. 15 Mustafa Rūmi had disposed the guns according to the Rūmi fashion. He was extremely active, intelligent and skilful in the management of artillery.

IV. 268, l 4 from foot I caused the Hindustani and Khurasani prisoners to run a ditch

There is nothing corresponding to 'prisoners' either in the Persian translation or the Turki text

علداران خراسا بي و هدوستاني و كالمد داران را الداخه خدق كده شد (T. B 206, l 10) "Khurāsāni and Hindustāni spadesmen and mattockmen were employed and a ditch was dug" So also B N. Tr 550 and P de Courteille (II 274) The word 'Khurāsāni' is not used here in the specific sense of 'inhabitants of Khurāsān', but for foreigners (Pardeshis) of all sorts Bābur himself observes elsewhere in the Memoirs that "just as 'Arabs call every place outside Arabia 'Ajam, so Hindustānis call every place outside India, Khurāsān'. (B N Tr 202) Barbosa, writing about 1510 A C, applies the term 'Coraçones' to the inhabitants of North Persia and the kingdom ruled over by Husain Mirzā Bāīqarā, including Sīstān and Herāt (Tr Dames, I 119-20 Note) Ibn Batūta also had remarked, two centures before, that the people of Delhi speak of all Asiatic strangers indiscriminately as Khurāsānis (Defremery, III 229 See also Thomas, C. P K D 205 note). "Prisoners" is, perhaps, a misprint for 'Pioneers'.

IV. 273, l 12 from foot. I encamped six kos from the fort of Alwar which was on the banks of the river Manisni

The Manishi or Ruparel flows eastward to the south of Alwar town This name is locally said to be derived from 'Mānas-le', which signifies in Gujarāti 'Man-taker, Man-killer or Man-eater'—a folk-etymology so fantastic that it is surprising to find it repeated without protest in the Official Gazetteer (Powlett, Gazetteer of Gurgāon, Pt. IV a, p 6) The river is also called 'Barah' and 'Laswāri' (I G V 256)

'Abdul-Rahim is called Shaghawal on l. 5 f. f. Shaghawal' in Turki "Abdul-Kaṇm is called Snagnaicat on 1. Diestrawai in Lurki means chief scribe, or a high official who was supreme over all Qazis IV. 277, l. 9 from foot.

and mullas. B. N. Ir. 400 uovel.

I gave an appointment of fifteen lacs.

To Tardika..... mardi vite, mardi hains the narrow 274, l. 2. To Tardika...... I gave an appointment of fifteen lacs.

The correct reading here is anithal countries and pointment of fifteen lacs.

The correct reading here is anithal countries and pointment of fifteen lacs.

The correct reading here is anithal countries and pointment of fifteen lacs. The correct reading here is Tardi Yika, Tardi being the personal brave, champion, wikka, is name and Yika, (Yakka), an epithet signifying, Yika, or understand valiant fighter, Mrs. Beveridge points out that this value to he understand value the Turki Yikit or Yinit. and Mullas. (B. N. Tr. 463 note).

valiant fighter. Mrs. Beveridge points out that this yika or xikka is really the Turki Yikit or Yigit, 'young hero,' and was sunnosed to have afterworks in Tukin as the Persian 'Yikku,' and was sunnosed to have really the Turki Yikit or, Yigit, 'young hero', and was supposed to have afterwards in India as the Persian coldier or private (R. N. 579, see afterwards in India as the Persian Yikka, and was supposed to have the same meaning as, Ahdi, a single soldier or private. (B. N. 579; see the same meaning as, Ahdi, a single soldier or private. tne same meaning as Andi, a single soldier or private. (B. N. 579; see also Ib. 16, 70 Notes and Appendix, pp. Xxvii-XXviii).

also Ib. 16, 70 Notes and Appendix of translated as a distinguished sharming as a part and translated as a distinguished sharming as a part and translated as a distinguished sharming as a part and translated as a distinguished sharming as a part and translated as a distinguished sharming as a part and translated as a distinguished sharming as a part and translated as a distinguished sharming as a part and translated as a distinguished sharming as a part and translated as a distinguished sharming as a part and translated as a distinguished sharming as a part and translated as a distinguished sharming as a distinguished sharm

also 10.16, 70 Notes and Appendix, pp. xxvii-xxviii). Yikka Jawanan, is used in the A.N.II. p. 284 and translated as the Fig. 10 for the means of the means of the Fig. 10 for the means of the mea is used in the A.N.II. p. 284 and translated as distinguished champions a by Mr. Beveridge. (II. 420). Cf. the use of the Fr. As, Eng. are announced by Mr. and recommon who has brought down a large armon who has brought down a large armon.

by Mr. Deverlage. (II. 420). Ur. the use of the fir. As, thug. Ace, for a large number of daring and renowned airman who has brought down a large number of enemy planes.

enemy prantes. from foot. [We encamped near Chanderil, having pre-This is the Or, a tributary of the Betwa. Tolorow (1 00) in (1 on) in (1 on

Village is the Ur, a tributary of the Hetwa. The correct name of the Village is miles N E of A and (N W D Clevatron VII 791) enemy planes.

Village is mauranpur. (B. N. Dyz Note). Jaiesar (I. Zu) is one a village six miles N. E. of Agra. (N. W. P. Gazetteer, vil. 48.0. 1. 21).

a village SIX miles N. E. of Agra. (N. W. P. Gazetteer, VII. (21). made it [the citadel of Chanderi] they have made it. 276, l. 21. On one side of it [the citadel of Chanderi] and the contraction of the a covered way which runs down to the water, is called "min."

This covered way which runs down to the Water, in the Talled "min."

This covered way which runs down to the water, in the Talled "min."

This covered way which runs down to the water, in the Talled "min."

This covered way which runs down to the water, is called "min."

This covered way which runs down to the water, is called "min."

This covered way which runs down to the water, is called "min."

This covered way which runs down to the water, is called "min."

This covered way which runs down to the water, is called "min."

This covered way which runs down to the water, is called "min."

This covered way which runs down to the water, is called "min."

This covered way which runs down to the water, is called "min."

This covered way which runs down to the water, is called "min."

This covered way which runs down to the water, is called "min."

This covered way which runs down to the water, is called "min."

This covered way which runs down to the water, is called "min."

This covered way which runs down to the water, is called "min."

This covered way which runs down to the water, is called "min."

This covered way which runs down to the water, is called "min."

This covered way which runs down to the water, is called "min."

This covered way which runs down to the water, is called "min."

This covered way which runs down to the water, is called "min."

This covered way which runs down to the water, is called "min."

This covered way which runs down to the water, is called "min."

This covered way which runs down to the water, is called "min."

This covered way which runs down to the water, is called "min." This covered way which runs down to the water is called different of Chanderi is hadly emphised with water the principal countries. This described in the I.G. course the principal countries water the principal countries hadly emphised with water the principal countries hadly emphised with water the principal countries hadly emphised with water the principal countries. double-walled road by Dabur. It is thus described in the Principal Source fort of Chanderi is badly supplied with water, the principal show he fort of the Kinet Caner tank of the foot of the hill reached from show he being the Kinet Caner tank of the foot of the hill reached from show he

Tort of Changeri is badly supplied with water, the principal source being the Kirat Sagar tank at the foot of the hill, reached from the most main in its peng the Rirat Sagar tank at the root of the hin, reached from above by a covered way, which at the same time formed the weak, we tank at the same time formed and it was a covered way, which at the same time his coont more it. In the Persian translation as well as the Turki text, Shaham is called for the Persian translation as well as the Turki text, on a signal of the Persian translation as well as the Turki text, on a signal of the persian translation as well as the Turki text, on a signal of the persian translation as well as the Turki text, on a signal of the persian translation as well as the Turki text, on a signal of the persian translation as well as the Turki text, on a signal of the persian translation as well as the signal of the persian translation as well as the signal of the persian translation as well as the signal of the persian translation as well as the signal of the persian translation as well as the signal of the persian translation as well as the signal of the persian translation as well as the signal of the persian translation as well as the signal of the persian translation as well as the signal of the persian translation as well as the signal of the persian translation as well as the signal of the persian translation as well as the signal of the persian translation as well as the signal of the persian translation as well as the signal of the persian translation as the signal of the persian translation as the signal of the persian translation as the signal of the signal W. 276, d. 5 from foot. Shaham Niv. Beg (scaled the wall).

In the Persian translation as well as the Turki text, Dhaham is that his Yuzbeg, i. e. centurion, not Nur Beg, the name Shaham is that his YUZDEG, v. e. centurion, not wir deg. (1. d. ZZU, 1. v; d. zv.);

De Courteille, II. 331). One explanation of the name Shāham is the chort full roma was Shāh Muhammad of which Shāham or Shāham is the chort De Courtellie, 11. 551). One explanation of the name Shaham is the short full name was Shah Muhammad, of which Shahim or Shaham is the form In the Travisit fort of coordinate to the coordinate tun name was duan munammad, of Wnien diamin or diamin is the Shahim-is form. In the Turki text of another passage, he is spoken of as the hrother Nur Heg, and Mrs Reveridge takes this to mean that he was the hrother Torm. In the Turk text of another passage, he is spoken of as the brother Nur Beg, and Mrs. Beveridge takes this to mean that he was mentioned at Nur Deg, and Mrs. Deveringe takes this to mean that he was the brothers are mentioned at of Nur Beg. (B. N. 454). Nur Beg's younger brothers are mentioned in the Gemitical And ed. in and ed. ... are constituted to be conformed at this And ed. in and ed. ...

or Nur Deg. (D. N. 404). Nur Degs younger provinces are membered as Ibid. 446.

Seript.

I encamped by the fort of Malli Khan.

I encamped by the fort of Malli Khan.

1 220, 1. 3 f. f.), i. e. near

1 277, 1. 9 from foot. I encamped by the fort of Malli Khan.

The T. B. reads,

The T. B. reads,

The Tank or Recensarion—not fort—of Malli Khan

Tank or Recensarion—not fort—of Malli Khan.

The Tank or Recensarion—not fort—of Malli Khan. The Lunk or Reservor—not fort—of Mahu Khan. So also D. N. dylian Courteille. H. 334. Mallu Khan was made governor of Malwa by Sultan Rahâdur Anjarâti and offenmenda accuracy the title of Courteille. Ourreine. 11. 554. Mahn Khan was made governor of Mahwa by Sultan, styling
Bahadur Gujarati and afterwards assumed the title of Sultan, another
himself Oadin Chah But B accome to see that he was the son of another Danaour Gularati and afterwards assumed the title of Sulvail, Styling that he was the son of another himself Qadir Shah. But F. seems to say that he was annhowed by Sulvainable mobile who had the same title and was annhowed by Sulvainable mobile who had the same title and was annhowed by Sulvainable mobile who had the same title and was annhowed by Sulvainable who had the same title and was annhowed by Sulvainable who had the same title and was annhowed by Sulvainable who had the same title and was annhowed by Sulvainable who had the same title and was annhowed by Sulvainable who had the same title and was annhowed by Sulvainable who had the same title and was annhowed by Sulvainable who had the same title and was annothed by Sulvainable was an annhowed by Sulvaina Malwa noble who had the same title and was employed by Sultan script.

Nāsīru-dīn Khalji in an expedition against a rebellious governor of Chanderi in 1500 A. C (II. 261, l 17, 270, l. 12). The Tank may have been built by the father

IV. 281, l 16. Asok the Hindu had himself been with Padmawati.

"This Hindu named Asoka was a near relative of Padmāwati, the mother of Bikramājit." See also B N 612 De Courteille II (350) has proche parent The word خویش appears to have been left out in Dowson's Ms This Asokamal Hindu is mentioned also in the Mirāt-i-Sikandari (Text, 174, 1 15, Bayley's Tr 273, Tr Fazlullah, 113)

IV 283, l 14. The Bengalis had watched them [Jalāl Khān and $D\bar{u}d\bar{u}$] with a realous eye

T B (227, 1 4 f f). Mrs Beveridge's rendering is "whom the Bengālis [Nusrat Shāh] must have held, as if eyebewitched, re held fast from departure, e g as a mouse is by the fascination of a snake" (B. N. 664 and note) But the real meaning of the phrase is "to keep under the eye", "to keep under surveillance" بحثم لگاه داشتن and the same idea is expressed by the word 'Nazarband' or 'Nazarquid', which signifies 'in open arrest', 'kept under constant observation' or 'vigilantly watched' P de Courteille also has gard's à vue par les Bengalis سلم شاه بسمامی حکم در مود تا Budauni uses the expression in this sense Salīm Shāh gave secret orders to his at- مررا کامران را چشم سد نگاه دارند tendants to keep Mırzā Kāmrān under open arrest" (I 390-Tr I. 502) Abul Fazl also speaks of Mırzā Hındāl and Mırzā 'Askarı being kept سطرسد گاه داشت (A. N l 231, 236, Tr I 462, 468) طرسد گاه داشت occurs in the Tuz Jah (369, 1 15, 371, 1 4) Khwafi Khan says Prince Muhammad Akbar was outwardly treated hospitably by the Imam of Masqat, but in reality kept under surveillance گاه داشت نظریق نظر سد (Text. II 285, 1 5 f f.=E D VII 313)

IV 284, l 4. I resolved to send Mullā Muhammad Mazhib [along with the ambassador of Bengal]

Mrs Beveridge also reads 'Mazhab' and supposes the sobriquet to mean that 'its bearer occupied himself with the Muhammadan faith, (in its exposition by divines of Islam" (B N 665) But I venture to say that 'Mazhab' has not and cannot have any such meaning in this context and that is a copyist's error for 'huhazzab', which Richardson says means "a good sincere man, integer vitae sceler isque pur us". The word is derived from the same root as if cleaning, purifying' See also Houtsma, E I, III, 704 'Khwāja Muhazzab or Muhazzib', also called Muhazzabu-d-dīn Husain was one of the Vazīrs of Sultān Raziyya, Mu'izzud-dīn Bahrām Shāh and 'Alāu-d-dīn Mas'ūd Shāh (T N in E D II, 938, 341, 342, 343) B (I S4, S6, 87=Tr I 120, 122, 124), T. A (32, L 10, 34, I 15) and F (I 79, I 16, 80, I 10), also call him 'Muhazzab' or 'Muhazzabu-d-dīn'. Barani tells us that Khwāja Muhazzab who had been a minister

in former times was so highly respected by Sultān Ghiyaṣu-d-dīn Tughlaq I, that he was allowed to sit in his presence. (Text. 427, l. 21). F. speaks of Sultān Firūz Tughlaq as بأد شاه معظم عهذب (I. 144, l. 6). Ibn Baṭūṭa mentions a Khwāja Muhazzib, who was a wealthy merchant of Kawlam or Quilon. (Defrémery, IV. 100—Gibb, 238).

IV. 284, l. 9 from foot. I called the Amirs, both Turki and Hindū to a council.

امرای ترك و هند را بعثورت طليده (T. B. 238, l. 4 f. f.). "I summoned the Turki Amīrs and the Amīrs of Hind to a council." The 'Amīrs of Hind' were not 'Hindūs', but Afghāns, Paṭhāns and other Musalmāns born in Hind. They were men like Dilāwar Khān, Malik Dād Kararāni and Shaikh Gūrān. (B. N. 567). Bābur had few or no nobles of the Hindū or Brāhmanical persuasion in his service. At any rate, there is no mention of any, either in his 'Memoirs' or in the later chronicles. Bābur speaks elsewhere also of امراي ترك و هند T. B. p. 210 (Recte 200), ll. 3 and 11. q. v. B. N. Tr. 530, 531).

IV. 285, l. 3. 'Askari should pass the Suru at the Ghat of Haldi.

Haldi is a not uncommon place-name in India. This Haldi must be the one near the confluence of the Sarjū and the Ganges. (B. N. 667, 668, 671 notes). It is in Ballia district U. P. about 65 miles east of Ghāzīpur. Lat, 25°-45′ N., Long. S4°-15′ E. Kharīd is in Shāhābād district. It is a low lying alluvial flat bounded on the north by the Ganges and on the east by the Son. (I. G. VI. 5). There is another Haldi near Sikandarpur West, with which this should not be confused.

IV. 286, l. 5 from foot. During the assault, some hay that had been collected, being set on fire by the fireworks, turpentine and other combustibles that were thrown on it,the fort was taken.

There is nothing either about 'fireworks' or about 'turpentine' in the Persian version or the Turki original. در اثنای جنگ گاه جم کرده شد و که 243, l. f. f. "In the course of the fight, dry grass had been stored and the rags (که) and thatch caught fire". See also B. N. 681, where the rendering is a "collection of wood chips, hay and thorns". Pavet de Courteille has herbes et broussailles, i. e. grass and brushwood. (II. 431). Richardson says هم المعادية ا

IV. 295, l. 2 from foot. The royal autobiographer Jahangir, records an instance of it in his Memoirs.

In the notice of Naqib Khān to which Elliot refers, Jahāngīr writes: "He has no equal or rival in the science of History or Biographies........ From the beginning of Creation till the present day, he has by heart the tale of the four quarters of the world. Has Allah granted to any other person such a faculty of memory!" (Tūzuk, Tr. I. 28; Text, 12, 1, 16). Elliot's statement that Naqīb Khān "knew the entire contents of the seven volumes of the Rauzatu-s-Safā" is copied from the Maāsiru-l-Umarā and should not be understood too literally. It probably means nothing more

than that he had all the historical facts" at his fingers' ends"

IV. 301, footnote The exact date of its composition is not given, but it was probably soon after 987 H (1579 A D), a date which is mentioned by the writer in the course of the work when referring to his personal affairs

In the Catalogue of Persian Mss in the British Museum (I 243), Dr Rieu quotes these words with approval and gives it at his own opinion that 'Abbas's Chronicle was written about 987 H It may be therefore permissible to point out that this date-limit can be still further extended by about seven or eight years. I beg to draw attention to a passage which both Elliot and Ricu have overlooked, and emphasise the fact that there is an event of later date which 'Abbas mentions in connection with "his personal affairs" and the decline of his own fortunes This is the death of his patron Shaikh Hāmīd Bukhāri (p 390 post) Shaikh Hāmīd was one of those who fell fighting against the Yusufzais near Begram (Peshawar) towards the end of 994 A H. (A N III 510= Fr III. 777, T A, 19, E D, V. 455, Budaun, II 354=Tr II 366, Blochmann, Ain, Tr L397) It follows that this history must have been written, some time after 994 H It seems indeed to have been taken in hand by Royal command with a view to provide materials for Abul Fazl's Akbarnama, like the 'Waq'iat of Janhar and the Humayun Nama of Gulbadan which were both composed after 995 H (E D V 137, Humāyūn Nāma, Tr Mrs Beveridge, 83 Note) We know that the first Farman directing the composition of the Akbarnama was issued on the 22nd of Isfandarmad of the thirtythird year of Akbar's reign, i e Rab'i II 997 H and this was followed by another Farman on 26th Ardibehesht of the thirty-fourth year, or Rajab 997 (Beveridge, Ahbai nāma, Trans I 33 note) The Memoirs of Bāyazīd Biyat (or Bayat), another of these materiaux pour servir-were dictated to a scribe, according to that author's own statement, in 999 A H. (Beveridge's summary in J A. S B LXVII, 1898, pp. 297, 316)

IV. 306, l 7 Rai Sihar Langah, Zamındar of Zabırı, expelled Shaikh Yüsuf from the kıngdom of Multan.

The reading of the first toponym is most probably wrong. The L. A. (639, 1-3) and F. (II 324 last line) say in the sections devoted to the History of Multān, that Rāi Sāhar was the ruler of Sīwī or Sawi, i.e. Sībī near Quetta But 'Zābiri' may be 'Seorāi' which lies about eight miles north-east of Sabzalkot. It is now called Sirwāhi (Cunningham, A G I 254-5) Lat 28°-10′ N, Long 70°-2′ East. It was destroyed by Shāh Husain Arghūn in 1525 A C. It is still a place of considerable sanctity to Muhammadans (I. G. XXII. 110). Sabzalkot is now in Bhāwalpur and lies 76 miles north-east of Bhakkar. It is shown in the London Times Atlas, Pl. 79, D 5

IV 308, l 20 Parganas of Hariana and Bahkala and Bajwara in the Punjab

Hariana and Bajwara are in Hos'narpur district, Punjab. Constable

Pl. 25 B b. 'Bahkāla' looks like a miswriting of 'Bhagwāl' or 'Begowāl' المكوال or بكوال, which is now in Kapurthalā State, but in their near neighbourhood. Constable 25 A b.

IV. 308, l. 3 from foot. Hasan.....entered the service of.....'Umar Khān Sarwāni Kalkāpūr.

This reading 'Kalkapur' is very doubtful and several variants, Kaktūr (347 Note), Kaknūr, Kalnūr and Laknūr (377 infra Note) are noted by Dowson himself. The sobriquet occurs only in connection with the names of distinguished individuals of the Sarwani tribe. It is invariably spelt as 'Gukboor' in Dorn's translation of Ni'amatulla's History of the Afghans, e.g. Mobarez Khan Gukboor (I. 101), Hybet Khan, son of Omar Khan Gukboor (Ib. 123), Hybet Khan, Aazem Humayoon Servani Gukboor, Mian Youb Gukboor Servani (Ib. 126), Isa Khan Gukboor (Ib. 128), and Said Khan Gukboor (Ib. 141). M. Garcin de Tassy also always reads the Nisba as Kakbūr in his French translation of the Urdū version of 'Abbās's chronicle (pp. 1, 7, 96, 104 etc.). But all these persons are called 'Kalkapur' in Dowson's version on 347, 377, 382, 383, 386, 408 infra. Now it appears from the Genealogies of the Afghans, that 'Gukboor' was the name borne by one of the famous forbears of the Sarwanis. He is said to have been the son of Suri, the son of Sarpal, the son of Sarbani. (Dorn, II. 52). He was the great-grandson of the primeval ancestor, Sarbani, and as he had several brothers, uncles, granduncles and cousins, the specific nisba or sobriquet 'Gukboor' came to be affixed to the names of his direct descendants, to distinguish them from other branches of the Sarwanis. In this translation 'Kalkāpūr' is affixed as a sobriquet to the name of 'Abbas Sarwāni (419, 428) and to that of his grandfather, Shaikh Bayazid Sarwani (388), both of whom belonged to the same family as Shaikh Malhi Kayal. Kalkāpūr looks like the name of a town or village, but any such supposition is negatived by the above explanation. Whatever the true reading may be-Kakbūr, Gakbūr, Gagbūr or Gazbūr-it is the name of a person and not of a locality.

Abul Fazl says in his account of the Afghāns that their remote progenitor Afghān had three sons, Sarban, Ghūrgasht and Batan, and that the Ghilzai, Lodi, Niyāzi, Lohāni, Sūr, Batni, Sarwāni and Kakbūr (variant, Gakbūr) clans or septs are descended from Batan. (Āīn, Tr. II. 402-3). Raverty states that the Sapis or Sasis belong to the Ghūrgasht division of Afghāns and are divided into three septs, Gazbūr or Gurbūz, Mas'ūd and Wader. He adds that a small clan of Afghāns called Guzbūr still dwells in the eastern part of Khost, between the rivers Tochi and Shamāl and belong to the great tribe of Wazīris. (Notes on Afghanistan, 105). Gazbūr is also said to be the name of a Balūch tribe in Makrān. (Houtsma, E. I., III., 266).

IV. 309, l. 3. ['Umar Khān held] as jāgīrs Bhātnūr, Shāhābād and Pāelpūr [in the Sarkār of Sirhind].

Shahabad and Paelpur [Pael] are both near Sirhind. 'Bhatnur' may

be a miswriting of Binnur (بنور) i. e. Bannur, which lies fifteen miles south-east of Sirhind and the same distance N. N. W. of Ambāla. It is the Banur of Bābur's Memoirs. (249 ante). Constable 25 D b

IV. 311, l. 16. He [Farid] also studied the Kāfiya.

The title of the work is Al-Kāfīyat fi-l-Nahw, i. e. "The Sufficient Book for Grammar" It is a Manual of Arabic Grammar composed by Jamālu-d-dīn bin Abu 'Amr Usmān, generally called Ibn-al-Hājib, who died in 646 A. H. (1248 A. C.) It is not easy to say whether young Farīd read or studied the Arabic original, or the marginal translation in Persian of Qāzi Shihābu-d-dīn-al-Jami (Ethé, India Office Catalogue, column 1313, Stewart, Catalogue of Tippoo Sultau's Library, p. 126). This Translation and Commentary is the Hāshiya Hindīa which is mentioned a few lines lower down. The Qāzi lived in the days of Sultān Ibrāhīm of Jaunpur and was known as the "King of Sages" among his contemporaries (E D VI 487, F II. 306, 1 22)

IV. 311, l. 17 He [Farid] had got by heart the Sikandar-nāma, the Gulistān, and Bostān, etc

This statement is repeated by Prof Qanungo (Sher Shah, p. 6) but it is founded on anerroneous translation and is, besides, hardly credible as it The Sikandarnāma must contain about seven thousand baīts, as it fills 140 pages of fifty couplets to a page in the lithographed edition of Nizāmi's Khamsa The Būstān cannot comprise less than four thousand The Gulistan is written in mixed prose and verse, but it cannot be much less in extent It is scarcely likely that young Farid could have "learnt by heart" about thirty thousand lines, and also read "the works of the philosophers" while he was at school in Jaunpur Nizamu-d-din Ahmad who has copied the passage from 'Abbas's chronicle does not say that Farid "committed these books to memory" The word he uses 18 خوالده (T. A 223, 11 8-9) and the word which Firishta uses is خوالده (I. 221, 1. 6). Dorn also speaks of his having " read the Gulistan, Bustan, and Sekandernamah ". (I 82) The word مدايد, which literally signifies "caused to pass, presented, submitted," is frequently used in connection with school and college classics and means nothing more than that the student read the books with or to the satisfaction of some teacher so as to acquire a passable knowledge of them. It is in fact synonymous with the 'Kafiya' and other . خوالد Thus the T. A says that he read (خوالد) commentaries and passed in [كدرانيد] the Gulistan and Bustan, whereas F inverts the order of the verbs and declares that he read (حوامد) the Gulistan etc and passed in [كدرابد] the Kafiya and its Commentaries and other text-books This word Loccurs several times in the Maasiru-t-(I 829, 1, 2 f f) مقدري طالب علمي داشت ترخي استحه متد اولكدرانيده اود Umarā also And again, کتب درسیه متداول در ایران کدراید (II. 285) It is said of Mirza With Chin Qulich that he read the ordinary text-books کتاب درسیه گدراید with his teacher, Mulla Mustafa Jaunpuri (III. 351) Tassy also says in his

translation that Farid read (lit) the Gulistan etc. (p. 10).

IV. 314, l. 13 from foot. He ordered his father's nobles to saddle 200 horses.

As Farīd's father, Hasan, was a commander of only 500 horse, he could scarcely have had any nobles (Amīrs) in subordination to him. 'Abbās himself says (p. 315 infra) that Farīd had no horses of his own at the time and obtained some after wards only by borrowing them from his tenants. It is therefore not easy to understand how he could "order 200 horses to be saddled" before he had got any. Dorn's version of the counterpart passage appears to be more correct. "He then ordered 200 saddles to be provided." (I. 83). The T. A. has copied the statement from 'Abbās and writes, (223, 1. 15) أد يد فر مود تا دوست ذين اسب ساختند. See also F. (I. 221, 1. 12) who has transcribed the very words of the T. A.

IV. 321, l. 21. On that occasion, [the battle with Qutb Khān], Farīd gained the surname of Sher Shāh and he bestowed that of Shujā'at Khān on Shaikh Ism'aīl.

There is something wrong here also, either in the original or the translation. The battle with Qutb Khān was fought very early in Farīd's career, about 935 or 936 H, whereas all authorities are agreed that he did not assume the imperial style and titles until about 945 or 946 H. Even if we read Sher Khān, instead of Sher Shāh, the statement is inconsistent with what 'Abbās himself states about Farīd having obtained the title of Sher Khān from Bahār (or Bahādur) Khān Lohāni, the King of Bihār, for his "gallant encounter" with a tiger. (325 post). The passage is reproduced in Dorn's translation of Ni'amatulla, (I. 93), but this statement about Farīd having "gained the title of Shīr Shāh on this occasion" is not found there. What 'Abbās himself wrote or meant to write was probably this: "At the time when Farīd himself assumed the title of Shīr Shāh, he bestowed that of Shujā'at Khān on Shaikh Ism'aīl."

IV. 323, l. 5 from foot. Muhammad Khān Sūr.....governor of the pargana of Chaundh.

This place is called 'Jaund' in the Ain. It was a Maḥāl in Sarkār Rhotās, Ṣuba Bihār. (Tr. II. 157). The pargana town of Chaund lies about forty miles west of Sāhsarām. "The area of the old Pargana of Chaund is now included in the modern one of Chainpūr. Chāwand is a common place-name in Tirhūt and is derived from Chāmunḍā, a name of Durgā, who, according to a local legend, destroyed a demon at this place." (J. Beames, "The Geography of India in the reign of Akbar (Ṣūbā Bihār), J. A. S. B. LIV. p. 181; Oldham, Journal of Francis Buchanan, 122, n. 3). Chainpur is shown in the I, G. Atlas. 29 A 2.

IV. 330, l. 11. [I was] in attendance on the Khān-i-Khānān Yūsuf Khail, who brought the emperor Bābur from Kābul.

At page 324 ante, this title is given to Daulat Khān Lodi and Dilāwar Khān is described as his son who was "sent to fetch Bābur". Professor Qānūngo points out that the Khān-i-Khānān mentioned here cannot kan a sent to fetch Bābur ".

Daulat Khān, as he was no longer alive and this man must be some other Afghān to whom Babūr or Humāyūn had given the title, but whom he is unable to identify. (Sher Shāh, p 180). At the same time, he maintains that 'Abbās has committed a blunder, because "Khān-i-Khānān Yūsūf Khail can be no other than Daulat Khān." (Ib 46 note).

I venture to say that the Khān-1-Khānān Yūsuf Khail who is mentioned here and also at 356, 357, 363, 368 and 379 infra is Dilawar Khan Lody. It was he who "brought the Emperor Babur to India" and not Daulat Khan In the Farman which was issued in Babur's name after the victory at Kanhwa, it is said that in the right wing were stationed "the Amīrs of Hind, the pillar of the State, the Khān of Khāns, [z e. Khāni-Khanan] Dilawar Khan, along with Malik Dad Kararani and Shaikh Guran." (B N. Tr. 567). Jauhar states that "Khan-1-Khanan Lody" was sent by Humayun with the advanced guard to Monghyr and that he was surprised and taken prisoner by a detachment sent by Shir Khan (Stewart's Tr. Rep. note 12), while 'Abbas tells us that the Khan-1-Khanan Yusuf Khail who had brought Babur to India was captured by Khawas Khan at Mungir and put to death as a traitor by the orders of Shir Shah (368,379) infra) Budauni gives Dilawar Khan the son of Daulat Khan Lodi the title of Khān-1-Khānān and says he "was living upto the time of the rebellion of Shīr Khān but at last died in prison". (Text, I 330, Tr I 436) F. explicitly declares that when Daulat Khan and his son Ghazi Khan proved false to their promises and turned traitors, Babur bestowed the title of Khān-1-Khānān on Dilāwar Khān (I 202, 1 7 f f) See also Ibid 204, 1 7 and 209, 1 4, where Diläwar Khan is styled Khan-i-Khanan and Erakine, H. B H. I 420

Lastly, the Emperor Jahāngīr states in the account of his favourite Khān Jahān Lody that Daulat Khān Lody was the uncle of Khān Jahān's grandfather and that when Daulat Khān died, "Dilāwar Khān was honoured with the title of Khān-i-Khānān and was with Babūr in the battle he had with Ibrāhīm" He adds that Dilāwar was taken prisoner when valiantly fighting in the thāna of Mungīr and that Shīr Shāh "ordered him to be shut up in a wall," because he refused to take service with him. "Thy ancestors," he said, "were always the servants of mine, how then could I do this!" (T J. Tr I 87-88, 42, 1 10 ff).

IV. 331, l 9 They placed before him a solid dish, which he did not know the customary way of eating

Dorn says that the dish is called 'Māhcha' () and that according to the Tārīkh-i-Faiz Bakhsh of Shiv Prasād, [a recent compilation of no particular authority, q v E D VIII 175], it is also called 'Usbekiah' (II 101) In the Ghiyāsu l-Lughāt is explained as "threads made out of fine wheat flour, cooked with milk and sugar, which is called in Arabic Atriya id. It would appear to have been some sort of sweet dish—a pudding or custard made of macaroni In an interesting note to his translation of the Akbarnāma, Mr. Beveridge has pointed out that

"Ash-i-Māhcha" is mentioned in a Farman issued by Shah Tahmasp in connection with the reception and entertainment of Humayun in Persia and that it was a delicate kind of sweetmeat or confection. Hājji Dabīr describes the sale as a succulent dish, but like macaroni difficult to eat. (Ed. Ross. 951). He also relates this curious anecdote, but the details are somewhat different. According to the version he had heard, Shir Khān did not cut up the 'Māhīcha' with his dagger, but ate it with his This unseemly exhibition of ill-breeding so angered Humāyūn that he ordered him to be forthwith turned out of the company. Shir Khān is said to have never forgotten the affront and it was the origin of the implacable hostility between the two men. Whichever version of the tale may be nearer the truth, it is interesting to find that the incident itself was remembered by persons living in the reign of Akbar. B. also had heard the anecdote and speaks of Bibur having observed Shir Khan "behaving in a manner which deserved censure at a banquet", (I. 359= Tr. I. 469). This independent version shows that the story was not invented' by 'Abbas as Prof. Qanungo suggests, 'Abbas Khan must have heard this story like the one which immediately precedes it from his uncle. Shaikh Muhammad, who explicitly states that he was present in Bābur's camp at Chanderi and took part in the siege.

IV. 342, l. 9. Sher Khan drew out....a picked force.

Abul Fazl states that the battle took place at Surajgarh. (A. N. I. 148=Tr. I. 328). This place lies on the right or south bank of the Ganges in a plain between that river and the Kharagour hills and is situated about twelve Kos or twenty miles west of Monghyr. (See Note on IV. 508 post). Mr. Beveridge hazards the conjecture that Abul Fazl must be wrong and 'Surajgarh' must be a slip for Teliagarhi in the Sonthal parganas. (loc. cit. note). Erskine, however, follows Abul Fazl and locates the battlefield at Surajour above Monghyr. (H. B. H., II. 136). Thornton observes that Monghyr is situated in a position of considerable strategical importance. "The route from east to west, from Berhampore to Benares by Patna and Dinapur, is the only route by which the mountainous tract extending southward into the Ramgarh district is avoided; and from lying along the right bank of the Ganges, it has the further advantage afforded by the navigation of that great river." It may be noted that 'Adli also was routed by Khizr or Bahadur Khan Gauriya in a battle fought at Sūrajgarh. (Tārīkh-ī-Dāūdi, 508 infra). Abul Fazl is probably right and Mr. Beveridge's surmise, which is not supported by any authority of weight, seems uncalled for.

IV. 346, last line. Hasan Khān.....and the Rājā of Dūngarpur, Rāwal by name, were slain.

There is some error here. "Rāwal" was the general titular designation of all rulers of Dungarpur, as 'Rāṇā' was that of their cousins, the Sisodiā rulers of Chītor. The name of the chief who fell at Kānhwa was Udi (Udaya) Sinha, according to Bābur's own Memoirs. (B. N. Tr. Beverid

573). The text of the passage in 'Abbās's chronicle must have been corrupt, as Dorn's translation or paraphrase is even more egregious in error. His rendering is "Hasan Khan ben Alauel Khān of Mewat was slain in the territory of the Raja of Dunkerpoor." (I 101) Abul Fazl informs us that Rāwal Pratāp was ruler of Dungarpur in the twenty-first year of Akbar's reign and that his daughter entered the Imperial harem. (A N III. 196 Tr. III. 277-8). The rulers of Dungarpur are still styled Mahārāwals (I. G. s. n).

IV. 349, l. 14. The two armies met at Lucknow

Jauhan's statement about the site of the battle is more precise. He says that it was fought at 'Doura' on the bank of the Gudi or Gumti (Tr. Reprint, p 3, Erskine, H B H II 10 note) This is the village of 'Dounru', about 15 miles north of Jaunpur. F also locates the battle somewhere near Jaunpur (I 224, 1 17)

IV 350, l 9 from foot Sher Khan withdrew, to the hills of Nahrhunda

Correctly, 'Bharkunda' which is entered as a Mahāl in Saikār Sharīfābīd (Bīrbhūm) in the Āīn (Tr II 139) But Blochmann states that the name was extended to the whole of the Bīrbhūm and Santāl parganas and it is in this "extended" sense that it seems to be used here In Blaeve's Map, 'Barcunda' is said to extend from "Bardwān to Garhi, the Gate of Bengal." (Notes on the Geography and History of Bengal in J A.S B XLII, 1873, p 228). Rennell calls it 'Byrcoodah' The par gana town hies about fifty miles south of Chunār. Lat. 24°-34' N Long. 83°-34' E 'Bohnkundal' at p 419 looks like another corrupt form of the same name. IV. 352, l. 13 Sultān Bahādur went to Sūrat

'Sūrat' here is a mistake for 'Sorath' Bahādur Shāh of Gujarāt fled from Mandū to Chāmpāner and thence to Ahmadābād, Cambay and Diu (T. A. in E. D. V. 193, Mirāt-i-Sikandari, Tr Bayley, 390) and are often confused in Persian manuscripts and even Rogers and Beveridge have not been able to escape the pitfall, as they speak of "the fort of Junāgar being in the country of Sūrat", in their translation of the Tūzuk i-Jahāngīri (II 19)

IY 352, l. 12 from foot M'arūf Farmuli joined him [Shīr Shāh]

The tribal name is written 'Qarmali' in the C H I. (III. 245), probably because it is spelt with the dotted Qāf in the lithographed texts of the T A and F. But the balance of authority is undoubtedly in favour of Faimuli The name must have been spelt with a and not a in the Mss of the Tārīkh-i-Shīr shāhi, Tārīkh-i-Dāūdi and Wāqi'āt-i-Mushtāqi, from which the extracts in Elliot's work were translated and also in Dorn's translations from Ni'amatulla. The authority of Abul Fazl also is in favour of the identical orthography (A N I 100, Tr I. 251, Āīn, Tr II, 399, 401) A still higher authority—the Emperor Bābur—speaks repeatedly of 'Farmul' in his description of Kābul (B. N Tr. 200, 206, 231, 233, 235) He explicitly states that the "Shaikhzādas, the descendants of Shaikh Muhammad

Musalman, who were so much in favour during the Afghan period in Hindustan, came originally from Farmul." (Ibid. 220). He tells us that Farmul was one of the 14 sub-divisions (tumān) of the Kābul district. If lies south-east of Ghazni. Its principal village was Urghun (Ib. 206 n.) which is shown in Constable, 24 C'a. Among modern writers, Erskine (H. B. H. II, 466). Raverty (N. A. 32 note and 86) and Sir C. R. Markham all vote for Farmuli or Farmuli. Raverty states that the Farmulis are named after the village of Parmul or Farmul which is situated on the river Tonchi and that Afghans generally do not admit their claim to be considered Afghans. We' read in the Makhzan-i-Afghāni also that "Farmul is the name of a river running between the confines of Kabul and Ghazni and that the Farmulis were so called because they lived on its banks. Their ancestor was converted to Islam by Shaikh Muhammad Musalman, a great saint among the Afghans and having passed some time in his service, they stylethemselves Afghans, though they really came from Khata and Khotan". (Tr. Dorn, II. 57). The Emperor Jahangir refers to the Farmulis' residing in Kābul. (T. J. Tr. I. 197 note). Sir Clements Markham tells us that the "valley of Furmul is at the back of Khost, which is watered by the Tochi in its upper course" and that the "Tājīks who now inhabit it have one village called Urghun'. (Proc. Royal Geographical Society, 1879, pp. 47, 48). Sir E. Denison Ross (C. H. I. IV, 16) and Mr. Dames (Houtsma, E. I., II. 68) also write 'Farmul'. This consensus of authorities. leaves no doubt that 'Qarmali' has its origin in the blunder of some copyist who read the initial letter amiss.

IV. 355, l. 14. When Nasīb Shāh.... died.

He is more commonly called [Nasiru-d-din] Nusrat Shah. But there is no reason for rejecting, as Mr. Beveridge does, (A. N. Tr. I. 332 note), the reading. 'Nasīb Khān' was the name he bore before he came to the throne.' 'Nasib' seems to have been a not uncommon name in these times: One of the three sons of Qatlu Lohani is said, in the Makhzan-i-Afghāni, to have been called 'Nasib Shāh'. (Dorn, II. 115). See also A. N. III. 649, l. 5; E. D. VI. 90, Blochmann, Ain, Tr. I. 520. A suburb of Murshidābād in Bengāl is still called Nasibpur. (Akbar Nāma, Tr. I. 333 note). Budāuni mentions a Nasīb Khān Taghūji as an Afghān Amīr who rebelled against Muhammad 'Adil Sur and was one of the chief adherents of Sikandar Sur. (I. 432, 459: Tr. 542, 593). Saiyid Naşîb Khan Barha ismentioned by the Emperor Jahangir. (T. J. 310, l. 3 f. f.; Tr. II. 167). The name of a Nasib Turkman also frequently arrests attention in the A. N. (III. 314, 413, 424, 471 and 619 and the T. A., Text, 376, l. 12). Nuṣrat Shāh died about the middle of 939 A. H.=January 1533 A. C. (Blochmann in J. A. S. B. (XLIII), 1874, p. 306).

IV. 355, l. 26. Mihr Sultān died on her way to the pargana of Kayat.. Garcin de Tassy's reading of the place-name is Kānt, كَانَت (p. 74). كَبُّت (Kayat) is most probably a miswriting of كنت (Kant) with the dot misplaced. Kant and Golā were two parganas in the Sarkār of Budāun. (Āīn,

Tr. II. 289) and are now included in Shāhjahānpur district Kant is in Lat. 27°-40′ N., Long 79°-51′ E, and is shown in Constable's Atlas, Pl 28 A b It is situated about ten miles south-west of the modern town of Shāhja hānpur, which was founded by Bahādur Khān Dāūdzai some time before 1059 A. H. 1649 A C (Ma'āsiru-l-Umarā, I.415) Shāhjahānpur district is in Rohilkhand and has a very large Afghān population Mihr Sultān was probably going to settle with her relatives there Kant and Golā are mentioned as the jāgīrs of 'Isā Khān Sarwāni at 384 infra

IV 357, l 27 The Rājā of the fort of Rohtās and Chūrāman, the Rājā's nātb

'Abbās does not give the name of the Rājā, but says that his minister was a Brāhman named Chūrāman Abul Fazl makes the Rājā himself a Brāhman and gives him the name of Chintāman (A N I 153, Tr. I 335) F calls the Rājā Hari Kishen (I. 225 l) Dorn follows 'Abbās (I. 137), but Erskine speaks of the Rājā as 'Hari Kishan Birkis.' (H B. H II. 147). 'Chūrāman' [Chūdāmani] and [Chintāmani] are both used in Sanskrit for certain kinds of gems or jewel-ornaments and are liable to be confused with each other by Musalmān scribes The sobriquet which has been read by Erskine as Bai kis (را المنافية) seems to be a misreading or reduplication of Harkishen (مرافية) Some copyist who had found it in the margin of an old manuscript as a variant wrote it side by side with in the body of the text, and this came to be read as "(Barkīs) and understood as a part or adjunct of the name itself

IV 359, l 8 [He said] 'If you do not admit him into the fort, I will take poison and die at your door'

This is the old Hindu custom which is known in Gujarāt as 'Trāga' and in Malwa and elsewhere as 'Chandi'. (Malcolm, Central India, Ed. 1832, II 137) Another arresting example of it will be found in B who says that when Akbar put under arrest Yusuf Khan, the ruler of Kashmir, (who had come to his Court under the safe-conduct promised by Bhagwandas Kachhwa of Amber) and talked of putting Yusuf to death, the Raja, from a sense of honour, stabbed himself with a dagger and threatened to put an end to his own life (II 353, Tr Lowe, 364) There is an allusion to Trāgā in the Mirāt-i-Sikandai i (Text 328, Bayley's Tr 433) also Some blood-curdling tales of the actual performance by 'Charans' of this ghast-' ly rite are narrated by Forbes (Ras Mala, Reprint, II 262, 263, 387, 429; Enthoven, Tribes and Castes of Bombay, I 284-5, Yule, H J s v Traga) For the derivation of Traga, which is much disputed, see my 'Notes on Hobson Jobson' in the Ind Ant LVIII, 1929, p 210 It seems to me to be a perversion by metathesis of the Gujarāti 'tagādo' which is derived from the Arabic المامية

IV 364, l 7 from foot Par gana of Munir Shaikh Yahyā, where they heard that Sultān Mahmūd Barri, the King of Gaur, was come Birlās went out to meet him

Read, " where Sultan Mahmud, the King of Gaur, was come. Barn

Birlas went out to meet him". The printer has dislocated and jumbled the words. It was 'Barri Birlas' who went out to meet the Sultan. ' Barri' was not the sobriquet of Mahmud the King of Gaur, but the name of an Amīr of the Birlās tribe who was in Humāyūn's service. Gulbadan speaks of him as 'Mîr Bardi Beg'. (Text, 22, 1.13; Tr. 106). Dorn calls him 'Huri Birlas' (I. 112), but he involves himself in another sort of error, when he makes his author state that 'Huri' Birlas and Khan-i-Khanan Yūsuf Khail were "both Afghans". (Ib. 111). The latter only was an Afghān. The Birlās is a Chaghatāi or Jaghatāī clan. The name may perhaps be read as 'Hari' or 'Huri Birlas,' as هري ملك تواچى and another معتبد هرى ملك are mentioned in the Zafarnama of Yazdi. (II. 26, last line and 59, 1. 2). But 'Barri' or 'Bari' may be correct as Garcin de Tassy calls him Pari Barlas. (l.c. 83, 84). A Pari Beg who was Mir-i-Shikar-Chief Huntsmanof Shah 'Abbas of Persia brought falcons as presents to Jahangir. (T. J. 280, l. 5 f. f.=II. 107). Barri Birlas is again mentioned by 'Abbas himself on this very page (1.9 f. f.) and on 365 (1.4).

Muner or Maner lies 20 miles west of Patna and the Son used to join the Ganges there in the days of Abul Fazl (\$\overline{Ain}\$, Tr. II. 150) and also of Rennell, whose Atlas was compiled in 1772. The junction now takes place about ten miles higher up. It is called the 'Maner of Shaikh Yaḥyā,' because a saint of that name who was the father of another \$P\overline{i}r\$ named Sharafu-d-d\overline{i}n\$ is buried there. Shaikh Sharafu-d-d\overline{i}n Maneri was a great S\overline{i}n\$ and his writings on the mortification of the human passions and desires were greatly admired by Akbar (\$\overline{Jin}\$, Tr. I. 48 note, and 103; III. 370), as well as by Aurangzeb. (\$Ma\overline{aisir-i-Alamgiri}\$ in E. D. VII. 161). Shaikh Sharafu-d-d\overline{i}n\$ died in 782 H.=1380-1 A. C. Maner is in Lat. 25°-7' N., Long. 84°-50' E. (Th.). Sikandar Lody as well as B\overline{a}bur paid a visit to the saint's tomb. (462 infra; B. N. Tr. 666; F. I. 211, I. 4).

IV. 365, l. 3. Muyid Beg, son of Sultan Mahmud, and Jahangir Kuli, son of Ibrahim, Bayazid, Mir Nurka.

The names as printed are more likely to mislead than enlighten the reader. Muyyad Beg was the son of Sultān Muḥammad Duldai (not Sultān Maḥmūd of Bengal). Sultān Muḥammad Duldai Birlās was an old servant of Bābur and is mentioned frequently in his Memoirs. (B. N. Tr. 294, 295, 465, 466, 582, 638, 686). Mirzā Ḥaidar tells us that Jahāngīr Quli was the son of Ibrāhim Begchik. (Tārīkh-ī-Rashīdī, Tr. 470). He is called Ibrāhim Beg Chabūk or Chapūk in the A. N. (I. 149—Tr. I. 330). Mīr Nūrkā may be an error for Mīr Nūr Beg who is frequently mentioned in Bābur's Memoirs. See Note on IV. 276, l. 5 f. f. ante.

IV. 368, l. 1. [ShīrKhān] went by way of Jhārkand to Rhotās.

'Jhārkhand' ['Forest region'], is a geographical expression of very extensive and indefinite connotation. Blochmann writes that in the Akbar-nāma, the whole tract from Bīrbhum and Pachet to Ratanpur in Central India and from Rhotāsgarh in South Bihār to the of Orissa is called Jhārkhand' or 'Jungle-land'. (Notes of tr.)

Pachet and Palamau in J. A. S. B. Vol. XL, 1871, p. 111) It is not a clear-cut topographical designation and is generally used for the hilly and forest region of Chutia Nagpur from Rhotas to Birbhum and perhaps, further.

IV 368, 1 30 Sher Khan sent Khawas Khan against Maharta, Zamindar. The name of this man is so written in all the chronicles, but the correct form is, perhaps. Bharat The Cherubs are mentioned by Abul Fazl as the principal zamindars in Ramgarh, Char Champa and Pundag ın Palamau (Ain, Tr II. 154 note) The Razas of Palamau were Cherühs and Partab the son of Balbhadra Cherüh who was Raja in the time of Shah Jahan was, after two invasions, compelled to pay tribute to the Mughal Emperor in 1642-43 A.C Seventeen years afterwards, the country was finally conquered and annexed to the Empire by Aurangzeb (1660 A. C.). I have cited before Blochmann's article in the J A S B (XL. 1871) on Chutia Nagpur, Pachet and Palamau. To that article he has appended an informative postscript or Note by Mr L R Forbes, Extra Assistant Commissioner of Palamau at the time This local antiquary writes thus of Bharat Cheruh "The fort of Deogna, one of the three strongest forts of Palamau which is mentioned in the Badishah Nama, (the two others being Kothi and Kunda), was built by Bharat Rai, a renowned border chieftain, more probably a bold and successful cattle-lifter". (p. 131) Of another fort called Mangarh or Tarhasi Ithe Narsi of the Alamairnāma], it is said that it was "originally built by Mansingh, a Raksel, but taken possession of by the Cherûhs under this Bharat Rai" These local traditions are not, perhaps, without value and they may provide a clue to the determination of the real name of "the renowned border chieftain", who appears to have harassed Shīr Khan to some purpose and to have been regarded by him as an opponent whom it was absolutely necessary to crush.

Gaicin de Tassy's reading is 'Sarak' (l c 97). Dorn calls him 'Husain Khan Surk', and says "he was then highly advanced in years". (I 123) 'Khizr Khān Surk' (ا العربة) is mentioned by B. (Text, I 364, Tr. 474), Nī'amatulla (E D. V 115) and others, as gover nor of Bengal under Shīr Shāh But he is called Khizr Khān Bairak in Elliot's version of 'Abbās. (p 390, infi a) Surk was the name of one of the ancestors of the Lodi tribe Surk 'Umar was the paternal uncle of Malik Shāhū, whose son was Baseen, whose son was Bahrām, whose son was Kālā, whose son was the (Sultān) Buhlūl Lody. (Dorn, II 51) A saint named Ḥasan Surk Batani is also mentioned in the Makhzan-i-Afghāni (Ib II, 120). Surk is, probably, correct. 'Nīrak' and 'Bairak' must be errors. 'Bairak' Niāzi also, on 416, 18 infra, should, perhaps, be read as Surk Niāzi

IV. 377, l. 13 from foot. He [Shir Khan] seated himself on the throne and struck coins and caused the Khutba

to be read in his own name.

The year in which Shīr Shāh took that title and assumed the rights and privileges of an independent sovereign has been variously given as 945 by Elphinstone, Thomas and Vincent Smith (O. H. I. 326), but 946 or 947 by others. His coins of 946 H. are not uncommon and there was one dated 945 H. in the Marsden collection (C. P. K. D. 397 note), but the date on it was not clearly defined. Better specimens however have been now discovered and at least four are registered in Mr. Nelson Wright's 'Coinage and Metrology of the Sultans of Dehli', Nos. 1040 A, 1040 B. 1257 and 1270 A. (See also p. 386). Mr. N. K. Bhattasāli has also described three other rupees which are of a different type, but exhibit the same date. (Islamic Culture, January 1936). He places the coronation of Shīr Shāh somewhere about the middle of Safar 945 H. Prof. Qānungo's contention (Sher Shah, pp. 205-208), that he assumed the title only after the battle of Chausa in 946 H. is thus proved to be unsound and Thomas appears to have been right in holding that he "assumed the title of Shah or King of Bihar" during the isolation of Humayun in Bengal. (op. cit. 393). The young men of the army came in crowds IV. 377, 1. 3 from foot. and danced, as is the custom of the Afghans.

Below at p. 391, 'Abbās himself is made to say by the translator that 'Bhopāl' was the name of the Rājā and not of the town or country.' Bhopāl' is there said to have "possessed the country of Bijāgarh and Tamhā (var. Mabhār)." According to Dorn's version, "Peemgur and Mahoor were possessed by Bhopāl." (I. 124) M. de Tassy also states that "Rājā Bhopāl possessed Bijāgarh and Mihra." (loc. cit. 101, 120). Abul Fazl records that "when Humāyūn arrived at Āgra (in 943 A. H.), Bhopāl, who was in Bijāgarh (in Nimār) finding the fort of Māndū empty, boldly entered it". (A. N. I. 145=Tr. I. 322. See also E. D. VI. 18). What 'Abbās really states here is that 'Bhūpāl was Rājā of Mahesar' (Variant, Mabhār, i.e. Nimār?). Bijāgarh is about sixty miles south of Māndū and about the same distance north-west of Burhānpur. It is now in the Nimār district of Indor State and Khargon—a place in its neighbourhood

—is the district headquarters. 'Tamhā' [variants 'Mabhār' and 'Mihra,' q. v. Tassy, 120], must be a miswriting of his Namhār, i.e. Nimār The importance of the town of Bhopāl dates only from about 1735 A.C., in which it was founded. (E. D. VIII. 59). It was an insignificant village before that, and is never mentioned in any old chronicle Bijāgarh, Khargon and Nimār are all shown in Constable's Atlas, Pl 27.

IV. 378, l 20 Mallū Khān put his seal at the head of the letter which he sent.

The story of the seal is told by 'Abbas incompletely and not quite fairly. He has suppressed the material fact that the provocation was first given by S'ir Shah himself, and not by Qadir Shah, as his mode of relating the event implies F (II. 270) and Nizāmu-d-dīn Ahmad (T A. 591) state in the Malwa Sections of their chronicles that when Humayun invaded Bengal and took possession of Gaur, Shir Khin addressed to Qadir Shah and other rulers, a Farman urging them to harry and rayage the Agra province and other Mughal territories in the vicininty of Malwa. with a view to effect a diversion in his own favour As Shīr Khān had placed his seal at the top of this Farman, Qadir Shah affixed his own seal in exactly the same spot, in his reply Mallu Khan bad, before this. assumed the imperial style and title of Qadir Shah and had even struck coms in his own name. (Numism. Suppl No XI to the J. A. S B (1909). Art 63, p. 316). He consequently regarded Shir Khan's arrogation of superiority and suzerainty as an affront and declared that self-respect and kingly dignity required that he should get even with and mete out to Shir Khan the same treatment which he had thought fit to mete out to himself. Erskine tells the story in the same way (H. B H II. 430). The etiquette in regard to the fixing of seals was very strict Babur complains that "Shah Beg Arghun had the incivility to seal his letter to me in the middle of the reverse, where Begs seal if writing to Begs or a great Beg if writing to one of the lower circle" (Bāburnāma, Tr Beveridge, 332). Morier explains that when the King of Persia writes to an inferior, the seal is affixed to the top, when to an equal, it is placed at the foot of the letter, or on a separate piece of paper" (First Journey to Persia, 219). See also Briggs, IV 371 note. Chardin gives us some very curious and interesting information on the Persian code of epistolary etiquette.

IV. 380, l 2 Humayun arranged his army and came to Kanauj

This "irretrievable rout" of the Chaghtais is generally said to have taken place at Qanauj, but the actual site was somewhere in Hardon district and on the other side of the Ganges, at some miles distance from Qanauj itself (I. G XIV 371) 'Abbas states elsewhere (419 infra) that Shīr Shāh built a city on the spot where he had gained his victory and called it 'Shīr Sūr' (Recte Shergarh) This Shergarh is situated about four Kos from Qanauj

IV. 382, l. 2 Ghāzi Mujli.

The Tarikh-i-Daydi calls him 'Ghazi Mahli' على (482 post) and B,

and F. (I. 229) have the same reading. The T. A. speaks of him as Mahldar' (234). Firishta (I. 229, 1. 7 f.f.) and B. (I. 376=Tr. 487) say he was المعالمة المع sonal attendants " of Islām Shāh. He was probably a man employed in the 'Mahl', i. e. the female apartments or Seraglio. He is spoken of as "Mahram", because he had the entry of the harem and may have been one of the eunuchs in charge of the wives and concubines of the Sultan.

Erskine speaks of him as one of the chief officers of the Household. (H. B. H. II. 451). The right reading is, most probably, 'Mahli', but or or was an Afghān name, e. g. Malhi Qattāl, and it may have been his own name or that of his father. IV. 382, l. 11. Kuth Khān Banet.

This sobriquet also assumes several forms. He is again called Banet' on p. 387 infra, but some Mss. of this chronicle have the reading Manib. (Ibid, footnote). In the T. A. (235), F. (I. 229) and the Tarikhi-Dāūdi (481 infra), he is called 'Nāīb', and Dorn has 'Nasīb'. (I. 116, 118, 126). Shīr Khān had a son named Qutb Khān, who must have been called Qutb Khān Sūr. A Qutb Khān Mochi-Khail is mentioned by 'Abbās at p. 350 and Qutb Khān Lody at 381 supra. There was also a Qutb Khān Niāzi. (Ahmad Yādgār in E. D. V. 43). Perhaps in or in is an error for si, Batani, or size Baitani, the name of another Afghan tribe. Hājji Khān Batani is mentioned at 378 ante note and Dorn, (I. 126). The name of Adam Khan Batni is found in Dorn, I. 128 and that of Fath Khān Batni in Budāuni. (II. 33=Tr. II. 27). But the balance of authority appears to be in favour of بال.

IV. 383, l. 5. [Shīn Shāh sent] Barmazīd Gūr [in pursuit of Humāyūn]. All the Musalman chroniclers are unanimous in calling him Barmazīd (T. A. 235, l. 10; F. I. 230, l. 20; B. I. 379=Tr. 490), but Prof. Qānūngo has in his monograph on Shīr Shāh hazarded the conjecture that this man was a Rajput named 'Brahmaditya or Brahmajit Gaur'. (op. cit. 197, 225, 369). It is therefore necessary to stress the fact that Mazīd and Barmazīd were and are common names among Afghāns as well as Turks. A Mazīd who was the chief man of Indarāb and Auzūn Mazīd Baghdīdi are mentioned in the histories of Timur. (E. D. III. 401, 491). Several other persons bearing the name, e.g. Shaikh Mazīd Beg, Mīr Mazīd Taghāi and Mazīd Beg Tarkhān Arghūn, are mentioned in the Bāburnāma. (Tr. 26, 27, 131, 167 and 51). The great leap of 25 feet across a gorge which is described by the Akhund Darveza was taken by the horse of a Sadozi named Barmazīd. This Barmazīd was the brother of the famous Khān Kāju who was a contemporary of Humāyūn and flourished about 956 H. (Raverty, N. A., 202, 227). Abul Fazl states that when Humāyūn marched to Bangash in 959 H., with a view to punish the rebellious Afghans, the first tribe attacked was the 'Abdur Rahmāni, the last the Barmazīdi. (A. N. I. 323=Tr. I. 598). This clearly shows that Barmazīd was

Gūr or Kūr also is a not uncommon sobriquet Bābur mentions a Mīrak Gūr (or Kūr) who was the Diwān of Bad'īu-z-zamān Mirzā (B N 328) Abul Fazl speaks of Idi Kūr or Gūr (A N III 298=Tr' III 441) and Maqsūd Ali Kūr or Gūr (Ibid, III.304=Tr III. 450) This last name occurs also in the T. A. (249, l 12=E D V 259) Mīr Husain Kūr (or Gūr) was one of the nobles of Tīmūr (Malfūzāt in E D III. 404). In the Tārīkh i-Dāūdi, the subject of this note is styled Barmazīd Sūr (485, 486), but this also indicates that the author who was himself an Afghān, was sure that the person intended was an Afghān and not a Hindu

IV 383, l 10. The Emperor Humāyūn told Amīr Sayyıd Amīruddīn The name has been miswritten or misread The person to whom Humāyūn told the story was Mīr Sayyıd Raf'īu-d-dīn Īji (Jauhar, Tr. Reprint, 38, A. N. I. 167, Tr. I 355, Dorn, I 128, Tassy, 109) He was one of the most learned men of his day and the leader of the 'Ulamā (402 unfra). Abul Fazl states that he was a Husaini Sayyıd firom Shīrāz and that Humāyūn went to his house and took counsel with him on the morning after his arrival in Agra after the defeat Mīr Raf'īu-d-dīn was the teacher and patron as well as relative of Abul Fazl's father, Shaikh Mubārak, and there is a long account of him in the Āīn, (Tr III 423-4) He died in 954 H. He is called Mir because he was a Sayyıd He was not an Amīr

IV. 385, l 12 from foot One Shaikh Gadāi was in Gujarāt to whom he [Bairam Beg] did good service

The meaning of the author is just reversed in the translation. It was Shaikh Gadāi who had rendered "good service" to Bairam. Of what Nizāmu-d-dīn Ahmad says. "At this time, the dignity of Sadārat-i-Mamā-lik (the office of Lord Chief Justice) was conferred upon Shaikh Gadāi,

, through the interest of the Khān-i-Khānān [Scil Bairam Khān], who remember ed the kindness which he had received from the Shaikh during the time of his exile in Gujarat" (T A Trans in E D V. 259) Abul Fazl tells us that Shaikh Gadāi had behaved well to Bairam Khān and showed him kindness during the time of his [Bairam's] sojourn in Gujarat. (A N. II 20=Tr II 36) Tassy also understands the sentence to mean that Shaikh Gadāi had tendered his good offices to and accompanied Bairam part of the way until he left the province (loc cit 112).

IV 388, l 11. Sharkh Ahmad Sarwāni who was the grand-father of Sharkh Malhi Kayāl

According to the Afghān Genealogies, Shaikh Mulhi Qattāl was the son of Shaikh Sulaimān Dānā, the son of Ahmad Jawānmard, the son of Mūsā, son of Mahmūd, son of Maulānā Gulbūr, son of Sūri, son of Sarpal, son of Sarbani (Dorn, II 52 See also Ibid, I 129 and II 27) This shows that Shaikh Malhi was the great-grandson of Maulānā Gukbūr, who was the great-grandson of Sarbani Shaikh Bāyazīd Sarwāni, the grandfather of 'Abbūs, is given the sobriquet of 'Kalkāpūr' by Dowson, but it is clear from this pedigree that 'Kalkāpūr' is a mistranscription or misrcading of some personal name like 'Gukbūr', 'Gugbūr' or

'Guzbūr', and not a place-name. M. de Tassy calls the Shaikh Mulhi 'Quitāl' and speaks of his grandfather as 'Shaikh Ahmad Kakbor Sarwani.' (p. 115).

The name of the Saint reminds one of Shaikh Mali or Malhi who is stated to have written a History of the conquest of Swat by the Yusufzais between 1413 and 1421 A.C. It is said to be the earliest known work in Pushtu. (T. H. Thornton's Art. on Punjab Literature and Folklore in J. R. A. S. 1885, p. 389; Encyclopaedia Britannica, Ninth Edition, I. 238, s. v. Afghānistān). The sobriquet is spelt 'Kayāl' by Dowson, but 'Qattāl' by Dorn and De Tassy and this seems to be more correct, as it is assigned to several other Saints also, e. g. Sayyid Sadru-d-din Rajū Qattāl, who was the brother of the still more renowned Shaikh Jalalu-d-din Makhdumi Jahīniān and died in 806 H. (Ain, Tr. III. 371-2; F. II. 417-8; Beale, Mistal, 98). Another member of the same family, Sayyid Sultan Ahmad is also styled Qattāl and Jalālpur in Shujābād talisil, Multān district, is called Jalalpur-Piricala or Jalalpur of the Pir, because he died and is buried there. (I. G. XIV. 16). Shaikh Yusuf Qattal lies buried in Dehli and his mausoleum near the mosque in Kharki was built in 903 H. (F. Cooper, op. cit. 94; Asar, I. 23). Another saint Jamal Qattal, who was a disciple of Shaikh Sharafu-d-din Maneri, is mentioned by Abul Fazl. (Ain, Tr. III. 370). Still another named Mu'inu-d-din Qattal, who was the grandfather of the more famous Shaikh Muhammad Ghaus, is buried at Jaunpur. (Houtsma, E. I., III. 687). The raison d'être of the epithet also is stated by Firishta. (II. 417, l. 9 f.f).

IV. 389, l. 9 from foot. But the Kāzi-ali.....spoke ill of us and said.

The manuscript used seems to have read of, 'high', 'exalted', 'chief', but the correct lection is undoubtedly, 'Alī of. We know that Qāzi 'Alī was deputed in 936 A. II. to the Punjāb to make inquiries-respecting the lands held in rent-free tenure. He was directed "to resume the old tenures, to measure them and to include them all in one district". (Budāuni, II. 254—Lowe II. 261; see also A. N. Tr. III. 343). He was appointed Bakhshi in 987 H. (A. N. Tr. III. 423) and killed in Kashmīr in 999 H. (Āīn, Tr. Blochmann, I. 346).

IV. 390, 1. 9. A short time afterwards, he [Mir Sayyad Hāmid Bukhāri] was himself slain.

As Sayyid Hāmid was killed in fighting against the $T\bar{a}r\bar{\imath}kis$ or Raushanais, towards the end of 994 H. (A. N. III. 510 = Tr. III. 777; T. A. 371, l. 9=E. D. V. 455; B. II. 354=Lowe, 366; Blochmann, $\bar{A}\bar{\imath}n$, Tr. I. 397), the allusion furnishes an important piece of internal evidence for fixing the inner limit of the date of composition of the $T\bar{a}r\bar{\imath}kh$ -i- $Sh\bar{a}hi$. See my note on Vol. IV. 301 supra.

IV. 390, l. 16. The hills of Padman and Girjhak.

'Padmān' is an error for 'Lid', Nadnān, i. e. 'Nadnā', 'Nandana' or 'Nindūna' of p. 389 supra. 'Girjhāk and Nandnā' are both in the Salt Range—the Gakhkhar country—and are both mentioned in jur'

in Dorn (I 129=E. D V. 114) and also by the Emperor Jahangir. (T. J Text, 61, 1 3 f. f.=Tr I. 81, 91, 1. 3 f f=Tr I. 129). Nandna lies about twelve miles distant from Jhelum town, Lat 32°-43', Long 78°-17'. It is a place of strategic importance and was captured by Mahmud of Ghazni. It stands on a rocky hill which commands the route across the outer Salt Range Girjhāk lies near Jalalpur in Pind Dādan Khan tahsīl of Jhelum district, Jalalpur is situated about thirty miles south of Jhelum, in a narrow valley extending between the river and the eastern extremity of the Salt Range It is one of the great passages of the Jhelum on the route from Afghanistan to India and is supposed by Elphinstone, Cunningham, Chesney and others to have been the site of Alexander's battle with Porus Lat 32°-39', Long 73°-26' (Thornton; I G XIV 14) Constable, Pl. 24 E a. 'Girjhak and Nandana' are both mentioned by Minhaj Inthe T N. (Text, 179, last line), he specifies in the list of Iltutmish's conquests, two places, the names of which were read by Raverty as "Nandanah and Gujah or Kujah" (Tr 627) There can be little doubt that the right reading is not Gujak, but \$\int_{\sigma} Girjh\bar{a}(k)\$

IV 397, l 6 from foot Bhaia Puran Mal sent 600 elephants, but did not himself come out

Puran Mal, the son of Silhadi, is styled 'Purabi' by Ni'amatulla, Silhādi is said to have been a 'Tuar' by Tod (A. A. R., Ed Crooke I 356), but a Gehlot [or Guhilot] by the T A (231, l. 15) and Dorn (II 104 notes) The question is not easy to decide, but the latter opinion seems to be invalidated by the fact that one of the wives of Silhadi was Durga, a daughter of the Rānā (Scil of Chitor) (Hājji Dabīr, Z. W. 225, l. 5 f f.). Elsewhere, the Hazzı states that the mother-in-law of Bhupat, the son of Silhadi, was the mother of Vikramajit, the son of Rana Sanga, t.e. Bhupat had married a daughter of Rana Sanga (Ib 227, 1 2) The T A also avers that the daughter-in-law [مروس] of Durgavati, the wife of Sılhadı, was the daughter of Sanga (506, 1. 2) The Mirāt-i-Sikandari also says that the wife of Silhadi's son Bhupat was the Rana's daughter (256, 1 10), while F speaks of Durgavati herself as the daughter of Sanga-(II.221, l 2 f.f.) We can scarcely expect the Musalman annalists to have been accurately informed about the family history and matrimonial connections of the Rapput princes, but it stands out clearly, notwithstanding some discrepancies, that Silhadi or his son was connected by marriage with the reigning house of Chitor It is quite possible that both Silhadi and his son had taken wives from that house. The practice is not at all unusual among Rajputs, though Sir E Clive Bayley was puzzled by it on account of imperfect acquaintance with Hindu customs (Loc. Cit 365 Note) But as a Gehlot can never marry a female of his own tribe, Silhādi must have belonged to some other sept

In this connection, it may be worth while to note that 'Purabiya' is said by Tod to have been one of the 24 branches of the Chauhans. (op. cit) In the Sanskrit poetical history of the Rajas of Rewa which has been

summarised by Dr. Hirānand Shāstri, Puraumal is described as a descendant of Hammīra, the Chauhān. (Memoirs of the Arch. Survey of India, No. XXI, (1925), p. 6). If this is correct, Silhādi also must have been a Chauhān. But the better opinion seems to be that 'Purabiya' means nothing more than 'Eastern' and all Rājputs were called 'Purabiya' in Mālwā, because they came from Purab—the Ganges-Jumna Duāb and Oude—because these districts were situated to the east of that province. Hājji Dabīr states that Medini Rāi was the title given to Rāi Chand Purabiya (213, l. 9), and he mentions several other Rājputs also who are styled 'Purabiya', c. g. Gangu Purabiya, Lord of Maudasā, (226, l. 9), Hemkaran Purabiya, (107, l. 1), and others. The T. A. also speaks of Rājputān-i-purabiya, as a general term, (584, l. 5) and appends the epithet 'Purabiya' to the name not only of Silhādi himself (587, last line), but to that of a man called Shādi Khān (586, l. 4).

In these circumstances, the balance of authority points to Silhādi having been neither a Gehlot nor a Chauhān, and Tod is probably right in making him a Tuār or Tonwar. This conclusion is borne out by the Emperor Jahāngīr, who in a detailed notice of one of his Amīrs, named Nāhar Khān, declares that he was the grandson of Narsinha Deva, the brother of Puran Mal Tonwar if of Rāisīn. (T. J. 365, l. 21). The 'Aligarh text has 'Lūlū' and some Mss. have if or J., but these are all mistranscriptions of 'correct or correct or significant of the same of the correct of the correct

IV. 398, l. 3. Fath Khan Jat had been in rebellion in Kayala.

Recte Qabūla, i.e. 'Kot Kabūla', as in Dorn. (I. 134). It is mentioned in the T. J. also. (77, l. 6; Tr. I. 160). It was in Sarkār Depālpur of the Lāhore Ṣūba. (Āīn, Tr. II. 332). It lies about seven miles north of the Sutlej in Montgomery district, Punjab. Lat. 30°-11′ N., Long. 73°-36′ E. Satgarha (l. 11) also is in Montgomery district and lies "about thirteen miles east of Gugera on one of the projecting points of the high bank, which marks the limit of the windings of the Rāvi on the east." (Cunningham, A. G. I. 242). The name is said to mean 'seven castles', but none of them now exist. Lat. 31°-0′ N., Long. 73°-0′. Constable, Pl. 24 E b. The mausoleum of Mīr Chākar Rind is at Satgarha.

IV. 398, l. 13. I am going to seize Mahla.

'Mahla' is not the name of any place which it was intended to capture. What Haibat Khān wanted to do was to take the Mahal (the dāgh wa mahal) of the contingent which Chākar [Chaqar or Jaghar] Rind was bound to maintain. Chākar was therefore asked to "keep his forces ready", so that the horses could be branded on the spot according to regulations. Four lines lower down on this very page, Haibat Khān is made to say, "I shall take your Muster (Mahal) at Depālpur". De Tassy renders it correctly thus: "qu'il prepare donc son armee et j'en passerai in revue". (p. 125). B. uses the phrase dāgh-u-mahalli. (II. 206, Lowe, Tr. 209=E. D. V, 522).

IV 398, 1 5 from foot Fath Khan Jat sent Shailh Ibrahim, son of Kuth Alam, Shailh Farid to Haibut Khan

The Qutb-1-'Alam Shakh Farid-[1-Shakargan] who has buried at Ajodhan of Pāk-Pattan died, according to Musalman hagiologists, either in 664 or 668 A. II., to in the 13th century A. C. (Beale, Mistāh, 63, Aīn, Tr. III. 364), and it is impossible for a person living in the 16th to have been either his son or his 'nephew', as Dorn has it (I. 135). The word is here used loosely for 'descendant', (q. v. 371 Note 2 ante). Prof. Qīnūngo has been misled by Dowson's wrong translation. (op. cit. 310). IV. 399, 1.9 from foot Fath Jang Khān. In the country of Multān founded a city which he called 'Shergarh'

This Shorgarh is still in existence and lies" on the right bank of the Biyāh, about twenty miles to the south-east of Satghara" (Raveity, Mihrān, 360 note) Coustable, 24 E b Prof Qānûngo conjectures that it must be either 'Sher Shāh,' about 8 miles south-west of Multān or 'Shāhgarh', 27 miles in the same direction (313 note), but Raverty's suggestion hits the mark much better in every respect. This Shergarh is mentioned also by B (II. Text, 155-6, Tr. 159, 160), as near Jahni or Channi (Chuniān) and it contains the Mausoleum of Shaikh Dāūd Channiwāl

IV. 403, footnote The Shaikhzādas of Barnawa .and the Shaikhzādas of Bhandner [complained to Shīr Shāh]

There was a Mahāl named Barnāwa in Sarhār Dehli, Sūba Dehli, (Āīn, Tr II 286) Barnāwa lies about sinteen miles north-west of Mīrat on the right bank of the Hindau (Th) It is supposed to be the Vāranāvata, to which the Pāndavas retired on their expulsion, and where Duryodhana attempted to burn them to death Lat 29°-7′ N, Long 77°-29′ E This 'Bhandner' may be an error for 'Pundir' (ريادي) oi 'Pundri', which was also in the same Saikār Pundri is shown in Constable, 25 B c It is a place of some antiquity It is most probably identical with the 'Banadri' of Wassāf See Note on III 36, 1 15 ante

IV 406, footnote

Shortly after the beginning of 951 H., he [Shin Shāh] must have started for Chitor, marching during the hot weather, passing the rains in Kachwara, and then occupying the closing months of 952 and the beginning of 953 with the siege of Kālinjar This makes the chronology very plain

It is permissible to point out that instead of making the chronology plain, this would make it inconceivably confused and utterly impossible, as Shir Shah died on the 10th or 11th of Rab'i I. 952 H. There is some inadvertence or typographical error here and the years should be read as 950, 951, and 952 respectively A. H. 950 began on 6th April 1543 Rāisin was sacked during the first half of 950 H and the campaignin Rāiputāna followed in the second half, November-March 1544 A. C. The attack on Chitor came three or four months later Kālinjar was besieged in or about Sh'abān 951 H. (November 1544) and Shīr Shāh died on 22nd or 23rd May

1545. At p. 304 ante, Elliot himself puts the expeditions against Rāisin, Ajmīr, Nāgor and Māldeo into 950 H., and the capture of Chītor and the commencement of the siege of Kālinjar into 951 H. See also the note at 404 ante. B. distinctly states that the siege of Rāisin began in 949 H. and he gives also the contemporary chronogram as قيام ياد كام باشد مبارك which stands for 949. He adds that the fort was surrendered in the following year. (I. 376, Tr. 476).

IV. 407, l. 16. When he reached the stage of Shahbandi.

M. Garcin de Tassy reads 'Sahpada'. (op. cit. 136). I suggest that it may be 'Shahandah, or 'Sahanda, i. e. Sehonda. It lies about 30 miles north-west of Kālinjar in the line of Sher Shāh's route from Kajwāra or Khīchīwāra. Like Kālinjar, it is now in Bānda district and is situated on the river Ken. It was near the lake of Sehonda, which is said in the Bādishāhnāma to be about twenty Kos from Kālinjar, that Khān Jahān Lody was defeated and killed. (Text, I. Pt. i. 349 = E. D. VII, 21). Constable, 28 B c.

IV. 407, foot note. Ahmad Yādgār says that the reason for his advancing against Kālinjar was that Birsingdeo Bundelah.....had taken refuge with the Rājā of Kālinjar, who refused to give him up.

Ahmad Yadgar is a careless and muddleheaded scribe. This 'Birsingdeo' was not a Bundela, but a Baghela. He was not the Raja of Panna in Bundelkand but of Bhata or Bhatghora (modern Rewa). He was contemporary with Babur and his name occurs more than once in that Emperor's Memoirs. (B. N. Tr. 521, 562, 639). Birsing [Vira Sinha] was succeeded by "Perbehan" or "Birbahan" (Vīrabhanu), who is stated by Jauhar and Gulbadan (H.N. Tr. 136) to have rendered material assistance to Humavun in his flight after the defeat at Chausa. Apart from this error, Ahmad seems to have confounded the father with the son. It is not unlikely that Birbhan [not Birsing] was summoned to court by Shir Shah to answer for his conduct and that the Baghela thought it the better part of valour to seek safety in flight. The Rājā of Kālinjar, with whom he took refuge, is called Kirat Sing by 'Abbas (407 infra) but Bhartichand, in the genealogy of the Rajas of Orchha and the local chronicles. (Silberrad, History of Western Bundelkhand, J. A. S. B. LXXI, 1902, p. 107). Birsingdeva is mentioned in the A. N. also (II. 210; Tr. II. 325). Abul Fazl says that Birsing was a vassal of Sikandar Lodi. Birsing, in fact, was the son of Shālivāhan, the brother and successor of Bhīdachandra, both of whom are mentioned at 461-2 infra and Nī'amatulla in E. D. V. 94-5.

IV. 409, l. 16. On the 10th Rab'iu-l-awwal 952 A.H., Shir Shah died.

Abul Fazl gives 11th Rab'i I (A. N. I. 336; Tr. I. 615). F. has 12th (I. 228). Ni'amatūlla says he died at midnight on Tuesday following the 9th, which was a Friday, i.e. the 12th or 13t'ı. (Dorn, I. 141). The Makhzan-i-Afghāni makes it the 17th. (Dorn, II, 111). Abul Fazl says that Islām Shāb ascended the throne eight days after the death of his father, i. e.

19th, but according to Ni'amatulla he did so on Thursday the 15th. (Dorn, I. 146). B. does not give the exact date of Shīr Shāh's death, but says Islām Shāh ascended the throne on the 15th of Rab'ī I. (I. 374=Tr.I 485) 'Abbās also makes 9th Rab'ī I a Friday. 10th Rab'ı I (Hisābī) 952 H. was Friday, 22nd May 1545. If Dorn is right in saying that he died on the night of the Muhammadan Tuesday, the Hisābī date must have been the 13th Rab'ī I.=25th May 1545 A. C. The dates given by Abul Fazl and F. must be Ruyyat dates Erskine says he died on the 24th of May 1545. (H B. H. II. 441 and note). See also Mr. Beveridge's Note at A. N. Tr. I 400. The Hijri date was most probably the 11th Ruyyat or 12th Hisābī. IV 415, l. 13. The Nagarhot, Jicāla, Dihdawāl and Jammū hills

'Jwāla' is Jwālāmukhi There is a Dhudiāl in Jhelum district in the Punjāb, Constable 24 E a, but there is another place bearing the same name in Hazāra district, about twenty-five miles from Abbottābād (*Ibid*, 24 D a). The first of these is most probably meant here, as the headquarters of the governor are said to have been at Malot, probably the place so called in the Hoshiārpur district Dudhiāl in Jhelum district is now a station on the Mundra-Bhaun Railway It is 28 miles south-west of Mundra, which is 52 miles north-west of Jhelum town.

IV. 416, 1. 9. The contumacious and highway plunderers inhabiting the pargana of Malkonsa

Malkonsa was a Mahāl in Sarkār Qanauj, Sūbā Āgra, (Āīn, Tr. II. 185), and is now called Rasūlābād (Elliot, Races II, 91). The district has been always notorious for the lawless and turbulent character of its inhabitants. Every man is said to have gone about armed and even peasants tilling the fields had loaded muskets fixed to their ploughs and never paid the land revenue or any other dues until compelled to do so by force majeure. (Maāsiru-l-Umarā, I 418) Rasūlābād is a not uncommon placename There is a Rasulābād which lies a little south of Asiwan in Mohan tahsīl, Unāo district, twenty miles north of Unāo town. (I. G. VI. 13). Constable, 28 B b But this Malkousa is 'Malgosa'—Rasūlābād, about forty miles north-west of Cawnpore and nine miles north of Jhinjhak station on the East India Railway. (N W P. Gazetteer (1881), VI. 253-4) The pargana contains a large area of swampy land. A saying commemorating the difficulty of realising the revenues in former times is quoted by the compiler of the Gazetteer

Rasūlābād-Malgosā, tin pahar jūti to ek pahar paisā, Rāt basen phir jaesā kā taisā. (Ibid, p. 8).

IV. 419, foot note. It cost eight knors, five lacs, five thousand and two and a half dams, which means Bahlolis. All which is written over the gate of the fort

The Emperor Jahangir who stayed at Rhotas for some days in his father's reign (T A in E D V 465) and visited it also in his own, states that according to an inscription on one of the gates of the fort, "the cost of erection was sixteen Krors, ten lacs of dams and a little more, equal to

forty lacs, twenty-five thousand rupees. (T. J. Tr. I. 96; Text, 46, last line). It will be observed that the figure, as it is given by Jahāngīr, is just double that given by the $T\bar{a}r\bar{\iota}kh$ -i- $D\bar{a}\bar{u}di$. Jahāngīr calls the coin $D\bar{a}m$ and reckons it at 1/40th of the rupee. 'Abdulla also speaks of it as $D\bar{a}m$, but his total is the exact moiety of Jahāngīr's. He adds that this $D\bar{a}m$ was the same as the Bahloli. His $D\bar{a}m$ or Bahloli must have been equal to $1/40 \times 2$, i.e. 1/20th part of the Rupee. In other words, it bore the same value as the $Sikandari\ Tanga$, of which twenty were accounted as equal in value to the Rupee. This shows that the word 'Dām,' is used very loosely and that two different coins, one, of which 40 went to the Rupee and another, of which 20 bore the same value, are both indiscriminately designated 'Dāms'. And this confusion is aggravated by the fact that the terms 'Bahloli' and 'Tanga' also seem to have been employed with equal laxity, not only in common parlance or the language of the street, but in the histories and chronicles of the period.

IV. 433, l. 5. And in the time of Sher Shāh, a decrepit old woman might place a basket of gold ornaments on the head and go on a journey and no thief or robber could come near her.

This is not historical verity but fatuous adulation. Unfortunately, it is repeated in the Zubdatu-t-Tawārīkh of Shaikh Nūru-l-Haqq (E. D. VI. 188-9), the T. A. (232, last line), F. (I. 228, l. 3 f. f.) and B. (I. 363; Tr. 473), as if it had been a real fact. Any decrepit old woman who had tried the experiment would have had good reason to rue it all her life, if her head had remained on her shoulders at all. The whole passage is rhetorical bombast of no historical significance. It is, at best, only a picturesque metaphorical expression, just like "the lion lying down with the lamb" or "the wolf drinking at the same fountain as the goat." And this flimsy fustian has not even the merit of originality. It has been pilfered from an older author and the very words, almost, occur in the Shajrat-u-l-Atrāk, the author of which writes thus:

"It is related in different histories that when Sultan Muhammad Khwarizm Shah conquered Mawarau-n-Nahr, the roads between Iran and Turan were well-guarded and safe, in so much, it is stated as an example, that if an old woman were to carry a dish full of gold all over the country, there was none hardy enough to molest her". (Tr. Miles, p. 110).

It may be pertinent to note that the *Shajrat* is an abridgment of the الربه الوس جنگزی, which was based on a History of the Mongols written by or under the orders of Sultan Ulugh Beg about 851 A. H. (Rieu, B. M. Catalogue, I. 164; Ethé, I. O. Catalogue, 77-8).

Similarly, all that is said a few lines higher up about travellers and wayfarers having been relieved from the trouble of keeping watch and about the Zamindārs keeping guard over them is 'stolen thunder'. It is just what Barani says about 'Alāu-d-dīn Khalji. (T. F. Text, 340, 11. 12-18).

"The safety of the highways, throughout the provinces," that historian states, "had become so great that the Hindu landed proprietors and headmen [Muqaddimān wa Khūtān] used to stand on the highroads and keep watch over wayfarers and caravans, while travellers with goods, fabrics, cash or any other property used to alight in the midst of the plains and deserts". (Major Fuller's translation in J. A. S. B. 1870, p. 48). And writing of Ghiyas-u-din Tughlaq, he declares that "so great was the fear of his sword in the hearts of all robbers and plunderers, that in his time, the robbers became the protectors of the public road and the name of robber was not heard, and the fear of the robber was wined from the minds of men." (Text, 442-3; [Sir Auckland] Colvin's Tr in J. A. S B 1871, p 238) When 'Abbas further assures us that in the reign of Shir Shah, there was not "a thief or robber who dared to direct the eye of dishonesty to the property of another, nor did any theft or robbery ever occur in his dominions" he is only repeating what had been said before. The fact is that this overpraised account of Shir Shah's administration has been pieced together out of borrowed material. For its most important passages, viz. those relating to the manner of his daily life and his system of civil and military government. 'Abbas must be indebted to Mushtagi, as that author died in 989 H. (534 infra), several years before the Tārīkh-i-Shīr Shāhi was begun.

It seems necessary to put this point in the proper light and nail the lie to the counter, as it is thus represented even in the CH.I. (IV 57) "Even the historians of the Timurids admit that in the Afghān's reign, an old woman with a basket of gold could safely sleep in the open plain at night without a guard", and another modern writer also assures us in an official publication, that "under the rule of Shīr Shāh, all disorders ceased and so complete was the order that prevailed throughout Hindustān, that a decrepit old woman might place a basket of gold on her head and go on a journey ete" (U P. Gazetteer, X. p 157)

IV. 435, l 11 from foot He summoned two competitors for the crown, Kiyām Khān and Malik Bahlol

No individual named Qiyām Khān is mentioned as a competitor for the throne of Delhi by any of the other historians and the must be a copyist's error, perhaps, for the Hisām or Husām (q v. E D V. 73) The T A and F agree in saying that the two other persons, besides Buhlūl, of whom Hamīd Khān thought were Sultān Mahmūd of Jaunpur and Sultān Mahmūd Khalji of Mālwa The first was ruled out because he was Sultān 'Alāu-d-dīn's son-in-law, the second on account of his being at too great'a distance from Dehli (T A 151, I 6, F I 172, I 6 f f)

IV. 437, l 12 It was the custom to distribute every thind day, Sherbet, pan leaves, etc

The author is referring to the Ziārat or funeral ceremony performed on the third day after a man's death See ante 322, 1 8 f f Herklots speaks of it as "the teeja alias Zeeārut of the dead, or the visiting the grave on the third day after burial." (Qanoon-e-Islam, Madras Reprint, 1863, p. 284). Barani in his elaborate eulogy of Balban's virtues says that he used to visit in person the houses of deceased Shaikhs and Sayyids on the day of the Ziārāt or third day (--e) after death. (Text. 47, l.). IV. 437, l. 10 from foot. Mullā Fāzin one of the elders of the city.

The correct reading seems to be 'Qāzan' or 'Qādan' (¿¿š). He is probably identical with the 'Miān Kādan' mentioned on p. 464 infra. This latter is spoken of as Miyān Qādan, the son of Shaikh Jūfū or Khujū in the T. A. (164, l. 4) and F. (I. 182, l. 26). A Qāzi Qāzan or Qādan (¿¸¸¸¸¸) of Bhakkar is mentioned in M'aṣūm's History of Sind. (Tr. Malet, 130=Kalīch Beg's Tr. in his History of Sind, II. 65, 68, 69. See also E. D. I. 310 note and T. A. 636, l. 20). Qāzi Qādan Bangāli was the spiritual guide of Ḥājji Ḥamīd Gwāliari, who was the Pīr or spiritual director of the renowned Shaikh Muḥammad Ghauṣ. (Maāṣiru-l-Umarā, II. 577, l. 6). The 'Miān Kādan of Dehli' mentioned at 464 infra is described there as one of the most eminent Mullās of the empire in the reign of Sikandar Lody. IV. 439, l. 16. It is also related of this prince, etc.

Several stories illustrative of the judicial sagacity and Solomon-like wisdom of Sikandar Lody are repeated by the chroniclers. One of them at least, a long and circumstantial yarn which is related in the T. A. (p. 172), F. (I.187) and the Makhzan-i-Afghāni (Dorn, I. 68) is really an old apologue borrowed from the inexhaustible store of Hindu folklore. It occurs in 'The Mongolian Tales of Ardshi Bordshi' which is said to be the Tibetan paraphrase of the Sinhāsan Dvintrashati, or 'Thirty-two Tales of a Throne'. It is told there thus: " A merchant entrusted a friend with a jewel to give to his wife, but the man sold it and afterwards declared that he had duly delivered it. When the merchant brought his case to trial, the false friend produced two witnesses who asserted that they had seen the merchant giving the jewel to the merchant's wife, and judgment would at once have been given in his favour, but for the interposition of a boy who advised that all four should be confined in separate rooms and each to be given a piece of clay, out of which they were to make models of the jewel. As the models of the merchant and his false friend were found to correspond, while those of the two witnesses differed, the fraud and periury were both detected". (Clouston, Popular Tales and Fictions, IL

other way. They are much older than the time of Sikandar and most of them are migratory sagas which illustrate the "tendency of all peoples to ascribe well-known anecdotes, sayings and adventures to well-known persons," as E. G. Browne puts it. (L. H. P. II 189).

IV. 447, 1. 16.

IV. 444, l. 6 from foot. On Friday, the 7th Sh'aban, A. H 894, he (Sihandar) was raised to the throne.

The date must be wrong, as the Julian correspondence, 6th July 1489 A. C. was a Monday The T. A (159, 1 13) gives it correctly as 17th Sh'aban, 17th July, which was a Friday and must be correct.

IV. 444, l 12 On the day he quitted Dehli, he first went to Shaikh Samāu-d-dīn . for the purpose of requesting him to repeat the fātiha

Budāuni tells a similar story of a poet who wrote a Qasīda in praise of Sultān Iltutmish, but first went to the celebrated Saint Qutbu-d-dīn Bakhtyār-i-Kāki and requested him to give his blessing by repeating a Fātiha before its presentation to that ruler. He then attended at Court and read it to the Sultān, who was so pleased with it that he gave him a reward of 53,000 white tangas—at the rate of 1,000 tangas for each couplet. (I. 65=Tr I 92) Another example of this custom is found in the Muntakhabu-l-Lubāb of Khwāfi Khān, who informs us that before marching against Dārā Shukoh, Aurangzeb went in disguise to a famous saint of Burhānpur and requested him to repeat a Fātīha, just as Sikandar is said by Abdulla to have done (Text, II. p. 11)

IV. 447, l 16. Their stone images were given to the butchers to make weights to serve them as meat-weights

This is a "wandering tale" of iconoclastic zeal which appears in varying forms 'Abdulla tells it here of Sikandar Lodi and associates it with the temples of Mathura According to the Wag'rat-i-Mushtage, the hero was Khawass Khan and the images belonged to the shrine of Mahāmāyā [Vajreshvarı or Ambikā] at Nagarkot and not to Mathurā (544 post) F had read in some book that the idol of Nagarkot was broken to pieces, mixed with cow's flesh and put into nosebags, which' were hung round the necks of the Brahmans But this had occurred, not in the reign of Sikandar Lodi, but in that of Firuz Tughlaq. (I 148, 1 6) F's story looks like a variant of a still older legend about Mahmud of Ghazna He is said to have had the stone images of Hindu deities burnt and turned into lime which was given to the Brahmans to eat with their betel leaves They were then told that they had their gods in their bellies! (Raverty, N. A 60, L. G. s n Butkhak) Still another variant of 'Abdulla's tale appears in the provincial histories of Mälwa. There, the idol-breaker is the Prince Ghiyasu-d-din, son of Sultan Mahmud Khalji. He is stated to have destroyed in one of his campaigns against the Rana of Chitor, the temples of Kombhalmer and converted the objects of worship into butchers' weights. (T A. 551). F repeats this yarn also (II. 247), having copied it, as usual, from Nizāmu-d-dīn. The story of the

practical joke played by Maḥmūd upon the Brāhmans has the appearance of an etymological myth. It seems to have been invented to account for the toponym Butkhāk, the name of a village near Kābul, where the incident is said to have taken place. But means 'idol' and Khāk' 'dust' in Persian. Aḥmad Yādgār also refers to the capture of Nagarkot in Sikandar's reign, but merely says that the idol was exposed to be trodden under the feet of the people. (E. D. V. 18).

IV. 449, l. 16. [The musicians] were ordered to play only these four tunes, (1) Malikur, (2) Kalyān, (3) Kānra and (4) Husaini.

The correct name of the first $R\bar{a}g$ is 'Mālkos'. In Persian Music there are, according to the *Ghiyaṣu-l-Lughāt*, twelve $Maq\bar{a}m$ (tunes or modes) of which 'Husaini' is the tenth. 'Kaldāra' and 'Hasani' which are mentioned as variants in the footnote seem to be mistranscriptions of July' 'Kedār' and 'Husaini'.

IV. 450, l. 12 from foot. The noble who had the general direction of affairs in the reign of Sikandar bestowed districts................to an extent that had never been known before.

The original words حضرت نخار مطلق مندرى remind one of the who was a minister higher even than the Chief Wazīr. The Wakīl-i-Mutlaq was the Viceregent, the deputy of the Sovereign himself and all the powers of the Sultān were, for the time, delegated to him. He was often appointed when the king was young and inexperienced or had to be unavoidably absent from the capital on protracted or distant military enterprises. The reference here is probably to Shaikh Bhuwa, who was Sikandar's prime minister and alter ego. Aḥmad Yādgar states that Miān Bhuwa was the most powerful and independent grandee and the absolute minister of Sultān Sikandar. (E. D. V. 13-4). Khwāfi Khān observes that in former reigns, the appointment and removal of Wazīrs and other ministers used to be vested in the Wakīl-i-Mutlaq. (Text, II. 597—Tr. in E. D. VII. 401-2).

IV. 451, l. 1. The Argar-mahā-bedak, was translated ... and received the name of Tibb-i Sikandari.

An alternative title of the Tibb-i Sikandari is M'adanu-sh-Shifai Sikandari and there are copies of the book in the British Museum and other Libraries. (Rieu, II. 471; III. 1120; Ethé, I. O. Catalogue No. 2305, Sachau and Ethé, Bodleian Catalogue, No. 1592; Stewart, Catalogue of Tippoo Sultān's Library, p. 108). The work has been also lithographed at Lakhnau. The author calls himself Bhuwa, the son of Khawwāss Khān, and says that the translation was completed in 918 A.H. (1512 A.C.). It is made up of an Introduction in praise of the Science of Medicine and three Bābs or Chapters, the names of the subjects of which are given in Sanskrit as Sutrasthān-Shārirak-Chikitsāsthān and Nidān. Argan-mahā-bedak may be a corrupt form of [9:1] Ayūr Mahā Vaidak,

Baidak [Vaidak] Miān Bhuwa states that it had been compiled from several Sanskrit works "which were the foundations of the physicians of Hind" and specially mentions those of Charaka, Sushruta, Sārangdhara and Chakradatta and the Mādhava Nidāna.

IV. 454, l. 20 A saiyyid from the district of Ardal, which is twenty or thirty Kos from Fanna on the Agra side.

The names 'Ardal' and 'Panna' are both wrong The first must be intended for Arwal in Gaya district, which lies on the Sone about 44 miles south-west of Patna. (Seeley, Road Book of India, 15-16) Constable, 28 D c The wāv has been wrongly read as a ze Arwal was in Bihār which we know to have been annexed by Sikandar The second name must be Patna.

IV 457, l. 4 Led by a Hindu named Juga.

IV. 457, l 9 Bārbak Shāh had gone to Daryābād

This Daryābād is probably the place of that name in Rāmsnehighāt tahsīl of Bārābanki district in Oude, U P Lat 26°-53′ N, Long 81°-34′ E (I G XI, 191). Miyān Muhammad Farmuli to whom Bārbak Shāh is said to have fled was the son of the sister of Buhlūl, who had given him the whole Sarkār of Oude (to which Daryābād belonged) in Jāgīr. (Tārīkh-ī-Shīr-shāhi, 352 ante)

IV. 457, l 15. Food is just ready, eat a little of it as a good omen, and then set out for Jaunpur

Another instance of this Oriental belief or superstition is found in the Memoirs of Jahāngīr. During the pursuit of his mutinous son Khusrau, the news of the two armies having come within sight of each other was brought to him, just when "a dish of roast meat was placed before him" But he tells us that he was so anxious to join his troops, that "he took only a mouthful by way of good omen (and started off at once for the scene of the battle" (T J Text, 29, Tr I. 63) This article of popular faith is not infrequently referred to in Hindu folklore also In a rare Collection of Indian Tales published by C. Vernieux at Calcutta in 1872), there is the story a prince who resolves to abdicate the throne and leave his country, but before doing so, receives

from a Fakir four maxims, the second of which is, "Never forsake ready food." The prince takes care to act upon these maxims and each of them saves him from certain death on a critical occasion. (The Hermit of Motee Jhurna and other Indian Tales, apud Clouston. op. cit. II. 450).

IV. 461, l. 16. The fugitive Rājā, by name Bhed, went to hell.

It is now possible to definitely restore the name of this Rājā. He was Bhīdachandra, Rājā of Bhaṭa or Bhaṭghorā. A Sanskrit Mahākāvya or Poetical History of the rulers of Rewā written about the middle of the 16th century A. C. has been summarized by Dr. Hirānand Shāstri in Memoir No. XXI of the Archaeological Survey of India (1925). See also the supplementary article in Journal, Bihār and Orissa Research Society, 1930. He is called 'Bhil Rājā of Phaphamau' in the C. H. I. (III. 237), but Bhīl is an impossible name for a Hindu King. He was not the Rājā of Phāphāmau, which is an insignificant village, near Allahābād, but of Bāndhū. Sālbhān (Shālivāhan), who is mentioned a few lines lower down, was his brother.

IV. 461, footnote. Alimad Yādgār adds, 'In short, from Jalālābād near Kābul, to Mandū and from Udīpūr to Patnā, coin was struck in his [Sikandar's] name.'

Ahmad Yādgār is a careless and very untrustworthy compiler of a later date and this statement is flatly belied by well-known facts. Neither 'Jalālābād' nor 'Udīpūr' existed in the days of Sikāndar Lodi. Jalālābād was given that name by Mun'im Khān in honour of Jalālu-d-dīn Akbar and Udipūr was founded by Rāṇā Udi (Udaya) Sinha, the son of Sanga, about the middle of the sixteenth century (1559 A. C.). (I. G. XXIV. 102).

IV. 462, l. 6. Sultān Husain had gone to Kahlgānw, in the country of Lakhnauti.

This is 'Colgong' now in Bhāgalpūr, Bengāl. Lat. 25°-13′ N., Long. 37°-17′ E., about 23 miles east of Bhāgalpūr town. Sultān Husain is said to have died there. Constable, Pl. 29, B. C.

IV. 464, l. 16. There came a Brahman by name Laudhan, who dwelt in the village of Kaner.

Appendix T. pp. lxxiii-vi. The place from which the Brāhman came is difficult to identify It may be 'Kāther' [Rohilkhand] The man himself was, probably, a follower of Rīmānand, one of whose twelve 'Chelas' was named 'Bhavānand' or 'Bhāvānand'. (H. H. Wilson, Religious Seets of the Hindas, in Works, Ed. Rost, I. 53-6, [Sir George] Grierson, J. R. A. S. 1909, p 642 Note)

IV. 467, footnote l 13 [Sikandar] sent Rai Ugar Sen Kachhwaha.

The name is so spelt in Briggs' translation of Firishta, but the lithographed texts of the T. A. (169, l. 5) and F. (I. 185, l. 5) call him 'Jagar Sen Kachhwah ' and they are followed in the C. H. I. (III 245) But ' Ugra Sen' seems to be correct and the person meant may be the Ugra Sen Khīchī of Rājput tradition, who is said to have been obliged by domestic strife to abandon Gagraun and found Khichipur (wrongly called Khiljipūr). (I. G. XV 279) 'Kachhwah' is, most probably, wrong Persian writers constantly confound "Kachhwah" and "Khichi" "Kachhwara" on p 407 ante is a misreading of 'Khichiwara'. The 'Khichis' are a branch of the Chauhans and are entirely distinct from the Kachhwahs. (Crooke, Tribes and Castes, III 278) This Ugra Sen Khichi is most probably identical with the Ugra Sen Purabiya of the Gujarat Chronicles. (Mirati-Sikandari, Tr Bayley, 256 and 272 note, Hajji Dabir, Z W 105, l. 1, 113, 1 3 f f, T. A 489, 1. 20 f f and F II. 210, 1. 7). Khīchīwara or the country of the Khichis comprises most of the country between Guna, Sārangpur, Shujāwalpur and Bhilsā (I. G XXI. 34).

IV. 471, l. 12 His [Sikandar Lody's] death took place on Sunday, the 7th of Zil-K'ada, 923 H

The TA' (170, 1.6) and F (I 186, 19) give the same date B. has 17th, but the same week-day. The Julian equivalent is given as 21st November 1517 A. C in the C H I (III 246), but calculation shows that the 21st of November was a Saturday. If the week-day is correct, Sikandar must have died on 22nd November, which was 7th Ruyyat, but 8th Hisābi It may be noted as a curious illustration of the state of society and communications, that the news of the demise of Sikandar at Agra reached Sultān Muzaffar II of Gujarāt in his camp on the Mālwa frontier on 9th Zī-l-hijja (Mirāt-i-Sikandari, Text, 158 last line, Fazlulla's Tr 98, Tr. Bayley, 255) 17th Zī-l-q'ada which is given by B. is most probably incorrect, as it was a Tuesday or Wednesday The length of his reign is here stated as 23 years and 5 months by 'Abdulla, but if Sikandar came to the throne, as he himself avers, on 7th Sh'abān 894 H. (444 ante), it must have been 29 (lunar) years and 3 months.

IV. 47.1, footnote 2 The Tārikh-e-Khān Jahān Lody informs us (Ms p 124) that the coffin was removed to Dehli and deposited there together with that of his father

The tombs of Sikandar and Buhlul are mentioned by Abul Fazl in his description of Dehli. (Ain, Tr II. 280 See also Asāru-s-Şanādīd, Pt 1.89 and 20; Plates 85 and 11) "Sikandar's tomb is about a mile

from Safdar Jang's Mausoleum, close to an ancient bridge which stood on the road leading from Firuzabad to one or other of the towns stretching from Sīri to Lalkot". (J. A. S. B. XXXIX, 1870, p. 84; Fanshawe, D. P. P. 244). Buhlūl's remains are popularly supposed to lie near the shrine of Shaikh Nasīru-d-dīn Mahmūd, Chirāgh-i-Dehli. But this is a low, mean-looking structure and modern archaeologists are not sure that the traditional ascription is worthy of credit. (Fanshawe, loc. cit. 288; Sir J. Marshall in C. H. I. III. 594). In this connection, it may be permissible to note that Sir H. Elliot speaks elsewhere of the author of the Tārīkh-i-Dāūdi having left it on record that Buhlūl was buried in the Bāgh-i-Jūd. (See E. D. V. 91 note). Unfortunately, the exact site of the Bagh-i-Jud is not known, although it is frequently mentioned in the chronicles of Minhäi and Barani. The Tarikh-i-Khan Jahan Lodi may be right in averring that the body of Sikandar was first deposited in his garden, [اغم خود] which Islām Shāh afterwards enclosed and this garden may have really been in the Bāgh-i-Jūd [الغرجود]. The statement is found also in Dr. Lee's copy of the Makhzan-i-Afghāni, (Dorn, II. 99). But the father and son do not now lie in the same spot and this fact may reinforce the doubts regarding the building in which popular tradition locates the grave of Buhlul. Perhaps the body was only deposited temporarily in the Jud Garden and afterwards interred elsewhere. I have thought it worth while to draw attention to these statements in the chronicles, as they do not appear to have attracted the attention of any writer on the Archaeology of Dehli.

IV. 476, l. 10. Ten Mans of corn could be purchased for one bahloli; five sīrs of clarified butter and ten yards of cloth could be purchased for the same coin.

As the Buhlūli was a copper or billon fulūs worth, at the most, the twentieth part of the silver tanga, this and several other statements of the same sort in this paragraph stand in need of being taken with some grains of salt. Most of the anecdotes illustrating the profuse expenditure and largesses of the nobles of Sikandar Lody's reign are pitched in a very high key of silly and incredible exaggeration. A few lines lower down in this very paragraph, this author tells us that gold and silver were only procurable with the greatest difficulty in Ibrāhīm's reign. But if this was so, it is hard to understand how the Amīrs of Ibrāhīm's father were able to squander gold mohurs by the handful and even by the plateful, to give away jewels whose value is estimated only in hundreds of thousands of tangas and to dissipate five hundred tangas daily in roses for their harems. (471-5 supra).

The partiality of 'Abdulla for the fabulous verges, not infrequently, on the absurd. For instance, he informs us that when Shīr Shāh was engaged in besieging Kālinjar, two thousand workmen were daily engaged in casting cannon and four thousand mortars (degs), each capable of discharging a ball weighing four Mans, were cast! (Qānūngo, op. cit. 338).

The fabulous cheapness of commodities which this writer ascribes

to a succesion of good seasons and "luxuriant harvests" seems to have been really due to very different causes,-to the depletion of the stock of precious metals and an insufficient supply of the circulating medium Timur had carried off enormous quantities of the treasure which had accumulated during the preceding two centuries of Muslim rule. The old sources of the flow of gold and silver from the seaports of Bengal and Gujarat had been largely cut off by the alienation of those provinces from the Empire of Dehli The normal movements of trade also must have been seriously interrupted by the misgovernment and lawlessness which prevailed under the Sayyids, the 'Thirty Years' War' with Jaunpur, and the revolts and rebellions of the turbulent Afghan aristocracy The slump in the money-value of agricultural produce could have hardly been an unmixed blessing, as it must have affected most disastrously the income of the peasantry as well as the resources of the government whose revenue was paid almost entirely in kind. (Thomas, C P K D 435-6, Moreland, A.S N I, 68)

IV. 477. l. 14 [Shir Shah had to march against] the thieves of Pali and Pāhal, who are of the Gujar tribe

Pāli and Pākal [not Pāhal] are both near Dehli Pāli lies in Gurgãon district at the eastern base of a rocky range about 18 miles south of Dehli (Thornton) Islāmābād-Pākal is registered as a Mahāl in Sai kār Dehli (Ain, Tr. II 285) Pali and Pakal are spoken of as 'an united pargana' by Elliot (Races, II. 129) Pākal is situated at about two miles' distance from Pali (Th.). Gurgãon is in the notoriously turbulent Mewat country and these brigands were the Gujars to whom Babur also gives a very bad character (B N. Tr 454-240 ante, Elliot, Races, I 99)

IV. 480. l. 15 He made privates (fard) officers (girohdar), and officers nobles

Ibn Batūtā says a regularly enrolled soldiei was called a 'Mufrid' (E. D III 601, 603). Baranı also uses the words معرد 'Mufrid' and 'Mufridzādah' (234, 1 3 f f) Cf the later synonyms 'Yakka' and 'Ahdı' both mean 'one, single. عدد See my note on E. D III 155, 1 8 ود and معدد solitary, alone

IV. 480, footnote 1, 1 4 To every fifty soldiers, there was a Turki and Hinduwi writer attached

"Turki" must be a slip for 'Farsi', 'Persian' There would be no sense in keeping regimental accounts in Turki and Islam Shah is not at all likely to have had any special partiality for men of that race Cf ante 413, where 'Abbas says that Shir Shah appointed in every pargana one karkun to write Hindi and another to write Persian F notes in his account of Sikandar Lody a fact which is of some interest in this connection Learning, he says, was in high favour in that reign Amin s and even Sināhis devoted themselves to the belles lettres and the Kāfirs or Hindus learnt to read and write Persian to which they had not paid any attention before. (I. 187, 1 4)

IV. 481, l. 12 and footnote. \bar{I} 'sā Khan Hujjāb.

The fine tomb of this 'Isā Khān is still one of the sights of old Dehli. In an inscription on the grave-stone, he is said to have been the son of Miān Aghwān and to have died in 954 A. H.=1547 A. C. (Āṣār, I. 33, Pl.31; Fanshawe, D. P. P. 234). Malik Firoz Aghwān was an Amīr of Sikandar Lody. (E.D.V. 101). 'Ḥujjāb' is the honorific plural of Hājib and signifies Hājibu-l-Ḥujjāb, 'Ḥājib of Ḥājibs' or Lord Chamberlain. Cf. Nāib and Nawwāb. The sobriquet is added to distinguish him from 'Isā Khān Niāzi, 'Isā Khān Sarwāni and other persons who bore the same name.

IV. 481, l. 9 from foot. Islām Shāh came forth to meet him in the village of Singār pūr.

The reading in the T. A. (233, l. 7 f.f.) is 'Singārpūr', and in Dorn (I. 150) 'Shikārpūr.' F. calls it 'Sikri' and says Islām Shāh was engaged in hunting در شکار اور (I. 229, l. 15). B. has (I. 375; Tr. I. 487) 'Shikārpūr' (with the variants 'Sankāpūr' and 'Sangārpūr') and explains that 'Shikārpūr' was just where the Emperor's [Akbar's] palace (in Fathpur Sikri) is at present. Bābur is said by Shaikh Zain and Abu-l Fazl to have changed the name of Sikri to 'Shukri,' in sign of gratitude for his victory near the place over Rāṇā Sanga, (B. N. Tr. 548 n.; A. N. I. 105—Tr. 260). The true reading may be 'Shukarpur' and the place identicp with or very near Sikri.

IV. 484, l. 9 from foot. A second battle took place at Firūzpūr (Jharka), near Mewāt.

Firūzpūr Jhirka is so called from the Jhirkā, i. e. small perennial stream or "ever-flowing fountain" (Āīn, Tr. II. 193), bordering the road which leads from the town via Tijāra to Rewāri. (Gazetteer of Gurgāon, 249). The town is shown in Constable, Pl. 27 C b.

'Marhākar' which is mentioned in the footnote is 'Madhākar' about ten miles from Āgra on the road from Āgra to Dehli. (Seeley's Road Book of India. Ed. 1825, p. 19). See also *infra* 507, where the distance from Āgra is given as six *Kos*.

IV. 485, l. 2. He [Islām Shāh] ruined first Kuth Khān Sūr, then Barmazīd Sūr, Jalāl Khān Sūr.

The words in the original are in the footnote is that they were "squeezed as poppy-heads for squeezed". The phrase itself is loosely paraphrased as 'ruined', but this interpretation is fanciful and far-fetched. The real meaning is that Islām Shāh fed these nobles forcibly on what was called "yellowsta", the boiled water of poppy-heads or Koknār. It was a slow poison administered to State prisoners with a view to reduce them to a state of physical prostration and mental imbecility. Bernier throws welcome light on the matter. He informs us that when Sulaimān Shikoh was brought as a prisoner before Aurangzeb, he told his uncle that "if it were intended to give him the Poust to drink, he begged he might be immediately put to death." The French physician explains that "the Poust is giran to "" ers.

whose heads the monarch is deterred by prudential reasons from taking off. It is nothing but poppy-heads crushed and allowed to soak for a night in water. . . . It emaciates the wretched victims, who lose their strength and intellect by slow degrees, become torpid and senseless and at length die." (Travels, Ed Constable, 106-107) Bernier's account is borne out by the contemporary Musalman historian, Muhammad Sāhh Kambu, who states that when the two princes Sulaiman Shikoh and Muhammad Sultan were ordered to be confined in the fortress of Gwähor, it was directed that "they should be fed upon Koknār". ('Amali-Sālih, Text, III. 344, 1 16, E D VII, 131). Monserrate observes of Bābā Kapūr, a Majzūb or half-mad mystic of the days of Akbar, that, he and his disciples indulged habitually in this drink, because they believed that it produced that "absence of all feeling and insensibility towards the ills of the flesh, which is indispensable for perfect happiness, and numbed and froze all the impure desires" of the body. (Commentary, Tr Hoyland 24-26. See also Fryer, New Account of India and Persia Ed. Crooke, III. and طرياقي - افيوني - سكي Koknāri' is a word formed on the lines of طرياقي - افيوني - سكي and means an addict or slave of this infusion of poppy-heads. It is used in this sense in the Mirāt-i-Sikandari (Text, 210, 1 3), where a story is told of Sultan Bahādur and a man who was a Koknāri and also a Bangi (Bhangeater), Another man named Mubarāk Koknāri is mentioned in 'Ināyatulla's Continuation of the Akbar Nāma, in connection with the death of Prince Dānyāl. (B I Text, III 838=Tr. III 1255) Bāyazıd Biyat says he had seen a man named Faridun, who "swallowed with impunity enormous quantities of Bhang and drank Koknar like water and yet behaved as if the drugs had had no effect on him". (Memoirs, Trans in J. A S. B Vol. LXVII 1898, p. 314), [Sir Richard] Burton says that "the lives of State prisoners were curtailed in Mughal times by a daily draught of 'Post'. After a few months, the frame became emaciated, the mind torpid and inert and these symptoms did not cease developing themselves till death was the result of the slow poison "(Sind or the Unhappy Valley, I 267-8). IV. 493, last line. He went thence towards Murin.

'Mūrin' ويتن is an error for ويتن 'Mau-Patan'. 'Pathan,' 'Pathān' or 'Pathān' is the 'Pathānkot' of our maps, which is about 100 miles northeast of Lāhor (by rail). It is now in Gurdāspur district, Punjāb. The name has nothing to do with the Trans-Indus Pathāns. 'Pathān' or 'Paithan' is a corruption of Pratishthāna, 'established city.' (I, G, XX. 28 and Note). 'Mau' is in the vicinity of Nūrpur. Lat. 32°-18' N., Long. 75°-57' E. Pathān or Pathānkot lies 14 miles west of Nurpūr in Lat 32°-18' N., Long 75°-42' E. (Th.).

IV. 494, 1 3. Parsurām, the Rajā of Gwaltor became a servant.

This is Gwaler or Goler, a hill State in the Punjab. See note on IV 19 ante Pandit Hiranand Shastri says, on the authority of a Sanskrit chronicle called Dilipranjani, which was written in V. S. 1762, that the real name of the Raja, who was contemporary with Islam Shah and Akbar, was

ŗ

4.1

٠, ز

* '[

\$7 .. `

4

1,2

* N

Rāmchand and not Parasrām. (Journal, Punjab Historical Society, 1912, pp. 140, 146). Mankot (l. 20) is now in ruins and known as Ramkot, It lies about 76 miles north of Amritsar, and 101 N. E. of Lahor. Lat. 32°-37' N., Long. 74°-55' E.

IV. 496, 1. 20. [Islām Shāh] encamped beneath Kaitāli-shahr and designed to pursue the Niāzis into Kashmīr.

I offer the suggestion that this 'Kaitali Shahr' is the Kotli of Constable's Atlas, Pl. 25 A a. It lies about twenty-five miles south-west of Punch and about thirty-five north-west of Naushahra which is mentioned a few lines lower down. Lat. 33°-28' N., Long. 73°-59' E. It lies on the frontier of Kashmir among the mountains south of the province.

IV. 497, 1. 7. [Islām Shāh] encamped at Ban, a village near Siālkot. B. states that Ban is five or six Kos distant from Mankot. (I. 410; Tr. 527). Raverty says that it is eighteen miles north-east of Sialkot and eight miles south-west of Jammū. (N. A. 354). The Governor of Jammū informs me that a village called Ban still exists about 2½ Kos W.S. W. of the modern town of Jammu. The Banihal Pass (l. 27) is at the eastern extremity of the Pir Panjal range and on account of its comparatively small elevation (only 8500 feet above sea-level), has always been a convenient route of communication towards the Upper Chinab valley and the eastern of the Punjab Hill States. It is the only Pass across the Pir Panjal on which communication is never entirely stopped by snow-fall." (Stein, Ancient Geography of Kashmīr, J. A. S. B. 1899, pp. 70-71). Banihāl is in Lat. 33°-21' N., Long. 75°-20'. Constable, Pl. 25 A a.

IV. 503, l. 4 from foot. [Shaikh 'Alāi died] in the year 956, as is shown by the chronogram Zikrul-l-Allah.

The letters composing the chronogram are not given correctly. فكرالا له would yield by abjad, 1017 and פֿתועל 987. Budauni who was fond of and a past master in this art, gives it as ذاكراله, i. e. 'The Mindful of God.' (I. 409=1. 6). The abjad value of 41515 [with only one lām] is 957 (700+1+ 20+200+1+30+5) and B. puts the event into that year. In the lithographed edition of the T. A. (238, 1. 7 f. f.) and F. (I. 283, 1. 5), the date is given as 955 H. in words and the chronogram as فاكرالك, but these statements are inconsistent and erroneous as the abjad value of the

IV. 505, l. 9. [Islām Shāh] departed to the next world in the year

The date of Islam Shah's death is given by Ni'amatulla (Dorn, L. 170) as 26th Zi-l-hijja 961 H. As he also says that Islam ascended the throne four days after Shīr Shāh's death (on the 13th of Rab'i I. 952) and reigned for eight years, nine months and seven days, the Hijri year given is manifestly wrong. It must be 960 H. Abul Fazl gives the date as 22nd Zī-l-q'ad 960 H. According to him, Shīr Shāh died on 11th Rab'ī I. 952. Islām Shāh succeeded him eight days afterwards on the 19th and reigned for eight years, two months and eight days. (At. N.

I 336=Tr. I. 615). But there is an inadvertent error here also and Abul Final must mean eight years, eight months and two days. The B. I Text of B. puts the event into 961 H., but Ranking observes that both his own Mss had the reading 960 H (I. 415. Tr. I. 533 and Note) He suspects that has been added by the Editors. The correct year appears to be not 961, but 960 H. Dr. Lee's copy of the Makhzan-i-Afghani also gave the date as 26th Zi-l-hijja 960 II. (Dorn II 111) This was Sunday, 3rd December 1553 A. C. The T. A (287, 1 5) and F. (I 231) say that Islam Shah was taken ill in the beginning of 960 II and that he reigned for about nine years. The date given by Abu Fazl, 22nd Zīl q'ad 960 II was Monday, 30th October 1553 A. C. The date given in the C H I (IV 61) is 22nd November 1554, ¿ c 26th Zi-l-hijja 961 ff, but it must be wrong It would leave only fourteen months for all the events of Muhammad 'Adıl's reign Indeed, Sir Wolseley himself states eleswhere (Ibid, p. 67) that Humayun determined to invade and recover India "after hearing of the confusion which prevailed" under 'Adli and reached Peshawar on 25th December, 1554 The numismatic evidence is distinctly and decidedly in favour of 960 H. The latest coins of Islam Shah are dated in 960 H A coin of Muhammad 'Adıl of the same year and several of 961 II are known. (Wright, C. M S. D. 326, 370)

1V. 505, l. 14 And the chronogram Zawāl-1 Khusrawān gives the dates of the deaths of these three sover eigns, viz A II 961

Dowson remarks in the footnote that "Firishta says his father wrote this chronogram" But Budāuni ascribes its authorship to a Mīr Sayyid Ni'amatulla, whose pen-name is spelt as Link the BI Text but Link Ranking's Translation. (I 415=Tr I 533 and Note) The compiler of the Makhzan-i-Afghāni gives the credit of the composition to Shāh Tāhir Dakhani (Dorn, I 170) But there must be some error, either in the original or translation, as this Shāh Tāhir is said to have died in 952 H—nine years before 961 H—according to the Tuhfah-i-Sāmi, the Majālisu-Imumina and the Zabaqāt-i-Shāh-Jahāni, all works of respectable authority. (Rieu, Persian Catalogue, I 395) There is a fourth claimant also and his pretensions are sponsored by Beale, who calls him Maulānā 'Ali (Miftāh, 159)

The numerical value of زوال خسروان is 961 and it is, perhaps, this chronogram which has misled the compilers and is responsible for the error adverted to in the preceding Note. Absolute accuracy is not demanded by the rules of this art and an error of one is condoned by all the connoisseurs.

IV 507, l. 11 from foot Ibrāhīm [Sūr] went to Patna where he fought with Rāmchand, Rāyā of that place, and was taken prisoner.

The place was not 'Patna' but Bhatā This Rāmchand was the son of Vīrabhānu, the son of Vīra Sinha, the son of Shālivāhan, the brother of Bhīdachandra, Rājā of Bhatghorā, who has been already mentioned at p.

461 ante, q. v. my note. The T. A. from which 'Abdulla has copied the passage has 'Bhata', E. D. V. 244. So also B. I. 432.—Tr. 553.

IV. 508, 1. 6 from foot. The action was fought at the stream of Sūrajgarh, about one Kos from Mūngīr and about twelve Kos from Patna.

There is a double error here. Sūrajgarh lies about twelve Kos, i.e. about twenty miles south-west of Mūngīr on the road from that town to Patna. Lat. 25°-12′, Long. 86°-19′ (Thornton), and Mūngīr (Monghyr) is about one hundred miles south-east of Patna. The river of Sūrajgarh is the Ganges, on the south or right bank of which it is situated. Constable, Pl. 29 B e.

IV. 512, l. 10. Akbar pursued Dāud as far as Daryāpur.

Abul Fazl places Daryāpūr at about thirty Kos' distance from Patna and on the other side of the Punpun. (A. N. III. 101; Tr. III. 142). It is 31 miles due west of Monghyr (Cunningham, A. G. I. 475) and to the north of Bārh, which is 33 miles east of Patna by the Railway.

IV. 518, l. 13. Divan-i-Salman.

Mirzā Muhammad Qazvini has recently shown that much of what is said here by Dowson and in the Persian Tazkiras about Mas'ūd-i-S'ad-i-Salman is more or less erroneous or inaccurate. The net result of his investigations is that Mas'ud was born about 440 A. H.=1048 A. C. at Lahore. (J. R. A. S. 1905, pp. 719, 708). The poet was a great favourite of the prince Saifu-d-daula Mahmud, the son of Sultan Ibrahim, when that prince was Viceroy of Hindustan. It was during this period that he composed the Qasidas eulogising his master's conquests, of which four or five are translated by Elliot. (Ibid, 721). Mas ud was obliged to leave India and go to Ghazni in 480 H. to demand justice against those who had deprived him of his jagirs or estates. But he fell, soon after his arrival, under. suspicion of having been implicated in the treasonable proceedings of his patron, Saifu-d-daula, and was confined for about ten years in the fortresses of Su, Dahak and Nai. (1b. p. 722). He was released shortly before Ibrahim's death in 492 H. (p. 733). When the Prince Shīrzād, son of Sultān 'Alāud-daula was appointed Viceroy of Hindustan, Mas'ud was made governor of Jālandhar, (p. 738). But when his patron Abu Nasr Pārsi fell into disgrace. Mas'ud was again thrown into prison and immured for eight years in a fortress called Māranj. (p. 739). He was released sometime after 500 H. through the intercession of Thiqatu-l-Mulk Tahir bin 'Ali the privy-counsellor of 'Alau-d-daula, and died in or about 515 H. 1121-9 A. C. (J. R. A. S. 1906, pp. 11-12 and 24). See also Browne, L. H. P. II 324, 326. Nizāmi 'Arūzi pays to Mas'ūd's 'Prison-Rhymes' the high compliment of saying that "their eloquence and lofty feeling were sucl as to make the hair stand on end on his body and tears trickle from his eyes''. (Chihār Magāla, Tr. Browne, 73).

IV. 519, l. 3. Tabarhinda is stronger than Nûrsādna.

^{&#}x27;Nursadna' must be 'Nandna' in the Salt Range, the great natural

strength of which is enlarged upon by 'Utbi and the other historians of the Ghaznavides 'Utbi calls it 'Narzīn' or 'Nārdīn'. 'Tabarhinda' is not Sirhind, as the note states, but 'Bhatinda'.

IV. 520, l 3 Thou didst bring an army from Dhangan to Jalandhar. 'Dhangan' is, probably, دهمال 'Dhangan', also written دهمال 'Dhangan', can can can be called the can be called the can be called the can be called the cal

mīri, 'which is said by Alberuni to have been the capital of Jālandhar (E. D. I. 62—Sachau's Tr I. 205) Cf also the extract from the Tārīkh-i-Alfi in E. D V. 162, where the name is spelt as 'Damāl' The transliterations 'Dihmīri 'and 'Damhari' (E D V 254, 248, 357) are not quite correct Dhamerī would be more accurate, as the name of the village, as pronounced by the inhabitants, is 'Dhaner' The present tahsīl office and hospital at Nūrpur are built inside the ruined fort of Dhaner. (Kāngrā District Gazetteer).

IV 521, l 11 For sixty years, this slave's father, S'ad bin Salmān served the State

A S'ad-i-Salmān is said by Baihaqi (E. D. II. 134) to have been appointed by Sultān Mas'ūd Ghaznavi, as Accountant and Treasurer of his son Majdūd, when the latter was nominated Governor of Hindustān in 427 A H. (1036 A. C). This S'ad bin Salmān was probably the father of the poet. IV. 522, l 12 Bū Rihān, five years previous to this, declared in the

book called Tafhim, that a King, lord of the conjunctions, would exist upon earth, when 469 years had passed from the Hijra

The reading in the best Manuscripts is not 'five years' but 'fifty years' (J. R. A. S. 1905, p. 713) The Tafhīmu-t-Tanjīm is an elementary treatise on Astronomy and Astrology which Alberum wrote in Persian for the Princess Rayhāna of Khwārizm in 420 H. Forty-nine years—just one short of fifty—had elapsed after 420 A.H., when the prince Saifu-d-daula Mahmūd, the son of Sultān Ibrāhīm, was appointed Viceroy of Hindustān in 469 H Mirzā Muhammad Qazvini observes, however, that he has not been able to find this prediction of Alberūni's in the fine old Manuscript of the Tafhīm (written in 685 H) which is in the British Museum. Herthinks it unlikely that such an elementary treatise contained any such announcement or prognostication of the distant future (Loc cit. 713-4) The Tafhīm has been recently edited and translated by Mr. Ramsay Wright.

IV. 530, l 17. He entered the Raja of Kumāon's country by the pass of Dabar

The village of Dabar 18 "seven or eight miles north of Sadhaura in Ambālā district, near the northern hills and on the edge of it is a small hill, difficult of access, on which Islām Shāh Sūr began to build a fort named Pawā-garh, which was never completed, but was subsequently restored and extended by Banda, the Sikh Guru." (Irvine, Later Mughals, I 116-7). The place is also known as Lohgarh, $qv \to 0$ VII 424 It is very near Mukhlispur which lies close to the Pass.

IV. 532, l. 23. [Khawāṣṣ Khān's tomb is pointed out at] Khawāspur in the Upper Punjāb, between the Jelam and the Chināb.

This must be Khawāṣpur, a town or village which is said by the Emperor Jahāngīr to be situated at about five Kos' distance from the town of Gujarāt and to have "been founded by Khawāṣ Khān, a servant of Shīr Khān Afghān." (T. J. Text. 44, l. 21; Tr. I. 91; E. D. VI. 303). It is mentioned in the Chihār Gulshan as a stage on the road from Lāhor to Attock and about 11 miles north-north-west of Gujarāt town. (Sarkār, I. A. p. ci. See also I. G. XII. 365). Sirsi, where Khawāṣṣ Khān was assassinated, lies about ten miles north-east of Sambhal. Constable, 27 D a.

IV. 533, l. 6. Surat Singh whose principality was Chonsu.

This is Chatsū, twenty-four miles south of the town of Jaipur. Lat. 26°-30′, Long. 76°-0′, Constable, Pl. 27 Bb. Sūrat Singh Rāṭhor was a vassal of the great Rāṭhor Rājā Māldev of Jodhpur. Chatsū is explicitly said by Tod (A. A. R., Ed. Crooke, II. 954, 955) to have been included in Māldev's dominions at this time.

IV. 535, l. 21. And his Paimāban Job Niranjan and other treatises in Hindi are celebrated throughout the world.

The correct title of the treatise was probably *Premānand Jog* [or Yog] Niranjan, i. e. '[Discourse on] Love, Ecstasy and Union with the Universal Spirit' [عثق و حال و وصل].

IV. 540, l. 19. He also read one of the takmīlas of Ghausu-s-Saklain and the whole of Husn [Hisn]-i-Hasīn.

'Ghaus' means succour, deliverance. It is also an epithet of the Qutb or head of the Sūfi hierarchy of Saints. (Houtsma, II. 145). Ghausus-Saqalain, the 'Helper of Men and Angels,' i. e. of the 'World of Men and the World of Demons or Genii,' is one of the panegyrical epithets of the saint 'Abdul-Qādir Jīlāni. (B. Tr. Lowe, II. 418, 446 note). Richardson says in his Dictionary that "Rasūlu-Ṣaqalān" is one of the epithets of the Arabian Prophet. 'Abdul Qādir Jīlāni is also called Ghaus-i-'Azam, Ghaus-i-Ṣamdāni, and Pīrān-i-Pīr or Pīr-i-Dastgīr. He was the founder of the order of Qādiri faqīrs. (Crooke, T. C. IV, 183). He has ninety-nine names and his devotees repeat them to implore his intercession. (Herklots, Ed. Crooke, 192).

IV. 544, l. 26. He sacked the temple of Debi Shankar.

This must be the shrine of Vajreshwari Devi. 'Debi Shankar' signifies 'Devi, the wife of Shankara or Mahādeva'. She is known also as Pārvati, Bhavāni, Durgā, Mahāmayā, Bhīmā etc. The shrine of Vajreshwari still exists at Bhavan, a suburb of Kāngra or Nagarkot. (I. G. XIV, 386). Tieffenthaler says that the idol was that of Bhavāni and represented the lower part of her body, the head being supposed to have fallen at Jwālāmukhi, which lies 14 or 15 miles south-east of Kāngrā. (Description, I. 108. See also T. J. 340, 1. 24—Tr. II. 224; Āīn, Tr. II. 314). 'Bhavan' is about a mile distant from the fort of Kāngra. (E. D. II. 445).

IV. 547, l. 11 from foot. [When] the shoes of the infidels in in this

action . were melted down, 20,000 Mohurs of gold were obtained from them

This tall story reminds one of Tod's tale of the sacred threads of the Rājputs slain after Akbar's sack of Chītor having weighed seventy-four maunds and a half. (A A R Ed Routledge, 1914, I 263) The historians of Kashmīr relate of Sikandar i-Butshikan that he put to death so many Brāhmans, that seven maunds of the sacred threads worn by them were burnt along with their bodies The legend is still popular in Kashmīr and is related in the I G (XV 92) A closer and also older analogue of Mushtāqi's story is found in the Roman historian Livy, who tells us that after the carnage at Cannae, Hannibal measured his success by the bushels of rings taken from the fingers of the equestrian Romans who had fallen in the battle (Bk xxiii, 12)

IV 548, l 9 Ambāla and Hodhna were held by Kālā Pahār

'Hodhna' looks like an error for 'Budhāna', now in Muzaffarnagar district. It was a mahāl in the Sarkār of Sahāranpur (Āīn, Tr II. 291) Constable, 25 B c. It lies about 43 miles south-east of Karnāl (Th) Mārahra (1 12) is in Etāh district, U. P. Lat 27°-45', Long 78°-38' Constable, 27 D b

IV. 551, l. 5 The whole of the territories in his possession contained 13,000 parganas

13,000 must be a typographical error for 113,000, as in the footnote on page 424 ante, Elliot himself states that the Wāqi'āt-i-Mushtāqi gives the number of parganas as 113,000 'Abbās also, who has copied-several passages from Mushtāqi (cf 410-424 ante), puts the number at 113,000, but takes care to add that by parganas he means 'villages'. (424 ante). The Tārīkh-i-Dāūdi asserts that 113,000 horsemen were distributed throughout the parganas for the protection of the district forts (417 note) 'Parganas' must be loosely used for 'villages' The total number of Mahāls or parganas in Akbar's Empire was only 2737 (Āīn, Tr II, 115) and in Aurangzeb's not more than 4440 (Bakhtāvar Khān, Mirāt-i-Alam in E D VII 163) Moreover, if there were, as 'Abbās (413 ante) and Mushtāqi assert, five revenue officials in each village, there would have been 665,000 of such parasites in the kingdom, which seems open to doubt IV 551, last line He kept dn ai my . in Khajuāra, one in the countily of Dhandhera

'Dhandhera' may be 'Dhundar', the district of which Daosa, the oldest seat of the Kachhwāh' rulers of Jaipur, was the centre "A range of rocky hills intersects nearly the whole of Shekhāwati in a north-east direction and close upon its eastern frontier. The country on the east side of these hills is called Dhundār, a name which was formerly applied to a large portion of Rajputāna, while that to the west is called Bāgar, which includes nearly the whole of Shekhāwatī and is generally applicable to the sandy country where water is procurable only at great depth" (Boileau's Ms. Journal, quoted in Elliot, Races, I 9-10 Note. See also

I. G. XIII. 385). The name is said to be derived from an ancestor of the Nikumbha Rājputs, who is said to have slain a demon named Dhūndhu and acquired thereby the title of 'Dhūndhumāra' or "Slayer of Dhūndhu." (Cunningham, Arch. Survey Reports, XX,3; Crooke, T. C. IV. 86). Dausa is shown in Constable, 27 C b.

But 'Dhandhera' may be meant for 'Dhamdhera,' a Rājput principality in Mālwā—a Rājā of which named Indarman [Indradyumna] is mentioned in the chronicles of Shāh Jahān. (Bādishāhnāma, I. ii. 223, 1.7). The town of Shāhābād-Dhamdhera is 90 miles north of Sironj and the same distance south-west of Gwālior. It is now in Jhālāwar State, Rājputāna. (I. G. Atlas, Pl. 34 E 3). The M. U. (II. 265) says Indarman's native place was Sahār Bābā Ḥāji in Sārangpur. Another chief called Jagman Dhandhera lived in the days of Akbar. (Ibid). 'Khajwāra' must be a mistake for 'Khīchīwāra.'

IV. 553, l. 23. Hereupon Mahmud feigned sickness etc.

The story of drinking a goat's blood which is told here of Sultān Maḥmūd of Mālwa is related by Nizāmu-d-dīn (T. A. 639, 1. 15) as well as by Firishta (II. 325, 1. 8), in the Multān Section of their histories of Sultān Quṭbu-d-dīn Laugah and he is said to have practised the same trick for the same object of securing the throne. And if we are to believe Manucci, Shāh Jahān had recourse to the identical ruse with a view to obtain the permission of the King of Bījāpur (?) to leave his territories, immediately after the receipt of the news of the death of Jahāngīr in Kashmīr. (Storia, I. 180). Manucci's tale is undoubtedly apoeryphal.

IV. 563, l. 4. Where then did he ['Abdu-r-Razzāq] get his history of Tīmūr!.......If Abdu-r-Razzāq did not use the Malfūzāt, he must have used some work remarkably similar to it. No such work is known.

This formidable conundrum can be easily solved. Such a work is now known, though it was not, when Dowson wrote. It is the Zafarnāma of Nizām-i-Shāmi which was composed in 806 A.H., several years before that of Yazdi, and which has been copied, verbatim, by Hāfiz Abrū also, See my Notes on III, 390, l. 6 ante, and IV. 91, l. 9 f. f.

VOL. V. BĀBUR, HUMĀYŪN, AKBAR.

V. 1, l. 5. Ahmad Yādgār, the author of this work, describes himself.
as an old servant of the Sūr Kings and says that Dāūd Shāh
gave him orders to write a History of the Afghān Sultāns
The author mentions incidentally that his father was wazīr
to Mizā 'Askari, when the latter was in command in Gujarāt

Every one of these three statements is, to say the least, very doubtful. The whole of the chapter (on the Reign of Humayun), in which the last of these assertions occurs, is copied verbatim, as Elliot points out (p. 2 infra), from the Tabagat-1-Akbari. It is there made by the author of that work of his own father. (196 infra=Text 198, 1.11) It is hardly likely that the father of Nızamu-d-din as well as of Ahmad Yadgar, should have both been Vazīrs, at the same time, and in the same circumstances. of one and the same individual If Ahmad's claim to be the author of the chapter is admittedly and demonstrably invalid, the supposition about his father having been 'Askari's Vazir must be also rejected. His claim to being the son of 'Askari's Vazīr is as unsubstantial as his pretence to be the author of this section of his work Everybody is agreed that Ahmad's assertion about his having compiled his chronicle by the command of Daud Shah Kararani must be false, as Daud was put to death in 983 H Moreover. Dr Rieu has shown that the M'adanu-l-Alhbar 2-Ahmadshaht, upon which Ahmad has drawn as freely as on the Tabagat, was composed about 1022 H (Persian Catalogue, III. 888) This fact also throws considerable doubt on Ahmad's claim to have been a "servant of the Sur Kings," as their power was extinguished so long ago as 963 H. sixty years before. The incidental remark on p 42 infra about ' 160 years having elapsed since" the capture and punishment of Mohan Mundahar in 936 H, seems to me to prove that his compilation is of much later date than has been supposed. Mrs Beveridge thinks that the remark "may have been originally only a marginal note" (B.N. Tr, 701 Note), but this surmise is hardly borne out by the fact that it is found not only in the copy belonging to the Asiatic Society of Bengal but in the "better Codex of Ahmad's work which is now in the Calcutta Imperial Library" (Ibid) Mrs. Beveridge admits that "the writings now grouped under the title of Tarikh-i-Salātin-i-Afāghana, present difficulties, both as to date and contents" These difficulties are perhaps of our own creation, and they would cease to exercise us, if it was recognised that Ahmad Yadgar's rigmarole is a late compilation made up of patches and shreds purloined from earlier authors and pieced together without discernment or discrimination. It is full of demonstrable errors in regard to names, dates and facts and its exiguous value is further discounted not only by the author's "liking for marvellous and ridiculous stories," but by its frequent mention of the use of artillery, e g. shells (p 5), camel guns (p. 6), cannon (p. 13), gunpowder (p. 14), and mat chlocks (p 15) by the Lodis. It is clear from the Memoirs of Babur

that Ibrāhim Lodi brought neither matchlocks nor field guns of any sort to the battle of Pānīpat.

V. 4, l. 14. Bahlol.....had by this time advanced as far as Narela.

Narela is stated, at 78 infra, to be 15 Kos from Dehli and it is mentioned as the next stage after Bādli Serāi in the itinerary from Dehli to Lahore. (Chihār Gulshan in Sarkār, I. A. xeviii). Finch also speaks of it as 14 Kos from Dehli. (E. T. I. 156). It is now a station on the Dehli-Kālkā Railway line, seventeen miles distant from Dehli Junction. Constable, 27 C a. This indicates that the Kos referred to by Ni'amatulla and Finch is the short or common Bādshāhi Kos of 1½ miles, q.v. Cunningham, A. G. I. 574.

V. 4, l. 4 from foot. Chattar Sāl, son of the Rānā's sister, was at Ūdipūr with 10,000 cavalry.

The mention of Udayapur here in Circa 1460 A. C. and the subsequent mention of it as the Rāṇā's capital in the reign of Buhlūl (p. 5, l. 10 infra) is unhistorical. Udayapur in Mewār was founded only in 1559 A. C., after Rāṇā Sanga's death, by his son Udaya Sinha, who ruled from 1537 to 1572 A. C. (I. G. XXIV, 89; Duff, C. I. 288). Aḥmad Yādgār's compilation is full of blunders and anachronisms of this sort.

V. 5, l. 12. After that, the Sultān [Buhlūl] carried his victorious armies into Munkhār.

The place-name appears to be corrupt and is difficult to restore, as there is no reference to this expedition in any other writer. The district meant may be that of Nimkhār which is mentioned at 296 infra and also at E. D. VI. 123. The town lies on the left bank of the Gomti in Hardoi district, Oudh. Lat. 27°-21′ N., Long. 80°-32′ E. Constable, 28 B b. But the reference may be to the country of the 'Mundhārs' [عندهاد] which was in the neighbourhood of Sirhind, as the Sultān is said to have returned immediately afterwards to that town. On the other hand, Nimkhār contains, as Abul Fazl says, a shrine of great resort (Āīn, Tr. II. 172) and is, even now, a place of pilgrimage. It is the Naimisha Aranya which is mentioned so frequently in the sacred literature of the Hindus, Sikandar's iconoclastic zeal may have taken him there.

V. 7, l. 1. [Ahmad Khān Bhatti] bestowed jewels upon her to the value of 10000 rupees.

The reference to. "rupees" is either one of the numerous anachronisms of this author or an unauthorised interpolation by the translator. It is common knowledge that the use of the word 'Rupee' for the silver tanga weighing about 175 grains is not older than the reign of Shīr Shāh. (Āīn, Tr. I. 31).

V. 18, l. 16. I slew the Rājā of Nagarkot and that stone which the Hindus had worshipped for 3000 years, I exposed to be trodden under foot by all the people.

In the narrative of the same event in the Wāq'iāt-i-Mushtāqi, the credit of the conquest of Nagarkot is given to a quite different in-

dividual, viz Khawāss Khān, the son of Miān Bhūwa, and the idol is said to have been "given over to the butchers to make weights for the purpose of weighing their meat" (E D IV. 544 See also my note on IV 447, 1.16 supra). The Rājā of Bihār, from whom Miān M'arūf boasts of having brought away seven Mans of gold, may have been the Rājā of Tirhut, who is said by Ni'amatulla to have submitted to Sikandar, but he is there said to have only promised to pay several lacs of tangas, as a fine (96 infra)

The fort of Jünd -2- (1 15) may be the same as that mentioned in the Tār ikh-2-Dāūdi (E D. IV 45° 460), from which Ahmad Yādgār has borrowed this and several other passages. It has not been satisfactorily identified but is perhaps Chiland -2- in Sāran, six miles east of Chupra. A mosque built by Sultān Husain of Jaunpur at Chirand still exists.

V 20, l 1 Mian Bayazid, the son of 'Ata Lodi.

According to 'Abbās Sarwāni (E D IV. 347), the Miyān Biban who joined Shīr Shāh was the son of 'Atā Lodi See also Ibid 352, 377 Miyān or Shaikh Bāyazīd was not a Lodi at all He was a Farmuli and a brother of Shaikh Mustafā 'They were both sons of the brother of Miyān Muhammaā Farmuli (Kālā Pahār) and sister's sons of Sultān Buhlūl (E D. IV 352-4, B N Tr 527, B. I 337=Tr 444) But F states that Biban was a Jalwāni (I 202, l 18, 204, l 15) Whether the Biban of 'Abbās was or was not identical with the Biban who was defeated by Bābur, and whether the latter was a Lody of Jalwāni, it is certain that Miyān Bāyazīd was not a Lody

V. 20, l. 3 from foot The Rājā [of Gwālior] had determined to send sever al pairs of elephants

Here "pairs" is an unsuccessful attempt to render the idiomatic expression رحير فيل, lit "chains of elephants," in which عن is only one of those meaningless adjuncts which have been variously described as "numerical affixes or co-efficients" and "quantitative or numerical auxiliaries." They are very common in Persian, e g فطعر لمل - مهار ستر - مرل Yule (Hobson Jobson, 632-4) gives examples of similar idioms in Malay, Burmese, Chinese and even the languages of Central America

V 25, l. 7. On Wednesday, 2nd Shawwal, 932 H., he [Bābur] set forth [from Kābul] -

The date, like almost all the other dates in Ahmad's work, is wrong. The battle of Pānipat was fought, according to this writer's own statement at p 28 infra, on 4th (really 7th or 8th) Rajab 932 H. Bābur started from Kābul on 1st Safar 932 H (B N Tr 445=E D. IV. 239, A. N. Text, I. 93=Tr I 239, F. I 203, I. 17) Ganaur (p 27, 1 5), where Sultān Ibrāhīm is said to have arrived, is nineteen miles south of Pānipat Garaunda, where Bābur is stated to have "mounted his horse" (28, 1 5), is ten miles north of it (Sarkār, I A. xcviii). Constable, 25 B c

V. 30, l. 14. Amīr Khalīfa, Allāhdād Khān, Tursam Bahādur [were despatched] to Dehli and Agra.

The names of the officers sent to both towns on this occasion are given by Bābur himself very differently. The Amīrs sent to Dehli were Mahdi Khwāja, Muḥammad Sultān Mirzā, 'Ādil Sultān, Junaid Birlās and Qutluq Qadam, while Prince Humāyūn, Khwāja Kalān, Muḥammadi, Shāh Mansūr Birlās, Yūnus 'Ali, 'Abdulla and Wali Khāzin were despatched to Āgra. It will be seen that not even one of the names mentioned in this connection in the corresponding passage of the Emperor's own Memoirs (B. N. Tr. 475=T. B. 176, ll. 8 f. f.=E. D. IV. 256) or other reliable authorities (A. N. I. 98=Tr. I. 246-7; F. I. 205, l. 11) is to be found in Aḥmad Yādgār's account and vice versa.

V. 30, footnote, l. 4. He [Ibrāhīm] endeavoured to cross into the Doāb at the ferry of Burāna.

This name '! '! is most probably meant for 'etc.', 'Būriya' in Ambāla, Punjāb. Constable, 25 B b. Thornton says that there is a ferry in the neighbourhood by which the Jumna is crossed. The name may be also read as 'Budāna'. There is a 'Budhāna' in Muzaffarnagar, 43 miles south-east of Karnāl (Th.), but that place is not on any river at all. But the whole story which is said to have been told by a man who was "present in the battle" and was "120 years old" when he related it is unhistorical. Ibrāhīm's head was actually brought to Bābur.

V. 33, l. 10 from foot. One day, Jalāl Khān.....said, "O Haibat Khān, I have heard that you are generous when intoxicated" etc.

This is one of those 'wandering tales' which are fitted to and fathered upon different persons by successive retailers of popular anecdotes. It is by no means new and there is a much older analogue in Barani who relates it in almost the same words of Sultān Balban and one of his freed slaves (مولا زاده) named 'Ali who had the title of Ḥātim Khān.

I. 230, l. 14). Firūzpur-Jharka must be at least fifty miles north of Kānhwa Muhammad Mahdi Kliwāja was not Bābur's son-in-law, as Ahmad asserts (l. 10), but his brother-in-law, the husband of his sister Khānzāda Begam. Hindāl's name also is wrongly inserted. It is a mistake for Humāyūn, who led the right wing at the battle Kānhwa (B N. Tr 566) V 37, l 9 from foot. His Majesty [Bābur] sent Sultān Junaid Birlās and Haidar Malik Hūlak to proceed with other Mughals and a Hindustāni armu.

'Haidar Malik Hūlak' can be meant for no other person than Mirzī Haidar, the author of the Tarikh-i-Rashidi Hulak must be a perversion of 'Dughlat', the name of his tribe, which is sometimes written as 'Oghlat' (vide B N Tr 22 note). But Haidar Mirza Dughlat was really in the service of Sultan S'aid of Kashgar from 918 up to 937 H. He came to India only during the reign of Humayan and about five years after Bābur's death. (Tārīkh-1-Rāshīdi, Tr 399, A. N. I. 135=Tr 308, B N. Tr 362, 695) The reference to Hindil on 1 24 is also founded on error The prince was not in India at all at this time and was less than ten years old (B. N. Tr 695-699). Here, Ahmad Yadgar has confused Hindal with 'Askari,' who was the prince really despatched as the nominal leader of the expedition (B N. Tr 628, 637, 651, 654, E D IV 285-6; A.N I 113, Tr 269-70) Hindal arrived in India for the first time only on the day of Humayun's colonation (Gulbadan, H N Tr. 110, T A. 188 infra). There is similar confusion and error in what is said about Kāmrān and Hindal on p 40 The statements are "discredited by Babur's own narrative" (B N. Tr 604 note) The names of the four princes are everywhere confused in this chapter which is a veritable jungle of errors

V. 41, l. 13 from foot The royalist troops turned their backs and fled, followed by the Kanwar

Here as well as below, at p 193, Note 5, the true reading is means "thieves, plunderers or robbers" in Persian (Richardson) Or it may be a vernacular word for 'villagers, peasants', which is used more or less contemptuously in the sense of 'rustics', 'boors' (Cf the Gujarāti Gamār and Gāvadi) It occurs in the Akbarnāma also, but Mr Beveridge (Tr. I. 809) leaves it untranslated and unexplained He speaks of 'Kolis and Gawārs' and 'Bhils and Gawārs' (in capitals), as if 'Gawār' was a proper name or a tribal designation Mrs Beveridge also adopts the same course in her translation of the Memoirs of Gulbadan where the word occurs twice. (Text 47, Il. 10, 12 Trans 143) The word is found in Budāuni also Ranking spells it as 'Kawārs' and thinks that the reference must be to "a tribe of Jats, otherwise known by the name of Gatwārās," (Text, 85, 168, 882—Tr 122 and Note, 231 and 493), but this cannot be accepted, as the 'Kolis and Gawārs' and 'Bhīls and Gawārs' of Abul Fazl are mentioned in connection with Cambay in Gujarāt

V 46, l 3 He despatched an army against the Rājā of Andrūn On page 58, he is called 'Rājā of Andardūn' His stronghold is there called 'Kisht' and he is said to have rebelled once more. It is permissible to suggest that 'Andrun' [Andarvan] or 'Andardun' [Andardavan] is not the name of the place but that of the Raja. He may have been called 'Indradyumna' or 'Indravadana.' Both these names are found in Sanskrit Literature and are common even now. (Duff. C. I. 299; Sir G. Grierson's Art. 'Gleanings from the Bhakta Mālā' in J. R. A. S. 1910. p. 300). 'Kisht' may be a miswriting of 'Kanth', i. e. Hat-Kanth or Hat-Kant, the old name of the Bhadauriya country, near Gwalior. The Bhadauriya chiefs were notorious for their lawlessness and turbulence. Bhind in Gwalior is locally known as Bhind-Bhadawar, on account of having been the chief seat of the Bhadauriyas. It is in Lat. 26°-33' N. and Long. 78°-48' E. (I. G. VIII. 110). It lies on the route from Etawa to Gwalior and is 54 miles north-east of the latter. Constable, 27 D b.

Hatkant is now included in Bah or Pinahat, the south-eastern taksil of Agra district (I. G. VI. 192) and lies in the ravines of the Chambal, (Elliot, Races, II. 86). The pargana town seems to be also called Athgath and lies on the route from Etawa to Agra, 20 miles west of the former. Lat. 26°-47' N., Long. 78°-47' E. A Raja named Indarman Dhandhera is mentioned in the Bādishāhnāma (I. ii. 223, l. 9 and M. U. II. 265-266) and Indarman Bundela in the Maāsīr-i-'Ālamgīri (Text, 163).

V. 48. l. 12 from foot. A battle was fought at Kanulapur near Ladanah. Thornton mentions a Ludhana in Gwalior State, 46 miles south-east of Nimach. Lat. 24°-0' N., Long. 75°-27' E. It is the 'Laduna' of the Post Office Guide and is near Sitamau which is in Lat. 24°-1′ N., Long. 75°-23′ E. Sitāmau is shown in Constable, Pl. 27 B d. 'Kanulapur' may be some place called 'Kamlapur' near Gwalior, where Jamal Khan was posted. V. 56, l. 11. On Friday, the 7th of Sh'aban [962 H.], a severe action was fought [at Farra between Ibrāhīm and Sikandar Sur].

The year is not given, but as 7th Sh'aban Hisabi 962 H. or 27th June 1555 A. C. was a Thursday, 7th Sh'aban Ruyyat must have been a Friday. The same date in the preceding year, 961 H., was Sunday, 8th July 1554. V. 56, footnote 4. Firishta makes him [Sikandar Sur] out to be the nephew of Sher Shah.

But Nizāmu-d-dīn (TA., 240, last line) and according to the Cawnpore lithograph of his History, Firishta also (I. 234, I. 8 f.f. and 236, I. 3) state that Sikandar was 'the son of one of Shir Shah's uncles' (الكي الزبني اعمام) and not his nephew. Ni'amatulla avers that he was only a relative. (Dorn. I. 174). In view of the uncertainty of the relationship, it may be worth while to point out that on some of his very rare rupees and copper coins: Sikandar styles himself, the son of Ism'ail. (Rodgers, J. A. S. B. (1887), LV, pp. 184, 187; Wright, I. M. C. II. No. 898; C. M. S. D., pp. 379-380). 'Abbas gives the names of the seven brothers of Shīr Shāh (E. D. IV. 310) and Ni amatulla gives a slightly different list, (Dorn, I. 81); but Ism'aīl does not appear in either of those authorities. V. 57; l. 4 from foot. Akbar spent that time on the borders of Mahain. J. Star

infra; A. N. I 822=Tr I. 596, F I. 241, I 18) Ghazni had been given to Akbar as his appanage after the death of Hindal (F I. 240, I 3 f f., T A. 234 infra) and all these authors state that he was sent there at this time V. 63, I 12. Hīmānvoiced that if he were destined to conquer Dehli, ..., he would become a Musalmān on his return to Dehli

This story must have been popular at the time, as it is told in the Memoirs of Bāyazīd Biyāt also "Hemū", he writes, "had vowed that if he defeated the Mughals, he would become a Musalmān. But God erased from the infidel's heart the recollection of this vow after he had defeated Tardi Beg. As the glory of Timūi had descended to Akbar, God, on the field of Pānīpat, put forgetfulness of his vow into Hemū's heart" (Mr Beveridge's Summary in J A S B 1898, LXVII, p 309)

V. 64, l. 3 from foot Ahmad Beg, the madman, who was unequalled ... in foretelling the future by what he saw in the blade bone of a sheep

Another 'wandering tale' The Emperor Jahāngīr tells a very similar story of a man named Hazāra who was a past master in this art of predicting events by looking at the shoulder-blades of slaughtered sheep But he relates it in connection with the battle between Akbar and Muhammad Husain Mirzā near Ahmadābād in 981 A H (T J 20,1 1=Tr. I 43) The Amīr whose death was foretold on that occasion was Saif Khān Koka Ahmad Yādgār has perhaps mixed up the two battles and transferred the tale from the one to the other He is, in any case, demonstrably wrong in asserting, as he does, a few lines lower down (65, 18 f f), that the reprobate, Shāh Abu-l-M'aāli, was the "chief of rank" who "obtained martyrdom" in this battle, as the Majāb had predicted Abu-l-M'aāli did not take part in the battle, as he had been thrown into prison He met a felon's death seven years later at Kābul (970 H) (T A 248, 287 infi a)

V. 67, l 6 from foot Khwāja Habībulla of Herāt

Can this Khwāja Habībulla who was Ni'amatulla's father have been identical with the Hājji Ḥabībulla, who is mentioned at 407 and 424 enfi a? Ni'amatulla says that his father had been in Akbar's service for thirty-five years. We know, that Hājji Habībulla Kāsi was employed by Akbar in conducting negotiations with his brother Mirzā Muhammad Hakīm and was also sent to Goa on a commercial mission in 986 H (407 enfi a)

'Kāsı'ıs the name of an Afghān tribe (M U III 637,14) Tātār Khān Kāsı was the Afghān governor of Rhotās in the Punjāb in 962 H (T A 237 infra, B I 459=Tr. 592-3).

V. 71, l 1 from foot. Both parties met near the village of Kaira in the par gana of Khizrābād

This 'Karra' [] is perhaps 'Kharār', now in Ambālā, in which Khiziā-bād also is included There is a Khizrābād in Kharār tahsīl, seven miles south of Rupār. Constable, 25 Bb, See the note on Vol. III, p 350, l. 6, ante.

V. 72, l. 8. There was a holy man named Saiyid ibn Majzūb who made predictions (Sāhib-i-lafz būd).

rather means that whatever the man happened to say without thought or premeditation, whatever passed his lips or was uttered by chance, was realized in fact and came to pass, as the utterance was inspired from above, although he himself was not conscious of it. The idea underlying the phrase is expressed in two couplets which are familiar quotations in Persian Literature:

مردان خدا خدا نباشند لیکن از خدا جدا نباشند "Men of God are not God, but they are not different from God." حدیث اهل فنا ترجان تقدیرست بود ضمیر و زبانش شبیه لوح و قلم

"The words of the men who mortify (lit. destroy) themselves are the interpreters of Destiny; their hearts and tongues are replicas (facsimiles) of the Tablet and the Pen of Fate". (T. A. 171, l. 14). The second couplet is quoted in the Tārīkh-i-Dāūdi also. (E. D. IV. 444). Both these authors cite it in connection with a presage or omen portending the rise to power of Buhlul's son Sikandar. Stories of this sort have a tendency to grow in the telling and to gather all sorts of excrescences relating to time, place and circumstance. The holy man's name is uncertain. He is called 'Sayyid Ibn' by the T. A. (149, l. 16), 'Saida' by F. (I. 174, l. 9) and 'Seid Ayen' by Dorn. (I. 43). The real name may have been صعيد مجذوب Sa'id. the Majzūb. According to a legend still current in Ludhiānā district, the Faqīr's name was Hazrat Shaikh Şadr-i-Jahān or Sadru-d-dīn, and he was a disciple of Shaikh Bahau-l-Ḥagq, i.e. Bahau-d-din Zakariya of Multan. The ruling Nawabs of the Maler Kotla family now claim to be his direct descendants and his mausoleum is shown in Maler. (F. H. Tolbort's art. in J. A. S. B. 1869, Pt. i. 92; I. G. XVII. 86).

V. 72, l. 5 from foot. But the truth or falsehood of this has never been ascertained.

Dorn's rendering of this sentence is very different. "Such as assert Behlol to have carried on the trade of a merchant are wrong." (I. 43). The original words used in the T. A. (149, I. 4 f. f.), from which this account has been borrowed by Ni'amatulla, are در بعضی تواریخ مسطوراست که ملك بهلول تجارت "In some histories it is written that Malik Buhlūl was engaged in trade, but it has no foundation in fact, i. e. it is not true."

V. 74, l. 7. Ahmad Khān Mewātti possessed the country from Mahrauli to Ladhū Sarāi near the city of Dehli.

'Aḥmad Khān Meo' [Mewāti] is mentioned as a grandson [فين] of Bahādur Nāhar who paid his respects to the Sayyid Sultān Muḥammad Shāh in 838 H. (T. M., Text, 243 last line). Dorn reads the place-name as 'Mahrwai', (originally, which may be an error for عجروى or هجروى i.e. هجروى Macheri, (originally, Matsyapuri), in Alwar. But the T. A. (150, l. 13) and F. (I. 142, l. 5) also call it 'Mahrauli', and it may be 'Maholi' near Mathura which was a Mahāl in Sarkār Āgra, Ṣūba Āgra. (Āīn, Tr. II. 183; Elliot, Races, II. 85-6).

As regards Ladhu Serāi, it is said in the Asāru-s-Sanādīd that the road to Ladhu Serāi starts from the Mausoleum of Iltutmish and passes via the Qutb Minar. (Pt. I 66) Ladhu Serāi lies a little north of the Qutb and is shown on the Map prefixed to Thomas's C P. K D. and the Tourist Map of Dehli issued by the Survey of India

V. 74, footnote 4 The empire of the King of the Earth extends from Dehli to Palam.

The point or sting of the epigram lies in the fact that this Sultān 'Alāu-d-dīn assumed the title of 'Alam Shāh', 'King of the Universe,' and had it engraved on his coins also Pālam is a village which lies about 10 miles south of Dehli. It is now a Railway station V. 79, l. 10 from foot. When he [Sultān Buhlūl] reached Burhānābād, Mubārak Khān, governor of Sakūt, came to pay his respects.

Burhanabad is said to have been near Marchra, which hes about 15 miles north of Etah (T A 150, l. 4 f.f) Here it is said to have been near Saket which also is in Etah. Yahya (E D IV 64) and B (I 293, Tr I. 386) speak of it as a dependency of Etawa and near or on the bank of the Black Water (Kali Nadi). Seely mentions a place called Burrawanpoor, fourteen miles north of Saket, thirty-nine north of Mainpuri and forty-three south of Koil or Aligarh. (Road Book of India, Edit. of 1825, 20-1, and 18).

V'80, l. 4 from foot. Sultan Mahmud confined him [Qutb Khan], and he remained captive for seven years.

So also in the T. A. 154, 1 2, from which Ni amatulla has transcribed-the words. But F. (I. 176, 1 7 f f) has "months" instead of "years" and the context which follows indicates that this is most probably right Sultan Mahmud of Jaunpur died very soon after the capture of Qutb Khan Lody. F says that Bhikhan Khan, styled Muhammad Shah, ruled only for five months and Qutb Khan was released very soon after peace was made on Husain's accession (F II 309, 19 f.f), B (I. 307-8-Tr I 403-4) also states or implies that Qutb Khān was released within less than a year of his capture The chronology of the Sharqi dynasty is not quite certain. The numismatic evidence is not only unhelpful, but confusing Mahmud Shah's coins in regular sequence from 844 to 863 have been found. But, at the same time, coins exist, both of Muhammad and of Husain Shah, which are dated in 861, 862 and 863 H. It would seem as if Muhammad and Husain had both aspired to supreme power and both issued coins. All that can be said is that Sultan Mahmud died between 861 and 868 H, that the reign of Muhammad Shah was a brief one and that peace was made between Buhlul and Husam very soon after the latter's accession. F. says that Mahmud died in 862 H, and that Muhammad reigned only: for five months (II. 308-9) The T A puts the death of Mahmud into 862 H. (532, 1 1), and gives Muhammad a reign of five years, (Ibid 1. 6), but, this is, most probably, a miswriting of ale for ale The incarceration of

Qutb Khan could not, in any case, have lasted for so long as seven years, even if it did not terminate after seven months. For the history of the Jaunpur dynasty and their coins, see H. M. Whittell, Numis. Suppl. No. XXXVI to the J. A. S. B. (1922), New Series, XVIII, pp. 10-35.

V. 81, l. 5 from foot. Muhammad Shāh reached Sūrseni Sultān Bahlol encamped in the pargana of Rāpri which; adjoined Sūrseni.

The T. A. (154, l. 13) and F. (I, 176, l. 16) read 'Sarsati' and this is transcribed as 'Saraswati' in the C. H. I. (III, 231), but no clue is given to its location. Can it be ... i. e. the old village of Sirsā (now-called Sirsāganj), near Rāpri, 27 miles south of Mainpuri and 14 from Shikohā-, bād? (N. W. P. Gazetteer, (Ed. 1876), IV. 751; I. G. Atlas, 31 A.3).

V. 87, l. 3. He [Sultan Husain] then proceeded against Dehli in the month of Zī-l-hijja, A.H. 893.

This date is out by ten years. It should be 883. Sultān 'Alāu-d-dīn died in that year. The T. A. (156, last line) and F. (I. 173, l. 4) put this invasion. into 883. B. gives the chronogram of the subsequent defeat of Husain as '(Tidings of Ruin), the letters of which have the numerical value of 883 (50+6+10+4+600+200+1+2+10=883). (I. 310; Tr. 407).

V. 88, l. 11. A desperate battle was fought at the village of Sonhär:

There are several variants, with in the T. A. (157, 1.15); in F. (I. 177, 1.5 f. f.), with in B. (I. 310=Tr. 407), and 'Lubhar' in Dorn (I. 53). Sir Wolseley Haig thinks it is Senha or Suhnuh in Lat. 27°-21', N.; Long. 78°-48' E. (C. H. I. III. 233 and 257 note). Thornton mentions a 'Senowra' in Mainpuri, 40 miles north-west of Etāwa in Lat. 27°-12', N., Long. 78°-36' E., and also 'Sooneyruh' in Mainpuri, Lat. 27°-37', N., Long. 78°-57', E., fifty mile snorth-west of Fatehgarh. The compiler of the District Gazetteer, opines that the battle was fought at the pargana village of Sonhār in Etāh talṣṣīl. (U. P. Gazetteer, (Ed. 1908), X., (Mainpuri), 154; I. G. XII. 36).
V. 89, l. 11. They met at the village of Rāngānw, which belongs to Kālni.

This is identified in the C. H. I. (III. 233) with Rāigāon in Khāgā taḥṣil, Fatḥpur district. Lat. 25°-54′ N., Long. 81°-16′ E. Khāgā is the eastern taḥṣil of Fatḥpur district. (Constable, 28 B c). Kālpi is in Jālaun. A glance at the map will show that the identification is very doubtful.

The correct name of the Rājā of Etāwa was not 'Sangat' but Sakat' Sinha and that of his son was not 'Dādand' but 'Dandū'. (T. A. 159, l. 5; F. I. 178). Both of them are mentioned in the Dynastic List of the Chauhān Rājās of Partābner. (N.W.P. Gazetteer, (Ed. 1876), IV. 374 and Note). 'Baksar' (l. 14) is not the well-known 'Buxar' in Shāhābād, but 'Bagesar' which lies about thirty-five miles south-east of Unão town. (I. G. VI. 218). V. 89, l. 17. Sultān Husain fled to the Panna country, the Rājā of which came out to meet him.

The T. A. rightly reads 4. Bhata (158, l. 6), i. e. Bhatghora, the modern Rewā. B. also has 4. (I. 311). The name of the Rājā, which is given at page 93 as Bhīd, conclusively proves that the right reading is

Bhata He was Bhidachandra the Baghela Raja of Rewa

On page 94, l 11, Kantit is called "a dependency of Panna", where also the right reading must be "Bhata". Kantit is now in Mirzāpur district, on the road from Allahābād to Rewā, sixteen miles south of the former (Th) Arail, which is mentioned on the same page, is now called Jalālābād and is very near 'Bayāk', ie, Prayāg (Elliot, Races, II 104) V 89, footnote 4 Firishta adds that Bībī Khunza, daughter of the late King, Savyid 'Alāu-d-dīn and chief lady of Husain Shāh's household was taken captive

Dorn speaks of her as Sultan Husain's 'first consort, Malka Jehan' (L 52) She is said by F (I 178, l. 9) as well as the T A (158, his most honoured مرم محترم بي بي خوازه or خوالما his most honoured wife. Bībī Khunza or Khunda' B speaks of her as his "chief wife, Malika-e-Jahān, Bībī Khūnzā" (Text, I 312-Tr I 412) Sir Wolseley Haig gives her name as Jalila (C H I III 231 and 255), but this seems to be founded on a misapprehension F says elsewhere that she was his Halila, (II 310, 1 5), or 'lawful wife' and instigated him to invade Dehli This word alls is used in the same sense in the T A also It is there said that the Khan 1-'Azam Mırza 'Azīz Koka went to Ahmadabad to visit his sister who was the wife [حليله] of the Khān-i-Khānān 'Abdu-r-Rahīm (362, 1 8f f=442 infra) In another place, Nizāmu-d-dīn writes that the wife حليله of Sultan Muzaffar II of Gujarat was the daughter of Jam Salahu-d-din's uncle A man speaks of his wife periphrastically as his did or of that which is lawful to me' (Richardson) The author of the Maasir-l Umara writes that the noble wife ملله عليه of Mir Abul M'aali Khwafi and mother of Khan Jahan Bahadur was the foster-mother of Aurangzeb (I 791, 18) 'Jalila'is only an adjective or qualifying epithet has very much the same حلية حلية عليه has very much the same הכתי שלתי meaning as

"Khūnza" or "Khūnda" seems to be a short form of "Khūdāwanda" or "Khūwanda" So, 'Khūndāār' is an abbreviation of "Khūdāwandāār" Ibn Batūta tells us that the name of the sister of Sultān Muhammad Tughlaq was Finūz Khūnda, meaning, 'l'hem euse main esse' or the 'Fortunate Lady' (Defremery, III 271). We know from Barani and Shams also that she was called "Khūdāwandzāda" Iltutmish's wife is said by Minhāj to have been styled 'Khūdāwanda-i-Jahān' after the accession of her son, Ruhnu-d-dīn Firūz, to the throne (T. N. Text, 181, 15 ff) Firishta states that the mother of Murtizā Nizām Shāh of Ahmadnagar, who reigned from 1565 to 1689, was called 'Khūnza Ilumīyūn' (II 130, 17)

V 90, l 1 Leaving Kuth Khūn Lodi and Khān Jahān at Majhauli, he himself [Buhlūl] proceeded to Budāun

'Mijouli' in Dorn (I 54) There are several places which bear this name and it is not easy to decide, but this is, most probably, Salempur-

Majhauli, which lies on the left bank of the Little Gandak, about forty-five miles south-east of Gorakhpur. Lat. 26°-17′ N., Long. 83°-58′ E. (Th.). There are two contiguous villages which constitute one town. Majhauli which is Hindu, lies on the north bank of the river and Sālempur which is Muḥammadan, on the south bank. (Hunter, I. G. IX. 213). Constable, 28 D b.

V. 91, l. 6 from foot. He [Buhlūl] reigned during the space of thirty-eight years, eight months and eight days.

So also in the T. A. (159, l. 6), F. (I. 179, l. 2) and B. (I. 312=Tr. 410), but the calculation has not been worked out correctly. The Sultān ascended the throne, as they themselves state, on the 17th of Rab'i I. 855. If he reigned for 38 years, 8 months and 8 days after that date, he must have died on the 25th of Zī-l-q'ad 893 H. But all these four authors put his death into 894 and also state that Sikandar ascended the throne on the 17th of Sh'abān 894 H. There must be an error somewhere. If 894 H. is correct, one or other of the two statements—either the computation or the date of accession—must be wrong. In the C. H. I., the Sultān is said to have died in the second week of July 1489 at page 235 and on 17th July at p. 504. The latter date corresponds with 18th Sh'abān, 894 H. This would make the length of the reign 39 (lunar) years, 5 months and 1 day.

The name of the place where Buhlūl died is given as 'Balāwali' (T. A. 159, l. 6), 'Bhadāwali' (F. I. 179, l. 1), 'Malāwi' here and 'Malawali' in Dr. Lee's copy of the Makhzan. (Dorn, II. 95). Can it be 'Malāwan', a village very near Saket which is mentioned in the Post Office Guide? According to the T. A and F., 'Jalāli' in 'Alīgarh was the place where Sikandar met his father's coffin and was crowned, not where Buhlūl died. V. 93, l. 12. Mubārak Khān had fallen into Mullā Khān's hands.

The discritical point on the fourth letter is a copyist's blunder and the right reading is it, mallahān 'boatmen,' as in the T. A. (161, l. 3), from which Ni'amatulla has copied his account. Similarly, at page 99, l. 11 infra, 'Mihtar Mullā Khān' is an error for Mihtar-i-Mallāhān, 'Chief of the boatmen.' The fact that the man is there called 'Nāyak' (leader, chief) and said to have commanded or steered the Sultān's barge settles the point. Dorn also has read it wrongly. (I. 57).

V. 93, l. 14. Rái Bhid, Rājā of Panna, had carried him off a prisoner. Here again, 'Panna' is an error for 'Bhata'. Mubārak Khān had been captured at Jhūsi near Prayāg and the Rājā of Bhatā was the ruler of Arail, which lies, like Jhūsi, just opposite to Prayāg. There was no Rājā and no separate State, Kingdom or chiefship of Panna at this time. The State of Panna was founded by Hirde Sāh, the son of Rājā Chhatarsāl Bundela, after Chhatarsāl's death in 1731 A.C. Hirde Sāh had a short reign and died in 1738-9. (Irvine, Later Mughals, II. 241; I. G. s. n. Panna. See also my note on IV. 461, l. 16).

V. 95, l. 2. Sultan Sikandar then penetrated as far as Phāphūnd belonging to Panna.

in the T. A. (161, last line), شهديو in F. (I. 181, 1, 13)

and 'Behavand' in Dorn (I 58). In Dr. Lee's Ms. of the Makhzan-i-Afghāni, Rājā Bhīd is said to have fied to Sirguja and Sikandar to have advanced to 'Behavund,' a dependency of Bhattia (Dorn II 95) which may be an error by metathesis of the letters, for Bahandū' or Bandhū, i.e. Bandhūgarh (Lat 23°-41'N, Long. 81°-3' E.), which lies about 60 miles south of Rewā and was the name of the kingdom and also of the chief town of the Rājās of Bhata (I G. VI 358-9). The Tārīkh-i-Dāūdi states that the Rājā was the ruler of Bhata and that the fort to which Sikandar afterwards laid siege was that of "Bandhū, the strongest castle in that district." (E D IV 462-3). 'Abdulla has transcribed his account from the T. A., which is the original source of Ni'amatulla also, and this may indicate that in his copy of the T. A., the names were spelt as Bhata and Bandhū. Phāphūnd is neither in Panna nor in Bhata

Y. 97, 1 10 from foot. Sikandar himself marched on Friday, the 6th Ramazān, 906. upon Dhūlpūr.

The week day is given correctly. The Julian correspondence, 26th March 1501 A C., was a Friday

Y 98, 1 3. [He] encamped for two months on the banks of the Asi or Mendhi, where his people fell sick on account of the badness of the water.

This is the Asun or Ahsin, a small river which joins the Kuāri, which is itself a tributary of the Sindh or Betwā. The Asun rises in Lat 25°-29' N. Long 77°-38' E. It has a course of about 80 miles and is crossed by an easy ford on the road from Agra to Gwalior (Thornton). The T. A. reads the other name as 'Mendaki', which is said to mean in Sanskrit, 'frog haunted.' (B. Tr. I. 419 note)

V. 98, l. 17 He raised the standard of war for the reduction of the fort of Mandrail

Mandrail, also written Mandlaer, is now in Karauli State. It lies about 12 miles south-south-east of Karauli town. It is mentioned in the Ain (Tr. II 190) and was the chief town of a Sarkar in Suba Agra. It is the 'Mandrel' of the I. G. Atlas, 34 E 2 and Constable, 27 Cb.

V. 99, l. 13 That which is 'Agra', or 'in advance', is the preferable

Mr. H. G. Keene mentions (Guide to Agra, p. 1) another equally apocryphal and factitious derivation of the name of the town from "Agur, a salt pan, the soil being brackish and much salt having been made here in old times by evaporation" But if Agra was captured, as the contemporary poet Mas'ud-1-S'ad-1-Salman states, in the reign of Sultan Ibrahim of Ghazni about 1080 A C, all that is said here about it must be a fiction (See E. D IV 522). The Emperor Jahangir also quotes a couplet relating to Agra from the Qasida of this poet (T J. 2, 1.7 f f) But the place taken by Ibrahim was, perhaps, Agrowah 'J. (q v, I G V 91)

V. 99, 1 1 from foot. One of the able scholars of Hind has traced the date [of the great earthquake of 911 H] in the

word 'Kāzī.'

The point of this chronogram lies in the fact that one of the meanings of قاضي is 'deadly, fatal' and قاضي signifies 'death, fate, doom.' (Richardson). The week-day is stated to have been Sunday and the date 3rd Ṣafar, 911 H. The Julian correspondence 6th July, 1505 was a Sunday.

V. 100, l. 14. He was attacked by the Rājā of Gwālior in an ambuscade at Chatāwar, about ten Kos from that place.

'Chanāwar' in the T. A. (165, l. 5 f. f.) and 'Janwar' in F. (I. 183, last line). It is the 'Chatiāwar' of the Ain, (Tr. II. 187). It may be Jatwār or Jetwār, which lies north of Gwālior.

V. 103, l. 6 from foot. In 912 H......the Sultan went towards the fort of Awantgar.

This is the 'Untgar' of the \overline{Ain} (Tr. II, 190), where it is entered as a maḥāl in Sarkār Mandlāer and stated to have had a stone fort, below which flowed the river Chambal. It is called Utgīr, Ontgir, Untgir, Awantgarh, Hanwantgarh and Himmatgarh also. It is now in the State of Karāuli, 28 miles south-west of the town of Karāuli, at the southern mouth of the Paniar Pass, which is between Narwar and Gwālior. (Cunningham, Arch. Surv. Rep. II, 328-330). Lat. 26°-6′ N., Long. 77°-0′ E. It is shown as 'Utgarh' in the I. G. Atlas, Pl. 34 E 2.

V. 101, l. 23. [He ordered] that they should destroy the idol temples and raise mosques in their places.

The word employed here in the T. A. (166, 1.9 f. f.) is with and B. (I. 320, l. 14) and F. (I. 184, l. 13) have copied it. But the words used by all these authors in connection with the similar destruction of the temples of Mandrael are بينجانها و كنائس (T. A. 165, l. 8; B. I. 319, Tr. 420; F. I. 183, l. as 'fire-altars' in his Essay on کنائس as 'fire-altars' 'Fireworship in Upper India' and pressed this ambiguous reference into his service to support the theory that there were large colonies of fire-worshippers, i. e. Zoroastrians, in the Punjab so late as the 15th Christian century. (568 infra). But is loosely used for a Christian church, a Jewish synagogue and any pagan temple, and Richardson and the Ghiāsul-Lughat give all these meanings. It is inserted here only as a synonym of idol house'. کنائس is used for Hindu temples by Muḥammad Sāqi بتخانه in his account of the destruction of the Hindu temples of Haidarabad and Parli by Aurangzīb. (Maāsir-i-'Ālamgīrī, 285, l. 14; 428, l. 4). Biladuri uses the word for 'churches' and 'synagogues'. He speaks of the churches of the Nazarenes " كنائس النصارى والبهود و يوت نيران مجوس and the Jews and the fire-temples of the Magians." (Reinaud, Fragments Arabes et Persans, 171, l. 10). Ranking in his translation of B. states that Sikandar" destroyed all the idol temples and churches of the place" (Tr. I, 420), but churches cannot be right.

V. 102, l. 15. Sultān Sikandar's proceedings at Hatkānt, Lucknow, Nāgor and Lesi-Sheopūr.

'Lesi-Sheopūr' must be an error for 'Sūi-Sūpūr,' and so it is written m the T A (Text, 169, 1 12 and also at 104 infra) 'Sūi-Sūpūr' is again mentioned at 385 infra B writes the name as 'Sui Supar' (I 821, 1.4 f.f =Tr. I 454) and F's spelling is -e section [Sivpur] (I 186, 1 5) It must be 'Sheopur' on the western boundary of Gwalior State, towards the Jaipur territory I G Atlas, 38 B 2 Lat. 25°-38' N, Long 76°-48' E Lahair is Lahar (1 17) in Gwalior State, six miles east of the right bank of the Sindh It is about 50 miles west of Kālpi, 85 miles south-east of Agra and 50 east of Gwalior Lat 26°-12' N, Long 78°-59' E (Th) Constable, 27 D b Sheopur is stated at 104 infra to have been not very far from Awantgarh, which is in Lat. 26°-6' N, Long. 77°-0' E Sheopur was a small Rajput principality upto 1816 A.C. when it was absorbed by Daulat Rão Sindiā. (Th. 885)

V. 103. Footnote [Sultan Ibrahim] appointed Shaikhzada Manjhur to the government of Chanders and gave the office of veshwā to Sultān Muhammad, grandson of the King of Mālənā

in F (I. 189, last line), but مجهو in the T. A. (176, 1 16) and 'Munjoo' in Dorn (I. 73). The correct form is Manjhū Manjhū, literally signifies "middle" and is generally given to a son who is neither the youngest nor the eldest in the family. Thus the renowned Gujarat saint, Shah 'Alam, who was the eleventh of twelve male children, was familiarly known as Miyan Manjhu or Miyan Manjhla (Mirat-i-Sikandari, Tr Bayley, 138 Note) The father of the author of the Mirāt-i-Sikandarī was known as Shaikh Manjhū (Bayley, Ibid, 59, 454) The second son of Sultan Nasıru-d-din Khaljı also was known as Mıyan Manjhla إيسر ميادكي (T A. 571, l 1, F II 260, l 5 ff.) Nı'amatulla has borrowed the whole sentence from the T A and Dorn's rendering of it is undoubtedly wrong, but Sir Henry Elliot's is almost equally exceptionable, as it implies that Sultān Muḥammad was the Peshwā and Shaikhzāda Manjhū the governor. شبخراده This is putting the wrong side foremost What the T A. says is متحهورا بتحافظت وحراست قلعة چند بري ويبشوا ثمي شاهراده محمد خان بواسه سلطان بايبر الدبي He entrusted to the Sharkh-zada Manzhu the watch and " . مالوى تىن مرود ward of the castle of Chanders and the Peshwaship of the Prince Muhammad Khan, grandson of Sultan Nasıru-d-din of Malwa" F states that of the fort and the Wakalat of حراست Machhū' was given the wardenship حراست the Prince It is clear that Manjhu was the Peshwa, i e the executive authority de facto, the Prince being only a puppet, figure-head or fainéant The word Peshwa is used here in the same sense as is and are used by Baihaqi and as اتالق (let little father) is by the Timuride historians, for the guardian, protector, adviser or administrator on behalf of a prince, who on account of his youth, incapacity, or for some other reason is unable or forbidden to manage his own affairs F.'s statement that Manjhū was the Wakil, t e. deputy, regent or representative of the Prince leaves no doubt that it was he who was the Peshwa Elsewhere,

the T. A. says that Fath Khān the son of 'Azam Humāyūn Shirwāni was appointed as the Wākil and Peshica of the Prince Jalāl Khān, brother of Ibrāhīm Lody. (173, l. 3 f. f.).

This usage is of ancient standing. Barani deplores the circumstance that a wretch like Kāfūr became 'Lia' 'Peshwā of the Kingdom' and all-powerful minister during the last five years of 'Alāu-d-dīn's reign. (Text, 337, l. 12). Perhaps the error is only clerical or typographical and what Sir Henry wrote was "He gave him [Manjhū] the office of Peshwā to Sultān Muḥammad." The insertion of the pronoun will set it right.

V. 109, l. 15. The tribe of Sarwanis, who are no better than sellers of dogs.

This epithet of revilement is founded on a pun on the tribal designation. The 'Sarbanis' or 'Sarbānis' are so called after their ancestor, Sarban. The original phrase is given in the T. A. 241, as —— Sarbāni-i-Sagbāni, a vituperative jingle formed by altering only a single letter. Captain Wood says that the Uzbegs as well as the Afghāns "dread above every other opprobrious stigma the epithet of dog-seller.' (Journey to the Source of the Oxus, Ed. 1841, p. 291).

V. 112, l. 10. Nearly all were slain with the exception of a very small number of Kipchi horsemen.

The right reading may be 'Qipchaqi' or 'Qipchāqi'. But it is more probably 'Tipchāqi' or 'Tupchāqi', as at 134 infra. Asp-i-Tipchāq is generally used, says Mrs. Beveridge, for "well-trained horses of good breed, fine cavalry mounts. 'Tip' is said to mean 'movement' and Erskine thinks that the horses are so called because they are taught special paces. But other meanings are also assigned to the word, viz. good roadsters or round bodied or swift horses." (B. N. Tr. 38 note). Jauhar says that "the peculiar quality or virtue of all Tipuchāk horses" is that even when severely wounded or hamstrung, they bring the rider safe to the camp, although they afterwards die, and he tells a story in illustration of it. (Memoirs, Tr. Stewart, Ed. 1832, p. 4).

V. 113, l. 19. He sent Khwāja Mu'azzamto rescue Begam Mariam Makāni from her dangerous position.

All this is inaccurate and muddled. Khwāja Mu'azzam was the half-brother of Ḥamīda Bānū or Miriam Makāni—the mother of Akbar—but she had not become Humāyūn's wife at all at this time. She was married to him only in 948 H.—some two years after the battle of Chausa. The lady captured was Bega (or Beka) Begam, afterwards known as Ḥājji Begam. Khwāja Mu'azzam was not in the Emperor's service at this time, nor did he "sacrifice his life" on the occasion. He lived long afterwards, went mad and was imprisoned by Akbar's commands. The men who were killed at this time were Bābā Jalāir and Tardi Beg Kūch Beg. (A. N. I. 159, Tr. 343; 203 infra note). The man who helped Humāyūn at Chausa was the water-carrier Nizām, not Shamsu-d-dīn Muḥammad Ghaznavi, as here stated. The latter came to the Emperor's rescue after

the rout at Qanauj in the year following.

V 118, l 4 from foot. Auspicious omens

This story is told with variations relating to time as well as place and the order in which the three men were accosted, by later writers The T A puts the event into 961 H, which is demonstrably wrong, as Khwāndamīr who relates it here died in 942 H. during Humāyuu's return march from Gujarāt (F I 215, l. 3 ff) The order of the names in Nizāmu d-dīn's account is Daulat, Murād and S'adat, not Murād, Daulat and S'adat as in the text F's version is a meie repetition of Nizāmu-d-dīn's with all his errors (I 241, l 2 f f) Abul Fazl closely follows the Humāyūn Nāma of Khwāndamīr. (A N I 357. Tr L 642) Sir Wolseley Haig has been misguided, as usual, by F. (C. H I IV 66)

V. 123, l 6 According to the different standards of gold, the ranks of all the people were divided into twelve orders or arrows

Khwāndamīr is referring to the 'Bārahbāni' standard of assaying gold, which Abul Fazl explains thus. "The highest degree of purity (for gold) is called in Persia 'dahdahī' (i. e ten out of ten), but they do not know over ten degrees of fineness, in India, it is called bārahbāni, as they have twelve degrees Formerly, the $H\bar{u}n$ which is a gold coin current in the Deccan was thought to be pure and reckoned at ten degrees, but His Majesty has now fixed it as $8\frac{1}{2}$, and the round, small gold dinār of 'Alāu-d-dīn which was considered to be twelve degrees now turns out to be ten and a half" ($A\bar{i}n$, Tr I 18) Abul Fazl means that the standard of purity had been considerably raised by Akbar and the metal refined more thoroughly.

V. 124, l 4. The Sharbat-Khāna, Sūji-Khāna, the digging of canals etc. were comprised in the Abi department

Read 'Sūchikhāna', the Turki synonym for "Ābdār Khāna," Water Department'. The Sūchi was the officer in charge of the water specially reserved for the use of the sovereign (B N Tr 835 and 551) The Sūchi was sometimes called 'Sharbatdār' or 'Sharbatchi' and both these terms are also employed at times as euphemistical periphrases for the Keeper of the royal Winecellar (or 'Sharābdār)' Abul Fazl, however, draws a distinction between the 'Sūchi-khānā' and the 'Sharbat-khāna' (A. N. I. 860, Tr I 647, III 251—Tr 363).

N 124, l 2 from foot Khawarnag and Sawir, the palaces of Bahram.

Khaucarnaq أحدى and Sidir المدر [not Sawīr] were the names given to the palaces built by N'umān Ibn Mundhir for Bahrāmgor. They are described in Nizāmi's Masnavi, called the 'Haft Paikar' (Khamsah, Bombay Lith 1260 H. Part IV, p 14). They lay two or three miles to the east of Najaf 'Khawarnak' is derived by Doctor Andreas from the Avestan Huvarna, "with a beautiful roof" and by Vullers from Khāwārnai, "Place of Feasting". 'Sadīr' is said to be a corruption of "Ukhaidīr." (Houtsma, II, 932, Lestrange, L E. C. 75).

V. 133, l. 10. The carriages (gardūn) and mortars (deg) and small guns (topakchiyān) were placed in the centre.

The true meaning of 'topakchiyān' must be not 'small guns,' but 'matchlock-men' or 'musketeers', or gunners, who are said only a few lines higher up (132 supra) to have numbered 5000. The forms, 'Topehi' and 'Tufangdār' occur in 'Abbās (E. D. IV. 416) and Mushtāqi (Ib. 551). 'Tupak' is a diminutive of 'Tūp' and 'Tufang' is a secondary form of 'Tūpak', the 'p' having been changed into 'f' as usual in Arabic.

V. 138, l. 3. Jauhar was appointed collector of the village of Haibatpur.

There are several places called Haibatpūr, but there can be little doubt that this is Haibatpur-Patti, 27 miles north-east of Kasūr and ten miles west of the Biyās. Constable, 25 Ab. "The antiquity of the town," writes Cunningham, "is proved by the number of burnt bricks and old wells which lie about the town. The old dry wells were noted more than three hundred years ago by Jauhar and the profusion of bricks struck Burnes, (Punjab and Bokhara, II. 9)." (A. G. I. 201).

Dowson has reproduced here the translation of Major Stewart, but it is not very reliable. Mr. Erskine has some very hard things to say about it in an annotated copy which is in the British Museum. "It is", he remarks, "no translation at all. It is full of errors. It adds, takes away, alters. It is not trustworthy and one does him no injustice in pronouncing him ignorant of the history of the manners of the times, ignorant of the geography of the country, ignorant of the language, ignorant of the duty of a translator." (Rieu, Catalogue, I. 246).

V. 139, l. 14. He [Rūmi Khān] had a slave named Khalāfat.......whom he so flogged that the weals were visible upon his body.

Neither Abu-l-Fazl nor any of the other chroniclers makes any reference to this ruse, and stories of such pretended quarrel and desertion in consequence of ill-treatment are only too common. The oldest example is the Zopyrus tale in Herodotus. (III. 154-8). Sextus Tarquinius is said to have got into Gabii by a similar device (Livy, I. 53) and Julian is credited with the employment of an identical stratagem during his Persian campaign. Alberuni has an analogue in connection with Kanik or Kanishka. (Sachau's Tr. II, 11; E. D. II, 11) and this is also found in 'Awfi's storehouse of bistorical and unhistorical anecdotes. (E. D. II. 170). Abul Fazl speaks of Kāmrān having availed himself of the trick to seize Lahore soon after the accession of Humayun. (A. N. I. 125; Tr. I. 290). Tavernier was told that Daulatābād had been taken by Shāh Jahān only after such a device had been employed (Travels, Tr. Ball. I. 143) and Nizāmu-l-Mulk Aşaf Jāh is said to have practised it in his contest with 'Alam 'Ali Khan for the supremacy of the Dekkan in 1720 A. C. (Irvine, A. I. M. 255). Jauhar may have lent too easy credence to some popular rumour and the tale is, most probably, apocryphal.

V. 141, l. 18. Defeat of Humāyūn at Chūpa-ghāt.

This heading is not in Stewart, and the place-name 'Chūpa' does

not occur anywhere in his version. Dorn calls the village 'Shûya' (I. p. 118) and the Makhzan reads the name as 'Shataya' (E. D IV. 370 note), but no such place as 'Chūpa', 'Shūya' or 'Shataya' can be now traced on the maps. The exact date of the battle is given only by Abul Fazl. It was 9th Safar, 946 H. te 26th June 1539 A. C (A N I 159—Tr. 344) Mr Beveridge gives 7th June, but it must be an inadvertent error or misprint for 27th, which is the date given by Erskine (H. B. H. II 173)

V 144, l 16 At length, some of the Camp colour-men who were on the look-out for him tied their turbans together

This is Stewart's rendering of the word used, and Dowson finds fault with it on the ground that 'Tüghbānān' means 'nobles of the Tūgh banner' But this cannot be correct, as Shamsu-d-dīn Muhammad Ghaznavi—the man who is referred to—was not a noble at all at this time, but a common soldier of no note in Kāmrān's service He owed his subsequent rise in fact to the service rendered by him on this occasion. Abul Fazl in speaking of the event says 'One of the soldiers [...] who had been saved from out of the whirlpool came there and seizing His Majesty's sacred hand, drew him up" (A N Tr I 854—Text, I, 166, I 17) Compare also the TA, 205 infra).

V 145, l 3 Battle of Kipchāk

The darra or pass of Qibchāq is also called 'Chārdār' or 'Chihārdār' and lies south-east of the "Dandānshikan Pass" (Erskine, Memoirs of Bābur, 139 note) The Chahārdār and Dandānshikān Passes are both shown in Constable, Pl 22 C c and 22 B c The Chārdār Pass is also maiked on Yule's Map to Wood's Journey to the Source of the Oxus and in the I G Atlas, 47 E 3

V. 146, l. 21 From Parwan we proceeded to Kahamrud

Kahmai d lies north-west of Kābul in a valley not far from the Dandānshikān Pass (Erskine, Memoirs of Bābur, 199 note; *Ibid*, H B H II. 384) Kahmard is marked on Holdich's Map to the Gates of India Parwān lies eight miles north of Chārikār Kahmard is 5600 feet above sea-level (Wood, Journey, Ed Yule, 132)

V. 165, l 8 from foot. [Murzzu-d-din Muhammad Sām] marched from Peshāwar on Thursday, the 25th of the said month [Rab'i I, 602 H].

This date is given only in the Tāi īkh-i-Alfi As the Julian correspondence of the Hisābi date, 9th November 1205 A. C was a Wednesday, the 25th must be the Rūyyat or Hilāli date

V 166, l 2 from foot The fort of Kālwar [was taken by 'Alāw-d-dīn].

This 'Kālwar' [Kālor or Gālor] is really Jālor The real name of the Rājā was neither 'Kathar Deo' nor 'Nahr Deo', but 'Kanhar Deva' or 'Kānhad Deva' He was a Chauhān of the Sonigara branch of that tribe. 'Kānhad' is one of the vernacular forms of 'Krishna' The compiler of the Tārīkh i-Alfi may have heard this story of Gulbihisht from some Rājput berd or Bhāt in attendance on Akhar. F. has copied it from the Alfi (I.

118, l. 4 f. f.) and Hājji Dabīr has also got it. (Z. W. 788, l. 21). It is not quite correct to say (as in the Footnote) that "Barani does not record these events." He does mention Siwāna as well as Jālor in the list of 'Alāu-d-dīn's conquests which is given in the T. F. (323, l. 14).

V. 175, l. 6. The place was held by Râi Surjan who had bought it of Hijjāz Khān, a servant of Salīm Khān (Islām Shāh).

B. calls the slave or servant Sangrām. (II. 31, l. 7; Tr. 25). Abul Fazl speaks of him as Jajhār Khān (A. N. II. 87=Tr. 133), and Nizāmu-d-dīn as Ḥājji Khān. (260 infra).

V. 178, l. 17. Khwāja Muqīm Harawi.....was raised to the office of diwān of the household [of Bābur].

Here Nizāmu-d-dīn Aḥmad's father is said to have been "Diwān-i-Buyūtāt" under Bābur. Dowson renders the phrase as above. Mr. Beveridge translates "Mīr-i-Buyūtāt" as 'Barrack-master' at A. N. Tr. I. 496, but at page 638 of the same volume, his rendering of the identical expression is 'Officer in charge of buildings', while it is 'Master of Works' and 'Director of Buildings' in his Translation of the T. J. (I. 22, 45 and II. 61). Mr. Irvine, whose opinion on all such questions is worthy of respect states that the "Buyūtāti belonged to the Khān Sāmān's or Lord Steward's Department, had charge of the Crown buildings and Government town lands (Nazūl),....., kept the Lord Steward's account, took possession of confiscated property and escheats and was collector of the Jizya or polltax." (J. R. A. S. 1910, p. 950).

V. 179, l. 7 from foot. He [Niṣāmu-d-dîn] accomplished 1200 miles by forced marches. The Waki'āt-i-Mushtāki says that the party completed the distance of 600 Kos in twelves days, i. e. at the rate of 100 miles a day.

The Kos meant is not the pucca kos of two miles, but the short one of 1½ miles. Nizāmu-d-dīn's march was from Aḥmadābād to Lāhore. The distance between these two places by the not very direct Rājputāna Railway route is about 850 miles. Dehli is about 550 miles by rail from Aḥmadābād and Lāhore is about 300 miles from Dehli. An average of seventy miles a day for picked camels would not be very extraordinary. Lāhore is in Lat. 31°-33′ N., Long. 74°-16′ E. Aḥmadābād in Lat. 23°5′ N., Long. 72°-35′ E., which is a map distance of about 630 miles only and a road distance of about 840.

V. 180, l. 19. ['Ābid Khān] went before Jahāngīr only in two sheets, one wrapped round his waist and the other round his head, as if prepared for burial, accompanied by several Tākiya Mughals.

"He withdrew from worldly affairs and presented himself at the Court of Jahangir, with a body of Mughals, wearing only a cap [الحالف] on the head and with a shroud [wrapped round the body, instead of a turban and the customary garments]." The Taqia was a skull-cap worn under or in stead of the turban and the purpose of donning this extraordinary garb was to proclaim his state of utter despair and determination to die rather than submit to such injustice or indignity. This appears to have been a not uncommon practice and we are told elsewhere in the Maäsir and by 'Abid Khan's father Nizamu-d-din Ahmad also, that during the Bengal discontents in 989 H, the followers of Bābā Khān Qāqshāl shaved off the hair of their heads, put on 'high [Mughal] caps' and roamed about the city of Gaur (M. U. I 892, 18, T. A 854, 1.7=415 infra and note, B II 280, last line, Tr. Lowe, II. 288), vide also my note on Vol. III. 285, 1 16)

V 180, l. 4 from foot Muhammad Sharīf [the son-in-law of 'Abid Khān] was afterwards appointed hājīb (chamberlam) of Haidarābād

'Hājib' has many meanings and it is used here not for a 'Chamberlain', but for a confidential agent, envoy, diplomatic representative or minister resident at the Court of a feudatory or independent prince. The 'strong fortress' of which Muhammad Sharif was appointed governor was that of Anki-Tanki (M U I. 664, 15).

V 186, l 18 The breadth of Hindustan from Kashmir to the hills of Barujh (Bioach) is 800 Kos Ilāhi, the breadth from the hills of Kamāun to the borders of the Dekhin amounts to 1000 Ilāhi Kos Its length from Hindu Koh to. Orissa, from west to east, is 1680 kos. At the present time, Hindustān contains 3200 towns, and upon each town there are dependent 200, 500, 1000 or 1500 villages. The whole yields a revenue of 640 Krors. ... Murādi tankas

Here 'breadth' is used for what we call 'length' and vice versa, The figures are themselves gratuitous conjectures and of little or no scientific value. The Ilāhi Kos of 5000 gaz of 41 fingers each has been reckoned at about $2\frac{1}{2}$ miles (Elliot, Races, II 177-8, 194, Yule, Hob Job s v) 800 Ilāhi Kos would be therefore equal to, at least, 2000 miles, 1000 Ilāhi kos to 2500 miles and 1680 legal kos to, at least, 2100 miles. The exaggeration here is obvious, when it is remembered that the total length of India (from Peshāwar to Cape Comorin) is only 1900 miles and the maximum breadth about 1500 miles.

The number of villages is also absurdly over-estimated Each town is said to have had 100, 500, 1000 or 1500 villages dependent upon it. Even if we take the second of these figures as the mean and leave out the drop-sical number 1500, (as it does not occur on some manuscripts), the average total for Akbar's Empire would be 1,600,000 This is incredible, as the

TABAQAT-I-AKBARI aggregate number of villages in the whole of the Indian sub-continent is only about 730,000. It should be also remembered that only a very small V. 193, 1, 13. part of Southern India was included in Akbar's Empire.

For the meaning of Muradi tanga, see my article in Num. Supp. No.

V. 187, 1 11 from foot. Several of the nobles took part with Mahdi XXVII to the J. A. S. B. (1917), pp. 80-97.

نان بسلام مهدى خواجه رفتاد (193, 1.9 f.f.). "They all went to the Salām i. e. the levee or Court of Mahdi Khwaja [with the object of paying their homage to him]." Abul Fazl says that Mir Khalifa forbade the Khwaja to appear at the Darbar and also prohibited every one from visiting him. (A. N. I. 117=Tr. I. 277). Mahdi Khwaja was not, as Dowson says, the sonin-law of Babur, but his brother-in-law, the husband of his eldest sister, Khānzīda Begam. The word also is used ambiguously for both these relationships. (See A.N. Tr. I. Additional Notes, p. xii and II. 163 Note). V. 187, last line. The Mahdi was considered to be a man of suspicious

بنا به جنون منسوب بود (193, l. 4 f. f.) which means that a suspicion of insanity attached to him. People suspected him of not being quite in his

V. 188, l. 5. 'O Tajik, the red tongue uses its sharp point to no purpose.' رون برت مرسبز مبد هد بياد (193, l. 2 f. f.). "The red tongue gives the green head to the winds." A foolish speech or indiscreet wagging of the tongue results in the ruin of the green-horn who is guilty of it. This proverbial expression occurs also in the T.J. (Text, 826, 1. 20; Tr. II. 287). It is an allusion to the fate of the parrot in the Tutinama of Nakshabi, a collection of Oriental tales and apologues, founded on the Sanskrit Shuka Saptati, 'The Seventy Tales of a Parrot'. Mahdi Khwaja warned Nizāmu-d-din's father that if he blabbed or repeated what he had heard

V. 192, 1. 4. The imperfectly armed Gujaratis, through fear of the by chance, his head would not stand on his shoulders. arrows, dared not venture far from the camp.

The Gujarātis were not imperfectly كجراتيان كوتاه سلاح armed. They were armed with swords and daggers, which cannot do any execution from a distance and are of use only in a close combat or hand to hand fight. They were not expert archers or matchlockmen like the Mughals. The Persian List correspond, says Mr. Irvine, " to the French 'armes blanche', which include swords, shields, battle-axes, spears and daggers." (Army of the Indian Mughals, 79). He cites the saying, The sword is better than the dagger, the spear better than the sword, and the bow and arrow better than the spear. (Ibid, 90).

"Sungar" (1. 5 f.f.) is correctly 'Songadh,' Golden Fort'. (Mirat-i-

V. 193, 1.13. A person came forward in a friendly way and nave information (of the intended nocturnal attack).

(197, 1 3). 'A person took his station شعصى ارقم داد خواهال الرسر راه آمده on the road [along which the Emperor was passing], like one sting for nustice' The writer is alluding to elected, the custom of Crying Dohāi' or proclaiming one's grievance publicly and vociferously demanding its redress-' Complaint by Outcry,'-as it is called by the old English travellers in India (Hobson Jobson, s. v. Doai). It is stated by a panegyrist of Sikandar Lody that "if any one who had been oppressed demanded justice when he was out riding, he immediately demanded who the petitioner was, on which the officials in attendance would take him by the hand and do their best to give him satisfaction" (Tārīkh 1-Dāūdi in E. D. IV 448) 'Abbās Khān also states that when Shir Shāh was besieging Rāisin, "the widows of the chief men of Chanderi waited for him on the roadside, and cried out for justice" against Puran Mal, who had "slain their husbands and enslaved their daughters", threatening to "accuse him hereafter on the Day of Resurrection, if he did not redress their wrongs". (Tärīkh 1-Shīr Shāhi, Ibid. 401-2)

Abul Fazl's account is that the person who sought redress, was an old woman whose son had been taken prisoner and she gave the information in the hope of obtaining his release (A. N. I. 136—Tr. I. 309) and Gulbadan also calls her ects. 'a woman'. (H. N. 39—Tr. 132)

V. 194, l 7 from foot [Humāyūn] repaired with 600 men to this place [Chāmpāner]

V 197, l 13 Ghazanfar who was one of his ['Askari's] companions and foster-brother of Kāsim Khān

'According to the text (198, l. 2 f.f.), he was the foster-brother of the Mirzā ('Askarı), himself and the real brother of Mahdı Qāsım Khān, which is correct See also B II 125, l=129, Āin, Tr I. 320 note. Abu-l-Fazl says Ghazanfar was a servant of Mirzā Yādgār Nāsır and deserted with 300 horse to Bahādur. (A N. I 143, Tr 320). Dowson renders the words which Ghazanfar uttered sotto voce, as "So thou art, but not for thyself" But in the Text, they are given as مستى اما خويش بستى اما خويش

V 198, l 19 Mirzā 'Askarı made a show of fighting

which is being slaughtered, made some desperate and unavailing efforts or convulsive movements like those of an animal under the knife of the butcher." The phrase is used in this sense in the Maāsir-i-ʿAlamgīri (Text, 268,12 ff, 299, 13f, f) Mr. Irvine says it is used for a feeble and

purposeless attack or defence which is not carried home. (A. I. M. 239).

But before Mirzā 'Askari retreated from Ahmadābād. V. 198, l. 25. the newswriters and reporters had communicated to the Emperor [information about 'Askari's hostile designs].

The words in the text are سخن سازان و واقع طلبان (199, 1, 16).

A مخن ساز according to Richardson, is "a person who makes his words suit his purpose, a deceiver, cheat or knave." The author means that they were backbiters and calumniators. واقع طلبان are not 'reporters', but persons who are waiting or watching for an opportunity of making mischief, strife-mongers, seekers of occasions for creating dissensions, adventurers who find their cue in fishing in troubled waters. The word for reporter' is واأم نويس. Nizāmu-d-dīn writes as a partisan of 'Askari. His father had been 'Askari's Vazīr.

It is said that Kalan Beg had built for himself a Chinese V. 199, l. 5. house of great elegance.

ود (199, l. 6 f. f.). Dowson suggests that this 'Chinese house' was so called because it was built of enamelled tiles. (VIII. xxvii). But it was, more probably, a fine collection of old porcelain vases, jars, etc. The taste for collecting these works of art is of very long two hundred " دويست عد د چيني ننغو ري " two hundred vessels of Old Chinese and Faghfuri porcelain" were among the presents sent by Sultan Mas'ud of Ghazna to the Khalif. (Text, 516, last line). Barbosa says of the wealthy Moor merchants of Reynel, [Rander near Surat], that in their "well-kept and well-furnished" houses, they have many shelves, all round the front room, which are "filled with fair and rich porcelain of new styles". (Tr. Dames. I. 147-8). Jahangir also frequently uses for Chinaware or Chinese porcelain. (T. J. Text. 100, l. 3 f.f.; 158, l. 17; 187, l. 7 f. f.). We are told in the Maāsir-i-'Alamgīri also that in 1088 H., Muhsin Khan was appointed 'Darogha' or Curator of the Chini Khana, i. e. of the Imperial Collection of China which successive Great Mughals had assiduously brought together.

V. 199, l. 14. When Sultan Bahadur was defeated, he sent away Muhammad Zamān Mīrzā to Hind, in order that there might be no difficulty about him.

But what the text says is كرنه خلل الدازد (199, last line), " that having gone there (to Hindustan), he might throw affairs into confusion or create disturbances". And this must be the real meaning, as we are told immediately below, that he actually did so and attempted to seize Lahor in Kāmrān's absence (cf. also B. I. 348; Tr. 456). Dowson seems to have read instead of اندازد. Abu-l-Fazl says that Muhammad Zamān " went to Lahor to stir up a commotion there." (A. N. I. 132-Tr. 303).

V. 199, l. 7 from foot. The Emperor [Humāyūn] marched against him [Shir Khan] on the 14th Safar 942 H.

The year is wrongly stated. It was 944 H. (F. I. 216, 1. 20). The siege of Chunar began very soon after Humayun's arrival there on the 14th Sh'aban 944 (See note on Vol V, 1 139 ante) Humayun took Champaner on 9th Şafar 942 H. (See note on V 194, 1 7 ante)

V. 201, l. 6 from foot The Emperor [Humāyūn] changed the name of the city of Gaur to Jannatābād.

All the Timurian chroniclers make this statement and Prof. Qānungo repeats it (Sher Shāh, 178), but it does not appear to be correct, as the name, Jannatābād appears on the coins of Sultān Ghīyāsu-d-din 'Azam Shāh of Bengal, who ruled from 792 to 799 H (1389-1396 A C) (H N Wright, I M C. II p 156; Thomas, C P K D 153) But it may be said that neither Humāyūn, who ordered Gaur to be called Jannatābād, nor any of his historians knew or could have known anything about the coins of 'Azam Shāh or the new name which he had given to his capital Firishta states that Humāyūn altered the name 'given to his capital Firishta states that Humāyūn altered the name 'given', because 'Gaur' means 'grave' and had unpleasant or ill-omened associations with death and burial (I 217, I 7) But this explanation is not found anywhere else and seems to be a gloss or conjecture of his own The real explanation is that he liked the climate so much that he gave himself up to pleasure and dissipation and thought it was a 'paradise' (Jauhar, Tr. p 13, A. N I 753—Tr 335)

V 201, last line He [Hindal] killed Shaikh Bahlol, one of the great Shaikhs of the time and lear ned in theology

(Text, 200, last line) "Who was one of the great Shakhs of his time and distinguished for his knowledge of [the thaumaturgical science which is founded on] the invocation of the [mysterious] Names of the Supreme Being."

Herklots says of this art that it enables one to command the presence of genie and demons, to cast out evil spirits, to cause the death of an enemy, to obtain victory in battle etc. He devotes to its exposition four chapters, which fill fifty-three pages in the translation of the 'Qanoon-i-Islam,' Second Edition, 201-253, Ed. Crooke, 218-273. See also B. (I. 338, 392), who uses the same phrase, which Ranking renders as 'Invocation of the mighty names' (Tr. 445, 459 Notes and 504). Mirzā Haidar observes that this 'Shaikh Pūl', as he calls him, taught Humāyūn to look upon incantations and sorcery as the surest means of attaining his objects. He deplores the fact that Humāyūn who had a passion for magic and conjuration had become his disciple (Tārīkh-i-Rashīdi Tr. 399). Abu-l-Fazi also states that the Shaikh was held in reverence by Humāyūn, only because the latter was inclined towards magic (A. N. II. 89, Tr. 135).

The name of the Shaikh is written as 'Phūl' also, but B (I 350, Tr I. 459) and Abu-l-Fazl (A. N I 154-5=Tr L 337-8) call him 'Buhlūl.' Erskine speaks of him as 'Bhūl' or 'Buhlūl' (H B H, II 162) He was the elder brother of Shaikh Muhammad Ghaus and claimed to be a descendant of Shaikh Farīdu-d-dîn 'Attār. His tomb is at Bayāna. (Beale, Oriental Biographical Dictionary, Ed 1894, p. 265). The date given for the event, 943-H. on l. 3 f. f., is wrong. It should be 945.

V. 205, l. 20. I was in hopes he had perished, but he has got off.

This is not a translation, but a loose paraphrase. What Shāh said was عند الما يردشد (202, 1.5 f.f.). "Our object was Checkmate, but it has turned out to be only a stalemate." It is stated in the Ghiyāṣu-l-lughāt that when a player at chess loses all his pieces except the King, it is called عند or half a checkmate.

V. 205, footnote 3. His [Mirzā Haidar's] advice was that the princes should occupy and fortify the hills between Sirhind and Sārang, while he subdued Kashmir (Akbar Nāma, I, p. 205).

Abu-l-Fazl's 'Sārang' is the name of a person, not of a place. Mirzā Ḥaidar Dughlāt himself explains that 'Sīrang' was "one of the Sultāns of the slopes of the hills (﴿ ﴿ ﴿ ﴿ ﴿ ﴾ ﴾) of Hind" (T. R. Tr. 483), and the editor rightly suggests that the reference is to Sultān Sārang Gakkhar. (Ib. 479-80 Note). See also A. N. (Tr. I. 357 Note) and 278 infra. Sultān Sārang Gakkhar is mentioned by Nizāmu-d-dīn. (279 infra). He and Ni'amatulla say that Sārang was flayed alive by Shīr Shāh. (114 ante). The Tārīkh-i-Dāūdi (E. D. IV. 493) ascribes that act of barbarity to Islām Shāh.

V. 206, l. 5 from foot. Mirzā 'Askari then crossed the Sind and went to the town of Pātar.

"Pāt" or "Pātar" was the most productive Maḥāl in Sarkār Siwistān (Sehwān) in the days of Akbar. (Āīn, Tr. II. 340). It is said here to have been 50 kos from Lühari (Rohri). It is now called 'Old Pāt' or 'Pāt-i-Kuhna' and is a ruined village in the Kākar pargana of Lārkhana district, (Haig. I.D.C: 91), about forty miles north of Sehwān, and ten kos, that is, fifteen or twenty miles; west of the Indus. (Humāyūn Nāma, Tr. 149 Note).

V. 207, l. 19. The Emperor now forbade him [Hindâl] to go to Kandaliär and directed him to return to Luhari.

و آن حضرت مرزا هندال را از رفتن قندهار منع فرموده دیگر بار بقصبه لهری رفتند (203, 1.3 f. f.). "And His Majesty [Humāyūn] having forbidden Mīrza Hindāl to go to Qandahār, himself went for the second time to the town of Luhari." Abu-l-Fazl tells us that some time after the marriage, "the territory of Bhakkar (i. e. Rohri) was the place of residence" of the Emperor and Ḥamīda Bānū Begam. (I. 174=Tr. I. 364). It was Humāyūn himself who returned to Luhri, not his brother.

V. 211, footnote. Removing from thence....., he proceeded by Divariant and Wasilpur.....thence to Pahlūdi.....and afterwards made three more marches to the tank of Jūki.

"Diwarawal" is the 'Derawal', "Wasilpur" the 'Birsilpur' and "Pahlūdi" the 'Phalodi' of Constable's Atlas, Pl. 26, 27. They are all mentioned also in the Ain, (Tr. II. 278, 277, 276). 'Derawal' is wrongly written there as 'Dewadar'. The 'Tank of Jūki' is called in the Ain text. It means 'pool, pond or lake of the Jogi' and is now known as

'Jogi Talão'.

V 214, l. 19. The Emperor under spiritual guidance, gave to the child the name of Jalālu-d-dīn Muhammad Akbar.

Nizāmu-d-dīn is referring to a dream of Humāyūn's, in which he is said to have been commanded by the Shaikh Aḥmad-i-Jām Zhanda Pīl or a Voice from the Spiritual World to give the prince about to be born the name of Jalālu-d-dīn He refers to the matter again at p. 408 infra, q. v Note The story is told by Humāyūn's sister, the Princess Gulbadan also. (Humāyūn Nāma, Text 45, Tr 145). According to her, Humāyūn saw this vision or dreamt the dream at Lāhor and after the defeat at Qanauj. (Ibid, 58, Tr.158). Abu-l-Fazl also tells the tale and gives the precise date of the vision as 4th Rab'i I 947 H (A. N I 13, Tr I. 42) 'Ārif Qandahāri, another contemporary writer, whose work has not been published, also tells the story and gives the same date (A N. Tr. I. Errata and Addenda, p 111). The battle near Qanauj took place on 10th Muharram 947 H and Humāyūn and his brothers and amīr's met in council at Lāhor on the 1st of Rab'ī I (A N I 168=Tr 356). Shaikh Ahmad-i-Jām was the ancestor of Akbar's mother, Hamīdā Bānū

V. 215, l 9. The perfidious Mirzā 'Askarı sent forward Hawali Uzbek to watch his movements.

The name of this man is written in a multiplicity of ways, 'Jawani,' 'Jui', Jiwi', 'Chūpi', 'Jūki' etc. He is called Jai Bahādur here in the A. N (I. 190=Tr. 391). Mr Beveridge thinks it may be 'Chuli' (or Choh) Bahādur," because Abu-l-Fazl states that Humāyūn afterwards ordered the honorary title of 'Chūh' to be subjoined to the names of all those who عول 'had been in attendance upon him in his wanderings through the ' Chol' or desert (A. N Tr I. 414 Note) A 'Nazr Shaikh Choli' is mentioned at 240, 241 infi a. The name of Shaikh Yusuf Chuli also occurs in Abu-l-Fazi's list of Humayun's fellow-sufferers in his perilous journey to Persia. (A. N.I 223, Tr. I 450). B. says that the messenger was an Uzbek named 'Chūli Bahādur' (I. 442, Tr. I 568), though 'Jūki' is given as a variant in the B I text But Jauhar says that when Humāyūn asked him what his name was, he said it was 'Juy Bahadur Uzbeq' (Tr Stewart). The 'Chuli' theory or explanation seems to be thus invalidated, as 'Jay', 'Juy' or 'Juwi' is stated to have been his original name and not a sobriquet subsequently acquired or conferred. 'Jai' does appear to have been a name and a 'Jai' Tawachi Bashi is mentioned in the A. N. (III 30=Tr 42, 307=Tr. 453 and 458 Note)

V. 217, l. 19. Ahmad Sultan advised His Majesty to proceed to Irak by way of Tabas Kilaki.

For 'Tabas-Gilakı', see my note on Vol. II. 193, l. 14 It lay on the road from Sīstān to Qazvīn which was, in Humāyūn's time, the capital of Persia (A N. Tr I. 416 Note). 'Pulāk-i-Sūrlīq' (218, l. 18), to which Shāh Tahmāsp had removed his camp, must be 'Bailāq' (camping-ground) or 'Yailāq' (summer quarters) of Sūrliq' Sūrliq' must have been near the

modern Sultāniya, as Abu-l-Fazl states that Tahmāsp proceeded towards Sultāniya and Sūrlīq with the intention of going into summer-quarters there. (A. N. I. 215=Tr. I. 436). F. speaks of it as يلاق قيدار نبي between Abhar and Sultāniya (I. 237, 1. 15) and in Stewart's Translation of Jauhar, it is called 'the fountain of Savuk Belak'. (1st Ed. p. 62). B. has on ورق or ورق (I. 444, Tr. I. 569 and note).

V. 220, l. 3. Mirzā Kāmrān sent Mahd 'Ali Khānzāda-i-begam to Kandahār.

مهد عليا خانز اده بيكرا بغند هار نرستاد (210, l. 9 f.f.). Mahd 'Aliā, 'Exalted Cradle, Couch or Litter,' is a title of respect prefixed to the names of Princesses and Royal ladies. Abu-l-Faẓl speaks of Ḥamīda Bānū—Akbar's mother—as Hazrat or Mahd 'Aliā. (A. N. I. 19—Tr. I. 57). A sister of Sultān Maḥmūd Ghaznavi is frequently mentioned in Persian literature as the 'Mahd-i-Chigal.' The sister of Sultān Sinjar the Seljūq who was the mother of Bahrām Shāh Ghaznavi was similarly entitled Mahd-i-'Irāq. (T. N. Text, 23, l. 6—E. D. II. 279). Mu'atamad Khān speaks of the Empress Nūr Jahān as 'Mahd 'Aliā Nūr Jahān, Bādishāh Begam'. (Iqbāl Nāma, Text, 57, l. 1). Salīma Sultān Begam is also styled 'Mahd 'Aliā' in the Ţ. A. (246, l. 3 f. f.). Khānzāda Begam [not 'Khānzāda-i-begam'] was the elder sister of Bābur and the aunt of Humāyūn.

V. 221, l. 8. Sūfi Wali Sultan Kadāmū.

in the lithograph (211, l. 9), but the correct form of the sobriquet seems to be 'Rūmlū'. Abu-l-Fazl speaks of him as 'Sūfi Wali Sultān, descendant of the Sūfis, Khalifa of the Rūmlū' (I. 219=Tr. I. 442), and elsewhere as Wali Khalifa-i-Shāmlū. (II. 78-79=Tr. II.119-120). F. calls him Ṣūfi Wali Sultān Shāmlū. (I. 237, 21). 'Rūmlū' signifies 'of, coming from or belonging to Rūm', i. e. Asiatic Turkey or Anatolia. Similarly, 'Shāmlū' means 'belonging to Shām' or Syria. These tribes are said to have been brought and settled in Persia by Tīmūr and were among the eight who called Shāh Ism'aīl to power. So also 'Taklū', 'Istajlū', 'Āq-qūinlū,' 'Qarā-qūinlū' etc.

V. 222, l. 1 from foot. The victory was accomplished on the 10th of Ramazān 953 H......Some place the event in the year 952, but God knows the truth.

The weight of authority is decidedly in favour of 952. Abu-l-Fazl gives Wednesday, 12th Ramazān 952 H. (A. N. I. 244; Tr. I. 480). Gulbadan, who was in Kābul at the time, explicitly states that Humāyūn entered the Bālā Ḥiṣār of Kābul, when five hours had passed of the night of 12th Ramazān 952. (H. N. 75; Tr. 177). The Tārīkh-i-Ibrāhīmi, another contemporary chronicle, gives 11th Ramazān, 952. (E. D. IV. 217). Bāyazīd Biyāt (J.A.S.B. LXVII. (1898), p. 299), F. (I. 238, l. 3) and B. (I. 449; Tr. 579), have 10th Ramazān 952 H. The 10th or 11th appears to have been the date of Kāmrān's flight and virtual surrender of the fortress. But Humāyūn who was a confirmed believer and supposed proficient in Horary Astrology would not enter the citadel-and take-possession until

the arrival of the auspicious moment, which is recorded precisely by his half-sister.

12th Ramazān 952 H.=17th November 1545 was a Tuesday, but as the Muḥammadan night began at sunset, the week-day is given correctly by Abu-l-Fazl. Firishta and B. give the contemporary chronogram for the event thus ميك كرت ملك كال ادرى, which yields 952. The numismatic evidence settles the question in favour of 952 H. Shāhrukhts struck by Humāyūn in Kābul in 952 and 953 are known (Whitehead, Punjab Museum Catalogue of Mughal Coins, II. Nos 53-54).

V. 226, l. 5. But Maham Anka . put herself forward and held him [Prince Akbar] towards the enemy (i e the garrison)

This is putting the wrong sideforemost. عيم ميدافت "Māḥam Aṇaga put herself in front and held [kept]-herself towards the enemy" She did not hold the child "toward the enemy, or the garrison, but herself" She exposed her own person, not the child's Jauhar's account is that Akbar was not really exposed at all, but Kāmrān only threatened to do so (Tr Stewart, Ed. 1832, p 87). Abu-l-Fazl's silence in regard to this detail has to be noted, but Budāuni corroborates the T A. He states that she (خود راسي نير للاساخة ود) "made herself [her own body] a shield [for him] against the arrows of calamity" He also quotes a couplet, which purports to say that "Even if the sword of the world leaps from its sheath, It cannot sever a vein without Divine permission." (I. 450, 17=I Tr 580) Mr Vincent Smith accepts Nizāmu-d-dīn's statement and "sees no reason to doubt the fact" (Akbar, 24 note), but when he says that Māham "held Akbar up towards the garrison", he is misled by Dowson

Kāmrān did not "make his way out" of the fort 'barefoot,' as is stated on 1 1 f. f He ran away 'hot-foot' and in a hurry, "putting his best leg foremost". The phrase used is حال خالي باي سرون برد (214, 1 13). He saved his life by stirring his legs. It occurs again on 1, 11, p. 211, and is rendered by Dowson himself by 'made their escape in hot haste' (239). V. 227, 1 2 Kāmrān then called out in the Turki language, 'I have

killed your father, Bābā Kashka' Hāji Muhammad when he heard this, retreated

The real meaning is very different "Have I killed your father that you are thirsting for my blood and pursuing me so relentlessly?". Hājji Muhammad felt the justice of the taunt. Bābā Qashqa was put to death several years afterwards by the orders of Humāyūn.

V. 229, l. 16. Kamran begged forgiveness for Manus Beg

written 'Nāmūs' by Dowson on p 226 supra, and 'Mānūs' by F (I 288, l. 7 ff). It is 'Bāpūs' in the Memoirs of Bāyazīd Biyāt (J A S.B 1898, p. 299), 'Bābūs' in the A. N. (I 230, 236, Tr. I. 461, 468) and 'Bāpūs' in Gulbādan (H. N. 76, 83, Tr. 177, 186) and Erskine (H. B. H. II 342) 'Bābūs' is most probably right, as it is the name of a place also, which is

shown on the Map attached to Ferrier's Caravan Journeys, and lies about twenty-five miles south of Kābul.

V. 234, l. 12. The date of his [Hindāl's] death is found in the words 'Shahādatash ba talab shud.'

Nizāmu-d-dīn is quoting the last line of a quatrain, the whole of which is cited by B. The words are تاريخ شيادتش از شبخون بطلب شد (218, l. 16). "And the date of his martyrdom was searched for [or required from] the word Shab-Khūn". That word signifies 'a night attack' and its abjad value is 300+2+600+6+50=958. Abu-l-Fazl gives the identical chronogram. (A. N. I. 314; Tr. 585). So also B. (I. 454, l. 6 and 455, l. 3). The exact date of the night-attack is given as Sunday, 21st Zī-l-q'ad 958 H. by Abu-l-Fazl (A. N. I. 312=Tr. I. 482) and F. (I. 240, l. 5 f. f.).

V. 234, l. 8 from foot. Humāyūn crossed the Indus between Dīnkot and Nilāb (5th Safar 962 A.H.=29th December, 1554).

The Lithographed Text has nothing corresponding to the date given in the parenthesis here. The statement itself is undoubtedly wrong and must be an interpolation. Kāmrān, whose capture was a subsequent event and is recorded afterwards, was blinded towards the end of 960 H. (A. N. I. 328; Tr. I. 604) and Humāyūn is said to have begun his march from Kābul for the reconquest of Hindustān in Zī-l-ḥijja 961—November 1554 A.C. (not 1553 as on l. 1, p. 237 infra). (I. 340—Tr. I. 620). The date given, Ṣafar 962 H., is that of a quite different and much later event—the arrival of Humāyūn at the Indus after leaving Kābul for the reconquest of Hindustān. (A. N. I. 341—Tr. I. 622; F. I. 242, I. 4).

V. 235, l. 12. The date of this event [the blinding of Kāmrān] has been anticipated a little.

V. 238, l. 6 from foot. The Afghāns, 100,000 in number, were defeated, being inferior in courage.

"The Afghan army which approximately numbered 100,000 persons was defeated by a small number of men." The Mughal force which routed them is stated to have been only about 20,000 strong, and it is again stated on 1. 15 f. f. to have been only one-fourth as numerous as that of the enemy. The error is due to Dowson having read an igafat after النك.

۴ع

It is not Andak-i-mardi, but Andak mardi, i. e 'n few men"

V. 239, l. 11 from foot. Kambar Diwana. had taken and plundered Bayana.

There is no reference to 'Bāyāna' in the lithograph. الماد على الماد (221, 18 f f.) "He began to plunder and destroy". Sambhal is at a very great distance from Bayāna and the latter place-name has crept in by circr. It indst be a miswriting of أماد والماد والما

V 240, l 8 Shaikh Juli was sent to the Punjab to summon Prince Akbar

The right reading is most probably, 'Chūli' Abu-l-Fazl calls the man Nazr Shaikh Chūli (I 364, Tr I. 657 and note) and so also B (I 466; Tr 601). For the exact date of the death of Humāyūn, see my Historical Studies in Mughal Numismatics, pp. 264-5. It was 13th Rab'i I, not 15th, as stated here.

V. 240, l. 16. All the wealth of the Hindustan would not have sufficed to maintain his generosity

The words in the text are حمر مدوسان وفاكردى (222,1 5), which really mean 'the estimated or actual revenue accruing to the state from all the territories comprised in Hindustan'

V 242, l. 7 from foot The hostile forces [of Tāz Khān and 'Adali]
met near Chhatrāmau, forty Kos from Agrā
and thirty from Kanauz.

Recte, Chlibramau, which is now in Farrukhābād district and lies about 18 miles south-west of Fathgaih and 80 miles east of Agra (Th) Lat. 27°-9' N., Long. 79° 82' E. (I G X 204) Constable, 28 A b

V 242, l 5 from foot He took possession of several local treasuries belonging to 'Adali

nean 'local treasuries', but 'officials appointed to manage the Khālisa or Reserved Lands which were administered, not by Jāgīrdārs or Ijārdārs (Fief holders or Farmers of the Revenue), but directly by the Dīwānz-Wazārat, the Sovereign's Chief Revenue Minister at headquarters The phésage has been copied by 'Abdulla in the Tārīkh-v Dāūdi and is translated thus at E. D. IV 506 "On his way thither, he [Tāj Khān] had seized various provincial officers of 'Adah and obtained from them whatever he could, either in money or goods"

V 244, l. 20. Sikandar Khān, ruler of Bengal, now raised the standard of rebellion.

The name is wrongly given. The Bengal ruler was known as Muhammad Khān [Gauriya] and the correct designation is given on the very next page, where his defeat and death are recorded. He is called Muhammad Khān Sūr by Abu-l-Fazl, who says that he was "nearly connected with Shīr Khān'. (I. 339; Tr. I. 618). F. calls him Muhammad Khān Sūr or Muhammad Khān Gauriya. (I. 235, Il. 3 and 13). He styles himself Shamsuddīn Muhammad Shāh on his coins. (I.M.C. II. 180).

V. 245, l. 12. Hemū fought with Muhammad Khān Gauriya at the village of Chhaparghatta, fifteen Kos from Agra.

The Tārīkh-i-Dāūdi states it was eleven Kos, not from Āgra, but from Kālpi. (E. D. IV., 507). B. (I. 432=Tr..555) and F. (I. 235, I. 13) put it at fifteen Kos from Kālpi. This latter statement is undoubtedly the correct one. Thornton says that "Chuppurghatee" is in Cawupore district, on the route from Allāhābād to Etāwa, 74 miles south-east of the latter. Lat. 26°-10′ N., Long. 79°-59′ E. Kālpi is in Lat. 26°-7′ N., Long. 79°-48′ E. As Āgra is in Lat. 27°-10′ N., Long. 78°-5′ E., it is clear that Chhaparghatta cannot be only fifteen Kos distant from it. Chapparghatta is mentioned by Finch.

V. 248, d. 7 from foot. Rājā Rām Chand, Rājā of Nagarkot.

So also in B. (II. 12=Tr. II. 4), but Abu-l-Fazl (A. N. II. 20, 1.7; Tr. II. 35), and F. (I. 244, 1. 19), have *Dharma Chand*, which is the right name, as it is in accordance with the Dynastic List compiled from local Hindu sources. (Duff, C.I. 306 apud Cunningham, Arch. Surv. Rep. Vol. V. 152). A Hindi poetical history of the Rājās of Nagarkot written in the reign and under the patronage of this Rājā and called *Dharma Chand Nāṭāka* after him is extant. See my note on Vol. III. 319, 1. 13.

V. 251, l. 2 from foot. Khwāja Sultān 'Ali and the Mīr Munshi and the Khanjar Beg of Tardi Khān.

(or son-in-law) of Tardi Beg Khān:" (See also B. II. 14=Tr. 7; A.N. II. 32=Tr. 52). The word خوش نودی است. Manuscript is must have been absent in: Dowson's Manuscript. Khanjar, Beg's, name is mentioned by Jauhar. He was one of the five men who were ordered to blind Kāmrān. (Stewart's Tr. Ed. 1832, p. 105). The Mir Munshi's real name was Muḥammad Asghar, and he was afterwards entitled 'Ashraf Khān'. (A. N. II. 30.=Tr. 48 and note).

V. 252, l. 7 and footnote 3. Hemū had sent on his artillery, which was obtained from Turkey, "Az Mamālik Rūm nishān mī dād" (Faizi Sirhindi).

"Taizi Sirhindi's words كَ الرَّمَالِكُ رَوْمُ نَدَانَ مَدَادُ do not mean that "the artillery was obtained from Turkey", but that it was "so formidable that it reminded one of Rūm or that it was made in the style or on the model of that of Rūm." No Indian ruler is known to have imported cannon from Rūm. Abu-l-Fazl merely says of Hemū's park of artillery and heavy guns at Pānipat that it was great both in quality and quantity. (II. 35: Tr. II. 58). Elsewhere, he states that "there was nothing

like it except in Turkey". (II 42, Tr II 69) Nizāmu-d-dīn ascribes to Rūmi Khān the statement that Bahādur Shāh's artillery was such that "no other potentate save the Emperor of Rūm possessed anything like it" (Text 196, l. 5=191 ante)

V. 254, l. 12 The Royal forces pursued him [Sikandar Sūr] to Dīsawa

Dowson notes several variants without fixing the locality, but the place intended is almost certainly Desūya, which lies 25 miles north-west of Hoshiārpur town, Punjāb (I. G XI. 194) Constable, 25 A b Raverty contends that the correct form is 'Dosūya' and that it means on both sides', but this savours of meaning-making The name is written 'Desūya' or 'Deswaha' in the Aīn, (II Tr. 316, 110) 'Dihmiri' with which it is associated by B (II. 18=Tr 10) and A F is the old name of Nūrpūr near Kāngra, which is about forty miles north-east of Desūya It is now called 'Dhaner'. 'Chamyāri' which is said by B. to have been the site of Khizr Khwāja Khān's discomfiture still exists near Ajnala in Amritsar, about 35 miles north-east of Lāhore

V 256, l. 16 Khān Khānān was married to Sultān Begam, daughter of Mirzā Nūru-d-dīn, who was the son of the sister of the late Emperor Humāyūn

The actual name of the lady, which was Salīma, has been left out in the translation, though it is given in the Lithograph (246, l. 4 f. f) She was the daughter of Humāyūn's sister and was married to Akbar himself after the assassination of Bairam Khān The statement that her father was the "son of the sister of Humāyūn" is founded on a misconstruction of the text (246, l 3 f f) Her mother was a sister of Humāyūn. Her father, Mirzā Nūrū-d-dīn was a Naqshbandi Sayyīd of Chaghāniān (A. N II 64—Tr 97, Gulbadan, H N Tr 176, Aīn, Tr I 309, 618)

V 257, l. 7 Infatuation of Khan Zaman for one of the royal troopers

The man had been one of the Qūrchis of the Emperor Humāyūn, whose after-death title is Jannat-āshiyāni. انطاع داشت (247, 17) "The Qūr was the collective name of the flags and ensigns displayed, along with a supply of spare weapons, at the door of the audience-hall and at the entrance to the Emperor's encampment or carried before him on elephants The men who carried these things were called Qūrchis and they were under the orders of a responsible officer called the Qūrbegi See Aīn, Tr I. 109 110" (Irvine, A I M. 51, 205).

V. 258, l 4 His temper now became so arrogant and perverted, that for some days, he would not come out of his house.

"His constitution (i e health, physical temperament) having become disordered (lit diverged from the path of equability), he did not come out of his house for some days" He was ill. It was his body which was suffering from some disease, not his mind or his temper. A. F. (II. 86=II. 131)

TABAQAT-I-AKBARİ and B. (II. 20=II. 27) both declare that he was ill. The V. 263, 1. 4.

which is used immediately below means "visiting the sick". The Pir made the excuse that the slave did not know him. Khan Khanan asked him how he knew what the slave V. 258, l. 13.

سامد راجه قدر شناختید که او شنامد (248, l, 7 f. f.). " Khān-i-Khānān said: 'How much (or how little) have you recognised us (or our position)? How then can he (be expected to) do so? How can he be expected to know who I am, what I am, and what I have done for you, when you yourself do not seem to do so?'" Lowe's rendering is, "When Pir You yourself do not seem to do so. How you, Muhammad apologized, saying 'Forgive me, my porter did not know you', the Khān-i-Khānān answered, 'Nor you either'." (Tr. II. 20; Text, 27). Pir Muhammad's excuse really aggravated his offence and Bairam practically said so. Cf. the proverb : "The excuse (apology)

His Majesty used often to read with him ghazals in mystic is worse than the fault'. V. 259, l. 14.

He [Akbar] used to read the Ghazals "عزلهاى لسان الغبر پيش مبر مي خواندند of Hafiz with the Mir ['Abdul Latif Qazvini, his tutor]." B. says that Akbar had "taken some lessons in the Discan of Hafiz from 'Abdu-l-

'Lisānu-l-Ghaib" is a laudatory epithet of Hāfiz. It means "the tongue which uttered [spiritual] mysterics or hidden secrets of the unseen world". Latif." (III. 98, 1.5 f.f.).

V. 260, l. 3 from foot. He had reached the town of Siri. The spelling is uncertain. B. has 'Sipri'. (II. 35=Tr. II. 29). The A. N. has a variant 'Seopuri'. (II. 90). 'Sipri' and 'Sheopuri' are towns in Gwalior State. Sipri is 65 miles south of Gwalior fort. (Th.). Constable,

27 Cc. Sheopuri or Shivpuri is about 75 miles south-west of it. V. 261, l. 4 from foot. [Akbar] reached the town of Sikandra, half

'Half way to Dehli'has nothing corresponding to it in the Lithograph. The place meant is 'Sikandra Rão', which lies about twenty-three miles S. E. E. of 'Aligarh town. (Th.). Constable, 27 D b. The distance between Agra and Dehli is about 134 miles. (Chihar Gulshan in I. A. xeviii).

V. 263, l. 4. [Shihabu-d-din Ahmad was] all the while exerting himself Sikandra Rão is only 45 miles north-east of Agra. to set the attendants of the Emperor against the minister.

به منان در انداخت (251, l. 1). "He spread آوازه تغرر مزاج بند گان حضرت از خان خانان در انداخت the report of the alienation of the mind (temper) of the Emperor from the Khān-i-Khānān". بندگان حضرت does not mean "attendants of the Emperor", but is a courtly phrase for His Majesty himself. (Cf. Lowe, II. 231). Shihābu-d-dīn did not instigate the attendants of the Emperor against Bairam. He told people that the Emperor himself was seriously displeased or offended with the minister and had lost all confidence in him. (Text, 265, l. 10) is again mistranslated at 293 infra.

V. 263, l. 16. And the messengers [of Bairam Khan] were sent back

The text has a negative and it is correct. The messengers could not obtain leave to return براست نیز رخست نیاخته (251, 1.6) The A.N says that they were not allowed to leave the Court (96, Tr. 196) and so also B (II. 37; Tr. 31).

V. 264, l. 18. Husain Khān, his Bairam's sister's son and his son inlaw Mahdi Kāsim Khān

שלים אוני בולים
V. 264, l 9 from foot. Abul M'aāli attempted to overtake His Majesty. ادرآن مودم شاه ابو العالى سواره حواست كه حصرت را دريا بد (251, l. 2 f. f). "Among those men, Shāh Abu l-M'aāli wanted to salute [lit embrace], His Majesty from his own diorse's back, i e without dismounting".

This was a gross breach of Court etiquette, an act of presumption and importanence which was instantly punished with imprisonment Abu-l-Fazl says that "that headstrong and disrespectful one offered the Kornish con II. 103, 1 11, Tr. II. 166 آن الد مست بي ادب سواره آمده كرش كود " note) Babur says that on one occasionthe and his cousin Mirza Muzaffar Husain saw each other without dismounting مر وادى در يامه (B. N. Tr 297). The rule was that when an inferior met a superior out riding, the inferior made his Kurnish after dismounting Abu-l-Fazl states that Humāyūn, on a certain occasion, conferred upon his brother Hindal some extraordinary favours and one of them was the privilege of paying his respects on horseback. (A N J. 275=Tr J. 527) He has taken the statement from Jauhar who states that when Hindal, on seoing: Humayan afar, off, wanted to alight from his horse, the Emperor, as a mark of special condescension, asked him to keep his seat (Ar Stewart, 181) It as also said of Shaikh Gadai Kambu that his ascendancy and arrogance during Bairam Khān's Protectorate reached such a height, that he once dared to bow to Akbar from on horseback and the young Emperor had to put up with the M. U II 551, .1.-2). The same) سواره سرش عاشیائی مصافحه می سود 'author notes the fact that an Amir called Fazlulla Khan was kindly given permission by Aurangzeb to make his 'Mujra'-or 'Kurnish' from the saddle, but this special consideration was shown only because this person was suffering from elephantiasis. (Ibid. III .29, 1. 6 f.f.).. See also the -Sharratu-l-Atrāk (Tr Miles, 250) for another instance.

V. 266, 1.9. When the royal forces reached the town of Dagdar and proceeded to the pargana of Konā.

'Dagdar' is said to have been in the vicinity of Jalandhar, between the Satley and the Biyas (A. N. II. 111; Tr. II. 169; Ain, Tr. I. 317 note and II. 316), but the name is spelt 'Dakha' in a Ms. of the A.N. (Tr. II. 169 V. 268, 1. 5 from foot. note) and it may be 'Dakha' which lies a few miles north of Ludhiana

The Lithograph reads the second name as J, & Konawar' (252, 1. · 8 f. f.), and Fairi Sirhindi speaks of it as "Konachur, a village in the town, but there is also a variant 'Dardak'. pargana of Rahun." Blochmann fixed the reading as "Gunachur," which lics south-east of Jalandhar. (Jin. Tr. I. 317 and 619). B. calls the place Ranur Phillaur, (II. 40=Tr. II. 35), which looks like an error for Kanjur Phillaur. A village called Gunachaur still exists and its Branch Post Office is registered in the P.O. Guide. It lies a few miles north-east of Phillaur, near Banga. Banga is shown in Constable, 25 A b. He reached the neighbourhood of Talwara, a district in V. 267, 1. 16.

Abu-l-Fazl says it was a strong place in the hills. (A. N. II. 116=Tr. 178). Elsewhere (II. 166=Tr. II. 261), he speaks of Riji Ganesh of Talwara as "the Raja of Nandun [Nadaun] which is in the hill-country between the Biyas and the Sutley". In the Ain, Talwara is placed in the Bari Duāb, along with Pathin, Dahmīri, Goler, Kotla, Kāngrā, Mau etc. (Tr. II. 318). Nādaun lies 20 miles south-east of Kāngra town and is now in the Hamirpur talisil of Kängra district. Lat. 31°-46' N., Long. 73°-19' E. (I. G. XVIII. 272). Constable, 25 B b. Talwara is about 35 miles north-west of Nadaun and 25 miles south-west of Kangra. It is shown on the Survey of He went to the Kolabi (lake), a place within sight

of the city and famous for Sahasnak. India Map of the Punjib.

سر الله المسلم famous as' Sahaslang', i. e. the Sahasralinga Tank, the Tank with a thou-V. 268, 1.5 from foot. sand Lingas, [Phalli or symbols of Mahadeval. It was built by Siddharaja Jaysinha about 1134 A. C. (B. G. I. i. 177, 179). "The excavation made for the reservoir is still pointed out at Puttun, but of the fabric itself nothing remains. The name was derived from the numerous shrines of Muha Der encircling it, similar to those which still remain around the Meenul

V. 268, 1.5 from foot. They call it in the Hindi langue there and nave it celebrity.

and an idol-temple is called 'Linga' and as there were 1000 temples [Lingas] in that lake, it came to be known by this name of 'Sahaslang' 'Rānāmand' is due to the Persian words having been misconstrued as a proper name.

V. 269, l 4. The words, 'Muhammad Bairām' contain the date of his murder.

The abjad value of fix of would be only 345 The words of the chronogram are given correctly in the Lithograph as Shahād Shud Muhammad Bairam (253, 1.4 f f.), which stand for 967 Cf. also B. who cites the Rubā'i in which the words of the Tārīkh are incorporated. (II 45=Tr 41)

V 269, last line The marriage of Muhammad Bāki Khan was celebrated with a lady whose family connections have been explained in another place

كد الراق التي كد المن التي كل التي التي كل التي التي كل التي

V 274, l 11 He performed the distance, one hundred and twenty Kos, in a day and night

The words in the text כנבוט כנכ (256, 1 18) are most probably an error for געבוט לנכ, t. e two days and nights. The actual distance between Ajmer and Agra is about 228 miles (See A N Tr II 510 note). Abu-l-Fazl states that this journey was completed in less than three days and he records the exact date of arrival at Agra as Friday, 8th Jumādi II, 969 A. H. (A N. II. 158=Tr. 244). F. says the distance was traversed in three algebras and days.

V 278, l 10 When they came to the pargana of Sarūt in the Duāb.

Dowson says this must be 'Saror' in Qanauj (see his Note in Vol VIII, Geographical Index, p xh), but this cannot be right The objective of the fugitives was Kābūl, as Mun'im's son Ghani Khān was governor there and they are said to have "gone over the Jumna and destroyed the bridge by which they crossed". The place meant must be Sarwart, Sarwat or Sarot, the old name of Muzaffarnagar. The village of 'Sarwat' still exists, about a mile north-east of the present town of Muzaffarnagar, which was founded in 1623 by Khān-i-Jahān Muzaffar Khān (Elliot, Races, II 130, I. G. XVIII. 93). The crossing of the Jumna and the destruction of

the bridge are mentioned in the Tarikh-i-Alfi also. (A. N. Tr. II. 279 Note). V. 279, l. 21. [Kamal Khan received] a grant of the parganas of V. 283, 1. 5.

The lithograph has "the parganas of Haswa, Fathpur etc. belonging to the Sarkar of Karra-Manikpur". (258, 1.4 f.f.). Haswa lies on the route from Allahābād to Fathpur, seven miles south-east of the latter. Lat. 25°-51' N., Long. 80°-58' E. Fathpur-Hanswa' is registered as a Maial in the Sarkār of Karra, Sūba Ilhābād in the Ain. (Tr. II. 168). Fathpūr and Haswa are now two distinct parganas in Fathpur Talistl. (I. G. XII. 83).

As there was a Fathpur-Bihiya in Ballia district and another Haswa also, in Bihār, 44 miles north-east of Sherghāti, this place was called Fathpur-Haswa to distinguish it from them. Abu-l-Fazl says that Kamāl Khān

was given fiefs in the Sarkar of Lakhnau and the parganas of Hanswa

V. 279, l. 23. Sher Khan, the son of Salim Khan, attacked 'Ali Quli and Fathpur. (A. N. II. 192; Tr. 297).

Sic in the lithograph also (258, l. 5 f.f.), but it is an error. This Sher Khān was the son of Sultan Muhammad Adil. Cf. what Nizāmu-ddin himself says at p. 272 ante. See also A. N. II. 138 Tr. 215; B. II. 48

Tr. 44. Salim Khān's only son Firūz was murdered by 'Adali.

V. 281, l. 1. Tulak Khan then went to the village of Mama Khatun. Māmā Khātūn is the name of a place on the road from Kābul to

Istālif. (B. N. Tr. 405 note; Masson's Journeys in Balūchistan, Afghanis.

And [Mun'im Khan] defeated and scattered her forces tan and the Punjab, III. 145).

V. 282, l. 13.

What really happened was just the reverse. It was Mun'im whose forces were routed and scattered and who was obliged to decamp from Kābul and return to the court at Agra, (Text, 259, 1. 9). B. says that "Mun'im Khan on the first attack met with a repulse," (Text, II. 57, Lowe, II. 55) and Abu-l-Fazl states that "defeat fell upon him and he him-

self would have been taken captive, if the enemy had not been engaged with

V. 282, 1. 4 from foot. Khwaja Abdulla, who was a distinguished man the spoil". (A. N. II. 188=Tr. 292).

who is generally [or better] known as Khwajagan-Khwaja (Khwaja of wno is generally for Debberl Khowh as Khowijayan-Khwaja or the Khwajas)". Khwajagan-Khwaja' was his familiar designation or generally called 'Khwāja Aḥrār'. (A. N. II. 21—Tr. 37; 127—Tr. 195;

Hazrat Husain Kuli Beg, son Wali Beg Zu-l-Kadar..... having been admitted to the order of nobility, received of 194=Tr. 301; Blochmann, Ain, Tr. I. 539). ضرت حسب آ بیک ولد ولی بیک ذوالقدار قرابت بیرم خان را که بواسطهٔ خدمات V. 283, l. 5.

يسنديده در رمرة امرا انتظام يافته و معطات حابي سرفرا ر كشته حاكير مرزا شرف الدين او عايت ورموديد (259, 1 2 f f) "Hazrat, 2 e' His Majesty, granted to Husain Quli Beg, son of Wali Beg Zu-l-qadr, the relative. (قرات) of Bairam Khān, who, on account of approved service, had been admitted to the order of nobility and made a Khān, the jāgīrs of Sharafu-d-dīn Husain" Husain Quli Beg was the son of Bairam's sister (A N.II. 196=Tr 304, Blochmann, Ain, I, 329) 'Hazrat Husain Quli Beg' is an absurdity.

V 284. l 15. The brother of Abu-l-M'aāli, who was also called Shāh Lündan

Recte, 'Shah-1-Lawandan', which means 'Prince of libertines, rakes, debauchees, lewd men.' Richardson says' Lawand' means 'a libertine who is afraid of neither God nor man' Lowe calls him 'King of libertines' (259, 12ff, II 56) His brother, Abul M'aāli also, was a profligate wretch and an unprincipled adventurer, who murdered his benefactress and mother-in-law

V. 285, l 2 He had a slave by name Koka Fulad times secretly did everything in his power to injure the Emperor

It was at Sharafu-d-din's instigation that the slave did so לא יפליב نام علای خود را برین داشت که گاه سگاه در کمین بود ه مین وجه که تواند بحصرت آسدی رساند (261, 1.3) "He [Sharafu-d-din] instigated a slave of his own named Koka Fūlād, to he in wait (lit. ambush) in season and out of season, and do everything in his power to hurt the Emperor" Abu-l-Fazl calls him قتلق Qutlug Fulad, the slave of Sharafu-d-din's father (A. N II 202=Tr. 314) His real name was probably Qutluq, and he may have been called 'Koka' because his mother had been the Mirza's nurse

V. 285, l 11 from foot. [His Majesty] mounted his royal litter

Dowson says in the footnote that "the word in the original is ork and that it must be meant for the Hindi 'Singhasan', Throne" This is not correct is really 'Sukhāsan', which is very different from 'Singhasan' and it is defined by Abu-l-Fazl as 'a litter, the boat of dry land' (A. N II 202=Tr 315) Elsewhere, the same authority says of the people of Bengal, that "they employ for land travel, the Sukhāsan This is a crescent-shaped litter, covered with camlet or scarlet cloth and It is conveniently adapted for sitting or lying at full length the like or sleeping during travel" (Ain, Tr. II 122) Sukhāsan is one of the Hindi words used by Amir Khusrav in the 'Ashiga' When Dewal Rānī was captured somewhere near Deogiri, he writes

Text, 142, last) شامد الدر سکماسن آل بريرا - چون کردول در تر ارو مشتري را couplet)

Elsewhere. Abu-l-Fazl states that when Mun'ım Khan was wounded in the battle of Tukaroi, he was carried for some days in a Sukhāsan, e. litter (A N III 130; Tr III 185 and Note) Briefly, the Singhasan was a throne, the Sukhasan was a 'palkee'

V. 286, l. 9 from foot.

Mirzā Muhammad Hakīm sent a person to

According to the lithio- مرزا محمد حکیم تبرکش خود نزد مرزا سلیمان فرسناده graph, what he sent was not one of his men [], but his or quiver. (262, 1.2). He did so because it was not possible for him to write a letter. The quiver was a symbol of authority, just like a ring, seal or signet. The historian Sikandar bin Manjhu tells us that when Mandu was sacked by Humāyim, he delivered to Bakhshū, the favourite musician of Bahādur Shāh of Gujarāt, his own quiver, in order that the singer might secure immunity of life and property, not only for himself, but for all his friends and connections. (Mirat-i-Sikandari, Text, 281, 1.1; Tr. Bayley, 389. See also Whiteway, Rise of the Portuguese Power in India, 279 note). Budauni states that when the great officials in the Provinces met together to hear the orders of Islām Shāh Sūr read out in public, a pair of shoes and a Quiver which Islâm Shāh had given to the Sardār was placed on the throne to symbolise the presence of the Sultan. (I. 385; Tr. 497). Similarly, Akbar gave an arrow from his own quiver to Husain Khan Tukriya, as a token of authority or Royal Warrant. (B. II. 185, 1.3 = Tr. 188; A. N. III, 110= Tr. 154). Mir M'asum also declares that when Shah Beg Arghun's army sacked Thatta in 927 H., the massacre was stopped only by the intercession of Qāzi Qāzan, the most learned man of the time. As several members of the Qāzi's family also had been taken prisoners, Shāh Beg gave one of his own arrows to the Qazi to be shown to the rapacious Mughals as his voucher and authority. (Tr. Malet, 80; Kalich Beg's History of Sind. II. (65). An earlier parallel will be found in an anecdote about the Sasanian Emperor Bahram Gaur and the Shepherd's dog in the Siyasatnama. (Ch.

Ghāzi Khān Sūr, formerly one of the nobles of 'Adali... IV. Bombay Lith. Part i. 30, l. 11).

In B. (II. 66=Tr. 65) and the A. N. (II. 182=Tr. 281), the Nisba is took flight and went to the country of Panna. V. 288, l. 3.

given as 'Tanuri', Egg. Mr. Beveridge explains it as Tanwari, strong. bodied. (A. N. Tr. II. 148 and 229 Notes). I venture to suggest that it is "Tonwar" or "Tonwari." He was a Tonwar Rajput converted to Islam or the descendant of one and was proud of his lineage. Such persons deliberately affixed the designation of their tribe to distinguish themselves from the converts drawn from the inferior Hindu castes and to indicate that they The author of the Maasiru-l-Umara also calls him Ghazi Khan

Tanwar ("ee()") and says that he fled to Ramchand, Raja of Bhata, who, when defeated, took refuge in Bandhu. (II. 135). The name of the country to which Ghāzi Khān fled is wrongly written by Nizāmu-d-dīn as well as $_{
m were\ nobly\ born}.$ by Abu-l-Fazl, though the name of the Raja is rightly given as Ramchand. B. has and 'Hatya' (II. 66—Tr. 65), but the right reading is in the Maasir (vide my note on Vol. IV. 462). Mr. Beveridge is in error when he says that 'Panna is another name for Bhata'. The two places are quite distinct. Panna is in Bundelkhand Bhata or Bhatghora is the old name of Bäghelkhand, now Rewä Ghāzi Khān had fled to this country of Bhata, the Rājā of which Rāmchand was called upon to seize and send him to Court. (A. N. II, 148—Tr. II. 229). This Rāmchand was Rāmchand Bāghela, the ruler of Bhata.

Many other Musalman converts of Rājput descent took care to append the designation of their original clan to their personal name, e. g. Hasan Khān Bachgoti (B II 25=Tr 18, T. A in E D V 582), Sulaimān Khān Panwār (A. N III. 136=Tr 192), Tāj Khān Panwār (A N III 140=Tr 193, 198). Shīr Khān Tūnwar (Maāsiru-l-Umarā, I 120, 163), whose original name was Nāhar Khān, was governor of Gujarāt, and died in the fourth year of Shāh Jahān's reign Ghāzi Khān Sūi, the father of Ibrāhīm Sūr [the biother-in law of 'Adah), had been put to death some years before in 962 H, by Haidai Muhammad Chaghatāi, who sent his head to Humāyūn. (B I 463=Ti 597, A. N I 354=Tr. 638).

V 289, l 13. [Ahbar] halted at Rawar

The lithograph leads Let Narwar (263, 14), which is also the reading in the A N (II 222) as well as in B (II 67, Tr. 66) and is no doubt correct

V. 290, 1 6. The imperial forces pursued him as far as the country of 'Ali on the borders of Gujarāt.

This 'country of 'Ali' comprised two small Hindu chiefships, called 'Ali Mohan and 'Ali Rājpur 'Ali Mohan is now better known as Chhotā Udaipur The chiefs are Chauhāns—descendants of Rāwal Patāi, who took refuge in the hills after the sack of Chāmpānei by the Gujarāt Sultān, Mahmūd Begada. Mohan is a hill fort which occupies a most advantageous position for commanding the passes Chhotā Udaipur is shown in Constable, 27 A d. 'Ali Rājpur is 44 miles south of Dāhod or Dohad They are both in the Rewā Kānthā Political Agency now (I G V 223; X. 331 See also Āīn, Tr II 251) On l 15, Zī-l hijja 791 H. is a misprint for 971 H V 291, l 11 from foot. He [Akbar] often rode out to Kākrāni.

None of the four variants mentioned in Dowson's footnote gives the right name, which is *Kakrāli* The village of Kakrāli still exists within the boundaries of Qabulpur, seven miles south of Agra (Fanthome's art on 'A Forgotten City' in J A S. B 1904, p 276).

The village of 'Nagarchain' was in existence and known as such, even in the reign of Shāh Jahān, as it is stated that when the Tāj Mahal was completed, thirty villages belonging to the Haveli of Akbarābād [Agra] and the pargana of 'Nagarchain', with an annual revenue of one lakh of rupees, were granted as an endowment for its maintenance (Bādshāhnāma, II 380, 14, MUI. 160, 115)

V. 293, l. 11. Upon reaching the river Mārān, Mirzā Sulaimān learnt 'Bārān' in the Lith (264, l 12) and also in the AN (II 238, Tr 360) The Āb-1-Bārān is another name of the better-known Kābul river.

Y 293, l. 6 from foot On reaching Jalalabad, they [the Imperial com-

manders] sent Mirzā Kasān into the place to summon Kambar.

مرزا کسانرا نرد ننبر فرسناد (264, l. 8 from foot). 'Mirzā Kasān' is an imaginary entity. The real meaning is that the "Mirzā [Muḥammad Ḥakīm] sent some persons [کسان] to Qanbar". Their names are not given here, but Abu-l-Fazl states that they were Sāqi Tarnabi and 'Ārif Beg. (II. 240; Tr. II. 362). The word کسان is used in the sense of 'persons' repeatedly on p. 274, ll. 18, 22, 24, 25 of the Text and Dowson's rendering there is 'messengers'. (311 infra).

V. 296, l. 5. Ibrāhīm Khān is a much greater man than I.

الراهيم خان بس از ما كارن احت (266, l. 1). "Ibrāhīm Khān is much older [in years] than ourselves." He is said to have been "like an uncle to them" at 302 infra. According to Abu-l-Fazl, Iskandar Khān said that Ibrāhīm Khān was their 'Aq Siqāl', lit. 'Grey-beard', i. e. the senior member of their family. (A. N. II. 219; 'Tr, 376: Ibid. 260=Tr. 388). B. says that Ibrāhīm Khān "was senior to the others." (II. 75, l. 3=Tr. 76).

V. 296, l. 9. They went to the town of Saráwar, which was in the jāgīr of Ibrālām Khān.

B. has 'Sarharpur' (II, 75, l. 4=Tr. 76) and so also the A.N. (II. 219=Tr. 376). 'Sarharpur' was a Mahalin Sarkār Jaunpur, Sūba Ilhābād. (Āīn, Tr. II. 164). It is 'Sarharpur' in Lat. 26°-16′ N., Long. 82°-26′ E. q. v. Vost, J.R.A.S. 1905, p. 135 Note. It lies in Faizābād district on the route from 'Azamgarh to Sultānpur, 46 miles west of the former and 32 south of the latter. B. puts it at 18 Kos' distance from Jaunpur. (II. 23, l. 9.=Tr. 16). See also A. N. Tr. II. 127 Note. It cannot be 'Sarwār' which is a vague geographical expression for the country on the other side of the Sarjū. Sarwār is, in fact, a short form of Sarjūpār.

V. 296, l. 2 from foot. They were obliged to.....shut themselves up in the fort of Namikhā.

'Nim Kahar' in B. (II. 75, 1.9; Tr. 76), and 'Nimkha' in the A. N. (II. 250; Tr. II. 377). Nimkhār is now in Sitīpur district, Oude. Constable, 28 B b. See my note on V. p. 5, 1. 12, ante.

V. 299, l. 8. He [Akbar] sent Husain Khān Khazānchi and Mahāpātar who was an accomplished master of Hindi music.

B. calls him 'Mahāpātra Bādfarosh', i.e. Bhāṭ and states that he had been a favoured courtier of Shīr Shāh and Islām Shāh, and was an unrivalled Hindi poet and musician. (II. 76, l. 5 f. f. = Tr. 77). Abu-l-Fazl bears similar testimony to his gifts. (A. N. II. 254; Tr. 381). Modern research enables us to say that his real name was Narhari Sahāi, not Mahāpātar. He was a native of Asni in the Fathpur district of Allahābād. Akbar is said to have given him the village of Asni in Jāgīr and the title of Mahāpātar, saying that other poets were 'gun kā pātra', 'vessels of virtue', but that he was a 'Mahā pātra', 'a great vessel of virtue'. ([Sir G.] Grierson, The Modern Vernacular Literature of Hindustan in J. A. S. B. 1888, Special Number, 38-39. See also Blochmann, Āīn, Tr. 611 Note). But this tale

and the derivation of Mahāpātar seems doubtful Mr Crooke (Tribes and Castes, II 22) states that Mahāpātra is the designation of one of the seven endogamous sub-castes among the Bhāts, the others being Bhāradwaja, Brahma, Jāga, Dasaundhi, Gajbhīm, and Keliya As B also explicitly declares that he was a Bhāt, it would appear that that 'Mahāpātra' was not a title especially bestowed upon him by Akbar, but the by-name or sobriquet by which he was generally known at the Court. Akbar was an inveterate punster and inordinately fond of such conceits and the saying attributed to him may be a jeu de mots on the designation of the sub-caste to which Narhari Sahāi belonged

V 300, l. 1 Asaf Khan intended to proceed to Garha Katanka

Garha town lies on the right bank of the Narmadā, about four miles south of Jabalpur Lat 23°-7′ N, Long 79° 58′ E Katanka is "Katangi", 22 miles north-west of Jabalpur Lat 23°-27′ N, Long 79°-50′ E It is now a station on the G.IP Railway European writers speak of this kingdom as that of Garha-Māndla

The sobriquet of Fath Khān which has been read on 1 18 as 'Tibati' تتى 'Batani' as in the Lith (268, 1 15)

V 301, 1 17 'Als Qult Khān sent his brother to the country of Sarwār. Dowson's proposed identification of 'Sarwār' with 'Sarharpur' is more than questionable, as 'Sarwār' is called a Wilāyat, or 'country, province or district' and Sarhaipur is only a town On p. 303, 1 1 infra, 'Sarwār' is again denominated a Sarkār or large territorial division 'Sarwār' is really 'Saryūpār', the tract beyond the river Saryū. The river itself—the Saryū or Sarū—is called 'Sarwar' at p 307 infra, Text, 271, 1 2 f f Sarwār included the modern district of Gorakhpur (E D I 56 note)

Narhan (1 4 f f) may be the place of that name in Kharīd, Ballia district, on the north side of the Sarū (B N Tr 674, 676, 677) It cannot be Narhan in Sāran, forty miles W N W of Chupra. (Th) But there is a Narhi, twenty-nine miles north-east of Ghāzipur and about two miles from the left bank of the Ganges (Thornton)

V. 302, l 15 It was determined that Khān Zamān should send his mother, 'Ali Khān and Ibrāhīm Khān his uncle to court.

The names are muddled in the translation مان و حواجه حيان و الراهيم خان كه سرله عم او بود بدر كاه برده در خواست تعسيرات او والدة على على حان و ابراهيم خان كه سرله عم او بود بدر كاه برده در خواست تعسيرات او (269, 1 15) "That the Khān Khānān [Mun'im Khān] and Khwāja Jahān [the officials who had been sent by the Emperor to secure Khān Zamān's submission] should take the mother of 'Alı Qulı Khān [s e. of Khān Zamān himself] and Ibrāhim Khān who stood to him in the position of an uncle, to Court and solicit the forgiveness of his offences" Cf B II 79, 1 14 = Tr 81, A N II 260, Tr 388

V 303, footnote Todar Mal was a native of Lahor

This statement is now known to be wrong, though the error is found in many otherwise well-informed writers. Todar Mal was a Khatri and was born, not at Lähor, but at Läharpur in Sitapur district, Oude (Pro-

ceedings, A.S.B. 1871, p. 138; Ibid, 1872, p. 35. [Sir George] Grierson, loc. TABAQĀT-I-AKBARI cit 34; Blochmann in Ain, Tr. I. 620). There is still near Läharpur, a village called Rājāpur, because it was founded by Rājā Todar Mal and a tank built by him there is also extant. Laharpur lies seventeen miles north-east of Sitapur town. Lat. 27°-42' N., Long. 80°-55' E. (I. G. XVI. 95). V. 306, l. 8 from foot. Orders were given for Ashraf Khān, Mīr Bakh-

Recte, Mir Munshi, as in the Lith. (271, l. 8 f. f. See also 251, 272 ante and 330 post; B. II. 83, 1. 7=Tr. 84).

Muḥammadābād (l. 18) is Mau-Muḥammādābād in 'Azamgarh. Constable, Pl. 28 C c. Nizāmābād is also in 'Azamgarh district, eight miles west of 'Azamgarh town and 32 miles east of Jaunpur. Lat. 26°-5' N., 83°-5' E. (N. W. P. Gazetteer, XIII. 177-8).

The name 'Karāk Khān Turkomān' (last line) should be read as Qazzāq Khān, قراق خان as in B. (II. 161, I. 2 f. f.=Tr. 165). Abu-l-Fazl speaks of his son as J'afar Khān Taklū. (A. N. I. 207=Tr. I. 422; II. 265= Tr. 395). Qazzāq Khān was the son of Muhammad Khān Taklū who had entertained Humāyūn in Herāt. (A. N. I. 207=Tr. I. 422; \bar{Ain} , Tr. I. 426,

V. 308, l. 10 and footnote. He sent Mirzā Mūbārak Rizwi to court.

The Lith. has Mīrak (272, l. 12) and so also B. (II. 84, l. 6; Tr. 85). He was one of the Razawi Sayyids, i. e. a descendent of the Imam Raza. He was subsequently ennobled with the title of 'Razawi Khān', (Ibid. Tr. 250, 275, 289), not 'Mubārak Khān', as is stated in the footnote. Abu-l-Fazl also gives his name as 'Mīrak Rizvi'. (A. N. II. 268=Tr. 398).

V. 310, l. 4 from foot. He himself went with Khwāja Hasan Nagshbandi

along with Khwāja Hasan Naqshbandi to Shakardarra and Ghorband." Abu-l-Fazl says that "he went off to Shakardarra and Ghorband." (A. N. II. 273=Tr. 407). Dowson seems to have read instead of and tacked the latter part of the name (دره) to Ghorband. 'Shakardarra' is a well-known place north of Kābul. Istālif and Shakardarra are both in the Tumān of Dāmān-i-Koh (Skirt of the Mountains). (Raverty, N. A. 67; Wood, Journey, 112). Shakardarra is shown in the I. G. Atlas, 47 E 3. V. 312, *l*. 8.

In the Pass of Sanjad-darra they overtook [the Mirzā's

'Sinjid' means 'red jujube', Zizyphus jujuba. The valley or Darra of Sinjid lies on the route from Kābul to Istālīf near Khwāja Sihyārān. (B. N. Tr. 196, 406). Qarābāgh, which is mentioned on 1. 11, p. 311, lies about twenty-five miles north of Kābu! near Istālīf. (A.N. Tr.I. 491 note; B. N. Tr. 196). It is shown in the I. G. Atlas, 47 E 3. V. 313, l. 8. Upon coming into the neighbourhard of the city, he [Now

Muhammad Hakim de an is plander,

The Lithograph has one Birth which Dowson has wrong year

'city' But 'Bhīra' must be right, as it is specifically mentioned in the same connection in Dowson's own translation at 314 infra The A.N. also reads 'Bhīra' (II 296, Tr. 410) and so too B. (II. 90, 1. 5 f. f., Tr 92).

V. 316, 1, 10 Pargana of Aazampur in Sambal

This is Thornton's 'Azumpoor' in Bijnor district, 28 miles east of Mirat. Lat. 29°-0' N, Long 78°-14' E. Sambhal is in Lat. 28°-35' N, Long 78°-39/ E.

Many of them [the Hindu pilgrims] threw themselves into V. 318. l. 16. the water of the Tank at Thanesar

What the author really says is that "they [the pilgrims] give gold, silver, newels and cloths to the Brahmans and some throw them [their afts] ار طلاو مره و حواهر و پارچه سرهمان مدهد و مصى در آن آن مى اندارند " into the water (279.1 2) B also states that the "Hindu people . give away both publicly and privately gold and silver and jewels ... and linen and valuable goods . . and secretly cast gold coins into the water" (II. 93. 1 7, Tr. 95). Treffenthaler mentions the Hindu belief that if gold is thrown into the tank or pool at Thanesar, it increases in weight. He drily remarks that it must be a fable, because no one who has thrown it has ever recovered it

Khān Zamān was besieging Shergarh, four kos distant V. 319, l 13 from Kanaur

The destruction of the old city of Qanau, and the foundation, by Sher Shah, of a new one, about four Kos further off from the Ganges, on the spot where he had gained the victory over Humayun, is mentioned by 'Abbas (E. D. IV 41n) Coms struck by Islam Shah and Muhammad 'Adalı at Shergarh-Qanauj (or Shāhgarh-Qanauj) are extant (H N Wright, C M S D pp 345-50, 386-389)

V. 320, l 14 and footnote 2 Asaf Khan and all the Atkas were on the right (The word Atka is taken from Badāuni The word used in the Mss of the Tabakat is doubtful) (Foot-

The doubtful word referred to by Dowson is written 4. in the Lithograph (280, 1 2) It is used synonymously with 'Ahdi' and must be right, as there is no reference to the Atkas—the relations of the Atka Khan -Shamsu-d-din Muhammad, in what follows There is no mention of the Atka Khel, in the counterpart passage in the A N also (II, 293, Tr 430) The reading & In B (II. 96, 1 2), looks like the desperate connecture of some copyist who was unable to decipher or understand the word [&1] in the manuscript lying before him.

V 321, l 11 from foot This battle was fought in the village of Mankarwal, one of the dependencies of Josi and Payāg.

So also in B (II. 98, 1 4-Tr 100), but 'Sakrāwal' in the A. N (II. 296, Tr =434), Cunningham (Arch Sur. Rep X, pp 5-6), identified it with

Mankuvār, a village standing on a ruined site about ten miles south-TABAQAT-I-AKBARI south-west of Allahābād and Mr. Vincent Smith agrees with him. (Akbar, p. 80 note). But Sir Wolseley Haig opines that they are wrong, because Akbar is not stated to have crossed the Jumna. He thinks that the battle must have been fought in the Duab itself and fixes the site at a village called Fathpur—Parsaki, seven miles south-east of Karra. He admits that there is no resemblance between 'Mankarwal' or 'Sakrawal' and 'Parsaki', but he lays stress on the point that the village was ordered to be called Fathpur after the contest and 'Parsaki' is the only village in the neighbourhood bearing the name of Fathpur. (C. H. I. IV, 96 note). V. 325, l. 1. Then he proceeded onwards to Mū-maidāna.

This obscure place lies about eight miles south-east of Gagrun and ten miles north-east of Jhālrāpaṭṭan. It is said to have been the first capital of the Khichis. Cunningham thinks that it was called Maū 'of the Maidan or Plain', to distinguish it from other places called Mau, e.g. Mau or Mhow which is in Mālwa, Maū-Chhatrapur and Mau-Rānipur which are in Bundelkhand etc. (Arch. Surv. Rep. II. 293.4), but this is not very convincing.

V. 328, l. 16. His Majesty started for the capital on Tuesday, the Sic also in the Lith. (284, l. 4 f. f.) and B. (II. 104 last line; Tr. 107). But the date must be wrong. Nizāmu-d-dīn has just said that the assault

was delivered on the night of Tuesday, the 25th of Sh'aban, that Akbar entered the fortress on the following morning and stayed in the camp for three days after returning to it. According to the A. N., the Emperor started on the return journey on Saturday, the 29th, four days after the sack (II. 324=Tr. 4.6), and this must be correct. Lowe also noticed the error in Budāuni, who has copied it from the T. A., but he could not rectify it. As 29th Sh'aban Hisabi 975-28th February 1568 A. C.-was a Saturday, Abu-l-Fazl must be right.

V. 329, l. 16. The Emperor fired a second time and brought him

It is manifest from what follows that the tiger was not brought down by the Emperor. What is really said is دکر کا نفنگی دکر آن بودند که نفنگی دکر آن حضرت در مقام آن بودند که نفنگی دیر ال سرت من المعالمة ا the musket once more, with a view to bring him down." Abu-1-Fazl says that Akbar was "endeavouring to discharge another bullet....but the tiger was on the watch and a fitting opportunity for shooting did not present itself ". (II. 328=Tr. 482).

V. 331, footnote 2. The fort was held by Rustam Khān, a Turki slave, in whose house the sister of Changiz Khan had

Mr. Beveridge's rendering is just as literal and misleading. (A.N. II. Tr. 486). She was not a fugitive or suppliant who had taken shelter or sanctuary with Rustam Khan, but his wife. She was married to him. Nizāmu-d-dīn himself says elsewhere that the sister of Sultē

Tughlaq was in the house of Shaikhzāda Bistāmi أو بود (Text, 105, 13) The Emperor Jahāngīr tells us that Rājā Mānsinha's aunt, e Raja Bhagwāndās's sister and Bhārmal's daughter was in "his father's house", e was his father's wife جائية أو در حائة بدرا بود (T. J. 7, 1. 6, Tr I 15). So also Khwāfi Khān states that one of the daughters of Shāh Nawāz Khān Safavī was married to Aurangzeb and another was "in the house of" e the wife of Muhammad Murād Bakhsh درحاء كله (Text, II 63, 15=E D VII 238) Elsewhere, he states that the sister of the Empress Mumtāz Mahal "was in the house of Saif Khān", e was married to him (I 392, 1.2 f.f.)

V. 332, l 13 from foot He [Akbar] made a hasty journey to pay a visit to the tomb of Fāizu-l-anwār Khwāja M'uinu-d-dīn Chishti.

anwār' signifies 'abounding in spiritual lights' and qualifies the shrine, not the name of the saint Richardson says مالس الدون means 'luminous' Elsewhere, Nizāmu-d-dīn states that Akbar visited the spiritually glorious mausoleum' of his father Humāyūn (339, 1 11) Abu-l-Fazl also speaks of the "illustrious shrine of the Khwāja" (A N Tr II 243, 496) and F calls it his روحه مورد (1 263, 1 5 f f)

V 332, l 10 from foot He arrived [at Agra] on Wednesday, 4th of Zi-l-q'ada 976

The date should be the 24th, as it is in the Lith 287, 1 10 If the 3rd of Shawwal was a Wednesday, as Nizāmu-d-dīn himself states, (1 14), 4th Zī-l-q'ad could not have fallen on the same week-day

V 332, 1 27 His Majesty went into [Darbar] Khān's dining hall

در محاس طعام او تشریف بر دند (287, 1 12) He really did the dead man the honour of being present at the funeral feast which is given either on the 3rd or the 40th day after death, when "friends and relatives as well as the poor partake of food, after the repetition of pravers", q v. Herklots, Ed Crooke 106-7 As Darbār Khān is said to have died sometime before Akbar's return to Āgra, it must have been the 'Chihlum', not the 'Ziārat' or 'Tija', i e the third day's feast Darbār Khān was the story-teller [نمه خوان] of Akbar His father had filled the same office in the court of Shāh Tahmāsp

V 333, l 1 footnote Rājā Rām Chandar had purchased the fort [Kālanjas] from Bijilli Khān

Dowson says in the note that Rāmchandar was the Rājā of Panna, but this is demonstrably wrong He was the Bāghelā Rājā of Bhata or Bhatghora, i e Rewā Mr Beveridge again writes "Panna" here (A N Tr. II 499), but it is erroneous Mr Vincent Smith has it correctly here and speaks of Rāmchand as Rājā of Bhatha or Rīwā (Akbar, 100) On page 447, l 16 infra, Rāmchand is called 'Rājā of Bittiah', which is another perversion of 'Bhata'

V. 334, l. 12. The date of the birth [of Prince Salīm] is found in the 53*1*

The correct chronogram is given in the Lith. 288, l. 11, as Shāh-i-

 \overline{Al} -i-Tamar (not $T\bar{\imath}m\bar{u}r$). 300+1+5+1+30+400+40+200=977. The abjad value of هاه ال قبور would be 993—sixteen too many.

V. 334, l. 21. Pilgrimage on foot to the shrine of Murādu-l-anwar...

also, the epithet applies to the shrine and not to the saint. [Mawrid] is "a place whence a person comes or through which he passes, hence a station or quarter." (Richardson). The phrase therefore signifies "station (or starting-point or source) of [Spiritual] Lights [or Illumination]" Cf. 332 ante, where the same mausoleum is styled والكان واله Overflowing with [Spiritual Lights].' Murādu l-anwar has no meaning at all.

V. 338, l. 2 from foot. His [Sultan Mahmud of Bhakkar's] men were

A mistake for 'Mātila', i. e. Māthelo in Sind, a very old town and fort lying about six miles south-east of Ghotki station on the North-Western Railway. The name is correctly spelt as 'Matīla' in the A. N. (II 362. Tr. 527), and the \overline{Ain} , (Tr. II. 329). See my note on I. 231, 1. 7 f.f. The reading in the Lith. is dale (291, l. 6 f.f.), which must be a slip for dele.

The date of Sultan Mahmud of Bhakkar's death is given as 983 H., at p. 339, l. 14 infra=Text, 292, l. 2, but Nizāmu-d-dīn himself puts it into the XIXth year of Akbar's reign (Zi-l-q'ad 981-Zi-l-q'ad 982 H.) at 384 infra. (Text, 323, l. 15). 982 H. is given by F. (II. 323 last line), Abu-l-Fazl (A. N. III. 91=Tr. III, 128) and B. (II. 176, 1.3 f.f.; Tr. 179). V. 341, l. 3. He dismissed them with his own hand.

He did not dismiss them "with his own hand"—whatever that may mean. "He gave them with his own hand the 'betel of leave' [الان رخمت] as is the custom of the people of Hind". The packet of betel was the token of permission to leave the room or outward sign of the termination of the interview and dissolution of the Darbar. Abu-l-Fazl's words are: ساف المادة المادة عند المادة and bidding them adieu, in accordance with the Indian custom." (A. N. III. 4; Tr. 7).

V. 341, l. 3 from foot. H. M. resolved to send one of his officers......to keep the road of Gujarat open, so that none of the Ranas might be able to inflict any loss.

ن الما کیکا بکسی مزاحت نرسد (وان دارد که از رانا کیکا بکسی مزاحت نرسد (293, 1.9 f.f.). "So that no person should be molested by Rānā Kika." Cf. Lowe, B. II. 144. 'Rānā Kīkā' is the familiar or contemptuou snickname by which Rāṇā

Pratap of Chitor is mentioned by the Mughal writers, 'Kīkā' was the name by which he was called in childhood in his own family circle. An only son isstill spoken of as 'Kīkā' (or Kukā) and an only daughter as Kīki' in Gujarāt households, 'Kīkī' literally means 'the pupil of the eye'.

See Kavīrāj Shyāmal Dās's Note in Graf Von Noer, Akbar, I 245 V. 342, l. 4. Yār 'Alt Turkomān. came as an ambassador from Sultān Muhammad Mirzā and from Shāh Tahmāsn

The ambassador was not sent by Shāh Tahmāsp himself, but by the Shāhzāda, Sultān Muhammad [Khudābanda], who was Governor of Khurāsān on behalf of his father at this time (A N III 5=Tr 7-8) He was the eldest son of Shāh Tahmāsp and had been the nominal governor of Herāt when Humāyūn passed through it in his flight to Persia (q v 217 ante).

V. 342, l. 2 from foot. 'Itimād Khān . . Mīr Abu Tūrāb, Saiyid Ahmad Bukhāri, ... Malik Ashraf and Wajhu-l-Mulk . came in to wait upon the Emperor

The Lath has the names more correctly and reads 'Hamid' for 'Ahmad', 'Maliku-sh-Shaiq' for 'Malik Ashraf' and 'Wajihu-l-mulk' for Wajhu-l-mulk'. (294,1 5) Cf also B (II 141, Tr. 145) who gives the names rightly See also Ibid II 219,1 13, Lowe 223 The reading of the second name in the Bibl Ind Text of the A N (III. 7) is Malik 'Mashriq' and Mr Beveridge thinks it must be 'Ashraq' (Tr III 10 note), but both forms are wrong and this person is correctly called 'Maliku-sh-Sharq'-'Malik of the East'-in the Mir at-i-Sihandari (Text, 377, 398=Tr Fazlulla, 270, 285) and also in Abu Turāb's Tārīkh-z-Gujarāt (56. 1 6) It seems preferable to rely on the provincial historians, as they were contemporaries who had seen and known the man personally Hajji Dabir also spells the name as 'Maliku-sh-Shara' and states that his real name was Muhammad Jiu Bābū. He describes him as a friend and protege of 'Itimād Khān who afterwards deserted him (Z. W 299, 891, 392, 431, 435) He is called 'Malik-us-Sharq' in the Mirat-i-Ahmadi also (Pt. 1, 116, 1 13, 120, 1 3) Malik-us-Sharq was a title given to nobles by the Sultans of Mālwā also

V. 343, l 15 Savyid Mahmud Khan Barha and Muhammad Bukhari brought their wives into the royal camp

The ladies whom these nobles brought were not their own wives, but those of the Emperor عدرات سرايرده عبت بيايه سرير اعلى آوردند (299, 1 14) "[They] brought the veiled ones of the pavilion of chastity (the Emperor's haiem) to the foot of the exalted throne" Lowe has translated the phrase correctly (II 145, Text, II. 141) The embassy which is mentioned on the line following was sent, not to a Rānā, but to the Rānā, scil, of Chitor. 'Ahmadnagar' (l 7 f f) is not the place of that name in the Dekkan, but Ahmadnagai or Himmatnagar [as it is now called], which lies 20 miles south of Idai It is mentioned again at 353 Note and 360 infra

y 344, l 5 from foot. Ibrāhīm Husain Mis zā was in the town of Sarnāl on the other side of the swer (Mahindri)

The B I. text of the A N calls it the river of 'Sakaner' or 'Bikani' (III. 18=Tr 18 and note), but the right reading must be a king.

Bankaner, i. e. Wünkiner. The river is the Mahi or Mahindri. Dowson suggests that 'Sarnāl' must be a mistake for 'Sinnole' [or Sīnor], but Sinor is an entirely different place from Sarnāl. The latter is a village, five miles east of Thasra, which lies on the Mahi, about thirty Kos south east of Ahmadibid. (Mirāt-i-Ahmadi, Text, Pt. II. 130, l. 2 f.f.). Mr. Beveridge says (A. N. III. Tr. 19 note) that Sarnil is not marked not the maps and seems to have disappeared, but this also is not correct. Sarnal still exists about five miles east of Thāsrā in Kairā district and twenty-three miles north-east of Nariād. (B. G. 1. i. 265). Thāsrā is a station on the Anand-Godhrā branc'ı of the B. B. and C. I. Railway, twenty-four miles from Anand. It is shown in Constable, 27 A d. Sinor is mentioned in the Ain as a pargana in the Sarkar of Baroda and it is explicitly said there that the Narbadā (nott he Mahi) passes under the pargana town. (Tr. II. 255). It is now in the Gāikawād's territory. Saenāl was in Akbar's Sarkār of Ahmadābād (Ibid, II. 253) and is now in British India.

V. 345, l. 15. Some of the enemy whose blood was up made a stand in

the street.

(295, 1. 2). "Some of that body of men whose hour of doom had struck," some of those doomed ones." They were men who had been caught in the toils of Fate and were doomed to perish.

The princes and the ladies of the harem...... were filled with joy enough to last them their

رعایت بین خبر فتح رسانید از شاهرادها و حضرات سرابردهٔ عنت سی جوں جو ای ناز بود (296, 1.5 f. f.). "When Surkh brought the news of the victory, he got so many gifts or presents from the princes and their Highnesses of the Imperial Harem, that he was enriched (lit. was without want) for the rest of his life."

V. 348, l. 4 from foot. There was near at hand in Surat a tank called

Recte, 'Gopi Talão,' as in the A. N. (III. 18=Tr. 25). Gopi was an Anavla Brahman who was the minister of Sultan Mahmud Begada and Muzaffar II. of Gujarāt. He is frequently mentioned in the Mirāt-i-Sikandari. (Text, 153, l. 7; 198-200; Tr. Fazlulla, 96, 131-3; Tr. Bayley, 249, 295-7). The Indo-Portuguese historian De Barros also speaks of him as 'Melique Gupi.' (Decadas. II. ii. 9). Alfonso Albuquerque calls him 'Melcupi' (Commentaries, IV. 60 f. f.) and Duarte Barbosa 'Milocoxim.' (Tr. Dames, I. 149). A very interesting contemporary Sanskrit poem written in his honour has been recently discovered at Baroda and published in the Journal of the Baroda Library Association. The Gopi Talao is now only a hollow used as a garden. It was certainly built by him, but the other local legends about his having founded Surat and first called it Surajpur appear to be unhistorical. (B. G. II. (Surat), p. 70). V. 350, note.

The plural is here used, but it would seem to only one

The plural seems to be used correctly and emendation is uncalled for Two big guns can be still seen in the Uparkot at Junagadh Major Watson tells us that near the mosque built by "Sultan Mahmud Begada in the Uparkot, there is a large cannon left by the Turks at Div and brought to Junagadh by Malik Eiaz by order of Sultan Bahadur Shah It is seventeen feet long, seven and a half feet in circumference at the breech and the diameter of the muzzle is nine and a half inches.

Another large cannon called Chudānāl, also from Dīv, is in the southern portion of the fort. It is thirteen feet long and has a muzzle fourteen inches in diameter" (B G VIII, (Kāthiāwār), 488) "An inscription on the first gun gives the name of the maker as Muhammad Hamza, who lived in the reign of Sultān Sulaimān, the son of Salimkhan" (Ibid) See also Mr Beveridge's note to A N (III Tr 41), where it is said on the authority of a MS of the Albarnāma in the British Museum, that "some of the guns were left in Junāgarh" Budāum says that most of the guns were brought into the fort of Sūrat by Khudāwand Khān and the remainder [La 4] were dragged by the Governor of Jūnāgarh into his castle" (II 146, Tr II 150) In his account of the siege of Junāgadh by the Khān 'Aram in 1000 A H, Abu-1-Fazl states that the "garrison" every day fired several times, a hundred guns, some of which shot shells weighing 1½ mans" (A N III 620, Tr 948-9) Some of these must have been those left behind by the ! urks

V 353, l 8 He ['Azam Khān] sent some Amīrs to M'amūrābād

This place is not easily identified, as no such name is now known All that B says of it is that it was on the Mahindri, i e the Mahi. (II 333, Tr 344) But it is stated in the Mināt-j-Ahmadi (Pt I 21, last line) to have been the Musalman alias of Jan This 'Khatnāl' must be an error for 'Kathlāl', which is now a railway station, seventeen miles north-east of Nadiād Elsewhere, the author of the Mināt states that M'amūrābād was twenty Kos east of Ahmadābād and had a fort on the spot where the Wātrak and the Majham unite (II 132, 1, 10) Nadiād is 29 miles south-east of Ahmadābād by the railway Kathiāl is entered in the Post Office Guide

V. 353, l 6 from foot At the town of Harbatpur, one of the dependencies of Pattan, he [Akbar] dismissed 'Azam Khan and the other amis to their jagirs

'Sītāpur'ın the Lith. (300, 1 5 ff) See also 369 infra, where 'Sītāpur near Kari' is again mentioned But the A N has 'Siddhpur' (III 33, Tr. 48) and so also the Mirāt-i-Ahmadi (Pt I 127, 1 4) Mr Beveridge thinks that it is right Siddhpur is about 12 miles north-east of Pātan. Pātan or Anhilwāra is 63 miles north of Ahmadābād (Th.)

V. 353, l 4 from foot Muzaffar Khān (late King of Gujarāt) i eceived the Imperial bounty. The sarkārs of Sāi angpur and Ujjain were taken from the Rāni and given to him.

There is great confusion here. The words in brackets are not in the text (300, 1.4 f.f.) and are an unwarranted and mislea ling interpolation. The jāgīr of two Krors and a half dāms in the Sarkārs of Ujjain and Sārangpur was not bestowed on the quondam Sultān of Gujarāt, but upon a namesake, viz. Muzaffar 'Ali Turbati (q. v. 237, 17), one of Akbar's Vazīrs. Cf. what Nizāmu-d-dīn himself says at 370 infra. Muzaffar Khān had been, some time before this, appointed governor of Mālwā. (A. N. III. 34=Tr. III. 48=E. D. VI. 42). B. states that Sultān Muzaffar Gujarāti was given a monthly pension of only thirty rupees (II. 149; Tr. 153 and 329, 1.6=Tr. 339). There is even worse in what follows. The Sarkārs of Sārangpur and Ujjain were not 'taken from any Rāni' before being given to Muzaffar Khān Turbati. The words of the text are مراح المراح المر

V. 355, l. 9 from foot. A party of Jhils who are fishermen dwelling about Multan, made an attack upon him.

The A. N. reads 'Balūchis' (III. 38; Tr. 53), but in the B. I. text of B. they are called Jata (Chahpal) (variant, Jata Jhūl). Lowe speaks of them as "Jhūls, a low class of Multān peasants". (II. 158; Tr. 162). The real name seems to be Jahbel, who are said to be "a fishing and hunting tribe of vagrant habits, living on the banks of the Sutlej in Multān district." (I. G. XVIII. 29). Mr. H. A. Rose also writes that the "Jhabels are a fishing tribe found in the Multan and Muzaffargarh districts..... They live mainly by fishing and gathering pabbans (seeds of the waterlily), say they came from Sindh and of all the tribes of the district, alone speak Sindhi". (Glossary of the Tribes and Castes of the Punjab, II. 380). V. 857, 1. 12. On arriving at the fort of Kutīla, he pitched his camp.

This 'Kūtila' or Kotla is situated on a steep ridge about thirteen miles eastward of Nūrpur and twenty-two miles north-west of Kāngra or Nagarkot. (Dr. Hirānand Shāstri in the Journal of the Punjab Historical Society, (1912), p. 141). 'Kotla' is registered as a Maḥāl in the Bāri Duāb Sarkār. (Āīn, Tr. II. 319). The name of the Rājā of Nagarkot was not 'Bidi' Chand as it is given at 356 supra or 'Bidai' Chand as it is written in the C. H. I. (IV. 103), but Vriddhi Chand. (Duff, C. I. 306 apud Arch. Surv. Rep. Vol. V. 152).

V. 358, l. 2. He encamped by a field of maize near Nagarkot.

قرب بباغ چوگان راجه رامچند که قریب نگر کوت است قرود آمد (303, 1.8). "Near the Chaugān garden of Rājā Rāmchand which is near Nagarkot". Dowson's Manuscript must have read باغ جو 'garden of barley'. But who plants barley or maize in a garden? The name of the fortress of 'Bhūn' (1.3) which had an "idol temple Mahāmāi" must be pronounced 'Bhavan', which means a temple dedicated to Shakti, also called Mahāmāya, Vajreshwari, or Devīshankar. (E. D. II. 445 and my note on Vol. IV. 544). The suburb of Kāngra in which the temple is situated is still known as 'Bhavan'.

V. 358, l 2 from foot The army was suffering from great hardships and the dogs in the fortress were anxious for neace.

This is a grotesque perversion of the real meaning with [Sagān] has been read instead of with [Sukkān], 'inhabitants, residents,' of the lithograph (303.14 f f.)

in this sense of 'inhabitants', 'occupants', 'tenants' is used by F. (II 307, 1 3 ff, 312, 1 15). It is the plural of 'Richardson' It is used in this sense of 'residents' in the Zafarnāma of Yazdi also (II 86, 1 4 ff., 123, 1.3 ff)

V. 360, l. 18. Hasan Khan Karkarah, the Shikkdar . . . fled to Ahmadabad

Recte, 'Karkarāq', which is made up of two vocables 'Kurk' or 'Kurg' is the fine short wool of the goat nearest the skin. It also means, 'fur' (Blochmann, Āīn, Tr. I 616) 'Kurk' and 'Barak' are also the names given to "certain soft, warm fabrics which are made of such wool of hair Both 'Barak' and 'Kurk' realise high prices, but the latter is finer in texture and consequently dearer" (I.G. Art on Afghānistān, Vol. V. 56) 'Yarāq' signifies 'garments, accourrements' Karkirāq thus signifies "woollen garments" and then "wardrobe" in general. See also Hawkins (E. T. I. 109). The sobriquet means that Hasan Khān, who is also called Khazānchi, had been formerly employed in the Wardrobe department.

V 362, l 3 from foot He [Akbar] took a short rest at Hans Mahal

This place lies on the route from Agra to Ajmer, a little north of Sanganer, which is about seven miles south-west of modern Jaipur (A N. II 242 Note) Toda, the immediately preceding stage, is Toda Bhīm, about 40 miles east of Jaipur Constable, 27 C b

V. 363, l 11 The night was bright moonlight

But what the lithogreph says is
"He [Akbar] travelled all night just like the moon" A similar phrase occurs in the Zafarnāma of Yazdi, who says that Tīmūr
"He [Akbar] travelled all night just like the moon" A similar phrase occurs in the Zafarnāma of Yazdi, who says that Tīmūr
As all night, he [Tīmūr] took no rest [continued to travel] like the moon." As Akbar left Fathpur on Sunday, the 24th of Rab'i II (A. N III 44, Tr 62) and left Ajmer on the night of Tuesday the 27th, te towards the end of the last quarter of the moon, there could have been no 'bright' moonlight, For 'Āsaf Khān Koka' (1 10) read 'Saif Khān Koka' The name is correctly given at 366 tafra

V.363, l 6 from foot. [Muhammad Khān was directed to join the party at] Bālīsāna, five Kos from Pattan

This should not be confounded with 'Mehsana', which lies eighteen Kos south-east of Pātan (Āīn, Tr I 486) 'Balisāna' is said to have been only five Kos from that town. It is really 'Bālisna' in the Kadi division of the Gāikawād's territories (I G s v) The Bibl Ind Text of the A N has the variants "Māliyana" and 'Pālitāna' (III 47, 1 20), both of which are wrong Mr Beveridge is for reading 'Maisāna,' (Tr III, 66 note), but

he cannot be right, for the reason already stated. The Mirāt-i-Ahmadi also reads 'Bālīsāna', (Pt. I. 130, l. 1).

Muhammad Quli Khān's Nisba should be read as 'Tuqbāi', as in the A. N. III. 54=Tr. 77, not 'Tūghbāni' as on 1.12. 'Tūqbāi' was the name of an Afghān tribe. (Blochmann, Tr. $\bar{3in}$, I. 403).

V. 365, l. 19. The feeling ran through the royal ranks, that it was unmanly to fall upon an enemy unawares.

"It was said by the inspired tongue [of the Emperor] that it was not proper for the brave to attack people who were ignorant and unaware" [of their approach]. It was the chivalrous sentiment or declaration of the Emperor himself, not the "feeling" of his followers. Cf. Text, 317, l. ō, where the phrase زیان المام یان is again used and it is said that "things happened exactly as the inspired tongue [of Akbar] had uttered".

V. 367, l. 4. His Majesty returned triumphant to his couch, which was placed at the edge of the battlefield.

"His Majesty alighted triumphantly on the top of a hillock which was situated on one side of the battle-field." B. says that Akbar "ascended a hill which skirted the field of battle." (Lowe, II. 171). Abu-1-Fazl states that Akbar took up his position on "a high ground, one Kos from the river." (A. N. III. 53; Tr. 76). F. also speaks of it as a in or mount, which was in the vicinity of the battle-field. (I. 261, 1. 12 f. f.). It is absurd to speak of a 'couch' in this connection. The interpretation of the lattle-field (I. 261, 1. 12 f. f.) and again on 368, I. 12 infra. Dowson must have read interpretation in the pushta.

V. 367, l. 14. Among the prisoners was a man named Mard Azmāi Shāh.

But this is an impossible name. He is called Shāh Madad, the Majzūb in the lithograph (309, 1.10) and in the A. N. also. (III. 59; Tr. 84). He was "the Mirzā's Koka and a partner with him in disloyalty." (Ibid).

V. 369, l. 5 from foot. Village of Pūna, three Kos from Sanganer.

The right reading is, probably, "is as in the A.N. (Text. III. 65, 1. Tr. 91). It is mentioned also in Abu-l-Fazl's account of Akbar's first journey from Āgra to Ajmer, as the next stage after Sāngāner. (A. N. II. 351; Tr. 510). Mr. Beveridge's conjectural identification of it with Lūni' or 'Būnli' near Ranthambor is, as a glance at any map will show, inadmissible. Sāngāner is about seven miles south-west of Jaipūr. Ranthambor is, at least, 75 miles south-east of it. (Th. 835). 'Būli' lies near Ranthambor. Akbar is said to have arrived at Hans Mahal after leaving 'Newata.' (A.N. III. Ibid). Hans Mahal lies a little north of Sāngāner. (See my Note on V. 362 ante.

. V. 371, l. 22. He [Akbar] remained till the 20th in the village of Dair.

B. also calls it 'Dāīr' (II 171, Tr 174). But the spelling is 'Dābar' in the A.N. (III 145, l. 2 f.f) and 'Dāyarmau' in the T. J (259, l. 4; Tr II 64). B. locates it at four Kos from Fathpur Sikri, with which Jahāngīr's account agrees Mr Beveridge votes for Dāīr (AN III Tr 206 note), but I am informed by a local authority that the correct form is "Dābar" It is now in the State of Bharatpur

V. 372, l 13. Sulaiman Kirani . died while the Emperor was engaged in his Surat campaign in the year 981

The exact date of Sulaimān's death is not found anywhere in the published literature relating to the reign of Akbar, but it is said to be given as 1st Ābān of the XVIIth year or 6th Jumādi II 980 (about 14th October 1572) in three MSS. of the Akbarnāma which are in the India Office and another which is in the British Museum (Beveridge's note, A. N III 5) Nizāmu-d-dīn states (348-50 anie) that the siege of Sūrat began about 18th Ramazān 980 (22nd January 1573) and that the fort capitulated on 25th Shawwāl (28th February 1573) The three statements are not compatible with one another and the real date is difficult to determine, but 981 H must be an error

As the tribal designation of Sulaimān is written in various ways as, خرانی فرانی می it may be worth while to state that on the coins of Dāud, the spelling is کردانی (Wright, I M C II. 128)

V. 373, l. 14. Lodi sent Daud this message. "You have never given me any good wishes or advice, but still I am willing to advise you"

It is obviously pointless, if not preposterous, to put into the mouth of Lody any such declaration as is made in the first part of this sentence Lody was the doyen of the Elder Statesmen of the Realm, Dāūd a youth of twenty, born in the purple, but without any knowledge or experience of affairs. What he really said was مرافع المرافع المراف

V. 375, l. 1. [Akbar stopped at the] village of Ratambh, one of the dependencies of Agra

n the Lithograph (315, l 11) The place intended is probably "Runkuta" which lies about ten miles from Agra on the road from Agra to Allahābād It is now a station on the G I P. Railway, about nine miles north-west of Agra As Akbar left Agra on Sunday, the last day of Safar and reached 'Ratambh' on the first of Rab'i I, 'Runkuta' which Jahāngīr also speaks of as the first stage and five Kos from Agra (T J Tr I 139=E D VI 316), would fit in very well See also the Ain (Tr II 180), where it is said to be a much-frequented place of pilgrimage near Agra. Religious fairs are still held there on certain days of the Hindu

calendar. (N. W. P. Gazetteer (1884), Vol. VII, 764).

V. 375, l. 16. On the 28th [Safar], he reached the village of Kori, a 539 dependency of Sayyidpur, at the confluence of the Gumti and Ganges.

The A. N. reads 'Godi' and 'Saijidpur' (III. 88; Tr. 125). Dowson says "Budauni has Jaunpur and he is probably right." But he seems to be mistaken. Akbar reached Valyāpur, one of the dependencies of Jaunpur, on the 2nd of Rab'i I, not on 2Sth Stfar. The T. A. (306, 1. 10 f. f.) and B. both say so. (B. II. 176=Tr. 179). Saiyīdpur is 23 miles north-east of Benares and about as many west of Ghazipur, on the left bank of the Ganges near its confluence with the Gomti (Godi). Lat. 25°-30' N., Long. 83°-18' E. See also I G. XXI. 384. s. v. Saidpur. Constable, 28 C c. V. 376, l. 11. His Majesty directed Saiyid Mīrak Ispahāni.........who

was learned in charms, to seek an augury in his books.

دائر علم جغر کرد (317, 1.11). "Who was perpetually making a pretence of proficiency in the science of Jafr." 'Jafr' has nothing to do with 'charms', incantations or amulets. It is really a Kabalistical method of vaticination, a 'Numerological' or Gematriacal system dependent on the combination and mutations of letters and numbers. Vide my note on IV. 124, 1. 2 f. f. ante. At A. N. III. 93, Tr. 131, the soothsayer is called "Sayyad Mīraki, the son of 'Abdu-l-Karim Jafari (diviner) of Ispahān". V. 376, l. 19. Isā Khān was slain by Lashkar Khān, one of the Em-

The lithograph states more correctly that the man who killed 'Isa Khān was not Lashkar Khān himself, but خان الكر خان one of his slaves. (317, l. 16). So also B. (II 178; Tr. 181) and A. N. (III. 93; Tr. 131).

Gangdaspur (l. 7) cannot be traced. What Abu-l-Fazl says is that the boats anchored at Daspur which is on the banks of the Ganges (III, 93, Tr. 130), but 'Dāspūr' also cannot be located.

V. 377, l. 17. Rājā Gajpati who had many armed adherents, was-diregi-

مستند مساد عمراه داشت (318, 1. 10). "And had a large number of Cheruhs and foot-soldiers in his train." B.'s words are, من عجون ور وملخ followers were numerous as ants and flies and Cherūhs and Pāīks." The B. I. text is corrupt and Lowe has wrongly rendered it as "a multitude of horses and mares." (Tr. II. 183). In the Nafaisu-l-Maasir, a Tazkira or 'Lives of the Poets' written by 'Alau-d-daula Qazvīni about 979 A. H., it is explicitly stated that Gajpati assisted in Akbar's invasion of Hājipur with a body of two thousand Cherūhs. (See Mr. Beveridge's Art. in J. A. S. B. 1905, p. 237. See also Ricu, Persian Catalogue III. 1022). These early references to this aboriginal tribe are interesting.

V. 330, l. 10. He increased his [Khān-i-Khānān's] military allowances

دنه کردنه (320, l. 11). Izāfeh-i Deh-si vea Deh-ehahi

really means 'an increment in the ratio of 10 to 30 and 10 to 40', that is, three-fold or four-fold B. uses the same words and Lowe renders them correctly, as "in the proportion of 10 30 and 10 40" (B Tr II. 185) Abu-l-Fazl states elsewhere that the allowances of all persons employed in Bengal were raised 50 per cent and 100 per cent (A N. III) See also my note on II 76. 1 20

V 33), l 8 from foot Muzaffar Khān . was sent with Farhat Khān, one of the late Emperor's slaves.

ورحت ان كه ار علامان وردوس مكابي ود (320, 14) "Farhat Khān who was one of the slaves of Firdaus Makāni" 'Firdaus Makāni' was the after-death title, not of the late Emperor, Humāyūn, but of the latter's father, Bābur Farhat Khān's original name was Mihtar Sakāi

V. 381, 7 2. He reached Fathpur Sahīna, which is twenty-one Kos distant from Patna

The lithograph has (Fathpur-Patna) (321, 1 1) The A.N. reading is the same and Akbar is said to have crossed here the Son which was in flood at the time. The next stage was Chausa (III 105, Tr 146). The place meant must be 'Fathpur-Bihiya' now in Ballia district, UP, on the direct road from Arrah to Buxar Bābur also halted here and mentions it in his Memoirs (B. N. Tr 662, 667 notes). Fathpur-Bihiya was a Mahāl in Sarkār Rhotās, Sūba Bihār, in Akbar's days (Āīn, Tr II 157). It "included the Duāba or tongue of land between the Ganges and Ghoghra rivers" (Beames, Art Geography of India in the Reign of Akbar, J. A. S. B. 1885, pp. 180-1). Bāyazid Biyāt says that the Ujjainiya Rājā Gajpati held Bhojpur and Bihiya as his Jāgir (Memoirs, Tr in J. A. S. B. 1898, p. 315). This Bhojpur is the place of that name in Shāhābād, Bengal Constable, 28 D.c. 'Behea' is now a station on the East Indian Railway, between Arrah and Buxar, 44 miles west of Patna Bihiya is shown in the I. G. Atlas, 29 B.2

V. 381, footnote 3 [Khān Khānān had taken Sūrajgarh and Mungu] with the help of Rājā Sangrām of Gorakhpur and Puran Mal of Kīdhūr (Akbar-nāma).

Sangrām was the Rājā, not of 'Gorakhpur,' but of Kharakpur. (A N III. 107, Tr. 150) Kharakpur is in the Monghyr sub-division of Monghyr district and is now part of the Darbhangā Estate Lat 25°-7′ N, Long 86°-33′ E. (I. G XV 246) Constable, 29 B c. Puranmal was the Rājā, not of 'Kidhūr,' but of Gidhaur (A N III 107, Tr 150), which is also in Monghyr district (I G Atlas, 29 C 2)

V 382, l 6 from foot He [Albar] presented to the nakāra-khāna of the Khwājā [of Ajmer] a pair of drums which had belonged to Dāūd

Some large drums are to be still seen in the shrine and it is stated in the I G. (V 171), in accordance, perhaps, with some local legend, that they were "taken by Akbar at the sack of Chitor" But doubt is thrown on the averment by the incidental but explicit testimony of Nizāmu-d-dīn, and its corroboration by B. (II. 185; Tr. 188). Mr. Vincent Smith, copying from Tod, (A.A.R. Ed. Crooke, J. 381-2) says that some 'Nakkāras,' eight or ten feet in diameter, and several massive candelabra were carried off by Akbar, from the shrine of the Great Mother at Chitor, (Akbar, p. 90), but he does not assert that they were given to or placed in the Khwāja's mausoleum.

V. 384, l. 11. Grain rose to the price of 120 tankas per man.

The lithograph reads is "Black Tangas." The monetary denomination 'Tanga' represents so many coins of widely divergent values and is used so loosely by the chroniclers, that it is very difficult to say what it stands for in a particular case. But this tanga-i-siyāh of Gujarāt was, most probably, the copper coin of the Sultāns of Gujarāt which weighed about 144 grs. and was valued at the hundredth part of an Akbari rupce. (Bayley, Tr. Mirat-i-Ahmadi, loc. cit. p. 6 and my paper on the 'Coins of the Gujarāt Saltānat' in J. B. B. R. A. S. 1922, pp. 46-8). V. 385, l. 4. [When Rājā Todar Mal] reached Madāran.

This is Bhitargarh-Madāran, eight miles north of Ārāmbāgh, in the Jahānābad pargana of Hugli district. It lies between Burdwān and Midnāpur, and as it was the frontier town on the Orissā border, it was the scene of much fighting in the 15th and 16th centuries. (Blochmann in J. A. S. B. XLII. 1873, p. 223 note: I. G. Vol. V. 398). It may be the is said by Minhāj to have been one of the chief towns of Jājnagar, but the situation of which has not been determined. V. 386, 1. 7. From Madāran, they marched to Jitūra.

"Jitūra" is an error for '53, Chatūa. It was a Mahal in Sarkār Madāran according to the Ain. (Tr. II. 141). 'Chitui' or 'Chitūa' is now in Midnāpore [Medināpur] near Ghattāl. (Beames, J. R. A. S. 1896, p. 107). Constable, 29 B d. It lies a little to the E. N. E. of Midnāpore town.

'Zarbzan', which is translated as 'swivels' on 1.5 f.f., seems to be really used here for a large field-piece. At p. 131 ante also, guns discharging stone-balls weighing 500 misgāls (about five pounds) and requiring four pairs of bullocks to drag them are called 'Zarbzan.' At pp. 175 and 350 ante, the same word is used for great "pieces which required 200 pairs of bullocks to drag them." B. calls "pieces of ordnance carrying balls of five to seven mans in weight" by the same name. (IL 107, 1.13=Lowe. Tr. 111).

V. 390, l. 6 from foot. The Emperor had from his early youth found pleasure in the assemblies of......men of imagination and genius.

اصحاب وجد و حال (322, last line) means "men who have themselves experienced the state of transport, rapture, or ecstasy, of union with the Deity"—mystics who had been able to attain to the union of the Individual Soul with the Universal. He means great Sūfis and Yogis.

V. 391, l. 20. The members of the assembly used to select a number of the most worthy among those present

This is likely to convey a fallacious and misleading impression to the modern reader The phrase used for 'the most worthy' is ادرات استحقاق It had a technical signification, which is not coincident with our connotation of 'worthy'. We have the authority of Abu-l-Fazl for saying that "it included four classes of persons, viz, (1) Inquirers after wisdom who had withdrawn from worldly pursuits, (2) Recluses and ascetics, (3) those who are weak and needy and poor, (4) Individuals of gentle birth who are unable to provide for themselves by taking up a trade" (Ain, Tr I 261) The three first classes included not only many really 'worthy' persons, but also the tens of thousands of mendicants and vagabonds of all sorts who preyed then and do so even now, in the name of religion, on the exiguous resources of the community and constitute a social nuisance. The fourth was, for the most part, made up of genteel beggars, sycophants and parasites of good birth, who sponged upon the State, because they were dependents and connections of the Emperor and his favourites or of other persons who were or had been formerly in power. Many of them were in the receipt of huge pensions and led lives of luxury and self-indulgence, if not vice and dissipation.

V 395, l. 16 At the end of ten days, in the month of Safar, 983 H, he [the Khān-i-Khānān] departed this life.

The month is wrongly stated. It was Rajab, according to the lithograph (331, 1 6) as well as B (II 217, Tr 221) See also 390 ante, where Mun'ım is said to have reached Tanda on the 10th of Safar 983 H (21st May, 1575 A C) The resolve to shift the capital to Gaur was taken subsequently, in the ramy season of that year (394 ante), with the disastrous results described in this paragraph Bayazid Biyat gives Monday, 18th Rajab 983 H. (A N Tr III 226 Note) and F (L 262, 1 4 f. f). has 19th Rajab 983 (23rd or 24th October 1575 A. C.) as the day of Mun'im Khan's demise Abu-l-Fazl says that it was the 15th day, Khur, Mah Aban of the Twentieth regnal year (Text, III 160, 1 1, Tr 226) But if 18th, (or 19th) Rajab is correct, fifteenth (بازدهم) must be an error for باردهم (eleventh) The 11th day of Aban was the 228th day of the Ilahi calendar, the initial day of which was 10th (or 11th) March It would be the 297th day of the Julian reckoning (228+69) and correspond with 24th October which was a Monday, as Bayazid states (Ind Ephemeris) 15th Aban would be 28th October which was a Friday

V 398, l 8 from foot Rānā Kikā came out of Ghāti Haldeo.

Haldi-ghāt lies about seven Kos from Gogunda, which is about sixteen miles north-east of Udaipur. (I G) The local derivation of the name is Haldi, turmeric, and supposed to be allusive of the yellow colour of the soil A F locates the exact site of the battle at the village of Khamnaur (or Khannaur), which lies at the mouth of the Haldi defile, a few miles north of Gogunda (A N. III. 174, Tr. 245) See also Noer. (Akbar, Tr I 247). Gogunda is shown in Constable, 27 A c A village named 'Kamnor' is shown north of Gogunda on the map prefixed to Tod's Rajasthan.

V. 399, l. 2. The enemy lost Rāmeswar Gwāliari and his son.

Rāmshāh [Sāh] in the Lith. (333, 1.5), which is correct. Both Rām Sāh and his son Shālivāhan are mentioned in the Dynastic List of the Tomar Rājās of Gwālior, which is inscribed at Rhotās. (Duff. C. I. 306). Rām Sāh and his three sons Shālivāhan, Bhān Sinha and Pratāp Sinha are all stated by Abu-l-Fazl to have been killed in this battle, at Haldighāt. (A. N. III. 175; Tr. 246). B. says that Rām Sāh was the grandson of the famous Rājā Mān [sinha]. (II. 232; Tr. 238).

. V. 400, l. 17. Dāūd, being left behind, was made prisoner.

cles داود در چهله معطل شده کرفتار کشت "Dāūd, having been obliged to remain stock still in a quagmire (or morass), was taken prisoner." Lowe says "his horse stuck fast in a swamp" [خلابی] (II .245; Text 238, l.13) and so also does the A. N. (Text, III, 162; Tr. 255).

V. 403, l. 4. He went along with Kalyān Rāi, a merchant (bakkāl).

Mr. Vincent Smith calls him a 'grain-dealer' and Mr. Beveridge, 'a shopkeeper' (A. N. Tr. III. Tr. 276 note), but he was really neither, and "Baqqāl" here really signifies that he was, by caste, a 'Baniya' Guj. Wānia, [of the Lād section]. Hemū also is called a baqqāl, q. v. my note on V. 241, l. 10 ante. Kalyān Rāi is mentioned also by Jahāngīr in his account of Cambay. (T. J. 206, l. 6 f.f.; Tr. I. 417). See my paper on 'The Old Parsi Settlement of Cambay' in the Journal of the K. R. Cama Oriental Institute, No. 8, pp. 6-14).

V. 405, l. 12. They attacked Muzaffar Husain Mirzā in the pargana of Nandarbār,.....who then went to Kambay.

The reading in the lithograph is 'Nariād,' (337, 1.4), which is correct. B. has 'Petlād' (II. 249; Tr. 249), which also serves to show that 'Nariād' is the place meant, as the two towns are in close proximity to and only twelve miles distant from each other. Abu-l-Fazl says that Bāz Bahādur came out with a force somewhere near Baroda. (III. 207; Tr. 292). Nariād is 35 miles north-west of Baroda by the railway.

V. 407, l. 4. The land of this place [Manoharnagar] was an ancient possession of Rāi Lon Karan.

Mr. Beveridge hazards the conjecture that 'Lonkaran' was not the real name of the Rājā, but a jocose nickname signifying 'Salt-maker', which was given to him, because he was the ruler of Sāmbhar, the site of the great Salt Lake in Rājputāna. (A. N. III. 295 note). But this is an instance of fanciful meaning-making, which is contradicted and disproved by concrete facts. Lūnkaran [or Nūnkaran] is a Rājput personal name which was borne by the Bhaṭṭi Rājā of Jaisalmir who was contemporary with Humāyūn and who is said to have tried to obstruct his passage through the Rājputāna desert. (A.N. I. 181—Tr. 375; Tod, A.A.R., Ed. Crooke, 1224-5; Duff. C.I. 291): It was also borne by a Raṭhoḍ Rājā of Bikāner who reigned from 1504 to 1526 A.C. (Tod, Ibid, 1132; Duff, C.I. 268, 273, 277). Lūnkaran Shaikhāvat was the elder brother of Akbar's favourite, Rāi Sāl Darbāri. (Tod. loc. cit. 1383).

V. 407. 1. 7. The town was called Manoharnagar after that child.

The original village, Mulathān, was a dependency of Amber. The town founded by Akbar still exists and hes about 28 miles N N E of Jaipur. (I G. XVII 200) There was another 'Manoharnagar' in Sarkār Nāgor, Sūba Ajmer, (Aīn Tr II. 277), while this 'Manoharnagar' was included in the Sarkār of Ajmer itself (Aīn, Tr. II. 277 and 272), Abu-l-Fazl states that the place near Mulathān in Amber was called Mūl Manohāragar, Old Manoharnagar, to distinguish it from its namesake near Nāgor (III. 221, Tr 311) Thornton's 'Manoarpoor', which was 132 miles south-west of Dehli and in Lat. 27°-19' N, Long 76°-1' E, is the 'Manoharnagar' founded by Akbar. Jaipur is in Lat. 26°-56' N, Long. 75°-55' E Thornton says that it had, in his time, a large bazar and was adequately supplied with water, though much decayed

Manohar's pen-name is wrongly given by Dowson as 'Tānsani' on 19. It was really , Tausani, from , a war horse, a high-blooded noble steed. (B II 252, Tr 259, see also *Ibid*, Text, III 201, 13) It has nothing whatever to do with Tānsen, the celebrated musician and poet The town founded by Akbar is shown as 'Manoharpur' in Constable, Pl 27 B b V 407. 1. 12. A comet appeared in the sky toward the east

Recte West, we as in the lithograph (339, 14) B (II. 240, Tr. 248) and Abu-l-Fazl both say that the comet appeared in the West (A N III 224—Tr 316) This is the comet about which Tycho Brahe discovered that it had no parallax and thence inferred that it must be situated at a greater distance than the moon (Fergusson's Astronomy, Ed. Brewster, II 355) It passed its perihelion on 26th October 1577 A C (Ibid) Abu l-Fazl gives the date as 25th Ābān Ilāhi of the 22nd year of Akbar's reign, which would correspond to 6th or 7th November 1577 25th Ābān is the 242nd day of the Ilāhi calendar which would correspond to the 310th or 311th of the Julian

V. 407, l 5 from foot He next halted at the Sarai of Bawali [after leaving Dehli]

Recte, 'Bādli' The 'dāl' has been wrongly read as a 'wāv'. The name is correctly written on E D. VIII 320, and incorrectly on Ibid, 271. There was a great Serāi here which is frequently mentioned in the old Itineraries (Chihār Gulshan in I A xcviii, Hearn, Seven Cities of Dehli, 168) Bādli Ki Serāi is now a railway station, nine miles from Dehli Junction Mr Beveridge's conjectural identification of it with 'Bāwal' in Rewāri (A N. Tr III 322 note) will not bear examination There is a Branch Post Office in the village of Bādli (Post Office Guide)

V 407, l 5 from foot. He [Akbar] was waited upon by Hazi Habibulla.
who had gone to Europe and had brought with
him fine goods and fabrics

حامی حسر الله از ولایت وریک مالس امتمه و اقسه و اساب آنولایت از تطر اشرف (339, 1 13). The original statement is somewhat loosely worded, but there is nothing like the categorical assertion that he had gone to Europe

The fact is that he had been sent only to Goa by Akbar, in the Twentieth year (982-8 H). Abu-l-Fazl states that he was "ordered to take with him a large sum of money and the choice articles of India to God and to bring for His Majesty's delectation, the wonderful things of that country." (A. N. III. 146, l. 9; Tr. III, 207). His return in the Twenty-second year, (985), is also recorded by the Imperial historiographer, who reiterates the fact that he had been sent to the nort of Goa. (III. 228, l. 13; Tr. 322). As Budauni has copied the T. A. and his translator, Lowe, also speaks of the organ having been brought along with other curiosities by Habibu-lla 'from Europe', (Tr. II. 299), it is necessary to stress the fact that the Hiii had gone only as far as Goa. ولات فرنگ is used here for the territory occupied by the Firingis in India, i.e. the Portuguese possessions on the West Coast. Elsewhere, Abu-l-Faul writes that one of the events of the 24th year of Akbar's reign was the "appointing of an army to capture the European ports " إبندر فرنك]. (III. 280: Tr. 409). He means Daman and the ports near Surat which had been seized by the Portuguese.

V. 408, l. 13. The Mauludnama or horoscope of His Majesty.

This is an important passage and it would have been better if Dowson had given a translation, instead of this summary dismissal in a single line, as it has some bearing on the question of the date of Akbar's birth and his lagab, which has been recently revived by Mr. Vincent Smith. The purport of the passage is that Mīr 'Ali Akbar Mashhadi presented to the Emperor a document in which the exact time and place of his birth was recorded in the handwriting of Qāzi Ghiyāṣu-d-dīn Jājarmi, a man of great learning, who had been for many years in the service of Humāyūn. In this Maulūdnāma, it was also stated that Humāyūn had a dream on the night of Akbar's birth, in which he had been directed to name the child Jalālu-d-dīn. (Text, 339, 1.8 f. f.). A very similar story is told by Gulbadan (H. N. 48, 1.7 f. f.; Tr. 145) and by Abu-l-Fazl (A. N. I. Tr. 42).

V. 409, 1. 9. In these days, there was a reservoir.....twenty gaz long by twenty broad and three gaz deep.

This must be the Anup Talav of B. (II. 201, 208, 215; Tr. 204, 212, 219) and the A. N. (III. 246; Tr. 354). Jahangir mentions a similar tank, called Kapur Talav, (T. J. Text, 260, l. 26; Tr. II. 68-9), but he gives the dimensions as 36 cubits [5.2] in length, 36 in breadth and $4\frac{1}{2}$ in depth, while Abu-l-Fazl makes it twenty gaz by twenty, but twice a man's height in depth. The site of the Tank is consequently uncertain, though there is a tank at Fathpur-Sikri, the dimensions of which exactly agree with those given by Jahingir, viz. 95 feet and 7 inches square, which would be just equivalent to 36 Ilāhi gaz at 31.8 inches to the gaz. (95 × 12) +7 = 1147 inches. 1147÷31.8=36. (Arch. Surv. Rep. XVIII. 1894).

V. 410, l. 5 from foot. Hakim Abu-l-Fath and Patr Das [were] to discharge jointly the office of Diwan.

According to the Lithograph, (341, l. f.f.), the Hakim was appointed 'Sadr,' Chief Judge and Almoner, while Patr Das and Mir Adham were

nominated Joint Diwans. B. (II. 267, Tr. 276) and the AN (III. 265, Tr. 386) are in agreement with the lithograph.

Patr Das's name is written wrongly in the T. A. as well as the A. N. It was really 'Tipar Das', which is a short form of Tripuraridas, 'Servant of Tripurāri' (or Tripurahara), an epithet given to Mahādeva, who is said to have destroyed the Asura, Tripura. He is the 'Tipperdas' of Ralph Fitch, "England's Pioneer to India," who passed through Patna in 1586 and writes of him thus, "He that is Chief here under the King (Akbar) is called Tipperdas and is of great account among the people" (Ryley, Ralph Fitch, p 110, Foster, E. T. I 24) The name is written correctly as with ב for the initial letter no less than four times, in the Bibl Ind Text of Budauni (II. 281, 11 3, 5, 8, and 282, 1 3) It is true that Lowe calls him 'Patr Das' (Tr II 289, 290) and says 'Tapar' is wrong, but it is quite right.

V. 413, footnote See Inshā-z-Abu-l-Fazl, Daftar IV

Dowson says that the Letter to Abdulla Khan is printed in the Fourth Volume of Abu-l-Fazl's Inshā or Letters, but only three volumes or daftars are known to have been published It is true that Amīr Haidar Husaini Wāsiti Bilgrāmi, the author of the Sawānih-2-Akbari (qv E D VIII, 193) speaks of four daftars of the Insha and notes also that the fourth is exceedingly rare, (Rieu, III. 930), but no copy of it is extant and Dowson is not likely to have seen any Mr Beveridge states that the letter under notice which was sent with Mirzā Fulād and Khwaja Khatīb is not found any where in the Lithographed Edition of the Insha (A N Tr III 394 Note)

V. 414, l. 16 [Muzaffar Khān] demanded the dagh (brand-tax) and brought old practices up again.

Enforced the (344, 1 2 ff) "Enforced the regulations relating to the branding (of all horses brought to the muster) and demanded the reimbursement of all past arrears or outstandings, [the payment of old debts and settlement of old accounts, i e refunds of the excess revenues of their Jagirs]. (Cf B. II Tr 288, Text, 280) 'According to the A N, he " made up all accounts from the beginning and instituted heavy demands" (III 293, Tr 431) for arrears and outstandings The 'dagh' was not a 'tax' but the 'brand' or 'system of branding.' V 414, l 20. The pargana of Jalesar was taken away from him.

It is also called 'Jaleshwar' [God of the Waters] and 'Jellasore' Medinipur [Midnapore] was included in the Sarkar of Jalesar (Ain, Tr II. 126 n and 142) The town is 49 miles south of Midnapore and contains an old mosque and also a ruined mud fort of great extent Lat 21°-46' N., Long 87°-14' E (Th) It is now in the Balasore district (I G. XIV 7). Constable, 29 B e

M'asum Kābult, who after the insurrection, V 415, l 2 from foot obtained the name of 'Asi,

The point of the word-play, the credit of which is ascribed to Akbar, (A. N. Tr. III. 471 Note) is not clearly brought out in the translation. It turns on the antithesis between ("Aṣūm and "Aṣī. The first means "sinless, innocent, guileless, saintlike"; the second "sinful, guilty, rebellious, seditious". He is called 'Āṣī M'aṣūm' at 416 infra and 'Āṣī Kābuli' at 417, 1, 20.

V. 416, l. 1. M'asûm Kābuli (and).......'Arab Bahādur and Sufaid Badakhshi resolved to rebel.

'S'aid' in the Text (345, 1.8 f. f.) and B. (II. 282; Tr. 290). He is called Sa'id at 426 infra, and also in the A.N. (III. 285; Tr. 418; 305; Tr. 451). Mr. Beveridge thinks that 'Safed' must be right, as "in the couplet quoted by B., the name of Bahādur's father is given as 'Isfed,' which is another form of Sufed." (A.N. III. 549 note). But Budāuni himself always calls him Sa'id (II. 196; Tr. 199; 282, Tr. 290), and also confesses his doubts about the genuineness of the distich. The statement about his father having been a 'Sultān' is, moreover, such an impudent and mendacious vaunt that the 'Bait' (B. II. 297; Tr. 308), must be a fake.

The nisba of 'Jan Muhammad', (line 20), should be read as 'Bihsūdi' not 'Bihbūdi'. (A. N. III. 301, Tr. 449). Bihsūd is a small town which is also called 'Basāwal' and 'Deh-i-Ghulāmān'. (Raverty, N. A. 45). It lies north of Jalālābād on the opposite side of the river and is shown in the I. G. Atlas, Pl. 47, F3. He is wrongly called Khān Muhammad Bahsūdi at E. D. VI. 40. The first name is Jān. Lowe has Jān Muhammad Khān Bahbūdi, (B. Tr. II. 290), but it must be an error.

V. 417, l. 12 from foot. Rājā Todar Mal had no confidence in the cohesion of the adventurers composing the enemy's ranks.

The 'adventurers' were the mercenaries and free lances in his own army, who were ready to turn coats at any moment. راجه تودرمل برسيا مان برسيا مان راجه تودرمل برسيا مان برسيا مان راجه تودرمل برسيا برسيا برسيا مان راجه تودرمل برسيا
V. 418, l. 9. 'Arab Bahādur.....scized upon the city [Paṭna] and appropriated the treasure.

He did nothing of the sort. He merely marched towards Patna [
in the hope of capturing the city and the treasury by a coup, but was overreached and had to raise the siege and beat a hasty retreat. See B. (II. 283; Tr. 292) and also Abu-l-Fazl, who says that 'Arab "took to brigandage and tried to plunder the treasure which Chaudhri Kishna was conveying to the Imperial army, but was foiled by the Chaudhri, who

arrived safely at the fort of Patna." (A. N'III. 321, Tr 470).

V. 419, l. 9 from foot. The sharp practice of the Diwan [Shah Mansur] having been repeatedly mentioned to His Majesty.

severity in connection with financial transactions had been repeatedly brought to the notice of His Majesty." Abu-l-Fazl says that Shāh Mansūr was "always laying hold of trifles in financial matters and displaying harshness". (A.N. III. 342, Tr. 501) B. states that Todar Mal complained of the exactions of Mansūr who had "written exceedingly harsh and threatening letters" to M'āsūm Khān and others, demanding large sums as arrears due from them. (II Tr. 295) There was nothing "sharp" about his "practices" The real complaint against him was that he had cut down by half the extra allowances which had been granted to the officers serving in Bengal and Bihār and made exacting and vexatious demands for the refund of all amounts in excess of the reduced scale of allowances, which they had drawn from the Jāgurs.

V. 420, l 18. Neyābat Khān [rebelled in] his jāgir of Jausa and Pravāg.

Recte 'Jhusi', which is also called 'Hadiabas' The lithograph has it right. (348, 1 6 f. f) It has nothing to do with 'Jausa' or 'Chaunsa' near Buxar It lies just opposite to Prayag or Allahabad. (Constable, 28 C c).

For 'Kantal, one of the dependencies of Patna' on 1. 6 f. f., read "Kantat, one of the dependencies of Bhata", ie Bhatghora, the old name of Baghelkhand or Rewā See my note on Vol. V 94,111 ante B reads 'Gasht', (II 289; Tr. 298), which is due to a dislocation of the nugtas of Kantit 'Mr Beveridge says (A. N. III 636 Note) that 'Bhath' is "another name for 'Panna' in Bundelkhand", but this is an error. The two places are quite distinct

N 422, l. 7 from foot Malik 'Ali brought him a letter to the following effect

The context which follows clearly indicates that there is some error or madvertent omission here. What Malik 'Ali said, when handing over the papers, had no reference to their contents. It related only to the circumstances under which the packet containing the letters had come into his possession. The paragraph beginning "When my scouts were coming to upto 'brought to me' (p. 423, 1.3) expresses what Malik 'Ali, who was the Kotival or Chief of Police, said by way of preamble or introduction. He had not read the missives. It is explicitly said that they were sealed and afterwards opened by the Secretary (423, 1.3 infra).

V. 423, l 16 So the Emperor gave the orders for his [Manşūr's] execution and he was hanged next morning.

B. says that Shah Mansur was hanged near the Manzil [Stage] of Kacha Kot. (II. 293; Tr. 301). Abu-l-Fazl calls it the Serai of Kot Kachhwa (A. N. III. 343, Tr. 503). Thornton mentions a village called 'Kotekutch-

wah', on the road from Karnāl to Ludhiāna, about 45 miles north-west of the former. Lat. 30°-17′ N., Long. 76°-53′ E. (See also Sarkār, I. A. p. c.).

Monserrate, Abu-l-Fazl and Firishta speak of Mansur's guilt, as if it had been proved to their satisfaction, and ignore the allegations in regard to the spuriousness of the letters. Nizāmu-d-dīn and Budauni appear to have been convinced that the last letters, which sealed his fate, were forged, even if the earlier ones were genuine. Among modern authors, Von Noer, in spite of his almost Boswellian admiration and partiality for Akbar, admits that the Emperor "unwittingly committed a judicial murder (Akbar, II. 55)", while Mr. Vincent Smith believes that Mansur had been really "guilty of sending letters of invitation to Muhammad Hakim in 1580 and that he actually was the head of the treasonable conspiracy. as stated by Monserrate." (Akbar, 197). In the Note appended to his translation of the A.N. published in 1913, Mr. Beveridge had taken up a noncommittal attitude and merely stated that "the story of Shah Mansur was a sad one and threw a lurid light on the morals of Akbar's officers." (A. N. Tr. III. 504-5). But he appears to have subsequently changed his mind and arrived at a positive opinion in favour of his acquittal. (J. A. S. B. New Series, XI. 1915, p. 203 ff.). Sir Wolseley Haig says that "there can be no doubt of his guilt, for Akbar fully appreciated his past services and deeply regretted his execution "(C. H. I. IV. 127), but this looks like a non-sequitur, Nobody says that Akbar did not believe him to be guilty when he gave the order. The point is, was that belief justified by the real facts.

V. 424, l. 4 from foot. Mirzā Muhammad Hakīm issued forth to the city of Khurd Kābul.

Khurd Kābul lies about twenty-two miles east of Kābul, on the road to Attock. (Chihār Gulshan in I. A. ciii). The distance from Attock to Jalālābād, which is said to have been traversed by Nizāmu-d-dīn Ahmad in one night and a day and reckoned as 75 Kos (l. 18), is really about 120 miles. (Ibid, cii-iii). This shows that the Kos is the Kachchā Kos of about 1½ miles.

V. 425, l. 13. [Akbar] remained there [at Kābul] for twenty days.

The lithograph reads is seven'. (351, l. 15). B. has is a week' (II. 294; Tr. 303) and F. also makes it seven days. (I. 264). The A. N. states that Akbar entered Kābul on 29th Amardād and left it on 6th Shahrīvar. As Amardād had 31 days, he must have stayed for seven or eight days only. (III. 367—Tr. 539). Monserrate also declares that he stayed for seven days. Dowson's Ms. must have read instead of a common error.

V. 429, l. 5. It was known that 'Asi Kābuli was in the country of 'Aisi.

معلوم شد که عاصی کابلی در و لابت عسی میباشد (354, 1.4). This 'Aisi is not the name of a place, but that of a person, and should be pronounced as 'Isā. 'Īsā Khān, the ruler of Bhāṭi, was one of the Bārā Bhūiyās, the twelve great Zamīndārs or territorial rulers of Bengal.

V. 430, l. 1. 'Itamād Khān was ordered to take away the country of Sirohi from Sarmān Deori and to give it to Jagmāl, his

brother.

The lithograph has سرتان ديون (355, l 11). 'Sartān Deoda' was the Rājā of Sirohi. The Deodas are a branch of the Chauhāns At A. N. III. Tr. 278, 545, 614, he is called Sultān, but the real name was 'Sartān.' The phonetic resemblance between this and the Arabic 'Sultān' is delusive Jagmāl was the brother of Rānā Pratāp of Chītor and not of Sartān Deoda (A. N. III 413, Tr. 613, Tod, A.A. R. Ed Crooke, I. 384-5).

Qanbar Beg is called 'Ishang Ākā,' on l. 6, but 'Aıshik' or 'Ishik' Āqā' would be more correct. He was "Lord or Keeper of the Gate," i.e. Chamberlain. See my note on IV. 231, l. 9 f.f. ante On l 12, 'Aghzan Khan' is a mistake for 'Ghazni Khān' [Jālori]. See Text, 355, l 14, B (IL 345; Tr. 346).

V 430, l. 5 from foot. He [Shihābu-dīn] told me that they would receive no encouragement or help from me.

mutinous troops] will not be conciliated or pacified by any words of mine and it will be also impossible [lit. inconceivable, unimaginable] for me [Shihābu-d-dīn] to give him ['Itimād Khān] any assistance" Lowe also has misunderstood the passage. (B II Tr. 337) He puts the answer wrongly into the mouth of 'Itimād Khān and says that he "would not accept the assistance of Shihābu-d-dīn, who had the means of quieting these people" V 430, footnote. Abul Fazl says he [Muzaffar] was an obscure individual named Tannū

The original name of Sultān Muzaffar III is written in at least three other ways, viz 'Nannū' or Nanhū. (A. N II 370, Tr II.507, III.409; Tr. 603, Mirāt-i-Ahmadi, Pt 1, 101, ll 10, 13). Abu Turāb (Text, 52, ll. 8, 13, 15), Jahāngīr calls him Nabū (T. J 212-3; Tr I 429, 431) and Blochmann, 'Nattū' or 'Natthū'. (Aīn, Tr I 325) Whichever is right, 'Tannū' is wrong According to Jahāngīr, 'Itimād Khān afterwards confessed to Akbar that Muzaffar was the son of a carter, (ill) (loc cit) Abu Turāb states that his father was a least [blacksmith] and tells a queer story about his birth in the palace of Sultān Mahmūd III which is neither worthy of credit nor of repetition Budāuni avers that the Kāthi who gave him shelter were his mother's relatives (II 327=Tr 337)

V 431, l. 15 He left his own son with Amir M'asum Bakhari and my son and started

Recte, 'Mir M'asum Bhakkarı' He was not an 'Amir,' but a 'Mir', an honorific title reserved for descendants of the Arabian prophet Mir M'asum, the author of the Tārīkh-i-Sind, was descended from the famous saint Hasan Abdāl and the Sayyıds of Sabzwār (E. D I 239 and my note).

On 1 5, the word translated as "Some Kāthīwār people" is Kāthīān, in the original (356, 1.1) It means 'Kāthīs' which is the specific name of one only of the numerous tribes who occupy the province. They constitute a very small part of its population. Lowe commits the same error, (B. Tr. II. 338).

V. 432, 1. 21. He sent forward his men to the town of Jhotāna, twenty Kos from Pattan.

Mr. Beveridge, relying on Blochmann (Ain, Tr. I. 518), says this should be 'Chotāna' (A. N. Tr. III, 9 note), although the Bibl. Ind. Text of the A. N. also has 'Jotāna' repeatedly. (III. 6, 7, 418). But the correct form is 'Jhotāna.' It is now a station on the Mehsāna-Viramgām-Waḍhwān Railway line and lies about twelve miles from Mehsāna Junction. The name is spelt Jhotāna in the Post Office Guide also.

V. 433, l. 8 from foot. Then, at the instigation of Tarwāri, Zamīndār of Pipla, he [Qutbu-d-din Khān] was put to death.

B. speaks of the chief as 'Nawari' and the place as 'Rajpipla' (II. 331, 1. 3; Tr. 341), but the Lithographed Text of the T. A. reads زواری (357, 1. 14). The designation 'Tarwari' has not been elucidated either by Noer, Beveridge or Vincent Smith. The clue to a solution is found in the dynastic history of the Rājās of Rājpīpla or Nāndod. They are Gohel or Gehlot Rājputs descended from Mokherāji Gohel of Pīram island, who was a contemporary of Sultan Muhammad Tughlag. (Bombay Gazetteer, VIII. (Kāthiāwār), p. 388; Forbes, Rās Mālā, I. 307-9). When Udayasinha of Chitod fled before Akbar, he sought shelter in Rājpīpla and Bhairavsinhji, the Rājā, gave refuge to the head of his house in defiance of the Emperor. Bhairvasinha was succeeded by Prithvirāj, a weak and inefficient ruler who left the administration solely in the hands of a Surat Brahman, named Ganpatrām Travādi. Travādi [Trivedi] was the surname of this allpowerful minister and as the Rājā himself was a puppet whose authority had been usurped by this Travadi, the Mughal chroniclers mistook the matter and have confused the Diwan with the Raja. (Narmadashankar, History of Surat in Narma Gadya (Gujarāti); [Sir] Manubhāi N. Mehtā. Hind Rajasthan, 737).

V. 434, l. 20. [Muzaffar left] the charge of the fort of Broach to Nasīr, his brother's son, and Charkas Rūmi.

Nasir was his wife's brother xclicic (Text, 358, 1.4). B. (II. 332, 334; Tr. 342, 344) spells the second name as 'Jarkas', which may be also read as Jargas, Jargis, or Jurgis, and may be forms of the Greek 'Georgeos'. Abu-l-Fazl calls him Charkas Khān in the chronicle of the 18th year and states that he was in the service of Akbar. (A. N. III. Tr. 34). He had afterwards deserted and joined Muzaffar. He also makes Nasīr the brother of Muzaffar's wife. But 'Charkas Rūmi' may mean that he was originally a "Circassian from Rūm".

The reference to Pāyanda Muḥammad Khān on l. 7, as one of the commanders under Mirzā Khān in this expedition is interesting. He may be Pāyanda Muḥammad Ghaznavi, who translated the first part of the Memoirs of Bābur into Persian in or before 994 H. Pāyanda Muḥammad Ghaznavi was the brother's son of Ḥājji Muhammad the son of Bābā Qashqa Mughal. (A. N. Tr. I. 390 Note).

·V 435, l 10 [Muzaffar's force again rose to] ten thousand men.

The number is given as 'two thousand' in the lithograph (358, 17 ff.) and B (II. 334, Tr 344) As the A. N also has 'two thousand' (III 428, Tr. 940), 'two' must be the right reading.

"Wāsad" [unb] (l. 15), is written as you, 'Basad' in the A N and Mr Beveridge thinks it must be 'Waso' (III, 640, note), another town in the same part of the country. But as 'Wāsad' is explicitly said to be on the Māht and 'Waso' is not so situated, he cannot be right. Wāsad is about 13 miles north of Baroda and 10 south of Anand. The river Mahi is crossed near it by a great bridge built by the B B and C. I Railway Company. Vāso is 15 miles from Petlād, and is a station on the Gāikwād's Baroda Štate Railway.

V. 438, l. 5. He [Muzáffar] gave a sımılar sum to Jām Māršāl, Rājā of Jhālāwar.

"Tarsāl" in the lithograph. (356, 1 6). Both forms are wrong The Jam's name was 'Satārsāl' and he was the ruler, not of Jhālawār, but of Hālāwār of Hālār—the province or division of Kāthiāwād ruled by the Hālā clan of Jādējā Rājputs, to which the Jāms of Nawānagar belong. B (II. 370; 373, Tr. 384) gives 'Satarsāl,' which does not merely look correct, as Dowson says in his Note, but is undoubtedly so Jām Satarsāl is mentioned as 'Jām Sahtā', at E D I 268, l. 21, g v. my Note. He reigned from 1569 to 1608 A. C (B G VIII, (Kāthiāwār), 567-9).

V 439, l 3 Muzasfar proceeded to a place called Othaniya, which is situated between the Sabarmati river and the mountain defiles

Othaniya or 'Asniya' (B. II. 359; Tr 371) which is said to be four Kos from Paranti [j] and thirty Kos from Bijapur [Vaijapur] cannot be identified. Bijapur (l 11) was a Māhāl in Sarkar Pattan. (Ain, Tr II. 254). It is now a Railway station 39 miles distant from Kālol. It is shown on Bayley's map about twenty miles north-west of Parantij

This Hadāla (l. 7), is not Hadāla in Kāthiāwād, but Hadāla Bhāl, which is a Railway station, thirteen inles distant from Dhandhūkā and about sixty from Ahmadābād

V. 440, l 2 Supported by the people of Kāthīvār and the Zamin-dars, he [Muzaffar] collected an army

Here again, the word in the text is Siril (361, 14), te Kāthīs. When Nizāmu-d-dīn says on 1.7, that he himself marched to Sūrath, he uses that toponym in its original and narrow sense of the district round about Junāgadh and Bāntwa (B. G VIII 4, 6), and not the later one of the whole of the Peninsula Muzaffar's principal adherent and devoted protector was Lumbhā Kāthi, the zamīndār of Kherdi, a village eight miles east of Rājkot (B. G. VIII 513) Lumbha was his personal name

This may indicate that Budāuni's statement about the Kāthis having been his mother's relatives (خونشان مادري) is not without foundation. This man's name appears in the perverted form of 'Lohīkathis' in the AN.

(Text. 410, 434; Tr. 608, 633). Mr. Beveridge's suggestion that "the name refers to their living near the sea and making salt" (A. N. III. 608 Note) stands in no need of comment and may be safely dismissed as untenable.

V. 440, l. 15. Muzaffar.....crossed the Ran, which is an inlet of the sea, and took the road to Jessalmīr.

The littliograph says that Muzassar went to Kachh ... (361, I. 12). But Budāuni states that he "crossed the marsh of the Ran, (which is separated from the salt sea by a distance of from ten to thirty cosses and entering the sandy desert of Jaisalmār there, loses itself), and came into the district of Kachh." (II. 344, I. 10; Tr. 355). This shows that the blunder about "taking the road to Jessalmār" is due to some words having been missed out by the copyist. The entrance into 'the sandy desert of Jaisalmār' is predicated of the Ran and not of Muzassar.

V. 443, l. 16. A feud arose between Rāyāt and Sāyat, nephews of the Chief of Khengār.

Delete "of". Khengār is not the name of a place, but that of the Rājā or Rāo who was ruling in Kaehh at this time. He died in 993 A. H. 1585 A. C. (A. N. III. 472; Tr. 711). 'Sāyat' is written 'Ṣāḥib' — in the lithograph (363, l. 7) and also in the A. N. (III. 464; Tr. 700). 'Rāyat' is called Jasā in the B. I. Text, but 'Rāyib' in the T. A. and in some Mss. of the A. N. (Tr. Ibid, Note).

On line 3 f. f. i. is again translated wrongly as "people of Kīthiīwār." On page 415 infra, Dowson himself speaks of 'Kāthis and Jhārejas'. See also B. II. 359; Tr. 371 and Note.

V. 444, l. 19. His opponents found their opportunity and encouraging their followers, they drew near him.

They did not 'encourage' their own followers; they corrupted his [Riisinha's] adherents by bribery and made them traitors to their master. ور اين مان آن مرد مهر اهان او دلاسا كر ده بجانب خود كشيدند (363, 1. 9 f. f.). "Meanwhile, those men [his enemies] won over his associates (or followers) and brought them over to their own side". Abu-l-Fazl's account of Rāi Sinha Jhālī's adventures differs in several details from Nizāmu-d-dīn's, but is in substantial agreement with it. (III, 464; Tr. 700). For the local version of Rāi Sinha's adventures, see B. G. VIII. 425-6.

V. 444, l. 15. [Muzaffar] came to Amarūn, where the tomb of Dāwaru-l-Mulk is.

'Āmbran' lies about 8 miles north-east of Bālambha and 16 north-east of Joḍiā in Nawānagar or Jāmnagar State. Dāwaru-l-Mulk was a noble of Sultān Maḥmūd Begaḍa, who was assassinated by a Rājput in 1509 A.C. and is now regarded as a martyr or saint. (B. G. VIII. (Kāthiāwār), 356; Mirāt-i-Sikandari. Text, 135-8; Tr. Bayley, 231-233).

On 1. 10 f.f., the Jām is said to have "sent his son to make excuses for his cruel treatment of Rāi Singh", but the real meaning seems to be that he pleaded in justification of his destruction of Rāi Sinha, the relation of the violent [outrageous or iniquitous] behaviour. الماري ا

(363, 1 2 f.f). خواست

V 445, l. 12. Muzaffar had gone to the village of Akhar, which was four Kos [from Biramaam]

This village still exists and is called 'Aghar' A local authority informs me that it lies about five miles from Virangam town.

'Jhajusa' (1.23) which is said to have been situated near the water of the Ran of Kachh, is spelt as محوبه 'Janjvania' or 'Jajvania' (Text, 364, 1. 14). It must be 'Vavaniya', a seaport now belonging to Morbi, situated on the Gulf of Kachh, which is about twelve miles south-west of Māliā and twenty-four miles north-west of Morbi (B G (Kāthiāwār), VIII 684) It should be noted that the 'Malia' mentioned here and also on the page following, is not Māliā Hāttinā, but 'Māliā Miyāna' It is situated on the west bank of the Machhū river, about 24 miles south of the Ran. (To 539) Māliā Hāttinā is about 32 miles south of Junāgadh.

V. 445. l. 10 from foot The Zamindars of Kach collected a force under the command of Jasā and Bajāin, nephews of Khangar

is a misreading of عان 'Pachanau,' [Panchanana], which is the name given by Abu-l-Fazl (A N III 524, Tr 799 and 530, Tr 808) Another man of the same name is mentioned as an auxiliary in A. F.'s account of the expedition against the Yusufzais (A N III 475, Tr 716 and 611, Tr 934) In Hindu mythology, 'Panchanana' is one of the epithets of Mahadeva The god's image has five faces and in each face, there are three eyes (Ward, View of the Religion of the Hindus, 3rd Edition, 1817, I. 232, Wilkins, Hindu Mythology, 236-7) Pachan or Pachanan is a not uncommon name even now in Kāthiāwād

We burnt and destroyed Kart and Kataria, two well known V 446, l 2 places in Kachh

"Karı" [کیدی] is really 'Gedi,' [کیدی], a village in the north of Vagad It is one of the oldest towns in Kachh and is mentioned in an inscription of V.S 1328,1271 A C, as 'Ghrita-ghadya,' and described as the principal place of a large district under Maldeva, viceroy of Arjundeva, the Chālukya king of Gujarāt There is a reference to it in another epigraphic record also, dated V S 1538 A, C 1476. (B G Cutch, Vol V p 23)

'Katāria' is on the south-east coast of Vagad, about eleven miles north-west of Maha It contains a ruined Jama temple about five hundred years old and other monuments of the 17th century (Ibid, 225)

V, 446, l. 11 from foot. Sidi Rihan. with Nokin Gohil. rated from the insurgents

The lithograph writes the second name correctly as وكري Noghan (365, 1 4) The reading in the A N is even more corrupt than Dowson's, as the man is called! Lokhan Karhal' or 'Khokhan Jain' (III 531, Tr 809, 620, Tr 948) 'Noghan' is an old Rajput name which occurs frequently in the indigenous chronicles of Kathiawad and it was borne by more than one of the Chudasama rulers of Junagadh (B G. VIII, 493, Ranchhod)1

Amarji, Tārīkh-i-Sorath, Tr. Burgess, 127-129; Rās Mālā, I. 432-3).

Bir Khān Singh' (l. 9 f. f.) is an impossible collocation. The Lith. has 'Pīr Khān Sakna' [Sakta १] على خان عان كية . V. 447, l. 15.

At this time, Zain Khān Koka, Rājā Rāmchandar, Rājā of Bittiah..... came to wait upon the Emperor at

Insert "through" between 'time' and 'Zain'. Zain Khān was the courtier who introduced Rājā Rāmchand to the Emperor. 'Bittiah' is Cr! in the lithograph (365, 1. 11 f.f.), and is another instance of a constantly 1.3; Tr. 345). He adds that Birbar had at one time been in Rājā Rāmchand's service. Zain Khān and Bīrbar were sent to summon the Rājā to Court, so that he might be compelled to make Kurnish, which he had never

done hitherto. He kept the envoys with him and then came in their company to Fathpur. (See also 538 infra). V. 449, l. 2. The Mirzā [Muhammad Hakīm] was the Emperor's own

The Lith. has a negative, which has been overlooked in the translation and the author's meaning turned upside down. Nizāmu-d-dīn explicitly states that Muhammad Ḥakīm was not the Emperor's own brother زادر اعانی (367, l. 11). The name of Akbar's mother was Ḥamīdā Bānū, Muhammad Hakim's Mah Chuchak.

V. 451, l. 13. When they reached the Pass of Karāgar, a person said

This Pass is on the north side of the Swat river between Swat and Buner (A. N. III. 478; Tr. 720) and lies east-south-east of Chakdarra, which is in Lat. 35° N., Long. 72° E. It is marked on the map prefixed to Mr. Winston Churchill's 'With the Malakand Field Force.'

Bīrbal's name is always written more correctly as simbar, by the Mughal Chroniclers. B. says that he was a begging Bhāt named Brahma Dās, (II. 161, l. 10), but other authorities state that his name was Mahesh Das. (Grierson. loc. cit. 34). Mr. Vincent Smith's explanation of the former form is that 'Bīrbal' wrote poems under the name 'Brahm Kabi', when he was in the Jaipur service. (Akbar, 237 Note). But 'Brahm Kabi' itself is only a pseudonym or pen-name and may have been assumed because Bīrbar was a Bhāt of the Brahm sub-section, one of the nine groups into which the Bhāts are divided. The title 'Bīrbar', Sans. Vīra Vara, 'best warrior', is not common and its origin or the reason for its bestowal upon a 'begging' [Lelia] Bhāt has not been elucidated. It may be therefore permissible to offer the suggestion that Akbar borrowed it from the Vetāla Panchavinshati or Baital Pachisi, 'The Twenty-five Tales of the Vampire,' In the third story of this collection, a man named Vira Vara offers his services to the king and fully earns the extraordinarily high pay allowed to him, by giving undeniable proofs of his loyalty and devotion to his master. (Kincaid, Tales of Vi krama, p. 28; Burton, Vikram and the Vampire

Rājā 'Dharm Singh' (17 ff) is called 'Rājā Dharmangad' in the Lith (369, 17), but 'Dharmakand' [recte, Dharmakānt?] in the A. N. (III. 485=Tr. 782)

V 451, l 2 from foot He dismissed these commanders

They were not dismissed from service The Emperor declined to see them, i e deprived them of the much coveted distinction of attending the Court and making their 'Kurnish' ایشارا ارشرف حدمت کرور دا شنده (369, ایشارا ارشرف حدمت کرور دا شنده (369, ایشارا ارشرف حدمت کرور دا شنده ایشارا ارشرف حدمت کرور دا شنده ایشارا ارشرف حدمت کرور دان ایشارا ایش

V 452, l 8 from foot When Muzā Shāhukh . reached the Pass of Bhūliyās, on the confines of Kāshmīr.

B calls it 'Phūlbās' (II. 352, Tr 363), and Jahāngīr 'Bhūlbās' (T J Text, 292, 293, 298). The name is written as 'Poliassa' also in some old maps, but 'Būliyāsa' seems to be the correct form. It lies on the right bank of the Jhelam about fifty miles west of Bārāmulā (Stein, Ancient Geography of Kāshmii in J. A. S. B. 1899, pp. 85, 129). Its old Hindu name, 'Bolyāsaka', occurs in the Rājātarangim

V 455, l 3 Mir Sadr 1-Jahān was sent as a complementary visitor to Iskandar Khān, the father of 'Abdulla Khān

[Sadr-1-Jahān] was sent to convey the Emperor's condolences on the death of Iskandar Khān to his son 'Abdullā Khān" The embassy was not sent to Iskandar himself. He had passed to 'the bourne from which no traveller returns' three years before, in 991 A. H. The Mīr was carrying to his son 'Abdulla Khān, a letter giving somewhat belated expression to the Emperor's sorrow on the occasion. (See A. N. III. 497, Tr. 753, B. II. 354, Tr. 365) The letter fills eight pages in Mr. Beveridge's translation. (754-61) It is printed also in the Inshā-ā Abu-l-Fact

V 457, l 6 from foot Abu-l-Fath died at Dhamtaur

This is a small town about sixteen miles east of the Indus on the loute into Kashmīr by the Dūb Pass Lat 34°-7′ N, Long 73°-7′ E (Th) It lies about five miles east of modern Abbottābād, on the light bank of the Dor liver and is close to Naushahra

V 459, footnote Briggs Justly observes that as no results followed this "victory," it was most likely a defeat

Nothing could be more unjust of contrary to fact than Briggs' remarks in his Tr of F II. 264 note. So far from having been a "complete defeat" of the Mughals, it was such a smashing blow to the Jām, that it is the theme of tragic tales and ballads which are even now recited in Kāthiāwāḍ Witness what Colonel Watson states in the Provincial Gazetteer "The Jām's army was most disastrously routed and his eldest son Ajoji and his minister Jasā Lādak were both slam The place where the battle took place is called Bhuchar More and is about one mile to the north-west of Dhrol.

So great was the loss sustained by Nawānagar on the fatal field, that since that day, the word 'Bhuchar Mori' has, in Hālār, been almost synonymous with a massacre'. (B. G. VIII, 567-S. See also Mirāt-i-Sikandari, Text, 350-352; Tr. Fazlulla, 323-4). B. states that 'Azam Khān" fought such a battle that anything approaching it has never been described" and Shaikh Faizi found the chronogram for the year, in which it was fought, in the words خوات 'Glorious Victories'. (II. 373, l. 6 f. f.; Tr. 385). Nizāmu-d-dīn says that 4000 Rājputs were slain in this battle. The Jām's defeat was followed by the invasion and occupation of his capital, Nawānagar, and he was forced to become a vassal of the Empire. (A. N. III. 593-595; Tr. 902-906). The date given by A. F. is 4th Amardād and by Nizāmu-d-dīn 6th Shawwāl, 999 A. H.=18th July 1591.

V. 461, l. 8. Daulat Khān.....had been wounded in a battle with the Jām and was dead.

This is worded so obscurely or equivocally as to convey a wrong impression to the reader. Daulat Khān had not been wounded in any encounter between the Jām's army and his own followers. What Nizāmuddīn really states is that he had been a partisan and auxiliary of the Jām, and had been mortally wounded in the battle between the Mughals and the Jām, which is described on page 459 ante, i.e. the fatal field of 'Bhuchar Mori' in which the Jādejas had been slain by the thousand.

V. 461, footnote. Firishta transcribes this account, but here he uses the more specific word Bini, a naze or promontory.

Briggs renders the passage by a paraphrase, "on a spot of ground surrounded by a swamp, which was flooded at high water".

Briggs is quite right here and no fault can be found with his version. In the Cawnpore lithograph of Firishta, this sentence which has been copied verbatim by him from the T. A. runs thus: علم المراف (I. 268, l. 2), "on a spot which was surrounded by water and a swamp [علم] on all sides." In the account of the battle which is found in the Tārīkh-i-Sind of Mīr M'aṣūm also, it is explicitly stated that the site of the battle was a swamp or morass, and there is no reference to any 'naze or promontory'. See my note on E. D. I. 249. The fact would appear to be that Dowson's Ms. wrongly read F.'s :::.

V. 463, l. 19. Khwāja Muhammad Hakīm Bakhshi.

Recte, Muḥammad Muqīm as in the Lithograph (376, 1. 21, and 460 ante). See also M'aṣūm in E.D.I. 249, and A.N. (III. 608; Tr. 930), where the name is 'Muqīm'.

'Dal Bait' (l. 20) is an error for 'Dalpat'. He was the son of Rāi Sin ha, the Rājā of Bikāner, and is frequently mentioned in the T. J. (Text, 106, l. 19=E. D. VI. 332, l. S, q. v. my Note). On 467, line 4 f. f. infra, the name is written even more incorrectly, as 'Rāi Bīl.' The lithograph has there. (379, l. 4 f.f.). It is a miswriting of another form, 'Dalīp', which occurs in some places, but is incorrect.

V. 464, l 19 Yadgar came up as far as Hamirpur.

The lithograph reads 'Hirpūr'. (377, l. 11) B. calls it 'Hirāpur' (II 383, Ti. 396) and so also the A. N. (III 622, Tr. 953) Hirāpur lies about thirty miles south of Srīnagar and twenty-seven north of Rājauri (Sarkār, I.A.p. cv) It must be Thornton's 'Haripoor' Lat 33°-40' N., Long 74°-51' E

The name of the Pass which Yādgār had blockaded is, as Dowson notes, variously written A place called 'Katarmal' is marked on Sir Aurel Stem's map, about 4 miles north-west of Rājauri (See A. N. Tr. III 764-5 note) Fairi Sirhindi calls it 'Katarbal' (A. N. Tr. III 962 note), and B has 'Katrīl' (II 353, 1 8 f f, Tr. 364) Katarmal may be the correct form Mr. Beveridge suggests that it may be the Darhāl Valley, but points out that it is 12 miles north-east of Rājauri, instead of north-west of it.

V 464, l. 9 from foot It was a currous coincidence, that the day on which the Emperor crossed the river of Lahore to proceed to Kashmir, was the day on which Yadaar broke out in rebellion.

The point of the anecdote is missed in the translation. What is really said is that on the very day on which the news of Yādgār's revolt first reached the Court, the Emperor had happened to say that it would not last for more than forty days. Nizāmu-d-dīn now notes with courtier-like wonder and admiration the "curious coincidence" that the day on which Yādgār was killed was exactly the fortieth, as Akbar had predicted (Text, 377, 18 ff, B II 383, Tr 396). The A. N. also records the fulfilment of the prophecy, with some variations and Abu-l-Fazl remarks that "the secret vision of the world's lord was impressed anew on high and low".

(A. N. III 624, Tr. 954)

V 469, l 12 He [Fathu-lla Shīrāzi] was also an adept in the secret arts of magic and enchantments For instance, he made a windmill which produced flour by a self-generated movement.

الد مراكم عربه المرائي على المرائي ال

Mīr Jākīr Zand, with his two sons, came to Multān V. 496, 1. 17. V. 470, l. 6.

Read 'Chakir Rind' as at E. D. IV. 398. The lithograph has (645, 1.5 f.f.). Rind' is the name of one of the leading Buluch tribes, the others being Magassi, Marri, Bugti, Buledi etc. (I. G. VI. 290; Dames, Baloch Race, 36). "Mawi" (1.7) must be an error for "Siwi" (Sibi), which is the reading of the Lithograph. 'Dudāii' (l. 10) is correctly written 'Dūdāi' in the lithograph. (645, l. 4 f.f.). See also my note on I. 314.

V. 474, l. 30. [I wrote] the following verse from an Ode (Bardah). The quotation is really from what is known in Arabic literature as the "Qasida-i-Barda." It was written by Sharfu-d-din Busiri, who died in 694 A. H. (1294-5). It is a most ornate punegyric on the Arabian Prophet, who is said to have rewarded the author with a miraculous cure of his paralysis. The Emperor Babur tells us that he made a metrical version of the Walidiya Risala composed by his own Pir, the Khwaja Ahrar, in the hope that his fever would be charmed away by the prayers of the Khwaja,

just as Busiri's paralysis had disappeared instantaneously by the blessing V. 477, l. 7 from foot. 'Abdu-l-Qādir was born at Badāun in 947 or of the Prophet. (B. N. 619-20).

The ambiguity is partly, if not entirely, due to the usual confusion between c. and in Mss. but there seems to be really little room for doubt in regard to the year. Budauni himself gives the precise date of his birth as 17th Rab'i I. 947 H. in his History, (I. 363, last line; Tr. 473), and as the date and the year are both stated, not in figures but in words, it may be safely accepted. Elsewhere, he states that he was ten years old in 957 H. (I. 409; Tr. 525) and in his fortieth year, when a son was born to him on 19th Safar, 987 H. (II. 267, 1. 5 f.f.; Tr. 276). His birth-place was not Budāun, but Toda Bhīm, (II. 236, l. 9; Tr. 243) near Basāwar (or Bhusāwar), where his family had been long settled and his childhood was passed at Basāwar. (II. Tr. 26, 51, 63). His grandfather also died at Basāwar. (II. 64; Tr. 63; Blochmann in J. A. S. B. XXXVIII, (1869), pp. 117-119). See also 496 infra. Basawar is now in the Bharatpur State and lies on the road from Agra to Ajmer near Toda. The name is spelt 'Bhusāwar' in the

I, G. Atlas, Pl. 34 E 2 and also in the Post Office Guide. The Tabakat-i-Shahjahani gives A.H. 1024 (1610 A.D.) V. 478, l. 8.

But Ghulām 'Ali Bilgrāmi gives the year as 1004 H. in his famous Tazkira, the Khazana-i-Amira, on the authority of the Sumratu-l-Quds, a work written by a pupil of Budauni. As Blochmann has accepted this date, it may be permissible to draw attention to a passage in the History itself, in which "the time of writing" is explicitly said to have been seventeen years after 989 H. i.e. 1006 H. (Text. II. 297, 1. 20; Lowe, 306). This must imply that Budauni was alive two years at least after 1004 H. V. 496, l. 17. I heard at Sansawan, in Sambal, of the death of my grand-

father in Basāwar

So also in Lowe's Tr 63, but the right reading of the first place-name is 'Saheswān', which lies 23 miles west of Budāun in Lat. 28°-4' N., Long 78°-50' E Constable. Pl 27 D a.

V. 497, l 5 Leaving his wife in distress at Khairābād, he [Ḥusain Khān] set off from Lucknow

This should be Khairābād in Sītāpur, district Oude, 62 miles northwest of Lucknow Lat 27°-32′ N, Long 80°-49′ E. (Th) Constable, 28 B b.

"Wajrāil in the country of Rājā Rankā" (I 18) is really "Jurail, also called Depail, the cold-weather residence of the Rājā of Doti on the Seti river, at the foot of the Kumāon hills His principal fort was at Ajmergarh, [qv line 5 ff], near Dandoldhura, where the Chauntara, governor now resides The statement that Husain Khān was within two days' journey from Tibet must refer to Barmdeo, which was then, as now, the principal emporium of Tibetan produce The title 'Ranka Rājā' was borne by the chief of Doti in the Terai" (Atkinson, NW Provinces Gazetteer, II 554-5) Doti is shown in Constable, 25 D c.

V 5)1, l 9. He [Husnin Khān] arrived at the village of Oudh, in Jalesar, when he learnt that the Rājā of Awesar still continued his depredations in the neighbourhood of Agra

This 'Oudh' must be a mistake for 'etc.' Awwah [Awa or Awah] in Jalesar, Agra It lies a few miles north-west of 'Awesar', which is really Ui esar, a large village "in Pargana Mustāfabād of Mainpuri district, 28 miles north-west of Mainpuri town and about 25 north east of Agra There is here a distinguished family of Chauhān Thākurs of the Partābner stock" (N W Provinces Gazotteer, Vol IV (1375), p 772) Awah and Uresar are both shown in Constable, 27 D b.

V 5)7, l 1. The Mirzā hid crossed the Ganges at the ford of Chaubāla This is Chaupla, the old name of modern Murādābad See my note on Vol III 538, l. 11 Shergarh (l 11 ff) is now in Montgomery district Constable, 24 E b Jahni is probably Chuniān, about twenty miles north of it 'Sankra' (l 3 ff) is an error for 'Satgarha' Constable, Ibid.

V 528, l. 10 Moreover, Sāmānis and Brāhmans managed to get frequent private interviews with His Majesty

Dowson takes 'Sāmāni' to mean "Hindu ascetics," but the men referred to as such by Budāuni, were really Jama priests who were neither Brāhmans nor Buddhists See my note on I. 68, l. 1 and Smith, Akbar, 166-8

V 531, l 5 On the festival of the 8th day after the Sun's entering Virgo in this year [XXVIth or 986 H], he [Akbar] came forth with jewelled strings tied on his wrists etc

Mr Beveridge hazards the conjecture that Akbar showed himself thus in public with marks on the forehead like a Hindu and with strings of jewels tied to his wrists on the 8th day of Virgo, because it corresponded to 8th Ābān Ilāhi, the anniversary of his birth. (A. N. Tr I. 72 note).

But this surmise is invalidated by the fact that Jahangir followed the same custom of tying jewelled strings on his wrists, eight years after he came to the throne, though Akbar himself is said by him to have latterly discontinued it, because he found that it was overdone by the Hindu nobles of the Court. (T. J. 120, l. 20; Tr. I. 246). Again, 8th Aban Ilāhi-Akbar's birth-day-would correspond to the 8th day after the entrance of the Sun into Scorpio-and not Virgo-as Aban was the 8th month of the Ilāhi year. The fact is that the festival to which Budauni refers is that of the Rākhi-bandhan. It is also known as the Nāreli Pūrnimā or Balev and is celebrated on the 15th day of the lunar month Shravana. It is consequently a movable feast, a feast of which neither the Julian nor the Ilāhi correspondence could be exactly the same from year to year. It follows, therefore, that even if the solar anniversary of Akbar's birth did happen to fall in 986 H. or 1578 A.C. on 15th Shrāvaņa, it could not possibly have synchronised with that day of the Vikrama Samvat in any subsequent year.

Akbar was born on 5th Rajab 949 H., 15th October (O. S.), 1542 A. C. (A. N. I. 54-5 and Note) and the solar anniversary of his birth could not possibly have coincided in any year with the 15th of Shrāvaṇa, because the latter must always fall either in July or August. In 1578 (986 A.H.), 15th Shrāvaṇa was 18th July. 18th July is the 199th day of the Julian year and would correspond to 6th Amardād Ilāhi. It may be that Budāuni has inadvertently written Virgo for Leo—the sixth sign instead of the fifth. Jahāngār states that in 1022 H., the Rākhi festival was celebrated on the 9th of Amardād (loc. cit.) and that the day happened to be also the lunar anniversary (r) of Akbar's death, i. e. 12-13th Jumādi II. (1022 H.) or 21st July 1612.

V. 533, l. 12. Experimental seclusion of infants.

This incident is related on the authority of what Akbar himself said about it to Jerome Xavier by Du Jarric. (Payne, Akbar and the Jesuits, \$4; Maclagan in J.A.S.B. LXV (1896), p. 77). It is also found in Manucci. (Storia, I. 142). Psammetichus is said by Herodotus (II. 154), to have made experiments with Egyptian children and Greek nurses, but Akbar is not likely to have heard of Psammetichus. The idea was, I venture to say, suggested to him by the curious passage in the Qābūsnāma, which is cited below:—

مردم از سخن شنیدن سخن گوی شوند د لیل بر ابن انکه آگر کودکی که از مادر متولد شود و در زیر زمینش برند و شبر دهند و در همانجا او را یرورند و مادر و دابه با وی سخن نگویند و نگذارند که سخن کسی را بشنود چون بزرگ شود بی شك لال بود و نبینی که همه (Bombay Lith. (1907), p. 39, I. 1).

"Human beings learn to speak only by hearing speech and the proof of it is this. If a child is born and if it is taken to a place underground and fed with milk and bred up there, and if the mother and nurse do not speak to it and do not allow it to hear the speech of any other person, it will be undoubtedly dumb when it grows up. Do not you see that all dumb persons are also deaf!"

Abu-l-Fazl tells us that the Qābūsnāma was one of the books which Akbar was not "tired of hearing read out to him over and over again." (Āīn, Tr I. 103) He also states that there was a great discussion at the Court when the man who heard without having any ears appeared in the Darbār Akbar maintained that speech was not spontaneous with children, but came to every one from hearing and that if speech did not reach them, they would not be able to speak (A N III 393, Tr 581) The experiment was made on the line ssuggested in the Qābūsnāma to prove that pont The only difference is that the author of that work speaks of only one child and 'Akbar had the trial made upon twenty.

V 534, l. 10 His Majesty was now (990 H.) firmly convinced that a period of 1000 years from the mission of the Prophet was the extent of the duration of the religion of Islām, and that period was now accomplished

This is an important passage from the numismatist's standpoint and it has been cited in almost all our Catalogues of Mughal Coins, on account of the bearing it has on the monetary issues which exhibit the date One Thousand' in words But its real meaning has not been exactly realised on account of the unfortunate use of the ambiguous word 'dispensation', or 'mission' by Blochmann (Ain, I. Tr. 191), Dowson, Lowe (B, Tr II 310) and others in their translations from Budauni The phrase used in the original is مثثر يجمر (Text, 301, 1 9), the first 'Rousing, Awakening, Sending or Dispatching', ¿ e Announcement by Muhammad of his having received God's commands to undertake the duties of a Prophet This event is said by the majority of his biographers, to have taken place in or about 612 A.C., e ten years before the year of his High at or Flight from Mecca (Muir, Life of Mahomed, p. 55, Hughes, Dictionary of Islam, 371-2) In other words, the first year of the Hijra corresponded to the eleventh year of the B'asat and the 990th year of the Hilla, in which the order for stamping the 'Era of the Thousand' or 'Era of the Millennium' on coins was issued, was the One Thousandth year of the B'asat. To put it differently, Akbar was of opinion that the period of One Thousand Years which was to be "the utmost extent or duration of the religion of Islam" should be reckoned, not from the year in which Muhammad fled to Mecca, but from that in which his creed was first preached or proclaimed and his prophetic office announced If the Islamic Millennium commenced in the year of the B'asat, it would expire in 990 Hijra It was to commemorate and proclaim this epoch-making event to the world that the was ordered to be issued

V. 559, l 11 from foot The Sultan [Ibrāhīm] turned his face towards

Hindustān and conquered a city inhabited by
a tribe of Khurāsāni descent, whom Afrāsiyāb
had expelled from their native country

The accounts of Sultan Ibrāhīm Ghaznavi's invasions of India are so vague and obscure and the names of the places raided by his armies are spelt so variously, that it seems to me unprofitable to build upon them theories about the existence of extensive Zoroastrian colonies in Upper India in those and later times.

The contemporary poet Mas'ūd-i S'ad-i Salmān mentions these incursions and states that the Sultan's son Saifu-d-daula invaded a place called Dhangan near Jalandhar, and took the forts of Tabarhinda [Bhatinda], Buriya and Agra, but there is no reference whatever in his writings to this deportation of the 100000 descendants of the people of Khurasan who had been exiled to India by Afrasiyab. Indeed, the tale cannot be traced to any authority earlier than the Rauzatu-s-Safa, which was compiled towards the end of the 15th century. The existence of Afrasiyab, a semi-mythical hero of the Iranian Epos, who is stated to have reigned for several hundred years and his alleged invasion of Khurāsān are legendary and unhistorical and as the story of these peoples' deportation to Ghazni is a corollary or epilogue of the myth, both of them must be equally unworthy of credit. It may be as well also to note that as Afrāsiyāb is supposed to have lived some hundred years before Zoroaster, these Khurāsanis could not have been 'Fire-worshippers' or Zoroastrians.

The difficulty and danger of adopting any other course is well exemplified by the most recent pronouncement on the subject. Sir Wolseley Haig tells us that in 1079 A. C., Ibrāhīm "is said to have taken a town named Rūpāl, which was perhaps the town of that name in Mahi Kānthā. as he appears to have advanced towards the western coast and to have come upon a colony of Parsis, which may be identified with Navsāri in Gujarat. This is the only supposition by which it is possible to explain a Muslim historian's obviously inaccurate statement that he reached a town. populated exclusively by Khurasanis, who had been deported to India by Afrāsiyāb". (C. H. I. III. 34-5. The Italics are mine). But why accept an 'obviously inaccurate statement,' at all and how crude and improbable is this "only possible supposition"?

The genesis of the hypothesis is this. The place near Jalandhar which Mas'ud S'ad Salman calls 'Dhangan' and the Tarikh-i-Alfi 'Damal,' (دمال), is perverted by Firishta into 'Rūdpāl' (I. 58, l. 4 f. f.), just as he transforms the 'Jūd' of the latter authority into 'Ajūdhan.' Sir Wolseley then adopts this blunder and identifies 'Damāl' with a village called 'Rupal' in the Mahi Kantha. He next supposes that the town of the Khurāsānis, called 'Derā' or 'Derāpūr,', which Elliot, Briggs and others had located somewhere near the Indus and in the Punjab, must be Naysari in Gujarāt, because, for sooth, there is a colony of about 5000 Parsis now in that town!

Sir Henry Elliot accepts also Yazdi's statement about Asandi, Kīthal and Tughlagour having been all populated by Majūs. But these assertionare most probably, due to the ignorance and indifference

in regard to the tenets of all religions except their own and the confusion of 'Gabr' with 'Zoroastrian.' Yazdi must have known that the 'Gabrs' of his native town and country believed in Ahuramazda (or Yazdān) and Ahrīman and the paragraph about their dualistic beliefs, on which so much stress is laid here by Elliot, is in reality an empty display of inapplicable learning, a tag borrowed from Shahrastāni, who has an almost exactly similar description of their cieed (See Dowson's Note to Vol III 506)

The inhabitants of Asandi, Kithal and Tughlaqpur were, like those of Sarsutī, Tohāna and other places laided by Timūr, Jāts and Gujars. Their chiefs are called Sālūn, which may be the name of one of the very numerous 'Jāt' or Gujar clans or septs They are said to have eaten the flesh of the pig, to which, it is well known, these people have no objection (Crooke, Tribes and Castes III. 40, II. 448)

Another point which has been emphasised in this essay relates to Safi the Gabr, who is said to have been one of the chiefs who commanded in the fortress of Mīrat and to have "thrown himself" after the surrender "into the fire which he worshipped" It is impossible to understand how a man, who was neither a Hindu nor a Muslim, could have come to hold such a position at this date, and there is no other instance of any other professor of the Zoroastrian religion having risen to such eminence at any time during the thousand years of Muslim domination in India Moreover, no Zoroastrian would have ever "thrown himself into the fire," as such a pollution of the sacred element or the cremation of a lifeless corpse is regarded as a deadly and inexpiable sin by them The allusion looks like a reminiscence of a hackneyed gibe which is found in S'adi's Gulistān (I 16).

اگر صد سال کر آتش فرورد - چویکدم اندر آن افتد سورد

The idea itself is as old as it is common and occurs in one of the Shatakas of Bharirihari (Niti Shatakas No 57, Tr Kennedy, 71)

V 570, l 6 On the knowledge of Sanskrit by Muhammadans

The thesis which Sir Henry Elliot maintains here is that the knowledge of Sanskrit was more generally diffused both before, and in the reign of Akbar, than is generally supposed, and that "Faizi was not the first Muhammadan who had mastered the difficulties of that wonderful language" But we have no reliable proofs of the Sanskrit scholarship of Mullā Sheri, Shaikh Ibrāhīm Sarhindi or Hājji Sultān Thānesari and it is quite certain that Budāuni and Naqīb Khān were ignorant of it.

Budāuni tells us that when the Emperor resolved to undertake a Persian rendering of the Mahābhār ata, he first assembled several Hindu experts [دارایان مند] and directed them to prepare an explanation آمیر و e to compose a version in the vernacular Then for several nights, he himself explained the meaning from the vernacular exposition to Naqīb Khān, so that the Khān might sketch out the gist in Persian ما حصل را سارسی املا مبکر د

These Hindu experts are always styled by B and he laments that at the time when he wrote this portion of his History, the majority of

the Interpreters (مترجان) as well as (مترجان) Translators, had gone over to the majority, or as he quaintly puts it, 'had been reckoned or gathered to the Kauravas and Pāndavas ' اكثر اذ آن معران و مترجان بكوران و و بندان معشورنه were quite distinct from the مترجان المدان معربان و مترجان بكوران و بندان معشورنه. The former were, in fact, Hindus, while the latter were Musalmans.

The names of at least three of these of these are specifically mentioned by him, viz. Purkhottam, the are of the Singhāsan Batīsi, Devi of the Mahābhārata and Bhāwan of the Atharva Veda. One of the Interpreters of the Rāmāyaṇa [عرات خان] is also mentioned, as working in a room specially set apart for them near the Hall of Audience [دولت خان] in Fathpur Sīkri. (II. 337; Lowe, 348). Naqīb Khān himself states that he completed his portion—Parvas XII-XVIII—in one year and a half în Sha'bān 992 II. and that he was assisted by Devi Misra Shatāvadhāni, Madhusūdan Misra, Chaturbhuj and Shaikh Bhāwan. (Rieu, Catalogue, I. 57).

It would seem that the Hindu معرات first wrote out Hindi versions of their own, though it is possible that they made use of or even appropriated older vernacular renderings where such existed. These versions were then handed over to the so-called Musalman Translators [عرجان] and also orally explained or elucidated in cases of difficulty. Indeed, Budāuni declares, that the version of the Atharva Veda had to be left unfinished, because it contained many difficult passages which Bhāwan could not explain or interpret to the satisfaction either of himself [Budāuni] or of Hājji Ibrāhīm Sarhindi, to whom the task was assigned after he himself had abandoned it. عبر عاجزان عبر يرد ومنا عبد مناوع المنافعة (II. 212, 1. 3 f.f.=Lowe. 216). It is clear that the result of such collaboration could not possibly be an accurate or fai hful translation. It could only be a loose paraphrase, abstract or abridgment suited to the literary taste of the age.

Francis Gladwin, who had seen a copy of the Razmnāma, or this Akbari version of the Mahābhārata, states that "it was nothing more than an extract, very indifferently executed, many beautiful descriptions and episodes being entirely omitted." (Ayeen Akbery, Trans. I. 103). He says that it filled 2000 folios, but this cannot represent anything like the real extent of the great Epic, as the English translation by Pratāp Chandra Rāy runs into ten volumes and almost as many thousand pages in print. The complete copy in the British Museum fills only 1224 folios. (Rieu, I. 59). The whole episode of the Bhagavad Gītā is dismissed here in three folios. (Ibid.). Indeed, Budāuni states that he finished his version of two out of the eighteen Parvas or sections $\ddot{\psi}$ in three or four months!

It is not quite easy to say whether Faizi's deep knowledge of Sanskrit is matter of history or only popular belief. But however that may be, it is certain that Dr. John Taylor, who was a competent Sanskrit scholar as well as mathematician, complains that his version of the Līlāvati has many omissions and the translation in some passages departs so far from the origina las to "induce the suspicion that Faizi-nte: I him-

self with writing down the verbal explanation afforded by his assistants." (Lilavati, Tr 1816, p. 2) This is just what Budāuni and his colleagues appear to have done, and this considered judgment probably represents the real state of the case, in regard to all the versions of Sanskrit classics made by Musalmans in Akbar's reign.

Alberuni's knowledge of Sanskrit was undoubtedly greater than that of Fairi or any other of these soi-disant translators. But Dr. Sachau, who has examined the matter both sympathetically and critically, gives his opinion in the following words.

"With what success did he [Alberuni] study Sanskrit? To me it seems impossible that, without a grammar and dictionary to help him, he should have been able to read books on philosophy, astronomy, and astrology and to translate them into Arabic proprio Marte and without the help of Alberuni knows the phonetic system. learned Pandits to some extent acquainted with the general features of the structure of As a rule, however, he seems to have read Indian books with Sanskrit, the aid of Pandits and to have written his translation simply from their dictation" (Indica, Arabic Text, Preface, xiv-v). Dr. Sachau then gives a long list of mistakes made by Alberuni, when he tries to interpret Sanskrit words or phrases according to his own knowledge and without the help of his Pandits (Ibid xvii-xviii See also his Notes to Tr. Vol L 351 and 394). Dr Bühler also has pointed out that Alberuni's "deficiencies in this respect are only too patent" and that he has " committed some very bad blunders in his translations." (Indian Antiquary, IX, 1880, p. 409)

VOL. VI. AKBAR, JAHĀNGĪR.

VI. 4, l. 12 from foot. "He [Abu-l-Fazl] had an extraordinary appetite.

It is said that, exclusively of water and soup,
he consumed daily twenty-two sirs of food."

One feels a mild shock of surprise on learning that the renowned statesman, philosopher and litterateur was such a guzzler and gourmand. If this 'ser' was the Akbari ser of thirty $d\bar{a}ms$, or $320\times30=9600$ grains, twenty-two sers would be equal to about thirty pounds avoir dupois. Hawkins states that the Akbari man of forty sers was equivalent to about 55 English pounds. (E. T. I. 105). Twenty-two Akbari sers would then be $=\frac{55}{1}\times\frac{22}{40}=\frac{1210}{40}=30\frac{1}{40}$ lbs.

Elsewhere, the author of the *Maāṣiru-i-Umarā* states of Abu-l-Qāsim Namakīn, another of Akbar's nobles, that he could eat one thousand mangoes, one thousand apples and ten *Kharbūzas* (melons) each weighing one *Man.* (M. U. III. 77, l. 5). He is also responsible for the averment that Āṣaf Khān, the brother of Nūr Jahān, had such a Gargantuan stomach, that it could digest one *man* Shāhjahāni of solid food. (I. 158). One Shāhjahāni *man* of 40 dāms was equal to about 70 lbs. avoirdupois.

VI. 5, l. 5 from foot. He [Abu-l-Fazl] presented a commentary on a Surat of the Kurān, which he called Ayatu-l-Kursi.

This is expressed badly and in such a way as to mislead the reader. The $\overline{Ayatu-l-Kursi}$ is the name of the $S\bar{u}rat$ or verse of the Qurān which was the subject of the Commentary and not the title given by Abu-l-Fazl to that Commentary or his own lucubration. The verse is so called, because the word 'Kursi' (Throne) occurs in it. It is the 256th verse of the Second chapter of the 'Holy Book' and contains a magnificent description of the glory and majesty of the Most High, sitting on His Kursi, Throne or Judgment-seat in the Eighth Heaven, which is just below the 'Arsh, the Ninth or Empyrean. See B. Text. II. 198 and 516 infra, where it is clearly stated that Abu-l-Fazl "presented a Commentary on the $\overline{Ayatu-l-Kursi}$ which treated on the nice points and subtleties of the Qurān." (Vide also A. N. Bib. Ind. Text, III. 95; Tr. 119). Subsequently, Abu-l-Fazl presented, on the occasion of his second introduction to the Emperor, a Commentary on another verse of the Qurān, the Fātiḥa. (A. N. III. 114; Tr. 161).

VI. 11, l. 6. In the year 933 H., Mirzā Kāmrān removed Mirzā 'Askari from the government of Kandahār and gave it to Khwāja Kalān Beg.

Sic in the B. I. Text, I. 126, but the date is evidently wrong, as Bābur was alive in 933 and Kāmrān could have left 'Askari in charge of Qandahār only after his father's death (p. 10 ante). A British Museum Ms. of the A. N. reads 939 and Mr. Beveridge thinks this must be correctly and the correctly of the A. N. reads 939 and Mr. Beveridge thinks this must be correctly only only have been miswritten or misread.

The fact of 'Askarı's deputising for Kāmrān in Qandahār is mentione'd in the great inscription engraved there by Mīr M'asūm (qv my note on I. 238, 1.4 f.f.) 939 H is most probably correct, as when Sām Mirzā of Persia attacked Qandahār in 942 H, Khwāja Kalān who superseded 'Askarı was the governor (A N I 135, Tr 307)

VI. 11, l 15. When he [Humāyūn] arrived at the town of Kinār, near Kālpi, he was informed that Sultān Bahādur had laid siege to the fort of Chītor

This is Kinār which was a Mahāl in Sarkār Kālpi (Āīn, Tr II 184). The old village is now in ruins and is known as Kanar Khera. A new town called Jagmohanpur or Jagmanpur has sprung up near the site. (Elliot, Races, II 95) Kinār is mentioned in the Memoirs of Bābur also, as a place on the Jumna, two or three Kos below its junction with the Chambal (ED. IV. 278, BN Tr 589, 598) Jagmanpur in Jālaun is shown in Constable, 28 Ab, about 40 miles north-west of Kālpi

VI 13, l 3 But Sadr Khān urged that they should press the stege, as no Muhammadan king would attack while they were engaged in war with infidels

The Mirāt-i Sikandari puts the matter very differently "When Humāyūn," its author writes, "reached Gwālior, he reflected thus, 'Sultān Bahādur is besieging Chitor If I at this time oppose him, I shall really be rendering assistance to the infidels and such a proceeding is not in accordance with religion' "(Text, 272, 16, Tr Bayley, 38, see also T. A 507, F II 222-3) A similar story is told by the same historian, in connection with Sultān Ghiyāsu-d-dīn Khalji of Mālwā and Mahmūd Begada's siege of Chāmpāner The Rājā having solicited the aid of the Khalji Sultān, whose ancestors had been at perpetual war with the predecessors of Mahmūd, Ghiyāsu-d-dīn invited the opinion of the Ulamā who unanimously declared that the giving of any help to a Kāfar at such a juncture was contrary to the religious law Ghiyāsu-d-dīn, who had marched half-way towards Gujarāt, consequently retraced his steps in the direction of his capital (Ibid 114-115, Bayley's Tr 208-9)

On l 14, 'Mırān Muhammad $Shuj'\bar{a}'$ is wrong The third word should be 'Shāh' as it is in the A N. Text I 132 He was the son of Bahādur Shāh's sister and the Fārūqi ruler of Khāndesh

VI 15, l 11 from foot Nausārī was held by . an officer of Husain Khān.

The real name of the fief-holder was Qāsim Husain Khān Uzbeg He is mentioned at p 13 as 'Qāsim Sultān,' as 'Qāsim Khān' a few lines lower down on this very page, and as 'Qāsim Husain' at page 14 supia. His negligence or disloyalty in allowing Bahādur Shāh to escape is also alluded to He was a Tīmūrid, and the son of a daughter of Sultān Ḥūsain Bāiqarā who was married to one of the Uzbeg Sultāns (Gulbadan, H. N. Text, 17, J'A in EDV 197, Text. 198, 14 f.f)

VI. 17, l 5 The Mirzas marched off by way of Ghat-Karji

Mr. Beveridge states that he cannot find this place. (A. N. Tr. I. 321 note). It is mentioned at least thrice in the Mirāt-i-Sikandari. (Text 243, 244; Tr. Bayley, 348, 349, 350). It is said to lie east of the town of Bānswālā. (M. V. Pandyā's article in J. A. S. B. 1897, p. 167). Bānswāla is shown in Constable, 27 B d.

VI. 18, l. 10 from foot. A European Kāzi (priest?) placed himself in the Sultān's way, and bade him stop. The Sultān cleft him in twain.

According to the Portuguese accounts, the man cut down by Bahādur was not a priest, but Manoel de Sousa, the Governor of Diu. Perhaps قاضى is used in the sense of civil and criminal magistrate, or judge.

VI. 21, l. 21. The fugitives proceeded to Dewati-Mājāri, a strong place which was Hīmū's family home.

Recte, 'Deoti' and 'Mācheri,' which are now two ruined villages or townships in close proximity to each other in the State of Alwar. Mācheri lies about 23 miles south of Alwar town and 3 miles east of Rājgarh, which is a station on the B. B. and C. I. Railway. (I. G. XVI. 224). Nizāmu-d-dīn Aḥmad (T. A. in E. D. V. 241) and Abu-l-Fazl (A. N. I. 337; Tr. I. 617) state that Hīmū was a [Dhūsɪr] Baniya of Rewāri in Alwar.

VI. 21, last line. The Rānā [of Chitor] was the son of that Rānā who had acted improperly towards the late Emperor Humāyūn, and had suffered defeat at his hands.

Read 'Bābur' for 'Humāyūn'. The text (II. 46) speaks of the Emperor correctly, as Firdaus Makāni, i, which is the after-death title of the Founder of the Mughal Empire. The prince who was ruling at Chītor in 963 H. was Udayasinha, the posthumous son of Sanga, who had been defeated at Kīnhwa or Khānwa by Bībur. Humīyūn is styled 'Jannat Āshiyāni.' (A. N. I. 120; Tr. I. 183-5). Sanga is said to have 'acted improperly' towards Bībur, because he had at first professed to be an ally of the Chaghtāi and then assumed a hostile attitude, when he found that the invader had no intention of abandoning his conquest.

VI. 22, l. 19. Saiyid Muhammad Bārha and Shāh Quli Khān Mahram were sent out with a force to capture Jītasāran.

The B. I. Text has 'Jītāran' (II. 66; Tr. 103), which is right. The name is spelt 'Jetāran' in the Post Office Guide. It lies 24 miles east of Pīpār in Jodhpur State. Pīpār is shown in Constable, 27 A b.

On line 7 f.f., the name of 'the son of Muḥammad Khān, the Ruler of Bengal', who defeated and slew Mubāriz Khān, alias Sultān Muḥammad 'Adali, is given as 'Sadar Khān who had assumed the title of Jalālu-d-dīn'. But it was Jalālu-d-dīn's predecessor and elder brother, Khiṣr Khān alias Bahādur Khān, (Gauriya) who avenged his father's death and 'Adali was killed in a battle against Bahādur, as A. F. himself states at 34 infra. Bahādur's coins show that he ruled from 962 to 968 H. Jalālu-d-dīn reigned after his death, from 968 to 971 H. (Wright, I. M. C. II. p. 181).

VI. 28, l. 7 from foot But the takhta-Begi, one of the ladies of the Court, told her [Māhum Anaga] the truth

The name of the lady is given as "Takhta Begam" and also as "Najība Begam" in the B.I Text of the A.N. (II. 177). She is said by Bāyazīd Biyāt to have been the mother of Dastam Khān (Memoirs in J.A.S.B LXVII, 1898, p. 311) As 'Takhta' or 'Tukhta' was a personal name borne by males as well as females, the definite article prefixed to it here should be deleted Tukhta Beg Kābuli was an old servant of Mirzā Muhammad Hakīm, who was afterwards ennobled as Sardār Khān (Āīn, Tr. I. 467, T J. Tr I 31, 151) Tukhta Begi, King of Makrīt, is mentioned in Miles. (Tr Shajrat, 117; see also A. N. Tr II. 274 Note) and look so very much alike in the Persian script that it is impossible to be positive about the real name of the lady

VI 29, l 18. It was an old standing custom for the rulers of Hindustan, to exact contributions from the pilgrims of holy shrines

This tax (on Hindu pilgrims) was called Karmi

(A. N. II. 190, 15) Mr. Beveridge's rendering is, "This (worship) was called 'Karma." He also reads Karmā as one word and explains it as the Sanskrit Karma, 'a religious act or the acquiring of merit' (Tr. II. 295 note) I submit that this is not an improvement on Dowson's meaningless 'Karmi.' I translate it thus 'And this tax [not this 'worship'] was called 'Kar' [by the pilgrims, in their vernacular]" The 'mi' in 'Kar mināmand' goes, not with 'Kar', but with 'nāmand' and the full form of the auxiliary verb is Mināmand. The vocalization, Kūf with Fath and Rā silent also proves that the word is the Hindi Kar VI. 29, 1 12 from foot And he [Akbar] remitted it [the pilgrim tar], although it amounted to Krors of i upees.

The two words which follow 'Krors' are an unwarranted and mis leading interpolation. There is no reference to 'Rupees' or any other unit of the currency in the original. (II 190, Tr 295). It is not easy to say positively what monetary denomination is meant, but the presumption would be in favour of either Dāms or Sikandari Tangas. It is exceedingly improbable that the pilgrim-tax should have yielded several Krors of rupees at this time. Akbar's total revenue during the last years of his reign has been estimated at about fifteen Krors of Rupees only

VI 30, l 12 from foot. On the north of [Garha-Katanha] lies Panna

Another instance of a persistent error Dowson notes that the name is written 'Patta' in the print and in the Ms and also by Faizi Sirhindi. The right reading is 'Bhata' or 'Bhatghora,' the old name of Bāghel Khand or Rewā. Thornton says that 'Goorha' is a town in Bāghel khand, thirteen miles east of Rewā and thirteen miles from the left bank of the river Sone Lat 24°-30′ N., Long 81°-35′ E Dowson asserts that "the description given applies to Panna," but it is equally applicable to Bhata or Bhatghora Katanka is Katangi, a town about 25 miles north-west of Jabalpur, Garha lies four miles south of Jabalpur Constable, 28 A d.

The country of which Asaf Khān is said, a few lines lower down (p. 31, 1.7), to have "accomplished the conquest", i.e. raided or overrun, was also 'Bhata,' not 'Panna.' On p. 34, 1.7 also, read 'Bhata' for 'Panna.' VI. 32, 1. 12. He fled to Rājā Nar Singh Deo, grandfather of Rājā Rām Chandar of Panna.

The correct name of the Rājā was Bir [Vīra] Sinha Deva and he is frequently mentioned in the Bābur Nāma. (Tr. 521, 562, 689). He was present at the battle of Kānhwa. He was the father of Vīrabhānu [Parbehān or Bīrbhān], who is said to have been the Rājā of Arīl. (Gulbadan, H. N. Tr. 136; Jauhar, Tr. Stewart, 189). This Vīrabhānu was the father of Rāmchandra, Rājā of Bhata (not Panna). See also my notes on IV. 461 and V. 93, 95. The same mistake is committed at 117 infra, where the 'Panna' of which Rāmchand was Rājā should be read as 'Bhata.' Māndhūn' to which the Rājā fled (p. 118) is correctly 'Bāndhu' which was the capital of Bhata.

VI. 37, l. 8. The enemy had halted at Sarnāl, on the bank of the Sakāner. The B. I. text reads 'Bikāner' (III. 13), an error for 'Bankāner,' i.e. 'Bānkāner' or 'Vānkāner.' The river is the Mahi and one of the most generally used fords on it was at 'Vānkāner' ('Wancaneer' on Bayley's map), which was also called Khānpur. The armies of the Sultāns of Gujarāt are said to have frequently crossed the river at this point. (Mirāti-Sikandari. Tr. Bayley, 137, 143, 330, 346). Sarnāl lies five miles east of Thāsrā and is said to be so called because it lies at the head () of a narrow and precipitous defile, river or hill (JV) (Ib. 431, l. 10; Tr. Fazlulla, 310; A.N. III. Tr. 19), but this derivation sayours of meaning-making.

VI. 41, l. 5 from foot. Jalāl Khān, Saiyid Hūri and Kālā Pahār whose name was Rājū, now separated from Lodi.

The B. I. text reads 'Jalāl Khān Sadhauri' (III. 22; Tr. 31) and it is said in the $T\bar{a}r\bar{\imath}kh$ -i- $D\bar{a}\bar{u}di$ also that "Jalāl Khān Sadhauri and Rāju, surnamed the 'Black Mountain' [Kālā Pahār] deserted Lodi." (E. D. IV. 511). But elsewhere in the A. N. he seems to be called "Sirhari' 'who was Dāūd's rational soul', (A. N. III. 120; Tr. 172), and also 'Jalāl Khān Gidhauriya'. (III. 72; 'Tr. 100).

VI. 48, l.11 from foot. But a few days afterwards, he [Junaid] found the means of reaching Nuzhatābād in that province, and there raised a revolt.

This 'Nuzahatābād' is a geographical mare's nest. حند روزی نگذشته (III. 136, l. 1). Mr. Beveridge's rendering is "many days had not elapsed, before Junaid thought he had his opportunity and proceeded to set up a commotion in Bihār.' (Tr. III. 192). Nuzhatābād is a mere flourish, a rhetorical or honorific epithet, signifying "Abode of pleasure, joy, etc." prefixed to the name of the country. 'Bahār' in Persian means 'Spring,' when 'joy' or 'pleasure' (Nuzhat) reigns everywhere. For other honorific epithets of Mughal towns, see my paper in Num. Supp. to the J. A.S. B. (1921), No. XXXV. pp. 31-97.

VI 52, last line Soon after this, Satir and Jatri, seized the opportunity of taking possession of the country of Bakra.

and in the B I. text (141, 18) are errors for Tegra, which lies west of Monghyr town and nearly opposite to Sūrajgarh, on the northwest bank of the Ganges and in the northwest part of the Begum Serāi sub-division (A N Tr III 199 Note). "The pargana itself is now called 'Mulki' in the official records, but the town of Teghara still retains its old name" (Beames in J A S B 1885, p 174) It seems to be the 'Patkhera' (variant 'Teghara'), which is registered as a Mahāl in Sarkār Hājīpur, Sūba Bihār in the Āīn (Tr. II 155) Thornton says 'Tegra' lies 33 miles west by north of Monghyr, Lat 25°-27' N, Long 86°-0' E

VI. 53, l 14 from foot Rājā Todar Mal now arrived, bringing with him fifty-four elephants, which had been taken in the campaign of Takrohi

'Takrohi' is Tukaroi, a village about seven miles south of Mughalmari. It is now in Balasore district and lies between Midnapore and Jaleshwar, rather more than half way distant from the former Lat 21°.53' N. Long 87°-1' E (Āīn, Tr I 376) The T A and B speak of the battle having been fought at "Feco or Feco or Feco or Tajhora' As Blochmann says that he cannot "give a satisfactory explanation" of either of these forms, I venture to suggest that all that is necessary is to transpose the dots and read "Tukhora' which is practically identical with 'Tukaroi' The name Mughalmari must be derived from the fact that the Mughals inflicted a crushing defeat there on their Afghān adversaries

VI 53, last line [Sīwāna] was held by Bathā Rāhtor

"Patā" in the B I Text (III 167, Tr 237) and this is probably correct Cf 'Jaimal' and 'Pata', the renowned heroes of Chitor 'Pata or Patāi Rāthor and Patāi Baqqāl' are mentioned as the persons to whom Chandra Sen, the son of Rājā Māldeva of Jodhpur, had handed over the fort of Siwāna two years before (XIX R Y) (A. N III 82, Tr 114) The last Hindu Rājā of Chāmpāner from whom Mahmūd Begada took the stronghold was known as Rāwal Patāi or Rānā Patāi (Z. W. 27, 28) VI. 55, l 12 Campaign against Gajpati. Capture of Rohtās.

Gajpati was the Ujjainia Rājā of Bhojpur and was the son or nephew of Dalpat Sāh. q v Āīn, Tr I 513 and Note The name is also written and and another that the real name was not Gajpati, but Gajni or Gajīni The family is now represented by the Rājās of Dumrāon or Hathwa, and it appears from their family chronicles that the original name was Gajan Sāhi (A N Tr III. 239 Note). The corruption 'Gajpati' is probably due to the Mughal historians' familiarity with it as the dynastic title of the Rājās of Orissa and in connection also with the ancient Hindu classification of Gajpati, Narpati, Ashwapati and Bhūpati (Beal, Buddhist Records, I 13-4) One of the kings in the old Hindu game of cards (Ganjīfa), of which Akbar was

very fond, was also denominated Gajpati. (Āīn, Tr. I. 306). According to another authority, (I. G. XI. 378), the founder of the Rāj of Dumrāon in Shāhābād Taḥṣīl, Bengal, was Santana Sāhi. During the struggle between the Afghāns and the Mughals, Gajan Sāhi and Dalpat Sāhi, two rival princes of the family, joined opposing sides. Gajan Sāhi received Rohtās and Shāhābād from the former. The capital was first at Jagdīspur, afterwards at Bhojpur and was lastly removed to Dumrāon in or about 1745 A. C. Bhojpur lies west of Arrah and north of Sahsarām. Dalpat's rebellion in 1579-80 A. C. is mentioned in the A. N. (III. 323, Tr. 474). Dalpat Ujjainia, who is mentioned at 72 infra as one of the Mughal auxiliaries was murdered by the orders of Prince Salīm in 1601 A. C. He had been taken prisoner some years before after another revolt and released in 1599 A. C. on the payment of a heavy ransom. (Āīn, Tr. I. 513).

Sangrām (l. 25) was the Rājā of *Kharakpur*, not Gorakpur, as Mr. Beveridge writes the place-name. (A. N. Tr. III. 461=Text, 315).

VI. 56, l. 11. When Gajpati was (first) defeated, he placed his son Srī Rām.....in the fort of Sher-garh.

Dowson says this is "Shergutty, 65 miles south-east of Jagdespur." But the place intended is Shergarh, 20 miles S. W. of Sahsarām, and north of Rhotās, where Shīr Shāh had built a great fortress. The B.I. text has 'Shergarh' (III. 188-9; Tr. 265-6) and F. also calls it by the same name. (I. 263, 1. 10 f. f.), See also I. G. XXII. 272 and E. D. IV. 419, where it is wrongly called Sher Koh [•• for •• J. Constable, 28 C c.

VI. 57, l. 3. Muzaffar Khān, Rājā Todar Mal and Khwāja Shāh Mansūr.....were summoned to a council at Kot-pakali,

Recte, Kot-putli. It is now in the Rājput State of Jaipur and lies about 60 miles N. E. of Jaipur city. (I. G. XVI. 3). It is on the road from Delhi to Ajmer and is about 92 miles S. W. of the former. (Chihār Gulshan in I. A. cvii. See also Āīn, Tr. II. 182, 194). Constable, 27 C b. The double-barrelled name is due to the existence of a village called 'Putli' in the vicinity.

VI. 57, l. 4 from foot. Defeat of the Rājā of Madhgarh.

Recte, 'Rājā Madhukar.' Madhgarh' is not a town or a district, but a miswriting of 'Madhukar', the personal name of the ruler. (A. N. III. 77, 209, 228; Tr. 108, 294, 324). He was one of the nine sons of the Bundela Rājā Pratāp Rudra of Undcha or Orchha and the father of Vīra Sinha Deva, the murderer of Abu-l-Fazl. Another expedition was despatched against Rājā Madhukar in the 35th year of Akbar's reign (999 H.) (A. N. III. 604=Tr. 922) and his death in the XXXVIIth (1000-1001 A. H.) is also recorded. (Ibid, 628=Tr. 961).

VI. 59, l. 9. Tribute from Rājā Māl Gosāin, the Zamindār of Kūch.

The name is sometimes written 'Bāl Gosāin'. But he is called 'Malla Deb' or 'Malla Nārāyan' in the local chronicles and control or inscriptions. He is also styled 'Nar Nārāyan'. (Gait, Total 49 note and 56. See also Blochmann, J. A. S. B. 187.

that Shukla Dhwaj was the elder brother of Māl Gosām, but he was really the younger, according to the epigraphic records (Gait, J. A. S. B 1893, p 295) Shukla Dhwaj is generally known as 'Sila Rāi', i e the 'kite king' VI. 59. l 13. Partāb Bār and his wife Basūrbā [came to court]

It has been suggested that the first name stands for that of Pietro Tavares and Mr Beveridge does not reject this, though he thinks that "Partāb Bāi" does not bear much resemblance to the name 'Tavares.'(A. N Tr. III. 349-50 Note) It may be possible to iemove the difficulty, if we suppose that what Abu-1-Fazl wrote was يتر تاك ساد Patar Tābiār. There is hardly any difference between 'Par' and 'Patar' in Persian writing

The name of his wife is more difficult to determine It is written as Basurbā, Nashūrnā, Nasūrtā Basūrbā and in several other ways also Mr Beveridge supposes it to stand for Isabella or Louisa. But the readings favoured by most of the Mss have little or no resemblance to either of these names May it not be a mistranscription by metathesis of 'Senoria', ie 'Senhora'? A F was probably not acquainted with the actual name He had only heard her spoken of as 'Senhora', and may have thought that it was her personal name

V. 67, l 9 from foot. Kāzı-zāda, a leading man . arrived from Fathābād bringing with him many war-boats

This Fathābād was a Sarkār named after Fath Shāh, Sultān of Bengal, and comprised parts of the modern Jessore, Farīdpur, Southern Bāqarganj and Dāccā districts The chief town was Farīdpur (Blochmann in J A S B 1873, p 217) Farīdpur is shown in Constable, 29 D d

VI 69, l 8 Jaimil (son of Māldeo). died His wife, the daughter of Mūna Rājā was unwilling to burn

The words enclosed in brackets must be a conjectural gloss or interpolation. There is nothing corresponding to them in the text (III, 402), according to which, Jaimal's wife was the grand daughter of Māldeva, the great Rāthor Rājā of Jodhpur The name of Jaimal's father is not given anywhere by Abu-1-Fazl Blochmann suggested that Jaimal was the son of Rupsi, who was a nephew of Bhārmal and cousin of Bhagwāndās Kachhwa of Amber. (Āīn, Tr I 427-8) M1 Beveridge (A N. III Tr 564, Note) and Mr Vincent Smith (Akbar, p 226) have endorsed his opinion or conjecture It may be a 'good shot', but, unfortunately, there is nothing except the name to go upon and there were several other Rajputs called Jaimal in Akbar's service 'Mūna Rājā' on line 10 is an error for 'Mota Rājā', the 'Fat Rājā', Udaysinha, son of Māldeo, was so called, because he was very corpulent

VI 69, l 4 from foot. At the new moon of Amardad, Sādih Khān attacked him

This is not a correct rendering of عرفة امرداد (Text, III 407), the first day of Amaidad, the fifth month in the Ilāhi calendar As the Ilāhi reckoning was solar, it is scarcely proper to speak of its first day as 'its New Moon' "The New Moon of Amardad" would strictly mean that day in the

month of Amardad, on which the Moon became New-a very different thing. VI. 70, l. 11. He [Murtizā Nizām Shāh], like his father before him, preferred Burhān to all his friends.

او بائين بدر برهان را بيشتر دوست داشتي و از همه گرای شردی (III. 407, l. 11). The pronoun must stand for the noun [مادر] which immediately precedes it and Mr. Beveridge takes it to mean that "She [Murtizā's mother], like his father before him, loved Burhān most and preferred him to all others." (Tr. III. 603). She was a Persian lady of noble birth and was called Khūnzā Humāyūn, as the wife of Sultān Ḥusain Sharqi was styled 'Khūuzā Sultān.' VI. 71, l. 1. He [Burhān] went to Kutbu-d-dīn Khān at Bīdar [from Baalāna].

"Bīdar" is an error for 'Nadarbār'. (See Text, III. 408, 1.9; Tr. III. 605). The Mughals were not masters of Bīdar at this time. Qutbuddin Khān had been appointed Atāliq of Prince Salīm and afterwards governor of "Broach as far as Nadarbār". (Āīn, Tr. I. 333-4).

VI. 72, l. 3 from foot. Bhāti is a low-lying country. ... It extends 400 Kos from east to west and 300 from south to north.

"Bhāṭi" literally signifies "low lands overflowed by the tide" but usually designates and is used for "the coast strip of the Sunderbans from Hijili to the Meghna, Lat. 20°-30′ to 22°-30′ N. and Long. 88°-0′ to 91°-14′ E." (Āīn, Tr. II, 116 note). A. F.'s description of its boundaries is neither easy to follow nor in agreement with this connotation. He appears to have included in Bhāṭi almost the whole of Eastern Bengal and even parts of Sylhet, (Beveridge. A. N. Tr. III. 646 Note). but even then it would comprise only four degrees of Longitude, i. e. about 270 miles. The figures for the breadth (400 Kos) as well as the length (300 Kos) are manifestly inflated, as Abu-1-Fazl himself states elsewhere that the entire extent of the province of Bengal from Chittāgong in the east to Garbi in the west is 450 Kos, and from the hills in the north to Madāran in the south only 220 Kos. (Āīn, Tr. II, 115; see also 326 infra;

VI.73, l. 15. 'Isā made ticelv' zamindārs of Bengāl to become his dependents.

twelve, (J.A.S.B XLIV 1875, p. 305). Manrique gives still another list, viz the Bhuyas or Boiones, as he calls them, of (1) Bengala, (2) Anjelim (Hıjılı), (3) Orıxa, (4) Jassor, (5) Chandecan, (6) Medinipur, (7) Catrabo, (8) Bacala, (9) Solimanvas (Sulaimānābād), (10) Bulva, (11) Dacca and (12) Rajmaol (Itinerario, Text, p 20, quoted by Dr H Hosten in J A. S B 1913, pp 437-438, Trans Hakluyt Society's Ed Luard, I 52). This list is apparently complete, but that is just the reason for suspecting it, and some at least of the names are faked "The strange thing about it, [Sir] Edward Gait writes, " is that they are always twelve and that there were twelve Bhuyas in Assam also Nar Narayan of Kuch Bihar had twelve ministers of state twelve chiefs or dalus administered the hilly portions of the Raja of Jaintia's dominions and there were twelve State Councillors also in Nepal" He suggests that "the number appears to have been connected in the minds of the people with all dignitaries ranking next to a Raja and so have come to be used in a purely concentional sense" (History of Assam, 37) He is probably right There never were exactly twelve of them at any time.

VI 73, l 20 The army of Shāhbāz Khān reached the banks of the Ganges, near Khizrpur

Khizrpur is a very common place-name in Deltaic Bengal, where the cult of Khizr, a sort of Water-god, was very widely spread Dr Wise thinks that this Khizrpur must be the place so called, which lies about a mile north of Nārāinganj in Dāccā district. It was the seat of 'Isā Khān of Bhāti "At this point, the Ganges, the Lakhiya and the Brahmaputra formerly met. Here also was the chief naval port of the Muhammadan government. It is only three miles from Sunārgāon and nine from Dhākā" (J A S B 1874, pp 211-212, see also Foster, E. T I 28 Note)

Katrāpur (1 8 f f) or Katrābo is a Tappa on the Lakhīya, opposite Khizrpur (Ibid, 1875, p 182, Hosten, loc. cit 440, Manrique, I 49 note)
VI 74, l 1 The Imperial officers then took post at Totak on the bank of the Brahmaputra.

This may be "Toke, which lies north of Dicca and at the head of the Lakhia or Bannar river, where it leaves the old Brahmaputra" (Beveridge, A N Tr III 650 note)

VI 7½, l 5 from foot Katlū Kirāni.

But see ante 66, where A. F himself speaks of Qatlu as a Lohām, and that is correct B also calls him 'Nohāmi' (II 323, Tr 333), which is a dialectical form of Lohāmi He is called 'Lohāmi' in the Makhzan also (Dorn, I 183, E D IV 513, note)

VI 75, l 11 Shahbaz Khan occupied a position on the Panar river, a branch of the Brahmaputra.

Recte 'Bannar', which unites the Brahmaputra and the Lakhiya, i e. the Burhi Ganga (A. N III, Tr 658 note)

It is said here (1 6ff.) that the large war-boats "were called 'Biyara' in the language of the country" But the BI. Text reads Binara or

Biyārā. Mr. Beveridge proposes to emend this and read 'palwār,' but I venture to suggest that the right lection is نارا 'Nabārā.' the Bengali pronunciation of 'Nawārā', which is said by Mu'atamad Khān (Iqbālnāma, Text, 220, 1.5; 409 infra), to be the Hindi word for "war-boats." It is used again in the same sense at Ibid, Text, 223, 232; 411, 413 infra. The word occurs also in the Ain (Tr. II. 115) and Abu-l-Fazl states that the Afghān Sultāns of Bengal had at their disposal for warlike purposes 20,000 horses, 100,000 foot, 1000 elephants and 4000 or 5000 war-boats (Nawāra). This passage is copied in his Tūzuk (101, l. 9; Tr. I. 207) by Jahangir, who uses the word in another place also and states that he appointed Intimam Khan to the command of the Nawara (fleet) of Bengal.' مير بحرى و سامان نواره بنگال (Text, 68, 1. 10 f.f.=Tr. I. 144). See also 67, 72 ante and 111 post, where these war-boats, vessels of war or Nawara are again mentioned by Abu-l-Fazl in connection with military operations in Bengal. See also A. N. III. 70; Tr. 97. Navārā is said in the Hindi Shabda Sagar, to be a word meaning 'ship or boat' which is derived from the Sanskrit Nāva. The Sanskrit and Hindi 'va' is always pronounced by Bengalis as 'ba,' and 'Nabara' is rightly said to be the form 'in the language of the country.'

VI. 76, l. 5 from foot. After eight days' retreat, the army rested to take breath at Sherpūr.

This must be Sherpūr Murcha, which is now in Bogrā district. (A. N. III. 660 note). It is again mentioned as 'Sherpur Miraja' on 1.7 f. f. of p. 77 and 1.6 of p. 79 infra. It is so called because there was a 'Murcha' or Thāna, i. e. a fortified post here. (J. A. S. B. 1873, p. 221; I. G. XXII. 273). Constable, 29 C c. There are at least four places called Sherpur in Bengal, viz. this one south of Bogrā, Sherpur in Maimansing (Constable, 29 D c), Sherpur Firingi in Bikrampur and Sherpur 'Aṭāi in Sharīfābād Sarkār (Āīn, Tr. II. 140), 18 miles south-west of modern Murshidābād, where Mān Sinha defeated 'Uṣmān Lohāni in 1598 A.C. (A. N. III. 784; Tr. 1174; Beames in J. A. S. B. 1883, p. 236; Blochmann in J. A. S. B. 1874, p. 283 note).

VI. 77, l. 19. On reaching the Jumnā, he learnt that M'asūm was at Sherpur.

Mr. Beveridge thinks that this must be Sherpur-Firingi, now in Bikrampur. It is also called 'Firingi Bazār', just as Mālda is called 'English Bazār'. (A. N. Tr. III. 673 Note).

V. 79, l. 1. The rebels.....took up a position on the banks of the river 'Mangalkot

Thornton says that the town of Mangalkot lies 71 miles N. N. W. of Calcutta, in Burdwan district. Lat. 23°-30′ N., Long. 87°-56′ E. The river is called Ajai or Adjai. It is a place of note and there are several old tanks and mosques in a fair state of preservation. (J. B. O. R. S. 1917, III. pp. 372-3). Constable, 29 C d.

VI. 79, l. 2 from foot. At this time, a force was detached against Kokra,

ł,

a flourishing country lying between Orissa and the Dakhin

Dowson suggests that the district meant is 'Khoorda' (near Cuttack in Orissa) But 'Kokra' or 'Khokra' is the old name of Chutiā Nāgpur (Āīn, Tr I. 479) Kokra is mentioned by Jahāngīr also in his Tūzuk (Text, 154, 344-6 2nfra) The country was merely overrun at this time and the Rājā (Mādhu Sinha) compelled to promise tribute, but it was more completely subdued and its diamond mines taken possession of by the Mughal Governor, Ibrāhīm Khān Fath Jang in 1024 A H (1615 A C)

VI. 80, l. 15 Kokaltāsh [Zain Khān] built a fort at Jag-dura in the midst of the [Yusufzai] countrij [Swāt]

This is 'Chaldara' on the north side of the Swāt river near Malakand It is in "the Lanwdah division of Swāt, opposite Allahdand, the chief town of Lower Swāt, which is centrally situated and commands one of the ferries over the Swāt river" (Raverty, N. A 259). I. G Atlas, 33 C 2 The Karākār Pass (1 3 ff) lies east-south-east of Chakdara and separates Swāt from Buner (Ibid, 259, 261) Lat 34°-44′ N, Long 72°-8′ E

VI 80, l 17 Twenty-three times he [Zain Khān] was victorious, and he destroyed seven armies.

Raverty denounces Dowson's rendering of Sangār (which is the word used here) as absurd It really means 'breast-works' He also asserts somewhat hypercritically that the 30,000 and 40,000 houses of the Yūsufzais were not so many 'houses', but 'families'. (N. A 259 note) The Altamsh, Iltmish or Yaltmish (1 13) was the 'advanced guard' The word literally means 'sixty' in Turki and Mr Irvine thinks it possible that "the advanced guard originally consisted of that number of men and the name was afterwards used for it regardless of the actual number of men employed" (A I M. 226)

VI 82, l 10 Hasan Khan Tabati was carried off wounded

The sobriquet is variously written Mr Beveridge reads it here as 'Patani' A) N III 483, Tr 729), but in Vol II, p. 380 note, and III 115 note, he says that Batani is the correct form Raverty tells us that the 'Batanis' are descended from the son of Bait (or Batan), the son of 'Abdur Rashīd (N A 262 note) Fath Khān Batani is mentioned in the T A. (268, 1 15), Hājji Khān Batani in E D IV 378 Note and Ādam Khān Batani in Dorn I 128 and A N III. 133—Tr 189 Abu-l-Fazl states that the Batanis or descendants of Batan, the youngest son of Afghān, include the Ghilzāi, Lodi, Niyāzi, Lohāni, Sūr, Bani (Pani), Sarwāni and Kakbūr (or Gakbūr) tribes (Āīn, Tr II 402-3. See also Ibid, Tr I 204 Note and 476).

VI 83, l 8 They marched towards the lofty mountain of Bulandrai The correct form is 'Malandaiāi' and Raverty (N A 265 note) laughs at Malleson for calling it 'Bilandri' on p 194 of his 'History of Afghanistan' 'Balandari' and 'Malandari' are both found in the B L text of the Ain. (Tr. II. 391 note). Mr. G. P Tate says that the Malandari pass

lies at the head of the Barkua stream, about thirty miles north-east of Hoti Mardan. (Kingdom of Afghanistan, 24 Note).

VI. 84, 1. 14. A force took Sānwali-garh from Nāhir Rāo.

Sänwlägarh is a pargana in Betül district, C. P., in a wild tract of hill and forest towards the west, where the northern and southern ranges of mountains meet. (I. G. VII. 7). See the Map in Bayley's Gujarāt.

VI. 85, l. 7. From want of proper information, a force was sent into an intricate country near Kherla, and suffered great loss.

Kherla lies about four miles from Badnūr in the Betūl district of the Nerbudda division of the Central Provinces. (I. G. VIII. 8). The Rājās of Kherla are frequently mentioned in the history of the Khalji Sultāns of Mālwā as well as of the Bahmanis of Gulbarga.

VI. 85, l. 12 from foot. At this time [XXXVth year], Pādre Farmalīûn arrived at the Imperial Court from Goa.

General R, Maclagan suggested forty years ago that this name was a perversion of either 'Leo Grimon' or of 'Duarte Leioton'. (J. A. S. B. 1896, p. 42 note). Mr. Beveridge accepts the suggestion, but in a different way and thinks that Abu-l-Fazl has mixed up the surnames of the two men, viz.' Grimon 'and 'Leioton 'and made "Qarmaliūn" by combining them into one name. (A. N. Tr. III. 873 note). But as Leioton did not come to Lāhor till 1591 and 'Farmaliūn' was there in April, 1590, Leioton cannot be meant. A simpler and more probable explanation seems to me to be that A. F. wrote غرضاون, 'Gharmanleon', merely reversing the position of the Christian name and the surname. He could not make any distinction between the two and to him it was the same whether Leon was placed first or last, whether the name was written أو تر مناون Ghermon Leon. The initial أو تر مناون is an evident error for È and the copyists must have missed out the nun of 'Gharman'.

VI. 86, l. 9. He [Rājā Mān Sinha] halted at Jahānābād.

There are two places of this name, one in Gayā district, Bihār, and another in the Hūgli district, on the banks of the Dhālkishor river. This is the latter. It is on the route from Calcutta to Bānkūrā, 45 miles north-west of the former and 56 miles west of the latter (Th.). Constable, 29 B d. Bishanpur (l. 23) also is in the Bānkūrā district and lies about forty miles north-west of Jahānābād. Constable, 29 B d.

VI. 88, l. 4 from foot. He sent him by way of Jhārkand, the Benares of that country, against Orissa.

VI. 90, l. 15. Somnāt, Kokā, Māngalor, Mahū and Paro and seventeen other ports fell into his [Khān-i-'Agam's] hands.

Four out of these five toponyms are wrongly spelt and should be read as Ghoghā, Māngrol, Mahūwā and Por, i e. Por bandar Ten ports of Gujarāt and Kāthiāwād are enumerated in the Aīn, (Tr II 259)

'Nur Beg Khan' (1 22) is an error for 'Naurang Khan'. He was the son of Qutbu-d-din Khan who was treacherously put to death by Sultan Muzaffar III (Ain, Tr. I. 334).

VI 91, l. 17. At the town of Shakhupur, Khan Khanan was summoned to an audience.

This may be Shaik hpurin Khāngāh Dogrān tahsīl of Gujran-wāla district, twenty-four miles south of Hāsīzābād and north-west of Lāhor It contains a ruined fort said to have been built by Prince Salīm, afterwards the Emperor Jahāngīr. That Emperor tells us that 'Shaikhū Bābā' or 'Shaikhū' was the name by which he was always called by Akbar, on account of his birth having been predicted by Shaikh Salīm Chishti (T J. Text, 1, 1. 8 f. f.=Tr L 2) See also I G (XX. 270) The town is mentioned at 240 infra as 'Shaikhpur' The name is written Shikohpur in Constable, 24 E b, and that name is supposed to have been given in honour of Dārā Shikoh

VI 93, l 1 Sādik Khān brought up an old grievance which he had against Shāhbāz Khān and rarely went to the Darbār

This is putting the saddle on the wrong horse It was Shāhbāz who did not go to the Prince's Darbār. Sādiq was the Atālīq or 'guardian' of the prince and was all in all on the spot Shāhbāz was an outsider who had just come from Mālwā (cf Text, III 699, Tr 1046 and Note).

VI. 94, l. 9 from foot. In this year, there was little rain, and the price of rice rose high

Pattan (1 1) is 'Mungīpattan,' (also called Paithan), on the Godāvari, a very ancient town, which is said to have been the capital of Shālivāhan. See my note on E.D Vol I, 60, 1 ante

VI 95, 1 13. The army marched from Shāhpūr and took up a posttion twelve Kos from Fathari

This is the 'Shāhpur' founded by Prince Murād in Akola, Berār, six Kos from Bālāpūr Constable, 31 D a. The B. I Text gives the name of the battle field as 'Āshti' (III 718, Tr 1070) It is called 'Āshta' by Constable and is in Parbaini, Haidarābād State It lies north-west of Pāthri or Pātri Constable, 31 D b Three other places called 'Ashta' and three known as 'Ashti' are also shown in the Atlas

VI 96, l 6 Dwarka Das and S'aid Jalal retired to Nilawi

دواركا There is no such place as 'Nīlawi.' What the Text says is that دواركا III 719, 1 14) 'Dwārkā Dās and Saiyid Jalāl nobly played away their short [lit. 'of, three to five days']

1

lives." (Tr. 1071). 'To Nilawi' is due to a misreading of بنيكونى ba-nīkūi, VI. 101, 1.2 from foot.

On line 14, it is said of the Imperial forces that "they had all " gloriously."

On line 14, it is said of the imperial forces that they which is night suffered from thirst and now carried the river Sugam, mgnt suncted from thirst and now carried the river Sugam, marched wrong as well as meaningless. What they did was that they wrong as wen as meaningless, what oney one was that oney marched (lit. turned their steps) towards the river برداشند (lit. turned their steps) towards the river را سوگا برداشند. (at. turned their steps) towards the river anywhere in these parts. Mr. Tr. 1071). There is no river called 'Sugām' anywhere in these parts. Vincent Smith speaks of this battle having been fought at "Supa on the Godavary, (Akbar, 270, 360), but there is no such place as Supa in

the Haidarabad territory. He has been misled by a statement of Blochmann's (Am, I. Tr. 336), which is made on the authority of Firishta, but mann's (Ath, 1. 11. 200), which is made on the authority of Ethishea, but what F. really says is that "the Khān-i-Khānan and Rājā Ali Khān

of Burhanpur encamped at Sonpet on the Godavary and the battle took of Durnaupur encamped at Dunpet on the Guadouty and the Davide took, place after they had crossed the river." (I. 270, l. 4; II. 163, l. 5). Sonpet,

is Soanpet in Nandair district and is shown in Constable, Pl. 31 D b. See also Mr. Beveridge's note to A. N. Tr. III. 1071, but it is not quite correct. VI. 97, 1. 9 from foot. [Prince Murad] died near Dihbari, on the banks

Read 'Purna' for 'Purta' Mr. Beveridge has left 'Dihbāri' unidentified. Perhaps it is 'Dhabadi', which lies about 30 miles north-east of Daulatābād and 18 north-west of Jālna (Th.). It lies on a branch of the river Purna in Bhokardan taluka, 16 miles south of the town of the same river rurna in Dhonardan taluna, to mines bouth of the town of the same name. (Aurangābād Gazetteer, 843). 'Dhabadi' is shown in Constable,

VI. 98, l. 11 from foot. Maha Singh... attacked them at Bhadrak. 31 Ca. Lat. 200-2/ N., Long. 750-46/ E. (Th). Bhadrak was one of the Malials of Orissa in Akbar's Rent-roll. (Am, Tr. II. 126, 143). It is now in Balasore district, Orissa, and lies 41 miles

Death of Jalala, the Sectary Jalala south-west of Balasore town. Constable, 32 E a. is generally called 'Tariki', Sectary.

Dowson finds fault with Chalmers and Elphinstone for reading the VI. 101, l. 4 and foot note.

sobriquet as 'Tājīk' and remarks that Jalāla's followers were Yūsufzais, not Tajiks. But his own meaning of 'Tariki' is equally open to censure. not Lajiks, Dut his own meaning of Larike is equally open to censure, Tariki really means one engulfed or immersed in (spiritual) darkness. It was only a nickname coined by the Akhund Darweza—a venerated Afghān saint, for Bāyazīd Anṣāri, the founder of the sect. Bāyazīd called himself 'Fir-i-Raushan', the Enlightened Pir'. The Akhund dubbed him in derision 'Pir-i-Tarik', the 'Darkened Pir'. (Raverty, N. A. 46 note). Akbar who was very fond of word-play was delighted with the antithetical retort and his historians were only too ready to repeat and ring One of the great vassals of Adil Khan Bijapuri

the changes upon it. VI. 101, l. 2 from foot.

The B. I. text gives his name as Wankū. (III. 788; Tr. 1180). I ven ture to identify him with Wankoji [Venkoji] Naik Nimball of Phaltan, better known as Jagpāl Rao Nāik Nimbālkar, who lived in the early part of the seventeenth century and was "notorious for his restless and predatory habits" Dīpā Bāi, the sister of Jagpāl Rāo, was the grandmother of Shivāji. The Nimbālkars were made Sardeshmukhs of Phaltan by the Kings of Bījāpur and derived their name from the village of Nimbālik, now called Nimluk (Grant Duff, H M 39, 40) Elsewhere, Abul-Fazl says of this Wankū that he sought shelter in Ahmadnagar from the oppression of the Bījāpur soldiers He had, before that, sent his eldest son Bābāji and his brothei Dhār Rāo to solicit the Khān-i-Khānān's protection, but as the Khān put them into prison, he had fled to Shāh 'Ali in Ahmadnagar, who also consigned him to a dungeon (III 794-5, Tr 1191) He is described as a great landholder of Ahmadnagar, commanding 5000 horse and 12000 foot, who had quarrelled with 'Ādil Khān and had come over to the Mughals (Ib III 788; Tr. 1180)

VI 102, l 5 He got possession of Kālna, which is one of the chief forti esses of Ahmadnagar

'Kālna' (Recte Gālna) and 'Jālna' are quite distinct, but are often confounded and even Mr Beveridge has mixed up the two places (See his Tr of A N III 1181 note, 1189 note and 1197). Jālna is the Jālnāpur, which is mentioned only three lines higher up It is now in Aurangābād district, Haidarābād State Lat 18°-51′ N, Long. 75°-56′ E. Constable, 31 C b It is the Jālna of the I G XIV 29, to which Mr Beveridge refers 'Gālnā' is now in the Mālegāon taluka of Nāsik district Lat 20°-46′ N, Long 74°-32′ E (I G XII 124) Jālna belongs now to the Nizām, Gālna is in British India Kālna [Gālna] was the place taken by Abu-l-Fazl, Jālna or (Jālnāpur), the town to which the Khān-i-Khānān went.

VI. 103, l 2 The Takmīla-i-Akbarnāma of 'Ināyatu-lla

The authorship of this 'Takmila' is a puzzle which has not been satisfactorily solved There are at least three recensions of the Continuation, which differ considerably in matter from one another Dr. Rieu points out that "there is a Ms in the British Museum which also is stated to have been written by 'Inayatulla bin Muhibb 'Ali, but which is quite distinct from the similarly-entitled history, extracts of which are given in Elliot, VI 103-115 While, in the latter, the murder of Abu-l-Fazl is told in a few words and without any direct implication of Jahangir in the crime, the author of the present work narrates the same event in the most circumstantial manner and distinctly states that Birsingh Dev. the murderer, acted at the instigation of Jahangir" (Persian Catalogue, (Supplement), IV 52, see also III 929, 1031) In the copies in the India Office Library, the compiler is called 'Muhammad Şālih' (Ethe, Catalogue, Nos. 260, 261, column 106), but elsewhere he calls himself 'Ināyatulla or Muhammad Silih, as in the Ms used by Dowson Dr Rieu surmises that this Muhammad Salih must be Muhammad Salih Kambu, the author of the 'Amali-Kalih and he thinks that the name 'Inayatulla may be accounted for by the fact that Muhammad Sähly had an elder brother called 'Inayatulla,

who wrote the Bahar-i-Danish and also compiled a General History of the World called Tarīkh-i-Dilkushā. (Rieu, 765, 1093). He proposes to substitute 'and' for 'or' in the clause just cited and suggests that it may be the joint production of the brothers. See III. 929, 1031. Mr. Beveridge has appropriated this suggestion and made it his own. Unfortunately, the three discrepant recensions militate against the supposition of their joint authorship. The Text printed in the Bib. Ind. differs admittedly from that used by Chalmers and the two Mss. in the India Office differ from both, though there can be no doubt that they are all copied, paraphrased or rewritten from the earlier portion of Iqbālnāma-i-Jahāngīri, which was completed in 1029 H. 1020 A. C. (A. N. III. Tr. 1201-5 note). Perhaps the true explanation is that the brothers wrote, not jointly, but successively. The version in which Jahangir is exculpated may be the one first drafted and compiled by 'Inivatulla. It may have been subsequently revised and recast, in accordance with later opinions on this and other points, by 'Inayatulla himself or Muhammad Silih Kambu who speaks of himself as the pupil and protégé of 'Inayatulla in his Preface to the Bahar-i-Danish. Jahangir's infatuation for Nur Jahan, his weakness and other defects of character are the subjects of frequent animadversion in the 'Amal-i-Ṣālih. VI. 104, l. 6 from foot. It has already been related that Sultan Salim had set out against the Raja of Ajmir.

Ajmer was not under any Rājā at this time and the B. I. text (III. 805-6) puts the matter very differently. "On 6th Mihr (XLIV R. Y.), the Prince Royal [Salīm] obtained leave to go to Ajmer to chastise Umrā, the Rānā [of Udayapur]". (III. 763; Tr. 1140). Umrā is Amar Sinha, who had succeeded his father Rāṇā Pratāp. Salīm was now (XLVII R.) sent again to Ajmer with a view to invade from that point d'appui the restricted territory that still remained in the hands of the Rāṇā of Chitor. See also A. N. ante 98 and Khāki Shīrāzi, 204 post.

VI. 106, l. 9. Bāz Bahādur, the Imperial commander, retired to Bhowāl. Bhowāl lies north of Dāccā, and is a jungly tract extending to the Garo Hills. The town is shown in Constable, 29 D d.

'Sarīpur' and 'Bakrampur' (l. 17) which were in or near the country of 'Isā Khān of Bhāṭī are 'Srīpur' near Rājābāri, at the confluence of the Meghnā and the Padmā. Bikrampur lies a few miles south of Dāccā. Bikrampur is marked in Constable, 29 D d. Srīpur has been long since washed away by the Padmā. (Foster, E. T. I. 28 note).

VI. 109, l. 10. [The Magh] Rājā who had just now acquired the country of Bangu.

must be an error for Pegu. The Magh Rājā who is said to have just acquired the country was the Rājā of Ārākān. (A. N. III. 479=Tr. 722). The people of Ārākān are known as 'Mugs'. (q. v. H. J. s. v.). We know from local histories that the Ārākān king, Minrazagyi, who reigned from 1593 to 1612 A. C.) had invaded and sacked Pegu, with the assistance of the Portuguese under De Brito in 1599. (C. H. I. IV. 487, 493-494).

VI. 111, l 5 Kaid Rai of Bengal

The correct name is 'Kedar Rai'. (A N III 824, Tr 1235) He was one of the twelve Bhūryās of Bengal and had his seat at Bhushna, which is now in the Faridour division of Bengal In Todar Mal's Rent-roll, Faridpur was included in the Sarkar of Bhushna, alias Muhammadabad "Kedar Rai and Chand Rii had gradually extended their sway from Rānābāri in Dāccā district to Kedāibāri, now in the Palang thana of Faridpur, where a deep ditch and a road known as Kach Kijura maik the site of their fort" (I G XII 54-5) Abu-l-Fazl records that Kedar's fort of Bhushna was taken by the Mughals in the 41st year (1596 A C), after a battle in which Kedar was wounded and fled to 'Isa Khan of Bhati. (A N. III 711, Tr 1059) He also states that Chand Rai had been killed in a fight with the Afghans sometime before (Ib III 632, Tr 969) This Chand Rai is mentioned by Ralph Fitch, who states that he went in 1586 from Bacola [Bakla, the old name of Bagargan] district] to Serrepore (Sripur), the king of which place was called 'Chondery' He says that 'Serrepore' was six leagues from 'Sunnergan' (Sonargaon) (Foster, E T. I. 28, J. H. Ryley, John Fitch, p. 118)

Kılmāk, who was the Imperial Commander in Srīnagar (19), is identical with 'Bāz Bahādur Kılmāk' of 106 ante (A N Text, 809, Tr III, 1214). He is also called Sultān 'Alī Qılmāq. (A N III 820, Tr 1231) Jahāngīr says that he had long been guilty of evil practices in Bengal, but afterwards repented of his errors and had the honour of kissing the threshold in the 1st year of his reign (T J. 37, 124, Tr I 78 and 88, 131, Tr I 184)

VI. 114, l. 12 from foot, [Dāniyāl's servants] continued to introduce the poison [spirits] unperceived, sometimes concealing it in the barrels of muskets.

This extraordinary method of smuggling the forbidden stuff is also mentioned by Dāniyāl's brother Jahāngīr, who states that "a musketeer named Murshid Quli, who was one of Dāniyāl's attendants, poured, at the urgent entreaties of the Prince, double-distilled spirit into his favourite gun. The rust of the iron was dissolved by the strength of the spirit. The prince no sooner drank of it than he fell down" (T. J. Tr. I. 35, Text, 15, 1. 11 f.f.)

VI 115, l 2 On Monday, the 12th Aban, corresponding with the 20th Jumāda-l-awwal, 1014 Hijra (September 1605), an illness instituted itself into the frame of the Emperor [Akbar]

The Hāhi month is wrongly stated, though the Hijri date is right. The B I. text has 12th Mihr and this is the correct Hāhi date. 20th Jumādi I was 24th September 1605–12th Mihr is the 199th day of the Hāhi calendar and the 267th (68+199) of the Julian. The Emperor's illness lasted for 23 days and he died on 16th October, O. S. corresponding to 4th Abān Hāhi. (A. N. III 841, Tr 1259-1261 and Note)

The proximate cause of death was diarrhoea followed by dysentery. The story of the Emperor having died by misadventure in an attempt to poison Mirzā Ghāzi of Thaṭṭa or Rājā Mānsinha of Amber is discredited by Mr. Irvine (Manucci, IV. 420 Note) as well as by Mr. Beveridge (A. N. Tr. III. 1260 Note), Mr. Crooke (Tod, A. A. R. I. 408; III. 1338 Note), Dr. Beni Prasād (Jahāngīr, 75 note) and even Mr. Vincent Smith (loc. cit. 325-6), though it is repeated by Terry (Voyage, 408), Herbert (Travels. 72), De Laet (Tr. Hoyland, 170), Mundy (Journal, II. 102-3), Manucci (I. 149) and others.

We know little of Akbar's clinical history, but it is certain that he had been suffering for many years before his death, from a very painful intestinal disease of some sort. We are told that this last and fatal illness began on 12th Mihr, that no medicines were administered or taken for eight days, that 'a bloody flux' then made its appearance. that it was treated without success for ten days, upon which the physician abandoned hope and fled from court. It is also stated that when the Hakim 'Ali attempted to arrest the diarrhoea by powerful astringents, they only brought on fever, strangury and other symptoms prognosticating a fatal termination of the disease. Whatever the exact pathology of the case may have been, it is certain that this intestinal complaint was one of long standing. Akbar had been seriously ill just in the same way in 991 H. (XXVII R. Y.). He had, then, as now, as Abu-l-Fazl puts it, 'an internal pain' on 20th Mihr, did not or would not take any medicine for some days, upon which "blood came." Laxatives were then administered on the urgent entreaty of Abu-l-Fazl, against the advice of the Hindu physicians, and Akbar recovered only after thirty-six days. During three days of this illness, he "touched no food" and had to "eat only boiled things without any oil or ghee" for seventeen days. (A. N. III. 394=Tr. 583-4). Firishta also mentions this attack of fever and diarrhoea (اسمال) and states that "great anxiety was felt on his account, as His Majesty had, like his father Humayun, taken to opium." (I. 264, I. 6 f.f.; Briggs, II. 253). Akbar had another attack of 'severe pain' in the bowels in the 34th year (997 H. 1589 A. C.). He was then forbidden all food for two days and afterwards allowed "only two spoonfuls of soup". He used to say, writes Abu-1-Fazl, that he had often been ill, but that the pains of those days had been such as he had never experienced before. (A. N. III. 552=Tr. 838). Towards the end of the same year (the 34th), he had another attack of "pain in the abdomen which caused great distress". (*Ibid.* 575; Tr. 870). Budāuni informs us that the same trouble, "stomach-ache and *colic*" recurred in the 36th year (999 H.) and he was so ill that he suspected Prince Salim of having poisoned him and openly said so. (II. 377=Tr. 390). He must have been again ill in the 42nd year (1597 A.C.), as Jerome Xavier states that he was privileged to enter the Emperor's bed-room and nurse him. (Smith, Akbar, 269; J. A. S. B. 1896, pp. 72-79). In the 44th year, he had two attacks of similar pains in the stomach, one

after the other, at short intervals (A.N III 766=Tr 1144-5). It has to be borne in mind that Akbai was "a hard liver" and addicted not only to arrack (double distilled spirits), but to Bhāng, opium and Kohnār or Pousta. It is common knowledge that when an opium-eater suffers from diarrhoea, it is an almost sure sign of death Hakim 'Ali must have been well acquainted with the prognosis of violent and continuous diarrhoea in the cases of habitual opium-eaters and he gave up all hope because he found that the patient's system had ceased to react to his powerful drugs Mr. Crooke asserts that Akbar died of cancer of the bowels, but the evidence available is not sufficient to warrant such a definite diagnosis.

The origin of the popular canard about the exchange of the poisoned packet of betel is possibly this As Mirzā Ghāzi was suspected of treason, he had been ordered to come to court. He made his Kurnish and received the betel on the 14th of Mihr, just two days after the Emperor was taken ill. Mān Sīnha had done the same, some days before on receiving promotion and the appointment of Prince Khusrav's guardian on or after the 16th of Shahrīyar (A. N. III 839, Tr. 1257)

VI 115, l 16 On the 9th of Azur, corresponding with the night of Wednesday, 12th Jumāda-l-Akhir he [Akbar] bade adieu to life.

Here also, the Ilāhi date is stated wrongly. It is given as Wednesday, 4th Ābān in the B. I text of the A. N. (III 841, l. 13) and as 2nd Ābān by the Bādishāh Nāma (I. 1 66, l 17), 'Amal i-Salih (I 15-16) and Khwāfi Khān (I 235, l 5) 12-13th (Hīsābi) Jumādi II 1014 H corresponded with 15-16th October 1605 OS 25-26th October N S Wednesday, after the midnight of which Akbar died, was 13th Hisābi and 16th October (O. S) As 9th Āzur 50 R Y was the 256th day of the Ilāhi year, which began on 11th March O S, it would be 21st November. But 2nd Ābān,—the 219th day—would be 15th October O S If it was the 4th of Ābān,—which appears to be correct—the Julian correspondence would be 17th October O S, or 27th October N S. (See my H S M N 266-7)

VIII., l. 9 from foot. He [Asaf Khān] desired to gain possession of the land of Panna, [belonging to] Rājā Rām-chand, whose ancestors had always ruled it

"Dowson notes the variant 'Palta' The right reading is "Bhata" Rāmchandra was the Bāghela Rājā of 'Bhata' or Bhatghora, now Rewā Cf. A. N. at 32 ante, from which this account is borrowed. Rāmchand is there said by Abu-l-Fazl to have been the son of Parbihān [Bīrbhān] and grandson of Bīrsingh Deo, who were both Rājās of 'Bhata', not Pannā. (Aīn, Tr. I. 367).

The 'Nisba' or sobriquet of Ghāzi Khān was not 'Tātār', as it is printed on! 6 f.f., but 'Tonwar' "
Ghāzi Khān had sought Rāmchand's protection after his flight from Akbar's Court (A N II 182, Tr 281)
Lowe says that Ghāzi Khān 'Tannūri' fled to 'Hatiyah' [Recte, Bhata] (B. Tr.II. 65, Text, II 66, l. 11).

VI. 118, l. 9. Rājā Rāmchand [the Rājā of Bhaṭa] fled to the castle of Māndhūn, which is noted for being one of the strongest places in Hindustān.

'Mandhun' is a mistranscription of 'Bandhu' or 'Bandhugarh' which Thornton says, is in the territory of Rewa in Baghelkhand, sixty miles south-west of Rewa town. Hamilton also states that "Baundhoo or Bhatta was the name of the northern part of the Hindoo territory of Gundwana", and he locates the fort about 60 miles north-east from Mandla. (East India Gazetteer, Ed. 1815, s. v. Bandoogur). Abu-l-Fazl has 'Bandhu' in the corresponding passage. (II. 183; Tr. 282).

VI. 119, l. 9. Damūda, one of her [Durgāvati's] chief towns.

A. F. has 'Dāmoh' in the counterpart passage (A. N. II. 212; Tr. 327, 328), which must be correct. It lies about 65 miles north-west of Jabalpur. Constable, 28 A d. The actual site of the first battle which is here stated to have been four marches from Dāmoh, is said by local tradition, to have been near Singaurgarh in Garha Māndla, about 32 miles south-east of Dāmoh and 26 north-west of Jabalpur. The Rāṇi stabbed herself after a second defeat, in a defile, 12 miles east of Garha. (Sleeman, J. A. S. B. 1837. VI. 627-9; C. P. Gazetteer, 225, 283; Arch. Surv. Rep. IX. 48). The battle said to have been fought at Narhi, east of Garha, (C. H. I. IV. 88), must have been the second. Singaurgarh is shown in Constable, 28 A d.

VI. 122, l. 14. He [Muhammad Sultān Mirzā] was the son of Rashīd Sultān Wais Mirzā.

He was سررشيد or سررشيد of Wais Mirzā, i.e. Wais Mirzā's most worthy, intelligent, sagacious or wise son. 'Rashīd' was not a part of the father's name. (A. N. II. 279; Tr. 413; T. A. in E. D. V. 315; B. Tr. II. 87 note). The name of Wais Mirzā's father was Bāiqarā, not Bābakra, as on 1. 10.

VI. 126, l. 8. The army then proceeded towards Jasruna and Lakhanpur.

Recte, Jasrota, formerly a small state in North-Eastern Punjab, but now included in Kashmir. Lat. 32°-29′ N., Long. 75° 27′ E. Constable, 25 A a. It is one of the small Chiefships attached to the Jammu or Central division of the Alpine Punjab. (A. G. I. 133). 'Samba'(l. 11) lies a few miles north of Jasrota. Constable, Ibid. On l. 12, 'Balidar' is a mistake for 'Balbhadra'. Mr. Beveridge says 'Lakhanpur' must be wrong and proposes to read 'Lakhnūr' (Tr. III. 884 note) but 'Lakhanpur' still exists under that name and this spelling is quite correct. See Hutchinson and Vogel in the Journal of the Punjab Historical Society, VIII, (1918), No. 1, p. 49.

VI. 130, l. 8. On the 27th of the month [Rab'i II. 1003], Koka died a Lähore.

"Koka" means 'foster-brother' and Akbar had several of them—all sons of his numerous nurses, wet and dry. The person who is meant and whose name is left out must be S'ādat Yār Koka. He died of dipsomania on the 16th of Azar of the XXXIXth year, which began on 28th Jumādi

II. 1002 H. and ended on 8th Rajab 1003 (A. N. III. 656, Tr. 1006) There is some error in Fairi Sirhindi's chronology. He says (1.18) that the thirty-ninth year began on 9th Rajab 1003 H, but according to the A. N., the year which began on 9th Rajab 1003 H. was the fortieth (III. 667, Tr. 1023 See also E. D. V. 246, Smith, Akbar, 457)

VI 131, l 7 In his [the poet Fairi's] early days, he and the author of this work had some connection through using the same takhallus for their writings

This is obscurely, if not enigmatically, worded Budāuni clears up the matter Abu-l-Fazl's brother, the poet, and this Shaikh Ilahdād Sirhindi had, by some unhappy chance, chosen the identical nom-de-plume, Faizi. The former therefore requested Sirhindi to give it up and assume some other pen-name As the latter declined to do so, the former thought it best to alter his own to Fāyyāzi, so as to preclude the possibility of any confusion and also with a view to make it "correspond with the grammatical amplification" as Budāuni puts it, "of 'Allāmi, by which his younger brother, Abu-l-Fazl, was known" (E. D. Vol. V. 545, B, Text, III 299, l. 11)

VI 132, l. 18 His mother [of Prince Rustam, son of Prince Murad] was sister of Khān-i 'Azam

The lady was the daughter, not the sister of 'Azīz Koka, entitled Khān-1-'Azam She was married to Prince Murād in the 32nd year (995 A. H) of Akbar's reign. (A N III 518, Tr. 791 See also Āīn, Tr I 326) She could not have been the sister of 'Azīz, as Shamsu d-dīn Muhammad Khān, the father of the Khān-1-'Azam, was assassinated on 12th Ramazān, 969 H In other words, she would have been at least 37 years of age at this time in 1006 H, while her husband, Prince Murād, who was born in 978 H. (T A in E D V 232), could have been only 29 years old

VI. 136, l 6 On arriving at Gharhol, a submissive letter was received from Bahādur Khan

There is no such place as 'Gharkol' It is an error for 'Khargon' (A N III 768, Tr 1148) It lies on the left bank of the Kundi, a tributary of the Narmadā and is now the headquarters of Nimār district in the Indore State (I. G XV 251) Constable, 31 C a. (See my note on Vol III. 87, 15 ante). Von Noer also speaks of it as 'Gharkol' (Akbar, Tr II. 31) He must have been misled by Dowson's Translation Elsewhere, Faizi himself states that Prince Dāniyāl took leave of Akbar at Ghargon. [Recte, Khargon] (A N III, Tr 1184 notc)

VI 137, l. 18 A dog who accompanied him set off in pursuit of a hare, but the hare turned round and attacked the dog etc

This story is a folk-tale, which crops up in many places and is given as the reason for the selection of the sites of several other capitals, e g Annilwad, (Mwat-i-Ahmadi, Pt i. 31=Tr. in Bayley, 25, Ain, Tr, IL 262), Halwad (B G VIII, Kāthiāwār, 423), Kharakpur (J A S B XL 1871, p. 24), Rewā (I G. s. n), Bīdar (Ind. Ant XXVIII. 1899, p. 129)

and Vijayanagar. (Sewell, A Forgotten Empire, 19). Mr. Sewell observes that "a similar tale is told of the rise of almost every kingdom, principality or large Zamīndāri in Southern India." (*Ibid.* Note).

VI. 143, l. 11. Next day, Miyan Saiyid went round and looked afterthe construction of the trenches.

The person meant is the author's patron, Shaikh Farid, who was a Bukhāri Saiyid. 'Miyān' is a title of respect used before the names of Saiyids and other persons of quality in Hindustān. Saiyid 'Abdulla, the father of the famous King-makers, was generally known as Saiyid Miyān. (Maāgir-i-'Alamgīri, 227, l. 4).

Mr. Vincent Smith speaks of Shaikh Farid repeatedly as 'Shaikh Farid of Bukhāra'. (Akbar, 318, 399, 493). This is not quite correct. The sobriquet merely means that he was decended from some Saiyid, who had come to India from Bukhārā in the old days. Shaikh Farid himself was really born in Dehli. Jahāngīr explicitly says so. (T. J. 65, 1.6; Tr. I. 137; see also Blochmann, Āīn, Tr. I. 413).

Borgãon, (l. 20), which is said to have been eight Kos from Āsīr, is now in Nimār district. It lies about twenty miles north-west of Burhānpur. Constable, 31 D a.

VI. 145, l. 1. The mine was exploded [at the siege of Alimadnagar] on the 20th Shahryūr in the 45th year of the reign.

Khāki Shīrāzi (205 infra) and Abu-l-Fazl give the date as 6th of Shahrīvar (A. N. III. 775; Tr. 1159=100 ante) and calculation shows that 6th is correct. Faizi has just given the Hijri date as 18th Ṣafar, 1009 A. H., which corresponds with 19th August 1600 A. C. (O. S.). 6th Shahrīvar, [not Shahryūr], was the 162nd day of the Ilāhi year, which began on 11th March 1600. Now 19th August was the 232nd day of the Julian year 1600 and it synchronised exactly with 6th Shahrīvar Ilāhi (70+162). سنتم must have been wrongly written for مشتم or مشتم, which also occurs in some copies.

VI. 146, l. 11. On the 17th Safar, the royal forces were admitted and the keys of the fortress of Asir were given up.

Here also, the date is stated wrongly. Faizi has just stated (144, 1. 10 f.f. ante) that Aḥmadnagar was surrendered on the 18th of Ṣafar. Āsīr was taken several months after that event and Ṣafar cannot possibly be right. Abu-l-Fazl gives the Ilāhi date as 7th Bahman, which corresponds with 17th January (1601), as it is the 312th day from 1st Fravardīn (11th March). Now 17th January 1601 synchronised with 22nd Rajab 1009 H. is must have been miswritten for in (See A. N. III. 780; Tr. 1169). is frequently confused with confused with carless copyists. As Faizi himself states that the siege of Āsīr commenced soon after the 4th of Ramazan (138 ante) and also that it lasted for about eleven months (139 ante), Ṣafar is manifestly wrong. A contemporary inscription in the Jām'a Masjīd at Āsīrgarh gives the Hijri date corresponding to 17th or 18th January. (Ind. Ant. 1924, LIII. p. 40). Five lines lower down, Faizi

himself states that Abu-l-Fazl was appointed Chief Commander of the armies for the subjugation of the Dekkan, soon after the capitulation of Āsīr, on the 8th of Sh'abān and that on the 28th of Shawwāl, the whole of the Dakhin, i e Khāndesh and Mālwā as well as Gujarāt, were placed under Prince Dāniyāl, as the Emperor was returning to Āgra.

Mr Vincent Smith asserts that Sirhindi's dates are 'incredible', 'impossible' and 'absurd' He even accuses him of having muddled the chronology and given a 'garbled account' of the events, (loc cit. 299), but the error is undoubtedly clerical or inadvertent The charges of perfidy and treachery which he has preferred against Akbar have been fully and conclusively rebutted by Mr. C. H. Payne in his 'Akbar and the Jesuits' (251-8).

VI 151, l 13 He heard the Emperor's command, "Bring Asad into the bath room, that I may cut him in pieces with my own hand"

The author uses the word 'Ghuskhāna', which was not a 'bath room', but the Privy Council Chamber of the Emperor. "Behind these galleries, from which the Emperor is wont to look on at elephant-fights, lies the Audience Chamber, which is called the 'Gussal-can' (De Laet, Tr 40) The greatest nobles and the most privileged persons only were admitted to it (Coryat in E T I 279, see also Sir Thomas Roe, Embassy Ed. Foster, I 106, 202, Mundy, IL 201, Bernier, Ed Constable, 265, 361, Manucci, II 361, 400) The mistake is committed again at 247, 1 5 ff, 421, 1 7 ff and 421 last line infra

VI 152, l 14 from foot The King of Bijāpūr was also vexed that he had not received a direct cession of Gwālior

This 'Gwālior' (?) is again mentioned at 163 *infra* Dowson says he cannot identify the place. (*Ibid*, note) Can it be meant for 'Gāwīlgarh', which had been captured by the Mughals in the 43rd year, 1006-7 H? Abu-l-Fazl says that there was not a stronger fort than Gāwāl or Gārwīl, as he calls it, in Berār (A.N III 744, 746=Tr 1111, 1115)

VI 153, l 4 Asad wore a badge, as a disciple of Akbar's "Divine Religion" The King [of Bijāpūr] took it to examine it, and professing himself a disciple, declared he would keep it

This is an illuminating and significant allusion to the 'Shast wa Shabīh' which is mentioned in the \$\overline{A}\tilde{t}n\), (Tr I 165), A N (Text, III. 354—Tr 520), Budāuni (II 338—Tr 349, 404—Tr 418) and Jahāngīr's Tūzuk (28, 1 16, 'Tr. I 60-61), as the badge or insignia given to followers of Akbar's New Religion Students interested in the subject may refer to my Historical Studies in Mughal Numismatics, pp. 147-155, where it is discussed at some length

VI 153, l 14 from foot The Prince also directed that 10000 rupees should be given to him, but he "got only 2000 muzaffaris."

The Muzaffari was a silver coin, weighing about 110 grains, first struck by Muzaffar II. of Gujarāt, who ruled from A. H. 917 to 932 (1511 to 1526 A. C.). It weighed about 110 grains, but was valued at about two to the Akbari rupee, as the silver was about fourteen per cent below the Akbari standard. (Ain. Tr. I. 23; F. II. 138, 287—Briggs' Tr. IV. 319). See my article on the Unpublished Coins of the Gujarāt Saltanat in J.B. B. R. A. S. 1926, pp. 42-45. The meaning is that what Asad got was equivalent to only 1000 rupees instead of 10000.

VI. 154, l. 4 from foot. When [Shaikh Abu-l-Fazl] was killed at Sarāi Barār, a dependency of Sironj, at prayer-time on Friday, 7th Rabīu-l-awwal 1010 H.

This place has not been satisfactorily identified. I venture to suggest that it must be the Bar-ki-Serāi, which is mentioned by Tavernier, in the itinerary of his journey from Narwar to Dholpur. He locates it at three Kos, about six miles, south of Antri, nine Kos north of Narwar and nine Kos south of Gwalior. (Travels, Tr. Ball, I. 62). There is a place called Barki-Serāi, i.c. Serāi of the Bar or Vad, i.e. Ficus Indica, still in existence at about 5½ miles south of Antri. (I. A. p. exvii). Lat. 25°-58½ N., Long. 78°-10' E. Tieffenthaler says that Abu-l-Fazl was killed near a ferry of the Sindh river, at a place close to Dhumghat, about two leagues to the west of Dehala, which is ten leagues west of Datia. (I. 184 apud A.N. III. Tr. 1220 Note). This is in fair agreement with the situation of 'Bar-ki-Serāi', as Datia is a few miles north-east of Narwar. The place is called 'Sarāi Bangā, two stages from Gwalior, by 'Inayatulla. (ante 107). 'Banga' may be an error for 'Bat Kā' or 'Bar Kā' (Serāi). Khāki Shīrāzi says that, Abu-l-Fazl was murdered at the Sarāi Bar (حراى بر), six Kos from Narwar on Friday the 4th of Rabī I. 1011 (MS. in the Mulla Firūz Library, folio 218 b). The place seems to be also called "Berke Serai, ten Kos from Gwaliar" in the Maasir-i-Jahangiri, from which extracts are translated in F. Gladwin's History of Hindustan, (Ed. 1788, p. vii).

The date of the assassination is given in the local Hindu chronicles of Bundelkhand as 9th Kārtika V.S. 1660 (Silberrad in J. A.S.B. LXXI, (1902), p. 112)=4th October 1602. But this must be wrong. The date given by Asad—Friday, 7th Rab'i I. 1011 H.—corresponds to 15th August 1602 O.S. but 15th August was a Sunday. In the Takmīla of the A.N. (ante 107), it is 1st Shahrīvar, [13th August]. In the recension used by Chalmers it is 4th Rab'i I and Noer and Smith think the latter must be correct. But 4th Rab'iu-l-awwal Hisābi was 12th August, and a Thursday. The correct date must be 4th Ruyyat or Hilāli, if the week-day Friday is given rightly by Asad.

VI. 155, l. 20. Gopāl Das Nakta.

Nakṭa looks like a nickname or epithet of revilement. In Gujarātī and Hindi, it means 'cut-nosed' and secondarily, 'impudent,' 'shameless.' Gopāldās appears to have been no favourite with the writer of this Diary, as he is afterwards stigmatised as 'a wretched villain.' (156 infra).

An old officer of Bābur and Humāyūn, named Jalālu-d-dīn Mahmūd had a Turki by-name 'Bujūk,' which has the same signification, viz. 'Cut-nose' Bāyazīd Biyāt, who had been at one time in Jalālu-d-dīn's service, tells us that Mirzā 'Askari had the man's nose cut or slit for using improper language on a certain occasion (A.N. Tr I 413 Note) See also Ibid, II 55= Tr. 85, where he is again mentioned Such barbarous punishments were only too common in the old days Khwāja Bhūl, who had been sent with a message to Prince Salīm, having spoken somewhat disrespectfully to His Highness, had the tip of his tongue—the peccant part—cut out by Akbar's orders (A N. III 727; Tr. 1088) Jahāngīr takes great merit to himself for having prohibited, immediately after his accession, the cutting off of the noses and ears of criminals and for having himself taken a vow never to inflict such punishments on any one (Wāqi'āt, 284 and 325 infra)

VI 158, 1 2 Sharkh Mustafa, governor of Kālābāgh.

Kālābāgh lies on the load from Sironj to Narwar Tavernier makes it 23 Kos from Sironj, 17 from Sipri and 28 from Narwar (Travels, I 57-61). Finch puts it at twenty Kos from Sironj (E. T. I. 143). The real distance is about fifty miles [north of] Sironj

VI 165, l. 1 The unhappy Khwājā Amīru d-din whose watch it was, came in sight

Recte, Aminu-d-din. (A N III 474=T1.715, Takmīla, Text. III. 836=Tr 1252) Jahāngīr also mentions him and says that very soon after his own accession, Aminu-d-din was appointed Yātish Begi, that is, Captain of the Watch, the post which he had held under Akbar (T J 6, 15, Tr I.13, 14 and note) He was the person who had been sent as envoy to Ahmadnagar by Akbar (T A in E D V 460, 467) His original name was Mir Muhammad Amin (B II. 377, 111, Tr. II. 390)

Rām Dās, who also "had a share in the misfortune" (17), was Rājā Rām Dās Kachhwa, a great favourite of Akbar's (q v 170 infra)

VI. 170, l 8 Savyid Khān, who was connected with the royal house and descended from an ancient and illustrious Mughal family

This 'Saiyid Khān' was S'aīd Khān Chaghtāi The name is not but but He was strongly opposed to the proposed supersession of Salīm on the ground that it was a flagrant violation of Chaghtāi law and custom As a descendant of Tīmūr, he looked upon himself as a custodian or trustee responsible for the strict observance of the 'Tora and Yāsā' (Aīn, I. Tr 331) Dr Beni Prasād identifies Asad's 'Saiyid Khān' with 'Saiyid Khān Bārha,' whom he describes as "a scion of an ancient and illustrious Mughal family, connected with the Imperial House' (Jahāngīr, p 73), but he must be mistaken, as the Bārha Saiyids were not Chaghtāis and not even Mughals Nor were they related to 'the royal house' by blood S'aīd Khān was the son of Y'aqūb Beg, the son of Ibrāhīm Beg Chāpūk, who was one of the Amīrs of Bābur and Humāyūn (M.U. II 403, see my note on IV 365, l. 3).

Murtazā Khān was Shaikh Farīd Bukhāri, who was given that title by Jahāngīr, as a reward for the defeat of Khusrav at Bhairowāl, i. e. Vairowāl near Govindwāl and Tarn Tāran in Amritsar district. (T. J. 32, 1. 8 f. f.=Tr. I. 69). Asad is giving him the title in anticipation.

VI. 171, l. 10. Farā Beg came and made salutation.

Recte, 'Qarā Beg'. He is the Qarā Khān Turkmān of the T. J. (8, 1.2—Tr. I. 17; 33, 1.27—Tr. I. 71). He had come to Akbar's Court with Mirzā Muzaffar Ḥusain Ṣafavi of Qandahār in 1003 A. H. (B. II. 402—Tr. 416; Āin, Tr. I. 313). Faizi Sirhindi also calls him Qarā Beg. (138 ante; see also the Ţ. A. Text, 367, 1. 7 f.f.).

VI. 177, l. 16. He lighted upon the Tārīkh-ī-Bahādur Shāhi, written by Sām Sultān Bahādur Gujarāti.

The real name of the author of this History was Ḥisām or Ḥusām Khān Gujarāti, not 'Sām Sultān Bahādur'. The book is quoted frequently in the Zafar al Wālih of Ḥājji Dabīr, as well as in the Mirāt-i-Sikandari (Tr. Bayley, 279, 341, 350), the Ţ. A. (3, 1.7; 635, 1.2) and 'Abdu-l-Ḥaqq Dehlavi (484 infra). The author was the grandson of Maḥfūz Khān, one of the ministers of Maḥmūd Begada and he himself was in the service of Bahādur Shāh, in whose honour, it is called Tārīkh-i-Bahādur shāhi. (Z. W. Ed. Ross, II. Introduction, pp. xxvii-xxix).

VI. 193, l. 10 from foot. Curious apartment.

A similar tank, reservoir or 'subaqueous chamber' is described in the A. N. III. 650=Tr. 1000; B. II. 265=Tr. 272 and the Tūzuk-i-Jahāngīri (73, 1.3; Tr. I. 152). Jahāngīr says that the one which had been constructed by Ḥakīm 'Ali in his father's reign [1002 A. H.], i.e. the one described here by Nūru-l-Ḥaqq, was in Lāhor. That which he himself saw was in the same Ḥakīm's house in Āgra.

VI. 203, l. 12 from foot. He [Muṣaffar Ḥusain Mirzā Ṣafavi] had four sons, Bahrām, Sadar, Alfās and Tahmāsp Mirzā.

Two of the four names are incorrectly spelt. 'Sadar' is an error for 'Ḥaidar'. He rose to great dignity under Shāh Jahān and died in 1041 Å. H. The name of the third son was 'Alqās' not 'Alfās'. (A. N. III. 836; Tr. 1238; Āīn, Tr. I. 314; 'Amal-i-Ṣāliḥ, I. 49, 1. 7 f. f.; Houtsma, E. I. II. 24). The three brothers of Shāh Ṭahmāsp Ṣafāvi were named Alqās, Bahrām and Sām. (Gulbadan, H. N. 68=Tr. 169).

VI. 204, l. 14. In this year [1005-6 A. H.=42nd R. Y.], Mirzā Rustam, son of Prince Shāh Murād, died at Lāhore after a severe illness of six years and three months.

There must be some muddlement here in the text or translation and the statement cannot be correct. (cf. 132 ante and my note there). The young prince died, according to Abu-l-Fazl, on the 9th of Azar of the 42nd year of the reign, (1006 H.), after only three days' illness, of some intestinal or gastric disorder. He was "nine years, three months and five days" old at the time. (A. N. III. 735, Tr. 1096-7). The

and what the author wrote or meant to write was that the Prince "died after a severe illness [at the age of] nine years and three months."

VI. 204, l 17 In 1006 A. II, the Emperor appointed Rai Hardas to act as Minister conjointly with Khwaja Shamsu-d-din

The first name is generally written "Patar Dās" in the A N., and the T A He was given the title of Rāi Rāyān by Akbar (160, 161 ante), and that of Rājā Vikramājīt by Jahāngīr. He was really called 'Tappar Dās' or 'Tirpur Dās', a short form of Tripurāri Dās (See my note on 287, 1.17 infra) In any case, 'Hardās' is wrong.

VI. 208, l 8 from foot In A D 1594, Firishta escorted the Princess
Begam Sultāna from Bījāpūr to Ahmadnagar,
was present at her nuptials with Prince Dānīāl
and attended her as far as Burhānpūr

The date is wrong and 1594 must be a slip for 1604. The marriage took place on the 9th of Tir of the 49th year of the reign=20th or 21st June 1604. (A N. Continuation, III 827, Tr. 1240) Firishta himself gives the date as Safar 1018 H (I 271, 1, 9 f. f), which began on 19th June 1604. Dāniāl died according to the first of these contemporary authorities, on Saturday, 28th Shawwal (Hisabi) 1013 H (Ibid. III. 837, Tr 1254)= 9th March 1605, which was a Saturday (Ind Ephem.) Mr Vincent Smith contends that the marriage took place in 1012 A.H or about March 1604, and that Dāniāl died soon afterwards in April 1604 (Akbar, 331-2, 459), because De Laet puts his demise before Salim's submission and arrest on 9th November 1604. But De Laet's account of Akbar's reign is a second-hand compilation and so full of blunders of all sorts, that he is hardly an authority on such a point Filishta who was present at the marriage may be safely trusted to know better. He gives the year of Danial's marriage and death as 1013 H. in words and Khali Shirazi, another contemporary author, who is, as Elliot states, "very particular with regard to his dates", also gives 1018. (MS. in the Mulla Firuz Library, folio 218 b).

VI. 210, l 22 Such conscientious and excellent use has he [Finishta] made of his predecessors, so entirely has he exhausted all the prominent facts mentioned by them, that they have been rendered almost useless

This amounts to saying that he has plundered older authors more thoroughly and shamelessly than others and has done them the additional injury of destroying their fame and reputation. Sir Henry Elliot's very high estimate of F's compilation is not endorsed by other scholars Raverty is never weary of denouncing Firishta as "a mere copyist who follows the Tabaqāt i-Akbari so closely and slavishly, that not only the poetical quotations, but the errors and slips also are appropriated" He has also proved that "wherever Nizāmu-d-dīn has misiead or misunderstood the original authorities, this Dakhani author has done the same." (T N Tr 441, 631, 651, 663, 665, 667, 697, 711, etc notes)

Firishta's work is really an adaptation of the I'abaqat with supplementary material picked up in odd corners and not infrequently interpolated without discrimination. Oriental writers rarely deal scrupulously with the intellectual property of their predecessors, but F. often betrays great carelessness also in such appropriation or misappropriation of the fruits of other peoples' labours. He adds, alters, takes away or mutilates at his own sweet will and rarely troubles to give his reasons or cite his authority. Even Sir Wolseley Haig, who often follows him, admits that "he was utterly devoid of the critical faculty, that he has made severalglaring errors even in his Annals of the Deccan, which was his peculiar province, and that the value of his work is further impaired by his gross ignorance of geography." (Houtsma, E. I. II. 111). It must be also said that his crude guesses about the coinage of the Dehli Sultans have often involved Thomas and other numismatists in puzzlement and confusion. VI. 218, last line. The Rājās of Ujein, Gwāliar, Kalunjar, Canauj,

Firishta's glosses and embellishments are frequently misleading and this is one of them. The interpolation of Dehli and Ajmer in this catalogue of Anandpal's allies is an absurdity and an anachronism, as neithe of these cities was in existence at this time (1008 A.C.). Dehli was founded only by Anangapala Tomar in 1052 A. C. The fact is stated in an inscrip. tion on the Iron Pillar in the Qutb. (I. G. XI. 233; Smith, E. H. I. 356). Ajmer was the creation of and named after Aja, Ajaya, or Ajayapāla Chauhan, who flourished about 1100 A. C. and whose son Ano was alive in 1150 A.C. (Bühler in Ind. Ant. XXVI, (1897), p. 162; I.G. V. 141). There is also no mention of the 30,000 Gakkhars in any of the earlier authorities. VI. 230, l. 16. Two thousand elephants, three hundred gun-carriages and

battering rams.... were included in the booty of the king. The words in the Text are ارابهٔ توپ و ضربزن (I. 290, 1. 10). Mrs. Beveridge thinks that Bābur's ضرب زن was a culverin or swivel-gun, weighing about fifteen or seventeen pounds only, but the term appears to have been used for larger pieces of artillery also. Mirza Haidar states that at the battle of Qanauj in 947 A. H., Humāyun had 700 Zarbzan, each throwing stone balls of 500 misqāls, Weight (about five pounds). (E. D. V. 131-2). A 'Zarbzān' is described by Faizi Sirhindi as a piece of artillery throwing a ball weighing from half a ser to two mans at 139 ante. See also the Tārīkh-i-Alfi in E. D. V. 175. But the existence of any guns in the days of Ahmad Shah Bahmani, who is the king referred to here, is VI. 232, l. 7 from foot. Ahmad Shāh [Bahmani] marched to reduce a

This 'Māhoor' was a Sarkār in Berār. (Āīn, Tr. II. 230, 235). The town is situated four miles from the right bank of the Pain-Ganga river, about 98 miles S. S. E. from Ellichpūr. Lat. 19°-50' N., Long. 78°-0'. E. (Th.) It is shown in the I. G. Atlas, Pl. 40 C 2. Kullum, which is mentioned on

line 2, p. 283 infra, as possessing a diamond mine, was another Sarkar in Berar. Eight of its parganas belonged then to a Gond Zemindar named Babjeo or Chanda, who had wrested the diamond mine of Biragarh [Recte, Wairagarh] only a short time before from another chief. (Ain Tr. II, 229, 280, 282. See also T J. Tr. II 21 and note). Kallam or Kallamb is now in Wun district, Berar, and shown in Constable, 31 E a

VI. 236, l. 13 from foot A poet observes. 'Royalt ybesitteth not the destroyer of a parent, nor will the reign of such a wretch be long'

The couplet is quoted by Mirkhwand also in connection with the short-lived prosperity of royal parrieides (Browne, L. H. P. III. 377). Nizāmu-d-dīn Ahmad in his Chapter on Sultan Nāsiru-d-dīn Khalji of Mālwā (571, last line) and his copyist F (II 261, l. 11) cite the saying as an argument of great weight. They urge in all seriousness, that as no parrieide is known to have reigned for more than a year and Nāsiru-d-dīn actually ruled for so long as eleven, he could not have been guilty of poisoning his father Ghiyāsu-d-dīn, as he is said by many historians to have done!

VI 236, l 9 from foot Beny Rāy recovered from his icounds.

Sic in Briggs, but the Cawnpore Lith of Firishta has كوال (II, 201-2) The T. A. calls him على أود يسك (476-7) and the Mirāt-i-Sikandari (كاي على (Text. 114-5, Bayley's Tr 208-9) He is called Patāi Rāwal in the Hindu accounts also and this must have been the sobriquet or designation by which he was popularly known. His real name was Jaysinha. (Rās Mālā, Reprint, 1924, pp 355, 357, 858, B G I. 1. 246) يس (Beny) must be a misreading of يش Patai.

NI. 243, 1 13. Akbar died at Agra on the 23rd of Jumādu-l-awwal, A H 1014, after a reign of fifty-two years

Neither of the two averments is correct. Akbar died on the 12th-13th of Jumādi-l-Akhir, 1014—4th Ābān Ilāhi, 50 R. Y., after a reign of less than fifty solar years or a little more than fifty-one lunar years. He reigned from 2nd Rab'ī II. 963 to 12th Jumādi II. 1014 H. The Hijri date given by this author corresponds with 12th Mihr Ilāhi, on which the Emperor was seized with the illness which proved fatal after twenty-three days (A. N. Cont. III. 840—Tr. III. 1259) 'Abdu-l-Bāqi has mixed up the dates of the two events

VI 280, l. 12. I had neither heart nor head to think about the foul copies of my Memoirs

"My heart and head did not keep pace together [did not work in accord or unison with each other] and I was unable to pay personal attention to the original Journals and Reports of Events." The real meaning is that Jahāngīr was suffering from some nervous or cardiac disorder, which prevented him from preparing and writing out with his own hand,

summaries of the Court-Circulars and News-letters, from which his autobiography was compiled. As his own hands shook and trembled, he was obliged to get the work done by Mu'atamad Khān. Manucci describes the Wakai as a "sort of Gazette or Mercury, containing the events of most importance. These News-letters are commonly read in the King's presence by women of the Mahal... so that by this means he knows what is going on in his Kingdom." (Storia, II. 331). Mu'atamad had been employed as a Wāq'ia Navīs so early as the 2nd year of Jahāngīr's reign. (T. J. 56, l. S=Tr. I. 117 and Note).

VI. 284, 1. 2. On Thursday, the 8th Jumādu-s-sāni, 1014 Hijra, (12th October 1605).....I ascended the throne.

المشتم, 8th, is an error for بشتر, 20th. Akbar died on Wednesday 12th-13th of Jumādi II. (115 and 248 ante). Jahāngīr ascended the throne eight days later on Thursday, the 20th (24th October, 1605 O. S. See my Historical Studies, p. 268, and the authorities quoted there.

VI. 284, l. 12. The reeight of it [the golden chain] was four Hindustāni Mans, equal to thirty-two Mans of 'Irāk.

This Hindustani Man must be the Man established by Akbar, which was equivalent to about 55 English pounds avoirdupois. The Man of 'Iraq must have therefore weighed about 7 lbs., which corresponds fairly well with the Man known as the Tabrīzi. (Yule H.J. s.v. Maund). At 304 infra, 500 Hindustani Mans are equated with 4000 Mans of Vilāyat, i. e. Persia, which gives the same ratio.

VI. 286, l. 28. The attendants upon the female apartments of my father were advanced ... from ten to twelve, or ten to twenty.

('Aligarh Text, 5, 1.2). The increments relate not to the allowances of the 'attendants' in the Harem, but to the allowances or pensions of "the curtained ones in the Pavilion of Chastity," i. e. the numerous ladies who were regarded as the wives of Akbar and other females related to the Imperial family. The persons who received the new Emperor's bounty and were so graciously treated were the ladies, not their 'attendants.'

VI. 287, l. 14. The \(\frac{1}{4}\) tola (silver coin) [was called] Aishyāri.

Recte, Sic as in the Text, (5, l. 14). The denomination Nisāri is inscribed on some of the quarter-rupees themselves and is derived from the fact that they were used for sic, i. e. for scattering among the people during the progresses of the Emperor and on Festivals and other ceremonial occasions at Court. (See my Historical Studies, 177-185).

VI. 287, l. 17. Har Dās Rāī, who had received from my father, the title of Rāy Rāyān, and from me that of Rājā Bikramājīt ... was made Commandant of artillery.

 the King, is", he writes, "Tipperdas and is of great account among the people" (E.T I 24, Ryley, Ralph Fitch, 110) He is mentioned as "Tirpur Kshattri" repeatedly, in the local chronicle of Bundelkhand, translated by Mr Silberrad in J. A S B LXXI. 1902, pp 112-3 The Sanskrit form is probably "Tripurāri Dās" "Servant of Tripurāri" (Enemy of Tripur), one of the epithets of Shiva or Mahādeva, (Vishnu Purān, Tr Wilson, Ed Hall V Pt. i 118)

VI 287, l 21 He had directions to keep 50000 gunners and 3000 guncarriages always in a state of readiness

حکم کردم که همیشه در توبیحاهٔ رکاب پستاه همرار توپیجی و سه همرار ارا به توپ مستمد ' artillery of the Stirrup' توپیحانهٔ رکاب The (کار) و آماده سرانجام باید consisted of a number of "light guns which accompanied the Emperor in all his marches and progresses and were ranged in front of the tents and fired a volley, the moment he arrived in camp" (Bernier, Travels, Ed Constable, 217, 218, 363) Manucci also speaks of the 'light artillery' which was placed round the tents of Aurangzeb in every camping ground, but he states that it consisted of only one hundred field pieces, each drawn by two horses (Storia, II 69) Gemelli Careri, who visited Aurangzeb's camp at Galgala in 1695, estimates the number of light guns which he saw at "sixty or seventy, each drawn by two horses" (Travels, in Churchill's Voyages, IV. 220, 222, 235, 236) Jahangir's '50000 gunners and 3000 guns ' are such monstrous and staggering departures from these modest figures, that one cannot but suspect some error in the text The Emperor is rarely guilty of exaggeration himself and it is not unlikely that he wrote or meant to write '5000 gunners and 300 guns' The phrase 'Artillery of the Sturup,' is derived from Rikab, which literally means 'stirrup'. but is used as a figurative expression for the Emperor's immediate entourage when on a journey (Irvine, A I M 134)

VI 290, l 4 from foot. As I had removed the practice of levying transit duties, which amounted to many Krors of runees.

תלפים אל הבים. The word 'rupees' is an interpolation and there is nothing corresponding to it in the Text (21, 1 4 f f) Jahängir probably means Dāms, as it is explicitly stated a few lines lower down, that the Sāir Jihāt [miscellaneous taxes] of Kābul yielded one Kior and twenty-three laks of Dāms. (p 291 infra) As the total revenue of the Mughal Empire under Jahāngīr was about sixteen Krors of rupees, it is not likely that the realisations from the "Zakāt" alone amounted to several Krors of that monetary unit.

VI 291, l 9 from foot. When I obtained the sovereignty, I confined (girifta) him [Prince Khusrav] and quieted my doubts and apprehensions

Jahangir does not appear to have confined or imprisoned Khusrav until after his overt treason and rebellion. What the Emperor really says or complains of here is that he "found Khusrav straitened at the art

and gloomy (haunted by fear and terror) همواره خسرورا کرفة خاطر و متوحش مافتم (24, 1. 11). Cf. also infra 338, where Jahängir laments, in the diary of the Ninth year, that Khusrav continued to be "sad and downcast," مأول و کرفته (128, 1. 7), even after receiving so many tokens of his paternal affection and regard. The "doubts and apprehensions" were not in Jahängīr's heart but in Khusrav's.

VI. 291, l. 4 from foot. On the night of the 20th of Zi-l-Hijja, [Khusrav fled].

The dating throughout this account of Khusrav's revolt is confused and inconsistent. We have 20th here, but 2nd Zī-l-Ḥijja at 295, l. 6 infra. The 20th should be 8th, and the 2nd should be 10th, fer not fer, as in the Text. (24, l. 14 and 26, l. 3 f.f.). A few lines lower down, the Emperor is said to have reached Dehli on the 13th of Zīl-Ḥijja. The I.N. gives the date of Khusrav's flight correctly as 8th Zī-l-Ḥijja, (9, l. 3), i. e. 5th April, 1606, Old Style. According to the contemporary Jesuit reports quoted in Du Jarric, Khusrav fled on the 15th of April, but this is the New Style date.

VI. 292, l. 15. He [the Amīru-l-Umarā] is envious of his peers, God forbid lest he should be malicious and destroy him!

meaning is again turned topsy-turvy. The Amīru-l-Umarā was the Emperors' favourite and he was not envious of his peers, but they were envious of him. What Jahāngīr was afraid of was that the other Amīrs would conspire against him and compass his ruin out of envy.

VI. 294, l. 15. From time to time her mind wandered, and her father and brothers all agreed in telling me she was insane.

Not so. The real meaning is that "the tendency to insanity was hereditary and her father and her brothers had all at one time manifested signs of insanity." چنانچه این حدیت میرانی بود که پدران و برادران او چه یکباری (26, l. 10). Khusrav's mother was the daughter of Bhagwāndās, whose attempt to commit suicide is mentioned by B. (II. 353=Tr. 384) and A. F. (A. N. III. 492=Tr. 745). Her brother Partāb [Pratāp] Sinha, the son of Bhagwāndās had also tried to kill himselfand put a dagger to his throat. (A. N. III. 744=Tr. 1111). Elsewhere, Jahāngīr records the fact that her nephews, Bhāu Sinha, Jagat Sinha and Mahā Sinha were dipsomaniacs and all died of drink. (337, l. 21=Tr. II. 218).

VI. 295, l. 6. I halted at Hindal.

Recte, 'Hodal', as in the Text. (26, l. 5 f.f.). For 'Palol' (l. 19) read 'Palwal'. Delete 'Ramazan' on l. 23. It is not in the Text and is an

Dehli. (I. A. xeviii). All these places are now stations on the N. W. Railway VI. 296, l 11 from foot. At Aloda, I sent Abul Bani Uzbek.to the support of Shaikh Farid.

The name of this man is variously written in the text itself as (12, 1, 3), which is the last of the l

'Aloda' is a mistranscription of 'Alūwa', eighteen miles north-wes of Ambālā, on the road from Dehli to Lāhore. Shāhābād (l. 23) is 16 miles south of Ambālā (Chihār Gulshān in I A cxix) Constable, 25 B b VI 297, l. 4 from foot. [The news reached me] in the garden of Āghā

The text reads 'Sarāi of Qāzi 'Ali'. (29, l. 10 f f.) The spurious Memoirs or Tārīkh-i-Salīm Shāhi also call the place by the same name, (265 ante), which must be correct Qāzi 'Ali was one of the ministers of Akbar See my note on IV 389, l. 8 f. f.

Kuli

VI 299, l. 17 On the 28th, my camp rested at Jahan, seven Kos from Lahore.

العبال (Jaipāl) in the Text. (31, 16). Mr Beveridge and Dr Beni Prasād leave this place unidentified I suggest that it is Chabhal, a village about 12 miles south of Lāhore, where there is a branch Post Office. It lies about eight miles west of Tarn Tāran, while Govindwāl, the preceding stage (298, 13 ante) is 14 miles south of Tarn Tāran 'Bhairowāl,' the place where the battle was fought, is the 'Vairowal' of Constable's Atlas, 25 A b It is a village on the Beas in the Tarn Tāran Tahsīl of Amritsar district. Lat 31°-25′ N, Long. 75°-10′ E (I G s n.)

VI. 302, l. 16 I passed Sunday, the 19th of Farwardin, which was the day of the Sun's entry into Aries in that garden.

The day of the Sun's entry into Aries is the first day of Fravardin Aries is the sign of his شرف or 'House of Honour' and he attains his 'culmination' or 'exaltation' in the 19th degree of that sign, i e on the 19th day of the month called Fravardin (B II. 309=Tr II 319). The Naurūz festival lasted for nineteen days from Roz Hormazd the 1st, to Roz Fravardin, the 19th of Māh Fravardin and the Jashn or Great Feast was celebrated on the 19th day (Aīn, Tr I 276).

VI. 303, l 7 Sıkandar Mai, the jāgīrdār of the pargana.

The second name is given as (Mu'in) in the Text (44, 1 12), which may be the short form of M'uinu-d-din, but if 'Mai' or 'Main' is correct, he may have belonged to the Main tribe, a branch of the Bhattis, who were converted to Islām in the fourteenth century 'Chandwāla' is written Mr Beveridge (Tr I 91 note) suggests that it may be Jandiāla of the I. G. (VII 137), which is in Amritsar, but a glance at the map must show

that the suggestion is untenable, as it does not lie on Jahangir's route from Lahor to Kabul. This Chandwala must be a few miles south-east of Hafizabad in Gujranwala. The name of the Krori of Hafizabad was Mir Qiwamu-d-din (Text, 44, 1.15), not Kiramu-d-din. Mir Qiwamu-d-din is again mentioned. (T. J. 323, 1.25=Tr. II. 192).

VI. 305, l. 19. Darahlar which joins the Behat at the village of Shahabudinpur is the best of all the streams [in Kashmīr].

Shihābu-d-dīnpur lies at the junction of the Sind and the Behat (or Jhelum) and is a *Frayāg* or *Tirtha* (Holy place) on that account. It is now called Shādīpur and lies about nine miles north-west of Srīnagar. Constable, 25 A a.

'Darahlār' really means "the valley (°,') of the 'Lār' river." The name of the river which joins the Behat (i.e. Jhelum) at Shihābu-d-dīnpur is Lār. It is also called the Sind. Jahāngīr's visit to the valley of the Lār is recorded in his diary of the XVth year. (314, 1.8 f.f.=Tr. II. 176. See also Text, 347, 1. 12=Tr. II. 238).

VI. 306, 1. 10. It is said that he [Zainu-l-'Abidin] passed many periods of forty days in this place.

The word in the original is , the Persian synonym of which is the period of forty days during which he remained in strict solitude as well as silence and fasted. (Herklots, loc. cit. 144). 'Chilla' is also used for the place where a Saint has performed the penance. The traditional scene of the forty days' fast of St. John the Baptist near Jericho is still known as 'Quarantina'. (Fanshawe, D. P. 280).

VI. 306, l. 24. The King is said to have performed many such miracles and he could assume any form he liked.

also thoroughly mastered the art of separating the body from the soul [or the soul from the body]". Abu-l-Fazl states that "Zainu-l-'Ābidīn was credited with the power of divesting himself of his corporeal form." (Āīn, Tr. II. 388). The T. A. also uses the phrase غلم بنت and tells a story of a Jogi having once transferred his own soul to the body of the Sultān and brought him back to life, when he was on the point of death. (Text, 601-2). F. repeats the tale. (II, 345). There are numerous references to this power or gift of projecting the individual soul into space and of even effecting a temporary lodgment in another corporeal tenement in Hindu literature and folk-lore. Stories of the 'double' or 'wraith' of a dead or dying person having been seen at the moment of death by friends or relatives living at a distance are related in many old books on the 'Night Side of Nature;' as well as recent works on telepathy and spiritualism.

VI. 307, 1. 6 from foot. The amount is 16;10,00,000 dams which is 34,25000 rupees.....or 1,21,75,000 Khānis of Tūrān.

The correct equivalent in Rupees is 40,25,000 as it is given in the text. (47, l. 1). Forty $d\bar{a}ms$ went to the rupee. The sum in $Kh\bar{a}nis$ is also stated wrongly here and should be 1,20,75,000, not 1,21,75,000. Three

Khānis went to the Rupee The total cost of the erection of the fortress is stated differently in the $T\bar{a}rikh$ -i- $D\bar{a}u\bar{d}i$ at E D IV 419 n., q.v. my note. VI 308, l 1 [From Tillah], I marched to the village of Bhakra.

Mr G. P. Tate agrees with Blochmann in identifying 'Bhakra' with 'Bakrāla'. He observes that "the winding bed of the Bakrāla river between the villages of Bakrāla and Dhamek was the road by which, for countless centuries, invading armies had entered and left the Punjab, when they did not use the Nilāb-Bhera route" (J. R. A. S. 1909, pp. 168-9) The Agra and Calcutta Gazetteer (Ed. 1842) places Bakrāla at twenty miles' distance from Rhotās (I. A. p. cii.) Hatya (l. 13) is mentioned in Finch's itinerary from Lāhor to Kābul, Lāhor to Rhotās, 78 Kos, Hatya, 15 K., Pukka, 4 K., Rāwalpindi, 14 K., Kalāpāni, 15 Hasanabdāl, 4 (E. T. I. 168) Hati, the Gakkhar Chief, after whom Hatya is called, is mentioned by Bābur (B. N. 389-90, E. D. IV. 235-7)

VI. 310, l 18 On this march, there occurs a hill called Margalla Mar in Hindi, signifies 'to rob on the highway' and galla, 'a caravan'.

This derivation is almost as apocryphal as another put forward by Cunningham, from galā, throat, and Mārnā, to cut, decollate The English antiquarian connects the name of the place with the local legend of 'Sir Kāp'—the Buddhist Jātaka or tale about 'the Enlightened One' having offered his head here to save the life of a man or a starving tigress and her seven cubs (A G I Ed 1871, p 111) Jahāngīr associates it with brigandage and highway robbery The name is written by Alberūni as 'Mārikala' (Sachau's Tr I 302) and 'Marigala' (Ibid II 8) 'Gala' occurs as a suffix in other toponyms also, e g Biramgala, which is the 'Bhairavgala,' of the Rājataringini.

VI. 315, l 7 from foot Khwāja Kuraishi, the dīwān of Prince Khurram. Recte, 'Waisi' as in the Text (58, l 11 ff) See also the Iqbālnāma (28, l 6 ff) He is the 'Godzia Vehees' of De Laet (Tr Hoyland, 178) and is again mentioned as Khwaja Waisi by Jahāngīr himself. (T J 283, l f.f, Tr II 118) See also Āīn (Tr I. 483, 464) and A N (III. Tr 1151)

VI 318, l 16 Asaf Khān presented me with a ruby seven tānks in weight.

The 'Tank' is defined in the dictionaries in many different ways, but II have shown elsewhere that the Jewellers' and Goldsmiths' 'Tank' of Akbar and Jahangir weighed about 63 grains During the last decade of his reign, Akbar struck a new denomination in copper called Tanki, specimens of which are now very rare and eagerly sought for by collectors See my paper on the subject in Num Supp No XXVII to the JASB 1916, pp 138-140 and HSM. N 102-114

VI. 321, l. 9 When Afzal Khān was about to march to Gorakpur, which lies about sixty Kos distance from Patna

An error for 'Kharakpur', though the text also reads 'Gorakhpur'. (83, l. 8 f.f.) and the Iqb Nām agrees with it. (42, 1 16). 'Kharakpur'

must be correct, as Jahāngīr states that soon after Afzal Khān was appointed Ṣūbadār of Bihār, the jāgīr of Sangrām, the Rājā of Kharakpur, was assigned to Afzal Khān for a year. (T. J. 68, l. 6; 70, l. 1=Tr. I. 143; 146). Sangrām had revolted and been killed in a battle with Jahāngīr Quli Khān, the former governor of Bihār. (T. J. 39, l. 10 f.f.=Tr. I. 83). Kharakpur is about thirty miles south of Monghyr and was in Afzal Khān's jurisdiction, as it was in the Sūba of Bihār. Gorakhpur was in Oudh. Patnā is in Lat. 25°-35′ N.; Long. 85°-15′ E. N.; Gorakhpur in Lat. 26°-42′ N.; Long. 83°-23′ E. This implies a map-distance of about 150 miles, and a road-distance of about 200, which is greatly in excess of 60 Kos.

VI. 321, l. 12. He placed the fort and the city in charge of Shaikh Banārasi.

This man's real name is not given by Jahāngīr, but it is written in the Compendium of Khāki Shīrāzi (206 ante) and the Iqb. Nām. (42, 1.5 f.f.), as Ḥusām. He must be the Shaikhzāda Gosāla Banārasi, who is the butt of Budāuni's biting comment and about whose morals he relates a scandalous story. He is said to have been a disciple of the 'New Faith' and appointed Krori of Banāras, through the influence of its great hierophant, Abul-Fazl. (B. II. 401; Tr. 419-20). This accounts for the sobriquet 'Banārasi.' 'Gosāla' in Persian means 'Calf' and secondarily 'a fool or coward' and looks like a vilipending nick-name coined by Budāuni.

VI. 321, l. 16. A turbulent person of Uch, by name Kuth, came....into the territory of Ujjainiya, which lies near Patna.

'Ujjainiya' (or Uchīna) is not the designation of a place, but of a ruling dynasty. The territory referred to is that of Bhojpur or Jagdishpur, which was ruled at this time by the Ujjainiya Rājās. They were so called, because they claimed to be descended from the Pramāra Rājās of Dhār and Ujjain. Their capital, Bhojpur, was named after the renowned King, poet and patron of poets, Bhoj Pramāra of Dhār. (Blochmann, Āīn, Tr. I. 513 note). Bāyazīd Biyāt states that Gajpati, the Ujjainiya Rājā, held Bhojpur and Bīhīya in Jāgīr. (J. A. S. B. (1898), LXVII. p. 315). Dr. Beni Prasād speaks of Qutb, the 'pseudo Khusrav' "as an obscure Muslim youth of Ujjaini in Bīhār" (Jahāngīr, 167), but there is no such place as 'Ujjaini' anywhere in that province. Khāki Shīrāzi states, just as Jahāngīr does here, that Qutb was born at Uch in Multān. (205 infra).

VI. 321, l. 7 from foot. As his eyes had been branded in times gone by, he told those people that when he was in prison, hot cups had been laid upon his eyes, which had left that mark.

The man was an undoubted impostor, but the allegation ascribed to him would point to a popular belief that Khusrav had been blinded in this manner. Texeira says that this peculiar method of blinding was practised by the ruling family of Hormuz and that fifteen princes of the

royal line who had been thus deprived of sight were imprisoned in the fort in his time (Whiteway, Rise of the Portuguese Power in India, 165 note) See my note on 448. l. 10 f. f infra).

VI. 322, l. 5 from foot Shaikh Banarasi, Ghayas Rihani and the other officers, were brought to Agra

'Zam Khām' not 'Raihām' in the Text (84, l. 6 f f.). He is so called by Dowson himself (321, l. 12 ante) He was probably a dependent, protege or connection of Zam Khām Koka, to whom two of Jahāngīr's wives were related. In the translation from Khāki Shīrāzi (206 ante), the personal name is printed as Iliyās, but this must be an error for Ghīyās. He is called Ghiyās Beg in the Iqb Nām also (42, l. 5 ff) Hawkins says that he was an eye-witness of the punishment inflicted by Jahāngīr upon the eight cowardly captains of the town (Voyages in E. T. I. 113)

VI 323, l 13 from foot [Khân Jahân said in his letter], "Either confirm him [Khân-i-Khānān] in the command, or recall him to Court and appoint me"

The real point is not brought out clearly in the translation. The alternative was not confirmation or recall, but investment with absolute autho-(86, يا اين حديث را باستعلال باو بار بايد كداشت يا اورا بدركا ، بايد طلبد السعلال باو بار بايد كداشت يا 1, 10 f.f). "Either this task (or duty) should be again assigned to him with absolute authority (or supreme control of affairs, not, as hitherto, in subordination to Prince Parviz) or he should be recalled to Court" Khan Jahan reported that the ill-success was due to division of authority and his advice was that either the Khān-ī-Khānān should be placed in sole charge with untrammelled authority or removed and Khan Jahan himself appointed as general-in-chief with full powers (See also Igh Nam 45) His real point was that Paiviz should be removed and the command entrusted either to the Khān-i-Khānān or to himself, but, in either case, with full powers Khān-1-Khānān had been formeily Chief Commander in the Dekkan When Jahangir afterwards set Prince Parviz above him, things went wrong, because his amour propre had been hurt. Khin Jahin also felt that the Prince's presence was more of a hindrance than a help.

VI. 325, l 6 from foot [I ordered them] not to give the Amīrs and Sardārs serving under them the annoyance of their own chair or of requiring obersance to the chair

of their own chair," has scarcely any meaning. "They should not require or force the Amīrs and Commanders who were sent [from the Imperial Court] to assist them [as auxiliaries on special duty or in emergencies], to mount guard or make obeisance to themselves, [as] those Amīrs and Commanders used to do to the Emperor, when mounting guard at Court] با المواقعة
reign] was the establishment of seven watches (Chaukis). All the servants who held office in the Court were distributed into seven divisions, each of which was to be on guard for twenty-four hours. One of the grandees was appointed to command each division, so that he might superintend everything." (A. N. III. 146=Tr. 207-8). The grandees or nobles had to do duty by turns with their contingents at the palace-gate once a week. The rules are recorded in the \overline{Ain} . (Tr. I. 257).

VI. 325, l. 2 from foot. [They were] not to forcibly impose Musalman burdens (taklīf-j-Musalmani) on any one.

What are 'Musalmān burdens'? كليف means 'force, pressure, compulsion' and the real meaning here is that they were 'not to force the profession of Islām upon any one', i.e. they were not to compel any one to become a Musalmān. 'Musalmāni' is used euphemistically in Hindustāni for 'Circumeision'. Taklīf-i-Musalmāni signifies 'compulsory circumeision'. The synonymous phrase, كالمناف الملائة is used in the same sense in Firishta. (Life of Sayyid Ṣadru-d-dīn Rāju-i-Qattāl, Text, II. 417, 1.2 f. f.).

VI. 326, l. 2. [They were] not to trouble the singers and musicians to give chairs after the manner of a darbar.

should not compel the musicians to put in *Chauki*, i. e. attendance [by turns, in their courts,] as is customary at the Imperial Court". William Finch tells us that the dancing girls of Agra had "to attend, as their several turns come every seventh day, that they may be ready when the King or his women shall please to call any of them, to sing and dance in his Moholl." (E. T. I. 183). See also Manrique, II. 161.

VI. 326, l. 5. When they presented a horse or elephant to any man....., they were not to require obsistance from him with a horse's bridle or an elephant's good placed upon his back.

· This refers to a strange observance of the old Mongol Code of Courtetiquette, which was enforced by the Timuride Emperors of Dehli. The explanation is provided by a European writer. He tells us that "Kettle drums and the right to play them were great favours which were bestowed by the Mughal Emperors only on officers of the rank of 2000 Suwar or upwards The drums, when granted, were placed on the recipient and thus accoutred, he had to do homage for them in the public audience hallBut when these favours were conferred upon Lord Lake soon after his great victory in 1803, "two small drums of silver were hung round his neck and struck a few times." (Thorne, 'Memoirs of the War in India', 1803-6, Ed. 1848, p. 356; Irvine, A. I. M. p. 30). Similarly, when a horse or elephant was presented to any one by the Emperor, the donee was bound to make obeisance (taslim) by way of thanks, with a horse's bridle or elephant's goad on his own back. Jahangir now strictly forbade governors of provinces to arrogate to themselves or usurp this peculiar privilege of Royalty.

VI 326, l. 9 [They were] not to place their seals upon letters addressed to royal seriants

etters to them [the Emperor's own servants], they were not to put their seals on the front (lit face) of the letter "as the latter were not their inferiors (See Ain, Book II. Chap XII on the Order of the Seals Tr I. 163 and my note on E D IV 378, 1 20)

VI 331, l 3 Certain political considerations induced me to depute him [Muqarrab Khān] to the sea-port town of Goa to visit the Wazir or ruler of that place

Muqarrab Khān's visit to Goa is mentioned in the Portuguese accounts also, in which it is stated that he was accompanied by the Jesuit Pinheiro We know from these sources that Muqarrab left Agra in September 1607 AC Though the orders for his recall had been issued by Jahāngir in 1610, he appears to have returned only now in 1612—1021 H. (V Smith. O. H I 380, Foster, E T I. 88 note)

VI. 332, l 8. I put the tika on the forehead of Dalpat with my Royal hands

The text reads Dalīp cl. 19), and Mr Beveridge has followed it (Tr I. 218) But the real name was Dalpat (Tod, A. A. R II. 1135 note, Erskine, Gazetteer of Rājputāna, III A. 319 and III B 83, Aīn, Tr I. 359, Duff, C I. 277)

VI 332, l 13 Lakhmi Chand was son of Rajā Rai (of Kamāun).

The father's name is printed in the text as الوحر 'Udar', (106, 1 7 ff), for which read *Rūdar*, و Rudrachand, (q v B II 365=Tr 377; E. D. V. 511, A N III 533, Tr 812, 735, 818, Duff, C I 281)

VI 335, l 11 Then they [the rulers of Chitor] took the title of 'Rup', 'handsome', instead of Ruja

they made 'Rīwal' a part of their name or title" 'Rūp' must be an error for 'Rēwal' "The Chief of the State (of Mewār)," Abu-1-Fazl writes, "was formerly called Rīwal, but for a long time past has been known as Rīna" (Ain, Tr II 268) Tod states that the ancient appellation of the rulers of Chitor was 'Rūwal' and 'Rūna' was assumed by Rahup, only in the 12th century, after his victory over Mokal Parihūr (A. A. R. I. 249,

305. See also I. G. XI. 380; Crooke, Tribes and Castes, II. 374). Rahup's date is disputed. Some put him in the 14th century. (J. A. S. B. 1886, p. 16). 'Rūp' in the translation may be due to some confusion between it and 'Rahup'. It was Rahup who changed the title.

VI. 335, l. 12. After that, they overran the mountain land of Mewāt and still advancing, got possession of the fortress of Jaipūr.

Both the place-names are wrong. Read 'Mewār' and 'Chitor'. The text has عيتور and عيتور (122, l. 13). Jahāngīr must mean Mewāḍ by the former.

VI. 336, l. 4 from foot. I left Agra and encamped in the garden of Dahra.

This 'Bāgh-i-Dahra' exists still to the south of the cantonment of Agra, opposite the third mile-stone on the Gwālior road. (Keene, Guide to Agra, 52). It is not far from the tomb of Firūz Khān, which is shown on Pl. 48 of Constable's Atlas. 'Dahra' is said to be an abbreviation of Dahr-ārā, 'Time-adorning', 'Ornament of the Age'.

VI. 337, 1.5. On the 21st day of Mihr, I started [from Agra].

21st must be an error for 1st: It is غرف in the Text (123, 1.12). As the intelligence of Rājā Basa's death is said, only two lines lower down, to have reached the royal author on the 2nd of Mihr [ودر مهر], Jahāngīr must mean 1st and not 21st.

VI. 337, l. 18. In this month Azur) [of the eighth year of the reign], news arrived that the Europeans of Goa...had plundered four ships engaged in the foreign trade of the port of Surat.

The eighth year corresponded to 1022-23 A. H. and 1613-1614 A. C. The reference is to the capture by the Portuguese in 1613, of four Mughal ships, the chief of which is said to have belonged mainly, if not entirely, to Jahāngīr's mother and is said to have carried "three millions of treasure". The name of the vessel is given in the English accounts as "Remewe" and this is copied without any attempt at emendation by Mr. Vincent Smith. (O. H. I. 381). The real name was "Raḥīmī".

VI. 339, l. 11. He had captured the families of many Singhs and had brought the enemy to such straits.

'Captured many Singhs' is unintelligible. فو اسير شدن اهل وعبال اكثر سكنه (133, last line). "And the capture of the families and children of most of the residents [سنك plural of سكن physical of that country, had made matters so difficult for the Rānā (pressed him so hard)." سكنه شهر برها نبور "occurs in the 'Amal-i-Ṣaliḥ (I. 421) and سكن شهر وقلعه in F. (II. 312, l. 15).

VI. 339, l. 3 from foot. I wrote him a kind and reassuring farman under my own seal.

The words used by the Emperor are نشان و بنجهٔ مبارک عنابت نرمودم (134, l. 15). The 'Panja-i-Mubārak' was not a seal in the usual sense of that word at all. It was really the impression of the palm of the

Emperor's right hand stamped in vermilion on the document Khān Jahān Lody afterwards begged for and was granted by Shāh Jahān a Farmān stamped with the Panja, assuring him of forgiveness and safety. (Bādishāh Nāma, I 1. 274) Such Farmāns were sought by the rulers of Bijāpur and Golkonda also from that Emperor and graciously issued after they had bound themselves to pay tribute and acknowledge the Great Mogul as their overlord and suzerain (Ibid, I. 11, 167, I. 8, 210, I. 7). Tod gives the English translation of a Treaty between the Rānā of Udaipur and Aurangzeb, on which the 'Panja-i-Mubārak' was stamped and the word 'Manzūri' inscribed in the Emperor's own handwriting. (A A. R. I. 452)

VI. 340, l. 12. Defeat of the Portuguese (Warzi) An action took place between them and the English.

The printed text has Action (134, 1 11 ff), which is a miswriting of the Portuguese Vicerei, or Viceroy, Recte eccept that is the Portuguese Viceroi, or Viceroy is used by Abu-l-Fazl for the Portuguese Viceroy, in his account of the death of Sultan Bahādur Gujarāti. (A. N. I. 145, 11. 13, 19—Tr. 323 and Note). The event alluded to by Jahāngīr is the defeat inflicted by Nicholas Downton on the Portuguese fleet in a battle in Swally Hole near Sūrat on the 20th of January 1615 (Hunter, History of British India, I. 320-6, Danvers, History of the Portuguese in India, II. 170-1) The Commander of the Portuguese fleet was Don Jerom de Azevedo, Viceroy of Goa. The news reached Jahāngīr in the month Bahman of the ninth year of his reign which synchronised with January-February 1615 A. C

VI 342, l 4 from foot [I diminished my wine, but] I took to eating faluha

Dowson notes several variants and thinks that it is Bhāng But it is light in the Text (151, l 9 ff) and 'Falūniā' is right. It is the Greek Philonia, an antidote or drug invented by Philon of Tarsus who lived in or before the first century of Christ Its ingredients are not exactly known, but it was most probably a preparation of opium (Mr Beveridge's Note, Tr I 308). Pelsaert speaks of "mosseri [Mufarrih, [and] or 'falong' as "exciting perfumes and efficacious preserves" which were habitually used by the wealthy. He also states that they contained amber, pearls, gold, opium and other stimulants (Remonstrantie, Tr. in Jahāngīr's India,' p. 65). Mr. Moreland's explanation or derivation from the seed 'falanja' will not bear examination

VI 343, l. 9 from foot. Having received assurances from Shahsawār Khān, who was at Bālāpur

Recte, 'Shahnawāz Khan', as in the text (153, 1, 17). He was the eldest and most capable son of the Khān-i-Khānān The Iqbāl Nāma also reads 'Shāh Nawāz Khan' (85, I 1)

For 'Bābā Jūkāyath' (1 7 f f) the text has 'Bābu Kāntiya' مار كاتبه 'Bābu [Jiu] Kāntiya [Ghāte ?] (153, 1. 19).

VI 344, l. 11 from foot Next day, the army having moved from Fathpur, marched towards Khirk; Neither the text (154, l. 10) nor the Jqb. Nām. (87, l. 4) makes any specific mention here of a town or village called Fathpur. What is said is that the army marched from the 'place of victory' to Khirki.

VI. 345, l. 3. Many little insects issue like gnats, which are called in the language of those people Chika.

The Text reads 'Jhinga' (154, l. 21). Mr. Beveridge says that 'Jhingur' or 'Jhinga' means, in Hindustani, 'cockroach' and 'water-locust' (Tr. I. 315 note), but neither of these creatures bears any resemblance to a gnat either in size or appearance, and the phonetic resemblance seems delusive. Jhinga (Sansk. Chingat) in Gujarāti means 'shrimps' or 'prawns,' but the insects intended must be some sort of mosquitoes or midgets.

This diamond mine in Khokra is described by Tavernier, who states that it was at 'Soumelpour,' thirty Kos south-east of Rhotās. According to his account, the stones are found in the river Koel, a tributary of the Sone, when the stream becomes low in January after the cessation of the rains and the sand is left uncovered. Dr. Ball has identified this 'Soumelpour' with 'Semah' on the Koel in the Palamau sub-division of Lohardaga district. He warns his readers that Tavernier's 'Soumelpour' should not be confounded with 'Sambalpur,' on the Mahānadi. (Travels, Tr. II. 84-86 and Appendix, 457-459). A place called Khūkra in Lohardaga, Bengal, is shown in Constable, 28 D d.

VI. 346, foot note. Jahāngīr records that one of his nobles died of cholera (haiza).

Aniza is generally used for all sorts of diarrhoea, or dysentery and looseness of the bowels. It does not always or necessarily mean cholera. There is no distinctive word for 'cholera' either in the old Hindu or Muḥammadan treatises on Medicine. The vernacular 'Modchi' is loosely used for cholera and also for other violent forms of intestinal disease accompanied by severe pain. Abu-l-Fazi has recorded the deaths of several nobles of Akbar's Court from Haiza, and Mr. Beveridge has rightly translated the word as diarrhoea. (A.N. III. Tr. 801, 922, 967, 1001, 1074, 1156).

VI. 348, l. 7. [In the tray of fruit, there were] the celebrated melons of Kārez, Badakhshān and Kābul.

'Kārcz' is used in Persian generally for the underground channels for irrigating fields and gardens, which are found everywhere in the country, but it stands here for the name of a place near Herāt.

VI. 348, l. 12. Pine apples from the sea-ports of the Europeans were also in the tray [of fruit, brought to me].

The pine-apple was introduced into India in the sixteenth century by the Portuguese. The name 'Ananās' by which it is known in most of the Indian vernaculars is derived from the Brazilian word for the fruit, which is 'Nana' or 'Nanas.' (Yule, H. J. s. v. Ananās). The earliest reference to it in Indian literature is found in the \overline{Ain} . (Tr. I. 68). Jahāngīr's statement that these fruits of 'excellent fragrance and fine flavour' which had

come from "the Frank ports" grew by the thousand in the Gulafshān garden at Āgra is interesting and indicates that this exotic plant had spread very rapidly Terry speaks of it as the best of all fruits and describes its taste as "a pleasing compound of strawberries, claret wine, rose water and sugar well-tempered together" (E T I. 297) A still earlier traveller, Linschoten, states that so many were grown in Malabār when he wrote (Circa 1596), that they were "good cheape" (Travels, II. 19)

VI 351, l. 9 From the twelfth year of my age AH. 988 to the fifteeth . year of my age, 28,532 animals and birds were killed in the course of my sport

A meticulous enumeration of the different varieties of animals which were shot by the imperial marksman during his hunting expeditions is repeated at the end of the chronicle of several other years in this Autobiography It appears to have been done in imitation of the Seljūq Sultān Alp Arslān, of whom it is recorded by Ibn al Athīr (Kāmil, X 74), that he ordered a register to be kept of each day's bag in the chase, which sometimes contained as many as seventy gazelles (Browne, L H P. II 183) Other Asiatic sovereigns also appear to have kept similar inventories or records of their prowess in the hunting field.

VI 352, l 8 from foot. I encamped on the bank of the tank of Jhanud

The text reads 'Jhasod' here (205, 1.8), but 'Jhanod' at (220, 1 24) Mr Beveridge suggests that it must be the tank of Jasodā (or Yashodā), the foster-mother of Krishna! (Tr I 414 note) When Jahāngīr mentions the place again in the itinerary of his return journey from Ahmadābād to Dāhod, via Petlāḍ and Nariād, he locates it at about nineteen Kos west of Jhālod and about six Kos east of Bālāsinor (Text, 219-220, Tr I 443-4). The place meant must be, therefore, Janod in Rewā Kānthā Bālāsinor is also in the Rewā Kānthā Agency and is shown in Constable, 27 A d Janod is entered as a village in the Post Office Guide.

VI 353, l. 19 It [Khambātt] was called Trimbāwati and Rājā Nar Sing Makhwār was its ruler

The text gives رَكَ كُوار (206, 15) as the name of the Rājā This form 'Trimbak Kunvār' is perhaps connected with the supposed name of the ancient city, which is said to have been called 'Trimbāvati,' but the assonance between the two names engenders the suspicion that both are factitious eponyms shaped by a false etymology The Prākrit name of Cambay is 'Khambhāvati' and the Sanskrit 'Sthambhavati,' the 'City of the Pillar god (Stambha),' i e Mahādeva 'Stambhavati' seems to have been turned into 'Tambhavati' or 'Tāmbavati' and the latter form confused with the vernacular 'Tāmbā' (Sanskt tāmra), which means 'copper.' Mythology may or may not be a "disease of language," but this folk-etymology does appear to have given birth to the local legend about the town having been enclosed by a wall of copper

Towns with walls of copper are part of the stock-in-trade of Hindu

folk lore. Ahār in Udaipur State, Rājputāna (I. G. V. 93) and Chatsu or Chaksu in Jaipur (Ibid, X. 182) are both said to have been anciently called 611 Tāmbāvati for that reason.

The fact that this Raja's descendant, in connection with whom Jahāngīr relates the story of the 'Pillar', was named 'Abhay Kumār' indicates that the second name has been read correctly in the Text as 'Kunvār', [Kumār]. 'Makhwār' must be wrong.

VI. 354, l. 2 from foot. It was also ordered, in these days, that tankas of gold and silver, ten and twenty times heavier than the current Mohur and rupee

مانند می مانند و دوریهٔ معمول که کنند میر و رویهٔ معمول که کنند و دون مهر و رویهٔ معمول که کنند (207) در بنولا حکم شد که تنکهٔ طلا و تقره ده بیست وزن مهر و رویهٔ معمول که کنند 1. 5). "About this time, orders were issued for the stamping of Tangas, double the weight of the ordinary Muhr and rupee". ... does not mean "ten times and twenty times," but "in the proportion of ten to twenty ", i. e. 'as one is to two 'or 'double.' See my H. S. M. N. 173-176.

Jahangir uses the parallel expressions -ده دو ازده - ده بانزده - (Text, pp. 4-5) and they have been correctly rendered by Sir H. Elliot, who translated the passage, as "ten to twelve", "ten to fifteen", "ten to thirty" and "ten to forty", i. e. 20 per cent, 50 per cent, 300 per cent and 400 per cent, at 286 ante. See my notes on Vol. II. 76, 1.20; III. 321, l. 1 and 327, l. 6.

VI. 355, l. 6 from foot. The Rājā of Khurda and the Rājā Mahendra. Read "Rājās of Khurda and Rājmahendra." Khurda is a well-known place in Puri district, Orissa. 'Mahendra' is not the name of the Rājā, but the tail of the toponym only "Rajamahendra" or Rajmundry. The town is "called after the Mahendra range of mountains, which is the principal physical feature in this tract of country and is mentioned in the Mahābhārata and the Vishnu Purāna.... The range divides Ganjām from the valley of the Mahanadi." (Cunningham, A.G.I. 516). VI. 357, l. 11 from foot. 20000 darabs were given to Hakīm Masīhu-

"Darab" or "Darb" was a fanciful name given to the half-rupee

by Akbar. It is derived from the Sanskrit, dravya, wealth. So, charan, Akbar's new-fangled denomination of the quarter-rupee is connected with Sanskt. charana, foot. (Historical Studies in Mughal Numismatics, 93-100).

VI. 358, l. 3. And by the advice of some physicians of Multan, I took my

The words "of Multan" are due to a misreading المتصواب حكما شب ثلثان عناد ياله (231, 1. 3). " And by the advice of physicians, I took on the third night, my customary cups (of wine)." is not unlikely to be misread

VI. 360, l. 2. Mansur is also a master of the art of drawing and he has Recte, 'Nādiru-l-'Aṣri,' as in the tr 235, 1,7f.f.). Nādiru-z-zamāni

was the title conferred upon his colleague and rival Abul Hasan. (359 ante). 'Asr' and 'Zamān' are synonyms and both mean 'time,' 'age.' Abu-l-Hāi (359, l. 6 f f.) "Father of the Ever-existing," ie of the Supreme Being, is an impossible name. Read 'Abdu-l-Hayy, 'Servant of the Living God.'

VI. 364, l 3 Upto the present time, nearly eight year's have elapsed since its first appearance

reight nights," not بشت سال The text correctly reads مشت شد "eight nights," not والماه years.' (250, 1 11 ff) The Cawnpore lithograph also has عثت شر (252, 1 15) The Iab Nam states that the malesicent effects of this astral phenomenon were felt for seven or eight years (Text, 118, 1 9 See also 407 infra) Elliot's surmise that it was a 'new star' is not correct. Jahangir records in a somewhat confused manner two starry visitations—the second of which was observed some nights after the first. Both of them were comets and are mentioned in Fergusson's Astronomy (Ed Brewster, II, 360) and also in Russell Hind's (128, 144) and Chambers' works (p. 25) on Comets The year 1618 witnessed the appearance of two comets, the first of which passed its perihelion on August 17th, the second on 8th November (New Style) Jahangir's date 17th Zi-l-q'ad 1027 A H. corresponds with 26th October 1618 O S The Iqb Nam (117, 1 15) gives 16th Dai, but this must be an error for 16th Zi-l-q'ad 1027 H. The immediately preceding event recorded by Mu'atamad Khān is the appointment of Mugarrab Khān as Subadar of Patria on 21st Shahrivar, the immediately following event. the birth of Aurangzeb on 11th (recte, 15th) Zi-l-q'ad=12th Aban [the 8th month (118, 1, 3 f f) Dar [the tenth month] is therefore impossible. The date given in the 'Aligarh Text is not 17th Zi-l-q'ad, but Saturday, 18th Aban, which corresponded with 31st October, 1618 (Q S)

Sir Thomas Roe's chaplain, Edward Terry, has left it on record that two comets were seen by himself in India in 1618, when he was at the Mughal Court (Voyage to the East Indies, Ed. 1777, p 393) Mr Beveridge's conjecture that the first phenomenon was not a true comet, but the Zodiacal Light, is conclusively negatived as both these comets are registered in modern astronomical works.

Vi 364, l. 11. It recalled to my mind the tale of the King and the Gardener.

This is an ancient folk-tale which is found in Firdausi's Shāhnāma, 'Awfi's Jāwāmi'a, the Alf Laila wa Laila, the Akhlāḍ-r-Muhsini and the Tārīkh-r-Firūz Shāhi of Shams-i-Sirāj See my note on III 317, 1 14.

VI 366, l 7 from foot. Sharkh 'Abdu-l-Hakk Dehlaw . presented to me a book which he had written upon the Sharkhs of India.

This hagiography must have been the Akhbāru-l-Akhiār It has been lithographed and is well-known Vide also 175, 176 ante and 485, 486, 488, 491 post

VI. 368, l 12 We entered the pargana of Hazāra Fārīgh.

Recte "Hezāra-i-Qārlugh" as in the Text, 289, l. 10 (قارلة). This district is also called Chach Hazāra. The old district of Pakhli is now called the Hazāra Country in our Maps. The name 'Hazāra' is traced by some authors to Abhisāra, the kingdom of Abisares of Alexander's historians, while Sir Aurel Stein derives it from Urasā the ancient Hindu name of Pakhli, which is said to be still preserved in Rāsh or Orāsh, a village in the district. (I. G. XIII. 76; V. Smith, E. H. I. 55 note, quoting the Rājatarangini. Tr. Bk. I. 180). A third and more probable opinion is that the district is so called, because the Hazāras of the Qārlughs had settled and ruled in these parts since the invasions of Chingiz Khān.

VI. 370, l. 10. The people themselves say they are by origin Farsīs (?).
..... They are now called Lāhori and their speech is that of the Jats.

مكويندكه ذات ما قارلنم است..... الحال خود لاعوري محض أند و يزبان چنان متكلم (290, 1. 21). See also the Igb. Nām. (136, 1. 2). "They say that they are of the Qārlugh tribe. But now they are pure Lāhoris and their tongue [speech] proclaims them as such [bears witness to the same fact], i. e. they speak just like Lāhoris": جنان and خان are errors for خان and خان and خان عمل المرابع على المرابع على المرابع المرابع المرابع على المرابع الم

The text has "Bakhshi" (291, 1.12) and this is correct. See 363 ante, where he is designated Mīr Bakhshi—Chief Bakhshi. His origin was not from "Nakhshab" but from Turbat-i-Ḥaidari or Zāvah in Quhistān. This place is called Turbat-i-Ḥaidari because Shaikh Qutbu-d-dīn Ḥaidar, the founder of the Ḥaidari Dervishes, is buried there. (M. U. I. 737, 1.2; Lestrange, L. E. C. 356).

Jahangir's derivation of the name Pham Dirang from Kashmiri Pim or 'Pham' cotton, and the Persian word Dirang delay, is not sound. Here 'Dirang' is really the Kashmiri word 'Drang' signifying "custom-house, toll-house."

VI. 373, l. 11. I went five Kos, in a boat and anchored near Manpur.

Recte, "Pampur", as in the text (312, l. 3). See also ante 303, where it is called by its right name and mentioned in connection with Virnag and the source of the Behat. It is the ancient 'Padmapura', which was founded by Padma, the minister of King Vrihaspati, who reigned from 832 to 844 A. C. (Cunningham, A. G. I. 102). It lies on the right bank of the Behat, eight miles south-east of Srīnagar. Constable, 25 A a.

VI. 374, l. 4 from foot. Chaupar Mal, son of Rājā Basu.

The text has Janhar Mal here, (319, l. 19), and so also the Lithograph. (324, l. 7 f.f.). But the Iqb. Nām. calls him Sūraj Mal (173, l. 6 f.f.) and this is the form found in the contemporaneous Shash Fathi-Kāngra also. (520, 521, 527, 528, 529, 530, infra). Jahāngīr himself calls him Sūraj Mal repeatedly on subsequent occasions. Rājā Basu had, Jahāngīr tells us, three sons, Sūraj Mal, Jagat Sinha and Mādhav Sinha, and they are all mentioned in the T.J. (254, l. 2; 264, l. 8; 376, l. 30; 377, l. 26; Tr. II. 54, 75, 287, 289). Faizi Sirhindi also mentions Sūraj Singh, son

of Rājā Basu of Maū in the 40th year of Akbar's reign. (126 ante).

VI 375, l 11 [Kängra] surrendered on Monday, 1st Muharram (1031)

The year is wrongly given and should be 1030 H. The news reached Jahangir on the 5th of Muharram of the 15th year of his reign (p. 374 ante), which had begun on 15th Ra'bi II. 1029 H. (373 ante).

VI. 376, l. 7 from foot [The rebels in the Dakhin] were burning and destroying ships and provender.

The destruction and burning of ships by the Dekkani armies in Ahmadnagar and Birār is not likely. کشتبا 'Kishtīhā' has been wrongly read here by Dowson for کشتبا " cultivated fields." See Text, آتش ردن و صابع علی مادی 321, 1 16

VI 375, l 27 and footnote.

Salt is not produced in Kashmīr and even in the beauty of the inhabitants, there is but very little, i e they have but little expression. Malābat is the word and a double meaning is intended (Footnote)

The right word is Malāhat the Malāhat. There is no such word as Malābat in the Dictionaries The former signifies 'a peculiar kind of charm or beauty, piquancy, delicacy or elegance, and is from the Arab Milli, salt Its literal meaning is 'being salt.' Jahāngīr is playing upon the word and observes that there is as great a lack of salt, i e expression in the faces of the inhabitants, as there is of edible or mineral saline matter in the country. As Kashmīr possesses no salt mines and no facilities for the artificial manufacture of that commodity, all salt has to be imported. The sarcastic remark is an interpolation. It is not to be found either in the text (315, 15 f.f.), or Mr Beveridge's Translation (II. 178)

VI 377, l. 10 from foot The rebels advanced fighting as far as Azdū. This 'Azdū' is another apocryphal toponym and the reader will vainly search for a place called 'Azdū' on any map or in any Gazetteer. It is an error for الردو, Urdū, z. e the Mughal Camp See Text, 322, l 6 The lithograph also has الردو. (327, l 10)

VI. 379, l 4 The sword bent like the genuine Almasi swords or those of the Dakhin

The 'Aligarh text reads & yamāni, i.e. 'of Yemen,' not 'Almāsi' (330, 13) and so also the Lithograph (335, 1.6 ff.) and the Iqb Nām. (180, 12) The author of the Mirāt-i-Sikandari speaks of Egyptian, Yamāni, Maghribi [Spanish, Moorish or African] and Khurāsāni swords. (Text, 98, 14). Sir E C. Bayley thinks it possible that German swords are meant, as "European sword-blades found their way to India at an early period and are still occasionally to be met with in the country." (Tr. Mirāt, 184 note) But he cannot be right, as Hasan Nizāmi also speaks of the "swords of Yemen and the daggers of Hind" (Tāju-l-Maāsir in E.D II 217) 'Unsuri also uses the phrase 'La alignitation' (Diwān, p 74, V 9) On the other hand, Hawkins in his Inventory of Jahāngīr's Treasure states that "of swords of Almaine (German) blades, with the hilts and

scabbards set with divers sorts of rich stones of the richest sort, there are two thousand and two hundred." (E. T. I. 103). Terry (*Ibid*, 314) and De Laet (Tr. 115) also note that as "the swords made in India will break rather than bend, there is a great demand for European sword-blades, which fetch high prices because they bow and become straight again."

If Jahangir wrote Almani Illis [Allemand], not Al-yamani or Ya-mani and meant "German," Janubi might signify 'Genoese'. The famous Andrea Ferrara blades came from Genoa. Mr. M. J. Wallhouse states in an article on the old weapons in the Tanjore Palace Armoury, that many of the Kaṭārs [daggers] were of European manufacture and "one of them bore the name of Andrea Ferrara." (Ind. Ant. 1878, VII. 193). Shivāji's sword Bhavāni is also said by Grant Duff to have been an excellent Genoa blade of the first water. (Reprint, I. 230, Note. See also Ind. Ant. 1924, pp. 18-19). But, all this notwithstanding, it seems preferable to understand Janubi as 'Southern' or 'Dekkani' and 'Yamāni' as 'Arabian.'

VI. 380, l. 11 from foot. It was settled that a space of fourteen Kos beyond should be relinquished.

So also in the Text, 331, l. 6 f.f. where the words are spice of spice of lam. reads i.e. territories yielding an annual revenue of fourteen Krors of Ilāms. (183, l. 2). The author of the Maāsiru-l-Umarā has understood the passage in the same way and states that (II. 15, l. 11). The author of the Maāsiru-lecen Krors of dāms from the districts adjoining the old dominions of the Empire were to be surrendered. The Bādshāhnāma (I. ii. 200, l. 4) and the 'Amal-i-Sālih' (I. 158, l. 4 f.f.) also read for and this indicates that in their Mss. of the Tūzuk and Iqbālnāma, the word was written as See also Khwāfi Khān (I. 532, l. 13), who has copied the I. N. in his slovenly way. Jahāngīr says that the Dekkanis had "got many of the districts of Aḥmadnagar and Birār into their power" (376 ante), and that they had occupied many parts of the Imperial dominions." A cession of only fourteen Kos of territory in such circumstances seems quiet paltry and 'not worth the candle'.

VI.382, l. 6. Village of Bahlun, a dependency of Sibā.

'Bhalon' and 'Siba' were Mahāls in the Sarkār of Beth Jālandhar Duāb. (Āīn. Tr, II: 316-7). 'Siba' is now part of Kāngra district, but was formerly an independent principality. The town is seventeen miles south-west of Kāngra. Bassin, Terry and some other European writers of the 17th century extend 'Sība' so as to include Hardwār and even speak of Hardwār as the capital of Sība, but this is an error. (Sir W. Foster's note to Terry in E. T. I. 294). De Laet says 'Siba' lies to the south of Nagarkot. (Tr. Hoyland, 12). Cunningham mentions it along with Kāngra, Goler, Jaswāl, Kulu, Chamba, etc. in his list of States attached to the Eastern or Jalandhar division of the Alpine Punjab. (A. G. I. 135-6).

VI. 382, l. 17. Nur Jahan, who was by my side, made signs and asked if I perceived [her father's] critical condition.

The real meaning is turned upside down What the Begam did was to ask her father, not Jahängir, if he recognised the Emperor who was standing by the bedside (مَى مُنَا مِنْ) and the dying man replied by quoting a couplet of Anwari's which means: "If even a congenitally blind man were present here, he could recognise in such a perfectly splendid mien a leader of men (or nobility and grandeur)." An example of the strength of the ruling passion or lifelong habit of adulation even in death! VI 383, l. 3 A letter from Khurram informed me that Khusrau had died of colice.

Though all the contemporary European authors, Terry (Voyage, p. 412), De Laet (Tr. Hoyland, 1989), Herbert (Travels, p 80), Peter Mundv (Travels. II. 124-5) and Pietro della Valle (Travels, I. 58) state that Khusray was murdered by the orders of Shah Jahan, Mr Beveridge maintains that "there is no evidence worthy of the name" in favour of the charge. (J. R. A. S 1907, pp 597-602). Sir Richard Burn also holds that "the cause of his death has never been established beyond doubt," though he admits "that the probability of murder is strengthened by Shah Jahan's later action," in regard to Shahriar, Dawar Bakhsh and other princes of the blood royal. (CH.L, IV 169) Dr. Beni Prasad, after reviewing the question at some length (Jahangir, 336-9), declares Shah Jahan guilty, but he does not adduce the authority of any contemporary Mughal historian of credit in support of his contention. It may be therefore pertinent to draw attention to the damning and decisive testimony of Muhammad Salih Kambu, the official chronicler and ardent panegyrist of Shah Jahan. His statement has been overlooked by all writers on the subject, and is therefore all the more important. This author boldly avows and justifies the crime, just as Jahangir unblushingly admits his instigation of the assassination of Abu-1-Fazl. He tells us that the destruction of the brothers and relatives of great kings is often for the peace and well-being of their subjects and that many leaders of church and state have declared the extirpation of such domestic enemies an unavoidable necessity in the interests of good government He then argues that the utter incapacity and insouciance of Jahangir, the intrigues of the Nur Jahan junta, and their machinations in favour of Shahriar left Shah Jahan no other course than the immediate removal of Khusrav and that it was an absolutely necessary preliminary to the discomfiture and destruction of his other rivals. He also states that the order for handing over Khusrav's person to Shah Jahan had been given by Jahangir when he was not in his senses after one of his drinking-bouts and that the eldest prince was strangled (4) on the 20th Rab'i II. 1031, A H (22nd February 1622) ('Amal-2-Salth, I. 162, 1 2 f f--165, 1 3) 20th Rab'i II is probably an error for 20th Rab'i I=23rd January, 1622.

VI. 383, l 8 A despatch arrived from the son of Khan Jahan,

عرصداشت مررد عامجهان رسيد (345, 1 1). The despatch arrived (from

Khān Jahān himself, on whom Jahāngīr had conferred the title of 'Son.' (T. J. 42, I. 13, Tr. l. 87). In the counterpart passage of the Iqb. Nām. also, the missive is stated to have arrived from Khān Jahān himself (192, l. 13; see also Ibid. 19, l. 7). Jahāngīr again speaks of Khān Jahān as 'farzand' (323, l. 5 and 324, l. 5). Akbar had bestowed the identical title on Rājā Mān Sinha of Amber. (A.N. III. 136; Tr. 236).

VI. 387, 1.8. When the army passed over the mountains of Chanda and entered Malwa.

The 'Pass of Chāndā' or 'the defile of Chāndā' has been mentioned before at pp. 154 and 352 also. It is there called 'Ghāt i-Chānda." It is the Gate [Gāté] of Tavernier, who locates it at three Kos from Dongri and four from Narwar. He speaks of it as a pass in the mountain which is half a quarter of a league long and so narrow that chariots can only pass one another with the greatest difficulty. (Tr. Ball, I. 59, 61). Dongri is 8 miles from Sīpri, which is 15 miles from Kolāras. Cunningham says that 'Dhongri' is a village about ten miles south-west of Narwar and there is a place called 'Patti Ghatti' near it, where a bridge was built in the time of Aurangzeb." (Arch. Surv. Rep. II. 325). For Kolāras, see Constable, 27 C c. VI. 387, I. 18. He [Khurram] sent his forces against the royal army

The text (368, 1. 5) reads collective in the environs of Kālīyādeh,' the real name of the place. Dowson has disjointed confrom US and translated it as 'village.' Kālīyādeh was a well-known beauty-spot, three miles from Ujjain. It is described as "one of the most delightful places in the world" (134 ante). See also 'Abbās in E D. IV. 393.

near the village of Kālīya.

VI. 389, l. 17. He [Khurram] crossed the river Mati and went off towards the Dakhin.

No such river is known. Read $\ddot{\omega}$ as in the $Iqb.~N\bar{a}m.$ (212, l. 6 f.f.). See infra line 26, where the $T\bar{a}pti$ is mentioned as the river across which Parviz and Mahābat Khān had pursued the fugitive Shāh Jahān.

VI. 393, l. 10 from foot. When Sultan Parwez...arrived at Allahābād, 'Abdulla Khān raised the siege and returned to Jhaunsi.

This is not Jhānsi in Bundelkhand, but Jhūsi or Hādiābās. opposite Allahābād "with which it communicates by a ferry across the Ganges." The printed text reads 'Jhūnsi' (388, l. 5 f.f.). The Iqb. Nām. explicitly states that this "Jhūnsi was on the Ganges opposite Allahābād." (411 infra, Text 223, l. 6). It has been supposed by some authors to be the Purāṇic Pratishṭhān, which was the residence of Pururvas, the first prince of the Lunar dynasty and grandson of Chandra, the Moon. It is also a sort of Hindu Gotham and known as Harbongpur, the capital of a legendary noodle named Rājā Harbong. (Elliot, Races, I. 262-3). It is shown in Constable, 28 C c.

VI. 394, l. 8. Prince Parwez and Mahābat Khān arrived at Dam-dama,

Damdama is a village in Allahābād district. The battle of the 'Tūnus', Recte, Tons, which is described here, took place at the junction of the Ganges with that river (C. H. I., IV 173 Note and Map)

VI. 396, l. 5 from foot. Mahābat Khān had married his daughter to Khwājā Barkhurdār, the eldest son of Naqshbandi

تواحه رحوردار بام بزركراده منسدى بست كرده (401, 1 16 f f). Buzurg-Zādeh-i-Naqshbandi really means 'a nobly-born Saiyid of the Naqshbandi family' The real name of Barkhūrdār's father was Khwājā-'Umar. (Iqb Nām 253, 1 13, see also 420 infra) 'Abdullā Khān Bahādur Firūz Jang was also a Naqshbandi Saiyid. (T J Text, II. 1 3 f f, Tr) Mahābat Khān himself was a Razwi Saiyid and his father Ghiyūr Beg had emigrated from Shirāz to Kābul. (M U. III. 385)

The Naqshbandı Saiyıds are descended from Khwājā Burhānu-d-dīn Naqshbandı of Bukhārā [born 728, died 791 A H.], who was so called because he and his father used to weave Kamkhā (Kincob) brocades adorned with figures. (Āīn, Tr I. 423 note) The Naqshbandis had married more than once into the Imperial family Mirzā Muhammad Ḥakim's sister was the wife of Khwājā Hasan Naqshbandı Jahāngīr's brother, Dāniyāl, had married a daughter of Sultān Khwājā Naqshbandı. The father of Salīma Sultān Begam, who was Bābur's granddaughter and Akbar's wife, was Khwājā Nūru-d-din Naqshbandi (A N II. 65, Tr. 98 note)

VI. 398, l. 14 from foot. The old servant called Dila Rāni, who had nursed the favourite lady of the king, [Nur Jahān] superseded Hāji Koka

'Dıla Rānı' is certainly wrong The woman is said, by Mu'atamad Khān, to have been the wet-nurse of Nūr Jahān and she is described as بر کر دای دلارای 'the old slave-girl, Dāt Dılārām'. (Igb Nām 56, l. 14) See also the Preface of Muhammad Hādı (Dıbācha to T J 21, l. 4) The M.U (I 133) speaks of her as مر ای دلارای which may mean that she had been originally, "a slave girl, named Hīrā and had afterwards come to be known as Dāt (nurse) Dīlārām," or that she was "Hīrā who had been the slave girl of Dīlārām, the nurse" of Nūr Jahān. The meaning turns upon reading or not reading an izāfat after عبر But عبر Hīrā is, most probably, a miswriting for بر [old]

VI. 403, last line On the road, as he [Ghiyās Beg] was passing through Qandahār, another daughter was boin to him

The popular tale of Nur Jahan's birth in the desert of Qandahar, the abandonment of the infant by the parents and the selection of the mother herself as wet-nurse, appears, like all such historical romances, to have been considerably embellished in passing from mouth to mouth There is no reference to her birth in a desert or the extreme destitution of her parents in any of the contemporary European writers, who do not spare her character and even repeat the vile and scandalous tittle tattle of

the bazars. It appears for the first time in the pages of Khwāfi Khān, who wrote more than a hundred years after Jahāngīr's death. He quotes as one of the sources of his information the Memoirs of a man named Muḥammad Sādiq Tabrīzi, who is said to have been a servant of Prince Shuj'ā, the brother of Aurangzeb. (B. I. Text, I. 263-4). He also speaks of having heard the circumstantial details which he relates from an old Darwīsh named Mirzā 'Ābid, who was living in retirement at Sūrat in 1107 A. H. (1696 A. C.) and claimed to be about 105 years of age at the time. This man is reported to have stated that he was, along with his mother, a member of the identical caravan which brought Nūr Jahān's parents to India. The story of the extremely sordid and beggarly circumstances in which she came into the world is explicitly stated to have been derived mainly from what this old man had seen with his own eyes.

But Khwafi Khan's chronology is, as is usual with him, shaky and a comparison of the dates given by him with other well-ascertained facts goes far to prove that this Darwish could not possibly have been the eyewitness he pretended to have been. If he was 105 years old in 1107 H., he must have been born in 1002 H. and if he was only seven years of age, when he accompanied his mother and Ghiyas Beg, the latter's arrival in India and the birth of Nur Jahan must be dated in 1009 H. But we know from Abu-l-Fazl's record, that Ghiyas Beg was already high up in the Imperial service as Diwan-i-Buyutat in 998 H. (A. N. III. 579, 1. 4-Tr. 877) and that when Akbar appointed twelve Divans for each of the twelve Sūbās of the Empire in the 40th year (1003 H.), Ghiyās Beg was promoted to be Divan of Kabul: (Ibid, 670, 1. 9=Tr. 1049). Again, if Nur Jahan was born in 1009 H., she must have been only 46 years old at the time of her death in 1055 H., 28 in the year of Jahangir's demise in 1037 H. and a child of only 12 when she married the Emperor in the 6th year of his reign (1020 H.). This is manifestly absurd, as she had already had, by Shir Afgan, a daughter who was then at least five years old. Briefly, the old man's pretensions to have been narrating what he had seen with his own eyes, must be dismissed and Khwafi Khan would appear to have swallowed too readily a fable. I may also mention that Nur Jahan is stated to have been born at Qandahār in 1577=985 A. H. (M. U. L. 127; Beni Prasād, Jahangir, 173; Houtsma, E. I., III. 891). If this date is correct, the Darwish must have been 129 years old in 1107 A. H.!

VI. 404, l. 7 from foot. [Jahāngīr] entrusted her [Nur Jahān] to the keeping of his [Jahāngīr's] own. royal, mother.

The phrase in the original is مادر سبی خرش (Iqb. Nām, Text, 53, 1.1), the real meaning of which is just the reverse. The 'Mācar-i-Sababi,' was a step-mother, a mother made by law, custom, or some man-made institution, as opposed to the Law of Nature. Mindaj states that Sultan Sanjar vowed vengeance against Arslan Shah Ghaznavi. because he had ill-treated his or step-mother who was Sanjar's sister. (T. N. 23, 1.4). Some writers explain this by stating that Arslan had forced her to dance be writers explain this by stating that Arslan had forced her to dance be

himself

VI. 405, l 11 Coin was struck in her name On all farmans also . , the name of 'Nur Jahan, the Queen Begam' was jointly attached

The words in the original are 'Nur Jahan Padshah Begam'. 'Padshah Begam' was a specific title which is heard of for the first time in the reign of Jahangir It implied that the recipient was the 'First Lady in the Land' The phrase has been rendered as 'Imperatrix Consors' by Marsden, as 'Imperatux, Queen Begam,' by Blochmann (Proc ASB 1869, p 255) and as 'Empress' by Mr Whitehead in his 'Catalogue of Mughal Coins in the Punjab Museum' All these equivalents are more or less wanting in accuracy and liable to obscure the true meaning of the title They are also calculated to convey a false impression in regard to the relationship to the Emperor of the person who bore it. The title did not imply that the lady was Empress or the wife of the reigning Emperor or even of his predecessor It was borne by the Princess Jahanara, the eldest daughter of Shāh Jahan (Khwafi Khan, II. 77, 1 19, 110, 1 13) Bahadur Shah, Shah 'Alam I conferred it on Zinatu-n-Nisa, his own half-sister and full-sister of 'Azam Shāh (1bid, II 30, 13, 600, 1 10, 735, line 2 f f, 736, 11). 'Padshah Begam' appears to have been the title given to the First Lady of the Court or Empire, the individual who in the feminine world, took precedence of all other women, as the Emperor did of all other men See my H S M N 319, where the subject is more fully discussed.

Mu'atamad Khān states that "coins were struck in her name," but this was done only in a few places and for only about five years from 1033 to 1037 H See my article on the 'Coins bearing the Name of Nūr Jahān' in Num Supp XLII to the J A S B 1929, Art 293 The number of Fai māns on which her name is found to have been endorsed also appears to be very small

VI. 408, 1 20 Ahmad Beg Khān, the Governor of Orissa, had gone forth against the Zemindars of Garha

The B I Text of the I N reads 's) or 's' (217, 1.3 f. f). The real name is 'Khurda' Sii Jadunāth Sarkār has pointed out that there is a detailed account of this invasion of Khurda in the Bihāristān-i-Ghaibi, a contemporary Chronicle of Events in Bengal from 1608 to 1624 A C, which was written by 'Abdullā Isfahāni, who was also called Shitāb Khīn (J B O R S IV 54, see also T J Tr II 298)

VI 417, l 8 from foot [His Majesty gave him to eat] a quarter of a Ser of saffron equal to forty miskals.

The Zakhīra i-Khicāi izmshāhi, which is quoted here for the supposed fact, is an old Cyclopaedia of Medicine written in 1110 A. C by Ism'aîl bin Husain Jurjāni It is a résum' or digest of the Theory and Piactice of Medicine as expounded in the Qānūn of Avicenna (Stewart, Catalogue of Tippoo Sultān's Library, 106, Browne, L H P II 346)

As the misquit was equal to about 72 grains, the Ser must be the

Jahāngīri Ser of 36 dāms $40 \times 72 \times 4 = 11520$ grs. and weighed about $1\frac{2}{3}$ lbs. 36 Dāms also would be equal to $36 \times 320 = 11520$ grs. On pp. 343, 361 ante, $7\frac{1}{2}$ tolās are equaled with $18\frac{1}{4}$ misqāls, which shows that 73 grs. went to one misqāl.

VI. 417, l. 14 from foot. The twentieth year of the reign commenced on the 10th of Jumāda-s-sāni, 1033 H. (10th March 1624).

Sic in the Text also (241, l. 1), but it is wrong and the Hijri year was the 1034th. Vide 390 and 393 ante, where the 19th year is correctly stated to have begun on 29th Jumāda-l-awwal 1033 H. (406, l. 6). Muḥammad Hādi (Continuation of T. J., 'Alīgarh Text, 396, l. 2) and the Cawnpore Lithograph also (406, l. 6), have 1034 H. The Christian year was 1625.

VI. 418, l. 9. [Shāh Jahān].....was compelled to go away to Rohangarh in the Bālāghāt.

in the B. I. Text also (244, 1.7), but the real name is 'Rohankheda,' now in the Malkapur talisil of Buldana district, Berar. It lies just below the Balaghat Pass. Lat. 20°-37′ N., Long. 76°-11′ E. (I. G. XXI. 301). It has been the site of two battles, one between the Bahmanis and the Faraqis in 1437 A. C. and another in 1590 A. C. between Burhan Nizam Shah and his own son Ism'ail. (I. G. IX. 60).

VI. 419, l. 4 from foot. The twenty-first year of the reign began on 10th Jumādu-s-sāni, 1035.

Here, the year is given correctly, but the date of the month is wrong. It should be 22nd, as in the Iqb. $N\bar{a}m$. (Text. 252, 1. 5; Hādī, 401, 1. 8 f. f.).

VI. 425, l. 16. On Sunday, the 20th Farwardin of the Ilāhi era [XXI. R. Y.], agreeing with 21st Jumāda-s Sāni, Āsaf Khānresolved upon giving battle.

Both the dates must be wrong. The 21st year began on the 22nd Jumādiu-s-Ṣāni. (Iqb. Nām. 252, l. 5; Hādi, 401, l. 8 f. f.). See also note on (419, l. 4 f. f. ante). The day on which the attack was made was or the eighth, and not twentieth of Fravardin, corresponding to the 29th contact (not 21st), of Jumādi II. as in Hādi. (405, l. 9). The editors of the printed text note that 29th Jumādi II. is found in one of their Mss. (261, l. 6 f. f. and note).

VI. 429, footnote. It is not stated when the Begam rejoined the Emperor.

But see ante 427, l. 8, where we are told that the elephant "swam to shore and the Begam proceeded to the Royal Abode." (Iqb. Nām. 264, l. 6). This Shāh Ism'aīl, to whom Jahāngīr is said to have paid a visit (l. 5), was not a Shāh or king, but a $p\bar{\imath}r$, i. e. a sort of saint or spiritual leader of the Hazāras who had encamped with his family at a village near Kābul. (I. N. 272, l. 8 f. f.).

VI. 433, l. 10. He [Shāh Jahān] determined to return by way of Gujarāt and the country of Bihāra (Birār?) to the Dakhin.

The real name is neither 'Bihāra,' nor 'Birār,' but 'Bhārā' and the 'country' was the province ruled over by Bhārā (Bhārmal or Bhārāmal) Jādeja, the Rāo of Kachh Abu-l-Fazl says that 'Bihāra Jāreja' was the ruler of Kachh in 1592 (A. N III 629=Tr 963), and he also records the death of his father, Khengār in 1585 A. C. (Ibid 472; Tr.711 and Note) Rāo Bhārā and Jām Jasā of Nawānagar were compelled by punitive expeditions sent against their territories to attend the Court and pay homage to Jahāngīr at Ahmadābād, in 1027 A H. (T.J 234-5, Tr II. 19-21, 34) See also my Note on Vol. I. 268, l 21. Dārā Shikoh also passed through' Kachh in his flight after the defeat at Deorāi, near Almer.

VI. 435, l. 14. When he [Jahangir] reached Bairam Kala.

Recte, Bîramgala, on the southern slope of the Pīr Panjāl Range It lies at the extremity of a dark and deep defile through which the river of Punch flows. Lat 33°-36′ N, Long 74°-40′ E The Pīr Panjāl Pāss really begins here, about 24 miles east of Rājauri 'Bīramgala' is the 'Bhairavagala' of the "Rājatarangini"

VI. 437, l. 18. Banārasi, the runner, left Jangazhati in the mountains of Kashmir

Jangız or Chingiz Sarai lies on the right bank of the Tawi, about half way between Naushahra and Rajauri and five miles N N E. of the former It is situated at the foot of the hills on the road to Kashmir, about twenty-one miles north of Bhimbar (Chihar Gulshan in I. A. p cv). VI. 439, l. 13. The author himself gives no name to the work.

This is denied categorically by Dr Rieu, who states that the title, $Ma\bar{u}_{3}v_{1}-v_{2}Jah\bar{u}ng\bar{u}_{1}v_{1}$ is found in the prefaces of both the copies which are in the British Museum. Dowson's assertion is, besides, conclusively negatived by the fact that the Abjad value of the title (40 + 1 + 500 + 200 + 3 + 5 + 1 + 50 + 20 + 10 + 200 + 10) is just 1040—the year of the Hijra in which the author says that "he was induced to undertake its composition" by the Emperor Shāh Jahān. The M. U. commends the work for its candid and veracious account of the rebellion of Prince Salīm (II 865)

VI 442, l. 13. They said that he [Prince Salim] had ordered coins to be struck in his name during his rebellion

No such coins have been hitherto found, though they do appear to have been struck, as I have shown in H. S. M. N. 76-79. Abu-1-Fazl (AN III 773, Tr 1155) and Khāki Shirāzi (205 ante) both state that Salīm "assumed the title of king." The question relating to certain coins which exhibit the name 'Salīm Shāh' is discussed in the Num Suppl. to the J. A. S. B., Nos. I. art. 5, X. ait. 59, XI. art. 70 and XII., art. 72 by Dr. G. P. Taylor. The arguments on the other side are stated by Mr. Beveridge in the J. A. S. B. 1908 (May) and Num. Supp. XII 71. They were struck only after Akbar's death

VI. 443, l. 22. Rājā Nar Singh Dev son of Rājā Budhkar. Both names are wrong Read 'Bir Sing [Vira Sinha] Deva' and

'Madhukar.' Rājā Madhukar Bundela was the son of Pratāp Rudra and was the father of eight sons. (J.A.S.B. 1902, p. 111). VI. 447, l. 21.

Shaikh Sikandar Gujarāti [was appointed to] introduce

This must be Shaikh Sikandar bin Manjhū, the author of the Mirāt-i-Sikandari. Jahangir visited his house and garden at Ahmadabad, which was famous for its figs. "As picking the fruit with one's own hand," the Imperial gourmet writes, "gives it quite a different relish and I had never before picked figs with my own, I did so, and their excellence was

For "Gujat Khān, the Superintendent of the Elephants," read 'Gajpatkhān' as at 423 ante. Gajpati in Sanskrit means 'master of elephants.'

VI. 448, l. 10 from foot. When the wire was put in his [Khusrav's] eyes,

There appears to be some truth in this anecdote. Pietro della Valle, who was in India about 1620, says that Khusrav's "eyes were sewed up, as is the custom here, to the end to deprive him of sight without excaecating him, so that he might be unfit to cause any more commotions, which sewing, if it continue long, they say, it wholly causes loss of sight. But after a while, the father caused the prince's eyes to be unripped again, so that he was not blinded, but saw again and it was only a temporal penance." (Travels, Trans. of 1665, p. 29; Hakluty Society's Edition, I. 56). Finch says that, "according to some, his eyes were burnt out with a glass, but that according to others, he was only blindfolded by a napkin tied from behind and sealed with the emperor's own seal". (Purchas, His Pilgrims, Ed. Maclehose, IV. 51; E.T.I. 160). Tavernier states that the sight was destroyed by a hot iron passed over the eyes (Tr. Ball, I. 334), which may be the wire' of this author. According to the Jesuit accounts and De Laet (Tr. 179), they were "smeared with the juice of the Ak or Madar, [Calotropis Gigantea], as a result of which the sight of one eye was entirely destroyed, though he could still see dimly with the other." Now we know from Jahangir himself that the title of Masihu-z-zaman and the mansab of 500 Zāt and 30 Suzvār were actually conferred upon Hakim Sadrā on or about the 6th of Jumadi I, 1018, during the Naurūz festival of the 4th year of his reign. (T. J. 74, l. 10 f. f.; Tr. I. 155). It is not improbable that this was his reward for restoring the sight of the Prince after the temporary revival of paternal love, of which this chronicler speaks. Jahangir says that he sent for Khusrav and had the chains taken off his legs, so that he might be able to walk in the Shahr-ārā Garden at Kābul on the 12th of Rab'i I. 1016 H. (Second Year), as his "fatherly affection would not allow of his depriving his son of that delicious pleasure." (53, 1. 14= Tr. I. 111). The Prince must have been able to see at that time, as otherwise there would be no sense in allowing him to enjoy strolls in the gardens. Khāki Shīrāzi states that Khusrav was blinded after the discovery of the

abortive conspiracy to assassinate Jahängir, on the return journey from Kābul. (Ms in the Mullā Firūz Library, Bombay, folio 219 b)

The contemporary European travellers have much to say about the good qualities and cruel treatment of Khusrav, but one statement which they make and which has been repeated by many modern writers also, seems to be unhistorical This is that he had only one wife—the daughter of the Khān-i-'Azam—during his life-time. But Jahāngīr records the birth of a son to him by another wife than the daughter of that nobleman Her father was Muqim, son of Mihtar Fāzil, the Rihāb-dār or 'stirrup-holder' and the boy was born on the 21st of Farwardin, XIR, ie 31st January 1616 (157, 118; Tr I. 321). Khusrav is also known have been betrothed to another lady who was the daughter of Jāni Beg Tarkhān of Thatta. (T J 8, 11 f. Tr I. 20, E D. I 252, 14)

VI. 451, 1. 19. The emperor Jahangir ordered them [the Seoras] to be banished from the country.

This order for banishing the Seorás from the Imperial dominions was issued in the 12th year of Jahängir's reign, as Mänsinha, the chief Guiu of the Khartara gachha or sect, had been guilty of disloyalty and abetment of the treasonable proceedings of Prince Khusrav, as well as of Rūi Sinha, the Rūjā of Bikāner. (T J. 217, 1 6=Tr. I 437-8) Jahāngīr says that he confiscated the property and condemned to death the Sikh Guru Arjun also for a similar reason (Text 34, 1 12=Tr I 72) The Sikh version is that Arjun was put to death because he refused to pay the heavy fine imposed upon him. (Macauliffe, The Sikh Religion, III. 84-100) VI. 452, l. 10 from foot. On the day Mahābat Khān took his leave fi om

This detail also is correct *Vide* 368-9 ante, where it is stated that Mahābat Khān presented "jewels and inlaid arms" on the 20th of Isfandārmaz of the 14th year of the reign, at a place named Sālhar, three days before the Emperor entered the boundary of Pakhli (T J Text, 289, 16 f Tr II. 124)

the camp at Pakhli, he again said etc.

VI. 455, l. 3 The early use of gunpowder in India.

This subject has been discussed by several other scholars since Sir Henry Elliot wrote about 1850 and his dissertation is now out of date. General R Maclagan, an aitiliery officer who reviewed the question very learnedly in a paper on 'Early Asiatic Fireweapons' in the JASB for 1876, (XLV. pp 30-71) arrived at the conclusion that the ancient Hindus had no knowledge of gunpowder or fire-arms of cannon, that the knowledge of gunpowder and of the most important weapons of war came from Europe to India and other Asiatic countries, that the missiles or machines described in ancient Hindu books were some sort of fire-arrows discharged from a bow, and that the various preparations for which recipes are given in the old Arabic books quoted by Reinaud and Favé (to which Elliot refers on p 459 infra), were forms of 'fire-powder' and not "gun-powder" (loc. cit. b6) Dr P C Ray also opines in his 'History

of Hindu Chemistry 'that" there is no reason to suppose that the combustible matter which the ancient fire-missiles (Agneyastra) contained, supplied motive power of the nature of gunpowder." (Ed. 1907, I. 179-180). It is true that Dr. Oppert contends, in his treatise on the "Weapons, Army Organisation and Political Maxims of the Ancient Hindus" (Ed. 1880, 43-82) that the Shataghni, and other Astras and Yantras mentioned in the Epics and the works on Rajnīti were just like our own cannon and guns, but Dr. Hopkins is sure that they were only "machines for throwing stones or other missiles ". More recently still, the question has been canvassed by two Hindu scholars, by Mr. N. G. Vaidya, in a paper on "Fire-arms in Ancient India" (J. B. B. R. A. S. 1928, pp. 26-38) and Mr. G. T. Dāté, in an Essay on the "Art of War in Ancient India" (1936). Both of them have, after discussing all the relevant passages, pronounced the opinion that the ancient Hindus "did not know the secret of making gunpowder", that the powder described in the Arthashāstra was only inflammable and not explosive, and that neither the Nalika, nor the Surmi was a gun. Mr. Vaidya goes so far as to state that these conclusions "have to be accepted, however unpalatable they may be to orthodox sentimentalists and uncritical theorists". (loc. cit. 38).

VI. 468, last line and footnote. Between every two gun-carriages, were

The word is, correctly, 'Tūra' not 'Tūbra'. Budāuni's gloss that they were "tobras or nosebags filled with earth" gives an entirely erroneous turn to the meaning, instead of "making it plain". The "Tura" was a mantlet, and was "made by binding together pieces of wood with chains and hooks, behind which the soldiers took shelter." (Irvine, A. I. M. 145-9). VI. 521, l. 29 and footnote. Suraj Mal...was overwhelmed with fear...

and ran away towards Pathankot. The local traditions and poems universally call Jagat Sing the son of Basu, and to him they ascribe

The note appears to be founded on error. These local traditions and poems relate, not to the events narrated in the Shash Fath-i-Kangra or to the rebellion of Sūraj Mal, which took place in the reign of Jahāngir, but to the much later revolt of his brother and successor, Jagat Sinha, which occurred about 24 years later in 1051 H., under Shah Jahan. Sir Henry Elliot seems to have mixed up the two revolts.

Jagat Sinha was made Rājā after Sūraj Mal's death in 1028-9 H. He served with distinction in Bangash and was appointed Faujdar of Bangash' in 1049 A. H. Soon after, he and his son Rajrup went into rebellion, which was suppressed in about six months. Both the insurgents surrendered and were consequently pardoned and their territories restored to them. The lengthy account of this campaign in the Bādshāhnāma (Text, II. 237; E. D. VII. 69) has been translated in the J. A. S. B (1875, XLIV, 194-200) by Blochmann for Mr. Beames, who has edited and translated the "Rhapsodies of Gambhīr Rāi", a contemporary rist of Jagat Sinha, in the same Journal. (Ibid. nn. 201-212)

VOL. VII. SHĀHJAHĀN TO MUHAMMAD SHĀH.

VII 4, l.5. Khāfi Khān has based his history of the first twenty years of Shāh Jahān's reign almost entirely on this work ['Abdu-l-Hamīd's Bādshāhnāma]

Dowson has copied this statement from Col Lees, but it is not quite correct Khwāfi Khān himself declares that his account of the first decade of Shāh Jahān's reign is abridged from the earlier Shāhjahān Nāma-t-Deh Sāleh, compiled by Mirzā Muhammad Amīn Qazvīni, generally known as Amīnā Munshi, and the authority of that work is expressly cited at least four times in his pages [B I Text, I. 165, 248, 346, 547] He has drawn upon 'Abdu-l-Hamīd's Chronicle only for the events of the 2nd decade. Jalāl Tabātabāi, the author of another fragmentary chronicle of the years 1041-5 H., has also followed the compilation of Amīnāi Munshi. [Rieu, III. 933] Muhammad Tāhir 'Ināyat Khān, another annalist of the same reign, explicitly informs his readers that from the fourth year to the tenth, he has preferred the guidance of the Pādshāhnāma of Mirzā Muhammad Amīn to that of 'Abdu-l-Hamīd (Rieu, III, 961 See also 75 infra).

VII. 5, l 4. Col Lees says, "This copy of the Second Part is written by Muhammad Sālih Kambū, the author of the 'Amalisālih."

Col. Lees has confounded here two persons who are now known to be distinct individuals and require to be differentiated Muhammad Sālih the Khūshnavīs (caligraphist), whose sobriquet was Kashfi and of whose elegant penmanship the manuscript referred to is a fine example, was a different person from Muhammad Sālih Kambū, the author of the 'Amali-Sālih The Khūshnavīs is known to have died in 1061 A H nine years before the composition of the History (Ricu, I. 263) The mistake is again committed at 123 infra

VII 5, l 15 He [Shahriār] now cast aside all honour and shame, and before Shāh Jahān started, repudiated his allegiance and went off in hot haste to Lāhor to advance his own interests

'Abdu-l-Ḥamīd says nothing about Shahriār " easting aside all honour and shame" or "repudiating his allegiance before Shāh Jahān started," and Dowson has misunderstood his involved and figurative verbiage What he really states is that "before the date of Jahāngīr's return journey from Kashmīr, Shahriār had lost (lit east to the winds) his eyelashes and eyebrows [j. not j.], was ashamed to show his face to his father and patron or to other people and obtained, after great importunity, permission to proceed in advance to Lāhor with a view to secure in the interval skilled medical treatment for his disease" Mu'atamad Khān also writes thus "Just at this time, Sultān Shahrīyār inopportunely fell ill The fox's disease (Dāu-s-Ṣ'alab, scald or loss of hair) robbed him of his honour, for all his hair, his whiskers, his eyebrows and his eyelashes fell off . So he returned covered with shame to Lāhor" (Iqbālnāma,

Tr. in E. D. VI. 435, Text, 291, l. 3 f.f.). Khwāfi Khān also says that Shahriār lost the hair on his beard and moustache موى ريش و بروت بياد داده (B. I. Text 388, l. 11). The 'Amal-i-Ṣāliḥ, (B. I. Text. I. 204, l. 9) roundly states that he was suffering from آنيك (syphilis) and had pustules all over his body.

VII. 6, l. 11. Shāh Jahān ascended the throne on the 18th Jumāda-s-Sāni, 1037 A. H. (6th February 1628).

The day of the Hijri month is wrongly recorded. The text has it correctly as Monday, 8th Jumādi II. 1037 A.H. corresponding to 25th Bahman Māh-i-Ilāhi. (I. i. 87, l. 2). The 'Amal-i-Ṣāliḥ gives 7th Jumādi II. at I. 225, l. 4, but 8th on I. 261, l. 16. Vide also p. 137 infra, where the Majā-līsu-s-Salāṭīn is said to give the 7th Jumādi II. Khwāfi Khān also has 7th. (I. 395, l. 9). See also my H. S. M. N. 270-1.

VII. 10, l. 16. The Khwāja reached the fort of Dholiya near the fort of Alang.

Dowson observes in the footnote that "the text here has 'Lalang', but afterwards 'Alang'. The text is right and Dowson has only made confusion by altering the name to 'Alang'. 'Alang' and 'Laling' are entirely distinct places. 'Alang' is said at p. 35 infra, to be near Gālna (or Kālna), but this also is an error for "Laling". Laling fort stands on the summit of a high hill, six miles south of Dhūliya and commands the Āgra road and the Avīr pass, leading to Mālegāon, which is about 27 miles south of Dhūliā". Dhūliā was at this time a village subordinate to Laling. (I. G. XI. 337; B. G. XII. (Khāndesh), 454). Gālna lies about 14 miles north of Mālegāon town and Laling is about 13 miles north of Gālna. (I. G. XII. 124). 'Laling' and 'Gālna' are both shown on the Map in Bayley's Gujarāt.

'Alang' and 'Kulang' are situated on the Ahmadnagar frontier of Igatpuri, about ten miles south-east of Igatpuri town. They are twin hill forts, about two miles distant from each other and lie at the southern-most point of Nāsik district. (B.G. Nāsik, XVI. p. 136). Alang is not near Gālna. VII. 11, l. 13. Those who escaped fled from Daulatābād to Sindghar near Jālnāpur in their native country.

الله Sindkher, as in Kh. Kh. (I. 428). It is in Buldāna district, Berār, about 25 miles north-east of Jālna. Constable, 31 D b. Lat. 19°-57′ N., Long. 76°-10′ E. In the M. U. (I. 523), it is said to be in Sarkār Mehkar, Sūba Berār, thirty Kos from Aurangābād, and six or seven Kos south of Deulgāon Rājā. The latter town also lies in Buldānā district, and is shown in Constable, 31 D a.

VII. 12, l. 17. When he reached the village of Rāmbhūri on the Bāngangā river.

This must be 'Vāmbori' or 'Wambooree' of Thornton, 14 miles north of Ahmadnagar. It is now a station on the G. I. P. Railway. It lies on a small river, which is, I understand, called 'Bāngangā' by the residents. There is a place called Rāhuri, 21 miles north-west of Ahmadnagar, but Vāmbori seems to be the village intended.

VII. 12, l. 3 from foot. Khān Jahān was at Rājauri, twenty-four Kos from Machhligāon, employed in dividing the snoil.

According to the M. U., the author of which displays a personal acquaintance with the geography of the Dekkan, this Rajauri was in Bhir district (I 416, l. 1 f. f), and lay only four Kos from the town of Bhir (Ib. I 725, l. 7) Constable, 31 C b.

'Machhligaon' must be an error for Alphalgaon or Mazalgaon which lies about thirty miles north-east of Bhir. (I. G. XVII. 244). Constable, 31 D b.

VII. 14, l. 4. Bihar Singh Bundela.

The variant Jr. Pahār Singh [Pahāḍ Sinha] occurs more frequently and is the correct form (Bād. Nām. Text, I. 197, 205, 248, 325, 'AŞ, I 386, I. 2). Pahār Sinha was one of the sons of Vīra Sinha Deva, the murderer of Abu-l-Fazl.

VII. 14, l. 15. A ball struck Bahadur, Khan, and he was unable to continue his flight.

The ball did not strike Bahādur Khān Rohela, who was the son of Daryā Khān and one of the Imperial Commanders, but Bahādur, then ephew of the rebel Khān Jahān Lody (B N I. 1. 325, 1 2). The courtly historian is careful never to style this Bahādur 'Khān' and some opprobrious epithet like من 'renegade' is almost always affixed to his name (Text, I 1. 324, 1 3 f.f., 325, 1. 3). His father also is said to have fled, but this is due to بن having been wrongly read for ابن المقادة المقاد

VII. 15, l. 9 from foot Samaje son of Sahuje

Recte, Sambhāji or Shambhuji, son of Shāhji. He was the elder brother of Shivāji and was killed in an attack on Kanakgiri in 1653 A. C (Grant Duff, H M 66) 'Bīzāpur' which lay about 25 miles west of Aurangābād is shown as 'Vaijapur' in the I. G. Atlas (40 A 2), but as 'Baizapur' on Constable's, Pl. 31 C b

VII 16, l 4 Went to Ir-Kahtala, half a Ros from Daulatābād.

This 'Ir' or 'Er' appears to be intrusive and has been probably transferred by a slip, from 'Erandol,' which has been decapitated and written as 'Andol' five lines lower down The copyist has lobbed Peter to pay Paul. 'Erandol' and 'Dhārangāon' are near each other and are both in East Khāndesh. Dhārangāon is now in Erandol taluka, thirty-five miles north-east of Dhūliyā (Bom Gaz XII (Khāndesh), 439). Both the places are shown in Constable, 31 C a

VII. 16, l 20. Mukarrab Khān and Bahlol who were at Dhārūr and Amba-jogāi.

Ambā Jogāi is in Bhīr district, Haidarābād State." The portion of

Ambājogāi, which lies south-west of the Jivanti river is now called Mominābād. (I. G., V. 275). Ambā and Jogāi are two distinct villages in proximity to each other. The names are derived from two synonymous designations of one and the same goddess, Pārvati or Durgā. Dhārūr also lies in Bhīr. Constable, 31 D b. 'Ojhar' may be Thornton's 'Wozur,' which lies about 10 miles north-east of Nāsik. Lat. 20°-4′ N., Long. 73°-54′ E. But Dowson locates it 20 miles south of Sangamner. (VIII, p. xli). 'Mānikdūdh' (l. 23) must be 'Mānik-punj' near Nāndgāon in Nāsik district, q. v. my note on III. 257, l. 9 f. f. It is shown on Bayley's Map. Dāmangāon (l. 9 f. f.) is Dhāmangāon in Bhīr, Constable, 31 C b.

VII. 17, l. 6. ['Azam Khān] proceeded from [Bhīr] to Partūr on the bank of the river Dūdna.

Pārtūr is now in Parbaini district, Ḥaidarābād State. It lies on the right bank of the Dūdna. Constable, 31 Db.

VII. 18, l. 2 from foot. ['Abdulla Khān] encamped at Lonihara.

This is 'Lūnhera', 'Nūnhera' or 'Lūnera'. It is mentioned in the itineraries of two European travellers. Finch (E. T. I. 142) and Jourdain (Journal, 149) who passed through it put it four Kos north of Mandū and about ten from Akbarpur. This Akbarpur, where the Narmadā was crossed by ferry, is 25 miles north-west of Gogāon, $12\frac{1}{2}$ west from Mandlesar (I. A. exii) and 43 south-west of Indore. Lat. 22° -8' N., Long. 75° -33' E. (Th).

Khiljipur, which is mentioned on 1.14, p. 19, is now the chief town of a feudatory state and is shown in Constable, 27 C c. The correct name is Khīchīpur, the town of the Khichi Chauhāns. It has nothing to do with the Khiljis or Khaljis. Lat. 24°-2′ N., Long. 76°-34′ E.

VII. 23, 1. 12. And the troops drove zigzags upto the end of the ditch.

The phrase which is rendered by 'Zigzags' is Lit. 'narrow passages or streets of safety'. (Text, II. 358, l. 18). The Lucknow editor of the Akbarnāma states that 's' is synonymous with Sābāt. (Text, II. 245, note). Steingass defines 'Sābāt' as 'a covered passage connecting two houses,' but it is used by the Timuride historians for "the covered ways or galleries of approach which were erected for the conduct of sieges'. There is an elaborate description of these 'Sābāt' in the T. A.'s account of the siege of Chītor (282 l. 13=E. D. V. 326) which F. (I. 257, l. 6 f. f.=Briggs' Tr. II. 230) has copied almost word for word. See also Budāuni, II. 103; Tr. 106 and note) and Irvine, A. I. M. 273.

VII. 23, l. 4 from foot. The eldest son of Ibrāhim 'Adil Khān by the daughter of Kutbu-l-Mulk.

The word in the original is • (I. i. 160, l. 6), which means 'sister' not 'daughter'.

VII. 25, l. 14. Taxes amounting to nearly seventy lacs of rupees were remitted by the revenue officers—a sum amounting to nearly eighty Krors of dams, and amounting to one-eleventh part of the whole revenue.

This is not the meaning. What 'Abdu-l-Hamid really says is that the

total Jam'a [Land Revenue] of the Empire was 880 Krors of Dams, te about 22 Krors of Rupees. Lands yielding about one-eleventh of this amount, i.e 80 Krors of Dams or Two Krors of Rupees were Khalisa, i e managed directly by the Imperial officers appointed by the Divan-Vizarat. The remissions made in consideration of the famine, out of this Khālisa revenue of two Krors, amounted to seventy laks of rupees or about 285 per cent of the total As the rest of the As the rest of the had been assigned to Mansabdars as تتحواه, those lands were managed by them and as the remissions granted by them were not known to him, he leaves it to his readers to قرب هيناد لك روبيه در هشاد كرور imagine what they must have amounted to (Text, I 1.364, ll 3-7) دام عال حالصة والاكه بازدهم ممالك محروسه است تحقيف دادمد VII. 25, l. 10 from foot Sipahdar Khan, after obtaining possession of the fort of Taltam . . laid siege to Sttunda

'Sıtunda'ıs 50 miles north-east of Aurangabad and is in Lat 20°-32' N., Long 75°-20' E Constable, 31 C a 'Taltam' cannot be satisfactorily identified The diacritical points of the letters seem to have been jumbled together It is mentioned along with Situnda in the AN also (III. 756, Tr III. 1131) in the chronicle of the 43rd year and said to be one of the choice foits of Berär (Ibid, 762=Tr. 1139) This description seems to apply to o'b Basim, but the latter is mentioned as 'Basim' elsewhere VII 26, l 8 from foot. Rockets, mortars, stones and grenades

'Rockets, musket ا (I 1 376, l, f.f)، "Rockets, musket مشكهاى اروت bullets, hand-grenades, stones, and leather-bags filled with gunpowder" The مشكراى الروت must have been sacks or bags like those used by Bhistis, filled with gunpowder with a fuse attached to them

VII 29, l. 6 Encamped near the river Nahnūrā.

י איפנו is an error for 'איפנו 'Bhunra', 'Bhimra', t e the 'Bhima' See note 54 infra. 'Nauraspur' was a village near Bijāpur, founded by Ibrāhim 'Adıl Shah who had assumed the pen-name 'Nauras'.

Mulla Muhammad is styled 'Lahori' (1 22), but his correct 'Nisba' was Lärn, as Khwafi Khan calls him (I. 464, l. 5) He was a Navayat and came like the renowned 'Abdur Razzāg Lāri from Lār in Persia and not from Lahor. He is mentioned as Lari by Jahangir also. (T. J. 385, last line, Tr II, 296). The 'A S also reads 'Lari' (I. 470, l. 12)

VII 32, l 18 And he resolved to put an end to them if ever he ascended the throne, that the coinage might always bear the state of the glorious dynasty and the pulpit might be graced with its Khutba

The clauses in this sentence do not hold together and the inconsequence is manifest. The correct rendering is this "And with the most pious intentions, he took a vow that when the faces of coins should be exalted by the stamp of his own name and the dignity of the pulpit enhanced by the recitation of his own titles in the Khutba, [t. e when he became, at some time in the future, the ruler of the Kingdoml, he would

و بنیت نبك طویت . . . ". extirpate the mischief created by these misbelievers." . . . تصیم یافته که هرگاه روی د نانیر بسکه این دولت روز افزون بر افراخته گرد د و پایهٔ منبر بخطبهٔ این سلطنت والا مرتبت بر افراخته خاربن فساد این ضلالت کیشان از این دیار بخطبهٔ این سلطنت والا مرتبت بر افراخته خاربن فساد این ضلالت کیشان از این دیار بخطبهٔ این سلطنت والا مرتبت بر افراخته خاربن فساد این ضلالت کیشان از این دیار بخطبهٔ این سلطنت والا مرتبت بر افراخته خاربن فساد این ضلالت کیشان از این دیار

VII. 32, last line. Makhsūsābād.

This is the old name of Murshidābād. Maqsūdābād is another form which occurs in Tieffenthaler, who says that it was founded by Akbar. Tavernier speaks of it as 'Madeṣou Bazār'. (Travels, I. 132). Blochmann says that the name was derived from Makhṣūṣ Khān who served in Bengāl and Bihār under Akbar and whose brother S'aīd Khān was at one time Governor of Bengal, q. v. A. N. III. 42—Tr. 62 (J. A. S. B. 1873 (LXII), p. 218 note; Āīn, Tr. I. 388. See also Riyāzu-s-Salāṭīn, Tr. 28). Maqṣūd was the son of Makhṣūṣ Khān. Murshidābād gets its name from Murshid Quli Khān, who was governor of Bengal and moved the seat of government to it in 1704 A.C.

VII. 33, l. 10. When the flotilla arrived at Mohāna, which is a dahna of the Hugli.

Dowson questions the correctness of the reading 'dahna' and asks if it is not the Bengāli 'dahra' which means 'lake'. But دهنه is quite right and means in Persian 'mouth, opening, entrance'. 'Mohāna' was, probably, the name by which one of the mouths of the Hugli was known and it is derived from the vernacular word Munh, Sans. Mukh, mouth. Thornton says that "Hidjelee was situated on the right or western shore of one of the entrances to the Hoogly, called the Inner Channel, and at the mouth of a small river falling into it." According to the I. G. also, Hijli was an old village in Midnapore district at the mouth of the Rasulpur river, which has been now washed away. (XIII. 116). Hijili was a place of importance at this time, as cargoes were landed here for transport up the Hūgli. It lay at some distance south-west of Hugli town and about 48 miles southwest of Calcutta. (Foster's note to E. T. I. 25). دهنه کوهستان 'Entrance to the hilly region 'and "mouth of a mountain pass" occur in the M. 'Ā. (44, l. 12 and 46, l. 3). As regards 'Muhna', Alberúni says that the mouths of the Indus were known in his day as the 'Small Munha' and the 'Great Munha.' (Indica, Tr. Sachau, I. 208 and Note at Ibid. II. 320). The 'A. S. says that "the mouth (دهان) of the Khor of Hūgli is known as Mohāna" (I. 498, l. 3) and speaks of سد موهانه 'blocking it up.' (I, 502. l. 14). VII. 34, l. 3 from foot. Out of the sixty-four large dingas, fifty seven ghrābs and two hundred jāliyas, one ghrāb and tico jāliyas escaped.

'Dinga,' is the Bengali 'Dingi' or 'Dongi', which is from the Sanskrit, 'Drona', a trough. The word seems to be used here, not in the usual sense of a small skiff or boat, but for a large vessel employed in war. 'Ghrāb' is the parent of the Anglo-Indian 'Grab', a" kind of vessel, which is frequently mentioned in the sea and river fights in India from the arrival of the

Portuguese to the end of the 18th Century." (H. J. 391) It is described as "a square-rigged Arab vessel with two or three masts and a sharp or projecting prow, but no bowsprit". Morier explains this absence of a bowsprit by sayingt hat the Arabs know how "to extend the timbers of a ship until they connect themselves into a prow, but they have not yet attained the art of forming timber fit to construct bows." (Journey to Persia, Ed 1812, p. 8) Both names are derived from the Arab Ghurāb, a raven Compare the English 'Corvette,' from the Latin Corvus, a crow. Like the Corvette, the Ghrāb also was used in naval warfare and in Mīr Jumla's invasion of Āssām, each ghrāb carried fourteen guns and fifty or sixty fighting men and was towed by four Kosahs or lighter vessels propelled by oars. (Gait, History of Assam, 128) The 'Jāliya'is another form of our 'Galley', the hard 'g' having been replaced by the soft one in Arabic (Yule, H. J 362)

VII 35, l 6 from foot Commandant of the fort of Alang, which is near to Galna

Here also the right reading and the place meant is Laling See note on p. 10, l 16, ante The text reads (I i. 442, l. 13). At 462 infra, 'Galna' is said to be seventy Kos from Aurangābād, which is correct

VII. 36, l 6 Bhāgirat Bhīl, ... relying on the strength of his fort of Khātākhīri, had refused obedience

Dowson says that this is 'Kuntherkhera' on the Kali Sind, about thirty miles north of Ujjain, which is shown on Malcolm's Map of Central India But the place meant seems to be 'Khātākheri', or 'Khānākhedi' which is mentioned in the 'Alamgirnama also (474, 615) It is stated there that when Chakrasen the Bhil Zamindar of Khātākheri, rebelled in 1660 AC, Bhagwant Singh Hādā was sent against him and captured his stronghold. Chakrasen's contumacy is said to have made it necessary for another punitive expedition to be despatched against him in 1677 also. (Sarkar, H. A., III. 24-25) See also Hind Rajasthan, 729 The place is now in the State of Kotah and lies about 15 miles north of Rajgarh (Biaora), q v. Constable, 27 C d. The Zemindar of 'Kanur', who is said to have interceded for Chakrasen (l. 12) was, most probably, the chief of Gannur or Gannurgarh, which lies thirteen miles north-west of Hoshangabad and 30 south east of Bhopāl (Th). There is a 'Khātkhari' in Rewā or Bāghelkhand also, about 83 miles south-west of Allahabad (Constable, 28 B c), but it cannot be the place meant, as it is not in Malwa.

VII 37, l. 11 from foot When Khan Khanan who was at Zafarnagar, was informed of these proceedings

Zafarnagar is now called 'Jafarābād' [Zafarābād] and is in Aurangābād district, Ḥaidarābād State Its old name was Tamarni Sundar, Rājā Bikramājit, cantoned here during the rainy season of 1026 H. and gave the cantonment the name of 'Zafarnagar.' See my article in the Num Suppl No XXXIV to the J. A. S B (1920), pp. 240-249, where the evidence for the identification is set out, Jafarābād is marked in Constable, 31 D a

VII. 47, l. 7. [Jajhār Singh] attacked Bīm Narāyan, Zamīndār of Garha.

Recte, Pem c. Nārāyan, i. e. Prem Nārāyan. He belonged to the old Gond dynasty of Gadha-Māndla. (Sleeman, History of the Garha Mandla Rājās in J. A. S. B. 1837, VI. p. 631 sq). 'Bhānder' (last line), is in Jhānsi district, about 25 miles north-east of Jhānsi town. Constable, 27 D c. VII. 52, l. 10. Chamārgonda and Ashti near to Ahmadnagar.

There are several places called Āshti. This must be the one in Naldrug district, Ḥaidarābād State. It lies a few miles south-east of Aḥmadnagar and north-east of Chamārgonda in Lat. 18°-50′ N., Long. 75°-15′ E. Chamārgonda is better known as Shrīgonda. Constable, 31 Cb. It has been mentioned at 56 infra and was the native place of Shāhu, i. e. Shāhji, the father of Shivāji. (M. U. II. 25, 1. 2 f. f.).

VII, 53, l. 5 from foot. Surrender of the hill forts of Anjarãi, Kānjna and Mānjna, Rola, Jola, Ahūnat, Kol, Būsrā, Achlāgar Conquest of the fort of the Rājā of Bīr Surrender of Dharab.

Many of these toponyms are spelt incorrectly and all of them are more or less obscure. 'Anjarāi' is, correctly, 'Indirai' or 'Indragīri'. which lies about four miles north-west of Chandor, on the Roura Pass. It is 4526 feet above sea-level. (B. G. XVI. (Nāsik), 445). 'Kanchan-Manchan' or 'Kachna' is about 2½ miles west of another fort in the same district, named Koledhair and about ten miles west of Chandor. (Ibid, 445), 'Rola-Jola' is 'Ravalya-Javalya', another of the hill forts on the Chandor Range. There are two peaks to the east of Markinda, which jut out, 'Rāvalya' on the west and 'Jāvalya' on the east of a hill, fifteen miles north-east of Dindori. (Ibid. 642 and 411). 'Ahunat', Recte. 'Ahvant' or 'Ahivant'- 'Serpent-fort'-is also on the Chandor range, fifteen milesn orth of Dindori, (Ib. 415). 'Kol' is Koledhair, about seven miles north-west of Chandor and four miles north-west of Rajdhair. (Ib. 449). 'Busra' must be 'Bhuragadh', about two miles north-west of Ramsej. (Ib. 641). 'Achlagar' is the westernmost fort in the Chandor range and lies about twenty miles north of Dindori. (Ib. 414). The 'fort of the Raji of Bîr'is an error for "the fort of 'Rājdhair." Khwāfi Khān calls it 'Rājdhir'. (I. 524, l. 1). It lies about fourteen miles south-west of Chalisgaon town (B. G., Khandesh, XII, 467). It is called 'Dhir'or Dehera' also, (Ib. 439), and is spoken of in the M. U as 'Rajdhar' (I. 209). Lastly, 'Dharab' is 'Dhodap', fifteen miles north-west of Chandor on the highest hill in the Chandor range. (B. G. (Nasik), XVI. 432).

VII. 55. l. 12. Capture of Sarādhun, Dhārāsiyūn, Kānti six Kos from Sholāpur and the town of Deogāon.

'Dhārāsiyun' or 'Dharaseo', which is 50 miles north-east of Sholāpur, is now known as Osmānābād and is in Naldrug district, Ḥaidarābād State. (I. G. XIX, 276). Constable, 31 Db. 'Sarādhūn' (l.11) is Thornton's 'Sheradone,' 172 miles W. N. W. of Ḥaidarābād and 60 north of

Sholapur Lat 180-31'N, Long. 76°-13' E. Constable, 31 D b 'Kantı'ıs 'Katı,' which lies about twenty miles north-east of Sholapur and is also in Hardarābād State Constable, 31 C c

VII 56, l. 7. Sahu was about to proceed by way of Parganu to Parenda.

This must be 'Pargaon' in Ahmadnagar district, 4 miles north of Chamargonda, which is mentioned on line 12.

Māhūli (1 6) is in North Konkan, about 50 miles north-east of Bombay (B G XV 219)

VII 57. l 8 Capture of the forts of Anki and Tanki, etc.

'Ankai-Tankai' are two forts in Nasik district, about six miles north of Yeola and near the Manmad and Ahmadnagar road They stand about 3200 feet above the sea and are now included in the Chandor taluka of Nasık district (B G XVI 419, I G XVII. 199) Constable, 31 C a

'Alka Palka' (l. 9) are two unfortified hills to the west of Ankai Tankai and divided from them by the road and Railway They are so close to Ankai Tankai, that, according to one local authority, they are said to be identical with them (B.G 420 note)

VII 59. 1 4. When he reached the Khorandi, he was detained on its banks

An error for the Ghod-nadi, the name of a river as well as of a town on its banks, which is in the Sirūr taluka of Poona district (I G XII 232) Constable, 31 C b. 'Gondhana' (19) must be 'Kondna', the old name of 'Sinhagadh', about 12 miles from Poona Constable, 31 B b 'Nūrand' is a mistake for the 'Niranadi' Tringalwadi (1 6 ff) lies 12 miles south of Nāsik (B G XVI. 439, 660)

VII 60, l 12 from foot. Forts of Haris, Judhan, Jund and Harsira were delivered over to Khan Zaman

Dowson says 'Haris' is Harishchandragarh, which is 56 miles north of Poona, and not far from Shivner, the hill fort of the town of Juner. (ED VIII. Index, p xxxix) But it must be Harish, four miles south of Trimbak, which is mentioned just before it (B G Nasik, XVI 439) 'Jund' must be Chawand Judhan is, really, Jalodhan, sixteen miles from Juner

VII 60, l 7 from foot. Khān Daurān takes possession of the forts of Kataljahr and Ashta and storms the fort of Nagpur

Kelchahr' in the 'Amal-1-Sālih (II. 218,1 8) and M U (I 755). 'Kataljahr'is a miswriting of 'Kheljhar' or 'Keljhar', [Kelzur in Thornton], now in Wardha district It lies 26 miles south-west of Nagpur. Constable, 32 A a Ashta is in Seoni district, Central Provinces Constable, 32 Aa Kheljhar and Ashta are both mentioned in the Ain (Tr II 233) One of them was a Mahal in Sarkar Paunar, and the other in Sarkar Kherla of the same Suba, viz Berar Sir J. Sarkar reads the name as 'Katanjhiri' or 'Katanjhar,' but does not say where it is to be found (H A, I 49, V 404) VII 62, l. 14 He marched by the difficult route of Karcha-barh.

in the 'Amal-i-Sālih (II. 254, l. 9). This 'Karcha-barh' is an imaginary toponym like 'Kant-barāhi' and 'Nākhachnuhgarhi', q.v. my Notes on III. 261, l. 8. and 318, l. 1. What 'Abdul Ḥamīd really says is از راه کرچه ره نوردی درآمد (I. ii. 282, 1.5). "He entered the country by marching along the route through Karcha." In a subsequent passage, he says that there are two passes into Little Tibet, namely, 'Karch' and 'Lar'. (I. ii. 286-7). The pass is called & Karaj'or 'Karaj'in the corresponding passage of the M. U. also. (II. 758, l. 3). יפעניגני means 'to travel, walk, wander' and د نوردی signifies "travelling, marching along or traversing a road." 'Karcha' is the 'Kertse' of Constable, 23 B c. Mirzā Haidar Dughlat tells us that after invading Kashmir in 939 A.H., he returned by the same route by which he had entered it, namely, through Lar. When he reached the frontiers of [Little] Tibet (Balti), the inhabitants of 'Karsa,' a valley exceedingly dark, narrow and steep, offered resistance and had to be attacked and killed. (Tar. Rash. Tr. 432). Mr. Ney Elias says that this is Kertse or Kartse, a village between 'Kargil' and 'Suru.' But he thinks it also possible that 'Kalsa' or 'Kalsi', another village on the Indus on the main road to Ladak andnear the foot of an extraordinarily deep and narrow gorge, may be meant. (Ibid, note). Lar is another name of the Sind river of Kashmir, which flows from the Zoji Lā Pass towards the Jailam. The 'Pass of Lir' must be the Zoji La Pass (Ibid, 423 Note). 'Shakar' (l. 26) is 'Shigar,' which lies a few miles north of Skardo or Iskardo in Baltistān. Constable, 23 A c. Mirzā Ḥaidar says that it was the capital of all Balti. (Loc. cit. 422).

VII. 65, l. 1. Rebellion in Kūch-Hajū.

Kūch-Hājo corresponded to the modern districts of Goālpāra and Lower Āssām. The second half of the name is derived from Hājo, a village in Kāmarūpa district, on the north bank of the Brahmaputra, fifteen miles from Gauhāti. Sosung (l. 15) lies east of the Brahmaputra, between the Karibari and Garo hills. (Blochmann, J.A.S.B. XLI. (1872) 50, 53, note). 'Kohhatah' (l. 5 f. f.) is an error for 'Gauhāti.' 'Utarkol' is the land which lies on the north or left bank of the Brahmaputra. It stretches from Gauhāti to the home of the Mishmi and Mīri tribes. 'Kol' is the Sanskrit Kūla, the bank of a river. (J.B.O.R.S. Vol. I. 1915, p. 182).

VII. 66, l. 9 from foot. Submission of Mānik Rāi, the Mag Rājā of Chātgām.

The name is really *Matak* Rāi. He "held Chātgām (Chittāgong) on behalf of the Rājā of Ārākān, but having quarrelled with his master, sought the protection of the Mughals and made over the district to the Sūbadār of Bengal. (I. G. X. 308).

VII. 67, l. 9. Sangi Bamkhal, the holder of Great Tibet had seized upon Burag in Little Tibet.

'Bamkhal' is an error by transposition of the nuqtas, for 'Namgyal', which means 'King' and is the family title of all the rulers of Great Tibet or Ladakh. Cunningham calls him 'Singgé Namgyal' and

cording to the local chronicle, he ruled from about 1620 to 1670 A.C. (Ladāk, 318 note, and 324). The Jesuit Hippolito Desideri, who passed through Tibet in 1714 A.C., states that the name of the then ruler or Ghiampo [recte, Gyālpo] was Nyima Nanjal (Recte, Nyima Namgyal), son of Dilik Nanjal [Delak Namgyal]. (Raveity, N. A. 294 Note). The rulers of Sikkim also are still called 'Namgyal' and that word always constitutes an integral part of their title (J. A. S. B. 1904, pp. 85, 88)

'Būrag' or 'Pūrik' was one of the chief towns of Balti. (Tār Rash. Tr. 15, 410, 442).

VII. 69, l. 5. Surrender of Tärägarh.

The fort of Tārāgarh lies on the bank of the Chakki river, 110 miles N. E. by E of Lāhor (Th) and about 15 miles south-west of Chamba

Palāmau († 10) is now in Lohardāga, Chutia Nāgpur The town is about 145 miles south-west of Patna Constable, 28 D d

VII 76, l 6. Nazar Muhammad Khān . . . who had stood fast at Nilchtrāgh.

Recte, 'Pul-1 Chirāgh', "The Bridge of the Lamp", which lies below Garzawān, west of Balkh It stands at the mouth of a triple-bridged defile. The name is also written Bil-chirāgh, as 'Bil' signifies 'Pass' or 'Gate' But 'Nīlchirāgh' is certainly wrong The 'Chirāgh' or Lamp is placed at the shrine of a Saint, just at the entrance of the defile (Grodekoff, Ride to Herat, Tr Marvin, 103 apud BN Tr. 69 note) Sir Thomas Holdich says that 'Pul-Chirāgh or Bilchirāgh' is about 25 miles south-east of Maimana, which lies half way between Balkh and Herāt (G.I 251) Maimana is in Lat. 36° N, Long. 65° E 'Belchirāg' is shown in Constable, 22 A c

VII 79, l 7 [Rustam Khān wrote that he was] proceeding towards
Kābul [from Marmana] by way of San chārik

It is the 'Sang charak' of modern maps and is shown in Constable, 22 B b, as lying south-south-west of Balkh. See also Holdich, G. I. 259 Abu-l Fazl states that it was also known as the 'Chūl-i-Zardak', te the Brown (or Yellowish) Desert (A N II 124=Ir 191). 'Andkhod' is Constable's Andkhūi, 22 A b It lies in Lat 37° N., Long 65° E.

VII 80, l. 9 from foot Nazar Bahādur Khān, Kheshyi Ratan son of Mahesh Dās, and others charged them.

'Kheshji Ratan' is an impossible name for a Hindu The comma should be placed after Kheshgi (خویشکی), which was the name of the Afghān tribe to which Nazr Bahādur Khān belonged (M. U. III 777, 1 14) The Kheshgis were famous for their piety and integrity and were settled round about Lāhor and Kāsūr (*Ibid*, III 818, 1 6)

Ghori (1 8 f f) is the Kala [Qil'a] Ghori of Constable, 22 C c It is in Lat. 36°-0′ N., Long 68°-30′ E

VII 81, l. 13 from foot After him should come the royal treasure, Karkhana [Wardrobe] and artillery.

The 'Karkhanas' did not comprise the 'wardrobe' only It was a general term for the numeious State establishments, factories and work-

shops which accompanied armies on the march and the Emperor himself on his progresses. There is a lengthy account of the most important of them in the First and Second Books of the \overline{Ain} . Shams-i-Siraj also mentions the thirty-six Karkhanas of Firaz Tughlaq. (Fext. 337; E. D. III. 356). See also the T. A. (318, ll. 8-9; E.D. V. 374).

VII. 89, l. 11. It was commanded that the army should hasten to Kābul, via Bangash-i-Bālā and Bangash-i-Fāyīn, as they were the shortest routes.

Bangash-i-Bālā or Upper Bangash, is what is no wealled Kurram Bangash-i-Pāyīn, Lower Bangash, is Kohāt. (I. G. XVI. 49). See also 95 infra, where Kohāt is mentioned in this connection.

'Sāz Khān Baligh' is an impossible name. The 'Amal-i-Sālih calls him 'Sārū Khān [Uzbek]' (III. 73, l. 12). and so also Kh. Kh. (I. 655, l. 1). VII. 90, l. 10. Top of the hill of Chihal-Zinah (forty steps), whence guns could be fired.

"The Koh-i-Chihal-zīnah is a rocky spur.... which overlooks Qandahār from the east.... It is so called because Bābar Bādshāh had a platform made and a seat placed there for his own recreation and forty steps had to be cut into the rock to reach it." (Raverty. N. A. 25 Note). It is about a mile from the citadel and commands both the citadel and the city.

VII. 98, l. 2 from foot. He [Shāh Jahān] quitted Kashmīr.....and set out for the capital by way of Shāhābād.

This Shīhābād is the place so called which is situated in a narrow valley bounded on the south-west by the Panjāl or Pass of Baīnhāl. Lat. 33°-32′ N., Long. 75°-16′ E. (Th.). Constable, 25 A a.

VII. 103, l. 14 from foot. When the world-subduing banners were planted at Khalilpur.

This town is in Gurgãon district, Punjab. Constable, 27 Ca. It is now a Railway Station, about 25 miles south of Gurgãon and 7 north of Rewāri.

VII. 105, l. 3 from foot. [The Rājā of Sirmur was invested] with the title of Rājā Sabhāk Prakās.

Recte, Sobhāg [Subhāgya] 'Prakāsh'. 'Prakāsh' forms even now a part of the style and titles of the Rājās of Sirmūr. Several letters addressed by Rājā Budh Prakāsh of Sirmūr to Shāh Jahān's favourite daughter, Jahānārā Begam and her replies have been published by Mr. H. A. Rose in the J. A. S. B. 1911, pp. 449-458.

VII. 106, l. 3. From the beginning of the month of Isfandiar.

This spelling of the name of the 12th month of the Yazdajardi, as well as the Ilāhi year, is found in many competent Musalmān writers, but it is not quite correct. 'Isfandiār,' which was the name of the son of King Gushtāsp [or Vishtāspa] and 'Isfandārmad,' or 'Isfandāmuz,' the designation of the month, are entirely distinct words, which have no real acceptation with each other. "Isfandiār" is the Modern Persian

Avestaic Spento-dāta, meaning 'Given by [Spenta-Mainyush] the Good Spirit or Angel' 'Isfandārmad' is Noo-Persian for the Avestaic Spenta-Armāiti, the 'Good Ārmaiti,' [lit. 'the Good Humility'], one of the seven Ameshāspentas. The error is repeated on 115 and 241 post

Mr. Beveridge always transliterates the name of the sixth Ilāhi month as Shahrvār (A N Tr III 1159, 1256), and Mr. Vincent Smith has followed him But the correct form must be 'Shahrīvar', as it stands for the Avestaic 'Khshthravarrya' (Pahlavi, 'Shatrovar'), and the Zoroastrians in India as well as Persia pronounce it always in that way.

VII 106, l 21 He [Khalīlu-lla] laid the foundations of a field-work close to Kilāghar in the Dun, lying outside of Srīnagar

'Kīlāghar' is 'Kaulāgarh' near Dehra. Sahījpur (l. 107, l 8) and Basantpur (107, l 4) were parganas in the Eastern Dūn belonging to Garhwāl. (E T. Atkinson, Gazetteer of the Himālayan Districts of the N W. P. II 563 Note)

VII 117, l 23 [Mir Jumla] presented 3000 Ibrāhimis as Nisār

The *Ibrāhīmi* was a gold com of low matt, worth between two and three rupees Abu l-Fazl says that it was equal to 40 *Kabīrs* and 14 *Kabīrs* were valued at one Akbari rupee The *Ibi āhīmi* was thus rated at about $2\frac{7}{8}$ rupees

VII. 119, l. 3 from foot 'Adıl Khān had bid adıeu to existence.... and his servants had constituted Majhūl Illāhi his successor, who professed to be his offspring

"Majhūl Illahı" [عرول علي] is not a proper name or the title of 'Adıl Khān's successor, but a phrase signifying 'a person of whom nothing is known, an utterly obscure individual, a nobody, a pretender 'This obscure individual was 'Ali 'Adıl Shāh II Fryer, Manucci, Tavernier (I. 183) and Bernier (Ed Constable, 197) speak of him as an adopted child. The Basātīn-i-Salātīn, a provincial history of Bījāpūr, represents him as the son of Muhammad 'Ādıl Shāh by a lady in the harem and adopted as her own by the favourite Sultānā, who was the sister of the king of Golkonda

and known as the 'Badi Sāḥeba'. 'Ali was about 18 years old at this time, in 1656 A. C. In the C. H. I. (IV. 209), Sir Richard Burn states that "some people doubted 'Ali 'Ādil Shāh's right to succeed, though the matter was uncertain," while Sir Wolseley Haig, on another page of the same volume (IV. 271), stigmatises the allegation of his spurious birth as a 'slander' invented by the Mughals, 'for which there is not a scrap of evidence.' The fact that several contemporary European travellers also speak of him only as 'an adopted child', may indicate that there were some reasons for doubting his parentage. See also Sarkār (H. A., I. 285-6).

VII. 122, l. 13. The Shāh of Persia had resolved upon this evil enterprize in that infatuation, which arises from youth and inexperience.

Shāh 'Abbās II had come to the throne on the 20th Safar of 1052 H. 1642 A. C. at the age of ten and was at this time (1059 H.) only seventeen years old. He died in 1077 H. (Lane Poole, Muhammadan Dynasties, 259; Oliver in J. A. S. B. (LVI), 1887, p. 48 note).

VII. 123, l. 2. 'Amal-i-Sālih.

As so little is known about Muḥammad Ṣāliḥ Kambu, it may be worth while to point out a fact which has been overlooked, not only by Dowson, but by Rieu, Dr. Yazdāni his Editor and others. The 'Maāṣir-i-'Ālamgīri' states that in consequence of the death of the Ṣadr, Sharīf Khān, on 12th Shawwāl 1093 H., Shaikh Makhdūm Munshi was appointed Chief Ṣadr and Muḥammad Sāliḥ Kambu, his peshdast or assistant. (222, l. 16).

Another point which is not undeserving of notice is that the title of this work is allusive and also amphibological. 'Amal-i-Ṣāliḥ may mean "The History of a Beneficent Reign, Regime or Exercise of Authority." But it may be also understood as the "Work, Performance or Book composed by Ṣāliḥ."

Similar allusions in the titles of books to the names of the authors or of their patrons are found in the Habību-s-Sīyar (E. D. IV. 154), Rauzatu-t-Tahirīn (VI. 195), Alısanu-t-tavārīkh (Ibid, 201), Subli-i-Sādiq (VI. 453), Burhānu-l-Futūlį (VIII. 26) and many others.

VII. 126, l. 8. This strong fortress [Bidar] was thus taken in twenty-seven days.

There is a difficulty here. This author says that Aurangzeb was joined by Mu'azzam Khān on 12th Rab'i II., reached Chāndor fourteen days later, sat down before Bīdar the very next day, i.e. on 27th Rab'i II. that the general assault was delivered on the 23rd of Jumādi II (125 ante) and that the fortress capitulated on the day following. The period must be, not twenty-seven days, but one month and twenty-seven days, if 27th Jumādī II. is correct. If 'twenty-seven days' is right, Jumādī II. must be wrong and an error for Jumādī I. Sir Jadunāth Sarkār states that Aurangzeb left Aurangābād on 18th January 1657 and reached Bīdar after a march of one lunar month and fourteen days on 28th February, as he was encumbered with siege-guns and heavy artillery. He points out

that Muhammad Salih has left out the month, so as to make it only fourteen days. This is the source of the apparent inconsistency and it would seem that the fort was taken in only 27 days (H A., I 264-8).

VII 135, l 8 from foot Bahrām Abiya . . . had revolted in Multān and put 'Ali Akhti to death

Both these anecdotes of Muhammad Tughlaq have been borrowed by this compiler from the history of Budāuni (Text, I. 227,Tr I. 304), who has copied them from the Tārīkh-i-Mubārak Shāhi (Text, 99-100). But both these authors give the sobriquet of this 'Ali', not as 'Akhti,' but as 'Khitati', i e caligraphist See also Hājji Dabīr (Z W 863, last line). The name of the saint who interceded for the people of Multān was not 'Shaikhu-l-Hakk', but Ruknu-d-dīn Quraishi (B I 227, 239, Tr 304, 318) He was the grandson of the Shaikh Bahāu-l-Haqq wa ad dīn Zakariya Quraishi of Multān

VII 140, l 8 Kāsım Khān

The person meant is Qāsim Khān-i-Juwaini, a Sayyid of noble birth who was the husband of Nūr Jahān's sister, Manīja Begam He was in charge of the government of the Punjāb (T J Tr II 2 and 182) and took leave of Jahāngīr, when the Emperor was returning from Kashmīr, (T J. 442-3, Tr. II, 228, 230) He was the man who afterwards took Hūgh from the Portuguese See 31-35 ante

VII. 142, l 2 Khãn Jahãn Lody was pursued by Rãjā Bahādur

This whole extract from the Tai ikh-i-Mufazzali contains so many inaccuracies and errors that one is compelled to pronounce it a compilation of little value 'Rājā Bahādur' is an error for 'Razā Bahādur', who was a Musalman and not a Hindu The youthful grandson of Khin Jahan Lody was called, not Ismat Khān, but 'Azmat Khān (Bād Nām I. i 278) The Peacock throne is said by the contemporary official chronicler, 'Abdul-l-Hamid, to have cost only one Kror of Rupees and not nine Ki or s, nine lacs and one thousand rupees (See ante p 46) 'Mudabbir Khān' (142, 1 20) must be an error for Muzaffar Khān, son of Khwāja Abu-l-Hasan, qv S, 25, 73, 74 ante Nadira Begam, the wife of Dara Shukoh, was the daughter of Prince Parviz and not his grand-daughter, as stated by this author (144, I. 22) The Khān-i-Khānān who took Daulatābād was entitled Mahābat Khān, not Muhammad Khān The name of the Rājā of Āssām was not 'Jar Bijar Singh' (144, 1 10), but 'Jardhicaj Sinha' (Gait, History of Assam, 123) "Karkalū" which is said to have been the chief residence of the Raja (1 20) is an error for 'Ghargaon' (qv 266 infra) The Khān-ī-Khānān (Mīr Jumla) is said on the last line to have received, among other honours, the insignia of the farman and the tugh, which is a blunder for tuman tugh

VII 143, l 3 His Majesty [Shāh Jahān] had been pleased to assure his mother-in-law

This canard is repeated by that inveterate gossip-monger, Manucci "When the said Jahangir was told that the mother of Shaistah Khan was

pregnant, lie was very glad and he resolved that if slie brought forth a son, he would at once assign him pay of three millions of Rupees a year." (Storia, II. 321). The author of the Maāsiru-l-Umarā also had heard the tale, but he denounces it as a fable and warns his readers that the current report about Shayasta Khan having been made a Pani-hazāri on the day of his birth is, not founded in truth. He stresses the fact that Abu Tālib was given the title of Shāyasta Khān only in the 21st year of Jahangir's reign, that he was given the rank of five hundred only at first, that he rose step by step to the mansab of Panj-hazāri, and that this grade was attained only at the accession of Shāh Jahān. (Text, II. 691). This last fact is incontestable, as it is stated in the Bādshāhnāma that one of the nobles who received promotion very soon after Shah Jahan's accession was Shayasta Khan and that he was raised on 1st Rajab, 1037 H. to Five Thousand Zāt. (I. i. 180, l. 4 f. f.). Jahangir himself notes that Abu Talib was promoted to the mansab of 2000 Zat, only in the 18th year of his reign. (Text, 361, l. 11; Tr. II. 261). Moreover, as Shayasta Khan is known to have died in 1105 H. at the age of 91 years, (Beale, Miftah, 288), he must have been born in 1014 A. H., when Shah Jahan himself was only a boy of fourteen and had not become the son-in-law of Shayasta's mother.

VII. 148, l. 15. Lanjar Kā-an and his descendants.

Recte, Būzanjar Khān. He was the ninth ancestor of Chingiz Khān, the fourteenth of Tīmūr and the twenty-third of Akbar. (A. N. I. 67; Tr. I. 183. See also Miles, Tr. Shajratu-l-Atrāk, 46, 50 notes).

VII. 160, l. 11 from foot. Aurangzeb ordered a remission of the transit duties upon grain...... and tobacco,..... to prevent the smuggling of which, the government officers committed many outrages, especially in regard to the exposure of females.

The order was issued in 1666 A. C. Tavernier (II. 251), and Manucci (II. 175), both bear witness to such harassment and speak of its leading to reprisals terminating in loss of life. The Governor of Surat was stabbed with a dagger by a Rājput in 1653. (Kh. Kh. I. 678). Another Rājput ran amuck, killed several officials and afterwards his own wife and daughter in Dehli itself. The M. 'Ā. also states, that the tax-gatherers "insulted the honour (in e. women) of the people." (Text, 530, l. 6 f. f.).

VII. 168, l. 2. The Lubbu-t-tavarikh-i-Hind.

Khwāfi Khān makes some uncomplimentary remarks about the Chronicle compiled by Bindrāban, on 283 infra, and Muḥammad Sāqī disparages his character. "Bindrāban, the artful, sly or tricky" (فرفن) was, he says, implicated in the correspondence and intrigues which led to the incarceration of Prince Mu'azzam and he was expelled from the Imperial Camp on the 18th of Shawwāl 1097 A, H. (Text, 293, l. 4 f. f.; 190 infra).

VII. 170, l. 7. If the title of the work is intended to be a chronogram, which is nowhere stated by the author, the date would be 1108 A.H.

This statement must be founded on some error or miscalculation, as the title given by Elliot, المن التواريخ من , would yield the date 1339, or 1280, if the last word من were left out. The fact is that the real chronogram, as given in all the three copies in the British Museum, is مالات مناك مندوستان, the numerical value of which would be 1106, or 1100, if 'Hindūstān' were spelt without a 'wāv,' as it actually is, in one of the Manuscripts. (Rieu, I. 229; Ethé, I O Catalogue, No. 359, Col. 136).

VII. 172, 1 7. Plaints were so few that only one day in the week, viz., Wednesday, was fixed upon for the administration of justice, . and even twenty plaintiffs could not be found

A very similar asseveration is found in Manucci. He may have been indebted for it directly or at second-hand to the Hindu Chronicler. However that may be, he also assures us that "though every day, proclamation was made by beat of drum that any one who had a complaint should present his plaint in the royal presence, months passed without a single complaint being heard of "(Storia, I. 209 See also *Ibid*, II. 20).

VII 174, l. 8. It [the 'Alamgirnāma] was dedicated to Aurangzeb in the thirty-second year of his reign, but on its being presented, the Emperor forbade its continuation

This statement is borrowed from Morley's Descriptive Catalogue of Persian Manuscripts in the E I Company's Library, p 125, but its correctness is dubious, as the death of the author, Muhammad Kāzim in the twenty-fourth year of the reign or 1092 A. H., is recorded in the Tārīkh-i-Muhammadi (Rieu, III. 1083, Muqtadir, Bānkīpur Catalogue, VII 85) Moreover, we know that Aurangzeb had promulgated a mandate against the compilation of chronicles, some years before the 32nd year of his reign (282 infra), and it is not likely that any author would have had the hardhood to present to him a work written in flagrant defiance of those commands Little or nothing is known of the author himself Muhammad Sāqi states in his chronicle of the XXIst year (1088 A. H) that Muhammad Kāzim, the writer of the 'Alamgīrnāma was dārogha of the all is e Selling and Purchasing Department (163, 1 6 f. f.)

VII 176, l 4 from foot. And it will contain an account of the undertakings and conquests achieved by His Majesty during the period of eighteen years

This assertion is manifestly wrong, as the 'Alamgirnāma' contains only the history of the first ten years of the reign. This Chronicle was written in imitation and upon the model of Amīnā-i-Qazvīni's Shāhjahān Nāma'z-Deh Sāleh and it was intended, like it, to record the events of the First Decade only, each Decade occupying a volume by

itself. A reference to the text shows that the error is due to •رد• [every ten] having been misread as •رد• [eighteen]. What Muḥammad Kāzim says is that مرد• ساله احوال یک بخلد سازد i.e. it was his intention "bind up [collect] the annals of each decade in a separate volume." (Text, 34, 1.11).

VII. 179, l. 15. He [Dārā Shukoh] employed them [the Brahmans and Sannyāsis] in translating the Bed.

VII. 180, l. 6 from foot. Illness of the Emperor Aurangzeb.

There is great confusion here. The author of the 'Alamgirnāma is made to say by Dowson that on the night of the 12th of Rajab in the 8th year, Aurangzeb was suddenly attacked with strangury and that he recovered in a few days owing to the skill and attention of the physicians. What Muhammad Kāzim really states is that the old Emperor Shāh Jahān [not Aurangzeb] was taken ill in this way on 12th Rajab, and so far was he from recovering, that he died fourteen days afterwards, on the 26th of the month. (1076 H.). See what is said by Khwāfi Khān on 275 infra; 'A. Ş. III. 350, l. 7; M. 'Ā., Text, 53, l. 3. Aurangzeb had a stroke of paralysis, but it was in the 5th year of his reign and not the 8th. (366 infra; M. 'Ā. 41, l. 9).

VII. 181, l. 2. Ma-āsir-i-'Ālamgīri.

The title of this work appears to have been suggested by that of Kāmgār Khān's Maāṣir-i-Jahāngīri, and is, like it, a chronogram. As Maāṣir-i-Jahāngīri represents H. 1040, the date of composition, so Maāṣir-i-ʿĀlamgīri stands for 1122 H., the year in which it was completed.

VII. 182, l. 10. The author of the 'Critical Essay'...complains ...that the author of the Maāṣir-i-ʿĀlamgīri...has not stated when Bahādur Shāh and Prince 'Aṣam were made Chihl hazāri and when Ghāzīu-d-din Khān Bahādur was made Haft hazāri and Zu-l-fikār Khān Shash hazāri.

Dowson observes quite properly that the "omissions will not appear of much importance to a European reader." But the criticism is not only trivial, it is also unjustified. The omissions complained of do not exist. The promotion of Bahādurshāh to the full rank of 40,000 is recorded at 268, l. 5 and 370, l. 5; and that of Prince 'Azam to the same rank is noticed

at 473, 1. 11. Ghāzīu-d-dīu Khān's rise to 7000 and Zulfiqūr's promotion to 6000 are registered on pp. 302, 1 3 f. f. and 309, 1. 1. In a word, if any one deserves censure, it is not the author, but his critic and "the boot is the other leg."

VII. 183, l 6 from foot. Intelligence arrived from Thatta that the town of Samaji had been destroyed by an earthquake; thirty thousand houses were thrown down.

In the B. I. text, the town is called 'Samāwāni' and said to belong to the taluga of Bandar Lāhri. (M. 'Ā. 73, last line). 'Samāwāni' or 'Samāwāti' was a pargana in Sarkār Nasrpur in the days of Akbar, (Āīn, Tr. II 341) and included lands now comprised in the pargana of Muhabbat Dero. The village itself is now a poor place, with only 500 houses. It is stated in the Tārīkh-1-Tāhiri that the town of Āgham (which is thirty miles south-east of Haidarābād) was in the pargana of Samāwāni. (E. D. I. 270 362). If thirty thousand houses were destroyed, the convulsion could not have been confined to a small town or even pargana. It must have extended over a considerable area, as seismic disturbances of great intensity always do. Sind lies within the seismic zone in Northwestern India, as the recent uphcaval at Quetta has abundantly proved and this notice of a similar convulsion in Aurangzeb's reign is not without interest.

VII. 187, l. 21. Song, Ragunāth Dās Bhāti, Ranghūr. Read 'Sonang, Raghunāthdās Bhatti and Ranchhor.

VII 189, l. 12 Parganas of Mandal, Pur and Badhanor.

'Māndal' and 'Por' are separately mentioned as Mahāls in Sarkār Chitor (Āīn, Tr II. 274) and both are shown separately in Constable, 27 B c Māndal is 76 miles north-east of Udaipur and 75 south of Ajmer. Lat 25°-25' N, Long 74°-37' E Jahāngīr says of Māndal that it is 30 or 40 kos from Ajmer (T J. Tr. I 50) Por is about forty miles south of Māndal Mandalgarh is a different place. Badhnor [Bednor] is 90 miles N. E. of Udaipur. Lat. 25°-51' N., Long 74°-20' E Constable, 27 B c.

VII 189, l. 5 from foot. Caves of Ellorā.

There is an earlier reference to these caves and the Kailāsa Temple, which has been described as "the most marvellous architectural freak in India" (Smith, E. H. I. 386) in Firishta's narrative of the capture of Devaldevi by the cohorts of 'Alāu-d-dīn Khaljı. (I. 117, 1.8 f.f.) There is a lengthy description of the caves in the Tazkiratu-l-Mulūk, a History of the Bahmani and other Dekkan dynasties written about 1020 A.H. 1611 A. C. by Raf'īu-d-dīn Shirāzi. (Rieu, I. 316, Sachāu and Ethé, Bodleian Catalogue, No 276, Col 145, Rehatsek's Catalogue, IV. 11). See the copy in the Mullā Firūz Library, Bombay, Folios 196a-198b

VII 193, l 18. About this time, the noble Shah ('Alam) was appointed governor of the province of Mālwā and Prince Kām Bakhsh, governor of that of Bījāpūr.

The word 'Alam' is not in the B. I. Text, (520, l. 10) and its interpolation here is unwarranted and misleading. The Prince who was appointed as governor of Mālwā in the 51st year of Aurangzeb's reign, was not Muḥammad Mu'azzam or Shāh 'Ālam, but his brother and rival, the prince Muḥammad 'Azam. See 386 infra. Shāh 'Ālam had been appointed to the government of Kābul in the 42nd year and he was there at this time. He left it only some months after Aurangzeb's death. Both Princes were called Shāh, but this 'noble Shāh 'is 'Azam Shāh, not Mu'azzam Shāh. VII. 198, l. 2. Futūhāt-i-Ālamgīri.

Besides being known as Wāq'iāt-i Ālamgīri, this work is also called Tārīkh-i-Shāh Shujā'a. It was written at Mālda in the year 1070 H. 1660 A. C., and the narrative does not go further than Shujā'a's' return to Tānda, just before his flight. (Rieu, I. 270). M'aṣūm was the son of Ḥasan bin Ṣāliḥ and had been in the service of Shujā'a for twenty-five years. (Ethė, I. O. C. Col. 130).

VII. 198, l. 6 from foot. There isanother work bearing this title [Futūhāt-i-'Ālamgīri] written by Sri Dās, a Nāgar Brahman of Gujarāt.

The name of the author was not 'Sridās', but Isardās and it is also written Isaridās [Recte, Ishwardās or Ishwaridās]. It is a desultory account of events from 1657 to 1698 A.C. and the copy in the British Museum is said to be the only one known to exist. (Rieu, I. 269). Ishwardās was in the service of the Shaikhu-l-Islām and was a resident of Pāṭan in Gujarāt. Another Memoir of the same sort is the Nuskha-i-Dilkushā of Bhimasen, son of Raghunaudandas, a Kāyasth of Burhānpur, who was the agent of Dalpatrāo, the Bundela Rājā of Datia. A loose and abridged paraphrase of the Nuskha was incorporated by Jonathan Scott in his Translation of Ferishta's History of the Dekkan.

VII. 199, l. 2. Tarīkh-i-Mulk-i-Ashām.

Shihābu-d-dīn Tālish's History of the Invasion of Āssām is more frequently cited as Fathiyya-i-'Ibriya or Fathiyya-i-'Ibratiya. It is sometimes called 'Ajiba-i-Ghariba also. (Rieu, I. 266; Ethé, I. O. C. No. 341. Col. 120). The title seems to have been chosen because, as the writer says in the Preface, the sufferings and losses of the invading army (q. v. 268, post) had been kept back from public knowledge to please Mir Jumla. Talish states that he had felt it his duty to write a truthful account of the campaign, after the Mir's death. The First Part was completed in Shawwal 1073 (May, 1663) and copies of this are not uncommon. He subsequently wrote a Continuation, of which the only copy known is in the Bodleian (Sachau and Ethé's Catalogue, I. No. 240). The First Part terminates with the death of Mir Jumla in April 1663. The Continuation carries on the narrative upto the triumphal entry of Buzurg Umed Khan into Chātigām on 27th January 1666. Sir J. N. Sarkār has given a summary of the Continuation in J. A. S. B. 1906, pp. 257-267. Blochmann's fuller abstract of the First Part was published in the Forty-first volume of same Journal, in 1872, pp. 51-96.

VII. 200, l 2 from foot Ni'amat Khān Hāji was an eminent personage

'Hājı' means 'Satırıst, writer of squibs, libels or lampoons' Ni'amat Khān's "indecent jests and coarse wittieisms" are referred to on p. 201 unfra The post of 'Bakawal' (1 15) to which he was appointed was that of Superintendent of the Imperial Kitchen Thetitle' Ni'amat Khan' was conferred upon him, because Ni'amat rignifies 'meals, victuals, viands.' Many books on cookery are entitled 'Khwān-1-N1'amat', i e 'A Tray of Dainties or Comestibles' Abu-l-Fazi states that a physician named Mulla Mîr, who was Akbar's Bagaical Begi, was given the title of Nî'amat Khan (A.N. III.) Ni'amat Khān is mentioned under his original name of Mirzā Muhammad-1-Hāji in the M'Ā. (p 267), and he is said to have been the son of Hakim Fathu-d-din, the uncle of Hakim Muhsin Khan, q v. 390 infra. Besides the works mentioned here, he wrote a Risāla i-Hazwi-Hukmā, i e a Collection of anecdotes of the incompetence of physicians, a number of Satires on contemporaries with the curious title, Rāhat-al-Qulub or 'Hearts' Delight', and a Miscellany of Rug'at wa Mazhikat or 'Letters and Facetiae' (Houtsma, E I, III. 922-3).

VII. 203, l. 9. First, the Kalimāt-i-Taiyibāt, published by one of his [Aurangzeb's] chief Secretaries, 'Ināyatullah

VII. 209, I. 29. Mill also complains that we have no complete history of Aurangzeb This defect has been remedied by the Hon'ble M Elphinstone who has judiciously availed himself of Khāfi Khān's history and thus has been enabled to give us a complete narrative of the reign of Aurangzeb

Elphinstone, Grant Duff and other European authors were obliged to draw very largely, if not exclusively, upon Khwāfi Khān's history for their account of the reign of Aurangzeb, but later and better equipped critics have entertained a less favourable opinion of his performance. "Khwāfi Khān has used," writes Blochmann, "the 'Alamgīrnāma, in his slovenly way, without the slightest exactness in his meagre geographical and chronological details" Blochmann then proceeds to give a formidable catalogue of errors found in this chronicler's narrative of Mir Jumlā's invasion of Āssām. (J A S B 1871, XL) Elsewhere also in the same article, he speaks of Khwāfi Khān as an 'untrustworthy historian,' (Ib, 68

note), and it must be said that subsequent researches have proved that his chronology is quite unreliable.

VII. 213, l. 15. If any discrepancies should appear between the earlier and later portions of his work.

اکر بسبب زنجیر بند سررشتهٔ سوانج بدست نیامده در مقدم و موخر سال تقاوت ظاهر کردد (II. 3, 1. 7). "If on account of a duly consistent chain of events having not to come my hands, discrepancies are noticed in regard to the precession or succession of the years of events," i.e. if the events are found to have been antedated or post-dated in his chronicle, when his account is compared with the narratives of other authors, i. e. if the dates assigned by himself are either too early or too late. Cf. 282 infra, where he again refers to this matter and admits that with respect to the annals from the 11th year to the 21st, he has not been "able to relate them in the order in which they occurred." The fact of the matter is that this is true not only of the second decade of Aurangzeb's reign, but of the entire period from the 11th to the 50th. Any one who compares Khwafi Khan's Chronology with that of the Maāṣir-i-'Zlamgīri,-a" regular Court Chronicle" based on State papers-will find that almost every important event is wrongly dated. Sir Jadu Nath Sarkar says that "though his description of the condition of society and characteristic anecdotes save Khwafi Khan's work from the dry formality of the Court Annals," he has often "added. unauthorized touches for the sake of literary effect". (H. A., II. 304).

VII. 215, l. 7 from foot. After the defeat, Muhammad Shuja' did not return to Bengal.

II. 6, 1. 13). There و محمد شجاع از صدمات فوج بادشاهي تا بنگاله بند نگرديد must be some error here, as we are told at 231 infra by Dowson himself that Shuja'a was once more "able to collect his forces and march from Dāccā to the assistance of Dārā Shuko'ı." The real meaning is that "Shuja'a did not halt anywhere in his flight, i. e. did not stop or draw rein, until he reached his own province of Bengal."

VII. 215, footnote. Defeat of Prince Shuja at the village of Bahadurpur on the side of the Ganges.

This village still exists and lies at about five miles' distance from Benares city and two miles east of the right bank head of the Railway Bridge over the Ganges. (Sarkar, H. A., II. 131 note).

VII. 218, l. 8 from foot. Aurangzeb then sent a Brāhman called Kab who had a great reputation as a Hindi poet . . . to the Rājā [Jaswant Sinha].

'Kab' was not the name of this envoy, but only his title. He was generally known as 'Kab', because he was a distinguished Hindi poet at Court. Shah Jahan had bestowed the title of 'Kab Rai'- 'King of Poets', -on a Gwalior Brahman named Sundar Das who has written much prose and poetry in the Braj dialect. We know that Sundar Das was often employed as an envoy in the Emperor's negotiations with Hindu princes. (Bādshāhnāma, I. ii. 76, 95, 98, 99; II. 238, 239),

VII. 219, l. 2 and footnote. The battle was joined ... near Dharmatpur (Alamairnama).

The village is said in the M. A. (5, 12), to he about seven kos from Ujjain. There is still a village named Dharmat, about 14 miles south-west of that town. (Sarkar, II. 3) The village of Fathabad, which was founded by Aurangzeb on the site, has now grown into a considerable town and is an important Railway junction, fifteen miles from Ujjain.

VII. 226, l 11. The authors of the three 'Alamgir-nāmas have each described the seclusion of the Emperor Shāh Jahān by the will of Aurangzeb, but 'Akil Khān Khāfi, in his Waki'āt-i-'Alamgīrt has entered fully into ... matters.

The text has موافق مرصى ممارك محمل مرمان قلم داد ، الد (II. 32, 1, 12). " They have written a short account, in accordance with the wishes of, i.e., in such a way as to be agreeable or acceptable to, the Emperor "'Aqil Khan's original name was Mirzā 'Askarı He wrote poetry under the pen-name of Razi. He was governor of Dehlı at the time of his death in 1108 A. H. He is frequently mentioned in the M. 'A. (26, 29, 36, 47, 383-4). His book is variously called Zafarnama-i-Alamgiri, Halat-i-Alamgiri, and Aurangnama. It begins from the invasion of Bijapur in 1657 and ends with the death of Mīr Jumla, (MU, II 821-823, Rieu, 265, 792, 936). Elsewhere also, (266 infra). Dowson makes Khāfi Khān state that "the author of the 'Alamgirnama, has given an account of the murder of دكر كشتن مراد حش را ". Murad Bakhsh as suited his own pleasure (Marzi) مرضى The Marze there also is the موافق مرصى قلم الدار سوده the pleasure of the Emperor, not the author's. At page 174 ante, Dowson himself states that "little reliance can be placed on the narrative of the 'Alamgirnama, when any subject is mentioned likely to affect the character of the monarch" This is because the historiographer had been enjoined to read what he had written to the Emperor and "incorporate his corrections" (176 ante).

VII. 226, l. 15. [Aqıl Khān] has described. the confinement of Shāh Jahān, the closing up of the waters (band namūdaniab).

Dowson hazards the surmise that the Persian phrase cited in the parenthesis is only a figurative expression signifying 'bringing matters to a crisis' and that it is not to be understood literally. But this charitable construction is unfortunately without foundation. There is now no doubt that the water-supply of the palace was really cut off. The fort of Agra was almost entirely dependent for its water on the Jumna and as the gate which opened on the river was taken possession of by the prince Muhammad Sultān, it was easy to prevent anyone from taking water into the fort. The fact of the matter is that these ruthless tactics of the son and grandson left the old Emperor "to quench his thirst in the burning heat of June by nothing except the bitter and brackish water of the wells in the fort." (Sarkār, H. A., II. 79-80 and note). The

contemporary testimony is explicit in regard to the matter. See 'A. S. III. 308, l. 10. f. f., where there is an allusion to the inmates of the palace and the soldiers deserting on the pretext of going out in search of fresh water. Tavernier states that "as the wells of the Agra fortress were dried up, he [Shāh Jahān] was compelled to provide himself with the river water by a small postern which was the weakest part of the whole place and which Aurangzeb had reconnoitred and taken possession of." (I. 341).

VII. 230, l. 16. His [Sulaimān Shukoh's] road passed through the Jāgīr of the Princess Kudsīya.

'Qudsiya Begam' was not a name but the title of Jahānārā, the eldest daughter of Shāh Jahān. She was also styled 'Pādshāh Begam'. (M. 'Ā. 166, l. 8). The same titles were afterwards conferred upon Aurangzeb's daughter, Zīnatu-n-Nisā. (M. 'Ā. 385, l. 1 f. f. See also infra 401). Later, Udham Bāi, the mother of the Emperor Muḥammad Shāh, was styled 'Nawāb Qudsiya.' (E. D. VIII. 133). Jahān Ārā is spoken of as 'Qudsiya Pādshāh Begam' at 225 ante also. The Qudsiya Gardens which were laid out by the mother of Muḥammad Shāh are still in existence and well-known to residents of Dehli.

VII. 232, l. 11 from foot. The commandants of Chitapur and Allahabad had surrendered their fort-resses and joined him [Shujā'a].

The Bibl. Ind. text also has 'Chitapur' (46, l. 7), but no great stronghold of that name is known. The right reading may be 'Sitapur.' It is in Banda district, about forty miles south-west of Allahābād. Constable, 28 B c. It is given the twelfth place in a Ms. list of the 42 strongest Imperial forts of the reign of Aurangzeb, which is in the British Museum. (Irvine, A. I. M. 269). But Mr. Irvine is not sure that he has read the name in the Ms. correctly. The suggestion may be offered that the place intended is Chunar or Chunargarh. Khwafi Khan says at 241 infra, that the fort of Chunar which Shujā'a had got into his power was given up to Aurangzeb. (Text, II. 76, l. 3). Allahābād is stated to have been surrendered to Aurangzeb by Shujā'a's commandant, Qāsim Khān, some time before. (237 infra; Text, II. 61, l. 15). Sir J. Sarkār says Rohtās, Chunār and Banāras had all opened their gates to Shujā'a. (H. A., II. 139).

VII. 237, l. 13 from foot. Aurangzeb appointed Amīr Khān to pursue the fugitive [Jaswant Sinha].

Recte, Muhammad Amin Khān as in the Text, II. 61, l. 4 f. f. and M. 'Ā. 17, l. 2 f. f. See also p. 234, l. 4 infra. He was the son of Mīr Jumla. Amīr Khān was a different person altogether. He was the brother of Shaikh Mīr who was killed afterwards in the battle near Ajmer. (Text, II. 70, l. 2). On l. 6 f. f., Amīr Khān is again described erroneously as Governor of Lāhor. He was really Governor of the Dāru-l-Khilāfat, i. e. Dehli. (Text, II. 62, l. 4). Salīmgarh was the name of the fort built by Salīm Shāh or Islam Shāh Sūr near Dehli. Murād Bakhsh had

to and interned there immediately after he was taken prisoner (209 ante).

VII. 247, 1 3.

VII 243, l 6. [Dārā] went to Kari, two Kos from Ahmadābād.

Sic in the Text, II 82, l 1 also, but Kadi near Pātan (or Anhilwād) is really about twenty-two miles by road from Aḥmadābād (Th) and twenty-eight miles by Rail via Kālol The T A. says that Kari is twenty [short] kos from Ahmadābād (E D V, 431). Khāfi Khān probably wrote ce de or ce lee or ce or ce lee or

VII. 243, l 24 Dara proceeded towards the country of Jawiyan

in the Text, 82, 1 2 ff The 'Alamgirnāma speaks of it as the country of 'Chānd Khān' or 'Jāndbān' (Text, 412), Recte, حديان Chandiān. Blochmann was the first to suggest the correct reading of this name in his paper on the 'Flight and Capture of Dārā Shukoh' "The ill-starred prince passed through the district inhabited by the Chandi tribe and came to the territory of the Magassis, whose chief received him hospitably. The chief town of the Chandiās is Chandiā, also called Dehi Kot, Lat 27°-38′ N, Long. 67°-34′ E The district of the Magassis, an important Baluch tribe, lies north of Chandia Dārā then continued his march to Dādar Lat 29°-26′ N, Long 67°-41′ E Masson says that the Pat of Shikārpur, i e, the country between Kachh Gandawa and Shikārpur separates the lands of the Magghazis from those of the Chandis (Kalat, 334)" (J A S B XXXIX 1870, p 275)

Sir J Sarkār gives the name of Dārā's betrayer as Jīwan (IL 209), but Mr G. P Tate assures us that "the real name of the chief of Dādar was Jiānd He was the eldest son of Ayūb, chief of the Barozai, a branch of the Parni Afghāns The Barozai are still settled round Sībi in the Baluchistan Agency Jiānd is said to have undertaken to see Dārā through the Bolan Pass" (Irvine's Note in Manucci, Storia, IV 427) The 'Ālamgīr-nāma and Khāfi Khān call him 'Malik Jīwan', (214 infra), but the real name must have been 'Jiānd' Mr Dames also tells us that 'Jiānd' is the correct Buluch form (Baloch Race, 36) Jīwan is more Hindu than Afghān.

VII 247, 1. 3 He also remitted the Pandari, a ground or house cess, which was paid throughout the Imperial dominions, by every tradesman and dealer, for every bit of ground in the market, for every stall and shop.

Sir Jadunāth Sarkār suggests that this may be the Marāthi 'Pandhraghatti' or rather, 'Pāndhrapatty' which is defined in Wilson's Glossary of Revenue and Judicial Terms as a "tax on shops, workshops, booths and stalls or upon artisans" But it is explicitly stated there that "the designation is in a great measure peculiar to the Presidencies of Madras and Bombay," and that similar taxes which were levied elsewhere were called by a very different name, 'Mohturfa' It is not likely that Khwāfi Khān should have used a technical Revenue term known only in Madras and Bombay, for a cess or cesses levied in Northern India and all other parts of the Empire, and it may be even doubted if he had ever heard of this

Pāndhrapatti. Elsewhere in the B. I. Text, Khwāfi Khān speaks of it as المائدوي Pāndvī. May not both these forms 'Pāndari' and 'Pāndavi' be errors for 'Māndvi', which is still commonly used for 'Octroi' and several other municipal taxes.

VII. 247, 1. 18. These and other imposts.......which brought in Krors of rupees to the public treasury were all abolished.

از همه ابواب زیاد از گرورها داخل خزانه سرکار میکردید (II. 87, 1. 9). The word 'rupees' is not in the original. The author probably meant only 'Krors of dāms'. Cf. 283 infra, where almost all these taxes are again said to have been abolished and to have brought in only lacs, not 'Krors', of rupees.

VII. 251, footnote 1. The 'Amal-i-Sālih says the Prince was confined in the fort of Mir Garh, or in Salimgarh, according to the 'Alamgirnāma.

'Mīr Garh' must be an error for 'Nūrgarh', another name by which 'Salīmgarh' was known, and which was given to it by Jahāngīr, whose laqab was Nūru-d-dīn.

VII. 255, l. 4 from foot. The origin of the name of Bhoslah,.....is from the Hinduci word, 'ghoslah', meaning place, or a very small and narrow place; and as that man was brought up in such a place, he received the name of Bhoslah.

Khwafi Khan's attempt to derive 'Bhosla' from 'Ghosla' and establish the philological identity of the two words is manifestly inadmissible. In the Shīvdigvijaya and some other Marāthā chronicles, the surname is traced to 'Bhosi', 'Bhosvat' or 'Bhosvant', which is said to be the name of a fort near Chitor. (Keluskar, Life of Shivaji, Tr. Takākhāv, p. 5 note; Kincaid and Parasnis, I, 113). Others say that Bhosāji was the man who originally emigrated to the Dekkan from Chitor, but there is no such name among Rajputs. 'Bhose' is also said to be the name of a village near Ellora (C. V. Vaidya, Shivaji, p. 9 and note) or in Parenda, but no such village has been yet traced. In this connection, I may point out that a village named Bhonsla (or Bholsna) is mentioned in the Bādshāhnāma of 'Abdu-l-Hamīd as existing near Bīzāpur, [Vaijāpur] which is about 25 miles west of Aurangabad (Text, 327, l. 8 and 328, l. 11; see also p. 15 ante). It was apparently not very far from Lasur, which was ten kos from Daulatābād, as Khān Jahān Lody is said to have fled from Baizāpur and Bhonsla to Lasur. It was, in fact, in the heart of the district in which the ancestors of Shivaji are said to have been settled. I understand from a local authority that there is a village called 'Bhosla' in the Kanad (or Kanhar) taluga of Aurangabad district. The town of Kanad is 33 miles N.N. W. of Aurangābād and is shown in Constable, 31 Ca. This toponym may be the real origin of the surname. Baizapur, Bhonsla and Shivgaon' are mentioned in juxtaposition in the 'Amal-i-Salih also. (I. 392, 1. 7).

VII. 256, l 8. The ports of Jiwal, Bābal, Dāndā Rājpuri and Chākna.

Recte, 'Chewal,' [Chaul] and 'Dābul', both places of note in the old days. 'Chewal' was the chief port of the Northern Konkan, as Dābhol was of the Southern, in the 14th and 15th centuries and both carried on an extensive trade with Persia and the ports of the Red Sea Chaul is now in Kolābā district, Constable, 31 B b, while Dābhol is in Ratnāgiri, Ibid, 31 B c. 'Jīwal' and 'Pābal' are again mentioned at 271 infra and are there said to be somewhere near Surat Chākan is not a port, but a village in Khed taluqa, 18 miles north of Poona. (I G. X 122).

VII. 258, l. 1. Sikandar 'Ali 'Adil Khān the Second.... who ruled when a minor as the locum tenens of his father.

در صدر سن قائم مقام يدر كرديد (II 115,13), e " who became the successor of his father (came to the throne) when he was young"

The facts of Sikandar's life show that he could not have acted as the locum tenens of his father. Sikandar was born in or about 1667 A.C and was only four or five years old, when 'Alı 'Ādıl Shāh died in 1672 Gemelli Careri who saw him in Aurangzeb's camp at Galgala in 1695 A.C. says that he was then about 29 years old (B.G. XXIII (Bijāpur), 439, 431)

VII. 261, l 17 At this time, Sivāji was at the town of Sūpa The Amīru-l-Umarā took Sūpa

Tavernier was present in the camp of the Amīru-l-Umarā, Shāyasta Khān, when he was besieging 'Choupart' or 'Choupar', as the jeweller spells the name of this fort (I. 31, 409 and note) Dr. Ball supposes this 'Choupart' to be 'Sholāpur', but it is Sūpa in Poona district Constable, 31 Cb The date given is 1660 AC. 'Seogānw' must be 'Shivgāon' in Ahmadnagar district, (Constable, 31 Ca), not Shegāon in Ākolā, Berār.

VII. 264, l 4 Bulghur Khanas.

652

The literal meaning of Bulghūr is 'pounded wheat or barley or a dish prepared by cooking it' (Richardson) The Hindi word for such public kitchens was 'Langar'. 'Abdu-l-Hamīd Lāhori calls them آئی بیر حامها "Soup-kitchens" (Text, I 1. 363, l 10, 25 ante)

VII 264, l. 10 from foot It [Assām] is said to be the native land of Pīrān Waisiya, the Wazīr of Afrāsiyāb, and the Rājā of the country traces his descent from this Pīrān.

This portentous statement is founded upon the fancied resemblance between 'Mug'—the name by which the people of Ārākān were then and are even now, commonly known—and 'Mugh,' Magian or Fireworshipper. The people of Ārākān were and are still, mostly animists

The Rājās of Āssām claimed to be descended from 'Biswa' (Sanskrit 'Vishva') Sinha, and this 'Biswa' or 'Viswa' seems to have been confused with 'Waisa' Both 'Pirān Waisa' and 'Afrāsiyāb' are prehistoric and semi-mythical characters

VII 265, l 22. When the Rājā of Assām and the Zamīndār of Kuch Bihār named Bhīm Nārāin heard of this. The Rājā of Āssām was named Jayadhwaj Sinha, and the ruler of Kūch Bihār was $Pr\bar{a}n$ Nārāyan. The latter was in power from 1633 to 1666. Some Musalman writers call him Pem[Prem] Nārāyan, but in the local chronicles of the Kochs as well as of the Ahoms, the first name is $Pr\bar{a}n$ and it is so spelt on his Coins. (Gait, History of Āssām, 115, 125, 135; Botham, Catalogue of Coins in the Āssām Cabinet, p. 526).

VII. 266, 1. 4. The Khān then retired thirty Kos and a half-from Ghargānw to Mathurāpūr.

'Ghargānw' is the old name of what is now called 'Nazira' in Āssām. It lay on the river Dikho or Disang, about nine miles east of Sibsāgar town. (J. A. S. B. XL (1871), 38, 49). Constable, 30 C b. Lat. 26°-56′ N., Long. 94°-45′ E. Mīr Jumla did not retire for thirty kos and a half, when he marched from Ghargāon to Mathrāpur, as he is said to have done, but only three kos and a half. مه و فريم كروه (Text, II. 154, l. 1). Mathrāpur really lies about seven miles south-east of Ghargāon. (Gait, Āssām, 133).

VII. 269, l. 1. The [Khān-i-Khānān] died at Khizr pur, on the frontiers of Kūch Behār, on the 12th Ramazān, at the beginning of the sixth year of the reign.

This place cannot be traced on modern maps, but Dr. Wise says that it was near Nārāinganj, eight miles south-east of Dāccā, which was in a pargana called Khizrpur. It was bounded by the Dāccā river, i. e. the Burhi Gangā. It lay about three miles west of Sunārgāon and nine miles from Dāccā. (J. A. S. B. XLIII, (1874), pp. 211-212).

The date of his death is given as 30th March 1663 A.C. (O.S.), by Gait (loc. cit. 137) and Sarkār, (H. A., III. 203); i.e. 12th Ramazān 1074 H. Kh. kh. has 12th, but the M. 'Ā. (44, l. 2 f.f.) has 2nd i.e. 19th March.

VII. 272, l. 1 from foot. At Sivāpur, which was built by Sivāji, and at the forts of Kandāna and Kanwāri-garh, not one trace of cultivation was left.

Sivāpur lies midway between Poona and Shirol or Shirwal. It is 16 miles north of Shirol and 26 south of Poona. 'Kandāna' is the old name of Sinhgadh. 'Kanwāri-garh' is 'Kumāri' in Junnar taluga of Poona district.

The name of the son of Rājā Jai Sinha of Amber was not Kesar Sinha, as it is given on 1.14, but *Kirat* Sinha. (M. 'Ā. 128, 167, 181).

VII. 275, l. 5 from foot. Subjugation of Sangrāmnagar and Chātgām near Arracan.

According to the 'Alamgirnāma (944, l. 2), 'Sangrāmnagar' or 'Sangrāmpur' was 18 kos south of Dāccā and 21 kos distant from Srīpur, which lay opposite to Chāndpur. According to Blochmann, it was one of the frontier thānas near Noakhāli. (J. A. S. B. XLI (1872), p. 241 and note). Chāndpur is now in Tipperah. Constable, 29 D d. The actual date of the conquest of Chātgām is given as 29th Rajab 1076 A. H.—25th January 1666, in the 'Alamgīrnāma. (Text, 951-2).

VII. 276, l. 13. He (Shivaji) made an offering of 500 Ashrafis and

6000 rupees, altogether 30,000 rupees.

The number of Ashrafis is stated wrongly here. It is 1500 in the Text, (190, l. 6), which is correct. The statement is not without interest, for it means that 1500 ashrafis were valued at 24,000 rupees (30,000 6000), that is, one ashrafi or gold Mulir was reckoned at 16 rupees at the time, 'Abdu-l-Ḥamīd rates it at 14 rupees only (45 ante) This may indicate that some notable change in the relative value of gold and silver had taken place in the interval. See my H. S. M. N. 245-252 Nathuji (l. 16) was Netāji Pālkar (Grant Duff, H. M., 99 Note)

VII. 276, l. 15. But his son [Shambhāji], a boy of eight years, had privately been made a panj-hazāri.

The word for 'privately' is also (II. 190, 19), which literally means 'in absentia', i. e., 'in the absence of the person himself from Court' The rule was that, whenever a Mansab was conferred upon any one, the recipient had to present himself before the Emperor and make the customary taslims and prostrations. The fact of an exception having been made in the case of Shambhāji is expressly recorded here. In the M. U., the word is explained as "without attending in person at Court" (II 430). The phrase occurs in the A.N. also (III 449), and is rendered as 'without waiting on Akbar' by Mr Beveridge (Tr. III. 722) At A. N. Text, III. 783, 17 also, it is said that when Mirzā Jāni Beg Tarkhān died, Akbar restored his territory also to his son Mirzā Ghāzi, who was then in Sind and sent him a diploma of investiture and robe of honour as a special favour. Cf. also 275 ante, where it is said that as a Mansab of 5000 had been granted to Shambhāji, who was then in the Dekkan, he also would have to proceed to court

VII. 277, l. 10 from foot. Mangal pahra and other [forts] were taken.

Recte, Mangalvedha, now in the small State of Sāngli, 13 miles south of Pandharpur and 15 north-east of Sāngli (I. G. XVII. 178). Constable, 31 C c Sir Jadunāth Sarkār spells it as 'Mangalbira' (H. A. IV. 290) or Mangalvide (C. H. I. IV. 284), but the I. G., (loc. cit.), Constable and the Post Office Guide agree in calling it Mangalvedha, which must be correct. It is said to have been founded by a Hindu chief named Mangal

VII. 283, l 16 Orders were issued prohibiting the collection of the Rāhdāri, Pāndari and other imposts

The second of these imposts is called & Dander in the Text, 212, l. 7 f. f. I have ventured to suggest that the right reading may be & Mānder, which is used in most of the Indian vernaculars for a Bazar or Market and also for Market dues, taxes levied on shops, octroi duties etc. VII 283, l. 10 from foot The Minstrels and singers . were made ashamed of their occupation and were advanced to the dignities of Mansabs.

کلاوتنان و قوالان . . . را از سرود خوانی تونه داده برمرات منصب ایشان افرود بد (II 212, last line) "The musicians and ministrels were made to repent and abjure their occupation of singing songs [t.e., they were made to publicly

confess that their occupation was sinful and to take solemn oaths to abandon it for ever] and their status in the cadre of Mansabs was raised."

They were not "advanced to the dignity of Mansabs." As Court officials, they already held certain Mansabs. But as they would now have no opportunities of getting munificent gifts and in ams from the Emperor on ceremonial and other occasions, their emoluments were increased, they were promoted to higher grades, carrying better pay and thus compensated for the loss of that part of their income which accrued from perquisites and presents. "Mansab was not," as Mr. Irvine points out, "a term confined to the military service. Every man in State employ above the position of a common soldier or messenger, whatever the nature of his duties, civil or military, obtained a Mansab." These 'musicians and singers' already held Mansabs, as Mansab really means 'rank' and "every man who was in State employ and bound to render certain services when called upon" was a Mansabdar. (A. I. M. 3-4).

VII. 283, l. 7 from foot. It is said that one day a number of singers etc.

This story of the 'Burial of Music' is also in Manucci (Storia, II. 8).

The order was passed in the 11th year (M. 'Ā. 71, l. 9). The practice of appearing at the Jharokha window seems to have been discontinued about the same time.

VII. 285, l. 12. 'I have two gems, a diamond and a ruby of great value, with more than a lac of rupees'.

A reference to the text shows that 'with' must be some sort of error for 'worth'. دو دانهٔ الماس و یافوت بیش قبست که ازلک رویه زیاده ارزش دارد (II. 218, 1. 3). Shivāji could not have carried a lac of rupees on his person. Precious stones only constituted portable 'stores of great value' in those days.

VII. 285, l. 8 from foot. Sivāji.....placed his boy in the charge of a Brāhman, named Kabkalas.

The name of this man is said to be a corruption of the Sanskrit 'Kavi Kulesha,' 'Prince of Poets.' (Sarkār, H.A. IV. 252-3), but 'Kalasa' or 'Kalasha' is used in Sanskrit for the globular or oval metallic ornament which is placed on the pinnacles of Hindu temples. Tod tells us that Rāṇā Sanga [Sangrāma] of Chitor was known as the "Kalas (or pinnacle) of Mewar's glory." (A. A. R., I. 299 (old Edition)). It may be as well to note that though in the fourth volume of his History of Aurangzeb, (252-3), Sir J. Sarkār speaks of him as Kavi Kulesha, Prince of Poets, he is styled in the fifth (p. 22) and in the C. H. I. (IV. 283-4), 'Kavi Kalash.'

The Marāthā annalists, however, have, in their 'communal' hatred of the foreign favourite, who was a Kanaujia Brahman from Allāhābād, perverted the name into 'Kalusha,' which signifies 'sin' or 'vice' in Sanskrit. Grant Duff and Elphinstone have followed them and call him 'Kuloosha', but this is only an opprobrious nickname founded on an equivoque. The chroniclers speak of him as a sorcerer, who had, by the

practice of necromantic arts, made Shambhāji the slave of his own will and represent him as Vice or Wickedness Incarnate. His original name is nowhere mentioned and appears to be unknown

Kh. Kh states here that the boy was placed in charge of Kabkalas at Banāras. On page 281, he is said to have been left behind at Allahābād. According to the Marāthā chronicles, however, Shambhāji was left behind neither at Banāras nor at Allahābād, but at Mathura, in charge of three Marāthā Brāhmāns, who were the brothers-in law of Moro Trimal Pingle, Shivāji's Peshwā. 'Kabkalas' could not have been the man, as he was a Qanaujiya, and not a Marāthā Brāhman (Kincaid, loc. cit I 221, Sarkār, Shivāji, 169-170, H. A, IV. 93).

VII 289, l 7 Fath Khān, an Afghān, was appointed governor of the country on the part of Bijāpur.

Fath Khān was not an Afghān but a Sīdi. These Africans were reputed to be the most skilful and daring sailors in Western India Ever since Janjīrā came into the possession of Ahmad Nizām Shāh, about 1490 A. C., its commandant had been a Sīdi. When the Nizāmshāhi Konkan was handed over by Shāh Jahān to Muhammad 'Adil Shāh, Janjīrā was placed in charge of Sīdi 'Ambar, the admiral of the Bījāpur fleet. On his death in 1642, his place was taken by Sīdi Yūsuf who was succeeded in 1655 by this Fath Khān, who also was a Sīdi. Khwāfi Khān him self states that Sīdis Sumbul, Khairiyat and Yāqūt were slaves of Fath Khān and that each of them had ten slaves who were also Sīdis

VII. 294, i 9 Outburst of the Hindu devotees called Satnāmis, who are also known by the name of Mundihs

Manucci explains the nickname and states that they were called [Mundihs or] Shavelings, because they shaved off all the hair from the body, not even sparing the eyebrows. (Storia, II. 167). The Nāgar Chronicler, Ishwardās, represents them in a very unfavourable light and states that they were extremely filthy and wicked, ate pigs and even dogs and saw no blame in sin and immorality. Their religious mysteries are also stigmatized as abominable (Sarkār, H. A. III. 337). Another sect bearing the name, 'Satnāmi', is described in H. Wilson's Account of Hindu Religious Sects, but it must be different, as it was founded only in 1775 A. C. VII. 297, I. 11 There was an old standing grievance in the Emperor's heart respecting Rājā Jaswant's tribute.

There is nothing about 'tribute' in the B I. Text, which reads ما معنان علام على على الله على على على الله على على على على على الله على على الله على على الله على الله على الله على على الله على

The battle at Dehli is stated in the Rajput chronicles to have been fought on 7th Shravana V. S. 1716—4th July 1679. (O. S.) (Duff C. I. 297; M. 'A. 177, l. 13; H. A. III. 377).

VII. 298, 1. 14. Until all doubt was removed by the Rānā of Chitor, who married Ajit Singh to a girl of his family.

The girl was the daughter of Gaj Sinha, a younger brother of the Rinā. (Tod. A. A. R., II. 1010). Ajīt Singh's mother also was an Udaypur princess and the Rinā's niece. She is said to have gone in person to her native home to entreat the Rinā to support her infant son. There can be little doubt that the real Rīni was not killed at Dehli and was able to reach Mīrwār in safety with her son. Any attempt at personation in the case is unthinkable, as it could not have escaped detection.

VII. 299, 1. 21. He [Muhammad Mu'acram] was directed to march against the lake of Anasagar.

אליב ולים (II. 263, 1.8). He was ordered "to encamp (lit. to alight) round the lake", not to march against the piece of water.
VII. 306, l. 19. He surrounded and attacked this place [Bahadurpur],

distant from Aurangābād (1 6 f.f) must be the Ajantā Ghāt or Pass in the Sahyādri, Inhyādri [or 'Anjandudh'] range Fardāpur was half-way between Aurangābād and Burhānpur (p. 498 infi a).

VII. 310, l. 17 There were several sacks of powder in the house

The word in the original is "Is which means" earthen pots" not 'sacks' Lieutenant-Colonel Fitzelarence says that "at times they havehad recourse" in Indian military operations to "thick earthenware pots with fuses and full of powder, the pieces of which wound dreadfully" (Journal of a Route across India to England, Ed 1819, p 246 See also Irvine, A I M 159)

VII. 312 l 7 Three officers in succession fail to take the fortress of Ram Sij

Rāmsej ['Rāma's Bedstead'] lies seven miles north of Nāsik and seven miles south of Dindori also. It stands about 3273 feet above sealevel (B G XVI (Nīsik), 141). The name is wrongly spelt as 'Masīj' at page 52 ante. The M 'Ā notes that Hayāt Khān was sent to attack Rāmsei on 26th Jumādi I 1093 H (129, 11).

VII 314, l 10 Prince Mu'azzam marched from Ahmadnagar to lay siege to the forts of Ram-darr a

This is the Rāmghāt, about 30 miles west of Belgim and the same distance to the north-east of Goa on the old Vengurla-Belgim road (I G XII 218-9) It was the great pass to the upper country from Sāwantwādi, Mālwan, Vengurlā and Goa and the whole tract of country below the Pass was wild, hilly and covered with jungle in the old days (B G XXI (Belgaum), 306) Grant Duff speaks of it as the Ambadurray [Ambā daira?] Ghat, not Rām Ghāt (H M 144), but there is no real difference, as the Rām Ghāt is a pass [Daira] lying a little south of the Ambā Ghāt It is in Lat 15°-52′ N, Long 74°-4′ E (Irvine's Note to Storia, II 287)

The grain called Kūdūn "which acted like poison" on the invaders (1 8 ff) is "Kodo of Kodon, Paspalum fi umentaceum or Sci obiculatum, which is frequently found to have inebriating or narcotic properties, when made into bread But the effects do not last long and inflict no permanent injury" (Elliot, Races, II 373, Watt, Commercial Products of India, 868, 871)

Muhammad Murād Khān, who is spoken of on the last line by Khwāfi Khān, as his 'late brother', was really only a near relative or intimate friend. The word 'birādar' is often used loosely. Muhammad Murād Khān was the son of Muhammad Husain, entitled Murshid Quli Khān (M. U. III. 682, 1.5 f.f.). Khwāfi Khān's father was Khwāja Mīr (207 ante).

VII. 314, l 17 On reaching the village of Sampganio, the fort of the place was invested

Sampgaon lies 18 miles south-east of Belgam Lat 15°-36' N., Long. 74°-50' E (B G XXI (Belgaum), p 600)

VII. 316, l. 13 from foot. The parganas of Sīram, Rāmgīr, etc. which had been taken by force,........ from the servants of the Imperial throne, must be restored [by Abul Hasan of Golkonda].

These parganas are said to have been dependent on Zafarnagar. (315 supra). Sīram is eight miles east of Mālkhed, which is 16 miles distant from Wāḍi Junction on the Nizām's State Railway. These places are again mentioned on 318 and 321 infra, but there, the names are given as Sīram and Kīr or Khīr. Sir J. Sarkār reads the second name as 'Mālkhed' (H. A., IV. 340, 349), but Bernier states that "the fortress of Ramguyre, with the whole of its appurtenances was ceded by Abdulla Qutb Shāh, as part of the dowry of his daughter, who was by the treaty of 1656-57, to be married to Prince Muḥammad Sultan.' (Constable's Edit. 21-22). See also Kh. Kh. (Text. I. 749, l. 12), who mentions Rāmgīr in the same connection and the C.H.I. (IV. 270). 'Ramguyre' which had been ceded then must have been now re-occupied by Abul Ḥasan. There is a place called Rāmgīr in Elgandal. Lat. 18°-35' N., Long. 79°-35' E. Constable, 32 A b, about 110 miles north-east of Ḥaidarābād, but it is too far off from Sīram.

VII. 321, l. 17. Rustam Rās (sic) also who had reached the house, was killed.

Rustam Rão was the incongruous and hybrid title given by Abu-l-Hasan to Yenganna, who was a nephew of the Minister Mādanna. (Sarkār, H. A., IV. 334). Mādanna himself had the title of 'Sūrya Prakāsh Rão'. (*Ibid*). His brother's name is written 'Ākanna' and also 'Venkanna'. VII. 323, l. 8 from foot. Hazrat Banda-nawāz Saiyid Muhammad

The Saint's epithet is Gīsūdarāz, 'Long-haired', not Gisū, which signifies 'hair' only. The Text has it right. (II. 322, l. 2 f.f.). His real name was Muḥammad Ṣadru-d-dīn Muḥammad Ḥusaini and he is said to have been born in 1321 at Dehli and died at Gulbarga in 1432 A. C. (Beale, Miftāh, 113; Herklots, Ed. Crooke, 141, 210). A mosque, a Sarāi and a college, all built by Aurangzeb in 1687 A. C., near the shrine of the

Gīsū.

VII. 343, l. 3 from foot In the beginning of this year [1103 H.],

Aurangzeb moved from Gürgäon and Shikärpur to Bidr and after a while to Gulka

Khwafi Khan's chronology is, as usual, faulty Dowson points out in the footnote that the previous march had been from Aklus to Gurgaon [Koregaon] (Text, 393, 1 1 f f) Aurangzeb left Bijapur on 14th December 1688 (1st Rab'i I 1100 H.), and reached Koregaon, 12 miles north-east of Poona, by way of Aklüj and Bahadurgarh on 3rd March 1689 21st Jumadı I. He left Koregaon for Bıjapur again in Rab'i I 1101 H (December) and encamped at Galgala on 19th Sh'aban, 21st May 1690 He left Galgala on 4th Jumadi II 1102 H (March 1691) and was in the environs of Bijāpur upto Sha'bān 1103 H May 1692 and thereafter at Galgala upto March 1695 (M'A 325, 333, 335, 338, 345, Sarkar, H A, V. 5-6, 28) 'Bidr' is not Bidar, but a village called Bidri (M 'A 383, 17), which is seventeen Los distant from Bijapur (M U I 288). Aurangzeb arrived there on 10th Jumadi I 1101 H (M'A, 333, 17) 'Gulka'is Galgala, on the southern bank of the Ghatprabha, thirty-two miles southwest of Bijāpui It is 14 miles north of Kalādgi, and the latter is 45 miles south-west of Bijapui (B G XXIII (Bijapur), pp 438, 648, 657) The Mughal historians speak of 'Galgala' by the new name of 'Qutbābād' (M ' Å 345, 370).

VII 345, ? 3 from foot They also use bits of copper which they call buzing, and four of these buzings pass for a fulus

What Khwasi Khan calls 'buzurg' is the Portuguese 'Bazarucco,' a coin of varying value and metal (copper, tin, lead and tutenague), the etymology of which is uncertain. Some derive it from the Pers 'Bazīr,' 'market' and the Canarese 'Rukka' 'money' and this is the opinion of Gray (Travels of Pyrard de Laval, II 68) and Burnell (Travels of Linschoten, IL 143), but other authors, e g C P Brown (Madras Glossary, s v) and Edward Thomas trace it to the Canarese Badaga, 'base' and Rukha, 'money' Molesworth says that in Marathi, Rukha signifies 1/12th of an anna Khwāsi Khān's etymology seems to be a striving after meaning, though 'Budrukh', a dialectic corruption of 'Buzurg', is affixed to the names of many villages in the Dekkan See H J, s v Bndgrook

VII 346, l 1 When the people [the Portuguese] there [in Goa] marry, the girl is given as the doiry

There is something manifestly wrong here What Khwafi Khan really says is that they [the Portuguese] give villages (ديرات) in dowry (مهار) when they give their daughters away in mairiage (II 402, 1.4)

VII 350, l 1. Capture of a royal ship called the Ganj-Sawai by the English

This ship was the property of the Emperor himself and was taken between Bombay and Daman by an English pirate named Francis Bridgman alias Avory or Evory in or about September 1695 A. C. (Elphinstone, H. I. 674; Sarkār, H. A., V. 343-6).

VII. 352, l. 8 from foot. I found drawn up in ranks on both sides nearly seven thousand musketeers, dressed and accounted as for a review.

The whole picture is grossly overdrawn. When a Dutch fleet attempted to surprise the island of Bombay in 1673, the total force which Governor Aungier could muster was 300 European and 400 topasses or half-caste troops under English officers and 300 Bhundāries armed with clubs and this, remarks Orme, was a "display of force far above the reality." (Hunter, History of British India, II. 216). In the recently published Account of Bombay written by John Burnell in 1710, it is stated that the total military force of the island consisted of five companies of Europeans, Topasses and Cofferes [African slaves from Madagascar] and eight companies of Sepoys. He puts the number of "the whole soldiery in constant service" at only 1200 men. (Hakluyt Society, 1933, Ed. S.T. Shepherd, 13-14).

VII. 353, l. 18. We got those scars at the time of the siege of Ṣādi Yākūt. The reference must be to the siege of Bombay by Yāqūt Khān of Janjīrā which was begun in 1689.

VII. 353, l. 7 from foot. Now they have gone and taken part with the dingmars or Sakanas, who lay violent hands on ships upon the sea and with them they are serving as pirates.

These 'Sakanas' are really the pirates who are called 'Sanganians' by European writers." The next province to Cutchnaggen is Sangania. Their seaport is Baet [Jagat or Dwārkā], very commodious and secure. They admit of no trade, but practice piracy." (Alexander Hamilton in Pinkerton's Collection of Voyages, VIII. 310).

VII. 355, l. 4. The Sakanās also, who are sometimes called bawārīl, a lawless set of men belonging to Sūrat, in the province of Ahmadābād, are notorious for their piracies.

و همچنان از قوم سکنه که بواریل نیز زبان زد است و از مفسدان سورت تعلفهٔ احمد آباد (II. 428, 1. 4).

The real name is varil, recte, Vadhel and they belonged, not to Sirat, but to Sorath, the Kāthiāwād coast. The initial φ is not part of the name, but the preposition.

Abu-l-Fazl says in his account of the Sarkār of Sorath that Jagat, (also called Dwārkā), Arāmra and Dhāri belong to the Bādhel tribe. (Āīn, Tr. II. 244. See also Ibid, 248). The Vāḍhels claim to be descended from two Rāṭhoḍ brothers, expelled from Mārwāḍ, who cut off the head of Bhojrāj, the Chāvḍa chief of Okhāmanḍal, towards the end of the 13th century. Their names were Verāvalji and Vejalji, but they assumed or were given the name 'Vāḍhel', from the Sansk. Vadh, to cut or slay. Their most famous descendant was Sāngaṇji, who extended his domi-

nions as far as Khambháha, forty miles east of Dwārkā, and made him self notorious by his "piratical expeditions" and "freebooting excursions into the territory of his neighbours" His son Bhāmji rendered himself "so obnoxious to the Musalman rulers of Gujarāt, by plundering pilgrim vessels on their voyage to Mekka," that Sultan Mahmūd Begada led a punitive expedition against him and sacked Dwārkā and Arāmdā In 1592 A C, Shivā Vādhel of Arāmdā offered an asylum to Muzaffar III of Gujarāt and was defeated and slain in a battle with his Mughal pursuers. He was succeeded by another Sānganji, whose grandson Akherājji, is said to have died about 1664 A.C. The piracies and abominable cruelties of the Vādhels or 'Sanganes', became at last so intolerable that between 1715 and 1718 A C, "the chiefs of Naw īnagar, Gondal and Porbandar had to send a combined force which inflicted condign punishment upon them" (B. G. VIII (Kāthrīwār), 590-593, Forbes, Rās Mālā, I. 293)

The 'Sakanas,' of Khwāfi Khān are really the 'Sanganas,' Sanganas' or 'Sanganes' of Fiyer, (New India, Folio Edit, 1698, p. 218), Ovington (Voyage to Suratt, Ed. 1696, p. 162), Manucci (Storia, II 227), and other European writers of the 17th and 18th centuries Some writers derive the name from Sindān, i e Sanjān, 88 miles north of Bombay, but the real etymology is that which I have indicated—from Sāngan—their first most formidable and famous chief

VII 359, l 2 Soon afterwards, Prince Muhammad 'Azum was ordered with his sons to Kābul

It was not Prince 'Azam, but the Heir-apparent, Prince Mu'azzam, who was appointed Governor of the Punjāb and Kābul at this time (Text, II 444, 14)

Mu'azzam is said by Kh Kh (358 ante) to have been released after seven years of restraint in the 39th year, but his chronology is inconsistent and erratic here, as in many other places. He also states (327 ante), that the Prince was interned on 18th Rab'i II in the 29th year. The correct date of his ariest was 18th Rabi II 1098 H (21st February 1687) and that of his release, 4th Zil-q'ad 1102 H (M 'Ā 292, 1 3 f f, 343, 1 11)

VII 360, l 4. Several years before, Santā had thrown a brother of Nāgoji under the feet of an elephant and this had produced a mortal hatred Under the guidance of his wife, he led a party in pursuit of Santā

According to other accounts, the man put to death by Santā was Amrit Rāo Nimbālkai. He was not, as Khwāfi Khān and the M 'Ā state, the brother of Nāgoji Māne, (Deshmukh of Mhāsvad), but of Nāgoji's wife, Rādhikā Bāi It was not Nāgoji who pursued Santāji, but another brother of Nāgoji's wife. As the woman had vowed to take vengeance for Amrit Rāo's death, she compelled another of her brothers to pursue Santāji to the (Shambhu) Mahādev Hills in Satāra district and it was this man who cut off Santāji's head at some time in June 1697, not 1694-5 Giant Duff (H. M. p. 172) and Kincaid (II 92) have followed Khwāfi

Khān, but Sir Jadu Nāth Sarkār prefers the other version. (H. A., V. VII, 368, l. 9 from foot.

Nearly one lac and 80,000 rupees were VII. 362, l. 9 from foot. raised from the jagirs. 126-7).

The B. I. text has ' one lac and eight (هشت) thousand, (458, 1.5), which also must be wrong. The right reading seems to be ., twenty thousand. A few lines lower down, it is stated that the Mahrattas actually got 140,000 rupees instead of the 80,000, which were really due to them, out of the promised ransom of two lacs. Now 200,000-80,000=120,000. The amount raised in the first instance from the $j\bar{a}g\bar{v}rs$ must have been there-

His [Aurangzeb's] camp had now remained at Islamfore one lac and twenty thousand rupees. VII. 363, l. 19.

This was the Musalman name given to 'Brahmapuri', which lies about 20 miles south-east of Pandharpur. (M. A. 373, l. 11; Grant Duff, 167). Khwafi Khan states here (Chronicle of the 43rd year) that Aurangzeb had now remained at Islampuri for four years, but at p. 346 ante, the Emperor is said to have taken up his quarters at Brahmapuri in the 37th year. Aurangzeb was encamped at Brahmapuri from the 17th of Shawwal 1106 H. to 5th Jumādi I. 1111 A. H., i. e. from May 1695 to the end of 1699 A.C. from the beginning of the 39th to the middle of the 43rd year.

VII. 364, 1. 6. The army marched towards the fort of Basant-garh.

Basantgarh, lies seven miles north-west of Karhīd in Satārā district. (B. G. XIX. (Satāra), p. 238). The M. U. says that it is three kos, about six or seven miles, south of Maisuri or Masur. (I. 499, 1.1).

VII. 364, l. 8. Prince Muhammad 'Azam Shāh came, in obedience to

Dowson observes in the footnote to page 383 infra, that Bīrgānw and Bahadurgarh have not been traced in the maps. Bahadurgarh was the name given to Birganw, Recte, Peduaon, by Aurangzeb's fosterbrother, Bahadurkhan, who established a Cantonment here which "continued to be for forty years one of the principal depots of the Mughal Army." (Grant Duff, H.M., 114). See my Note on VII. 337, 1. 6 f. f.

VII. 368, l. 9 from foot. The name of Parli was changed to Nauras-

The reason was that Parli Fort had been built by Ibrāhīm 'Ādil Shāh of Bījāpur in 1035 H. Ibrāhīm used to call every new thing 'Nauras'. For instance, a new town founded by him near Bijāpur was called 'Nauraspur'. A copper coin struck by him was named 'Dam-i-Nauras' and a book composed by the Court-poet Zuhuri was entitled 'Kitāb-i-Nauras '. (M. 'Ā. 428, l. 5). Ibrāhīm's contemporary, the Emperor Jahangir, states that Ibrahim used to call the verses in Hindi or Durpats, [Recte, Dhrupad], which he was fond of composing, 'Nauras.' (T. J. 183, 1.20; Tr. I. 272). He is also said to have written a treatise on Music.

'Nauras' (Rieu, Catalogue, II 741 b)

As Satārā which was conquered about the same time was renamed 'Azamtārā in honour of Prince 'Āzam, so Parli was styled 'Nauras Tāra,' for the sake of assonance, after 'Nauras', the 'takhallus' of its builder, Ibrāhīm 'Ādil Shāh The correct date was 3rd Muharram 1112 H. 44th year, not 43rd, as in Kh Kh (M.'Ā 427, last line, Sarkār, H A., V. 168).

VII 369, l 1 In the middle of Safar, the army reached an obscure fort.

This was 'Bhūshangad'i '(M. 'Ā 428, l. 13) It lies about seven miles south of Aundh and about thirty miles south-east of Satārā. The year was the 44th, not 43rd (1112 A. H.) (Sarkār, V 170 Note)

VII. 370, l 4 The [royal] army reached Püngarh, a fort connected with Panhāla

The second letter should be pronounced as a consonant. 'Pavangarh' is the sister fort of Panhāla or Parnāla, near Kolhāpur. Thornton says that it is 64 miles south of Satārā in Lat 16°-47' N., Long 74°-12' E 'Kahāwan' (1 19) is really, Khatāu, 25 miles east of Satārā

VII 371, l. 1 Ambā Ghāt took twelve days to reach

The Ambā Ghāt is five miles north of Khelnā and about 35 miles north-west of Kolhāpur (B G XXIV. 2-5). It leads from Ratnāgiri to Kolhāpur (I G. XII 218)

The new name given to Parnāla or Panhāla was, according to the M'Ā (439, 440, 442), not 'Banī Shāh Darak', as it is printed here, but 'Nabi Shāh Drug' The Mughal alias of Rājgarh also is stated in the M'Ā. (486, 497, 516) to have been Nabi Shāh Garh not Banī Shah Garh as in Kh Kh (373 infra)

Paras Rām (19 ff.), the Commandant of Khelnā, was Parashu Rām Trimbak the *Pratīnīdhī* He was the ancestor of the present chief of Aundh

VII 372, l. 10 The name of the fort [of Khelnā] was altered to Sakh-kharalanā

VII 376, l 11. The enemy effected a complete overthrow of the Imperial Army.

Kh. Kh. puts this defeat into 1114 H, but the event really happened towards the end of A H 1117, about 15th March 1706 The site was the Ghat or Ford of Baba Piara, near the village of Ratanpur in Raipipla

State. (Mirāt-i-Ahmadi, I. i. 378-380; Sarkār, A. H., V. 432).

VII. 377, 1. 10. The tribe of Bedar, which is the Hindi for 'fearless'. This is an example of the striving after meaning which is characteristic of folk-etymology. The real name is 'Byaduru', 'Bairad' or 'Berad', which means 'hunter' in Canarese. (B. G. (Dhārwār), p. 184). Sherring mentions the Berads as "a tribe in Mysore and the Southern Mahratta Country, who are mostly huntsmen, dark, tall, and warlike and who were largely employed as soldiers in Hyder's wars." (Hindu Tribes and Castes. II. 321; III. 153). Sir J. Sarkār suggests that Khwāfi Khān's derivation is only a pun or conscious play upon words, (H. A., V. 215), but this supposition seems to me to be largely invalidated by the fact that he always calls them Bidar and never speaks of them as 'Berad'. He was ignorant of the true designation or spelling, as well as of the real origin of the name and his hybrid etymology is put forward in all seriousness as a philological dictum which he himself believed to be sound and incontrovertible. It is also relevant to note that they are called 'Bedar' in the M. 'A., the M. U. and other Musalman histories, and that the Hindi word for 'fearless' is not 'Bidar' but 'Nidar'. Bi or Be is Persian.

VII. 377, l. 14. And Pādshāh Khānzādah Khān, son of Ruhullah Khān was sent to subdue his fort of Sagar.

'Pādshāh Khānzāda Khān' is an impossible collocation. A reference to the text shows that we should read the sentence thus: "And the Pādshāh [Aurangzeb] appointed Khānzāda Khān, son of Ruḥulla Khān, to conquer the fort of Saggar." (524, l. 10). See also M. 'Ā. 305, l. 10 f.f.

Aurangzeb's Court is said on l. 10 f. f. to have been at 'Ahmadābād' before the Bījāpur affair. But this is a printer's error for 'Aḥmadnagar'. See Text, II. 524, l. 7 f. f., where the history of Paryā Nāik is again related and the name of the place is correctly given as 'Aḥmadnagar'.

VII. 388, l. 8. Muḥammad Murād Khān, who was Wāk'i-nigār of all the province of Ahmadābād and was faujdār of Thānesar and Kūdra.

Sic also in the B. I. Text (II. 566, l. 4), but both names are wrong. The places meant are Thāsra and Godhra. Thāsra is now in Kairā [Kheḍā] district, Bombay Presidency, and lies about 36 miles east of

few specimens are still in existence. The subject is discussed at some length in my H. S. M N. 53-80

VII 391, l. 8 The Prince [Kām Bakhsh] sent him [Ahsan Khān] to lay siege to Karnūl, and directed his youngest son to accompany him as a check (tora)

Kām Bakhsh had three sons The eldest was Muhiu-s-Sunnat, who was born about 1110 A H and must have been about ten years old at this time, i e 1120 A H The others, Firozmand and Bārikulla, were younger still and mere children (Irvine, LM, I 66) It is scarcely likely that a boy of five or six should have been deputed to act as a "check" on a masterful commander like Ahsan Khān and it is clear that 'tora' must have some other meaning here

VII. 393, l. 1 Directions were given that the new rupee should be increased half a masha in weight.

This is a very interesting reference to one of the numismatic freaks of Bahādur Shāh, Shāh 'Ālam I The matter has been explained and discussed in my paper in the Num Supp XXVIII to the J A S B XIII, New Series, (1917), pp 67-69.

VII 395, l 2 After crossing the river (Nerbudda) at Handiya, he arrived at Doraha

This is not the Dorāha near Sirhind or Sihrind, but Dorāha, about 65 miles north of Hāndiya or Hindia and 18 miles north-west of Bhopāl It lies on the route from Hīndia to Sironj and is about 64 miles distant from the latter. (Chihār Gulshan in I A exv) It is shown in Constable, 27 C d, but the name is wrongly printed as 'Duraiba' instead of 'Duraiha' or 'Duraha'.

Kokarmunda (1 15) is on the north bank of the Tapti on the frontier of Rajpipla State, 62 miles north-west of Dhulia It was an outpost on the frontiers of Khandesh and Rajpipla (Th and B G XII, (Khandesh), p 452) It is shown on the Map in Bayley's Gujarat

VII. 395, l 13 Sāhū then went on to a Mahratta named Ambū, but more famous under the name of Pānd.

The real name of this russian was Amrit Rāo Kadam Bandé (or Bhandé). 'Pānd' is a miswriting of Bandé. (Irvine, L. M., II. 162 note). The name of Kantāji Kadam Bandé occurs in the Mahratta histories. Bhīm Sen speaks of a man called 'Inū Mānd', a former liquor seller of Khāndesh, who had taken to a very profitable course of highway robbery and sacked Baroda in league with Dhanāji Jādhav and other Marāthās in 1706. (Tārīkh-i-Dilkushā quoted in Sarkār, H. A., V. 251). This 'Inū [ii.e. for jil] Mānd' may be the same as Ambū Pānd of Kh. Kh.

VII. 400, l. 11. He looked fiercely at that dog, Rustam 'Ali Khān.

Sic in the Text (II. 597, l. 7 f.f.), but this man's title is given as Rustam Dil Khān, in the Tārīkh-i-Irādat Khān. (543, 547 infra). Mr. Irvine also calls him Rustam Dil, and cites several other authorities for that reading. (L. M., I. 27, 33).

VII. 403, 1. 4. One of the most acceptable and beneficial measures of the Khān-i-Khānān was the relief he afforded in that oppressive grievance, the feed of the cattle of the Mansabdārs.

Text II, 602, l. 12; 603, l. 9. This is a very difficult passage and Dowson himself admits that "parts of it are involved, and the meaning is not always clear". Mr. Irvine has thought it necessary to give a translation of his own in the A. I. M. p. 21, because, as he says, 'Dowson could make nothing of it.'

VII. 404, 1. 2. He wrote a book, Al Hāmiya, upon the spiritual life and Sūfi mysticism,... which in the opinions of controversialists, passes beyond the bounds of the Law upon some points.

is devoid of any meaning. According to the M. U. (III. 675, l. 14), the correct title is المائد الم

VII. 406, l. 13. Kām Bakhsh arrived at Burhānpur,......where he was detained by the swollen state of the Tapti.......

Marching from thence by way of Malkāpur and Nānder, he had got near Haidarābād by the end of Shawwāl.

There is great confusion here. A reference to the Text (II. 618-9),

shows that it was not Kām Bakhsh, who arrived at Burhānpur, or was detained there or who marched to Haidarābād by way of Malkāpur, but his brother and antagonist, Bahādur Shāh, Shāh 'Ālam I. It was the latter who was marching south from Dehli via Burhānpur, Malkāpur and Nānder to encounter Kām Bakhsh at Haidarābād. (L M, I. 58)

VII. 406, l 18 Bahādur Shāh had with him nearly 8000 horse

A cipher has been inadvertently dropped and the correct number must be 80,000, as it is in the Text, II. 619, 1 12 See also L. M., I 61

VII. 407, l 11 from foot. European and Greek surgeons were appointed to attend them

at all, either by race or by nationality They were in reality Musalmans trained in the Yūnāni, e the Greek or rather Greco-Roman system of Medicine and Surgery Arabian Medicine is, for the most part, founded on the works of Hippocrates عاليوس and Galen حاليوس and their disciples The mistake is again committed at 425 unfra.

VII. 410, l 8 from foot. The freebooter Pap Rat

The name is spelt in the Text (II 630, 1 3 ff) and also in the M U. (I 255, 256, 257) The real name must be $P\bar{a}pr\bar{a}$ and the conversion of the last two letters of the name into the adjunct or title 'Rāi' is a misleading emendation 'Rāi' was not so cheap then as it is now, and was a title which was not allowed to be borne by Hindus, except when specially conferred by the State See the story told in L. M, I 138

VII 411, l 12 Pāp Rāi went to the village of Shāhpur in the pargana of Narganda, Sarkār of Bhūngīr

This 'Narganda' and probably the 'Tarıkanda' also of p 412, l 11 infra must be the 'Nedikonda' of Constable's Atlas, 32 A c. Kulpāk and Bhongir lie south of it. Kaulās is thirty miles north of Bīdar.

As Shāhpui is said to have been in the pargana of 'Naiganda' and the new fort of 'Tarīkanda' is stated to have been only four kos distant from Shāhpur, Tarkanda is, most probably, only another form of 'Narīganda' or 'Nadīkanda' In the M U (I 255, 256, 257), the name is spelt 'Tarīkanda' Nedīkonda lies about fifteen miles north-east of Kulpāk This 'Narganda' can have nothing to do with 'Nargund' in Dhārwār

VII. 414, l 9 from foot All his followers kept shouting Sacha Padshah and Fathdaras

This 'Sachā Pādshāh' was the Sikh Guru Banda 'Fathdaras' signifies 'May you behold victory' (Irvine, L. M., I. 110) The Sikh Guru Tegh Bahādur, who was put to death by the orders of Aurangzeb in 1675 A.C., is said to have been the first to arrogate to himself the title of 'Sachā Pādshāh' and to have thereby given mortal offence to that Emperor (Ibid, I. 79) After Guru Govind was assassinated, a man who greatly resembled him, appeared in the Punjab, declaring that he was the Guru Govind miraculously brought back to life This man was Banda Bairāgi and he styled himself Sachā Pādshāh, the True King.

VII. 416, l. 9. Sarangpur......Jalālābād in the Punjāb.

'Sārangpur' must be an error for 'Sahāranpur'. The B.I. Text (II. 655, l. 11) has the name correctly. This Jalālābād is now in Muzaffarnagar district, U.P., and lies about 30 miles south of Sahāranpur or 20 west of Deoband. Constable, 25 B c. Rāhūn (418, l.7), which was seven kos from Sultānpur, is marked in Constable, 25 B b. Sultānpur, 40 miles west of Ludhiānā, is the place of that name in Kapurthalā State. *Ibid*, 25 A b. The distance between these two places is under-estimated.

VII. 419, l. 9 from foot. After leaving Lāhor, they returned to......... Shādhūra and Karnāl.

'Shādhūra' is Sadhaura, about thirty miles north-east of Thānesar, which latter is about 22 miles north-west of Karnāl.

VII. 420, footnote. The formula was "Ali is the saint of God and the heir of the Prophet of God."

'Saint of God' is both amphibological and obscure. The word used is which means 'intimate friend, favourite, beloved etc.', according to the Dictionaries. But it has been the subject of interminable discussion and disputation among the Musalman theologians. Abu-l-Fazl, after giving a summary of the discordant opinions, states the outcome to be that Wali means "one who has attained to the knowledge of the Supreme Being". (Āin, Tr. III. 350). 'Waṣi' literally means 'Executor' [Scil. of the Prophet's testament or will]. Shi'as speak of 'Ali as 'Shāh-i-Wilāyat' and Shāh 'Abbās I. had the words "Banda-i-Shāh-i-Wilāyat 'Abbās", l'Abbās, the slave of the Lord of the Walīship] engraved on the exceedingly fine ruby, which he sent as a present to Jahāngīr. (T. J. 325, l. 5; Tr. II. 195). This phrase is inscribed on the coins of 'Abbās II. also and of Shāh Sulaimān, his son. (Oliver, The Coins of the Ṣāfavi Dynasty in J.A.S.B. 1887. (LVI), p. 68).

When Uljāiltu Khān was converted in 709 H. to the Shī'a faith, he ordered the words على ولي "'Ali is the Wali of God", to be stamped on the coinage, which earned him the honorific title of Muḥammad Khudābanda from the followers of that sect, but the abusive nickname of Kharbanda, 'Slave of the Ass,' from their antagonists. (Shajrat, Tr. 290-1). Bahādur Shāh Shāh 'Ālam I. claimed to be a Sayyid through his mother Nawāb Bāi. Her real father was said to be a descendant of the Saint 'Abdul Qādir Jīlāni, named Sayyid Shāh Mīr, though she had been made to pass as a daughter of the Hindu Rājā of Kishtwār. (Kh. Kh. II. 594, 604; Irvine, L. M., I. 136).

VII. 422, l. 8. Tulasi Băi......came demanding payment of the Chauth to the town of Rānwīr, seven kos from Burhānpur.

Recte, 'Rāver' in Khāndesh, now a station on the G. I. P. Railway, twelve miles south-west of Burhānpur and twenty-two north-east of Bhusāwal. Constable, 31 D a.

VII. 424, l. 6. The infidels retreated to Longarh, which is near

the hills belonging to the Barfi Rajā

The exact situation of this fort has not been satisfactorily determined Mr Irvine says that it was about half way between the towns of Nāhan and Sadhaura and about twelve miles to the north-east of the latter (L. M., I 1167). In the I G., however, it is identified with Gurdāspur (XII 393) The name of the Barfi Rājā, i e, the Rājā of Nāhan or Sirmūr was Bhūp Prakāsh The man who deputised for the Guru was a tobacco seller called Gulāb Khatri (M. U III. 673, 14, Irvine, Ib).

VII 427, l 9 It is said that the Government officials took nearly nine lacs of rupees out of his treasury

The real story is left untold Only the first sentence of the paragraph devoted to the anecdote is translated by Dowson, and all the rest omitted. The gist of the matter is that the culprits abstracted nine lacs of rupees from the bags in the treasury and craftily substituted copper coins in their stead. Ghāziu-d-dīn Khān, on coming to know of the affair, made no fuss about it, but managed matters so adroitly, that the delinquents made speedy and silent restitution and surreptitiously replaced the rupees which had been purloined (Text, II. 681, 1 12) The story is related to show that the Khān was "a disciplinarian of commanding dignity and power, a silent man, such has as rarely been seen or heard of among the men of Tūrān"

VII 428, l 23 and footnote On the night of the 8th of the month, [Muharram] (1123 H), the Emperor died.

Khwāfi Khān puts the death of Shāh 'Ālam I into 1123 H. and Dowson accepts his statement on the ground that he is consistent in his dates But this consistency is only in error and many wrongs do not make a right There can be no doubt that the year was 1124, as it is given by Irādat Khān (556 infra) and the Siyaru-l-Mutaākhirīn (Tr I. 22) The numismatic evidence also leaves no doubt on that head See my H S M. N. 279-80 and my Note to Article 324 in Num Supp. XLV. to the J. A S. B XXX, 1934, p 92 (Vide also L M, I 135).

VII 432, l 3 He sent Muhammad Karīm and Prince Humāyūn Bakht, who were only nine or ten years old, to Delhi.

The relative clause applies correctly to Humāyūn Bakht only and the verb should be in the singular Muḥammad Karīm was, as is explicitly stated at 438 infra, Farrukhsiyar's elder brother According to the M. 'Ā. (181, 1 2 ff), Muhammad Karīm was born sometime before 7th Ramazān 1090 A H., on which day the news of his birth reached Aurangzeb, Farrukhsiyar was born on 9th Ramazān 1094 H and he was thirty-eight years old when he was put to death in 1131 H (481 infra, note, Rieu, Catalogue, I 273) Muhammad Karīm must have been therefore about thirty-four years and not nine or ten only, in 1124 H. See also Irvine, L M, I 143. Humāyūn Bakht's birth must be placed in 1117 H, as he is said to have been forty years of age at his death in 1157 H. (Ibid, I 145).

VII. 432, l. 5 from foot. The brother of Lāl Kunwar was named Sūbedār of Āgra.

Lāl Kunwar was the daughter of Khasūsiyat Khān Kalāwant, (Musician), who is said, in the Hadāqatu-l-Aqālām, to have been a descendent of Miyān Tānsen. (L.M., I. 180 n). It is hardly correct to speak of her as "a vulgar, thoughtless, dancing girl from the streets," as in the C. H. I. IV. 328.

VII. 434, 1. 13. He now sent against them his son A'azzu-d-dîn Khān with 5000 horse.

Delete 'Khān'. It is not in the text (II. 697, l. 11). Princes of the blood royal were not called Khāns, but Sultāns or Shāhzādās. 5,000 also is wrong. It should be 50,000 as it is in the Text (II. 697, l. 12). At page 390, l. 8 f.f., the title 'Khān' is similarly affixed to the name of Aurangzeb's son Muḥammad 'Azam. The text is free from the error. (II. 570, l. 10).

VII. 439, 1. 20. Thereupon Farrukhsiyar, in the beginning of Rab'īu-l-awwal 1123 A. H., struck coins.

The year is wrongly given. Farrukhsiyar heard of Bahādurshāh's death near Paṭnā on 7th Ṣafar 1124 H. He proclaimed his father 'Azīmush-Ṣhān Emperor and had coins struck in his name on the 13th. 'Azīm had been drowned four days before on the 9th, but Farrukhsiyar heard of the event only on the 29th and announced his own accession immediately afterwards. (L. M., I. 193 and note). According to the contemporary Farrukhsiyarnāma of Mīr Muḥammad Aḥsan Ijād, Farrukhsiyar was proclaimed at Paṭna on the 29th of Ṣafar 1124 H. He crossed the Jumna on 13th Zī-l-qʻad and defeated Jahāndār's army on 13th Zī-l-ḥijja 1124. (Rieu, Catalogue, I. 273).

The numismatic evidence also is decisively in favour of 1124 H. Coins struck by Shāh 'Alam I in 1124 are extant. All the known mintages of 'Azīmu-sh-shān bear the same date and the issues of Jahāndār Shāh exhibit the identical year. How then could Farrukhsiyar have struck coins when his father and grandfather were both alive? See Whitehead, Punjab Museum Catalogue, pp. 286-292; H. S. M. N. 281 and my note in Num. Supp. No. XLV to the J. A. S. B. XXX, (1934), p. 92.

VII. 442, l. 10. Farrukhsiyar encamped in the environs of Dehli on the 11th Muharram 1124 A. H. (Feb. 9th, 1712).

The year should be 1125 H. and the Julian correspondence 27th January (Old Style) or 6th February 1713 New Style. *Vide* the preceding note and L. M., I. 246.

VII. 445, l. 5. Farrukhsiyar entered the city and fort on the 17th Muharram (15th Feb. 1712).

As the Hijra year was 1125 and not 1124, as postulated by Dowson, the correct Julian date must be 2nd February, 1713 (O. S.) or 18th February (N. S.). So on l. 17, p. 446 *infra* also, the official date of the accession of Farrukhsiyar should be corrected to 1st Rab'i I. 1124.

VII 447, l. 23 A grain-dealer named Ratan Chand.

The word used is Jil. (II 739, 16), which does not necessarily mean 'grain-dealer' It is frequently used by Musalman writers in India for members of the Baniya caste in general Abu-l-Fazl writes that there is in India "a caste of Vaisyas called Banik, more commonly called Baniya The Persians name them Baqqal and of these there are 84 divisions" (Ain, Tr III 118). Ratan Chand was an Agarwal Baniya and a native of the town of Jansath, where his ruined haveli still exists and is in the possession of his descendants (L M, I. 291 note)

VII. 452, l. 2 from foot. He [Daud Khan] placed Hiraman Baksariya . . . in charge of his advanced force.

The Baksariyas are so called from Baksar, (Buxar) on the Ganges, near the Bhojpur country. Mr. Irvine tells us that "the region is one which still supplies the finest sepoys in our Hindustani regiments. Bhojpur shared with Oudh the supply of men to our native army in Bengal from its earliest to its latest days. They had already been accustomed to serve as match-lock men and guiners in the army of the Mughals. In the historians of the 18th century, the garrison-artillery are usually designated 'Baksariyah'. (A. I. M. 168-9) See also Yule, H. J. s. v. Buxerry.

VII 456, l 12 from foot [The Sikhs] ravaged the country from Lähor to Sihrind, otherwise called Sirhind

Readers who are interested in the niceties of nomenclature and orthographic exactitude in the transliteration of place-names may be referred to my article on this subject in Num Supp. No XXXI to the J A S B 1920, pp 335-7

VII 460, last line Asad Khan Karam mālu

in the Text (II 771, last line), but it is generally written وَمَالُو اللهِ أَلُو اللهِ أَلُو اللهِ أَلُو الله Qarāmānlu, as in the M. 'Ā (27, 1 16) and (M U I 310, last line) أناء said to mean 'of' in Turki. Cf Shāmlu, Rūmlu, Istājlu, Osmānlu (or Osmānli), Āq-qūīnlu, (of the White Sheep), Qarāquīnlu (of the Black Sheep)

VII 466, l 9 from foot He [Husain 'Ali Khān] availed himself of the services of a Brahman named Sankrāji

This was Shankrāji Malhār Nargūndkar (the Sachīv), who is again mentioned at 499, 500 infra. He is said there to have been one of Shāhu's ministers. There was another Shankrāji, whose father's name was Nārāyan and whose surname was Gandekar (Grant Duff, H. M. 188). Jamnāji (l. 2 f.f.) should be Chimnāji, the second son of Bālāji Vishvanāth and the younger brother of the Peshwā Bāji Rāo I (Ibid, 197, 209). VII 472, l. 11. Santā and several other Mahratta chiefs vent with

This was not Santāji Ghorpade, but Santāji Bhoslay, who is said to have been a natural son of Parsoji Bhoslay (Grant Duff, H. M 199 and

note). He was killed during the riots in Dehli, q. v. 477 infra. VII. 475, I. 2. No one had the force to speak a friendly word to him

"Whose head was mulled" has no sense or meaning here. الم عدامة من معاملة من معاملة من معاملة من معاملة من معاملة من المعاملة من المعاملة من المعاملة من المعاملة الم the courage to make his tongue associate itself with (i. e. utter) that hidden secret." The word is not - head, but - secret and Khwafi Khān uses the synonymous phrase راز رادر " closely-kept secret" on the

VII. 475, 1. 12. If the nominations to the artillery and to the office of the President of the Council teere made etc.

The words in the text are خواصان خاص و خواصان خواصان عامل و داروغكى دروان خاص و خواصان عامل و خواصان عامل و داروغكى دروان خاص و خواصان عامل و داروغكى دروان خاص و خواصان عامل و داروغكى دروان خاص و خواصان عامل دروان خاص دروان (805, 1, 2 f. f.). This 'Dirogha' was not the 'President of the Privy Council. He was really the minister without whose permission no Amir could obtain admission to the Hall of Private Audience in which the Emperor met and received the homage of the leaders in Church and State. The Darogha-i-Khawassan was the Commandant of the Guard on duty at this Hall or Diwan-i-Khas. Manucci thus explains the real meaning. "As regards the royal establishment, there is an officer styled Daroga do Cosea Choqui [Darogha-i-Khās Chauki], that is, officer of the chosen sentinels. They are all picked men and of the noblest families. Ordinarily, they number four thousand horsemen. This officer has charge of the Gousaleana [Ghus] Khina]." (Storia, II. 422). The 'Khawassan' are the 'Cossa choqi' of the Venetian. They were the Emperor's Lifeguards or the Imperial Bodyguard. VII. 477, 1. 10 from foot. Fourteen or fifteen horsemen in the service

of Khan-i-dauran, who were called 'Blanketicearers', shot a few arrows against the

"Kammalposh" in the original, from the Hindi Kammal, 'a coarse blanket and having also the secondary meaning of a kind of cuirass,' which is most probably the right signification here. (Irvine, A.I.M. 44.) VII. 479, footnote. The Siyaru-l-Mutaākhkhirīn makes [the year of

Rafi'u-d-darajāt's accession] 1132 H. and is gene-

Numismatic evidence leaves no doubt as to 1131 being correct. That year has the distinction of being, in the history of Musalman domination in India, a year of four Emperors and the names of four different rulers are found stamped during its twelve months on the coinage of the Realm. Farrukhsiyar's issues of 1131 or the 8th Regnal Year have been found. All the mintages bearing the names of the two pageants, Rafi'u-d-darajāt and his brother, exhibit the identical year and the dateexpression 1131—Ahd (First Year) is stamped on the earliest coins of Muhammad Shāh also. (Whitehead, P. M. C. 310, 314, 318, 350; Num. Supp. No. VII to the J. A. S. B. 1907, p. 63; H. S. M. N., 28).

VII 484, l 8 from foot. The sheet of pearls, which was spread upon the tomb of Mumtaz Mahal upon the anniversary of her marriage and on Friday nights.

נכנ' כננ' (II 837, 1 9 ff.) was not the anniversary of her marriage, but that of her death The סיף of a great or holy personage is observed on the day of the union or nuptials of his or her soul with the Supreme Spirit or Universal Soul (Herklots, Qanoon, Ed Crooke, 190, 192)

VII 484, 1 5 from foot There was the ewer of Nur Jahan and the cushion of woven gold and rich pearls

The sentence reads very differently in the B I text وحورة محق ال المسلم المعلق
VII. 485, l 2 The faujdars of Surat should be held by [Rājā] Jas singh and the Sūbadārīs of Ahmadābād and Ajmer.

should continue under Rājā Ajit Singh
Here we have another example of the confusion between 'Surat' and
'Sorath' The B I. Text reads the name correctly as *-- (II 838, 1 10)
VII 485, 1 17 Prince Muhammad Roshan Akhtar, son of the late
Jahān Shāh, and grandson of Aurangzeb

Delete the conjunction Raushan Akhtar was not the grandson, but the great-grandson of Aurangzeb His father Jahān Shāh was the son of Bahādurshāh, who was the son of Aurangzeb The text has it correctly, as it styles Jahānshāh the 'nabīra' of Aurangzeb (II 840, 12).

VII. 490, l 9 An envoy came from Usmān Khān, a soldier (hazāri) of the fort of Asīr, proposing to surrender the fortress.

A common soldier could hardly have made any such offer 'Hazāri' literally means 'thousander,' i e commander or leader of one thousand [men] The word is loosely used for "a military officer of the rank of our Captain or Colonel, and specifically for an officer of garrison-artillery or artillery in general" (Irvine, A I.M. 157)

VII 491, l 13 from foot The armies approached the village of Jhūni, about thirty kos from Lähor

This is 'Jahni', which Budauni speaks of as near another place called 'Shergarh'. (E D V 407-8) As the Maasiru-l-Umara states that

this 'Ihūni' was eighteen kos from Kāsūr (I. 604. I. 7), which is 42 miles south of Lihor, it may be Chūniān (Constable, 24 E b), which lies about sixty miles south of Lihor and about thirty west of Kāsūr. Shergarh is in the same district (Montgomery), about 20 miles south of Chūniān.

VII. 496, l. 4. On arriving within two or three kos of Ratanpur, and sixteen or seventeen from Burhanpur, he encamped.

A glance at the map will show that this cannot be the well-known Ratanpur in Bilispur. In the B.I. text, it is said to be in the taluga of the Rājā of Makrāi. (II. 875, l. 4 f. f.). Makrāi is a small State in the Hān liya subdivision of Hoshaugībīd district and the town of that name is about thirty miles south of Hāndiya and about seventy miles north-east of Burhīnpur. It is shown in Constable, 27 D b. See also the Central Provinces Gazetteer, 256; L. M., II. 21 and 27 note.

VII. 496, l. 17. 'Alam' Ali Khān had arrived at the tank of Hartāla, seventeen kos from Burhānpur,

This is a lake lying four miles south-west of Edlābād [or Ādilābād] in the Bhusāwal subdivision of Khāndesh district. It is a place of pilgrimage and the spot where Rājā Dasharath is said to have expiated his sin. Vide the passage quoted from the Āin. Tr. II. 223, in my Note on VII. 307 ante. 'Hartāla' means the 'Tāla (lake) of Hara, i. e. Mahādeva.' (B.G. XII. 142, 449).

VII. 501, 1. 3 from foot. A camel express arrived, despatched by Ghairot Khān (sic),announcing the slaughter of Husain 'Ali Khān, Ghairat Khān and Nūru-llah Khān.

There is something obviously amiss here. A man who is stated to have been one of the persons slaughtered could not have despatched any messenger. According to the Text, the despatch was sent by Ghairat Khān and the person killed was 'Izzat Khān. (II. 901-2). 'Izzat Khān was the nephew of Ḥusain 'Ali Khān (502 infra) and his death from a musket shot is mentioned by Dowson (505 infra). Mr. Irvine says the man killed was Ghairat Khān. (L. M. II. 62 Note and 63; A.I.M. 104). The despatch must then have been sent by 'Izzat Khān.

VII. 502, last line. The royal army was encamped at Tora, thirty-five kos from Fathpur.

There are at least two places named Toda—Toda Bhīm and Toda Tonk. This 'Tora' must be Toda Bhīm, which is about sixty miles south or (about 35 kos) west of Fathpur Sikri. It is now in Jaipur State and lies about 50 miles east of Jaipur town. Constable, 27 C c. Toda Tonk is at a much greater distance from Fathpur. Constable, 27 B b. It lies about 65 miles south-west of Jaipur. Lat. 26°-55′ N., Long. 76°-49′ E. (Th).

VII. 503, l. 3 from foot. Some of the artillery men began to fire muskets and Rämchangis.

The last word has puzzled even that most erudite and painstaking scholar, William Irvine. It is written, he observes, in various ways,

Rāmjaki, Rāmjanki, Rāmjangi and Rāmchangi. He thinks that it must have been some sort of field-piece or cannon, and admits his inability to indicate the derivation. (A M I. 137).

I venture to suggest that it is the Hindi 'Ramjani,' Pleasure-girl,' dancing-girl, fille de joie, or Bailaden a, as the Portuguese in India used to call the Indian 'Nautch-girl'. The name seems to have been given to a small cannon by way of humorous allusion to the dances or capers cut by the gun, t e. to its recoil when fired off. The designations of several pieces of artillery, even in English, are founded on similarly fanciful or jocose analogies, c. g musket (from L Mosca, a fly), falconet, culverin (L Coluber, a snake), Saker (a hawk), Brown Bess, Basilisk, Pistol So also here in India, a culverin was called Zamburak. (little wasp) and another sort of light cannon was known as Dhamaka, from the sound made by the fall of a heavy body on the ground (Irvine, A. I. M 137). There was also a pistol which was styled a Sherbacha ('Lion's whelp'), q.v my note on E. D VIII 399 Footnote, and a cannon very similar to, if not identical with the Zamburak, was known as Shāhīn, falcon (Ib. 136) In the same way, the gargantuan balista, which is stated to have been brought from Khurasan by Muhammad-i-Qasim and to have required five hundred men to work it, is called by Biladuri The Little Bride ' (E D, I 120) and Amir Khusrav uses the same word for the mangonels ['Manjanik'] which were used by 'Alau-d-din الله الله scatter gold and silver coins among the populace عروساك ساخت ('Ashiga, p 56, verse 3') اصرت را رر ادشان--طعر عراده شد کوهر ادشان

VII 507, l 8 from foot It was very inexpedient to march against the enemy without toras

The sign of the plural number is unauthorized مدون تور مقابل رفق (II 912, 17) The meaning suggested in the footnote,—
'mantelets or movable breast-works'—is not at all appropriate. The word is used here by Khwāfi Khān, exactly in the same sense in which it is employ ed by him in another passage. It means 'a Prince of the blood royal,' who was to be used as a Pretender or rival to the Emperor. See my Note on VII. 391, 18 ante. Mr Irvine tells us that Muhammad Qāsim Aurangābādi applies the word in the same way to the claimant Nikū Siyār in his Ahuāl i-Khawāqīn, Ms 125 b (A. I. M. 145)

VII 518, l 13 Koki Pādshāh, a woman of great charms and intelligence colluded with Khwāja Khidmatgār Khān

The name of this Koki [foster-sister] of the Emperor was Rahimun-news and she was the daughter of Jan Muhammad, a geometre Mr. Irvine says that there is no evidence to show that she had ever been suckled by the same nurse as Muhammad Shah and he thinks that the tale was invented only for facilitating her free access to the palace. Some writers suggest that she was his concubine, but the probabilities are, in his opinion, against the supposition (L M, II 263-5)

VII 525, l 17. Pargana of Sahur, near Strong in Malioa.

Recte, 'Sehore', now in Bhopāl State, 22 miles south-west of Bhopāl town, on the right bank of the Saven, a tributary of the Pārbati. Constable, 27 C d.

VII. 526, l. 8 from foot. A battle was fought near the town of Shakar-Khera in Birār.

This place is in Buldana district, Berar, and lies about eighty miles from Aurangabad. (Berar Gazetteer, 168). It is now called Fath Khelda, in commemoration of this decisive victory and is marked under that name in Constable, 31 D a. Shakarkhera was a place of some note even in the days of Akbar and is registered as a Mahal in Sarkar Mehkar, Sūba Birār. (Āīn, Tr. II. 237).

VII. 528, l. 18. Between Rustam 'Ali Khān and Pilūji, a Mahrātta chieftain,......there had been......a continual state of war.

The person meant is Pilāji Rāo Gāikwāḍ, who was the son of Jhingoji Rāo Pāṭil. Jhingoji Rāo was the brother of Dāmāji Rāo Gāikwāḍ. Dāmāji and Khanḍerāo Dābhāḍe both died in 1720 A.C. within a few days of each other. The Gāikwāḍ family is said to have come originally from the village of Dhāvḍi, near Poona in the Kheḍ taluka.

For 'Safdar Khān Bāni' (l. 6) read 'Safdar Khān Bābi'. He was the ancestor of the ruling Nawabs of Junagadh, Rādhanpur and Bālasinor (or Wādasinor).

VII. 528, l. 9 from foot. He [Hamīd Khān] was joined by a Mahratta chief named Khantha.

This was Kantāji Kadam Bānday. (Grant Duff, H. M. 216). The surname is also written $Bh\bar{a}nde$.

VII. 528, l. 8 from foot. On reaching the banks of the Mahi, a great battle was fought.

The site of the battle is not mentioned by Khwāfi Khān. It was at the village of Arās or Adās in the plain between Ānand and the Mahi. (Rās Mālā, Reprint, 1920, II. 5; B. G. I. i. 305).

VII. 529, l. 7 from foot. Bir-nagar was a flourishing town full of merchants of the famous Nāgar class.

Recte, 'Vadnagar,' [Vriddhanagar], now in the territories of the Gaikwād of Baroda. Abu-l-Fazl speaks of it as "a large and ancient city containing 3000 [?] pagodas, near each of which is a tank, and chiefly inhabited by Brāhmans". (Āīn, Tr. II. 232).

VII. 530, l. 2. Muḥammad Shāh appointed Rājā Dūngar Singh [as Ṣūbadār of Aḥmadābād].

'Dungar' is an error for *Dhankal* or *Dhokal* (Sinha). He was one of the sons of Mahārāja Ajīt Sīnha of Jodhpur. His real name was Abhaya Sinha. 'Dhankal' or 'Dhokal' was only a nickname given to him by the Mughals, q. v. my note on Vol. VIII. 44 post.

VII. 531, l. 16. Haidar Kuli Khān was sleeping in his Khas-khānā, when it caught fire.

"Khas" is the name of a grass, Andropogon Muricatus, which is "used to make screens, which are kept constantly wet in the window openings, the evaporation of which greatly cools the house" Abu-1-Fazl, in his wonted adulatory manner, ascribes to Akbar the invention of these Khaskhanas He describes them as "trellised chambers of a root called Khas, upon which, if water be sprinkled, winter arises among the summer heats" (Āīn, Tr III 9) But the assertion is without warrant, as they appear to have been used long before Akbar.

VII 534, l 2 Tarīkh-1-Irādat Khān

Irādat Khān was a poet also and his nom de plume was 'Wāzih', which signifies 'evident, lucid, clear, manifest' Dowson says that he was appointed Faujdar of Jagna by Aurangzeb in the XXXIIIrd year, but the real name of the place is Chākan, alias Islāmābad, about 20 miles north of Poona (M 'A. 330, last line, MU, I 205) He was afterwards Faujdar of Aurangābād, and Qıl'adār of Gulbargā (M 'Ā 383, 1 1 and 472, 1 12) "We learn from Mırza Muhammad Bakhsh (Āshob) that his work was unfavourably received on account of the overweening conceit displayed by the author, who has been sharply saturased by the contemporary Ni'amatkhan 'Ali" (Rieu, III 938) There are several passages even in these extracts, which fully bear out this indictment and they must have furnished rich material for the mordacious wit and irony of the Haji Speaking of his relations with Prince Bidar Bakht, for instance, Iradat Khan blows "In a short time, such a friendship grew up his own trumpet thus between us that a greater between a prince and a subject cannot be conceived He would not be an instant without me, he would not eat of anything but he sent me part of it" etc. (537, 1 1) Similarly ridiculous boasts may be found on 538, 1 8 f f, 549, 1 18, etc.

On line 12, the name of his grandfather should be read as 'Azam Khān, not عطي 'Azīm Khān

VII 544, l 4 from foot 'Azam Shāh . eaclaimed, "Do men think that I will use cannon against a breeder of cattle!"

This contemptuous epithet is evidently intended for his antagonist, Bahādurshāh, but the raison d'être must be matter of conjecture Manucci states that 'Azam Shāh's "favourite nickname for his elder brother was the 'Baniya,' that is, one who is the very incarnation of timidity" (Storia, II 396 and note) He informs us that Aurangzeb always spoke of Bahādur as a poltroon, who would never rebel against him and illustrates it further by a story of Mu'azzam having been terribly frightened in boyhood on seeing a rat pass before him (Ibid, II 395)

VII. 553, l 10 His [Kām Bakhsh's] flatterers having told him that his eldest son would also at some time become Emperor, he became jealous of the innocent child

Like many another prophecy recorded in histories, this prediction was partially fulfilled, though not exactly in the manner indicated by the

seer. The eldest son referred to, Muhiu-s-sunnat, really died by poison in 1160 H., but his son, Muhiu-l-millat, did become Emperor for a few days as Shāh Jahān III, in 1173 H. 1759 A. C. (E. D. VIII. 243, 278).

VII. 556, 7. 17. [Mun'im Khān] resigned his soul to the angel of death (1124 A. H. 1712 A. D.).

The year is wrongly given. Mun'im Khan died about the begining of 1123 A.H., February 1711. (L.M., I.124; 425 ante and M.U., III. 672-674). Bahadur Shah died in 1124 H.

VII. 561, l. 17 from foot. Intelligence was received that the Suiyidshad gained the ford of Gao-ghāt.

This ford lay about fourteen miles above Āgra. (Chihār Gulshan in I. A. xcvii). Khwāfi Khān says that the Saiyids crossed near the Sarāi-i-Rūzbihāni, about four kos from Āgra on the Dehli side. (Text, 720, 1.7). VII. 565, 1. 2. Tārīkh-i-Bahādur Shāhi.

Dr. Rieu denies that this is an independent work. He states that it is only a portion of the concluding Part of the first Mail'a (Section) of the third Maqāla (Book) of Khūshhāl Chand's Tārīkh-i-Muḥammad Shāhi, entitled Nādiru-z-zāmānī, which is noticed at E. D. VIII. 70-1. (Persiān Catalogue, III. 894). He states that Sir Henry Elliot must have seen only imperfect copies of Khushhāl Chand's work and that his notice relates only to the earlier and useless part.

VOL. VIII. MUHAMMAD SHĀH TO SHĀH 'ĀLAM II.

VIII. 5, l 5. [The Khulāsatu-t-tawārīkh] was composed by Munshi Subhān Rāi Khattri, an inhabitant of Pattiyāla.

Subhān Rāi [حال رائی] is an incongruous combination and an almost impossible name for a Hindu. Dr Rieu has shown that the correct form is Sujān Rāi, and that the ζ has been wrongly read as ζ on account of the perplexing resemblance of the two letters in Persian writing. The author was a native of Batāla, not of Patiāla, though Raverty (Mihrān, 319 note and 392) and even Dr. Rieu (Catalogue, I 230) had repeated the error committed here by Elliot Batāla is a town in Gurdāspur and Sujān Rāi gives a lengthy and loving description of its gardens, tombs and tanks in the Introduction to this History (Sarkār, I A 83-88) Patiāla is not so much as mentioned anywhere in it Batāla is now a station on the North-Western Railway, nineteen miles north-east of Amritsar

VIII 8, l 1 Tārīkh-1-Firūzshāhi by 'Izzu-d-dīn Khālidkhāni

The TA (117, 16), F (I 141, ll 1-3) and B (I 249, Tr 332), all state that this 'Izzu-d-dīn Khālid Khāni translated from the Sanskrit into Persian, a quasi-scientific treatise on the import of the risings and settings of the planets and auguries and omens, to which he gave the name of Dalāil-i-Firūzshāhi But it was not a History of the reign of the Sultān. Sujān Rāi is evidently speaking without book and we may be sure that he had never seen, much less read, any such History He has lifted the names and titles of many of the other chronicles which he cites, from the T A. or F He does not appear to have ever seen them and he has certainly made no use of them in his compilation

VIII 8, 1 3 History of Akbar by 'Atā Beg Kazvini

'Atābeg Qazvīni never wrote a regular "Tārīkh-i-Akbari" Sujān Rai must mean the historical introduction to the Nafaisu-l-Maasir, which is really a 'Tazkira' or Biographical and Critical Account of Persian Poets and not a History The Nafais is cited by Mu'atamad Khan along with the Akbarnama of Abu-l-Fazl among his authorities for the Second volume of the Iqbalnama There are copies of it in the British Museum (Rieu, III 1022) and the Bankipur Library (Catalogue, VII. 61) Another copy which was in the Moti Mahal Library, Lucknow, 18 noticed at length in Sprenger's Catalogue (45-55). The real name of the author was 'Alāu-d-daula (not 'Atā Beg', as in the Khulāsat), and he was the brother of Mir 'Abdul-l-Latif Qazvīnı (Akbar's tutor) and the son of Mîr Yahyā, the Compiler of the Labbu-t-Tawārīkh (q v E D. IV. The Introduction contains an account of the reigns of Babur, Humāyūn and Akbar which goes down to 975 A H (1567 A C) and 18 interesting, if not valuable, as it is the earliest of all the extant Lives of Akbar. See Mr Beveridge's art in JASB (1905), p 236 sq Budaum also mentions 'Alau-d-daula Qazvini as the author of a Tazkira or 'Loves of the Poets' and cites the chronogram composed by him for the wack of Chitor, (II 105, Tr. II 108 and Note).

VIII. 11, l. 6. Sultān Ghiyāsu-d-dīn Balhan built another fortress, which he called Shahr-zaghan.

Abu-l-Fazl states that Balban erected a fortress in Dehli, without mentioning its name. Sir Sayyid Ahmad Khān copies the statement (Āṣār, Pt. iv. 4), and adds that it was called Shahr-i-Zaghan. [Sir] J. Sarkār thinks (I. A. 2 note) that 'Shahr-Zaghan' signifies 'City-kite,' but this has no meaning in such a context. There was at Herāt a garden called Bāgh-ī-Zāghān, which had been laid out by Mirzā Shāhrukh, the son of Taimūr. (T. R. Tr. 83). Zaghan means 'kite,' Zāghān 'crows.' Amīr Khusrav ('Ashīqa, 47) and Badr-i-Chāch (E. D. III. 545 note) speak of the Hindus as "cawing crows" ('S. c. diblo') and Ḥasan Nizāmi derides them as 'crow-like Hindus' and "crow-faced Hindus.' or 'City of Crows,' i. e. the 'City of the crow-like Hindus.'

But another and better explanation seems to me to be that it is a paroly of the old Hindu name of Dehli, which was Jogṇipur "City of the Jogṇis [Yoginis]." It is said in the Prithvi Rāj Rāsā, that Shihābuddīn Ghori invaded Hindustān and proceeded with a howl towards Juggini ज्ञिनी (Canto XLIV. 14. See J.A.S.B. LV. 1886, p. 10). The assonance between 'Zaghan' and 'Jogṇi' is close enough to suggest the word-play. Dehli is often called 'Jogṇipur' in the extracts cited from the Rājput chronicles in Tod's Annals. It is called 'Yoginīpura' in thé second verse of an inscription dated V. S. 1272 (1216 A. C.) which is edited in Ind. Ant. XLI (1912), pp. 85-86, and also in the Hammīra Mahākāvya, IV. 101 (Ibid). An old temple dedicated to Yogamāyā also exists in the city. This Shahr-i-Zaghan was most probably identical with Barani's 'Ghiyāṣpur,' another name by which the new quarter founded by Ghīyaṣu-d-dīn Balban was known. q. v. E. D. III. 148 and my note. The Kūshk-i-L'al palace built by Balban was situated in Ghiyāṣpur.

VIII. 14, l. 10 from foot. He is the same Muhammad Hādi, who wrote the Introduction and Conclusion of the Autobiographical Memoirs of Jahāngīr.

The identity of Muḥammad Hādi, the Continuator of the Tūzuk-i-Jahāngīri (q. v. E. D. VI. 392) and Muḥammad Hādi, Kāmwar Khān, who wrote the Haft Gulshan-i-Muḥammad Shāhi and the Tazkira-i-Chaghtāi is extremely doubtful. Dr. Rieu who had followed Elliot in assuming it in the First volume of his monumental Catalogue [p. 208], retracts the opinion in the Third. He states that Kāmwar Khān was really a Hindu convert to Islam, whose original name was Chanḍīdās and that Muḥammad Hādi obtained the title of Kāmwar Khān, according to his own statement, in the 2nd year of the reign of Bahādur Shāh. (Catalogue, p. 1084). See also the Bānkīpur Catalogue, VII. 15.

VIII. 16, l. 8 from foot. Sultan Muhammad Tughlaq......put the Amīrs of Sind, Dakhan and Gujarāt to death.

is a blunder of transcription for امران صد 'Centurions or Commanders of One Hundred,' who were 'New Musalmans,' te Converted Mongols. (ED. III 252) Firishta, from whom Muhammad Hādi copied this passage, has the right reading امران صده (I 274, 1 9) They were, in fact, the commanders of "the Mughal mercenaries" of whom the writer speaks only five lines higher up

VIII. 16, l. 6 from foot The Sultan conferred on him [Hasan Gangū]
Bhakkar, which was one of the dependencies of Bhakhri, in jägir

These place-names also are wrong F, from whom the passage is borrowed, states that Hasan was given "the title of Zafar Khān and the 'Iqtā'a (fiefs) of Rāibāgh, Mīraj, Hūkeri, Kalhar and Gulbarga'' (I. 275, 19) 'Bhakri' looks like a misreading of 'Hukeri' and 'Bhakkar' of 'Kalhar' Hukeri is in Belgaum and Kalhar is 'Kolhar' in Bijāpur.

VIII. 19, 1. 9 Bahādur Shāh died on 10th Muharram, 1024 A H. 9th February 1615)

Both dates are manifestly wrong The correct Hijri year was 1124, not 1024, and the Julian correspondence was 28th February 1712 See E D. VII 556, Irvine, L M, I 135, and my H S M N 279)

VIII. 23, l 9 from foot The mosque of Rasadu-d-daula which is situated near the Court of the Superintendent of the Police

"Rasadu-d-daula" would be nonsensical as a title Read "Raushanu-d-daula" The founder was Bakhshi under Muhammad Shāh and his Golden Masjid is near the Kotwāli (Fanshawe, DPP 50, Āsār, Pt III, 18, Pl 5) He is mentioned again at p 48 and this mosque is called by its right name on p 64 infra Elphinstone says that "Nādir sat all the time in gloomy silence in the little mosque of Ruknu-d-daula in the great Bazar," (H.I 718 note), but he also has fallen into error "The Court of the Superintendent of the Police" is the Kotwāli of Fanshawe

VIII 26, l. 7 Muhammad 'Alı, son of Muhammad Sādık-al-Hasanı al-Naishāpuri al Hanafi

Dr Rieu reads the second nisba as 'Najafi' (Catalogue, III 893) and it may be correct, as the author was a Shi'a and a Sayyid, connected with Najaf, near Kerbela But he may have called himself Hanafi, when he subsequently dedicated it to a Sunni

VIII 29, l 10 Sultans of Juiza

'Arabistān' has taken its place. (Lestrange, L. E. C. 232, 241; Houtsma, E. I., II. 224). Aḥwāz is in Lat. 31° N., Long. 49° E.

VIII. 30, l. 9 from foot. Tārābai, wife of Sambhā, son of Sivā.

A slip of the author's. She was really the wife of Rām Rājā, Shambhuji's younger brother.

VIII. 44, l. 6. Rājā Ajīt Singh..took refuge in the fort of Garhpatti.

The specific name of the citadel of Ajmer is Garh-Bītlī or 'Gārh-Bitlī'. The latter form is said to be derived from Bīthhal, Vīthhal or Visaldeva Chauhān, who reigned circa 1153 A.C. and is said to have built it. (Tod, A.A.R. Ed. Crooke, II. 900; Hunter, I.G., I. 119; Khulāṣat, I.A. 57; Chihār Gulshan, Ib. 138). But there is a range of hills called 'Bithli' very near Ajmer town and the name may be derived from it. 'Patti' must be a miswriting of 'Bītlī.'

VIII. 42, l. 12. [Ajīt Sinhā's son] Dhankal Singh...... obtained the investiture of the chiefship [of Jodhpur].

VIII. 45, l. 14. The hills at Kasipur and Rudarpur.

Kāshipur is now in the Tarāi district of the U.P., on the route from Morādābād to Almorā, thirty-one miles north of the former, Constable, 25 C c. Rudarpur also is in the Tarāi on the route from Bareilly to Almorā and 53 miles north of the former. Constable, 28 A a.

VIII. 45, l. 1 from foot. Mir Jumla Yar Khan was appointed...... to decide it [the dispute].

Mir Jumla is styled 'Tarkhān' at 49 infra and this must be correct, as he is said to have received the addition of 'Tarkhān' to his former titles on the 7th of Zī-l-Ḥijja. 1130 H. (Irvine, L. M., I. 356. See also Ibid. 268). According to the M. U., one of his titles was A'atabār Khān (III. 711), but I cannot find it anywhere in the list given by Mr. Irvine in L.M., I. 268. Fār Khān may be a decapitated form of it.

VIII. 46, 1. 9. Muzaffar Khān pitched his tents near Pothorganj.

Pathargani lies about 8 miles south-east of Delli, near the left bank of the Jumna. The battle in which General Lake defeated the Hahrathas

commanded by Bourquin in 1803 A. C was fought near this place (Th) Muzaffar Khān was marching from Dehli to Oude, as he had been appointed Suba of the province

VIII. 46, l 20 The fort of Jitgarh, where he [Rājā Chhatarsāl] resided. was taken

Jîtgarh is also called 'Jaitpur' and is now in Pannā State, Bundel-khand It lies twenty miles west of Mahoba and about six miles south of Kulpahār, which is in Hamīrpur district. (L M, II 232, J A S B (1878), pp. 294-5, IG XIX 242, 402) It is shown as Jaitpur in Constable, 28 A c

'Chāchandı near Shāhabād Kanauj' (1 24) is the 'Chychendee' of Seely's Roadbook of India, where it is placed fourteen miles north of Cawnpore, on the route from Cawnpore to Etāwa (p 28) Qanauj is about 52 miles from Cawnpore

VIII 47. 1 9 Antrat Singh

"Amrat Singh" at 53 and 66 infra, but the correct form is Aniruddha Sinha Elliot (Races, I 30) says of his father, Gopāl Sinha, that Burhānu-l-Mulk, S'ādat Khān, the Nawāb of Oude, had such a regard for him that he used to call him 'Son' Mr Irvine calls him 'Anuradh' (LM, II. 286), but it must be a slip or some sort of error for "Aniruddh"

VIII 48, l 22 Kaira Khan

Recte, Qāim Khān as at 116, 213 infra 'Sher Afghān Khān' (13ff) is an error for 'Sher Afgan Khān' which is repeated on p 46, 18 Similarly, 'Udū Afghān Khān' (p 51, 123) is a misreading of 'Udū Afgan Khān' (Enemy-routing Khān' خار الكن خان).

VIII 50, l 13 Udār u the Zamīndār of Kora Jahānābād, who had killed Jān Nisār Khān

But on pp. 52 and 341 infi a, Jan Nisar is said to have been killed by Bhagwant, the son of this Udaru [Udaram], and that is correct Udaram was the Khichar Zamindar of Enchhi (otherwise called Ghazipur), a pargana in Kora Jabanabad Elliot himself states elsewhere that it was Bhagwant and not Udaru, who was responsible for the death of Jan Nisar. (Races, II 107-8 See also Irvine, AIM, 257) The name is given as 'Araru Singh' in the CHI, IV 355, but this must be a slip or misprint

VIII 52, l 3 The Mahratta chiefs advanced from [Ajmer] to the fort of Rupnagar

Rūpnagar lies 26 miles north-east by north from Ajmer and 61 miles west by south from Japur It is now in the State of Kishengadh (I G XV. 312-3) Constable, 27 B b There is another place of the same name in Godwār, Constable, 27 A c, with which this should not be confounded

VIII 52, l 9 Yādgār Khān Rão, Savyid Kirpārān and Najābat 'Ali Khān

The names have been dislocated by the copyist or the printer Read 'Yādgār Khān, Rāo Kirpārām and Saiyid Nijābat 'Ali Khān.'

VIII. 53, 1. 19. [The enemy] sent the other half through the towns of Gohad and Barhad to the town of Ater.

Gohad lies 28 miles north-east of Gwalior, and Barhad is at 31 miles' distance from it in the same direction. Ater is situated among quicksands and jungly ravines on the right bank of the Chambal, 46 miles north-east of Gwalior. Lat. 26°-44′ N., Long. 78°-43′ E. Constable, 27 D d. Bhadaura or Bhadawar is in the pargana of Hatkant or Bah Panahat and is in the neighbourhood of Ater. (Elliot, Races, I. 25).

Firozābād is the old name of Chandwār, about 24 miles east of Āgra. Itimādpur lies about 14 miles from Āgra on the road from Āgra to Allahābād and Benares. (I. A. exi). It was founded by and named after the cunuch, Phul Malik, entitled Itimād Khān, who was murdered in 986 A. H. by a man named Maqṣūd Ali. (M. U. I. 90).

VIII. 55, 1, 3. 'Itimādu-d-daula........... who was encamped near Kāmān Pahāri, also returned to Delhi.

Kāmān Pahāri, now in Bharatpur State, lies 39 miles north-west of Mathura. Kāmah and Pahāri, were two of the seven maḥāls or parganas in Sarkār Sahār, Ṣūba Āgra. (Āīn, Tr. II. 195). Constable, 27 C b. Nimrāna (l. 8) lies 76 miles south-west of Dehli. It was in Akbar's days, one of the maḥāls of Sarkār Rewāri. (Āīn, Tr. II. 293). Mitrol (l. 2 f.f.), is, correctly, 'Mitnaul', which lies 10 miles north-west of Hodal, (not Kodal as in Dowson), and 11 miles south of Palwal. Hodal is shown in Constable, 27 C b. It is about sixty miles south of Dehli and sixty-six miles north of Āgra on the route from Āgra to Dehli. (I. A. xevii).

VIII. 58, l. 4. The invaders [Mahrāthās] went towards Ahirwāra, the country of the tribe of Ahirs..... and besieged the fort of Korwāi.

There is a place called Ahraura in Mirzāpur district, 12 miles southeast of Chunār, (Constable, 28 C e), but there is another place of the same name south of Jhānsi and the later seems to be the town intended. Korwai (l. 6) in Sāgar district, lies on the right or east bank of the Betwa, about 60 miles south-west of Tehri in Oreha. Lat. 24°-6′ N., Long. 78°-5′ E. Constable, 27 C c. 'Izzat Khān, son of Diler Khān, (l. 7), was an ancestor of the ruling Nawāb of Kūrwāi,

VIII. 64, l. 3. Nādir Shāh chose ... the Garden of Hayāt Bakhsh for his own accommodation.

'Bāgh-i-Ḥayāt Bakhsh' signifies 'Life-giving Garden', and is not so called after any man named Ḥayāt Bakhsh. It was a private garden of the Emperor and was situated near the north-western corner of the Lāl Qil'a or Palace. (Āṣār, II. 18-19; Fanshawe, D.P.P. 30-40; Cārr Stephens, Archaeology of Delhi, 6, 216). As it is mentioned in the Maāṣir-i-Ālam-gīri in 1080 H. (Text, 84, l. 11), it must have been laid out before that date. For the name, compare 'Bagh-i-Dilāmez' (near Lāhor), 'Bagh-i-Shahrārā,' 'Bāgh-i-Gulafshān,' (Āgra), 'Bagh-i-Dahrārā,' which are all mentioned by Jahāngīr in the T. J., Tr. I. 90, 131, 111, 4-5, etc.

VIII. 65, 1. 18. The chief [of Sind], who was of the tribe of Bhatti.

There must be some confusion or blundering here. The chief referred to was Nur Muhammad Kalhora, also called 'Abbasi See 97-8 infra, where he is spoken of by his title of Khudayar Khan 'Abbasi At page 24 ante, Warid, the author of the Tarikh-i-Chaghtai, is made to say that "on the way to Latte, the ruler of Sind was defeated by Nadir Shah" There is some error there also, but the confusion is cleared up by the author of the Maāstru-l-Umarā who says "At present, (t e when he wrote the work about 1159 AH), the whole of Sindh is under Khudayar Khan Latti (التى). From a long time, he had farmed the Sūbā of Tatta and the Sarkār of Siwistan and Bhakkar Subsequently, when the districts on the other side of the Indus were ceded to Nadır Shah, Khudayar administered them for Nādır Shāb" (III 312, see also Aīn, Tr I 363, Note) Elsewhere, the same well-informed author writes thus "Khudāyār Khān is the Marzbān [Governor] of Sind and known as Litti (مشهور به ليتي) and is of the 'Abbasi lineage His tribe is called Kalhora and his family is designated Siraiyan, because they came from Sara, a district between Bhakkar and Multan They are followers of Salyid Muhammad Mahdavi of Jaunpur" (I 825) Khwāfi Khān also states that an ancestor of Khudāyār Khān, whose turbulence and lawless proceedings had compelled the Prince-governor of Multan, the Shahzada Jahandar, to despatch in 1110 H, a punitive expedition against him, belonged to a timbe called Lappi (or Latti) " (Text, II 444, 1 2, 463, 1 3) 'Latti' was not the name of a place, but that of the tribe to which Khudavar Khan, the ruler of Sind, belonged Mr H. A Rose tells us that the Kalhoras, are, originally, a Jat tribe, also known as Dodai Late, which gave a dynasty to Sind and is still represented in Dera Ghāzi Khān . Late is said to be derived from the Hindi Lat, tangled or knotted hair, and 'Kalhora,' in Sindhi, is said to mean the same thing A derivation from Lat, a club, in Sindhi, has also been suggested, and in front of the Kalhora Chiefs' tombs at Khudabad, a number of clubs are suspended" (Tribes and Castes of the Punjab, II, 440 and Note) Dowson is mistaken in registering 'Latti' in the Geographical Index.

VIII 69, l 10 He sat at the gate of the shrine of Saint Zainu-l-Mulk, where also . 'Alamgir is interred.

This is the Rauza or Khuldābād, near Aurangābād The saint is Zainu-d-dīn Dāūd, who is said to have been born at Shirāz in 701 and died in 771 H Aurangzeb's grave lies to the west of Zainu-d-dīn's tomb, while those of 'Azam Shāh (his son) and 'Azam's wife are to the east Facing the entrance, is the shrine of Shaikh Burhānu-d-dīn, the saint after whom Burhānpur is named and a little to the right is the last resting-place of Āsaf Jāh Nizāmu-l-Mulk Zainābād on the left bank of the Tapti opposite to Burhānpur is named after this Zainu-l-Mulk or Zainu-d-dīn. (Aurangābād Gazetteer, pp 396-7)

VIII 70, l 8 from foot He calls his work Tārīkh-i-Muhammadshāhi, to which he gives the honorific title of Nādiru-z-zamāni,......as it contains, in combination with another word, the date of composition, 1152 A.H.

Dr. Rieu enables us to understand this obscure statement and set it right. According to him, what the author really says is that the date of composition, (1154 H.), is conveyed in the following distich, which is found at the end of the first book (Folio 189 a):

تاریخ از این مقاله جستم ـ شد دقتر عشق سر نوشتم

"I sought for the date of this disquisition. It was 'Daftar-i-Ishq.' I wrote it down.' The letters of دنتر عشق stand for 4+80+400+200+70+300+100=1154. This is the word or rather phrase, which by itself, contains the date of composition. (Catalogue, I. 121). There is no need to combine it with any other.

VIII. 81, 1. 11 from foot. The author himself, Anand Rām, accompanied by his beloved sons, Rāi Kripārām and Sālāh Fath Singh, left the capital.

The author, \bar{A} nand $R\bar{a}$ m, is using the vernacular word 'Sālā' in the sense of 'brother-in-law' or wife's brother. The sign of the plural which is affixed to 'son' should be deleted. Kripārām was the son, and Fath Singh, the $(S\bar{a}l\bar{a})$ 'brother-in-law' of \bar{A} nand $R\bar{a}$ m.

VIII. 82, l. 4. Near Karnál, flows a canal which issues from the Jumna river, near Mukhlispur.

Mukhlispur is not to be traced on our maps, as it is now called 'Bādshāh Maḥal'. It lies near the town of Sirmūr, where the Jumna leaves the hills and descends into the plains. Shāh Jahān ordered a palace to be built here in 1065 A. H. It is a few miles below the heads of the present Eastern and Western Jumna Canals. (Khulāṣatu-l-Tāwārīkh in I. A. 17; M. U. II. 867; L. M., I. 108). Lat. 30°-20′ N., Long. 77°-39′ E. Th 742.

VIII. 87, l. 9. Nasakchis were ordered to be in attendance on them.

Morier speaks of the Nasakchi-bāshi as the Chief Executioner, but also states that he was the officer employed to seize state-prisoners. (First Journey through Persia, 19). Jonas Hanway also describes the "Nassackhchi Bashi" as 'the officer who makes seizures'. (Revolutions of Persia, II 372). 'Nasaq' means order, arrangement. The Nasaqchis were armed men employed to enforce orders. Military punishments were inflicted through them and one of their duties was to stand in the rear of the army and cut down every one who dared to flee. (A. M. I., 227).

VIII. 88, l. 15. The Chandni Chauk, the fruit-market, the Dariba-bazar were set fire to.

Darība or Zarība is synonymous with the Hindi 'Mandavi', 'Toll-house, Tolls or octroi duties.' The Darība-i-Barg-i-Tambūl, the octroi of the Pān Market, is mentioned in the Mirāt-i-Aḥmadi, II. 122. (1.17). The Mandavi-i-Barg—a tax levied on the sale of greens, betel leaves and vegetables—was one of the unlawful cesses abolished by Firūz Tughlaq. (E. D. III. 377, q.v. my note). The Darība of gum-lac, gold and opium also is s eci-

fically referred to in the account of the municipal revenue of the city of Ahmadābād (Mirāt-i-Ahmadī, I i 20 l 15, Trans. in Bayley, op. cit 8 and Notes, Bird, History of Gujarat, 113) The Darība Bāzān still exists in Dehli Fanshawe states that it "leads from the Jām'a Masjid to the Chāndni Chawk, upon which it formeily opened through the Khūni Darwāzā, which was so called from the massacre, which took place there under the orders of Nādir Shāh West of the Darība, is the Phul kī Mandī or Flower market" (D P P. 49) There is even now a branch post-office in the Darība quarter of Dehli and the town of Morādābād also possessed one in the quarter which is known as Darībah-i-Pān, i e Betel-leaf Market (Post Office Guide)

VIII 89, l 16 The Feacock throne alone . which had cost one Kror of rupees

The Peacock Throne is here said to have cost one Kror of supees The Tārīkh-1-Jahān Kushāi Nādiri (360, l. 11) puts its value down at two Krors Bernier says it was worth four Kiors (Travels, Ed Constable, 268). Tavernier valued it at ten Krors and seventy lakhs of rupees (Travels, Ir Ball, I 381, 385 and note) The remains of the throne which were in the Treasury at Teherān about 1890 were appraised then at £2,600,000 or thirteen millions of dollars by Mr S W Benjamin (Persia and the Persians, p 73) 'Abdul Hamīd Lāhori, the contemporary historian of Shāh Jahān states that one Kror of rupees were spent upon it (E D VII 45, Text, II 62) but additions may have been made afterwards

VIII. 89, last line The marriage of Nasir Murza, son of the Persian Emperor, to a daughter of Murad Bakhsh, third son of Shah Jahan

There must be some error here Murād Bakhsh was born in or about 1037 H, 1627 AC, and was put to death in 1072 H (ED VII. 132) The lady was really his great-grand-daughter, the daughter of Dāwar Bakhsh, the son of Izad Bakhsh, the son of Murād Bakhsh Dāwar Bakhsh's mother was a daughter of Aurangzeb She was married to Izad Bakhsh in 1083 H. (M 'Ā 120, l 4 f f, E D VII 197, Irvine, L M, II 370) Moreover, Murād Bakhsh was not the third, but the fourth son of Shāh Jahān Aurangzeb was the third In the C H I. (IV 332), she is described as a grand-daughter of Kām Bakhsh

VIII. 92, l 10 All the countries about Sind, westward of the rivers Attock and Sind, and of the Sanjar stream, which flows from the latter, namely, Peshāwar, Bangashāt, the country of Kābul, Ghazni etc

There are three other versions of this Treaty, viz, one given by Raverty from an author called Ni'amat Khān, (Mihrān, 466), Fraser, (History of Nadir Shah, Edit 1742, pp 223-226) and Hanway, (Revolutions of Persia, Edit. 1754, II 386-7), but the names of most of the places are written so discrepantly that it is far from easy to restore them The "Sanjar stream" is, probably, the Nālā [or Nārā?] Sānkrā, an old branch of the Indus or the Indus itself Raverty thinks that it must be the Hakra

TAZKIRA-I-INANDRIN (Mihran, 461). Khudabad is the place of that name which lay seventeen miles north of Sehwan and was the capital of Nur Muhammad Kalhora. (Haig, I. D. C. 114; I. G. XV. 284). Layagaon' is Ladkana or Larkana, 'The fortress of Rāhīma' is Raḥam-kā or Raḥīm-kā-Bāzār (Constable, 26 B c). It is called 'Rām' by Fraser and Hanway. 'Badīn' appears there as 'Terbin.' It lies 56 miles south-east of Haidarābīd (Constable, 26 B c). The pargana of 'Chūn' is the pargana of 'Jūn,' q. v. my note on I. 250, l. 5. 'Samwāl' is 'Samāwāti' or 'Samāwāni' (q. v. my note on VII. 183, l. 6 f.f.). 'Bakarnāchāk' cannot be identified. The 'Singarh rivulet' (l.21) must be the same as the 'Sanjar stream' (l.11), i.e. the Nālā Sānkra. 'Tuhari' زمرى is called the 'castle and town of Lohry Bundar,' by Fraser and Hanway, and this must be correct. 'Bindrawach' must be due to some copyist's misreading of the phrase Bandar-wa-shahr, which is prefixed to the name of 'Lohri'. See Raverty Mihran, 466 Note. VIII. 96, 1. 7. Having made Hut and Ghāzi Khān Dūdahi obedient, he

remained some time in the government of Bhakkar. This is Bhakkar in the Cis-Indus taksil of Mianwali district, not Bhakkar in Sind. Constable, D b 24. It lies about twenty-five miles south of Dera Ism'ail Khān. Mirzā Mahdi Khān explicitly states that the name of the 'Hūt' (Hot) chief was Ism'ail Khān. (T. J. K. N. Text, 370, 1.2). "Malık Sohrāb, a chief of the Dūdai clan of the Hots, left Kach-Makrān with his two sons, Ism'ail Khān and Fath Khān, and reached Multan, vhere he took service with Sultan Husain Langah about 876 A. H. Dera sm'ail Khan and Dera Fath Khan were founded and named after his sons. After Malik Sohrab, another adventurer, and from the same country, named Hāji Khīn (Mirāni), with his son Ghīzi Khīn, founded Dera Ghāzi Khān. A strange custom existed in both these families, of alternating between two names or titles, from generation to generation. Thus Ism'ail Khān's son was Brīham Khīn. His successor was another Ism'ail Khān and he was followed by another Brāham Khān and so on. In the same way, the line of succession of Dera Ghāzi Khān alternated between Ghāzi Khīns and Hīji Khāns upto a recent date, though each chief bore an independent name of his own besides". (T. H. Tolbort, Art. on the District of Dera Ghazi Khan, J. A. S. B. XL. (1871), pp. 10-11). VIII. 97, last line. The Shah......pushed forward from Ladgaon,

distant from Amarkot, thirty farsakhs.

The place meant is Ladkana, Larkana or Larkhana, which lies on the route to Southern Sindh from Qandahār and Baluchistān, through the Bolan Pass. The name is clearly written & y in the T.J.K.N. 369, 1.2 f.f. It is spelt wrongly as 'Layagaon' at page 92 ante also. The sandy country to which Khudiyar Khan sent away his women must be the Thar Parkar district. This author must be mistaken in saying that Larkhana is only thirty farsakhs distant from Amarkot. The real distance must, by road, be about two hundred miles, as Lārkhāna is in Lat. 27°-30' N., Long. 68°-10' E. and Amarkot or Umarkot is in Lat. 25°-22' N., Long. 69°-47' E. What the

T. J K. N says is that Amarkot is in a desert and thirty farsakhs distant from water and habitations سی عرست از آب و آبادای دور است (370, 1. 9), and this is no doubt the right way of putting it

VIII 115, l 16 Siālkot, Imānābād, Parsarūr and Aurangābād

'Imānābād' is 'Emīnābad' in Gujranwāla tahsīl, Punjab It is said to have been formerly called 'Sayyīdpur' Shīr Shāh destroyed it and built Shergarh, which was itself demolished by Akbar's general, Muhammad Amīn Khān, who built another town, and called it Amīnābād It is now a railway station, 34 miles north-west of Lāhor Parsarūr or Pasrūr lies about sixty miles north of Lāhor. Constable, 25 A a Aurangābād is in Sīālkot district, near Narowāl. (See the Post Office Guide)

VIII 116, l 14. The Emperor made war upon S'adu-llāh, son of the Zamīndār of Alola and Bangash, in the district of Sambhal

Both the toponyms are wrongly spelt Here, as on page 119, l 1 mfra, Alola I is an error for I. I. Inla See 78 supra, where the correct form occurs The place-name is derived from Amla, Myrabolan Emblica. 'Bangash' is an error for 'Bangarh', which is again miswritten at 350 infra, q v my note See also Irvine, (A I. M, 561, 291), where the siege is described at some length

VIII 118, l. 1. The wazīr sent Rājā Rām Husain, his diwān

This must be another error of transcription. The name must be Rām Jīban and has been wrongly read or written as 'Rāmjīvan' is a common name and there are others also like it, e. g. Harjīvan, Prānjīvan, Jagjīvan, Sukhjīvan, etc. Rāmjībanpur is a well-known place in Midnāpur, Bengal Constable, 20 B d 'Atāipur (1 23) is in Farrukhābād near Fathgarh (Post Office Guide)

VIII. 119, l 4 The Jumna has a ford at Burya.

Būriya is now in Ambāla district Constable, 25 B b It lies on the right bank of Firūz Shāh's Canal and there is a ferry on the Jumnā in the neighbourhood Lat 30°-9' N, Long 77°-25' E It is mentioned at E D IV 519 and in the Tūzuk-i-Jahāngī; ī also Constable, 25 B b.

VIII 121, l 7 'Itimādu-d-daulā obtained . the titles of Imāmu-l-mulk, Khān Khānān

'Imāmu-l-Mulk' sounds strange and looks like an error His titles are given as, 'A'atamādu-d-daulā, Intizāmu-d-daulā, Khān-i-Khānān' in the M. U (I 361, 367) Zulfiqār Jang's real title was not S'ādat Khān سادت, as it is spelt on lines 2 and 6, but Sādāt Khān ادات (M U II. 526). The two words are etymologically quite distinct المناف is the plural of بادات Zulfiqār Jang was a nobly-born Sayyid His father had borne the same title. S'ādat Khān conveys no such implication

VIII 134, l 19 The Nawab Wazir halted for some days near . . Talkatorā and Khizrābād

This Khizrābād is about five miles south of the Dehli Gate of Shāhahānābād. It is said to have been built by and named after the Saiyid

ruler, Khizr Khān, in 816 H. 1413 A. C. (Aṣār, Pt. III. 25). The Tālkatora Garden still exists in Dehli and is a well-known place of public resort.

VIII. 135, l. 19. Zūlfikār Jang,...on pretence of going to pay a visit to the tomb of the Saint Shāh Mardān, went and joined the Wazīr's army.

The tomb of Shāh-i-Mardān in Dehli is near the mausoleum of Ṣafdar Khān. The Shāh-i-Mardān, "Prince of Men", is 'Ali, the cousin and son-in-law of the Arabian Prophet, an impression of whose foot (qadam) is said to be stamped on a stone there. For that reason, it is also called 'Alīji. (Āṣār, Pt. i. 87). Zamāna Beg, Mahābat Khān I, who had become a staunch Shī'a in later life is said to have left instructions that he should be buried below the 'qadamgāh' of the Shāh-i-Mardān. (M. U. III. 407-8).

VIII. 140, l. 2 from foot. After the defeat at Sikandra, Ahmad Shāh fled into the citadel of Shāhjahānābad.

This Sikandra or Sikandarībād is the place of that name near Bulandshahr, about 36 miles south-east of Dehli (Th.). Constable, 27 C a. At 272 infra, it is said to be twenty kos east of Dehli. The 'defeat' is described at 321-2 infra.

VIII. 141, l. 17. Akibat Mahmud,..... bringing forth 'Azīzu-d-daula,conducted him towards the royal palace.

The lagab of 'Ālamgīr II is printed here again as 'Azīzu-d-daula,' but it should be 'Azīzu-d-dīn, as at 140 supra and on 1.11 f.f. infra. It is inscribed as 'Azīzu-d-dīn also on his coins. Jahāndār Shāh had three sons, named A'azu-d-dīn, 'Izzu-d-dīn and 'Azīzu-d-dīn. (M. 'Ā. 345, l. 7; 516, l. 11). A'azu-d-dīn was blinded in 1126 H. and died in 1157 H. 'Izzu-d-dīn died in 1151 H. 'Azīzu-d-dīn was born in 1099 H. at Multān. (Irvine, L.M., I. 242. See also Beale, Miftāl, 340-1; H. S. M. N. 326-7).

VIII. 144, l. 5. This work was composed at the instance of His Majesty,
Abu-l-Fath Sultan Muhammad Shah Bahadur.

Dowson remarks in the footnote that "this is an error, as the Mughal Emperor Muhammad Shāh died in 1161 A.H. thirteen years before the battle, which is the subject of this work". But the animadversion is founded on a misconception or error of his own. The ruler referred to is the Safavi Prince Muhammad Shāh of Persia, who was living in exile at Lucknow as a pensioner of the East India Company. He fled from Persia to Sind in 1205 H., and finally settled at Lucknow in 1210 A.H. As the author says that he was in the service "of the late Nawāb Najaf Khān" (156 infra), the work could not have been written before 1196 H., the year of Najaf Khān's death. (Beale, Miftāh, 359).

The date of composition is said by Dr. Rieu to be not earlier than 1208 H. (Catalogue, II. 839-40 and I. 133). It could not possibly have been before 1204 H. q. v. note on 157, l. 13 post).

VIII. 147, l. 8. He [Alimad Shah Abdali] crossed the Jumna. and took

up his quarters at Sabit-Kasra for the hot weather.

'Sābit-Kasra' is an error for 'Sābitgarh,' one of the many names of Koil, now known generally as 'Alīgarh The name is derived from Sābit Khān, who was governor of the district about 1717 A C. (I. G., V. 218, Tieftenthaler, I 200) Other names by which Koil has been called are Muhammadgail and Rāmgarh. 'Alīgarh was given to it by Najaf Khān, who was a Shī'a, after its capture. (I. G s n).

VIII 148, l 9. Bhão and Wiswas Rāi .. moved towards Kunjpūra

Kunjpūra, lit 'the Heron's Nest', is in Karnāl talisīl. It was founded by the Ghurgasht Pathān, Nijābat Khān, in the marshes of the Jumna about the middle of the 18th century. (I. G. XVI 27). Lat 29°-43′ N., Long 77°-8′ E. Thornton notes that "in the battle between Nādir Shāh and Muhamma dShāh, a division of Persian matchlockmen concealed among the houses and orchards of Kunjpur fell upon the flank of the enemy during the height of the engagement and routed them with dreadful carnage"

VIII. 149, l 6. The Mahratta chiefs then sent Kākā Pandit .. towards Ghāziu d-dīn Nagar.

Ghāziu-d-dīn Nagar is on the route from Dehli to Murādābād, at about eighteen miles' distance from the former It lies on the left bank of the Hindan (*Chihār Gulshan* in I A. cix), Constable, 27 Ca It is now called Ghāziābād. Kākā Pandit's name was Govind Rāo Bundelā

VIII 149, l. 16 Hāze Nawāb Alkūzae.

'Halkozāi' or 'Alıkozaī' is the name of one of the eight clans or divisions of the Durrāni tribe, the others being Sadozai, Populzai, Achakzai, Barakzai, Nūrzāi, Ishāqzai and Khagwāni (Bellew, Races of Afghanistan, 20, Crooke, T and C. IV 161, Sir R C Temple in JASB 1879, XLVIII. p. 181)

The chief eunuch of Shāh Quli Khān, the Vazīr, must have been called 'Ākā Sandal' (150, 19), because is a man who has been emasculated in a particular manner, which is described in detail by Abu-Fazl in the Āīn. Two other types or classes of such persons are called Bādāmi and Kāfūi i. See Richardson's Dictionary, sv.

VIII. 151, l 6 from foot. Shāh Pasand Khān who was both a great noble and Charkhi-bāshi.

The spelling is 'Charkhchībāshi' in the T. J K. N. (347, 1.2) Sir William Jones renders it as 'Mattre d'Artillerie', but Mr Irvine thinks it means "Head of the Crossbow-men" and not 'Commander of the artillery' (A.I.M., 92). 'Charkh' has many meanings, wheel, cart, cross-bow, etc. Abu-l-Fazl describes the 'Charkhi' as a firework like our Catherine which, which was used to-frighten mast or unruly elephants. (Aīn, Tr. I 127) The Bahār-1-'Ajam says 'Charkhchi' means 'advanced guard.'

VIII. 151, footnote

The date of the third battle of Pānīpat is given here as 6th Jumādi II. 1174 H. on the authority of the Tārīkh-i-Ibi āhīm Khān. This was 13th

January 1761, according to Gladwin's Tables. According to the Mahrāthā chronicles, this fateful event took place on the Makar Sankrānti and the Hindu date is given as Paush Shudi 8th (13th January, 1761) in the letter written by Anupgir Gosāin to the Peshwā Bālāji Bāji Rāo (Kincaid and Parasnīs, III. 69 note). See also Sardesāi, Marāthāchi Riyāsat, Madhya Vibhāg, III. 260 and C. H. I. IV. 421. Grant Duff (H. M. 317), Elphinstone (H.I. 750) and Vincent Smith (O.H.I. 462) give 7th January, but there can be little doubt that it is wrong.

VIII. 156, l. 12. The Durrāni warriors pursued the fugitives as far as the villages of Ballamgarh and Farīdābād.

Ballamgarh or Ballabhgarh is five miles south of Farīdābad and 29 miles south of Dehli on the road from Dehli to Mathura. Lat. 28°-20′ N., Long. 77°-23′ E. It is said to have been founded by a Jat named Balu or Bilrām, a relative of Sūrajmal of Bharatpur. (Elliot, Races, II. 125). Faridābād (Constable, 27 C a) is named after Shaikh Farīd, Mu'azzam Khān, one of the great nobles of Akbar and Jahāngīr.

VIII. 157, l. 13 from foot. Thirty years ago, the author of this work
.....beheld the horse's skeleton
fixed in the battlements.

Dowson does not state when this work, the Manāzilu-l-Futūl, was written, but this incidental reference proves that it must have been after 1204 H., as the battle was fought in 1174. See my note on 144, 1.7 ante.

VIII. 159, l. 4 from foot. He was a scholar of Hakim-l-Mulk Takri Khān.

"Takri Khān' must be an error for Tuqarrub (﴿﴿ Khān. His originalna me was Muḥammad Dāūd. He was the physician who was employed to treat Jahānārā Begam, when she was severely burnt all over the body by accident. He died in 1073 A.H. (Bādshāhnāma, II. 367, 369, 399, 766; M. 'Ā., 42, l. 12; M. U., I. 190; E. D. VII. 118). He is said to have treated Shāh Jahān's great minister S'adulla Khān also in his last illness. He is frequently mentioned by Manucci.

VIII. 161, l. 2. Mulammad Shah left the city of Dehli to go on a hunting excursion to the village of Sioli.

This was in Jumādi II. 1135, January-February, 1723 A.C., and the chronicles record that the stages on the route were Agharābād, Nārela, Siyūbi [Recte, Siyūli], Ganaur and Pānīpat. (Irvine, L. M. II. 125 and the authorities cited there). Farrukh-Siyar also is said to have hunted in or around Siūli in 1130 A.H. (Ibid, I. 344 and Note).

VIII. 166, l. 14. In the third year of Ahmad Shāh's reign, corresponding with A. H. 1160.

There is some error here. The third year of Ahmad Shāh's reign began on 28th Rab'ī II. 1163 H., as his father Muḥammad Shāh had died on 27th Rab'ī II. 1161. (Vide 111 supra).

VIII. 169, l. 18. Jahān Khān.....pitched his tents at Kachchi-Serāi.

Kachchi Sarāi or Kachchā Serāi is about ten kos north of Lāhor and is mentioned by Finch in his Itinerary as 'Coojes Serāi' (E. T. I. 167) See also De Laet, Tr. Hoyland, 55 Tieffenthaler makes it 24 miles from Lāhor and six miles north of Emīnābād (I. A. eii)

VIII. 170, l. 1 Najibu-d-daula . departed to Sakartāl on the banks of the Ganges

Sakartāl is in Muzaffarnagar district and contains a fort erected by Zābita Khān Lat 29°-29' N, Long. 78°-3' E (Th) Scealso my note on Ghausgadh, VIII 258 post

VIII 170, l 7 from foot The Abdāli sacked Dehli and encamped at Anūpnagar

Anūpsingh Badgujar, a favourite courtier of the Emperor Jahángír, who gave him the title of Anīrāi Singhdalan (T. J Tr. I 185-8, 263, 336, 373). "The town was of great importance in the 18th century, as it commanded an important crossing on the Ganges on the road from Dehli to Rohilkhand" (I. G. V, 388)

VIII. 175, l, 18 The affair of Lat Dong

Recte, "Lāl Dhāng" It is the name of a strong fort in the forest on the borders of Bijnor district, which often proved a safe refuge in the struggles between the Rohillās and the Nawābs of Oude. Lat 29°-52 N, Long 78°-23′ E (I.G. VIII 194). The 'Affair of Lāl Dong' was the treaty signed in 1174 A C, by which Shujā'u-d-daula agreed to give a jāgīr of 15 laks to Faizulla Khān. (Gulistān i-Rahmat, Tr C.A Elliot, 125-7). The title, Tār īkh-i-Faizbakhsh, was chosen as a compliment to Faizullā Khān Rohillā, by whom the author, Shiv Prasād, was employed as his agent in negotiations with the Colonel of the British forces at Bilgrām (Rieu, I. 306) A translation of the Tārīkh-i-Faizbakhsh was published by Dr W. Hoey, at Allāhābād, in 1888.

Jalkanā (176, l. 8 ff) is, most probably, Chilkia (﴿), in Morādā-bād district, "on the northern frontier towards Kumāon, in the pass or gorge through which the river Kasila flows towards the plains" (Th) Lat 29°-21′ N., Long 79°-10′ E

VIII. 190, l. 7 from foot. When Rājā Uchaina made a treaty and agreement with Mu'azzam Khān Fathpuri at Allāhābād

Recte, 'Rājā Ujainiya.' The reference is to the Rājās of Jagdishpur and Bhojpur in Shāhābād, Bengal, who claimed to be descended from the Pramāra Rājās of Dhār and Ujjain. Their capital Bhojpur is supposed to have been named after the celebrated Rājā Bhoja of Dhār (Blochmann, Āīn, Tr I 513) See also my note on VI. 321, 19. ante "The Rājā who made the treaty," ie who was assured of forgiveness and safety on behalf of the Prince Salīm, was named Dalpat. Mu'azzam Khān Fathpuri was Jahāngīr's foster-brother, Shaikh Bāyazīd, qv MU. III 365 VIII. 196. 114 from foot Dūvān-v-Tan or overseer of the household.

He was Diwan of the Tankhwah or salaries of the troops.

VIII. 200, 1. 5. This is a compilation by Ghulam Basit, undertaken on the suggestion of an English Officer.

The name of Ghulām Bīsīj's patron has been read here as 'Charles Burt,' but Dr. Rieu has shown that it was Giles Stibbett. He was Commander of the Bengal Army from 1777 to 1779 and again from 1783 to 1785. (Catalogue, I. 237 and Note). There is a copy of the work in the Mullā Firūz Library in Bombay and Mr. Rehatsek also has read the name as 'Jayles Estbet'. (Catalogue Raisonné, Section IV. No. 15, p. 76).

VIII. 202, 1, 20. Their [of the people of Malabar] chief is called Ghaiar (Ghamyar?).

'Ghair' is a copyist's blunder for A Nayar, i.e. Nairs. All the four paragraphs translated here have been copied by Ghulim Bisig from the Account of the Kings of Malabir in the history of Firishta, who states on the authority of the Twifatu-l-Majāhidin, that the " علي [tribes, families] of the country are called Niyār." (II. 373, 1. 15).

VIII. 215, l. 13. Afterwards, they crossed the Ganges, and proceeded to Mahdighat.

This appears to be the same as Mahdipur of 276 infra, which is said to have been in Etima and on this side of the Ganges. Bibipur (1, 22) may be the place of that name on the route from Fathgarh to Cawnpore, thirty-two miles north-west of the latter. (Th.). Lat. 26°-49′ N., Long. E0°-8′ E.

VIII. 217, l. 1. [The English left the city of Patna and] assembled at Bach Pahāri, six kos from that city.

Recte, "Panj Pahāri." They are five old Buddhist or Jaina stupas, half a mile south of Papa. (Smith, Akbar, 127 note). Nigāmu-d-dīn Ahmad states that it was a monastery near Patna. "This Panj Pahāri or Five Domes is a place built in old times by the infidels with burnt bricks in five stages." (T. A. 319, l. 1=E. D. V. 378; B. II, 179=Tr. 182).

VIII. 221, 1. 11. On leaving Lucknow, the Nawāb encamped at a bāoli, (well), near Rustam-nagar.

Rustamnagar was one of the older names of Murādābād, which was also called Chaupla. See my note on Vol. III. 538. It is called 'Chaubāla' by Budāuni at E. D. V. 507. "Simru Gārdi" is 'Sombre,' the husband of the 'Begum Sumroo.'

VIII. 232, 1. 2. Tarikh-i-Shahadat-i-Farrukh Siyar.

Another valuable history of the reign of Farrukhsiyar, which does not appear to have been known to Elliot, is the Farrukhsiyarnāma of Muhammad Ahsan Ijīd, which was written about 1131 A. H. (L. M., I. XII). A Muhammad Mun'im Jāfarābādi also wrote a Farrukhnāma about 1123 A. II. (Ibid, A. I. M., 302).

VIII. 238, l. 19. 'Imidu-l-Mulk set about a reformation of the cavalry and Sin dagh syste:

This obscure phrase is thus explained by M1. Irvine. "It is obvious that in addition to the Imperial brand $(d\tilde{a}gh)$, a second brand was required by each noble for the recognition of the horses ridden by his own men. Towards the end of the Mughal period, the great nobles often had the first or last letter of their name as their special brand (Seir, I. 481, Note 27), as for instance, the Sin- $d\tilde{a}gh$ [σ] of S'adat 'Alı Khan' Nazim of Oudh. The brand of Sayyad 'Abdulla Khan was the Muhammad Ishaq Khan, about 1153 A.H., used the last letter of his name, a $g\tilde{a}f\tilde{\sigma}$ as his brand." (A. I. M, 50).

VIII. 243, l. 6. This tragedy [murder of 'Alamgir II] occurred on Thursday, the 20th of Rab'iu-s-sāni, 1173 A. H

The correct date was the 8th Copyists often mistake and for and vice versa 8th is given in the Shāh 'Ālam Nāma (B.I. text, 93) and Mirāt i-Ahmadi, (I. i 111, l 1). See also my H S.M.N. 287. The Julian correspondence of 8th Rab'i II was 29th November, 1759. It was a Thursday. The 20th of Rab'i II 1173 H., i e 11th December, was a Tuesday

VIII. 247, l 17 [Bidar Bakht] then ascended the throne on the 27th Shawwal 1204 A.H (22nd June, 1790).

Recte, 1202 A H See ante 244, 245, 246, where the year is repeatedly given as 1202 H The Julian correspondence is also wrong It was the 31st of July, 1788 Mr. H. G Keenc, following the Tārīkh-1-Muzaffari, makes it 29th July 1788, while Mr Seton-Karr gives 2nd August 1788. (Selections from the Calcutta Gazetteers, I. 263).

VIII. 250, l. 19. Tărâji Bhão.

'Tārāji' is not a part of the name but an opprobrious epithet, signifying "plunderer, ravager, looter" The raison d'être of the by-name is provided by the author of the Tārīkh-i-Ibrāhīm Khān, who bitterly complains that this Mahrāthā vandal broke to pieces the silver ceiling of the Dīwān-i-Khās and coined seventeen lakhs of rupees out of the metal (276, infra) The Mahrāthā chroniclers themselves boast that he stripped the tomb of Nizāmu-d-dīn Awliyā of its treasure and silver ornaments, rifled the mausolea of the Emperors and seized the golden throne and canopy (Kincaid and Pārasnis, III 63)

VIII. 253, l 7 Ghūlām Kādır started off for Ghaus-kada, his home

Recte, Ghausgadh, "Heavenly-help Fort." It was "one of the three forts in the Bāwani Mahāl (now included in the Muzaffarnagar and Sahāranpur districts) They were Pathargarh on the left, Sakartāl (or Sukhartāl) on the right bank of the Ganges and Ghausgadh, about eleven miles north-west of Muzaffarnagar. The first two had been built by Najīb Khān to protect the ford, which led to his fief in the north-western corner of Rohilkhand, for the Ganges is almost always fordable here except in the high floods. The last was the work of Zābita Khān." (Keene, Fall of the Mughal Empire, 96, see also M U III. 867, 1 4 ff, I. G. XVIII. 87).

VIII. 263, 1. 6. The freebooters who form the vanguard of the Mahratta forces andravage the enemy's country are called pūikārahs; the troops who are stationed as picquets for the purpose of keeping a vigilant watch are styled Mātī.

'As Pūīkārah and Mātī are both unintelligible and manifestly corrupt, it may be worth while to note that in a Manuscript of the Tārīkh-i-Ibrāhīm Khān, which is in the Cama Oriental Institute, Bombay, the first word is written 'Lūnkāra, which may be meant for Lūtkāra, Plunderers. Lūtmār is a common word in the vernaculars. See also 'Looty' and 'Lootiewalla' in H.J. 520. 'Māti' is spelt there as It may be really Bātmi, which means 'news, intelligence, secret information, espionage' in Gujarati as well as Marāthi.

VIII. 264, l. 2. At length, in the year 1163 (1750 A. D.), Sāhū Rão, the successor of Sambhāji, passed away.

The date is wrong. Elphinstone (H. I., p. 727) gives June 1748, which corresponds to Jumādīu-s-ṣāni, 1161 H., and this is followed by Mr. Vincent Smith in the O.H.I. 457. But the event really occurred on Friday, Mārgashirsha 1671 Shaka or 15th December 1749. (Sardesāi, Riyāsat, III. 119; Kincaid, II. 300).

VIII. 265, l. 16. 'Alamgir (II) had an interview with him [Aḥmad Shāh] on the margin of the Maksūdābād lake.

This must be Mas'ūdābād, which lies about fifteen miles south-west of Dehli. Ibn Batūṭā states that he halted at Mas'ūdābād, on his way from Hānsi to Dehli. (Tr. Lee, 110). Najaf Khān built a fort here called Najafgarh, which is said by Thornton, to have been situated on the west shore of an extensive jhil or lake, formed by the overflow of the Hansouti torrent during the rainy reason. Constable, 27 C a.

VIII. 267, l. 7 from foot. Jankūji entrusted the government of Lāhor to a Mahrātta, called Sāmā.

Here, has been wrongly read or written as h. His name was Sābāji or Shābāji and he was a relation of Dattāji Sindhia. (Grant Duff, 310).

VIII. 269, l. 6. Govind Pandit.....allowed no portion of Chandpur...... to escape conflagration and plunder.

This must be Chandpur in Bijnor, 42 miles north-west of Muradabad. Lat. 29°-8′ N., Long. 78°-20′ E. (Th.). Constable, 25 C c.

VIII. 271, l. 17. [Dattā] took up a position in the plain of Bāwali, which lies in the vicinity of Shāhjahānābād.

Here the has been confused with s. Read Bādli. It lies about seven miles north-west of Dehli and is now à railway station. It is correctly mentioned as 'Bādli' at 320 infra. See also my note on Vol. V. 407, 1. 5 f. f.

Jankuji is represented here as the uncle and Datta as the nephew, while on line 24 of the same page, the position of the two men is reversed and Datta is said to be the uncle. At 268, Datta Sindhia is called Jan-

kuji's uncle, and this is correct Jankoji was the son of Jayappa Sindhia, the brother of Dattaji. (Grant Duff, 310, 312).

VIII. 271, l. 3 from foot. Malhar Rão Holkar, who at that time was staying at Makandara.

This is the Mokundra [Mukundwāra] Pass in Kotah, Rājputānā, 90 miles north-east of Nīmach and 32 south-west of Kotāh town Its strategical importance is due to its being "the only practicable pass for carriages, for a considerable distance over the range extending from the Chambal to the Kali Sind" Lat. 24°-50′ N., Long 75°-59′ E. (Th). Constable, 27 C c. The name is said by Tod to be derived from Mukunda, Rājā of Kotah, who fortified it about 1630 A. C.

VIII 273, l. 4 from foot Jaswantrão Bewär

"Bewar" عواد is an error for "Pawar" عواد (Grant Duff, 213, Kincald III. 60). See also 400 infra, where he is correctly styled "Panwar" (Pramar) The name of Jaswant Rão's tribe is again wrongly printed as 'Balwar' on 282 infra. He was a descendant of Shivaji Pawar or Puār, Patel of the village of Maltan, 30 miles north-east of Poona.

Jan Rão's surname was *Dhamdhere*, not 'Dhamadsarı.' A village called Tālegāon-Dhamdhere near Poona is shown in Constable, 31 C b.

VIII. 278, l. 2. Sarāi Badarpur, which is situated at a distance of six kos from Dehli.

"Less than three miles east of the Surajkund, the road reaches that from Dehli to Mutrā at Badarpur, built inside the enclosure of an old Sarāi This place lies about eight miles distant from Nizamu-d-dīn and the Mausoleum of Humayun" (Fanshawe, D. P. P. 292) Keene states that Badarpur is ten miles south of Dehli. It is mentioned as 'Badelpour,' by Tavernier (Travels, I. 104)

VIII 283, l 1. Appāgi Gārkawār and Bithal Sudeo.

Here, the personal name and not the sobriquet is wrong Appāji is an error for 'Dāmājī' and the mistake recurs at 400 infra

"Bīthal Sūdeo" was Vītthal Shivdeva Vinchurkar. (Grant Duff, 313, Kincaid, III. 73, 75).

VIII 284, l. 17 Karāza twelve kos from Jhānsi, towards the west. This is 'Kurāra' of Thornton, 'about 28 miles west of Jhānsi and on the right bank of the Mohwar river' Lat 25°-28' N, Long 78°-13' E (Gaz 543). It is the 'Karehra' of Constable, 27 D c, and is now in Gwālior State. (See also Silberrad, JASB, 1902, p 105 note) Kurāra in Hamīrpur (Constable, 28 B b) is a different place

VIII. 286, l 3 Bithal, Diwan of Nawab Nizam 'Ali Khan Bahadur

This "Bithal" is not Vitthal Shivdeva Vinchurkar, but Vitthal Sundar Raje, who was given the title of Raja Pertabwunt [Pratapvant] by his master (Grant Duff, 327, Kincaid, III. 85, 87, 88). Gopal Rao (17) was Gopal Rao Govind Patwardhan, Jagirdar of Miraj (*Ibid*).

The battle which is said on 1.9 f f. to have been fought on the bank of the Godavari, was that of "Rakisbone" or 'Rakisbone' [Rakhshas-

bliuvan] or Tandulja. (Grant Duff, 329; Kincaid, III. 87-8). It lies 37 miles south-west of Jalna. Constable, 31 C b.

VIII. 289, l. 22. Kankumā Tāntiā.

Here as well as on 1. 1, 290 infra, read 'Gangūbā' Tāntiā, i.e. Gangādhar Yashvant, the Diwān of Holkar. (Grant Duff, 340; Kincaid, III. 79, 94). His surname appears to have been Chandrachūd. (Sardesāi, Riyāsat, 42, 131, 228).

VIII. 292, l. 18. Shamsher Singh.

Recte, Sumer Singh. (Grant Duff, 360; Kincaid, III. 104).

VIII. 293, l. 11. Sakhārām Bāpu in unison with Trimbak Rāo, commonly called Matāmādhari Ballah and others deemed it advisable.

'Matāmādhari Ballah' is obviously bungled. The correct reading must be الماء في الله "Trimbak Rāo, commonly called Māmā and Hari Ballāl and others." Trimbakrāo Vishvanāth Pethe was generally called 'Māmā', because he was the maternal uncle of Sadāshiv Chimnāji Bhāu. (Grant Duff, 325). "When the Peshwā Mādhav Rāo assumed the supreme control of the government and Sakhāram Bāpu resigned the office of Diwān, Trimbakrāo Māmā was appointed to the post and Hari Ballāl Phadke and Bālāji Janārdan Bhānu (i. e. Nānā Phadnavīs) were nominated as the Peshwā's private secretaries." (Kincaid, III. 82. See also Ibid, 85, 97; Grant Duff, 326).

VIII. 295, l. 11 from foot. Nurghat, twenty kos from Puna.

A mistake for 'Borghāt' or Bhore Ghāt, a pass in the Ghāts on the road from Bombay to Poona, "which was considered to be the key of the Dekkan in the early wars of the East India Company with the Maharattas." (Thornton, 111). It is about 40 miles south-east of Bombay and the same distance north-west of Poona.

VIII. 300, l. 7 from foot. Tārīkh of Jugal Kishwar.

Recte, 'Jugal Kishore.' The "wav" is a vowel and not a consonant here. The Hindi 'Kishore' has nothing to do with the Persian Kishwar, 'Continent.' It is really a form of "Keshavrai," one of the many names of Krishna. Dr. Rieu (Cat. 1027, 1051), reads the name as 'Kishor'.

VIII. 303, l. 12 from foot. Hāfiz Rahmat was returning from Farrukhābād to Tilhar.

Tilhar lies on the road from Shāhjahānpur to B areilly, 12 miles W. N. W. of the former. Constable, 28 A b.

VIII. 304, l. 4. He proceeded to Nanakmath in the skirt of the hills.

Nānakmath lies 22 miles north-west of Pīlībhīt town and on the right bank of the Garra. Constable, 28 A a.

The Shāhābād which is mentioned here (l. 12) is now in Rāmpur State and is the old Lakhnor, the seat of the Katheriya Rājās. (Elliot, Races, II. 138). Constable, 28 A a.

VIII. 306, l. 12 from foot. Hāfiz Rahmat.....sent Ahmad Khān....... from Ānwala to secure the ford of Rām-ahāt.

Rämghät in Bulandshahr is situated on the right bank of the Ganges on the route from 'Alīgarh to Bareilly, thirty miles north-east of the former. The river is here crossed by a ferry (Th.). Constable, 27 D a.

Asadpur (1 2 f f.) lies on the loute from Bulandshahr to Budaun, forty-two miles west by north of the latter The town of Gannaur was at one time in this pargana of Asadpur, which was formed from parts of Gannaur and Jadwar. (Elliot, Races, II. 138-9)

VIII. 310, l 5 from foot. The Nawāb prepared to pass the Ganges by way of Koriyāgang.

Koriyaganj lies sixteen miles south-east of 'Aligarh' on the route from that town to Bareilly (Th.).

VIII. 311, l. 9 from foot. Hasiz Rahmat .. . entered Faridpur, seven hos to the east of Bareilly

Faridpur is twelve miles south-east of Bareilly and was originally called 'Tappa Khalilpur' (Elliot, Races, II 145) Constable, 28 A a.

VIII 311, l 4 from foot. Hafiz Rahmat then . . encamped in the groves around Karra.

Recte, 'Katra', which is said to have been seven los distant from Tilhar in Shāhjahānpur (Gulistān-i-Rahmat, Tr [Sir] C A. Elhot, 114) Thornton states that Katra is also called Miranpur-Katra and is "situated at the spot where the road to Fathgarh passes off to the right from the direct line to Shāhjahanpur" The origin of the double name is that Katra was founded on the ruins of the old town of Mīranpur by Kamālzāi Khān in the days of Aurangzeb (Elliot, Races, II. 145) Constable, 28 A a. VIII 316, l 2 Tārīkh-i-Muzaffari.

The Tārīkh i-Muzaffari is really the third volume of the Bahru-l-Mawwāj, of the same author, which has been noticed on p 235, but under a new title In Elliot's Manuscript, the history was brought down only to the death of Āṣafu-d-daula in 1797 A C, but the British Museum possesses a copy going upto 1810 A. C. or 1225 A H. (Rieu, Catalogue, I 263)

VIII. 322, 1 8 He went off to the town of Khoraja

This is 'Khurja' in Bulandshahr. The name is said to be derived from the Pers. Khārija, 'revenue-free,' as the town is said to have been built by Bhale Sultān Rājputs on a revenue-free grant made by Sultān Firūz Tughlaq (I. G XV. 297)

VIII 330, l. 12 Bhagwangola

Bhagwangola is in Murshidabad, on the right bank of the Ganges and about 120 miles north of Calcutta. Constable, 29 C c. It was the riverport of Murshidabad town Constable, 29 C c.

VIII. 332, l 3 from foot. The name appears to be derived from the poetical name of Aftab, which the author assumed by direction of Shah 'Alam

The Mirat-i-Aftābnûma is said here to have been so called, because 'Aftāb' was the poetical title, which the author assumed by direction of Shāh' Alam II, but this seems to be an error. Aftāb was the nom de

plume of Shāh 'Ālam II. himself. The history is the Mirror in which, so to say, the exploits and character of this $\overline{A}ftab$, i. e. Shāh 'Ālam, are clearly reflected. Another reason for incorporating the word 'Āftāb' in the title of the work is that is in a chronogram. 40 + 200 + 1 + 1 + 400 + 1 + 1 + 80 + 400 + 1 + 2 + 50 + 40 + 1 = 1218 H. (Rieu, I. 132; Muqtadir, VI. 71). The work was composed in that year (1803 A. C.).

VIII. 334, 7. 8. 'Aliwardi Khān Turkomān was the inventor of a mode of hunting styled Tūrkalāni.

This Turkalani is a misreading of get Bawar-i-Kalani, 'the big net.' The statement made in the footnote on the authority of the Maasir-u-l-Umarā is really copied by its author from the detailed description of the net in Mu'atamad Khān's Iqbālnāma-i-Jahāngīri (Text, 272, 1.6 = E. D. VI.). Mu'atamad Khān says that the net was called Bāwar in Hindi. This reading, Bāwar, seems to be correct, as 'Bāwariya' is the designation of a hunting tribe found even now in Muzaffarnayar and Mirzāpur. The name of the tribe is derived by Mr. Crooke, from 'Banwar,' a creeper, (Sans. Bhramara), "in the sense of a noose, made originally from some fibrous plant and used for trapping animals, which is one of the primary occupations of the tribe." (Tribes and Castes, I. 228). 'Kalāni' means 'large.' But the Hindi word may be 'Nawār,' which is used for stringing cots. The net may have been made of this 'Nawār.'

VIII. 340, l. 2. Nawāb Mumtāzu-l-Mulk Sarbuland Khān.

Sarbuland Khān's real title seems to have been Mubarizu-l-Mulk. (Kh. Kh. Text, II. 1106; M. U. III. 801. See also 44 ante).

The name of his birth-place also is wrongly given on I. 3. He was not born at 'Lūni' near Dehli but at $T\bar{u}n$ in Persia, from which he came to India, with his father Mirzā Afzal, entitled Muqtadawi Khān, in the reign of Aurangzeb. (M.U. III. 801, 805). 'Alāu-l-Mulk $T\bar{u}ni$, entitled Fāzil Khān, who was one of the Vazīrs of Shāh Jahān and Aurangzeb, was also a native of $T\bar{u}n$. (M. U. III. 524, l. 12).

VIII. 347, l. 16 from foot. His eldest son...was superintendent of the bath and the private chapel.

Here 'Ghuslkhāna' is again wrongly rendered as the 'Bath.' It was also called Khilvat Khāna and was the Private Hall of Audience or Privy Council Chamber. The Dārogha of the Ghusl Khāna was usually an official of very high rank and one of the principal ministers. Thus Ṣādiq Khān, who obtained the post in the 20th year of Shāh Jahān's reign, was a commander of Six Thousand at the time. The importance of the office seems to have varied at different times. The 'Private Chapel' was the Tasbīh Khāna or Jā-nimāz Khāna, the room where the Emperor used to tell his beads in privacy and say his prayers on a Jānimāz or carpet.

VIII. 350, l. 10. At the time when Muhammād Shāh Bādshāh went against 'Ali Muhammad Khān, and besieged the fort of Bangash.

Here as well as at 116 ante, 'Bangash' is an error for 'Bangarh' (A.I M., 261, 291) See the Gulistān-i-Rahmat (Tr. [Sir] Charles A. Elliot, p 20), where the fort is called 'Bungurh' and said to lie "five kos distant south of Aonla and surrounded for a distance of two kos by jungle." 'Ali Muhammad Khān's correct nisba was 'Rohillā' Bangāsh was the sobriquet of the Nawābs of Farrukhābād

VIII 358, l. 12. The four Imams, founders of the Sunni doctrines, and the ten persons who are said to have gone to Paradise.

The phrase عشرة مشرة literally signifies 'The ten receivers or harbingers of good tidings' and is used for "the Ten Evangelists", so to say, of Islam These ten persons were assured of Paradise by Muhammad and are thus enumerated in the Tārīkh-i-Guzīda of Hamdulla Mustaufi. The four Khalīfs, Talha, Zubair, S'ad bin Abi Waqqās, Sa'īd bin Zaid, Abu 'Ubaida and 'Abdu-r-Rahmān bin 'Auf. (Text, I. 209-11. Tr 51) They are referred to by Ḥasan Nizāmi and Minhāj also (E. D II 206 and 261) VIII. 360, l 16 He was a zamīndār of mauza Sansani

Sansani is a mauza or village situated eight miles south of Dig. 'Waira' or 'Wer' lies about thirty-five miles south of Bharatpur Constable, 27 C b 'Thūn' lies between Dig and Gobardhan, west of Mathura, about twelve miles west of Sansani (I G VIII 95, A I M, 285) Kumher, Kumbher or Kumbhergarh is six miles to the south-east of Sansani It is said to have been founded by and named after a Jāt named Kumbha. (I G XVI 22) Constable, 27 C b Barsāna (p 366, 1 22) is fourteen miles north of Dig

VIII. 365, l. 19. He at last glutted his vengeance by wresting the territory of Kāmūn from Rājā Madhu Singh (of Jaipur).

This is not Kumāon, but an error for Kāmān (Pahāri), q v my note on VIII 55 ante

VIII 367, l 13 from foot. When the British, after reducing
the strong forts of Dig and Kishengarh,
determined to take the fort of
Bhartpur [in 1218 A. H. 1203 A C]

Here as well as on 268, I 10, and 270, I 16, 'Kishengarh' appears to be an error for 'Kumhergarh' See 360 and 362 ante, where Dig and Kumbher are mentioned in juxtaposition. The mistake may have been due to the resemblance between 'Kumbhar' and 'Kanhar' or 'Kanhad,' which is one of the dialectic forms of Kishan (Krishna).

Dig and Kumbher are associated together eleven lines higher up on this very page.

VIII. 376, l 2 Akhbar-1-Muhabbat.

Elliot says nothing about the author of this work, except that his name was Muhabbat Khān Dr Rieu tells us that he was the son of a Rohillā chief named Faiz 'Atā Khān Dāudzai, who was fifth in descent

from Diler Khān Rohillā, who played a conspicuous part in the wars of Aurangzeb and died in 1094 A. H. (Catalogue, III. 911).

VIII. 379, l. 3. Gholghāt and Mughalpura near Hūghli.

This is the 'Golgot' of Orme, in whose 'Historical Fragments of the Mogul Empire', Job Charnock is described as "the governor of the Factory at Golgot near Hughley." (Edit. 1805, pp. 281, 283). Yule says that Golghāt appears to have been the name of the particular locality where the English factory at Hūgli was situated. (H. J. 146).

VIII. 380, l. 4. The police station at Makhūā.

The 're' has been wrongly read as a "wav". 'Makhūa' must be Magra, Mugra or Moghra, (مكرا), which is now a station on the East Indian Railway, about five miles from Hugli. (Blochmann, Inscriptions in Hugli District, J. A. S. B. XXXIX (1870), Pt. i. 280). The place where Job Charnock anchored and which is known by the name of Chanak (l. 3 f.f.) is 'Achanock.' Sir H. Yule says that it is the "designation by which Barrackpore near Calcutta is still known to Sepoys and other natives. Some have connected the name with that of Job Charnock, the founder of Calcutta. But this is rendered improbable by the fact that 'Tajannok' is entered as the name of a village opposite 'Ogly' in the map of Bengal in Valentijn, which appears to have been compiled in 1662, though Valentyn's book was published only in 1726." (Hobson Jobson, s. v. Achanock). Charnock appears to have come to Sutanuti-a village north of modern Calcutta in 1686, after his skirmish with the Mughals at Hugli and formulated certain demands, the rejection of which by the Nawāb led to hostilities and his seizure of Hijīli. He returned to Sutānati in 1690 at the invitation of the Nawab and laid the foundations of Calcutta. (I. G. IX. 263).

VIII. 383, l. 21. Chochra (Chinsura).

"Chinsura" is still called 'Chuchura' by the inhabitants and 'Chichira' is the form found in the Translation of the Siyaru-l-Mutaākhirīn. (Reprint, 1902, II. 225). The name is said to be derived from 'Chirchira,' a weed, Achyanthes Aspera, with which the place abounded. (N. Dey, History of Hūgli, in J. A. S. B. 1910, N. S. VI. p. 601).

VIII. 385, l. 20. Goa, Dābul and Chand.

As 'Dābul' is certainly meant for Dābhol in Ratnāgiri, 'Chand' must be an error for Jiz Chenwal or Chīval, the Chaul of the Portuguese and Saimūr of the old Arab writers. The great naval battle, which is said at 387 infra to have been fought at 'Chand' between the allied Sultāns of Gujarāt and Egypt and the Portuguese was really waged near Chaul in 913 A. H. 1508 A. C. (Mirāt-i-Sikandari, Text. 126, l. 9—Tr. Bayley, 222; T. A. 479, l. 4 f. f.; Firishta, II. 371, l. 2 f. f.; Elphinstone, H. I. 765). VIII. 386, l. 2. Ports of Kandāria and Kālikot.

'Kandāria' or 'Qandāria' is an error for 'Fandaraina,' the Arab form of Pandarāni, which lies near the Sacrifice Ruck of mode ps, about thirty miles north of Calicut. It has been now ppl uilandi.

('Koilad' of footnote), which is shown in Constable, 35 A a VIII. 388, l. 5 from foot. The Firingis founded a fort at Jāliāt, six kos from Kālikot.

'Also written Chalia, Chale, Chaliyan, Chalayom This is the 'Shāhyāt of Ibn Batuta (Defrémery, IV. 109) and 'Chalyani 'of Barbosa. (Tr Stanley, 153). Chālyan was an old Malabār port, formed by the Beypore and Kodalundi rivers and lay opposite to Beypore. Beypore is marked in Constable, 35 A a (See Yule H J s v Chalia).

VIII. 389, l. 6. Sultān Sālīm of Rūm ... despatched his minister Sulaimān Bādshāh in command of one hundred vessels.

The author must have meant to write 'Pāshā' (1212). He is spoken of as 'Solyman Bāshāw, Governor of Cairo, in Danvers' History of the Portuguese in India (I 425) and as the commander of the fleet. See also Whiteway, Rise of the Portuguese Power in India, 256, 265. He was by birth a Greek converted to Islam.

VIII. 392, l 2 from foot. Shikakul, Rajbandar and other possessions of the French

The place meant is Rājmandri, now in Godāvary district. The mim has been wrongly written as a be. It is the 'Rājā Mahendra' of Jahāngīr's Memoirs in E D. VI. 355, q. v my note. The name is derived from Mahendragiri, a mountain range in Ganjam, which is frequently mentioned in Sanskrit literature. It has nothing to do with 'Bandar' 'port.'

VIII 393, l 10. Tārīkh-i-Shāh 'Alam

Sir Henry Elliot's copy of Manu Lāl's History of Shāh 'Alam was, like most other copies, defective or imperfect and extended only to the 24th year of that Emperor's reign. A Manuscript in the Bānkīpur Library brings down the narrative upto the 48th year It contains a regular and detailed chronicle of all important transactions upto the 30th year. But the author states that as he had grown old and his eyesight was failing, he had been obliged to rest content with a bare summary of the events of the remaining eighteen years. (Muqtadir, Catalogue, VII. 95).

VIII. 399, footnote Sherbachas (pistols) of Kābul and two thousand small guns carried by camels

This 'Sherbacha' was a musketoon or blunderbuss. "In the last quarter of the 18th century, there was," writes Mr. Irvine, "a regiment of Persian horse in the Lakhnow service, known as the Sherbacha They may have taken the name from the weapon with which they were armed, or the name may have been due to their supposed ferocity." (AIM, 112). VIII. 400, l. 12 Appān Mangesiah.

The real name of the man was Antaji Mānkeshwar. (Grant Duff, 313, Sardesāi, Riyāsat, III 204).

VIII 407, l. 2 from foot. Nawābganj, which is six kos from Allahābād.

Five places called Nawābganj are entered in Thornton's Gazetteer.

This must be that which lies eleven miles north-west of Allahābād on the

.

route to Lucknow.

VIII. 420, l. 5. There is only one copy of the Yadgar-i-Bahaduri in existence, the autograph of the author, in my possession.

Dr. Rieu denies this claim and states that Sir Henry Elliot's copy of the Yādgār-i-Bahāduri could not possibly be the author's autograph, as it contains several clerical errors which can only be ascribed to a copyist, (Catalogue, III. 897).

SOME MINOR EMENDATIONS.

[There are several other misprints, misreadings and minor mistakes of transcription or transliteration in these eight volumes. They were not included, at first, in the body of this work, for fear of distracting the reader's attention. They have been thrown together in an Appendix and dealt with briefly, as it has been impressed upon the writer that they should not be overlooked, on account of their liability to mislead Hindu and European scholars unacquainted with Persian The correct forms are printed in Italic type All corrections indicated by Dowson himself in his Errata have been excluded]

- I 117, 1 3 'In the reign of Mu'awiya, son of Abû Sufain 'Read Sufian
- L 156, l. 3 'Allāsi killed 'Abdu-r-Rahmān, son of Ash'ab.' Correctly, Ash'as, as at E.D. I 428
- I 197, l. 11. 'A report was also sent to 'Abdu-l-Malık, the Khalifa of the time.' The Khalifa of the time was Walid, the son of 'Abdu-l-Malik, who reigned from 86 to 96 A. H. See E.D. I. 428.
- I. 215, l 13 'Jānī Beg. . was succeeded . by Mırzā 'Āsı.' Read Ghāzī
- I. 221,1 18 'He came to a place Daryācha Nārī Sang'. Is it not Daryācha, i.e. rīver, of Nāra Sānkra or Sankrā? See E.D. I. 294
- I. 252, 1 5 'Conquest of Ahmadnagar and the fort of Kasım.' Read Asîr [garh].
- I. 292, 1. 18. 'Tribes of Bina, Tak and Nabūmiya' The last name must be the same as Nahmrūi of E.D. I. 286, q. v. my Note.
- I. 293 footnote, 3. 'She was his sister's son.' Read daughter.
- I 301, Footnote, l. 2 'Rai Khanhar of Kach' Read Khengar.
- I. 302, 1 18. 'Sharīru-l-Mulk' Read Sharīfu-l-Mulk as at E.D. VI. 432, 444
- I. 304, 1 3 'Sultan Husam bi-l Karar' Read Barqara or Bargra.
- I. 312, 1 2 'Bhara and Khushib.' Read Bhera [on the Jhelum].
- I 314, 1 11 f f 'Bulüch, Jat, Rind, Dadi and other tribes' Read the last name as Dodar.
- 316. 1 26. 'He sent .. Mırzā Kāsım Tafai to the Emperor' Recte, Taghāt, i. e maternal uncle or mother's relative (BN Tr 27 Note)
- I 323,1 19. 'Hulākū Khān, son of Changīz Khān,' Correctly, grandson
- I 237, l 11 f f. The name of Dashrath's father was not Ajīpār, but Aja or Ajapāla. 'Dera' is an error for Dirghabāhu (Vishnu Purāna. Tr Wilson III. 313-4). 'Kasila, Kailiyā, Simiyā,' should be Kaushalyā, Kaileyi and Sumitrā For 'Chatargun,' (l. 7 f f) read Shatrughna. 'Parīhār' should be Pushkara and for 'Atat' read Atithi 'Tawākas' (l. 2 f.f) is a blunder for Lava and Kusha
- 1. 338, 1. 2 'Sambūt Rājā,' must be meant for Sambrat, ie Samprati.
- I 338, 1 3 'Hanrat, also called Dakan.' Read Mahrat
- I. 338, l. 6 'Harbat' must be Haspat, r e Ashvapati Note that Gazpat and Bhūpat are said to have been his brothers.

- 338, I. 25. 'Falial, the father of the celebrated Läkha Fasläni.' Read Phula, the father of the celebrated Läkhā Phulani.
- I. 839, II. 4, 8 and 26. 'Hankur.' Read Hingora.
- 1. 339, 1. 7 f. f. 'Pāmbiya, [variant, Pāmbaniya].' Correctly, Bābīniya, i.e. Bāmanīyo, See my Note on Vol. I. 226, 1. 9 f. f.
- I. 411, Footnote 1, 1, 10. 'Ghumte,' Read Ghümli. See B.G. VIII. (Kāthi-awar), 410.
- 11. 112, 1. 9. 'Bu Nasr Muctaufi, commander of a detachment'. Correctly, Accountant, Auditor. Controller of expenditure.'
- II. 175, II. 3 and 2 f.f. For 'Sanjaris' read Sijizis, and so also at I. 176, I.4. (See J. H. 167 and 11 Note).
- II. 181, J. 2. 'The chief of Gharni, Abû 'Ali Kûbak.' Recte, Lawik.
- 11. 2M. 1. 9. 'Wasa Abhir's property worth ten lacs of Rupees.' Polete 'Rupees', 'Awfi could not have used the word.
- II. 201, 1. 16 from foot. 'The most generous king, the staff of the world and supporter of religion.' This is only a literal and uncalled-for translation of Qufford-dunya sca'd Din.
- II. 205, I. 4. 'Sibi, the historian of Kibas', Read Qabus.
- II. 212, 1.7 f. f. 'Qiw inu-l-mulk, Rühu-d-din Hamza.' Read Ruknu-d-din, (F. I.58, I.3). The mist ske is committed again at 219, I. 7 f. f.
- 227, 1, 11 f.f. For 'Bhangar', read Thunkar [Tahangarh], as at 300,
 20 of this Volume. See my Note on II, 226, 1, 24.
- 11. 303, 1. 4. Read 'Khwija Muiadu-l-Mulk Sanjari's nisha as Sijizi or Sajazi, i. c. of Sijistin (とうこ not とうこ). He is called Sistăni by Minhaj himself in the T. N., Text, 98, 1. 13.
- 324, l. 15. In A. H. 615, Jabilu-d-din king of Khwarizm fled towards Hindustin', Correctly, 618 H. as in the E. N. Text, 171, l. 11;
 T. A., 28, l. 6 f.f.; F. I. 65, l. 3 f. f.
- II. 325, l. 21. 'Kubācha's minister, 'Ainu-l-Mulk Husain Ashghari,' Read Ash'ari as in T. N. Text, 173, l. 1; E.D. I. 183 and II. 330.
- 11. 336, 1. 18. 'The other entered the gate of the Mu'izzi.' Correctly, by the Gate of the Madrasa-i-Mu'izzi, or the Mu'izzi College [which had been named after Mu'izzu-d-din Sām]. T. N. Text, 189, 1. 15.
- II. 318, last line. 'On Thursday, the 11th Zi-l K'ada 645,' Read, Thursday the 15th. Monday the 12th has been already mentioned on 1. 12.
- II. 350, l. 19. For 'Lashkar Khān,' read Kashlū Khān, as in Ţ. N. Toxt, 222, l. 2 f.f.; 268.
- 11. 351, l. 17. 'Gwālior, Chanderi, Bazawāl (१) and Mālwa'. Recte, Naraırāl, Narıcar. الحراد-تروال is a mistranscription of للحراد-تروال (Nalapura).
- III. 19, II. 4 and 9. 'Abu-l-Hasan, son of Simhur,' Recte, Simjur.
- III. 33, l. 8. 'The Rukhs of Rustam,' Correctly, Rakhsh. The Arabic and Persian form of Arachosia, the Greek name of Zābul, which was Rustam's country, is 'Rukhaj'. E.D. I. 23; II. 281.
- III. 64, l. 6. 'In.....the year 293, he [Mahmud] made war upon

- Jaipāl,' Read 393 [H.]
- III. 102, I. 8 ''Adıl Khan, Tabar Khan and others,' Read Tamar Khan, as ın E.D III 109, 114
- III 133, 1 11 'Jalalu-d-din [Khalji].... received the title of Siyasat Khan,' Properly, Shayasta Khan.
- III. 146, 1 16 'Khān Jahān, his [Jalālu-d-dīn's] eldest son was then dead 'Correctly, Khān-ī-Khānān
- III. 146, l 9 f f 'He ordered . tunnels (sābāt) to be sunk.' Sābāt are covered approaches for the conduct of sieges, constructed above ground, not underground 'tunnels'
- III 150, l 6 'Alāu-d-dīn arrived at Ghāti Lajaura.' The place intended must be Lāsūra Constable, Pl. 31 C b It is about 10 miles west of Daulatābād.
- III 168, 1 8 'In the third year of his reign'. כנ مه مال حلوس T F Text, 261, 1 9 f f Correctly, during the [first] three years of his reign.
- III 198, l. 23 'A battle was fought in Khikar,' Correctly, on the Ghaggar river
- III 244, 1 2 'He there. made [Shihāb Sultāni] governor of Bīdar and the neighbourhood, with a fief of a lac of tankas,' Read one hundred laks of tangas T F Text, 481, 1 10
- III 293, l 6. 'Sultān Firūz Shāh issued twenty-one edicts (sikka) and thirty-one instructions ('Alāmat) upon matters of royalty.' These 'Sikkas' were really the insignia reserved for the sovereign, e g Khutba, Throne, Tughra, Ghāshiya, Crown, etc. T F. (Shams), Text, 108
- III. 400, 1 4 'In . Rajab, A.H 800 (March, 1408)' Read 1398
- III 444, 1 15 For 'Azurbāijān' Arzanjān in the Z N Text, II 118, L 7
- III. 521, 1 15 'The princes, the numans, the amirs of tumans,' Read 'numan' ريان grandees
- III. 563, 1 9 'Whatever other stories and fables they [the Hindus] have, is contained in Kabits, parwānas and nāmahs,' Read Purānas
- 1V 3, 1 6 f f For 'Shalghāzis of Fārs,' read 'Salgharīs' or 'Salghuris' See Baizāwi, in E D II 254, Tārīkh-i-Guzīda, I 503, Tr II 118
- IV. 34, 1 17 'Amīr Tīmūr had attacked Talīna' Tulamba must be the place meant
- IV 38,1 12 For 'Taghi Khān Turkchi,' Read 'Taghi Khān Turkbacha' as in T M 170,1 9, B I 273=Tr I 360, E. D IV. 40, 43, 48
- IV 44, 1 18 'He [Khizr Khān] proceeded by Pānipat to Firozpur,' Correctly, Fathpur, as in the TM Text, 179, last line
- IV 62,1 22 'The Rais of Gwalior. Bhangar and Chandawar.' Read the second name as Tahangar, q v Note on II 226, 1.24.
- IV 124, l. 14 'I took my flight on the wings of travel for the city of Bijanagar' Read 'from the city of Bijanagar.' He was returning
- IV 163, l 1 '[Subuktıgin] . . . subdued Afghan and other places,' Recte, Lamghan as in 'Utbi, E D. II. 22, Reynolds' Tr. 39.

- IV. 186, l. 21. For 'Mamichilir,' read 'Manuchilir' and for 'Washmichilir,' Washmagir.
- IV. 205, Footnote 2, l. 11. For 'Abū-l-Farah Ruwaini,' read Abu-l-Faraj Rūni.
- IV. 239, Footnote 2, 1.4. For 'Kalatūr,' read Kalānaur [in Gurdāspur].
- IV. 262, Footnote 1, 13 f. f. l. For 'Sirohi,' read Sarvar [Sarjūpār, Gorakhpur] as in B.N. Tr. 521.
- IV. 262, Footnote, l. 10 f. f. 'Rājā Muttana and Rājā Rup Barīn (Narāin?).' Muttana' may be Mithila [Tirhūt]. His name was Rāmabhadra or Rūpa Nārāyan, Duff, C. I. 266, 305; B. N. Tr. 521 and lvii.
- IV. 262, Footnote 1, l. 4 f.f. For 'Rājā Gulanjari,' read. 'Rājā of Kālanjar.' He was, probably, Rudra Pratāp Bundela.
- IV. 262, Footnote 1, l. 3 f. f. For 'Rājā Sing Deo' read 'Rājā Bir Sing Deva' [of Bhaṭa]. See my Note on IV. 407, Footnote.
- IV. 262, Footnote 1, last line. 'Rājā Bikram Chand' must be Rājā Bhī-kham [Bhīshma] Chand of Almorā. Duff, C. I. 281.
- IV. 266, Footnote 1, 1.2. 'Humāyūn proceeded from Ghāzīpur to Khairā-bād.' Read Kharīd [in Balliā district]. B. N. Tr. 544.
- IV. 283, l. 12. 'A messenger from Dūdū and his son Jalāl Khān............ arrived in my camp.' Read 'her.' Dūdū was the mother of Jalāl Khān.
- IV. 294, l. 3 f. f. 'The Mir [Yaḥyā Qazvīni] died in A. H. 971.'
 The correct year was, most probably, 981. (B. Text, III. 98).
- IV. 304, l. 16. 'Humāyūn [marched] eastward against Ben and Bāyazīd,' Correctly, Biban.
- IV. 304, l. 3 f. f. 'Sher Shah dies, Rajab 1st, at Kalinjar.' Correctly, Rab'î the 1st. See E. D. IV. 409.
- IV. 396, l. 14. 'Mubārak Khān Shīrīni killed the third.' The sobriquet must be Sarbani or Sharbati.
- IV. 408, l. 20. For 'Shaikh Halil' read 'Shaikh Khalīl.'
- IV. 440, l. 23. For 'Saif Jan' read 'Saif Khan'.
- IV. 475, Footnote 1, l. 2. For 'Khān Jahān Tokhāni,' read Nohāni or Lohāni. q. v. E.D. V. 9 note.
- IV. 497, l. 8 f. f. For 'Idi Ratna,' read Raina and for 'Lali Chak,' read Kaji or Kachi Chak. (Tar. Rash. Tr. 485).
- V. 12, l. 4 f. f. For 'Garha-Kantak,' read 'Garha-Katanka.'
- V. 86, 1. 18 and 88, 1. 5 f.f. For 'Rāi Karan Sing, Rājā of Gwālior,' read Kīrat Singh. See my Note on IV. 39, 1. 4.
- V. 133, l. 8. 'On the 10th Muharram, 948 H., we mounted.' Correctly, 947 H. H. B. H. II. 187; F. I. 218, l. 4 f. f.
- V. 147, l. 5 f.f. For 'Abdu-l-M'aāli' read Abu-l-M'aāli.
- V. 173, l. 17. For '5th Sh'aban, 955 [Riḥlat],' read 25th Sha'ban 965 [Riḥlat] or 975 A. H. T. A. 283, l. 3 f. f.
- V. 189, l. 10. For 'Baban Bāyazīd' read 'Bibān and Bāyazīd,' though the conjunction is left out in the Lith. T.A. also, 194, l. 15. See E.D. IV. 347.

- V. 189, l. 20 For 'Sultan Husam Mirza Babakra' read Baigara.
- V 199, 1. 4. For 'Sam Marzā' read 'Sām Mirzā.'
- V. 203, l. 11 For 'Shaikh Julil' read 'Shaikh Khalil'
- V. 206, l. 5 f. f. 'Mırzā 'Askari then crossed the Sind and went to the town of Pātar.' Read Mırzā Hindāl, as in the T.A. Text. 203, l. 12 f. f.
- V. 230, l. 7 f.f. For 'Muhammad Käsim Khān Fauji,' read Mauji, as in A. N., I. 223, Tr 450. See also Budāuni, II 314, l. 6, Tr. 324, A. N Text, II. 59, Tr. II. 91, III 87; Tr 123
- V. 293, l. 1 Read Khwāja 'Abdu-s Samad's sobriquet as Musancicar [1e Painter] not Masūr
- V. 235, I. 10 'Sayyıd Muhammad Bıkına.' Read Pahna, ie stout, fat, corpulent, as in A N.I 223, Tr. 451
- V 237, 1, 17 For 'Nasir Khan,' read 'Nasib Khan,' as at V 243 infra
- V 255, 1 17. 'Sikandar sent his son along with Ghāzi Khān Sūr' Read 'Tanūr' [Tonwar], ود not -ود
- V. 265, Footnote 2, 1 1. 'Pisar-khwandah' is not a 'reputed son,' but an informally adopted son, a person affection itely called or addressed as Pisar or 'Farzand.'
- V 273, Footnote 3 For 'Sanjarı,' read 'Sijizi,' i c native of Sistan. See A N. Tr. II 238 and Note.
- V 283, l 10. For 'Tughbām' read Tuqbāt, as m A N II 134, Tr. 208, 372, Tr 540, Budāum, II 192, Tr. 195 and Note
- V 291, 1 1. For 'Rustam Khān' read Dastam Khān. A N II 218; Tr. 386
- V. 304, 1. 2. For 'Beg Mürm Khān,' read 'Beg Nürın Khān'. Nürīn is a short form of Nüru-d-dīn
- V 315, 1.3 'When the Imperial court arrived at Lucknow.' Read Lahor, as in the T.A 277, 1.7
- V. 315, Il. 9 and 8 ff For 'Mankarā Mirzā,' read Bāigarā.
- V. 324, l. 11 f.f For 'Udı Sıngh, Raja of Marwar,' read Mewar.
- V. 335, 1.13. For 'Mu'inu-l-hakk wau-d-din Hasan Sanjari,' read Sijizi
- V. 337, l. 16. For 'Hasan Kulı Khan,' read Husain Qulı Khan.
- V. 340, l. 5 f.f For 'Mīrath' read Merta [in Jodhpur], as in the Lith. T. A. 293, l. 4 and B. II 140, Tr 144,
- V. 342, l. 2 f.f For 'Saiyid Ahmad Bukhāri,' read Hāmid Bukhāri.
- V. 363, l. 12. For 'Mühammad Kulı Khān Tughbānı,' read 'Tuqbāt'
- V. 364, Footnote 2. For 'Rollyā,' read Rawaliya or Rāwaliya. See A.N. III. 65, 1 3, Tr. 90.
- V. 369, l. 9 f.f. For 'Wednesday, 3rd Jumāda-l-awwal, 981,' 1ead 3rd Jumādu-s-Şān, as Sunday, 16th Jumāda-l-awwal occurs on 1 13 ante
- V. 411, l. 5 f. f For 'twenty-four tankas' read 'twenty-four thousand tangas' as in the Lath. T.A. 342, l 15. See my paper on the 'Muradi Tanga' in Num. Supp. XXVIII to the J.A.S B (1917), p. 83
- V. 413, 1 4 For 'Sultan Khwaja Kalij Khan,' read 'Sultan Khwaja and Qulij Khan,' as in B II, 269, Tr. 277. See also Ain, Tr. I 354 and 423.

- V. 420, l. 14 f.f. For 'Garha' read 'Karra,' as on l. 6 f.f. of the same page. B. II. 289; Tr. 297.
- V. 427, l. 12. For 'Shāham Khān Jalesar,' read 'Shāham Khān Jalāīr.'
 A. N. III. 528; Tr. 806; B. II. 310, Tr. 320.
- V. 430, l. 6, and 431, l. 7. For 'Ishang Ākā' read Ishīk Āgā.
- V. 434, l. 6 f. f. For 'Friday, 16th Muharram 991,' read 13th Muharram. A.N. Tr. III. 633 Note; Mirāt-i-Sīkandari. 443; Tr. 319.
- V. 440, l. 4. For 'Amartali,' read Amreli. (Constable, 31 A a).
- V. 440, Il. 9 and 7 f.f. For 'Ghazīn Khān,' read Ghazni or Ghaznīn Khān.
- V. 449, l. 5 f. f. For 'river Behut (Beyah),' read 'Behut (Jhelam).' The same mistake occurs on 453, l. 12 f. f.
- V. 452, l. S. For 'Mir Kuraish', read Mir Wais.
- V. 460, l. 15. For 'Mīr Mīrzā,' read Mīr Munir, as at 467 of the same Volume; B. II. 377; Tr. 390.
- V. 468, l. 3 f. f. 'He [Husain Khān Tukriya] was nephew and son-inlaw of Imām Mahdi Kāsim Khān,' Delete Imām.
- V. 476, l. 9. For 'Pābal,' read Pāīl [in Patiālā State].
- V. 483, l. 12. For 'Death of Sultan Muzaffar Gujarati,' read Defeat.
- V. 484, 1. 20. 'Commencement of the second Karan.' Correctly, Qarn (period of thirty years).
- V. 488, 1. 21. 'These low persons used to beat their drums and claim the dignity of the dogs of the heavens.' Read residents, or dwellers, for 'dogs.' The word is Sukkān, not Sagān. See my Note on V. 358, 1. 2 f.f.
- V. 492, l. 14. 'When the enemy passed the river Karwi,' Read Godi فردى i.e. Gomti.
- V. 496, l. 4 f. f. 'Ḥusain Khān Kashmīrī.' Delete ' Kashmīrī.' It is not in the Text, II. 125 or Lowe's Tr. II. 128.
- VI. 46, last line. 'He drove Adham Khān Mutanabbi out of Ibrāhīm-pur,' Ādam Khān Batani in A.N. III. 133; Tr. III. 189.
- VI. 52, 1. 10 f. f. 'Jalal Khan Ghazni.' Ghilzai in A. N. III. 140; Tr. 198.
- VI. 98, last line. For 'Bālpūr,' read Mālpur, as in A. N. III. 773; Tr. 1155. Constable, 27 B b.
- VI. 119, l. 18. 'Abu-l-Fath and Dāmaghānī were sent.' Delete and; read was for 'were.'
- VI. 124, l. 6. For 'Maghrib Khān Dakhini,' read Muqarrab Khān as in A.N. II. 280; Tr. 415.
- VI. 124, l. 4. For 'In this same year 947 H.' read 974 H.
- VI. 141, l. 6. For 'Takhati,' read Talahti [bottom, lowest part, foot of the hill].
- VI. 156, l. 9. For 'Nar Singh Deo,' read Bir Singh Deo. The error recurs on 157, l. 8.
- VI. 156, l. 11. For 'Abu-l Khān', read Abu-l-khair Khān. (E.D. VI. 112).
- VI. 185, l. 19. 'Khurram Arslan Shah' is called Salar Shah, in the T. M.; T. A. 121, l. 4; F. I. 15, 1. l. 6 f. f.
- VI. 186, l. 8. For 'Hundreds of the nobles of Samana,' read 'Centur's

- or the Commanders of hundreds in Samana '(اميران صدة سياه), as in T M. E D. IV 21
- VI. 205, l. 4 'Dahapur' The place meant may be Dholpur (دهلبور)
- VI. 224, l. 18 'The king [Firuz Tughlaq] penetrated as far as Bundwa.' The place meant is *Pandua*, Constable, 29 C c.
- VI. 292, last line 'I questioned him, but he denied the intention' Read 'He did not deny it' (T J 25, 1 13, Tr I 54)
- VI 300, l. 7 f. f , 301, l 3 For 'Abdu-l-'Azīz,' read 'Abdu-r-Rahīm
- VI. 330, l. 19 For 'Abdu-l-Islām,' read 'Abdu-s-Salām (T J 104, l. 5, I N 64, l. 3).
- VI. 374, 1 10 For 'Rājā Sang Rām,' read 'Sangrām'
- VI. 383, l. 2 f f. 'Ashrafu-l-Mulk' should be Sharīfu-l-Mulk, as at 432, 444 of this Volume, T J 346, l 17, I N. 193, l 1 f. f.
- VI. 396, l. 10 'And then to come with Sultan Murad Bakhshi' Read Sultan Murad Bakhsh, as in the Text
- VI 401, l. 4 f. f 'On the 9th Safar, the Emperor [Jahangir] reached Lahor, Correctly, 9th Muharram. Cf E D VI 300-1, T. J. Text, 32.
- VI. 424, l. 7 'Jahju, [grandson of Shuja'at Khan]' Recte, Chhajju
- VI 440, l. 9 'Peshāwar, where all the north-eastern tribes were at that time in arms.' Read 'noith-western'
- VII 6, l 18. 'Jajhār Singh was the son of Nar Singh Deo Bundela.' He was the son of Bir Sinha Deva Bundelā
- VII 21, 1 15 'Some [of Khān Jahān Lody's] elephants were caught by Rājā Amar Singh of Bāndher' Read Bāndhū Amar Singh was the Rājā of Bāndhū or Bhata. Dowson is wrong in contending in the footnote that the place meant must be 'Bhānder N E of Jhānsi', because Kh. Kh (I p 40) calls it Bhāndūr The Bādshāhnāma (I i 349, 1 11), states that the village of Nemi was in Bāndhu and Amar Sinha was the Rājā of Bāndhū See also M U. II 134-138 He is mentioned as the Rājā of Bāndhu in the 21st year of Jahāngīr's reign by Muhammad Hādi also (T. J Text. 418, 1 4)
- VII 32.1 6 f f For '1240 H.' read 1041 H.
- VII 89, l. 10 'Aurangzeb had been ordered to overtake the royal forces at Bhimbar' Recte, Bhīra 'A S Text III 72, l 7
- VII 111, l 15 For 'Husain Sajar lake,' read Husain Sagar lake,' as on 117 of the Volume
- VII. 185, l 14 For 'Nawāb Rāi, the Prince's [Muhammad Mu'azzam's] mother,' read Nawāb Bāi
- VII 189, l. 17 'An interview took place at the Raj Sambar tank,' Correctly, Raj Samandar [Samudra] tank
- VII 213, 1 7 f. f 'Aurangzeb was born in 1028 A. H. (1619 A D), at Dhūd, 'Sic in the B I Text, but properly, 1027 A H. and Dāhod T. J 249, last line, Tr II 47, Kh Kh I 296, 1 15
- VII 263, l 18 'Kunwar Rāī Singh, son of Rājā Jai Singh,' Recte, Rām Singh See 279, 281 of this Volume

- VII. 373, l. 18. 'Haināji, the commander of Rājgarh.' Read Hāmānji.
- VII. 401, 1.12. 'Zebu-n-nissā Begam, eldest sister of 'Azam Shāh.' Recte, Zīnatu-n-nisā Begam. See M. 'Ā. in E. D. VII. 196-7 and Kh. Kh. Ibid, 363, 385. Zebu-n-nisā died in 1113 A. H. when Aurangzeb was alive. M. 'Ā. 539.
- VII. 402, l. 10. 'Samsāmu-d-daula Amīru-l-Bahādur Nusrat Jang.' Read Amīru-l-Umarā Bahādur Nusrat Jang, as in Kh. Kh. Text, II. 601, l. 3.
- VII. 428, l. 4 f. f. For 'The treasure of thirteen lacs of rupees,' read 'The treasure of thirteen *Krors*', as in Kh. Kh. Text, II. 684, l. 3.
- VII. 570, l. 4. For 'Hājū,' read Jājū.
- VII. 570, l. 3 f. f. For 'Hamla Bahadur' read [Mīr] Jumla Bahādur.
- VIII. 31, l. 9 f. f. "Abdu-llah, son of Zahīr." Read Zubeir.
- VIII. 75, 1. 12. 'The chosen of the Adored writhed in the depths of anguish.' The literal translation of the name of the man, which was 'Abdu-l-M'abūd, can only bewilder the reader.
- VIII. 106, l. 16. 'Sadar Zilla Khān Kāsur Pathān' is called 'Jumla Khān' in Sarkār, Fall of the Mughal Empire, 210 note.
- VIII. 138, l. 13 f. f. '[They] got possession of the little fort of Firūz Shāh and another called the Old fort.' The places meant are the Kotla-i-Firūz Shāh and the Purānā Qil'a. See p. 143 infra, where 'the Kotila of Firoz Shāh' is mentioned.
- VIII. 146, l. 14. 'Ahmad Sultān.....pursued them as far as Būryā and Sārangpur.' Read the second name as Sahāranpur.
- VIII. 178, l. 9. 'Account of Sankar Gangāpūr.' Properly, Sarkār Gangāpūr.
- VIII. 236, l. 14. For 'Pūranjar Khān,' read Būzanjar Khān.
- VIII. 236, l. 16. For 'Chanbanians,' read Chaubanians or Chapanians.
- VIII. 236, l. 17. For 'Sarībārans,' read Sarbadāriāns.
- VIII. 255, l. 4. For 'Rām Chatar Mān,' read Rāi Chatar Mān.
- VIII. 276, l. 20. 'Nārad Shankar Brahmin was then..............appointed governor of the fort.' Read Nārū Shankar.
- VIII. 279, 1. 13. For 'Pākpat,' read Bāgpat (or Bāghpat).
- VIII. 281, 1.3 f. f. For 'Shisha Dhar Pandit,' read Sheshādhar Pandit.
- VIII. 310, l. 20. For 'forty thousand' read 'forty lacs.' Shuj'āu-d-daula had given his bond to the Mahrāṭhās for forty lacs of Rupees.
- VIII. 336, l. 6. 'He.....resided at Malāwanūr near Lucknow.' Dr. Rieu (III. 913) reads Malānwa, "Alan (q.v. Āīn, II. Tr. 179).
- VIII. 370, l. 4. For 'Raghūji Ghoslā,' read Rāghūji Bhosla.
- VIII. 372, l. 5. 'This Revealer of Secrets [Kāshifu-l-Akhbār] was composed by 'Ināyat Husain of Mahrard.' Māraharavī in Rieu (II. 1059), i.e. of Mārahra in Etah, U.P. q.v. Constable, 27 D b.
- VIII. 400, l. 5 f. f. For 'Nārad Shankar,' read $N\bar{a}r\bar{u}$ Shankar. The variant 'Tāru' mentioned in the footnote must be also wrong.

INDEX.

PERSONS.

(The correct forms are printed in brackets.)

bhata), 232 'Abdu-r-Rashid, son of Mahmud Bahbūd (Mahādeva?), 21 not Ma'sud, 430-1 Bajāin (Panchānan), 554 'Abdus, 153 Abtigin (Aitigin), 260' Băla, Rājā of Mālwā, 173 238-9 Abul Beny (Bey?) Uzbek, 600 Abul Farah Ruwaini (Abu-l-Balharā (Vallabh-Rāya), 1, 2, 3 Balhit (Bălāditya), 22 Balidar (Balbhadra), 587 126-7 Faraj Rūni), 481 Balkā Malik's father, 215 Abu-l-Fazl's Commentary on Banārasi, Shaikh, 608 557 the Quran, 567 Abu-l-Farl's assassination, 591 Bārābhuiyās of Bengal, 575-6 Abu-l-Hasan Nakhshabi (Bakh-Barbak Khan-i-Jahan, 865 Barkamārīs (Vikramādit?), 75 shi), 618 Barkhurdar Nagshbandi, 618 Abu-l-L'ais (Abu-l-Ghais), 105 Abu Muslim Marwazi, 199 Barkis (Har Kishen), 452 'Abuya the Parsa, 160 Barmazid Gur, 457 Ahmad (Hāmid) Bukhāri, 582 Bartuh (Prithu?), 218 Ahmad Chap's sobriquet, 266 Bazābas (Viehvāsaka), 86 Ahmad Thanesari identified, 355 Basurba, 574 Ahmad Yadgar, as an Historian, Batha (Pata) Rathor, 572 484 Bauura, (Bodza, Bhoja), 25 Bawaril, (Vadhel), 661-2 419 Ahodan (Shams Khan Auhadi), Bayazid, son of 'Ata Lody (?), 355 Aibak (meaning of), 204 486 Airākuli Adīghūr (Aidakū Ui-Bāz Bahālur Qalmāq, 584, 586 556 Beny Rai (Patai Rai), 596 ghur), 349 'Aisi ('Îsa Khan of Bhati), 549 Bedar (Bairad), 665 Aj Deo (Vaj Deo?), 183 Bhatti (Latti), 686 Akūgha (Āq Būghā), 846 Bhagwant, son of Udaru, 694 'Alam Khan ('Alim Khan ?), 289 Bhairū (Bhairay ?), 97 Albari or Alpari (tribe), 214 Bhaiyā Puranmal, 460 Bhandargu Bhagu (Bhadra-Alfas (Algas), 593 'Allikat (Pati-jab?), 12 rakhū Bhikkhu), 84 Bhārā, Rāi of Kachh, 118 Bhīd, Rājā of Bhata, 471, 495 'Ali Akhti (Khatati), 640 'Ali ('Alam) Khān of Kālpi, 439 Bhīd, Rājā of Bhata, 471, 495 'Ali Hauja ('Ali of Uchcha), 361 Bhīm Deo (Bhillam Deva), 372-3 Alkūzni (tribe), 692 Bhīm Nārāyan (Prān Nārāyan), Alp Ghāzi, why so called, 866-7 653 Altamash (Iltutmish), meaning, Bhopāl, Rājā of Mahesar, 455 Biharn (Bharmal of Kachh), 621 Fath Khan Sidi of Jazīra, 656 213-4Bîm (Prem) Narayan, 633 Ambūji Pānd, 666-7 Amīr (Amin) Khān, 649 Binattigin (Alptigin?), 427 Bindraban, the Historian, 641 Amir i Dad Hasan, 183 Amīr Kāzi (Amīr Rayi), 423 Bīrāhān (Parīhārs?), 295. xvi Amīru-d-dīn (Amīnu-d-dīn), 592 Birbal (Viravara), 555 390 Andrun (Indradyumna?), 488-9 Bîr Bhan Deo (Vîra Bhanu Deva Gajpati (Gajani?), 539, 572-3 Antrat (Aniruddh) Singh, 684 III), 387 Anük (Lawik), 190 Bir Singh Deva (Bāghelā), 463 Appāji (Dāmāji) Gāikawār, 698 Arzaki (Azraki), 481 Bithal Sudeo (Vithal Shivdey), 675 Bithal (Vithal Sundar), 698 Ashara i-Mubashahara, 702 Astān (Adashţān?) Shāh, 98 Bodhagan (Boraha), 282-3, xv 'Ata Beg ('Alau-d-daula) Qaz-Brahmanpäl (Trilochanpäl), 133 vīni, 680 Budehi Bamman Dhaval (Bud-Azīz Ḥīmār (Khummār), 298 dhi Varman Dhavala?), 97 Budhkar (Madhukar), 622 Bābā Ḥasan Abdāl, 108 Bābā Jūkāyath (Babūji Kān-Būjabala (Bhujabala?), 170 604 tiya ?), 608 Buledi or Burdi (tribe), 107 Bābanīya (Bāmaniyo), 101, 324 Burabrah (Paupera, Raja of Badru-d-din Daulatshäh, 383 Jawhar near Dahanu), 383-4 Bāghara (Nāgavarman?), 24 Burhan Ughlan Jüjitar, 347-9 Bahadur Khan Rohila, 628 Chach (Jajja), 80 Bahadur Khan Lody, 628 Charkas Daftir (George the Bāhar Deo (Bāhad or Vāg-Factor?), 122

Charkas Rūmi, 551 Chaupar Mal (Suraj Mal), 613-4 Dabishlim (Durlabh Solanki ?), Dähir (Dhīra Sena), 80 Daireal (Wairieal, Bairieal), Dal Bait (Dalpat of Bikaner), Dalki wa Malki (Trilokyamalla?), 222-3 Dalpat Ujjainiya, 573 Dārābars (Dhārāvarsha), 182 Daur, Rai of (Dhar), 173.3 Dawar Malik's father, 509-10 Devaldevi's hands, were they off?, 368 Devaldevi. Was she forcibly married to Khusrav?, 368 Deva Rāya II. of Vijayanagar, Dhankal or Dhokal Singh, 683 Dharm Singh (Dharmangad?), Dhar Rāj (Hari Rāj), 128 Dharsiya (Dhar Sena), 80 Dīlā Rāni (Dāi Dilārām?), 618 Dilip (Dalpat) of Bikaner, 606 Drohar(Dhruva Sena), 80 Düngar (Dhonkal) Singh, 677 Fara (Qara) Beg, 593 Fakhrud-d-din Mubarakshah, the Historian, 203 Fardaghān (Farrukhān?), 175 Farghan (Qarghan), 304-5 Farkhi (Farrukhi), 221 Farmaliun (Gharman-Leon, i.e. Leon Grimon), 579 Fath Khān Tibati (Batani), 526 Firdaus Makāni (Bābur), 543 Firishta, as an Historian,594-5 Firuz Tughlag's age at death, Gang (Gangeya Chedi), 161 Ghairat Khān or 'Izzat Khān?, Ghāzi Khān Sūr(Tonwar),523-4 Ghaiyār (Nāyar), 695 Ghausu-s Saqalain, 481 Ghāzi Mujli (Mahli), 455 Ghāzi Khān Tatār (Tonwar). Ghiyas Raihani (Zain Khani), Gīsūdarāz, Ḥazrat, 659 Gopal Das Nakta, 591-2 Gujat (Gajpat) Khan, 623 Gürpal (Kuvarpal, Kumarpal), 174-5 Habībulla, of Herāt, 490 Haidar Malik Hūlak (Mirzā

Haidar Dughlat), 418 Hājji Habībulla, 544-5 Hamba Nürîr (Nambiyattîri), Kangā (Gangā) Khatrı, 409 Kankūmā (Gangūbā) Tāntia, Har Das (Tapar Das) 597-8 Harnand (Pradhan), 249 50 Mıran Muhanımad Shuja'a Karāk (Qazzāq) Khān, 527 Hasan Khan Tabati (Batani), 578 Kantajı Kadam Bande, 677 Mir Jumla Yar (Thr?) Khan, 683 Husain Khan Nirak (Surk), 454 Kathis, 550, 552, 558 Karam Mālū (Qarāmānlū), 572 Mir (not Amir) Masum Bhak Hasan Makon (Makhan), 489 Karan Rai (Kırat Rii), 182 Hasan Sabbah, 237-8 Mırzā Kasan (error), 525 Hasnak Mish katı (Mi kailı), 988 Kesar (Kirat) Singh, 653 Mig'ar bin Muhalhil, 712 Hawalı (Jiwi, Jūi) Uzbek, 510 Khān i Khānān Yūsuf Khail, Mubarah (Mirah) Razvi, 527 Hıraj (Harı Raj), 180 Mudabbir (Muzaffar) Khan, 640 Hisamu d din, brother or cou-Khengar, Rājā of Kachh, 553 Muhammad Hadı, 681 sın of Khusrav Khan, 286 7 Khankhār (Khongār, the Rājā Muhammad Halim (Muqim) Hisamu d din Ulbak (Ughlabak), Khūnza, Bibi, 424 of Karnal or Girnar), 302 8 Khudayar Khan Lattı, 695-6 Muhammad Khan Bihbudi Hushang, Amir, identified, 383 Hiraman Baksariya, 672 (Bıhsūdı) 547 Khusrav blinded, 603, 623 4 Muhammad Quli Tughbani, Hurra-i Khutalı, 168 Khusrav's murder, proof of, Husain Khan (Fulriya), 518 Muhammai Shah Safavi, 681 Husain Quli Khan, 518, 521 Khusrav Khan Charkas, 114 Ilyas Afghan identified, 955 Muhammad Sālıh Kambū, 626, Khwājagān Khwāja, 521 Imadu d-din Shaikh, 882 Khwaja Mansūr executed, 548 9 Muhazzab, Khwaja, 219 Muhammal Sālih Khūshnavīs, Imāmu I mulk (Intizāmu I Khwandamir, the grandson of Mulla Fazin (Qazin), 467 Iobal Mudbir, why so called, 248 Koka Pradhan, 249 50 Kılmāk (Qalmāq), 584, 586 fradat Khan as Historian, 678 Mulla Muhammad Mazhib Ismat Khan ('Azmat Khan),640 Jagat Sinha, Rājā of Mau, 625 Kuraishi (Waisi), Khwāja, 602 (Muhazzab), 442 Kulchand (Kokalla Ohedi II), Mulla Muhammad Lahori Jahan (Ohupan) Malik Agha, Mumtazu l Mulk (Mubarizu l Jāhir Deo Ajāri, 224 5 Kurs and Pūris, AX XXI Jai Mal, son of Rupsi (?), 574 Mulk) Sarbuland Khan, 701 Jai Mai, son or Kupsi (7), 574

Jakir Zand (Chaghar Rind), 559

Laudhan (Bandhan), 471 2

Today (arrow for Laur) 141 Lakhzīr (Lakhdhīr) 119 Mūna (Mota) Rājā, 574 Lal kana Dandanayaka, 419 Mundihs, 656 Jājū or Jajjū (Ohhajju), 395-6, Mür Khan (Muwarrıkhan, 18 Historians), 380, 896 Mūsa Zakmāl (Ragmāl), 848 Jakar Beg (Chaghar Beg), 431 Lody (error for Lawr), 141 Lona (Lumbha) Kathi, 552 Jalal Khan, Salyıd Hüri or Muzaffar Khan Turbati 584 5 Sadhauri ?, 571 Lon Karan (Lunkaran), 548 Jalālu d din Dīvāni (Dawwāni), Mahārta (Bhārat ?) Cherūh, 454 Muyyad Beg, 453 Nagoji Mane, 662 Nahar (error for Bahar) Deo, Jarjir (Gurji or Karkhi ?), 481 Jarjir (Gurji or Karkhi?), 431
Jaswantrāo Bewār (Pawār), 698
Malikzāda Harbūi (Harivi), 398
Māl Gozāin, 573
Mal Gozāin, 573
Nar Sinch /Bir Sinch Toinar of Nahamrūi or Nuhmardi (Tribe) Januan (Chandian), 650 Nakbia (Nakpai, a Mongol), 388 Jhila (Jhabila), 585 Jibawin (Sambadova ?), 99 Jihtar (Jaitra Sinha?), 181 Jiwan, Malik (Jiand), 650 Nar Singh (Bir Singh Tounar of Mallu Khan (Mallahan, boat Juga (Bachgoti), 470 Gwalior), 894, 398 Jugal Kishwar (Kishore), 699 Nar Singh (Bir Singh) Bundela, Manar Barmul (Mara Varman Juli or Chull, Shaikh, 514 or Māra Perumal), 245 Nar Singh Doo (Bir Singh Deo Kabakan Najda (Gangeya Man Deo (Nanya Deva), 299 Mānik Rāi (Matak Rāi?) 685 Nar Sing Makhwar (Kumar), 610 Kabir (Kālı) Bhadra, 97 Manjhur (Manjhu) Shaikh, 198 Kablalas (Kavikalasa), 655 Nasıb Shah (of Bengal), 451 Mankburni, meaning of, 240 1 Nasiru d din Qubacha, suicide Mankūta, 222 Kaberi (tribe), 107 Manua Shaikh (Munawwar), 859 Kaid (Kedar) Rai, 594 Naukar Khan, an error, 860 1 Mānūs (Bābūs) Beg, 512 Kaira (Qāim) Khan, 694 Nauruz Kargan (Gurgan, son-Mard Azmāi Shāh (Shāh Madad Kalsa (Kākutstha ?), 93 in law ?), 300 Kajar Shāh (Gujar Sāh), 998 4 Nayak (Nanak ?) Hindi, 244, Kiv Marani (Satarani), 552 Marud i Sad i Silman, 479 Kajwi (Gujar) Khatri, 409 Nazr Bahadur Kheshgi, 686 Nı'amat Khān Hājı, 646 Kalyan Rai Baqqal, 543 Mātāmādharı Ballah (Māmā Kalnish (Kailash ?), 955 Nimeh pezir (Nambiyattiri), 422 and Hari Ballal), 699 Kamālu i din Gurg, 251 Kamālu i din (Main), 859-60 Nohin (Naughan) Gohel, 554 M'asum 1 'Ası, 5167, 549 Nur Beg (Naurang) Khān, 581 Mihlak (Melag, Melal or Molal) Nur Jahan's birth, 618 9 Deo, Raja of Malwa, 249 50 Nür Turk, 219 Milak Doo (Melag Dava), 216 Pādshāh Khānzāda Khān (?), 665 Pandya Guru (error), 872 l'anhun (Bhanu, e Sun ?), 130

Pāp Rāi (Pāprā), 668 Param Deo (Viram Deva Chau- Sadr Zilla (Jumla) Khan, 713 han of Sambhar), 286-7 Partab Bac (Patar Tabar), 574 Patr Das (Tipar Das), 545-6 Pāyanda Muhammad Khān, 551 Saifu-l-Mulūk and Badī'u-l-Pilūji Mahrātta (Pilāji Gāikawād), 677 Piran Waisiya, 651 Pisar-i-Thanosari, 299 Püranmal Pürabiya, 460 Qabul Toraband, Malik, 317 Qādir Shāh of Kālpi, 400 Qāīdi, (Fāndi or Pāndya), 21 Qarmali (Farmuli), 450-1 Qarmatian, 141, 219 Qatlu Kirāni (Lohāni), 576 Qāzi-'āli, (Qāṣi 'Ali), 459 Qiwāmu-d-dīn-i-Ilāqa, 262 Qudsiya Begam, 619 Qurbat Hasan Kangu, 326-7 Qutb Khan Banet (Naib?), 457 Qutbu-d-din, Saiyid, 221 Rājā Bahādur (Raṣā Bahādur), 640 Rām (Dharma) Chand, Rājā of Nagarkot, 515 Rājā Rām Ḥusain (Jīban), 690 Rājā Rāi (Rudar) of Kamāūu, 606 Ramai (Bhārmai or Nirmai?), 85 Sassi (Shashin, i. e. Hare or Rāmchand, Rājā of Panna (Bhata), 478 Rāmchandar, Rājā of Bittiah (Bhata), 555 Rāmeswar (Rām Sāb) Gwāliyari, 543 Rānā Kīkā, 542 Randhol (Randhaval), 289 Rāni of Mutfili (Motupally), 253 Rasadu-d-daula (Raushanu-ddaula), 682 Ratan, Malik, 101 Rashīd (?) Sultān Mirzā, 587 Rāyst, 553 Rukn Janda (Junaidi ?), 391 Rusāl (Rāi Zābul ?), 175-6 Rustam Rão, 659 Rustam Dil Khan, 667 Rustam Khān Rūmi, 529-30 Sabhāk Prakās (Subhāgya Prakāsb), 637 Sabli, (Chakki?), son of Shāhi, 145 S'ad-i-Salman, 163

Sadar, error for Haidar, 593 Safar (Shukrā[chārya?]), 75 Sahasi (Sinha Sena?) 80 S'aīd Khān Chaghtāi, 592 Jamāl, legend of, 115 Saifu-l-Mulk, uncle of Tarsun Muhammad Khan, 110-1 Saiyid bin (?) Majzūb, 491 Sakanas (Sangāniān), 661-2 Sāmā (Sābāji), 697 Sāmāji (Shambhāji), 628 Samar (Tamar), 261 Sām Sultān (Ḥusām Khān) Gujarāti, 593 Sanā'ī, correct lagab of, 432 Sandal Āgā, why so called, 692 Suratmish (Siyurghātmish), Sangi Bamkhal (Singgé Namgyal), 635-6 Sangrām, Rājā of Gorakhpur (Kharakpur), 540, 573 Sankh Deo (Singhan Deva), 372 Takhta-Begi, 570 Santāji Ghorpade's death, 662 Särang Gakkhar (Malik), 509 Sarman Deori (Sartan Deoda), 549-50 Sarvādharan, error for Bīr wa Uddharan, 394-5 Sarwar (Sumer) Räi, 392, 393 Moon), 130 Sāyat (Sāhib?), 553 Saz Khan Baligh (Saru Khan Uzbek), 637 Shakurkani (Shaturgani), 221 Shāh-i-Lundan (Lawandan), 522 Udaru (Udaram), 634 Shabsawar (Shahnawaz) Khan, 608 Shamsu-l-Kāh (Kufāt), 237 Shaikhzāda-i-Jām identified, 378 Shamsher (Sumer) Singh, 699 Shamsu-d-dīn Dabū (Dabīr), 366 'Umar Khān Sarvāni, Kalkapūr Shavkrāji Malhār, 672 Sharaf Kai (Qaini), 278 Shayasta Khan, story of, 640 Sherafghān (Sherafgan) Khān, Sher Khān, son of 'Adli (?), 521 Yamkhīru-l-mulk (Mujīru-l-Shīr Abrū Chashm (error), 306 Siharas (Shri Harsha?), 60 Sihtā (Satareāl) Jām, 118 Sikandar Maī (or Mu'īn), 600 Sikandar bin Manjhu, 623 Sikandar Sur's father, 489 Silāij (Shilāditya), 80

Sinānu-d-din Habsh (Chanesar), 214.5 Sīr (Sumer) Rāi, 396, 397 Sisākar (Shikshākar or Yashaskara?), 90 Soli (Lüli), 171 Stibbett, Giles, Colonel, patron of Ghulam Basit, 695 Subakh (Sunj) Tamur, 349 Sübhan Deo Räni (Shobhan Devi), 83 Subhān Rai (Sujān Rai), 680 Sufaid (S'aid) Badakhshi, 547 Süfi Wali Kadāmü (Rümlü or Shāmlū?), 511 Sulaimān Bādshāh (Pāshā), 704 Sumragān, Sumrā tribe, 303-4 404.5Tadar Jaipāl (Trilochanpāl),245 Tāhir bin Rust (Zainab?), 426 Tāi Balwi (Tābūi), 248 Takri (Tagarrub) Khan, 693 Tannu, Nannu, Natthu, original name of Muzaffar III, 550 Tānseni (Tāusani), 544 Tārāji Bhāo, why so called, 696 Tardika (Tardi Yakka), 441 Tarmashrīn's invasion, 362 Tarwāri (Travādi), 551 Tihāru (Thāru), 207 Tilak, bin Jaisen (Jahlan), 163 Tuztigin (Pürtigin), 429 Ubaid, not 'Ubaid-i-Zākāni, 291 Uchaina (Ujjainiya) Rājā, 694 'Uduaighan ('Uduaigan) Khan, 654 Ugar Sen Kachhwāha (Khīchi), 472Ujjainiya Rājās of Bhojpur, 603 (Gazbur), 445 Wanku (Venkoji Nimbalkar), Warash (Wirmish or Durmesh) Khan, 123, xii mulk), 257 Yūsuf-i-Sarūb (Swarūp or Sarwar), 407 Zasi (Narsi), 170 Žībak (Kaibak) Tarkhār, 125 Zinbanda (Zain Rinda), 200

INDEX.

INDEX.
Addiana 11 to
Adia or Aros os Alor 690
Adrehtan (Adh.) Atroli, 400 Rather
Adashtān (Adhishthāna), 55 Afghanpur, 272 Agrowah, 202 Ator, 686 Atroli, 406 Autoli, 406 Autoli, 406 Autoli, 406 Autoli, 406 Autoli, 406 Autoli, 406 Bālbak or Balbun (hūyal ?), 68 Aurangābād (near Stāll 2) Awair keri
Agrowah, 202 Awair karet (noar Smill of Ban (- (Malpur) 536
All antighar (III.
Ahrūni (Ahirwan), 858 Ahūnat (Ahirwan), 858 Alsi (not a place 1988)
Alsi (not a place), 683
Albarpur, 629 Babal (Daharrauri, 202 3 Bengan (Pandua) 512
Althor (Agham) of Binger (Flor) con
Akhār (Aghām), 91 Akroda (Agrowa), 807 Alagh Khāni (Ulugh), 807 Alagh Khāni (Ulugh), 807 Alagh Khāni (Ulugh), 807 Alagh Khāni (Ulugh), 807
Akroda (Agrowa), 554 Bach (Panj) Pahāri, 695 Alagh Khāni (Ulugh Khāni), 314 Badarpur Sorāi, 698 Alang, 627, 692 Ali Mohar, 692 Badarpur Sorāi, 698 Badlinor (Bodnos), 501 Bangash i Pālā (Kurran), 637 Bangāv an (Bāngār), 207 Bangash i Pāla (Kohāt), 637 Bangāv an (Bāngār), 210
Alamut, 200 Alang, 627, 632 Ali Mohan, 694 Badhnor (Bednor), 694 Bangai an (Bangai), 697 Bangai an (Bangai), 697 Bangai an (Bangai), 697 Bangai an (Bangai), 697 Bangai (Pogu), 697
(A) = 440, 504
Alipūtra, 127 Ali Rājpur, 524 Alika Palka, 684 Aloda (Alūwa), 600 Aloda (Alūwa), 600 Aloda (Alūwa), 600 Bāgar, 180 Bāgar, 180 Bāgar, 180 Bāgar, 180 Bāgar, 180 Bāgar, 180 (Durg), (Panhāā) 664 Bāghi i Ilayāthal
Alor (Aluva), 600 Bigh i Harati
Alola (Aluwa), 600 Amartalı (Amrelı), 711 Ambi i İlayütbaklısh, 685 Bāgh 1-Jūd, 229 Bāgh 1-Jūd, 229 Bagh 1-Jūn (Bāgh 1-Jūl), 185 Banpur (Banpur), 118 Banpur (Banpur), 118
American (Ambres), 711 Baghpat use (Bugh i Jul) 100 Bannu (Bampur) 238
Book - Cadiforn Book - Cadiforn 2 - Taylor Book - 198
Apply (Anhilvad) 90 Bagina (Pachia ?) 90 Barada (Pachia
Andarat Bath (Day), 18 14 Roll Harry 1007 204 104 (Roman 1) 186 7
Andardin (not a plant)
Andardūn (not a place), 488 9 Andardābah (Andrāna), 486 Andol (Erandol), 686 Andol (Erandol), 686 Andol (Erandol), 686 Bahādurpur (near Banāras), 647 Bahādurpur (near Burhānpur), Bardār (Hard vār ?), 226 Bāhalmır (Badmer), 128 Bahar (Nahr or th), 128 Bahar (Nahr or th), 128
Andkhod (Andrāna), 486 Andkhod (Andkhūi), 686 Andol (Erandol), 628 An Makinda (Hanamkonda), 286 Andwar (Indūr in Alandol), 286 Annawar (Indūr in Alandol), 255 Bakar (Badmer), 128 Bahar (Nahr or the Indus), 71 Bahakila (Begon 518) Barhad, 686
Andol (Erandol), 626 An Makinda (Hanamkonda), 256 Anjandudh (Anjandarra, Ajantā Bahlūn, 615 Anjarāi (Indīrā), 658 Bahar (Nahr or the Indus), 71 Bahkūla (Begowāl?), 445 Barhānpur (Barhān), 294 Bārkar (Romān), 294 Bārkhān), 107 Barhan, 185 Barhan, 165 Barhan, 165 Barhanpur (Bhuranpur), 441
Grandull (Anna Alwar), 405 Dania Wal (Di Wal ?), 445 Barba, 300
Anjandudh (Anjandarra, Ajantā Bahlawāl (Bhilmāl or Nahr Anjarāi (Indirāi), 688 Bahrah (1902)
Appen Bar, 694 Barot (Planta War), 857 Barot (Planta War)
Bahii (7) Bahii (7) - Bahii (7
Apsur, Asūr (Barcelor?), 48 Arat irat (Argha tirtha) 45 Arat (Argha tirtha) 45 Arat irat (Argha tirtha) 45 Arat irat (Argha tirtha) 45 Arat irat (Argha tirtha) 45 Bailamān (Bhilamān) 450 Barsan (Swarkā), 57 Barsana, 702 Bartol (Rataul), 273 4 Bailamān (Bhilamān) 450 Barsan (Warkā), 57 Barsana, 702 Bartol (Markal), 273 4 Bartiji (Wardas 2), 409
Aral, 494 Arak tirat (Argha tirtha), 48 Arat'hūr (Abūhar ?), 52 Arikanpa (Arwal), 470 Baila (In Kashmir), 857 8 Bailamān (Bhilamāl), 77 8 Bairam Kala (Bhilamāl), 77 8 Barwāla (Mardhā ?), 254 Barwāla (near_Jiod), 290
Artia (Arwal) 470 /, 52 Bajhora (Tol.) Biramgale) can Barwa (near dind)
Arıkanna (Arkāt ?), 244 Arman (Burma), 58 Arımın (Burma), 58 Bajlana (Bachlana), 402 Bajlana (Pachlana), 402 Bajlana (Pachlana), 402 Bajlana (Barnan), 572 Bajlana (Barnan), 572 Basanlot, 211 Basanlot, 211
Barring (Full Bota), 88 Barring (Full Inrot) 102 December 211 Barring (Full Inrot) 550
Asadpur, 700 Bakar (Versillar), 15 Bakar (Versillar)
Assir (Abuhan) 00 Bakialan (Buston) 182 Basiah (Pasina), 809
480 to
Table (Agh) To Co. Bake Ful (Viene 5 Table 1097
Askalanda (2) 1496 Balal on Unao) 400 Belal Bain) 408
Bhague, 600 Bhague, 681
Balārām (Bilrām), 895 Balāwarda (Ballāvar, Bisohl), r. Bhallar (Kalhar 2), 699 Bhalkar (Kalhar 2), 699
Balāwarda (Ballāyar, Bisohli), 51 Bhakkar (In Miānwall), 682
Balārām (Bilrām), 805 Bhakhrı (Huleri?), 682 Balāwarda (Ballāvar, Bisohli), 51 Bhakra (Bakrāla), 689 Bhakra (Bakrāla), 602
- VI 002

Bhandarkāl (Bhadrakāli), 275 Bhander, 633 Bhandner (Pundir?), 462 Bhangar (Tahangarh), 181 Bhāti (in Bengal), 575 Bhāti, near Aror, 51 Bhātia (Bhera), 138-9 Bhatnur, (Banur?), 445-6 Bhimnagar, origin of name, 142 Chun (Chola), 46 Bhojpur (in Farrukhābād), 259 Chūn (Jūn in Sindh), 689 Bhojpur (in Shāhābād), 603 Bhonsla, village, 651 Bhowal, 588 Bhūkānū (Bhūingāon), 405 Bhūliyās (Būliyāsa), 556 Bhushangarh, 664 Bhut (Bettiah?), 48 Bibipur, 695 Bidr (Bidri). 650 Bidrur (Belur), 415 Bijānagar (Bairāgarh), 254 Bijlana (Pachlana), 402 Bijnor (or Pinjor?), 226 Bilūchpur, p. xxiii Bindrawach (?), 689 Bīrāhān (Babrahān), 54 Bīrampuri (Brahmapuri), 663 Birgaon (Pedgaon), 659, 663 Birnagar (Vadnagar), 677 Biswar, (Ellichpur ?), 50 Bittiah (Bhata), 555 Biturāshit (Petora), 42 Bitura (Batoro?), 126 Bituri (Tripuri, Tevar), 48 Biyalas (Walistan), 34 Bizapur (Vaijapur), 628 Brahmanabad, 76-7 Brahmashīl, 45 Budfattan (Badagere?), 70 Budha or Budhiya, 33 Buhi (Boh or Bopur), 404 Bulandrai (Malandarai), 578.9 Bulbad (Walwalaj), 189-190 Būrag (Pūrik), 686 Būrāna (Būriya?), 487 Būrgānw (Borgāon), 589 Burhānābād, 492 Būria or Būrya, 690 Būsra (Bhūrāgadh), 633 Chāchandi (Chichandi), 684 Chāchkān, 126 Chākna (Chākan), 652 Chamargonda (Shrigonda), 633 Champā (Bhāgalpur), 47 Chamyāri, 516 Chānak (Achānock), 703 Chand (Chenwal, Chaul), 703 Chāndi (Chandīpur), 383 Chandpur (in Bijnor), 697 Chandrud (Chinab), 39.40 Chanduka (Chandkoh), 112 Chanir (Chanesar?), 94 Chāniūt, 435 Chārīkār, 116 Chatawar (Jatuar?), 497 Chaubāla (Murādābād), 560 Chaundh (Chainpur), 447 Chhaparghatta, 515

Chhatramau (Chhibramau), 514 Druta (Darunta), 41 Chhatur (Chatar Bazar), 107 Chihal-zīna (near Qandahār), 637 Chitapur (Chunar?), 649 Chitar (Chhapar?), 438 Chochra (Chinsura), 703 Chonsu (Chatsu), 481 Choupart (Supā), 651 Chupa ghat (?), 501 Dabar Pass, 480 Dādar (in Baluchistān), 650 Dagdār (Dakhdār), 518-9 Dahand (Dhand, Lake, Pool), 394 Dahanda (river), 397 Dahatrath (near Jind), 314 Dahmiri (Dhaner, Nurpur), 480 Dahnaj (Rander), 14, 77-8 Dahra Garden, 607 Dahūk (Dashtak), 36 Dāīr (Dābar), 537-8 Dakdaki (Dugdugi), xix Damāl (Dahmāl, Dahmīri), 480 Firanj (Qiranj, Kalinga), 7 Dāl (Rārh), 212 Damdama (in Allahābād), 618 Damrila (Darbela?), 304 Damūda (Dāmoh), 587 Dandanagan (near Panjdeh), 194 Galna, 632 Dangali, (near Rawalpindi) 403 Dar, Dawar, Dur (Dravira), 46 Darahlär (Lär Valley), 601 Dara-karib (Jalugar), 106 Darak Yamuna (Yakmina), 65 Darbela, 112 Dardur (Mussendom), 61 Darība Bāzār (in Dehli), 687-8 Daryābād, 470 Daryāpur, 479 Dawaru-l-Marsad, 54-5 Dehra (Dera Bugti), 107 Delly, Mount, 69 Deokot (Devikot), 209 Deoli (in Etāwa), 230 Depur (Udayanapur), 195 De valgāon Rājā, 627 Dewati-Mājāri (Mācheri), 569 Dhal (Dahala or Chedi), 48 Dhamāi (Dihbāi), 269 Dhamtaur, 556 Dhandhera (Dhundar?), 482 Dhangan (Dihmīri?), 480 Dhanjur (Rander), 51 Dharab (Dhodap), 633 Dhārāsiyūn (Dharaseo), 633 Dharmat (near Ujjain), 648 Dihāyāt, 84 Dihbāri (Dhābādi), 581 Dihdawal (Dhudial), 404 Dinarkotsh (Dhingret), 165 Dinkot (Dhangot), 165 Dinur (Udayanapur), 195 Disāwa (Desūya), 516 Diwarawal (Derawal), 509 Dorāba, 666 Doura (Dannrua), 450, xix

Dublāhan (Dobaldhan), 333 Dudhi (Dudhāi), 49 Dūkam (Dogāon), 47 Dukampur (Vikrampur?), 47 Dushāb (Uchcha?), 26-8 Eden (Aden), 301 Ellorā Cares, 21, 644 Fahraj (Pahra in Kerman), 63 Faj Hanisār (Khaesār), 199 Fāmhal (Anhilwād), 38 Fandarina (Pandarani), 66, 70 Fardapur, 657 Farghan (error for Amir Qarghan), 304 Farīdābād, 693 Farīdpur, 700 Fathabād (in Bengal), 574 Fath-Bagh, 114 Fath Khan (Fath Bagh), 114 Fathpur (near Multan), 399 Fathpur Haswa, 521 Fathpur Sahina (Bihiya), 540 Firābuz (Panjgūr), 63 Firozābād (Chandwar), 281, 685 Daliya (Dubwali Nyewāl?), 290 Firozābād Harnīkhera, 352-53 Firuzpur-Jharka, 475, 487 Cadarāra Ghāt, 202 Gagri (Kakar ?), 112 Gambaz (Gambat), 111 Ganaur, 486 Gangā Sāgar (Sāgar Island), 47 Gangdaspur (or Daspur ?), 539 Gāoghāt, 679 Garaunda (Gharaunda), 486 Gardez, 168 Garha (Khurda), 620 Garha Katanka, 526, 571 Garh-patti (Garh Bithli), 693 Gāti (Koil?), 52 Ghāna (in the Sudān), 67 Ghanur (Ganaur), 260 Gharjistan, 424 Charkol (Khargon), 588 Ghāt-i-Chāndā, 617 Ghaus-Kada (Ghaus gadh), 696 Ghaziu-d-din Nagar, 692 Ghaztik (Ghazniyak), 347 Ghiyaşpur, 269 Gholghat (Golgot), 702.3 Ghori, 636 Ghūrgānw (Khargon), 256 Ghūzak or Ghūrak, 41 Girjhāk,459-60 Goda (Goa, not Goga), 606 Godh (Gehad), 685 Golitālāb (Gopītālāb), 533 Gogunda, 542 Gondhāna (Kondana), 634 Gorakpur (Kharakper), 523 Gorindwāl, 600 Gudrang (Guzar i-Nazza i-1.6 Gulka (Galcala), 600 Gulshanākās (Nasīkās Gurgān (Hyrasis) Gürgany (Scarette, ett

Gwālior (Gāwilgarh?), 590 Gwāliyar (Goler), 891, 476 Hādāla, near Dhandūka, 552 Jalkanā (Ohilkia), 694 Hadbārı (Hatbārı), 92 Jālna, 582 Hatdapura (not a place name), Jalugar, 106 Kāmun (Kāmān Pahāri), 702 Jalwalı (?), 94 Hāfizābād (m Gujranwāla), 601 Kandābil (Gandāva), 84 Jambo (Yanb'ū), 412 Haibatpur (Patti), 501 Kandahar (Gandhara), 70 Jamu (Mau or Mahoba?), 282 Haibatpur (Siddhpur?), 584 Kandahār (Gandhār, near Janawal (Chunwal), 67 <u>Н</u>ајо, 685 Jāngaz-hatı, 622 Hajnir (Janer ?), 52 8 Hāla-landi (Old Hālā), 126 Kandahat (Khambait?), 1878 Janid (Jind), 314 Kandarīna (Pandarāni), 66, 70 Jankan (Jangan), 61 Haldı (in Ballıa), 448, XIX Kandārīa (Fandarāina), 708 Jannatābād, 508 Haldi Ghat (ın Udayapur), 542 Kandı, 159 60 Jāran Manjhūr (Machhiwāra?), Kandur (Kannanur 7), 255-6 Halin (Hindan ?), 360 Hamirpur (Haripur), 558 Kanjna Manjna (Kanchan Man Jārtolı (Jarolı) 406 Hanāwal (Chunwal), 67 Jās₁ (Hānsi), 243 Hans Mahal, 586 Kantal (Kantit), 548 Jasruna (Jasrota), 587 Hanur (Honawar), 422 Kant barahı (Kanth kot), 302 Jausa (Jhūs1), 548 Hāpūr (Bahāpūr), 865 Kant Gola, 451 2 Jāwian (Chāndiān), 650 Harmakut (Haramukh), 85 Kanthur (Kithor ?), 389 Jewar, 365-6 Harbi-Khir (Harnikhera), 886 Kāntı (Katı in Haidarābād), 634 Jhajūsa (Vavania), 554 Haris, 634 Kānwari (Genori?), 259 Jhalawar (Halar), 552 Haroli (Jaroli), 406 Kapūr Talāo, 545 Harur (Hindur or Haripur?),487 Jhanud, 610 Kanulapur (Kamalapur?), 489 Jharkhand, 458 Hartāla (near Edlābad), 675 Kanw wahan, 437 Jhar or Jahra (Tijāra?), 405 Hasht-bihisht Garden, 440 Kanwarigarh, 658 Jhaunes (Jhues), 617 Hatanpur (Hastinapur), 979-4
Hat Kant (Athgath), 489 Karā (Farrab), 128 Jhūni (Chuniān), 674-5 Karagar Pass, 555 Jidia (Chandi [pur]?), 888 Karajal (Kurmachal, mountains Hatya, 602 Jirbattan (Kananore), 66 70 Hawariun (Honawar), 422 of Kumaun), 294 5, 382-8 Jitasaran (Jitaran), 569 Hazāra 1 Fārigh (Qārlugh), 612 Jūbāla (Chaupla), 081 Karaza (Karehra), 698 Jitgarh (Jaitpur), 684 Hijli or Hijili, 681 Hindal (Hodal), 599 Karcha barh (Karcha, Kertze), Hindbari or Hatbari, 92 Kardan (Quzdar ?), 80-1 Judhan (Jalodhan), 684 Hındwarı (Mandawar), 898 Karez (near Herat), 609 Jūiza (Khūwiza), 682 Husainpur, XXIII Karı (Gedi in Kachh), 554 $J\bar{u}_n$, 114 Hodhna (Budhāna?), 482 Karı (Kadı near Patan), 650 Jund (Chawand), 684 Ibn Kāwān, 15 Karjāt (Qurīāt), 412 Karji Ghāt, 569 Jurz (Gurjara), 5 Idalābād (Edlābād), 657 Ikdāla (Ekdalla), 811 2 Jūtāna (Jhotāna), 551 Karkālū (Ghargāon), 640 Karoda (Agrowa) 807-8 Kach Nakti (Kachh Nagan), 128 Imānābād (Eminābād), 690 Indar-dar-bandi (Antarvedi), 161 Kahālgānw (Colgong), 471 Kachehi Sarai, 698 4 Karoha (Goa or Gheria), 58 Kachwara (Khichiwara), 468 Karra (Kharār in Ambāja ?),490 Kahamrud (Kahmard), 502 Irijpur (Irach, Erich), 252 8 Kurra (Kadı Patan), 801 Iriyab (in Kurram), 349 Karra (Kutra Miranpur), 700 Kartal (Kutarmal ?), 558 Kahāwan (Khatāu), 664 Islāmpūri (Brahmapuri), 668 Kahlūr, 437 Istiya (in Kurram?), 201 Karur, Kahror, 82 Kahura Kanil (Khor Kampila), Karwa (Kora Jahanabad), 45 Itimadpur, 685 Jatal (Jibal, Mountains in Karwi (Godi, Gomti), 492 Kāin (Qāin), 278 Kāshbīn (Kāmatā), 6 Kaitali Shahr (Kotli), 477 Jabbāl (Jibāl or Irāq 1 'Ajam), Kāsıpur, 688 haithar (Kather), 226 Jabhan (Chibhan Bhimbar), 358 Kalabagh (in biaiwa), 592
Jagdara (Chaldara), 578
Jagna (Chaldara), 578
Kalarjai (Kulachala ?), 58, 413
Kalatur (Kalanaur), 709
Kalna (Gālna), 582 Kasmandı, 238 Kasmur (Kashmor), 107 Kasrān (Quedār), 63 Kasr-i Kajūrān (Kajūri Kach?), Jahan (Chibhan, Bhimbar), 601 Kālna (Gālna), 582 Jahra (Tijīra ?), 405 Kasrkand, 82 Jaipal (Chabhal), 601 Kassa, (Khasa, Kashmir ?), 98 Jahanabad (ın Huglı), 579 Katah (Katha), 355 Kalıyada, 617 Jahns or Chhans (Chunsan), 560 Katala (City of Deogir), 880-1 Jāl (not a Place-name), vvn Jalālākād (m Muzassaragar), Kalrı, 62 Kataljahr (Kheljhar), 694 Kalwan (Kolwah), 86 Kalwar (Jalor) 502 Kataria (in Vagad, Kachh), 554 Katehr (Rohilkhand), 259 Kāmīn (Kāmatā), 6 Jalili (near Etima?), 230 Katiāna (Kutiāna), 130 kaman Pahārı, 685 Jalesar (Chhalesar), 441 hator, 348 Jalcear (Jalcahwar), 546 Jalia, (Chalia), 703-4 Kambala (kamplı) 296 Katrāpur (Katrābo), 576 Kambalı (Khairlot), 33 Katif (near Bahrein), 58 Kampat (kantit), 548 Kampil 259, 401 Kaugha (Gugu in the Sudan), 67 Kautpur (Kantitpur 1), 866 kāmuhul (Anbilwād), 38 Kawachir (Korman), 284 Kayat (Kant-Gola?), 451 2 Kayula (Kot Qubula), 461

Khabirun (Kapadvanj), 67 Kenn (Kish), 15 Konāwar (Gunāchur), 519 Khabis, 177 Koriyāganj, 700 Khairābād (near Multān), 408 Kormāi, 685 Khairābād (in Oude), 560 Kotara (Kotra), 123 Khajwāra (Khichiwāra), 472, Kot-pakali (Kot-putli), 573 Kuch Hajo, 635 Khalilpur, 637 Kudra (Godhra), 665 Khālis Kotali, 852, 859 Kūkā (Gargā) mountains, 357 Kham (Kambam Valley?), 257 Kulam (Quilon), 72 Khandhar (Khandwa ?), 253-4 Kulpāk, near Bhongīr, 668 Khārak, 14 Kumār (Khmer), 8-9, 18, 23 Kharakpur, 540 Kharid, in Ballia, 526, xix Kumba, 84 Kumbh, 88 Kharol (Gehrol), 399 Kumber (Kumbher), 702 Kharosa (Khorasa), 312 Kunak (Kongu), 46-7 Khātākheri, 632 Kunar (Valley), 234 Khatibpur (Khutpur), 408 Kunarpal (Gurapalli?), 255 Khatlan (Kolab), 162 Kundaki (Khandwa ?), 50 Khawak Pars, 947 Kundali (Kandhla?), 392 Khawarnag (near Najaf), 500 Kūnjpura, 692 Khawaspur, 481 Kupila (Hardwar), 510 Kherla, 579 Kupila (Kotla in Alwar), 862 Khikar (Ghaggar R.), 708 (?) Kūrāha (Kora-Jahānābād), 45 Khiljipur, 629 Kurākhūr (Gorakhpur), 986 Khizrābād (in Ambālā), 930 Kusari, Kusnari (Kunhar R.), 54 M'amurabad (Kathlal), 534 Khizrabad (near Dehli), 690 Khirpur (near Dāccā), 576, 653 Kūtila (Kotla near Kāngra), Kutila (Kotla in Alwar), 394 Khor (near Shamsabad, 296 Khoraja (Khūrja), 700 Khorandi (Ghod nadi), 684 Ladāna (Ladūna), 489 Khudābād, 689 Ladgaon (Larkhana), 690 Khuldābād, 686 Ladhū Sarāi (near Dehli), 492 Khulm, 347 Lāfat, 15 Khūr (Khair), 68 Lahair (Lahār), 498 Khurda, 388, 620 Laharpur, 526-7 Khurd Kābul, 549 Lahen, (Al-Hasa), 58 Khūrfakāu, 428 Lajaura (Lasur), 708 Khūshāb, 435 Lakhanpur, 587 Khwaja Khizr (near Bhakkar), Lakhnaur (Shāhābād), 212-3 Lakki, 120-1 Kicha, 410 Lakri (Gāgri, Kākar ?), 114 Kidhur (Gidhaur), 540 Lalang, 627, 632 Kīlāgarh (Kaulāgarh), 638 Laldong (Lal Dhang), 694 Kili (near Dehli), 271 Lārjal (Kulāchala?), 55-6 Kilokhari, Kiliughari, 264 Latti (not a place), 686 Kinār (in Jālaun), 568 Mankāla, 233 Layagaon (Larkhana), 689 Mankir (Malkhed), 22.3 Lesi-Sheopur (Sui-Supar, Sheo-Mankul, 245 Kinkot (Kin), 111 Kinkuta (Gangtha), xix Kipchāk Pass, 502 Līdda (Līdar river), 52 Kiranj (Kalinga or Coringa), 7 Lohar (Loharin in Kashmir), 56 Mansar, 357-8 Kirāt, Qirāt, R. 234 Loharāni (Kohri mouth of the Mansūra (Mansūri), zviii Kīri (Shāhbāzgiri), 160, 169, Lohari (Bohīri), 113 Kirkāyān (Lacoriān ?), 81 Lohgarh (in Punjab), 669-71 Kish (Island of Kenn), 15 Manu (Bāo), 358 Loni (near Dehli), 432 Kish (Kach), 65 Lonihara (Lünhera), 629 - Kishengarh (Kumher ?), 702 Lun (Tun in Persia), 701 Kisht (Hatkant ?), 489 Machhligāon (Māzalgāon), 628 Kochi (?), 486 Marahra, in Etah, 492 Māchiwāra, 246-7 Kodal (Hodal), 685 Mārgala, Mārgalla, 602 Madh-garh (not a place), 573 Kohāna (Gohāna), 343 Madaran (Bhitargarh), 541 Koh-hatah (Gauhāti), 635 Mārīkala, 1934 Mahaban (Mahawan), 147 Kohistan (Quhistan), 163 Marmad (Mārwād?), 77-8 Mahain (Ghaznin?), 489-90 Kokā (Ghogha), 580 Mahari (Macheri), 390 Kokarmanda, 666 Mahdighat or Mahdipur, 695 Kokra (Chutia Nagpūr), 577-8 Marūt (Marot), 224 Mahindwari (Mandawar), 393 Kol (Koledhair), 688 Mahminara (Manāra), 41-2, xiii Māskān (Mashkel), 63 Masīj (Rāmsej), 658 Masisa (Mopsuestia), 62 91 Mas'udpur, 251

Mahpalpur (near Dehli), 331 Mahrard (Marehra), 719 Mahrauli, 491 Mahuli (in the Konkan), 634 Mahumahra (Maheswar?), 50 Maimanah, 636 Maithili (Motupally), 288 Majhauli, Manjhauli, 494-5 Makam (not a toponym), 434 Makamkam (Konkan), 60 Makandara Pass, 698 Makhua (Maghra), 703 Makida (Maksida), 210-1 Magsudabad (Murshidabad), Makhşūsābād (Murshidābād), Māliā (near the Ran), 554 Mālja (Malcha), 331, 380, xvii Malikpur (near Dehli), 331-2 Malkonsah (Malgosa), 464 Maluh (Malcha), 343, Xvii Māmā Khātun, 521 Mandal (in Udayapur), 644 Mandawar, in Alwar, 393 Mandhūkūr, 53 Mandhun (Bandhu), 587 Mandrail (Mandrel), 496 Manduripatti (Madura), 21 Maner-i-Shaikh Yahya, 453 Mangalkot, 577 Mangalpahra (Mangalvedha), Mangarh (Mankot), 477 Mangiri (Monghyr), 46 Manhabari (Bhambor ?), 36-8 Manhal, (Muthalo?), 96 Mānikdūdh (Mānikdarra), 629 Manīla (Mātelo), 531 Maniani R., 440 Manjābāri (Bhāmbor?), 86-8 Mankarwal (Mankuvar), 528.9 Mancharnagar, 548-4 Manpur (Pampur), 613 Mantus (Santosh), 211 Mārān (Bārān) river, 524 Mardhan-kot (Burdhan-kot), Marhākar (near Āgra), 475 Marminara (M'abar-i-Manara?),

Pābal (Pāil), 711 Māsūrjān (Rogān ?), 65 Matarı, 181 Pābiya, 82 Matdakar (Mungipattan), 50 Padmān (Nandua), 459 Mātela, Mathelo, Māthīla, 106 Padmāvati (Padmakshetra?). Mathurapur, 653 Pahal (Pākal in Gurgāon), 474 Matı (Taptı), 617 Mıyapur (Hard var), 857 Pahan (Behat or Jhelum), 74 Pahlūdi (Phalodi), 509 Rasak, 32 Mendhi (Mendaki) River, 496 Milwat (Malot), 437 Pākpat (Bīghpat), 713 Mir Garh (Nur Garh), 651 Pālam, 492 Mitrol (Mitnaul), 685 Palāmau or Pālamūn, 686 Mohāna, 681 Pālı (in Gurgāon), 474 Mūdūla (Mandaula), xviii Palol (Palwal), 599 Mughalmarı, 572 Pauar (Bannar R), 576 Mughalpur (near Dehli), 269 Pani (Bain R), 403 Muḥammadābād (Mau), 527 Panna (Bhata), 493 5, 528, 571 2, Rola Jola (Rawaliya Jawaliya), Mukhlispur (Bādshāh Mahal), 586 Pārgāon, 684 Mū Maidana, 529 Parhālah (Pharwāla), 485 Mung (Munak), 360 Parian or Parwan, 186, 347 Paro (Por Bandar), 580 Munir (Mungir), 206 Munj, 149 Parsarur (Pasrur), 690 Münkhär (Nimkhär?), 485 Pārtūr (m Parbam), 629 Murin (Mau Pathan), 476 Parwan or Barwan, 234 Mut'alwı (Matärı), 131 Nadama (Samma?), 75 Pāt or Pātar, 509 Pathari, Pāthri, 580 Naghar (Baghzan), 168, 849, 864 Patiāla (error for Batāla), 680 Naghaz (Baghzan), 349, 864 Patiāli, 259 Nagīnābād (Tigīnābād), 429 Patna (Bhata) 478 Nahnura (Bhimra R), 680 Patpargan; 658, 727 Nakwān (Naganwān), 218 Pattan (Müngi Pattan), 580 Pham dirang, 618 Nākhach nuh garhi (not a place), Phaphund, in Etawa, 495 6 Pinjor, 226 Pirar, 125 Namāwar, 60 Namikhā (Nimkhār), 525 Pirozpur, 855-6 Nānakmath, 699 Por or Pur (in Udayapur), Nandana (Talsanda?), 222 Nandana (in Jhelum), 459 60 Pulāk (Bailāg or Yaılāg) Sūr-Nangnehār (Nagarhāra) 195 liq, 511 Narain (Nardina?), 2023 Pūna (Neota), 537, XXI Narela, 485 Pun garh (Pavangarh), 664 Narganda (Nedikonda), 668 Purta (Purna R.), 581 Rābarı or Rābri (Rāpri), 281 Narhan, 526 Rāchap (an error), 311 Rāhān (Rākhāng, Ārākān), 59 Rāhab or Rāhib (river), 149 50 Narmasira, 16 Nauras pur, 680 Nauras tārā (Parlı), 668 Rähmän (Rahm ka-Bāzār), 126 Nasrpur, 216 217 Nawabganj, 704 Rāhima (Rahm ka-Bazar), 689 Nilawi (not a place), 580 1 Rahmi, Ruhmi, 4-6 Nılchiragh (Bilchiragh), 636 Rāhūn, 669 Nilhan (Bilhan?), 88 Rāj Sambar (Rāj Samandar), Nimrānu, 685 189 Nirohi (Sirohi?), 128 Rajabpür, 859 Rājadhīr, 633 Niyās (Newāj R. ?), 251 2 Nun o Batal (Tappal), 397 Rājā Mahendra (Rājmundry), Niyūl (Palwal), 718 611 Nur (valley), 284 5 Rājauri, 628 Nurand (Nira Nadı), 694 Rājbandar (Rājmundry), 704 Nurghat (Bor, Bhor Ghat), 699 Rajgiri, 56 Nur-o-Kirat (rivers), 42 Rajivah (Rajabwah) Canal, 314 Nūrsādna (Narsinha, Nandana), Rakban (Raflyan or Rukan), 128 Sandur River (Shatadrud or Rakisbone (Rakhshasbhuvan), 479-80 Nuzhatābād (not a place), 571 698 Obolla (near Basra), 14 Ramal, 85 Olhar, 629 Rāmbhūrı (Vāmbūrı), 627 Othaniya, 552 Rām darra (Rāmghāt), 658 Oudh (Awah in Agra), 560 Ramdinpur (Radhanpur), 128 Sanjar R (Nārā Sānkrā?),688 9 Outakyn (Okha?), 17 Rämghät (in Bulandshahr), 699

Ram Ghat (in the Dekl an), 653 Rāmgīr, 659 Rām Sij (Rāmsej), 658 Rāngānw, 498 Ranipur (in Khairpur), 110 Rānwir (Rāvor), 669 Raran (error for Ran), 278 Rāsiāt (not a place), 199 Ratambh (Rankata?), 858 Ratanpur (near Makrāi), 675 Ratbān (Martabān in Pegü), 58 Rāwar (in Sind), 87 Rewar (\nrwar?), 524 Rohangarii (Rohankhera), 621 Rūdāna (Rūdkhāna?), 952 Ruderpur, 683 Ruhmi or Rahmi, 45 Rūjhān (near Shikārpūr), 81 Rüpāl (or Rüdpāl?), 568 Rupnāgar, 684 Rustam nagar (Murādābād), Säbit Kasra (Säbitgarh or 'Ali garh), 691 2 Sadhaura, 408 Bafidon, 314-5 Bāhanıwāl (Sāhīwal ?), 409 Sahasnak (Sahasralinga), 519 Salıbān (Ceylon), 76 Sahijpur, 638 Sahlat (Bhagwat), 206 Sahlı (Bhūilı), 206 Sahur (Sehore in Bhopal), 676-7 644 Saılaman (Ceylon), 144 Sairasb (Surāshtra), 14 Saryidpur, 589 Sakāner (Bānkāner), 571 Sakartāl, 694 Bakawand, 165-6 Sakina (Sakit, Saket), 401 Sakkharalana (Khelna) 664 Salaura (Sadhaura), 930 Salama (Sonba river?), 989 Salman (Bhilmal?), 14 Samāji (Samāwāni), 644 Samana, 360 Sāmānd (Sāmāna), 185 Samangān (Harbak), 347 Samba, 587 Sampganw, 658 Sāmrā (Sāmarrā), 131 Samwāl (Samawānı), 689 San Charik (Sang charak), 636 Sandabat (Sonpat?), 374 Sandaruz R (Shatadrud), 98-9 Sandur, the town (Chandwar or Sodhra), 645 Sutlej), 64-5 Sänganer, 596 Sang i Surākh, 201 Bangramnagar, 653 Sangwan (Sanawan?), 184 Sanjaddarra, 527

INDEX.

GENERAL.

A'amāl i Khālisa, 514 Abkand (water hele, pool), 485 Adabu-l mulük (Shukraviti?). Aftab, the nom-de-plume of Shah 'Alam II 700 Afzalu lanāmi, 429 Aishyarı (Nizari), a com, 597 Ākāshmukhi, 8 Akbar's death, cause of, 535-6 'Ālamgirnāma, 642 Alfi Coms, 562 Almāsı (Al Yamānı) swords, 614 'Amal ı Şālliı, 689 'Anbar (Amborgris, not ambor),7 Amīr i-dād (Justiciar), 214 Amīr 1 Kūl, Stroot Profect, 410 Amrud (pear, not guava), 875 Ananās, 609 Aq Siqiil (Grey beard), 525 Arab Itinoraries, 30 2 Arbāb-ı ıstiliqaq, 541 2 Argar Maha Bedak, 469 'Arıx, duties of, 154 5 Ashāb-ı wajd o hāl, 542 Ashrafi, Rupee value of, 654 Askudar (Courtor), 167-8 Auzun (Long, tall), 852 Ayatu l Kursi, 567 Babin (Bain, stepwell), 877 Bagnı or Bugni (Beer), 276 Bahadur Shah's rupces, 666 Bahliks (Bhikkuks), 89 Bakeariya, 672 Balanjārīya, 9 Bandagān i Hazrat, 517 Bandagan ı Mahtlı (Bihtli), 827 Baqqal (Banıya), 672 Barahbanı, 500 Bard (stalemate) 509 Barda (Burda), Qasida 1, 228 4 Bātiniya, 191 Bawartiya (Vartia), 180 Bhosle, origin of name, 651 Bikh (Paika), 888 Bilkarı (Nılgarı), 840 Biyara (Nabara), 576-7 Bodahgan (Boraha), 281 3 Bombay, garrison of, 661 Buhlul Lody's Tomb, 477 8 Buhlülı (Coin), 464 Bulghur Khana, 652 Bum i Salim Nama (Abu Mus lım Nama), 298 Burial of Music, 655 Būrni (quagmire), 1989 Busurg (Bazarucco), 660 Chanesar Nama, author of, 117 Charkhi bāshi, 692 Chashmband, 442 Chashm zadan, 271, 288 Ohihārgān doh yāzda, 221-2 Chihla (swamp), 118 Ganwar (Rustics), 488, xx

Chilla (forty days' fast), 601 Chim Khana, 507 Ohital, derivation of, 206 Choti (Hindu scalp lock), 187 Chungi i Ghalla, 840 Chühra, 849 Coins of Nur Jahan, 620 Coins of Prince Balim, 622 Coins of Taimur, 854 Comet of 1677 A C, 544 Comet of 1618 A.O, 612 Dādkhwāhi, 506 Dagh wa Mahalli, 546 Dahna (mouth, entrance), 631 Darab (a coin), 611 Dimid (double meaning), 866 Danāik (Dandanāyaka), 422 Dänishmand, meaning of, 1578 Dar khāna ū būd, 529 80 Dariba in Dohli, 687 Dariba i Tanbul, 840 Darogha i Diwan i Kha, 678 Darogha i Ghusal Khana, 701 Dărul Amăn 2612 Dast 1 rast dadan, 201, 229 Dāwah (Dhāwa, runner), 878 9 D'anat-ı Jaghrat, 420 Deh bist, meaning of, 293.4 Doh dwazdah, Deh bist, 597 Deh panzdali, meaning of, 155 6 Dharana, 68 Dinga (boats), 631 Diwan i Buyutat, 604 Diwan : Tan, 694 (?) Diwan i muzalim, 153-4 Doshākha, 265 Double Tangas (coms), 611 Dragon fountains, 1945 Droit de Seigneur in Sind, 115 Duarpa, 280, xv Durbash, 875 Durust 1 zar, 868 Earthquake near Thatta, 644 Elephant, story of, 189, 418 Elephants from Ceylon, 144 Elephants could be owned only by the Bultan, 189-40 Faluha (Philonia), 608 Faniz (Loaf sugar) 68 Fardaj (Gharwa?), 98 Farman yast, meaning of, 157 Farsakh, Longth of, 80 1, 48-4 Farzand, 272 Fire-worship in Upper India, 562 B Folk-etymology of Agra, 496 Folk tales in History, 108, 117 7, 117, 120, 188 9, 319, 465, 501, 589 90, 612 Futuhat-ı 'Alamgiri, 645 Gabar (Coin), 121 2 Ganj Sawāi (name of a ship), 680

Garogan (hostages), 268 Gazid (Guzaid), 75 Ghaibana, 654 Ghazrak (Gharna?), p xi Ghurāb (Grab), 682 Ghusal Khana, 590, xxu Girsbasp Nama, 201 Golden Ass, story of the, 251 Gunigir (Kanizaki?), 116 Gung mahal, 561 2 Gunpowder, use of, in early times in India, 624 5 Hāiza, diarrhoea not cholera, 609 Hājib (diplomatic agent), 504 Harisa (Ragout), 167 Harkat al mazbūlu, 206 Halila ı jalila, 494 Hashm wa hashiya, 888 Hazāri (Captain, Colonel), 674 Hindustan, longth and breadth of, 504 History of 'Afa Beg Qazvini (? 680 Huzzā Huzz, 255 | balıatian, 281 8, 842 Ibaritos, 15-6 Ibrahim Ghaznavi's invasions of India, 562 8 Ibrāhīmi (Com), 688 Ilhāmāt 1 Mun'imi, 667 'Ilm i D'awat, 508 Indigo trade, 17 In janib, meaning of, 816, 828 Irādat, 824 5 Islandiar (Islandurmuz), 687 8 Jafr, 422 B. 599 Jahängiri Ser, 620-1 Jāliya (Galley), 682 Jāmkhāna (Carpet), 268 4, 808 Jandarbak, 867 Jarr (ravine), 281, 485 Jata treated as helots, 85 6 Jazıb (Chamberlain), 148-4 Ja-zāri, 840 Jhinga (inscots), 609 Jigar khwār (Witch, Dākin), 12 Johar, Juhār (etymology of), 18 Kamar ı zar i hazārgām, 160 1 Kamalposh, 678 Kanāis (idol temples, not fire temples), 498, XX Kanwar (Ganwar, villagers), 48 Kar (Pilgrim Tax), 570 Karibak (Qirbak, Qarabeg), 86 Karkhanas, 686 Karkarah (Karkıraq), 586 Kataba, meaning of, 888-9 Katūt (palanquins), 58 Kipchi horsemen, 499 Khaizuran (Ruscus), 16 7 Kharak (meaning of), 818 4 Kharbūza (Big drum), 180

		Sukhāsan (Pālki), 527
	463	
	451 Pantari Clardari (), C10 C14 Pantari Cuarata C01.5	
To the second se	142 - 14 - 1 - 1 - 1 - 1 - 1 - 1 - 1 - 1 -	Street, the his are a second of the second o
are the michilla 1990	Panteraulul, glici	State 13th, 275 C
Khursamah, 207 Khursamah, 207	Panforantis, was liburrar a, 163,	##_\$_\$_\$#\$\$#\\$#\\$#\\$#\$\$#\\$\$\$\\\\\\\\\\\
Thanh Khin & Hise Co. ye	zelii	Takitti Chapli, for
	A 400 m m m m m m m m m m m m m m m m m m	Talutianteralmani, 605
Kucha-i-Salamat, 629 Kucha-i-Salamat, 629	* * * * * * * * * * * * * * * * * * *	
Kūdūn (Kodo, a grain), 655 Kūdūn (Kodo, a grain), 655	\$ +18 m 4 7 8 8 4 5 7 6 8 4 5 7 7 7 7 7 7 8 8 8 8 8 8 8 8 8 8 8 8 8	かくけんちょく ふりょす ト・コードバ
Kullen (established)	Phon Dirang 61.	
Kutan Santa 10.00	Literification and a	
Lahud (M-dhonosya), Talle cl. (Latitudes, Alberuni's Talle cl. (0 123	programme and a series of the contract of the
Latitude, Attenuated, 646 Lotters of Aurangrad, 646	rations (15th hear 1997) or Osbar (arthur largest), 1816	to the state of th
Lotters of Aurabatas, or Low prices of agricultural pr	Gartal-Henli (Bamber), 60	
duce in Sikandar Lody's	Server the	Trees dishibite print of trees to the control of th
reign, 475-6	Qurest 536 2 Ribbit mathill, 531	
1. L. 04 . () T. () 1 1 1 1 1 1 1 1 1	Rathi landhan, Cond	g was blacker than of the
Massir-l-Alamgiri, 618-1	Ramphanel (elymnical), Cit	
MEDABLIA (VICTION)	~*!!!	attal fatte at the state of the end of
191-5 Ranne	ts), 1254(5t, 122	
Maratib (Drums and 2000)	Rasuldar, 547	10 10 10 10 10 10 10 10 10 10 10 10 10 1
S16-6 Day's journ	by), Ranal, title : Ranas of this	ein in
	purant Chiler, 117, 134	The first or the first of the f
Nāti (Būtmi, Espionago). G	97 Rivati (Rititi), 5"?	and the contract of the contra
Mati (Brim, 1814) Mauludnima of Aklar, 545	Right (Mile), literal line and an in-	(10) this is the state of the s
	231 Sabkuttiga (Tarka) with in the	i, Ed. Tar i'alian bel tere line ami, emi Taresh faireacto), til
Manar-i-Fäizu-lanwar, 500	631 Sibin (merchants), 10%.7	Tartah Paretti (19)
	612 Sahibi-Biris, 153	Tate of the billions, was and a few and
Atmonths of Mills Community	Stith (brother-in-law), for	Tankin Kana a salah masas
Mahanatini teritiri,	Samanle (Ininne), 19, 64,	
Mahcha, 410	Canariva (1703)1819). 10	A 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1
Mahd 'Aliya, 511	Samele (B) (CATENCTER), HE	Tarre Tablic 11
Majhūl Ilaihi, 688 Majlis-i-t-aām, 590	Sangheit, Mushimans, Ki	DD17 - 48 - 41 - 41 - 41 - 41 - 41 - 41 - 41
Majzūbi-lāikhwār, 432	ledge of, in Akhar's re	ign, 101 km 2.556
Malahat (not Malahat), 61	4 564-6	neigh. Trápa, 452
Man (manna) of rantie,		terms at Amilana firsh
Mandapika Ol Biller, 130	ing 41 rounds, 149.9 Sar sunnti, 518	Tul in (Turn of maile of), Oas
Mandagid-Barr, 217		Tüchlach, 191
Mansab, meaning of, 655	Sarajal-Hindi (Mala' at	tournal Transition SES
Mulahida, 184 Mulahidat-i-Alamüt, 20	0. 2034 72	Tile bedigitt first true as a second
Muradi Tanga, 512	Some off integral and of	OG Turkthri, 242 Upanishals, Persian Transla-
Musri'an (Couriers), 19	6 Scoras (Jaina priesta), 6	tion of, 648
Africaffari (Coln), 090-1	Substyle dientime, 201	stine (magning) bid
Nachakh nuh garin, 313	Shamsu-l-kufat, 237	n cor Vilaganagar, Army, 211
Nādiru-l-așli (Nādiru-l-	'Asri), Sharki or Sirki (a reel Sharu (a mythical anim	nel), 178 Vijiyanagar, Columge of, 41
611-2		322-3 V(m (Dim), 438
Nakta (meaning of), 59	Shashgan denyman, of Caine	a for the Wali Allah, 669
Nām giraltan, 286	first time by Firu-,	
Nänkhurish, 121 Nasaqchi, 687	Shast-o-Shabih, 590	Watti of Watti () Icotcil, 003
Nasiks (Jainaz ?), 80	Sherbacha (a pistol), i	701 Yalgar-i-Bahaduri, 701-5
Nūniān (Nūinān, Gone	rals), 703 Bhughal-i-lehraf, 155	YIKKA (YIKIL), 441, 020
Nünian (Tuinan, Bude	inist sikka-i-Garrionawa-,	
priests), 210	pin-aaga, opo-o	Yunani surgeons, 668 Zakhira-i-Khwarizmshahi, 620
Ordeal of water, 129	Singhūsan (Throne),	dantal 607 Kaniir-i-fil. 486
Pādshāh Begam (mea	Sikandar Lody's To	donls), 607 Zanjir-j-fil, 486 mb, 477-8 – Zarbzan, 541, 595
620 Paimāban Jog Nirani	~ ~ . ~ . ~ . ~	word with an emission of a cit
Paimābau Jog Nirau Pram, Anaud Yoga N	(iranjan (?), Sūji (Sūchi) khūna, (500
Trom, Mana Toka L	manifest (1) and family in early	

ERRATA

```
P 3, 1 9 Roal' Rashtrakutas'
                                          P 181, 1, 18 Rial 11 121, 1 G from foot'
P 3, 1 0 f f Roil' Shanlaciarmai'
                                           P 161, l 1) Real 'Paldes' for 'Paldens'
P 7, 1 13 f f Rml'hrs' for 'his'
                                          P 175, I 34 Rost Irai isongo Samenbich!
P 8, 7 21 Roll'i tonic'nil' l'truit'
                                          P 181, 134 Him Post 'Sorly' for 'Sopley'
P 10, 1 3 Correctly, 'Sinhallelpa'
                                          P 131,1911 Wall'p 233' for 'p 236'
P 13, 1 8 1 f Dele'o the 127fut after -
                                           P 185, 1 164 f Read ( Illutrush )
P 15 1 16 Rail'Quaire nore's'
                                           P 138, I B f f All tof tafter thought
P 17, I 11 Roll bambon for 'bombon'
                                          P 192 , 11 f f Perl' fourteauth
                                          P 116 15 1 11 0-1/2.
P 21, 15 Roll ambhirt'
P 23, 1 8 Rost 'appare' for 'appara'
                                          P 196, 1 13 P al that for the
P 40, Il 20 and 18 f f Correctly, "Tila"
                                           P 195 l 12 f f Reil'miker' for 'mike'
P 42, 1 13 Roal 'Tao Direa (vallo ) of Nur
                                          P 199 I 20 Invet 'page' but many 534 and
             is sho in ' for 'tue" are shoun'
P 42, 1 13 Rost 'north cast' for 'north
                                           P 200, t 1 f f Roal' Amullat
                                           رمان P 210, 1 1211 Pc11 رمان
P 44 ! 13 Read 'Seely 'here and else; here
                                           P 212, 1 25 Real ' Lakarl unda'
P 45, 1 2 f f Ronl' XI 115 'for ' XI 175'
                                           P 215, 1 4 Add 'bit' before 'is'
P 47,1 14 Real' 5000 yards for '500
                                           P 223 1711 Rest 16 1011, 3 B1'
             vards'
                                           P 230, 1 6 1 f l'ent 'n cutir'
P 47, 1 18 f f Roal ' Long 20" 30 E'
                                           P 235 1 41 1 Rul 'Torr erg'
P 47, 1 15 1 1 \ 11 ' 1'13' after ' o''
                                           P 233,1 131 f Rant Qr ida for Quitins?
P 52, 1 2 Revi'lrequently 'for 'frequenty'
                                           P 240 / 3f f Roll 'Illutmish'
P 52, 19ff Roil 'district' for 'dirtrit'
                                           P 241, 1 10 Rest publican or palla
P 55, 1 28 Read 'Bod Inal' for 'Bol =
                                                        toin '
                                           P 247, 1 25 Rril Ribhal Akhir'
P 59, 1 5 f f Real 'goographical'
                                           P 250, 1 20 Roal ' 1905 A C and 705 A H '
 P 60, I 13 Roal'EI II 451' for'E I,
                                           P 254, 1 21 1 Read 'dilour'
              III, 451 '
                                           P 256, 1 121 f Raid 'Muhammalan'
 P 62, 1 22, Roal '281'
                                           P 257, 1 5 Rml'SIMI'for'S MMI'
 P 67, 1 19 f f Corrotly, 'kapaliany'
                                           P 258, 1 22 R 11 503 infra '
 P 67, 1 17 f f Ranl' Kunl'
                                           P 259 / 9 f f Real 'Baliun'
 P 68, 1 10 Real 'Gildomoistor'
                                           P 234,1711 Real C D 11 382'
 P 73, 1 11 Roal 'Saaj al Hindi'
                                           .حدو for حدو P 209,1 12 Renl
 P 75, 1 10 f f Properly, 'Shukramti'
                                           P 272, last time Ald 'south' before 'of'
 P 83, 1 24 Roal 'untwisted'
                                           رىد P 235,1 21, Roal رىد
 P 80, 1 3 Road 'Thalurs' for 'Thalu'
                                           P 299, 1 25 Rend '1776 \ C' for '157c'
 P 90, 1 20 Dalete 'of'
                                           P 301,18 Road Defremory
 P 93, 1 5 f f Real مده. P 101, 1 7 Road 'Ibn kballılan'
                                           P 310, l 19 Real 'Khusrat Khan
                                           .خطباي P 310 1 12 f Read خطباي.
 P 101, 1 12 Read 'Zakariva' or 'Zakar
                                           P. 314.1 13 Read ' Magrada wah'
               13 ya ' for ' Zakarriya '
                                           P 323 1 27 Correctly, 'Zalariya.'
 P 117,1 10 Properly, 'Tazkira'
                                           P 334, I is Rord on for in
 P 123, 1 20 Read 'Bahadmer'
                                           P. 335, 1 2 Road Bagija Nagija.
 P 124, L 24 Insert'up' between 'setting'
               and 'a.'
                                           ورر not رور not رور not رور not
                                           P 335, 1 20 Delete 'them'
  P 129, 1 8 f f Road ' Al Muhit'
                                           P 347, 1 5 f f Rend '1879' for '1876'
  P 129, last line Read 'Dakin'
                                           P 357, l 1 Read 'Narmada' for 'Tapti.'
  P 136, l 22 f f Insert 'us 'botween 'as
                                           P 366, 1 2 Read 'Dabu' for 'Dabu'
                  sures ' and ' that '
                                           P 372, l 11 Read 'paronomasia'
 P 143, l 15 Properly, 'Sapadalaksha'
                                           P 332, l 17 f f Read 'toponyms'
  P 144, Il 4 and 6 Corrootly, 'Jazib'
                                           P 336, 1 18 f f Ald 'by 'alter 'upon.'
  P 144, 1 7 Correctly, 'Jazaba'
```

- P. 391, l. 19. Read 'T. A; p. 6, l. 6. P. 395, l. 11. Read ' Balaram.' P. 396, l. 6 f. f. Read ' Sarang Khan.' P. 398, Il. 9 and 14 f. f. Correctly, ' Kirti Sinha. P. 404, l. 2. Road ' Ranking.' P. 404, 1.8 f. f. Real of for or. P. 409, l. 24. Insert 'ns' after 'misrerl.' P. 412. l. 19. Road ' port ' for ' part.' P. 439, L. 9. Read 'Chanderi' for 'Chanderi.' P. 439, 1. 12 f. f. Read 'brother' for 'uncle.' P. 444, l. 17, Read ' T. A. 371, 1, 9. P. 459, 1. 25. Read 'Qāṣi-āli,' for 'Qāṣi-ali.' P. 464, l. 22. Read ' Suba ' for ' Suba.' P. 469, l. 6 f. f. Real ' Khawan Khan.' P. 475, l. 20. Read 'identical.' P. 494, l. 23. Read 'Salāhu-d-din's.' P. 500, 11. 8-9. Read . Stadat . for . Stalat. P. 504, l. 1 f. f. Road ' in ' for ' on.' P. 506, l. 6 f. f. Delete the :zafat niter 3. P. 503, l. 1. Read Vol. V. 139, l. 14 antc. P. 503, L 17. Read ' Humāyun ' for ' he.' P. 512, l. 1 f. f. Real ' Gulbadan.' P. 513, 1. 6 f. f. Road ... for ... P. 514, l. 1. Read ' andak mardumi' for · andak mardi.' P. 527, l. 14 f. f. Read ' attached.
- P. 551, I. 13 f. f. Read . Kāthis." P. 560, I. 6 f. I. Road 'XXIIIrd' for ·XXVIth! P. 575, l. 9. Read ' Khunza Sultan." P. 580, I. 9. Read Shaikhupur. P. 585, 1. 5. Revd 'III, 1234 Note. P. 590, I. 16 f. f. Road Gawil. P. 608, l. 10 f. f. Read + 535, Tr. 818. P. 628, l. 19 Read ' Darya.' P. 637, 1. 4. Read . Tughlag. P. 637, 1. 25. Read . Banihal. P. 637, I. 3 f. f Road . Islandarmuz. P. 664, l. 6 f. f. Read . Sachau. P. 645, l. 22 f. f. Real ' Raghunandandas.' P. 646, l. 11. Revl ' A. N. III.' P. 650, l. 20. Read ' Kachh Gandawa.' P. 669, l. 12. Read 'north of Karnal.' P. 680, l. 18 f. f. Read ' Nafaisu-l-Maagir.' P. 683, l. 4 f. f. Read ' Patparganj.' P. 685, l. 17 f. f. Read 'latter' for 'later.' P. 690, l. 17. Read 'Myrobalan.' P. 695, l. 3 f. f. Delete ' Ibid.' P. 701, l. 2. Real 'Lun' for 'Luni' and delete ' near Dehli.' P. 701, l. 12. Revl 'Ghusalkhana' P. 704, I. 9. Read 'Sullan Salim' for 'Sultan Sālim."